

CALL ORDER : 180

CONTRACT ID : R -31867-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-74035 SIGN, REMOVE	5.000	EACH
10	202-96133 PIPE, REMOVE	280.000	LFT
11	202-98488 PIPE END SECTION, REMOVE	8.000	EACH
12	203-02000 EXCAVATION, COMMON	16,574.000	CYS
13	203-05859 FILL	7,389.000	CYS
14	204-02290 SETTLEMENT PLATE	10.000	EACH
15	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	2.000	EACH
16	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	66.000	TON
17	205-06933 TEMP DITCH INLET PROTECTION	2.000	EACH
18	205-06937 TEMPORARY SILT FENCE	2,396.000	LFT
19	205-09543 NO 2 STONE	100.000	TON
20	207-08263 SUBGRADE TREATMENT, TYPE IA	12,548.000	SYS
21	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,010.000	SYS
22	211-02050 B BORROW	6,440.000	CYS
23	211-09264 STRUCTURAL BACKFILL, TYPE 1	361.000	CYS
24	214-07202 GEOGRID, TYPE I	2,120.000	SYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,588.000	TON
26	302-06464 SUBBASE FOR PCCP	2,960.000	CYS
27	303-01180 COMPACTED AGGREGATE, NO. 53	707.000	TON
28	304-07494 WIDENING WITH HMA, TYPE C	8.500	TON
29	306-08034 MILLING, ASPHALT, 1 1/2 IN	127.000	SYS
30	402-07432 HMA SURFACE, TYPE A	60.000	TON
31	402-07434 HMA SURFACE, TYPE C	12.000	TON
32	402-07435 HMA INTERMEDIATE, TYPE A	179.000	TON
33	406-05520 ASPHALT FOR TACK COAT	0.200	TON
34	501-09107 QC/QA-PCCP, 9 IN	11,825.000	SYS
35	503-05240 D-1 CONTRACTION JOINT	6,950.000	LFT
36	603-92636 FENCE, CHAIN LINK, 72 IN	1,360.000	LFT
37	603-97442 FENCE GATE, CHAIN LINK, 72 IN X 32 FT	1.000	EACH
38	605-06090 CURB, INTEGRAL, CONCRETE	405.000	LFT
39	610-09108 PCCP FOR APPROACHES, 9 IN	1,010.000	SYS
40	615-06490 RIGHT OF WAY MARKER	12.000	EACH
41	615-06505 MONUMENT, B	1.000	EACH
42	615-06515 MONUMENT, D	13.000	EACH
43	616-02320 GEOTEXTILES	12,499.000	SYS
44	616-06405 RIPRAP, REVETMENT	19.000	TON
45	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
46	621-06545 FERTILIZER	2.000	TON
47	621-06553 SEED MIXTURE, R	782.000	LBS
48	621-06557 SEED MIXTURE, T	192.000	LBS
49	621-06565 MULCHING MATERIAL	14.000	TON

CALL ORDER : 180

CONTRACT ID : R -31867-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	621-06567 WATER	9.000	KGAL
51	621-06574 SODDING	2,437.000	SYS
52	628-09402 FIELD OFFICE, B	5.000	MOS
53	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	5.000	MOS
54	706-09545 COARSE AGGREGATE, NO 8	1,850.000	CYS
55	715-04509 TEMPORARY PIPE	120.000	LFT
56	715-04555 PIPE END SECTION, MIN. AREA 5.1 SF	2.000	EACH
57	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	4,615.000	LFT
58	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	203.000	LFT
59	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN	69.000	LFT
60	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN	271.000	LFT
61	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN	70.000	LFT
62	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN	249.000	LFT
63	715-05327 PIPE, TYPE 2, DEFORMED, MIN AREA 1.83 SF	139.000	LFT
64	715-08447 PIPE, TYPE 1, DEFORMED, MIN AREA 5.1 SF	120.000	LFT
65	715-09064 VIDEO INSPECTION FOR PIPE	918.000	LFT
66	715-46000 PIPE END SECTION, 12 IN	3.000	EACH
67	715-46005 PIPE END SECTION, 15 IN	6.000	EACH
68	715-46055 PIPE END SECTION, MIN AREA 1.8 SF	2.000	EACH
69	718-06528 OUTLET PROTECTOR, 1	6.000	EACH
70	718-06529 OUTLET PROTECTOR, 2	4.000	EACH
71	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
72	718-52610 AGGREGATE FOR UNDERDRAINS	367.000	CYS
73	718-99153 GEOTEXTILES FOR UNDERDRAIN	3,677.000	SYS
74	720-01092 MANHOLE, J15, MODIFIED	2.000	EACH
75	720-45030 INLET, E7	1.000	EACH
76	720-45275 PIPE CATCH BASIN, 24 IN	1.000	EACH
77	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
78	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
79	801-06625 DETOUR ROUTE MARKER ASSEMBLY	20.000	EACH
80	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
81	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
82	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
83	801-07118 BARRICADE, III-A	144.000	LFT
84	801-07119 BARRICADE, III-B	144.000	LFT
85	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	99.000	LFT
86	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	44.000	SFT
87	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	25.000	SFT
88	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN	4,904.000	LFT
89	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN	4,607.000	LFT
90	808-05534 LINE, EPOXY, SOLID, WHITE, 8 IN	565.000	LFT
91	808-09038 TRANSVERSE MARKINGS EPOXY, SOLID, WHITE,	142.000	LFT
92	808-74805 TRANSVERSE MARKING EPOXY,	65.000	LFT
93	808-74807 PAVEMENT MESSAGE MARKING, EPOXY, LANE INDICATIONS ARROWS	1.000	EACH
94	808-74809 PAVEMENT MESSAGE MARKING, EPOXY, (R X R)	1.000	EACH

