

CALL ORDER : 131

CONTRACT ID : IB-31413-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06899 RADIO	3.000	EACH
3	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	54.000	MOS
5	105-08523 RADIO ONLY SERVICE	54.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
16	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
17	202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS	LUMP	LUMP
18	203-02000 EXCAVATION, COMMON	12,511.000	CYS
19	203-02070 BORROW	3,718.000	CYS
20	205-03371 SEDIMENT, REMOVE	289.000	CYS
21	205-06933 TEMPORARY DITCH INLET PROTECTION	2.000	EACH
22	205-06936 TEMPORARY SEDIMENT TRAP	76.000	TON
23	205-06937 TEMPORARY SILT FENCE	5,275.000	LFT
24	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	406.000	CYS
25	207-08267 SUBGRADE TREATMENT, TYPE IIIA	17,891.000	SYS
26	211-02050 B BORROW	211.000	CYS
27	211-06467 AGGREGATE FOR END BENT BACKFILL	89.200	CYS
28	211-09265 STRUCTURAL BACKFILL, TYPE 2	485.000	CYS
29	303-90466 SUBBALLAST	529.000	TON
30	303-92491 BALLAST	2,832.000	CYS
31	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,476.000	TON
32	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	2,460.000	TON
33	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	7,872.000	TON
34	406-05520 ASPHALT FOR TACK COAT	13.400	TON
35	601-02241 GUARDRAIL, REMOVE	866.000	LFT
36	601-06238 IMPACT ATTENUATOR, R1, W1, TL-3	2.000	EACH
37	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	844.000	LFT
38	606-07484 MILLED HMA SHOULDER CORRUGATIONS	4,155.000	LFT
39	610-07486 HMA FOR APPROACHES, TYPE A	396.000	TON
40	614-09986 RAILROAD	2,281.000	EACH
41	614-92148 RAILROAD TRACK	4,172.000	LFT
42	616-02320 GEOTEXTILES	1,572.000	SYS
43	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
44	621-06545 FERTILIZER	1.750	TON
45	621-06554 SEED MIXTURE, U	605.000	LBS
46	621-06557 SEED MIXTURE, T	323.000	LBS
47	621-06565 MULCHING MATERIAL	8.100	TON
48	627-09327 CABLE BARRIER SYSTEM, TYPE TL-4	3,570.000	LFT
49	627-09331 SAFETY TERMINAL, TYPE TL-4	2.000	EACH

CALL ORDER : 131

CONTRACT ID : IB-31413-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	628-09403 FIELD OFFICE, C	18.000	MOS
51	701-05561 DRILLED SHAFT	288.300	LFT
52	701-05561 DRILLED SHAFT	212.800	LFT
53	701-05561 DRILLED SHAFT	1,251.000	LFT
54	701-05782 UNCLASSIFIED EXTRA DEPTH EXCAVATION	8.800	CYS
55	701-05782 UNCLASSIFIED EXTRA DEPTH EXCAVATION	36.400	CYS
56	701-05782 UNCLASSIFIED EXTRA DEPTH EXCAVATION	21.500	CYS
57	701-05783 OBSTRUCTIONS	24.000	HRS
58	701-05787 INSTRUMENTATION, INTEGRITY TESTING AND DATA COLLECTION	LUMP	LUMP
59	701-90386 TEMPORARY SHEET PILING	LUMP	LUMP
60	702-02925 WATERPROOFING MEMBRANE SYSTEM	8,978.000	SFT
61	702-51005 CONCRETE, A, SUBSTRUCTURE	447.900	CYS
62	702-51015 CONCRETE, B, FOOTINGS	117.200	CYS
63	702-51090 BRONZE PLATES	1,140.000	LBS
64	702-51863 FIELD DRILLED HOLE IN CONCRETE	96.000	EACH
65	702-92857 CONCRETE, C, SUBSTRUCTURE	31.600	CYS
66	703-06028 REINFORCING BARS	62,352.000	LBS
67	703-06029 REINFORCING BARS, EPOXY COATED	25,592.000	LBS
68	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	155.000	EACH
69	704-03131 DECK DRAIN, HALF ROUND, 8 IN.	924.000	LFT
70	709-07110 SEAL COAT, GRAFFITI RESISTANT	6,400.000	SFT
71	711-51038 STRUCTURAL STEEL	LUMP	LUMP
72	714-44240 CONCRETE, A, STRUCTURES	1.400	CYS
73	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN	2.000	EACH
74	715-05032 PIPE, TYPE 2, CIRCULAR, 15 IN	92.000	LFT
75	715-05115 PIPE, TYPE 1, CIRCULAR, 6 IN	14.000	LFT
76	715-05116 PIPE, TYPE 1, CIRCULAR, 8 IN	250.000	LFT
77	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN	29.000	LFT
78	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN	7.000	LFT
79	715-05422 PIPE, SLOTTED DRAIN, 12 IN	3,030.000	LFT
80	715-05423 PIPE, SLOTTED DRAIN, 15 IN	2,164.000	LFT
81	715-05424 PIPE, SLOTTED DRAIN, 18 IN	310.000	LFT
82	715-08162 PIPE, TYPE 1, DEFORMED, MIN AREA 8.8 SF	838.000	LFT
83	715-91361 PIPE, PVC, 6 IN	104.000	LFT
84	715-92537 PIPE, PVC, 8 IN	83.000	LFT
85	720-45416 MANHOLE, E4	2.000	EACH
86	725-03133 CONCRETE FACING	3,911.000	SFT
87	731-03915 ARCHITECTURAL SURFACE TREATMENT	6,399.000	SFT
88	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
89	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	31,083.000	LFT
90	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
91	801-06710 FLASHING ARROW SIGN	180.000	DAY
92	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
93	801-08400 TEMPORARY TRAFFIC BARRIER, TYPE 1	3,748.000	LFT
94	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	6,648.000	LFT
95	801-08402 TEMPORARY TRAFFIC BARRIER, TYPE 3	708.000	LFT
96	801-08508 TEMP TRAFFIC BARRIER, TYPE 2, ANCHORED	730.000	LFT
97	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	1,694.000	LFT
98	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	6,774.000	LFT

CALL ORDER : 131

CONTRACT ID : IB-31413-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
99 808-06716	LINE, REMOVE	9,950.000	LFT
100 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	6,774.000	LFT
101 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	86.000	EACH
102 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	86.000	EACH

CALL ORDER : 201

CONTRACT ID : R -29037-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	4.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	203-02000 EXCAVATION, COMMON	220.000	CYS
14	203-02070 BORROW	36.000	CYS
15	203-02100 EXCAVATION, PEAT	750.000	CYS
16	203-09752 TIRE SHREDS	387.000	TON
17	203-09753 GRANULAR SOILS	258.000	TON
18	203-09754 COHESIVE ENCASEMENT MATERIAL	241.000	CYS
19	205-03371 SEDIMENT, REMOVE	5.000	CYS
20	205-06937 TEMPORARY SILT FENCE	900.000	LFT
21	205-09543 NO 2 STONE	100.000	TON
22	207-09935 SUBGRADE TREATMENT, TYPE 1C	889.000	SYS
23	211-02050 B BORROW	175.000	CYS
24	214-07202 GEOGRID, TYPE I	437.000	SYS
25	303-01180 COMPACTED AGGREGATE, NO. 53	556.000	TON
26	306-08034 MILLING, ASPHALT, 1 1/2 IN	700.000	SYS
27	402-07433 HMA SURFACE, TYPE B	120.000	TON
28	402-07438 HMA INTERMEDIATE, TYPE B	98.000	TON
29	406-05520 ASPHALT FOR TACK COAT	1.000	TON
30	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
31	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
32	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
33	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	168.750	LFT
34	615-06336 MONUMENT	1.000	EACH
35	615-06490 RIGHT OF WAY MARKER	8.000	EACH
36	615-06505 MONUMENT, B	3.000	EACH
37	616-02320 GEOTEXTILES	2,062.000	SYS
38	616-06451 RIPRAP, UNIFORM	7.000	TON
39	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
40	621-06559 MULCHED SEEDING, R	1,367.000	SYS
41	628-09401 FIELD OFFICE, A	4.000	MOS
42	701-09558 TEST PILE, INDICATOR, PRODUCTION	90.000	LFT
43	701-09560 TEST PILE, INDICATOR, RESTRIKE	2.000	EACH
44	701-09662 PILE, STEEL PIPE, 0.250 IN, 14 IN	717.000	LFT
45	723-06660 WINGWALL	72.000	SFT
46	723-08134 STRUCTURE, PRECAST THREE-SIDED, 144 IN. X 120 IN.	42.000	LFT
47	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
48	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
49	801-06625 DETOUR ROUTE MARKER ASSEMBLY	34.000	EACH

CALL ORDER : 201

CONTRACT ID : R -29037-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50 801-06640	CONSTRUCTION SIGN, A	11.000	EACH
51 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
52 801-07118	BARRICADE, III-A	48.000	LFT
53 802-07060	SIGN, SHEET, RELOCATE	1.000	EACH
54 808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	900.000	LFT
55 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	900.000	LFT

CALL ORDER : 205

CONTRACT ID : R -29482-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE CONCRETE	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	329.000	SYS
13	202-02279 CURB AND GUTTER, REMOVE	1,894.000	LFT
14	202-06541 REMOVE	117.000	EACH
15	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
16	202-74045 SIGN AND SUPPORTS, CHAN POSTS, REMOVE	53.000	EACH
17	202-90747 RETAINING WALL, REMOVE	23.000	LFT
18	202-91840 FENCE, CHAIN LINK, REMOVE	127.000	LFT
19	203-02000 EXCAVATION, COMMON	6,982.000	CYS
20	203-02070 BORROW	10,603.000	CYS
21	205-02770 EROSION CONTROL BLANKET	3,562.000	SYS
22	205-06932 TEMPORARY CHECK DAM, STRAW BALES	27.000	LFT
23	205-06933 TEMPORARY DITCH INLET PROTECTION	47.000	EACH
24	205-06936 TEMPORARY SEDIMENT TRAP	36.000	TON
25	205-06937 TEMPORARY SILT FENCE	8,130.000	LFT
26	207-08262 SUBGRADE TREATMENT, TYPE I	7,617.000	SYS
27	207-08266 SUBGRADE TREATMENT, TYPE III	16,922.000	SYS
28	207-08267 SUBGRADE TREATMENT, TYPE IIIA	7,090.000	SYS
29	211-09264 STRUCTURAL BACKFILL, TYPE 1	176.000	CYS
30	211-09265 STRUCTURAL BACKFILL, TYPE 2	4,439.900	CYS
31	211-09266 STRUCTURAL BACKFILL, TYPE 3	695.900	CYS
32	211-09268 STRUCTURAL BACKFILL, TYPE 5	144.020	CYS
33	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	276.700	CYS
34	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	210.000	TON
35	302-07455 DENSE GRADED SUBBASE	53.900	CYS
36	306-08034 MILLING, ASPHALT, 1 1/2 IN	954.000	SYS
37	306-08043 MILLING, TRANSITION	1,650.000	SYS
38	306-08432 MILLING, APPROACH	513.000	SYS
39	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	4,041.000	TON
40	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	6,676.000	TON
41	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	7,926.000	TON
42	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	5,830.000	TON
43	401-08333 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	4,704.000	TON
44	406-05520 ASPHALT FOR TACK COAT	35.800	TON
45	601-01522 GUARDRAIL TRANSITION TYPE TGB	3.000	EACH
46	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT 3 IN SPACING	6.250	LFT
47	601-02241 GUARDRAIL, REMOVE	292.000	LFT
48	601-06037 GUARDRAIL END TREATMENT, I	1.000	EACH
49	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH

CALL ORDER : 205

CONTRACT ID : R -29482-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
50	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	37.500	LFT
51	602-06729 BARRIER DELINEATOR	12.000	EACH
52	603-03829 FENCE	133.000	LFT
53	603-06045 FENCE, CHAIN LINK, 48 IN	349.000	LFT
54	603-06065 FENCE, CHAIN LINK, RESET	2,887.000	LFT
55	603-96521 FENCE GATE, CHAIN LINK, RESET	2.000	EACH
56	604-07894 CURB RAMP, CONCRETE, A	13.000	SYS
57	604-07897 CURB RAMP, CONCRETE, C	3.000	SYS
58	604-07900 CURB RAMP, CONCRETE, F	153.000	SYS
59	604-07901 CURB RAMP, CONCRETE, G	112.000	SYS
60	604-07902 CURB RAMP, CONCRETE, H	7.000	SYS
61	604-91531 SIDEWALK, CONCRETE, 4 IN	7,706.000	SYS
62	605-06120 CURB, CONCRETE	584.000	LFT
63	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	17,858.000	LFT
64	607-06350 PAVED SIDE DITCH, D	210.000	LFT
65	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	323.600	SYS
66	610-07487 HMA FOR APPROACHES, TYPE B	1,768.000	TON
67	610-08446 PCCP FOR APPROACHES, 6 IN	2,557.000	SYS
68	610-09108 PCCP FOR APPROACHES, 9 IN	1,932.000	SYS
69	611-06497 MAILBOX ASSEMBLY, SINGLE	25.000	EACH
70	611-06498 MAILBOX ASSEMBLY, DOUBLE	4.000	EACH
71	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	35.000	EACH
72	615-06490 RIGHT OF WAY MARKER	207.000	EACH
73	615-06496 PARKING BARRIER	7.000	EACH
74	615-06505 MONUMENT, B	28.000	EACH
75	616-02320 GEOTEXTILES	135.200	SYS
76	616-93019 RIPRAP, GROUTED, 18 IN	89.200	SYS
77	621-06560 MULCHED SEEDING, U	2,796.000	SYS
78	621-06574 SODDING	163.000	SYS
79	621-06575 SODDING, NURSERY	18,913.000	SYS
80	622-01937 PLANT	9.000	EACH
81	628-09402 FIELD OFFICE, B	30.000	MOS
82	701-51195 PILE, STEEL H, HP 12 IN X 53	1,013.000	LFT
83	701-91792 PILE TIP, STEEL H	36.000	EACH
84	702-94139 CONCRETE, A, ABOVE FOOTINGS	67.700	CYS
85	703-06028 REINFORCING BARS	20,866.000	LBS
86	703-06029 REINFORCING BARS, EPOXY COATED	48,698.000	LBS
87	704-51002 CONCRETE, C, SUPERSTRUCTURE	160.300	CYS
88	706-06342 RAILING, PS-1	231.330	LFT
89	706-06353 CONCRETE BRIDGE RAILING TRANSITION, TPS-1	4.000	EACH
90	706-51025 CONCRETE, C, RAILING	428.000	LFT
91	707-05977 STRUCTURAL MEMBERS, CONCRETE BOX BEAM,	5,928.000	SFT
92	709-51821 SURFACE SEAL	LUMP	LUMP
93	714-04661 STRUCTURE, PRECAST, RC, BOX SECTION 11FT X 6FT	56.000	LFT
94	714-26708 STRUCTURE, PRECAST, RC, BOX SECTION 8FT X 4FT	12.500	LFT
95	714-44240 CONCRETE, A, STRUCTURES	182.000	CYS
96	715-04555 PIPE END SECTION, MIN. AREA 5.1 SF	1.000	EACH
97	715-04612 PIPE	171.000	LFT
98	715-04809 PIPE, PVC, 3 IN.	9.000	LFT

CALL ORDER : 205

CONTRACT ID : R -29482-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
99	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	19,220.000	LFT
100	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	132.000	LFT
101	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN	6,626.000	LFT
102	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN	2,249.000	LFT
103	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN	1,918.000	LFT
104	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN	1,643.000	LFT
105	715-05156 PIPE, TYPE 2, CIRCULAR, 30 IN	1,303.000	LFT
106	715-05331 PIPE, TYPE 2, DEFORMED, MIN AREA 3.3 SF	5.000	LFT
107	715-05335 PIPE, TYPE 2, DEFORMED, MIN AREA 5.1 SF	85.000	LFT
108	715-05350 PIPE, TYPE 2, DEFORMED, MIN AREA 20.5 SF	219.000	LFT
109	715-07590 CULVERT	4.000	LFT
110	715-08303 CONCRETE ANCHOR, MIN AREA 20.5 SF	1.000	EACH
111	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	146.000	TON
112	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	223.000	TON
113	715-46000 PIPE END SECTION, 12 IN	4.000	EACH
114	715-46005 PIPE END SECTION, 15 IN	2.000	EACH
115	715-46010 PIPE END SECTION, 18 IN	2.000	EACH
116	715-46020 PIPE END SECTION, 24 IN	3.000	EACH
117	715-91361 PIPE, PVC, 6 IN	31.000	LFT
118	715-91584 PIPE, PVC, 1.5 IN.	6.000	LFT
119	715-92037 PIPE, PVC, 4 IN	26.000	LFT
120	715-92537 PIPE, PVC, 8 IN	5.000	LFT
121	718-06526 HMA FOR UNDERDRAINS	242.000	TON
122	718-52610 AGGREGATE FOR UNDERDRAINS	1,036.000	CYS
123	718-99153 GEOTEXTILES FOR UNDERDRAIN	13,334.000	SYS
124	720-44000 CASTING, ADJUST TO GRADE	35.000	EACH
125	720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE	1.000	EACH
126	720-44055 CASTING, 10, FURNISH AND ADJUST TO GRADE	1.000	EACH
127	720-45030 INLET, E7	18.000	EACH
128	720-45035 INLET, F7	20.000	EACH
129	720-45040 INLET, G7	1.000	EACH
130	720-45045 INLET, J10	72.000	EACH
131	720-45055 INLET, M10	41.000	EACH
132	720-45075 INLET, R13	13.000	EACH
133	720-45145 INLET, J10, MODIFIED	10.000	EACH
134	720-45155 INLET, M10, MODIFIED	6.000	EACH
135	720-45410 MANHOLE, C4	103.000	EACH
136	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	4.000	LFT
137	720-91973 MANHOLE, H4	8.000	EACH
138	720-93411 INLET, C15, MODIFIED	1.000	EACH
139	720-95409 MANHOLE, J4, MODIFIED	1.000	EACH
140	720-95422 MANHOLE, J4	4.000	EACH
141	720-97958 MANHOLE, K2	1.000	EACH
142	720-98174 INLET, B15	7.000	EACH
143	720-98555 INLET, C15	5.000	EACH
144	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	148.500	LFT
145	732-08419 MODULAR BLOCK WALL	54.800	SYS
146	732-08420 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	521.900	SYS
147	732-08421 MODULAR BLOCK WALL ERECTION	576.600	SYS



CALL ORDER : 205

CONTRACT ID : R -29482-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
148	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	7.000 EACH
149	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	49.000 EACH
150	801-01851	TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP LUMP
151	801-03290	CONSTRUCTION SIGN, C	6.000 EACH
152	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.000 EACH
153	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	71,607.000 LFT
154	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	11,279.000 LFT
155	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	10.000 EACH
156	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	279.000 LFT
157	801-06625	DETOUR ROUTE MARKER ASSEMBLY	26.000 EACH
158	801-06640	CONSTRUCTION SIGN, A	33.000 EACH
159	801-06775	MAINTAINING TRAFFIC	LUMP LUMP
160	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.000 EACH
161	801-07118	BARRICADE, III-A	110.000 LFT
162	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	245.000 LFT
163	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	753.000 LFT
164	802-09837	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.080 IN	19.800 SFT
165	802-09838	SIGN, SHEET, WITH LEGEND 0.080"	363.500 SFT
166	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN	91.250 SFT
167	802-09840	SIGN, SHEET, WITH LEGEND 0.100 IN	112.670 SFT
168	802-09842	SIGN, SHEET, WITH LEGEND 0.125 IN	94.660 SFT
169	802-91122	SIGN, GROUND MOUNTED, RESET	2.000 EACH
170	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000 EACH
171	805-01842	HANDHOLE, SIGNAL	5.000 EACH
172	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP LUMP
173	805-02151	PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 12 IN	4.000 EACH
174	805-02262	FLASHER INSTALLATION, LOCATION	LUMP LUMP
175	805-03372	TETHER FOR SIGNAL	4.000 EACH
176	805-78100	CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000 EACH
177	805-78205	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	4.000 EACH
178	805-78230	TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN	4.000 EACH
179	805-78370	PEDESTRIAN PUSH BUTTON	3.000 EACH
180	805-78420	DISCONNECT HANGER	4.000 EACH
181	805-78445	SIGNAL SERVICE	1.000 EACH
182	805-78470	SIGNAL CABLE, ROADWAY LOOP, 1C 14GA	2,830.000 LFT
183	805-78480	SIGNAL CABLE, 3C 14GA	330.000 LFT
184	805-78485	SIGNAL CABLE, 5C 14GA	360.000 LFT
185	805-78490	SIGNAL CABLE, 7C 14GA	640.000 LFT
186	805-78510	SIGNAL CABLE, 2C 16GA., SHIELDED	820.000 LFT
187	805-78785	SIGNAL DETECTOR HOUSING	9.000 EACH
188	805-78795	SAW CUT FOR ROADWAY LOOP AND SEALANT	1,080.000 LFT
189	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN	651.000 LFT
190	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	24,247.000 LFT
191	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	338.000 LFT
192	808-06716	LINE, REMOVE	46,760.000 LFT
193	808-08258	TRANSVERSE MARKINGS	31.000 LFT
194	808-75043	LINE THERMOPLASTIC, SOLID, WHITE, 6 IN	2,475.000 LFT
195	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN	376.000 LFT
196	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN	382.000 LFT

CALL ORDER : 205

CONTRACT ID : R -29482-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
197	808-75063 LINE, PREFORMED PLASTIC, BROKEN, YELLOW, 4 IN	80.500	LFT
198	808-75067 TRANSVERSE MARKING, PREFORMED PLASTIC, STOP LINE	22.000	LFT
199	808-75069 TRANSVERSE MARKING, PREFORMED PLASTIC,	152.000	LFT
200	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	3,385.000	LFT
201	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	22,595.000	LFT
202	808-75260 TRANSVERSE MARKING THERMOPLASTIC, SOLID,	58.000	LFT
203	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	525.000	LFT
204	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	74.000	EACH
205	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	54.000	EACH
206	801-06539 TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	LUMP	LUMP
207	801-02595 CONTROLLER, RESET TIMING	1.000	EACH
208	805-78900 PEDESTAL FOUNDATION, A	1.000	EACH
209	805-90005 SIGNAL PEDESTAL, 10 FT	1.000	EACH
210	702-51863 FIELD DRILLED HOLE IN CONCRETE	263.000	EACH
211	605-06140 CURB AND GUTTER, CONCRETE	4.000	LFT

CALL ORDER : 211

CONTRACT ID : R -29568-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITIES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	38.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-02245 TREE, 6 IN, REMOVE	7.000	EACH
12	201-02250 TREE, 10 IN, REMOVE	10.000	EACH
13	201-02255 TREE, 18 IN, REMOVE	19.000	EACH
14	201-02260 TREE, 30 IN, REMOVE	7.000	EACH
15	201-02264 TREE, 42 IN, REMOVE	1.000	EACH
16	201-02265 TREE, 48 IN, REMOVE	1.000	EACH
17	201-02270 TREE, 60 IN, REMOVE	1.000	EACH
18	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
19	201-91010 TREE, 24 IN, REMOVE	22.000	EACH
20	201-91011 TREE, 36 IN, REMOVE	1.000	EACH
21	201-93091 TREE, 15 IN, REMOVE	14.000	EACH
22	201-93898 TREE, 12 IN, REMOVE	35.000	EACH
23	202-02240 PAVEMENT REMOVAL	35.000	SYS
24	202-91840 FENCE, CHAIN LINK, REMOVE	20.000	LFT
25	203-02000 EXCAVATION, COMMON	4,800.000	CYS
26	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	4.000	EACH
27	205-02770 EROSION CONTROL BLANKET	433.000	SYS
28	205-06937 TEMPORARY SILT FENCE	14,036.000	LFT
29	207-08267 SUBGRADE TREATMENT, TYPE IIIA	10,590.000	SYS
30	211-02050 B BORROW	1,100.000	CYS
31	211-07454 STRUCTURAL BACKFILL	200.000	CYS
32	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,230.000	TON
33	303-07449 COMPACTED AGGREGATE, NO. 73	1,350.000	TON
34	402-07432 HMA SURFACE, TYPE A	420.000	TON
35	402-07435 HMA INTERMEDIATE, TYPE A	910.000	TON
36	402-07440 HMA BASE, TYPE A	110.000	TON
37	601-01115 GUARDRAIL, W BEAM, 1 FT 6.75 IN SPACING	465.000	LFT
38	601-02103 GUARDRAIL, W BEAM, SHOP CURVED, 6 FT 3 IN SPACING	70.000	LFT
39	601-06037 GUARDRAIL END TREATMENT, I	6.000	EACH
40	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	401.000	LFT
41	603-01984 BICYCLE GATE	2.000	EACH
42	603-01984 BICYCLE GATE	9.000	EACH
43	604-06070 SIDEWALK, CONCRETE	987.000	SYS
44	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
45	615-97672 TRASH RECEPTACLE	4.000	EACH
46	616-06405 RIPRAP, REVETMENT	65.000	TON
47	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	10.000	EACH
48	621-06559 MULCHED SEEDING, R	9,420.000	SYS
49	622-05639 PLANT, DECIDUOUS SHRUB, 18 TO 24 IN	5.000	EACH

CALL ORDER : 211

CONTRACT ID : R -29568-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITIES		
50	628-09401 FIELD OFFICE, A	19.000	MOS
51	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	19.000	MOS
52	702-51015 CONCRETE, B, FOOTINGS	30.000	CYS
53	702-93722 CONCRETE, C	295.000	CYS
54	703-06029 REINFORCING BARS, EPOXY COATED	17,865.000	LBS
55	711-02554 PEDESTRIAN BRIDGE	LUMP	LUMP
56	711-02554 PEDESTRIAN BRIDGE	LUMP	LUMP
57	712-03812 BENCH	4.000	EACH
58	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	200.000	LFT
59	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	2.000	LFT
60	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN	292.000	LFT
61	715-05173 PIPE, TYPE 3, CIRCULAR, 24 IN	60.000	LFT
62	715-46000 PIPE END SECTION, 12 IN	9.000	EACH
63	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	200.000	LFT
64	718-52610 AGGREGATE FOR UNDERDRAINS	18.000	CYS
65	718-99153 GEOTEXTILES FOR UNDERDRAIN	40.000	SYS
66	720-45075 INLET, R13	1.000	EACH
67	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
68	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
69	801-08402 TEMPORARY TRAFFIC BARRIER, TYPE 3	64.000	LFT
70	802-03776 SIGN POST, WOOD, 6 IN X 6 IN	555.000	LFT
71	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	296.000	LFT
72	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	2,157.000	SFT
73	808-03114 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (XING) 8 FT	14.000	EACH
74	808-03442 PAVEMENT MESSAGE MARKING, PAINT, BIKE SYMBOL	14.000	EACH
75	808-03442 PAVEMENT MESSAGE MARKING, PAINT, BIKE SYMBOL	4.000	EACH
76	808-05535 TRANSVERSE MARKINGS EPOXY SOLID WHITE,	810.000	LFT
77	808-06723 PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	4.000	EACH
78	808-74804 LINE, EPOXY, SOLID, WHITE, 6 IN	5,620.000	LFT

CALL ORDER : 231

CONTRACT ID : R -29969-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	16.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	202-96133 PIPE, REMOVE	44.000	LFT
14	202-99187 FENCE, FARM FIELD, REMOVE	461.000	LFT
15	203-02000 EXCAVATION, COMMON	1,036.000	CYS
16	203-51223 EXCAVATION, WATERWAY	131.000	CYS
17	205-02770 EROSION CONTROL BLANKET	278.000	SYS
18	205-03371 SEDIMENT, REMOVE	14.200	CYS
19	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	4.500	TON
20	205-06932 TEMPORARY CHECK DAM, STRAW BALES	132.000	LFT
21	205-06936 TEMPORARY SEDIMENT TRAP	42.000	TON
22	205-06937 TEMPORARY SILT FENCE	668.000	LFT
23	205-09543 NO 2 STONE	100.000	TON
24	207-08265 SUBGRADE TREATMENT, TYPE IIA	1,823.000	SYS
25	207-08267 SUBGRADE TREATMENT, TYPE IIIA	91.000	SYS
26	211-09264 STRUCTURAL BACKFILL, TYPE 1	19.000	CYS
27	211-09268 STRUCTURAL BACKFILL, TYPE 5	302.000	CYS
28	214-07202 GEOGRID, TYPE I	261.000	SYS
29	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	328.000	TON
30	303-01180 COMPACTED AGGREGATE, NO. 53	569.000	TON
31	306-08033 MILLING, ASPHALT, 1 IN	350.000	SYS
32	306-08034 MILLING, ASPHALT, 1 1/2 IN	60.000	SYS
33	306-08037 MILLING, ASPHALT, 3 IN	200.000	SYS
34	306-08042 MILLING, SCARIFICATION/PROFILE	430.000	SYS
35	306-08043 MILLING, TRANSITION	240.000	SYS
36	402-07433 HMA SURFACE, TYPE B	201.000	TON
37	402-07438 HMA INTERMEDIATE, TYPE B	702.000	TON
38	406-05520 ASPHALT FOR TACK COAT	0.900	TON
39	601-02241 GUARDRAIL, REMOVE	397.000	LFT
40	601-06854 GUARDRAIL, W-BEAM, NESTED	1.000	EACH
41	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
42	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	313.000	LFT
43	610-07487 HMA FOR APPROACHES, TYPE B	25.000	TON
44	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
45	615-06490 RIGHT OF WAY MARKER	20.000	EACH
46	615-06505 MONUMENT, B	3.000	EACH
47	615-06530 BENCH MARK POST	1.000	EACH
48	616-02320 GEOTEXTILES	197.000	SYS
49	616-05688 RIPRAP, CLASS 1	165.000	TON

CALL ORDER : 231

CONTRACT ID : R -29969-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50	616-06451 RIPRAP, UNIFORM	185.000	TON
51	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
52	621-06545 FERTILIZER	0.100	TON
53	621-06557 SEED MIXTURE, T	19.000	LBS
54	621-06559 MULCHED SEEDING, R	29.000	SYS
55	621-06565 MULCHING MATERIAL	0.500	TON
56	621-06567 WATER	9.300	KGAL
57	621-06574 SODDING	222.000	SYS
58	622-52436 SIGN, DO NOT MOW OR SPRAY	2.000	EACH
59	622-98200 SIGN, DO NOT DISTURB	2.000	EACH
60	628-09401 FIELD OFFICE, A	8.000	MOS
61	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	8.000	MOS
62	714-03591 STRUCTURE, PRECAST REINFORCED CONCRETE	69.750	LFT
63	714-08514 WINGWALL	312.000	SFT
64	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN	60.000	LFT
65	715-05438 PIPE, DRAIN TILE TERMINAL SECTION, 4 IN	5.000	LFT
66	715-46010 PIPE END SECTION, 18 IN	2.000	EACH
67	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
68	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
69	801-06625 DETOUR ROUTE MARKER ASSEMBLY	31.000	EACH
70	801-06640 CONSTRUCTION SIGN, A	15.000	EACH
71	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
72	801-07118 BARRICADE, III-A	60.000	LFT
73	801-07119 BARRICADE, III-B	48.000	LFT
74	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	17.750	LFT
75	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
76	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,340.000	LFT
77	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	670.000	LFT
78	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2,595.000	LFT
79	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	17.000	EACH
80	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	17.000	EACH

CALL ORDER : 251

CONTRACT ID : R -30953-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	100.000	SYS
10	202-96133 PIPE, REMOVE	54.000	LFT
11	202-99187 FENCE, FARM FIELD, REMOVE	2,786.000	LFT
12	203-02000 EXCAVATION, COMMON	9,073.000	CYS
13	203-02010 EXCAVATION, ROCK	10.000	CYS
14	203-02070 BORROW	6,788.000	CYS
15	203-09334 BACKFILL, ROCK	63.000	TON
16	205-03371 SEDIMENT, REMOVE	74.000	CYS
17	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	301.410	TON
18	205-06932 TEMPORARY CHECK DAM, STRAW BALES	285.000	LFT
19	205-06937 TEMPORARY SILT FENCE	1,050.000	LFT
20	207-08262 SUBGRADE TREATMENT, TYPE I	8,912.000	SYS
21	211-09264 STRUCTURAL BACKFILL, TYPE 1	80.000	CYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,945.000	TON
23	303-01180 COMPACTED AGGREGATE, NO. 53	84.000	TON
24	306-08043 MILLING, TRANSITION	100.000	SYS
25	306-08432 MILLING, APPROACH	100.000	SYS
26	402-07432 HMA SURFACE, TYPE A	663.000	TON
27	402-07435 HMA INTERMEDIATE, TYPE A	1,114.000	TON
28	406-05520 ASPHALT FOR TACK COAT	2.000	TON
29	610-07486 HMA FOR APPROACHES, TYPE A	162.000	TON
30	611-06497 MAILBOX ASSEMBLY, SINGLE	6.000	EACH
31	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
32	615-06490 RIGHT OF WAY MARKER	35.000	EACH
33	615-06505 MONUMENT, B	20.000	EACH
34	616-02320 GEOTEXTILES	847.000	SYS
35	616-05688 RIPRAP, CLASS 1	7.000	TON
36	616-06405 RIPRAP, REVETMENT	46.000	TON
37	616-06451 RIPRAP, UNIFORM	358.000	TON
38	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
39	621-02770 EROSION CONTROL BLANKET	1,049.000	SYS
40	621-06545 FERTILIZER	2.000	TON
41	621-06553 SEED MIXTURE, R	816.000	LBS
42	621-06565 MULCHING MATERIAL	10.000	TON
43	621-06574 SODDING	3,500.000	SYS
44	628-09402 FIELD OFFICE, B	12.000	MOS
45	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN	8.000	EACH
46	715-03476 SAFETY METAL END SECTION, 4:1, 24 IN	2.000	EACH
47	715-03584 SAFETY METAL END SECTION, 4:1, 18 IN	3.000	EACH
48	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN	126.000	LFT
49	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN	86.000	LFT

CALL ORDER : 251

CONTRACT ID : R -30953-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
50	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN	153.000	LFT
51	715-46010 PIPE END SECTION, 18 IN	1.000	EACH
52	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
53	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
54	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
55	801-07119 BARRICADE, III-B	60.000	LFT
56	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	123.000	LFT
57	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	5,250.000	LFT
58	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5,010.000	LFT
59	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	32.000	LFT



CALL ORDER : 261

CONTRACT ID : R -31065-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PEDESTRIAN IMPROVEMENTS, SIDEWALKS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02272 PAVED SIDE DITCH, REMOVE	36.000	LFT
12	202-02279 CURB AND GUTTER, REMOVE	438.000	LFT
13	203-02000 EXCAVATION, COMMON	268.000	CYS
14	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	9.000	EACH
15	205-03371 SEDIMENT, REMOVE	2.000	CYS
16	205-06937 TEMPORARY SILT FENCE	2,567.000	LFT
17	205-09543 NO 2 STONE	100.000	TON
18	207-08267 SUBGRADE TREATMENT, TYPE IIIA	70.000	SYS
19	211-09265 STRUCTURAL BACKFILL, TYPE 2	28.000	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	20.000	TON
21	603-06065 FENCE, CHAIN LINK, RESET	554.000	LFT
22	604-07894 CURB RAMP, CONCRETE, A	17.000	SYS
23	604-07901 CURB RAMP, CONCRETE, G	15.000	SYS
24	604-91531 SIDEWALK, CONCRETE, 4 IN	2,260.000	SYS
25	605-06120 CURB, CONCRETE	292.000	LFT
26	610-08446 PCCP FOR APPROACHES, 6 IN	70.000	SYS
27	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	9.000	EACH
28	616-02320 GEOTEXTILES	63.000	SYS
29	616-06406 RIPRAP, REVETMENT	31.000	SYS
30	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
31	621-06545 FERTILIZER	1.000	TON
32	621-06554 SEED MIXTURE, U	74.000	LBS
33	621-06557 SEED MIXTURE, T	147.000	LBS
34	621-06565 MULCHING MATERIAL	1.000	TON
35	628-09402 FIELD OFFICE, B	10.000	MOS
36	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN	28.000	LFT
37	715-46005 PIPE END SECTION, 15 IN	1.000	EACH
38	715-91361 PIPE, PVC, 6 IN	28.000	LFT
39	720-04682 INLET	2.000	EACH
40	720-44000 CASTING, ADJUST TO GRADE	8.000	EACH
41	720-45145 INLET, J10, MODIFIED	1.000	EACH
42	801-03290 CONSTRUCTION SIGN, C	5.000	EACH
43	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
44	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
45	802-07060 SIGN, SHEET, RELOCATE	5.000	EACH
46	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	212.000	LFT

CALL ORDER : 271

CONTRACT ID : R -31160-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	823.000	CYS
11	205-03371 SEDIMENT, REMOVE	5.000	CYS
12	205-06933 TEMPORARY DITCH INLET PROTECTION	6.000	EACH
13	205-06937 TEMPORARY SILT FENCE	1,125.000	LFT
14	207-08264 SUBGRADE TREATMENT, TYPE II	430.000	SYS
15	207-08267 SUBGRADE TREATMENT, TYPE IIIA	898.000	SYS
16	207-08268 SUBGRADE TREATMENT, TYPE IV	4,229.000	SYS
17	211-09264 STRUCTURAL BACKFILL, TYPE 1	73.000	CYS
18	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	450.000	TON
19	304-07492 WIDENING WITH HMA, TYPE A	290.000	TON
20	306-08034 MILLING, ASPHALT, 1 1/2 IN	365.000	SYS
21	306-08037 MILLING, ASPHALT, 3 IN	200.000	SYS
22	306-08043 MILLING, TRANSITION	101.000	SYS
23	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	750.000	TON
24	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,275.000	TON
25	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	1,800.000	TON
26	402-07450 HMA WEDGE AND LEVEL, TYPE A	1,022.000	TON
27	406-05520 ASPHALT FOR TACK COAT	6.800	TON
28	601-06035 GUARDRAIL, RESET	14.000	LFT
29	601-07050 GUARDRAIL END TREATMENT, OS, RESET	1.000	EACH
30	604-91531 SIDEWALK, CONCRETE, 4 IN	73.000	SYS
31	605-06120 CURB, CONCRETE	223.000	LFT
32	605-06140 CURB AND GUTTER, CONCRETE	267.000	LFT
33	610-07487 HMA FOR APPROACHES, TYPE B	688.000	TON
34	611-06497 MAILBOX ASSEMBLY, SINGLE	5.000	EACH
35	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
36	621-06560 MULCHED SEEDING, U	500.000	SYS
37	621-06567 WATER	1.000	KGAL
38	621-06575 SODDING, NURSERY	70.000	SYS
39	628-09401 FIELD OFFICE, A	8.000	MOS
40	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN	118.000	LFT
41	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN	129.000	LFT
42	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	15.000	TON
43	715-09064 VIDEO INSPECTION FOR PIPE	247.000	LFT
44	720-44000 CASTING, ADJUST TO GRADE	8.000	EACH
45	720-45075 INLET, R13	1.000	EACH
46	720-45105 INLET, A2, MODIFIED	1.000	EACH
47	720-93409 INLET, B15, MODIFIED	1.000	EACH
48	720-94847 INLET, R13, MODIFIED	1.000	EACH
49	720-98555 INLET, C15	2.000	EACH

CALL ORDER : 271

CONTRACT ID : R -31160-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
51	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
52	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
53	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
54	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	75.000	LFT
55	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	101.750	SFT
56	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	9.000	SFT
57	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
58	805-01815 SIGNAL SUPPORT FOUNDATION, 36 IN X 144 IN	4.000	EACH
59	805-01842 HANDHOLE, SIGNAL	6.000	EACH
60	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	650.000	LFT
61	805-01879 SIGNAL SERVICE	1.000	EACH
62	805-09471 SIGNAL CABLE, PREFORMED PAVE-OVER LOOP	32.000	EACH
63	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
64	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	4.000	EACH
65	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN	4.000	EACH
66	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
67	805-78420 DISCONNECT HANGER	4.000	EACH
68	805-78467 SIGNAL CABLE, 3C 8GA	22.000	LFT
69	805-78485 SIGNAL CABLE, 5C 14GA	175.000	LFT
70	805-78490 SIGNAL CABLE, 7C 14GA	600.000	LFT
71	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,100.000	LFT
72	805-78785 SIGNAL DETECTOR HOUSING	10.000	EACH
73	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
74	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	4.000	EACH
75	808-75205 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,302.000	LFT
76	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1,816.000	LFT
77	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	108.000	LFT
78	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	6.000	EACH
79	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	2.000	EACH
80	808-92027 LINE, THERMO, SOLID, YELLOW, 8 IN	1,621.000	LFT
81	808-96016 LINE, THERMOPLASTIC SOLID, YELLOW, 12 IN	240.000	LFT

CALL ORDER : 281

CONTRACT ID : R -31651-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT, CONCRETE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	5.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	145.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
9	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
10	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
11	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
12	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-01066 HYDRO DEMOLITION	6,298.000	SYS
16	202-02240 PAVEMENT REMOVAL	777.000	SYS
17	202-02240 PAVEMENT REMOVAL	88,777.000	SYS
18	202-02278 CURB, CONCRETE, REMOVE	3,600.000	LFT
19	202-02286 PRESENT STRUCTURE, REMOVE	66.000	EACH
20	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
21	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
22	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
23	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
24	202-51368 SLOPEWALL, REMOVE	673.000	SYS
25	202-51822 BRIDGE DECK OVERLAY, REMOVE	6,298.000	SYS
26	202-74045 SIGN AND SUPPORTS, CHAN POSTS, REMOVE	72.000	EACH
27	202-96133 PIPE, REMOVE	3,601.000	LFT
28	203-02000 EXCAVATION, COMMON	11,964.000	CYS
29	203-02070 BORROW	116.000	CYS
30	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	29.000	EACH
31	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	22.000	EACH
32	205-02459 EROSION CONTROL	LUMP	LUMP
33	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	895.000	TON
34	205-06937 TEMPORARY SILT FENCE	5,331.000	LFT
35	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	60.000	CYS
36	207-08263 SUBGRADE TREATMENT, TYPE IA	74,450.000	SYS
37	207-08267 SUBGRADE TREATMENT, TYPE IIIA	11,565.000	SYS
38	211-06467 AGGREGATE FOR END BENT BACKFILL	66.000	CYS
39	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,730.000	CYS
40	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	225.000	CYS
41	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	19,285.000	TON
42	302-06464 SUBBASE FOR PCCP	18,612.000	CYS
43	302-07455 DENSE GRADED SUBBASE	137.200	CYS
44	306-08042 MILLING, SCARIFICATION/PROFILE	12,365.000	SYS
45	306-08043 MILLING, TRANSITION	570.000	SYS
46	306-08159 MILLING ASPHALT	10,970.000	SYS
47	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
48	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,160.000	TON
49	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	1,840.000	TON

CALL ORDER : 281

CONTRACT ID : R -31651-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT, CONCRETE		
50	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	3,680.000	TON
51	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	4,130.000	TON
52	406-05520 ASPHALT FOR TACK COAT	16.000	TON
53	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
54	501-06321 QC/QA-PCCP, 10 IN	74,585.000	SYS
55	501-06325 QC/QA-PCCP, 14 IN	785.000	SYS
56	503-05240 D-1 CONTRACTION JOINT	41,880.000	LFT
57	503-05310 TERMINAL JOINT	315.000	LFT
58	601-01115 GUARDRAIL, W BEAM, 1 FT 6.75 IN SPACING	45.310	LFT
59	601-01522 GUARDRAIL TRANSITION TYPE TGB	16.000	EACH
60	601-01700 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 1	1.000	EACH
61	601-02241 GUARDRAIL, REMOVE	7,138.000	LFT
62	601-94689 GUARDRAIL END TREATMENT, OS	14.000	EACH
63	601-94690 GUARDRAIL END TREATMENT, MS	5.000	EACH
64	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	4,050.000	LFT
65	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	725.000	LFT
66	602-06729 BARRIER DELINEATOR	84.000	EACH
67	603-03829 FENCE	202.000	LFT
68	603-03829 FENCE	214.000	LFT
69	604-91531 SIDEWALK, CONCRETE, 4 IN	795.000	SYS
70	605-06090 CURB, INTEGRAL, CONCRETE	900.000	LFT
71	605-06140 CURB AND GUTTER, CONCRETE	3,335.000	LFT
72	605-94811 CURB TURNOUT	8.000	EACH
73	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	787.900	SYS
74	610-09108 PCCP FOR APPROACHES, 9 IN	942.000	SYS
75	615-06510 MONUMENT, C	5.000	EACH
76	615-06515 MONUMENT, D	27.000	EACH
77	616-02320 GEOTEXTILES	2,626.000	SYS
78	616-06405 RIPRAP, REVETMENT	1,078.000	TON
79	616-06451 RIPRAP, UNIFORM	670.000	TON
80	616-51367 SLOPEWALL, CONCRETE, 4 IN	673.000	SYS
81	616-93772 INSPECTION HOLE	6.000	EACH
82	619-09429 CLEAN STEEL BRIDGE, PARTIAL TYPE 1, QP-2	1,262.000	SFT
83	619-09429 CLEAN STEEL BRIDGE, PARTIAL TYPE 1, QP-2	1,182.000	SFT
84	619-09429 CLEAN STEEL BRIDGE, PARTIAL TYPE 1, QP-2	1,205.000	SFT
85	619-09437 PAINT STEEL BRIDGE, PARTIAL, TYPE 1	1,262.000	SFT
86	619-09437 PAINT STEEL BRIDGE, PARTIAL, TYPE 1	1,182.000	SFT
87	619-09437 PAINT STEEL BRIDGE, PARTIAL, TYPE 1	1,205.000	SFT
88	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
89	621-06554 SEED MIXTURE, U	2,346.000	LBS
90	621-06570 TOPSOIL	17,962.000	CYS
91	621-06574 SODDING	249.000	SYS
92	621-06575 SODDING, NURSERY	28,770.000	SYS
93	628-09403 FIELD OFFICE, C	29.000	MOS
94	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	58.000	MOS
95	702-04325 TEMPORARY SHORING	LUMP	LUMP
96	702-04325 TEMPORARY SHORING	LUMP	LUMP
97	702-51005 CONCRETE, A, SUBSTRUCTURE	49.000	CYS
98	702-51100 DRAIN PIPE, CAST IRON, 6 IN	9,578.000	LBS

CALL ORDER : 281

CONTRACT ID : R -31651-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT, CONCRETE		
99	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	1,536.000	LBS
100	702-51863 FIELD DRILLED HOLE IN CONCRETE	7,116.000	EACH
101	703-06028 REINFORCING BARS	4,019.000	LBS
102	703-06029 REINFORCING BARS, EPOXY COATED	153,140.000	LBS
103	704-51002 CONCRETE, C, SUPERSTRUCTURE	89.100	CYS
104	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	8.000	EACH
105	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	8.000	EACH
106	706-51020 CONCRETE, C, RAILING	279.300	CYS
107	708-51814 WELDED STEEL WIRE FABRIC	528.000	SFT
108	709-51821 SURFACE SEAL	LUMP	LUMP
109	709-51821 SURFACE SEAL	LUMP	LUMP
110	709-51821 SURFACE SEAL	LUMP	LUMP
111	709-51821 SURFACE SEAL	LUMP	LUMP
112	710-09158 PATCHING CONCRETE STRUCTURES	900.000	SFT
113	711-51035 STRUCTURAL STEEL	1,123.000	LBS
114	715-02628 SAFETY METAL END SECTION, 6:1, 15 IN	2.000	EACH
115	715-03476 SAFETY METAL END SECTION, 4:1, 24 IN	2.000	EACH
116	715-04611 SAFETY METAL END SECTION, 4:1, 12 IN	1.000	EACH
117	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	34,651.000	LFT
118	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	8,033.000	LFT
119	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN	243.000	LFT
120	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN	66.000	LFT
121	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN	1,954.000	LFT
122	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN	622.000	LFT
123	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN	184.000	LFT
124	715-05168 PIPE, TYPE 3, CIRCULAR, 12 IN	54.000	LFT
125	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN	267.000	LFT
126	715-06629 PIPE END SECTION, MIN. AREA 10.2 SFT.	2.000	EACH
127	715-08177 PIPE, TYPE 1, DEFORMED, MIN AREA 10.2 SF	70.000	LFT
128	715-46000 PIPE END SECTION, 12 IN	28.000	EACH
129	715-46005 PIPE END SECTION, 15 IN	3.000	EACH
130	715-46010 PIPE END SECTION, 18 IN	3.000	EACH
131	718-06529 OUTLET PROTECTOR, 2	61.000	EACH
132	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	42,684.000	LFT
133	718-52610 AGGREGATE FOR UNDERDRAINS	3,136.000	CYS
134	720-44000 CASTING, ADJUST TO GRADE	8.000	EACH
135	720-45065 INLET, N12	15.000	EACH
136	720-45070 INLET, P12A	9.000	EACH
137	720-45250 CATCH BASIN, K10	17.000	EACH
138	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	9,985.000	SFT
139	722-51842 BRIDGE DECK OVERLAY	6,298.000	SYS
140	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	226.000	CYS
141	722-51874 OVERLAY DAM	80.000	SFT
142	722-60824 SURFACE MILLING	6,298.000	SYS
143	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	86.000	LFT
144	724-51925 STRUCTURAL EXPANSION JOINT, SS	260.000	LFT
145	801-03290 CONSTRUCTION SIGN, C	16.000	EACH
146	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	70,649.000	LFT
147	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	140,309.000	LFT

CALL ORDER : 281

CONTRACT ID : R -31651-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT, CONCRETE		
148	801-06577 TEMPORARY PAVEMENT MARKING	1,741.000	LFT
149	801-06640 CONSTRUCTION SIGN, A	199.000	EACH
150	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
151	801-07119 BARRICADE, III-B	876.000	LFT
152	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	2,710.000	LFT
153	801-08509 TEMP TRAFFIC BARRIER, TYPE 3, ANCHORED	20.000	LFT
154	801-52818 TEMPORARY CROSSOVER, A	15.000	EACH
155	802-03821 SIGN, SHEET, WITH LEGEND	3.000	EACH
156	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	1,187.000	LFT
157	802-07060 SIGN, SHEET, RELOCATE	72.000	EACH
158	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	73.000	SFT
159	805-01842 HANDHOLE, SIGNAL	16.000	EACH
160	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	2,865.000	LFT
161	805-01879 SIGNAL SERVICE	1.000	EACH
162	805-02328 SIGNAL CABLE, 1C 14GA	2,658.000	LFT
163	805-04973 CONDUIT	1.000	LFT
164	805-09094 SIGNAL CONTROLLER, TS2, TYPE 1	1.000	EACH
165	805-09539 LOOP DETECTOR DELAY COUNTING AMPLIFIER, 2 CHANNEL	19.000	EACH
166	805-09540 LOOP DETECTOR RACK	4.000	EACH
167	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	5.000	EACH
168	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	3.000	EACH
169	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12 IN	3.000	EACH
170	805-78415 SPAN, CATENARY, AND TETHER	2.000	EACH
171	805-78420 DISCONNECT HANGER	2.000	EACH
172	805-78485 SIGNAL CABLE, 5C 14GA	585.000	LFT
173	805-78490 SIGNAL CABLE, 7C 14GA	510.000	LFT
174	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	7,740.000	LFT
175	805-03175 PREFORMED LOOP DETECTOR	66.000	EACH
176	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
177	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	870.000	LFT
178	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
179	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT	3.000	EACH
180	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHAN	2.000	EACH
181	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN	5,130.000	LFT
182	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN	19,435.000	LFT
183	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN	17,620.000	LFT
184	808-05534 LINE, EPOXY, SOLID, WHITE, 8 IN	595.000	LFT
185	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	5,140.000	LFT
186	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	5,140.000	LFT
187	808-06716 LINE, REMOVE	142,050.000	LFT
188	808-07831 LINE, EPOXY, SOLID, YELLOW, 12 IN.	30.000	LFT
189	808-74807 PAVEMENT MESSAGE MARKING, EPOXY, LANE INDICATIONS ARROWS	42.000	EACH
190	808-75067 TRANSVERSE MARKING, PREFORMED PLASTIC, STOP LINE	490.000	LFT
191	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5,140.000	LFT
192	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	261.000	EACH
193	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	273.000	EACH
194	808-98796 LINE, THERMOPLASTIC DOTTED WHITE, 4 IN, 2FT LINE, 4FT GAP	225.000	LFT

CALL ORDER : 291

CONTRACT ID : R -31744-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	EROSION CONTROL, FAILING RETAINING WALL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	20.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02272 PAVED SIDE DITCH, REMOVE	124.000	LFT
12	203-02020 EXCAVATION, UNCLASSIFIED	2,925.000	CYS
13	205-06932 TEMPORARY CHECK DAM, STRAW BALES	40.000	LFT
14	205-06937 TEMPORARY SILT FENCE	80.000	LFT
15	211-09266 STRUCTURAL BACKFILL, TYPE 3	2,310.000	CYS
16	303-08210 COMPACTED AGGREGATE NO. 53, TEMP FOR DRIVEWAYS	120.000	TON
17	616-02320 GEOTEXTILES	1,989.000	SYS
18	616-06405 RIPRAP, REVETMENT	203.000	TON
19	616-06451 RIPRAP, UNIFORM	142.000	TON
20	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
21	621-06559 MULCHED SEEDING, R	2,152.000	SYS
22	621-06570 TOPSOIL	719.000	CYS
23	621-06574 SODDING	98.000	SYS
24	628-09402 FIELD OFFICE, B	10.000	MOS
25	701-02936 PILE, STEEL H, HP 14 IN X 89	1,915.000	LFT
26	701-02938 CORED HOLE IN ROCK, 24 IN	852.000	LFT
27	711-51035 STRUCTURAL STEEL	1,490.000	LBS
28	713-04509 TEMPORARY PIPE	LUMP	LUMP
29	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	420.000	LFT
30	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	30.000	LFT
31	731-93945 FACE PANELS, CONCRETE	5,426.000	SFT
32	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
33	801-06196 DETOUR ROUTE MARKER ASSEMBLY, MULTIPLE ROUTES	24.000	EACH
34	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2,631.000	LFT
35	801-06625 DETOUR ROUTE MARKER ASSEMBLY	9.000	EACH
36	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
37	801-06645 CONSTRUCTION SIGN, B	5.000	EACH
38	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
39	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	1.000	EACH
40	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	910.000	LFT
41	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	896.000	LFT
42	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	1,754.000	LFT
43	808-06716 LINE, REMOVE	1,754.000	LFT



CALL ORDER : 301

CONTRACT ID : R -31984-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,599.000	TON
14	303-01180 COMPACTED AGGREGATE, NO. 53	4,775.000	TON
15	304-07491 HMA PATCHING, TYPE C	2,924.000	TON
16	306-08042 MILLING, SCARIFICATION/PROFILE	133,092.000	SYS
17	306-08043 MILLING, TRANSITION	3,235.000	SYS
18	306-08432 MILLING, APPROACH	3,063.000	SYS
19	306-08563 MILLING ASPHALT, 1 1/4 IN	40,861.000	SYS
20	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
21	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	14,618.000	TON
22	406-05520 ASPHALT FOR TACK COAT	45.100	TON
23	610-07487 HMA FOR APPROACHES, TYPE B	365.000	TON
24	615-06520 MONUMENT, RE-ESTABLISH	32.000	EACH
25	628-09402 FIELD OFFICE, B	8.000	MOS
26	725-06858 PIPE LINER, THERMOPLASTIC, 36 IN	92.000	LFT
27	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
28	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	13,411.000	LFT
29	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	13,411.000	LFT
30	801-06640 CONSTRUCTION SIGN, A	39.000	EACH
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN	1,043.000	LFT
33	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN	878.000	LFT
34	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	121,492.000	LFT
35	808-06716 LINE, REMOVE	1,922.000	LFT
36	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	12,107.000	LFT
37	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	41,368.000	LFT
38	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	197.000	LFT
39	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	9.000	EACH
40	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	6.000	EACH
41	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,267.000	EACH
42	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,267.000	EACH

CALL ORDER : 311

CONTRACT ID : R -33250-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITIES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
8	202-02278 CURB, CONCRETE, REMOVE	66.000	LFT
9	202-91840 FENCE, CHAIN LINK, REMOVE	1,181.000	LFT
10	202-96133 PIPE, REMOVE	121.000	LFT
11	203-02000 EXCAVATION, COMMON	3,870.000	CYS
12	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	7.000	TON
13	205-06933 TEMPORARY DITCH INLET PROTECTION	6.000	EACH
14	205-06937 TEMPORARY SILT FENCE	21,910.000	LFT
15	207-09895 SUBGRADE TREATMENT, TYPE V	11,994.000	SYS
16	211-09264 STRUCTURAL BACKFILL, TYPE 1	67.000	CYS
17	303-01180 COMPACTED AGGREGATE, NO. 53	7,002.000	TON
18	402-07432 HMA SURFACE, TYPE A	867.000	TON
19	402-07435 HMA INTERMEDIATE, TYPE A	1,319.000	TON
20	406-05520 ASPHALT FOR TACK COAT	3.100	TON
21	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
22	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	1,356.250	LFT
23	603-03829 FENCE	1,105.000	LFT
24	603-03829 FENCE	1,725.000	LFT
25	604-07894 CURB RAMP, CONCRETE, A	61.000	SYS
26	604-07901 CURB RAMP, CONCRETE, G	79.000	SYS
27	604-90256 SIDEWALK, CONCRETE, 6 IN	81.000	SYS
28	616-02320 GEOTEXTILES	543.000	SYS
29	616-06405 RIPRAP, REVETMENT	7.500	TON
30	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
31	621-02770 EROSION CONTROL BLANKET	600.000	SYS
32	621-06545 FERTILIZER	1.000	TON
33	621-06553 SEED MIXTURE, R	405.000	LBS
34	621-06565 MULCHING MATERIAL	5.000	TON
35	621-06570 TOPSOIL	1,923.000	CYS
36	628-09401 FIELD OFFICE, A	9.000	MOS
37	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	9.000	MOS
38	715-05118 PIPE, TYPE 1, CIRCULAR, 12 IN	57.000	LFT
39	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN	23.000	LFT
40	715-46000 PIPE END SECTION, 12 IN	1.000	EACH
41	720-06525 CASTING, ADJUST TO GRADE, MONUMENT	2.000	EACH
42	720-45035 INLET, F7	6.000	EACH
43	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	2.000	LFT
44	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
45	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
46	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
47	802-03776 SIGN POST, WOOD, 6 IN X 6 IN	101.000	LFT
48	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	41.000	LFT
49	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	34.000	SFT

CALL ORDER : 311

CONTRACT ID : R -33250-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITIES		
50	805-02262	FLASHER INSTALLATION, LOCATION	LUMP
51	807-02191	HANDHOLE, LIGHTING	3.000 EACH
52	807-03972	CONDUIT, PVC, 1 IN, SCHEDULE 40, FOR ELECTRIC	202.000 LFT
53	807-04866	LUMINAIRE	2.000 EACH
54	807-04866	LUMINAIRE	16.000 EACH
55	807-04866	LUMINAIRE	7.000 EACH
56	807-05073	JUNCTION BOX	2.000 EACH
57	807-08214	CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC	50.000 LFT
58	807-86805	SERVICE POINT, I	1.000 EACH
59	807-86886	WIRE, XHHW, NO. 8, COPPER, XLP SUNLIGHT RESISTANT	2,875.000 LFT
60	807-86930	INSULATION LINK, NON-WATERPROOFED	17.000 EACH
61	808-75215	LINE, THERMOPLASTIC SOLID WHITE 12 IN	70.000 LFT
62	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	10,881.000 LFT
63	808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	83.000 LFT
64	808-75300	TRANSVERSE MARKING, THERMOPLASTIC,	248.000 LFT

CALL ORDER : 321

CONTRACT ID : R -33302-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BICYCLE LANE AND SIDEWALKS		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	201-93898 TREE, 12 IN, REMOVE	1.000	EACH
12	202-02279 CURB AND GUTTER, REMOVE	178.000	LFT
13	203-02000 EXCAVATION, COMMON	122.000	CYS
14	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	9.000	EACH
15	205-03371 SEDIMENT, REMOVE	2.000	CYS
16	205-06937 TEMPORARY SILT FENCE	771.000	LFT
17	205-09543 NO 2 STONE	100.000	TON
18	211-09265 STRUCTURAL BACKFILL, TYPE 2	68.000	CYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	10.000	TON
20	406-05520 ASPHALT FOR TACK COAT	1.000	TON
21	604-07901 CURB RAMP, CONCRETE, G	30.000	SYS
22	604-07902 CURB RAMP, CONCRETE, H	7.000	SYS
23	604-91531 SIDEWALK, CONCRETE, 4 IN	781.000	SYS
24	605-06120 CURB, CONCRETE	122.000	LFT
25	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	5.000	EACH
26	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
27	621-02770 EROSION CONTROL BLANKET	77.000	SYS
28	621-06545 FERTILIZER	1.000	TON
29	621-06554 SEED MIXTURE, U	21.000	LBS
30	621-06557 SEED MIXTURE, T	42.000	LBS
31	621-06565 MULCHING MATERIAL	1.000	TON
32	628-09402 FIELD OFFICE, B	10.000	MOS
33	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN	84.000	LFT
34	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN	54.000	LFT
35	715-08282 HMA FOR STRUCTURE INSTALLATION, TYPE A	55.000	TON
36	715-91361 PIPE, PVC, 6 IN	10.000	LFT
37	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
38	720-45045 INLET, J10	2.000	EACH
39	720-45055 INLET, M10	1.000	EACH
40	720-45410 MANHOLE, C4	1.000	EACH
41	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
42	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
43	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
44	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	285.000	LFT
45	802-07060 SIGN, SHEET, RELOCATE	6.000	EACH
46	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	150.000	SFT
47	808-02977 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	67.000	EACH
48	808-04096 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (LANE)	67.000	EACH
49	808-04767 LINE	218.000	LFT

CALL ORDER : 321

CONTRACT ID : R -33302-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BICYCLE LANE AND SIDEWALKS		
50 808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	24,365.000	LFT
51 808-09503	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, DIAMOND	67.000	EACH
52 808-75043	LINE THERMOPLASTIC, SOLID, WHITE, 6 IN	24,365.000	LFT
53 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	715.000	LFT
54 808-75300	TRANSVERSE MARKING, THERMOPLASTIC,	376.000	LFT
55 808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	67.000	EACH
56 808-98796	LINE, THERMOPLASTIC DOTTED WHITE, 4 IN, 2FT LINE, 4FT GAP	218.000	LFT

CALL ORDER : 331

CONTRACT ID : R -33310-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT BIKE LANE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	306-08034 MILLING, ASPHALT, 1 1/2 IN	2,933.000	SYS
9	402-07433 HMA SURFACE, TYPE B	242.000	TON
10	406-05520 ASPHALT FOR TACK COAT	7.800	TON
11	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6,625.000	LFT
12	801-06640 CONSTRUCTION SIGN, A	416.000	EACH
13	801-06710 FLASHING ARROW SIGN	30.000	DAY
14	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
15	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	1,577.000	LFT
16	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	780.000	SFT
17	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	56.500	SFT
18	808-02977 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	150.000	EACH
19	808-02977 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	50.000	EACH
20	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	4.000	SYS
21	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	13,643.000	LFT
22	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	33,084.000	LFT
23	808-06716 LINE, REMOVE	57,378.000	LFT
24	808-09968 PAVEMENT MARKING	3,125.000	SFT
25	808-75043 LINE THERMOPLASTIC, SOLID, WHITE, 6 IN	32,949.000	LFT
26	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	30.000	LFT
27	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	24,894.000	LFT
28	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	10.000	EACH
29	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	7.000	EACH
30	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	200.000	EACH
31	808-96075 LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN	3,568.000	LFT

CALL ORDER : 361

CONTRACT ID : B -29004-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK OVERLAY		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	200.000	SYS
9	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	10.000	CYS
11	302-07455 DENSE GRADED SUBBASE	33.000	CYS
12	306-08043 MILLING, TRANSITION	880.000	SYS
13	402-07451 HMA WEDGE AND LEVEL, TYPE B	97.000	TON
14	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
15	601-02241 GUARDRAIL, REMOVE	400.000	LFT
16	601-02565 GUARDRAIL, W BEAM, 12FT 6 IN SPACING	150.000	LFT
17	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
18	602-06729 BARRIER DELINEATOR	4.000	EACH
19	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	200.000	SYS
20	628-09402 FIELD OFFICE, B	4.000	MOS
21	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	4.000	MOS
22	702-92857 CONCRETE, C, SUBSTRUCTURE	16.800	CYS
23	703-06029 REINFORCING BARS, EPOXY COATED	10,252.000	LBS
24	709-51821 SURFACE SEAL	LUMP	LUMP
25	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	122.000	SFT
26	722-51842 BRIDGE DECK OVERLAY	270.000	SYS
27	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	2.300	CYS
28	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	122.000	SFT
29	722-60824 SURFACE MILLING	270.000	SYS
30	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
31	801-06625 DETOUR ROUTE MARKER ASSEMBLY	31.000	EACH
32	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
33	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
34	801-07118 BARRICADE, III-A	80.000	LFT
35	801-07119 BARRICADE, III-B	40.000	LFT
36	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	336.000	LFT
37	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	673.000	LFT
38	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6.000	EACH
39	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	6.000	EACH

CALL ORDER : 371

CONTRACT ID : B -29732-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	20.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
14	202-91385 INLET, REMOVE	1.000	EACH
15	203-02000 EXCAVATION, COMMON	3,148.000	CYS
16	203-02070 BORROW	10,825.000	CYS
17	205-03371 SEDIMENT, REMOVE	10.000	CYS
18	205-06932 TEMPORARY CHECK DAM, STRAW BALES	240.000	LFT
19	205-06937 TEMPORARY SILT FENCE	2,170.000	LFT
20	207-08263 SUBGRADE TREATMENT, TYPE IA	11,200.000	SYS
21	207-08267 SUBGRADE TREATMENT, TYPE IIIA	278.000	SYS
22	211-06467 AGGREGATE FOR END BENT BACKFILL	74.000	CYS
23	302-07455 DENSE GRADED SUBBASE	45.000	CYS
24	303-01180 COMPACTED AGGREGATE, NO. 53	2,530.000	TON
25	303-08210 COMPACTED AGGREGATE NO. 53, TEMP FOR DRIVEWAYS	100.000	TON
26	306-08043 MILLING, TRANSITION	530.000	SYS
27	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
28	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,210.000	TON
29	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	820.000	TON
30	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	2,695.000	TON
31	404-05511 SEAL COAT, 2	4,000.000	SYS
32	404-05514 SEAL COAT, 5	172.000	SYS
33	406-05521 ASPHALT FOR TACK COAT	13,230.000	SYS
34	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
35	601-02241 GUARDRAIL, REMOVE	500.000	LFT
36	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
37	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
38	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
39	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	362.500	LFT
40	602-06729 BARRIER DELINEATOR	6.000	EACH
41	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	266.200	SYS
42	610-07486 HMA FOR APPROACHES, TYPE A	165.000	TON
43	610-07487 HMA FOR APPROACHES, TYPE B	111.000	TON
44	611-06497 MAILBOX ASSEMBLY, SINGLE	3.000	EACH
45	615-06490 RIGHT OF WAY MARKER	26.000	EACH
46	615-06505 MONUMENT, B	6.000	EACH
47	616-02320 GEOTEXTILES	1,130.000	SYS
48	616-06405 RIPRAP, REVETMENT	686.000	TON
49	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH



CALL ORDER : 371

CONTRACT ID : B -29732-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-01743 SEED MIXTURE, GRASS, 2	198.000	LBS
51	621-02468 SEED MIXTURE, GRASS, 1	296.000	LBS
52	621-06545 FERTILIZER	1.600	TON
53	621-06553 SEED MIXTURE, R	104.000	LBS
54	621-06557 SEED MIXTURE, T	320.000	LBS
55	621-06565 MULCHING MATERIAL	7.900	TON
56	621-06574 SODDING	449.000	SYS
57	621-52448 SIGN, DO NOT SPRAY	8.000	EACH
58	622-52436 SIGN, DO NOT MOW OR SPRAY	3.000	EACH
59	622-91786 SEEDLING	121.000	EACH
60	622-98200 SIGN, DO NOT DISTURB	3.000	EACH
61	628-09401 FIELD OFFICE, A	10.000	MOS
62	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	10.000	MOS
63	701-03753 PILE, CONCRETE, STEEL SHELL ENCASED, 0.209 IN, 14 IN	1,584.000	LFT
64	703-06029 REINFORCING BARS, EPOXY COATED	60,416.000	LBS
65	704-51002 CONCRETE, C, SUPERSTRUCTURE	248.500	CYS
66	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	4.000	EACH
67	706-51020 CONCRETE, C, RAILING	23.100	CYS
68	707-08643 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	819.000	LFT
69	709-51821 SURFACE SEAL	LUMP	LUMP
70	715-03475 SAFETY METAL END SECTION, 4:1, 15 IN	1.000	EACH
71	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN	124.000	LFT
72	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN	172.000	LFT
73	715-05407 PIPE, END BENT DRAIN, 6 IN	160.000	LFT
74	715-46005 PIPE END SECTION, 15 IN	3.000	EACH
75	715-46010 PIPE END SECTION, 18 IN	4.000	EACH
76	720-44040 CASTING, 7, FURNISH AND ADJUST TO GRADE	1.000	EACH
77	720-45030 INLET, E7	1.000	EACH
78	721-43120 AUTOMATIC DRAINAGE GATE, 36 IN X 24 IN	4.000	EACH
79	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
80	801-06625 DETOUR ROUTE MARKER ASSEMBLY	32.000	EACH
81	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
82	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
83	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
84	801-07118 BARRICADE, III-A	72.000	LFT
85	801-07119 BARRICADE, III-B	120.000	LFT
86	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	19.000	SFT
87	802-76055 SIGN POST, A	39.000	LFT
88	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,950.000	LFT
89	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	240.000	LFT
90	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	8,310.000	LFT
91	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	24.000	LFT
92	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	40.000	EACH
93	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	60.000	EACH

CALL ORDER : 381

CONTRACT ID : B -29778-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
3	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
4	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	24.000	MOS
5	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
6	109-08359 LIQUIDATED DAMAGES	1.000	DOL
7	109-08360 CONTRACT LIENS	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
11	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
16	202-02272 PAVED SIDE DITCH, REMOVE	45.000	LFT
17	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
18	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
19	202-96133 PIPE, REMOVE	43.000	LFT
20	203-02000 EXCAVATION, COMMON	1,614.000	CYS
21	203-02070 BORROW	114.000	CYS
22	205-03371 SEDIMENT, REMOVE	50.000	CYS
23	205-06932 TEMPORARY CHECK DAM, STRAW BALES	112.000	LFT
24	205-06936 TEMPORARY SEDIMENT TRAP	174.000	TON
25	205-06937 TEMPORARY SILT FENCE	2,922.000	LFT
26	205-09543 NO 2 STONE	100.000	TON
27	206-51215 EXCAVATION, X	221.000	CYS
28	207-08263 SUBGRADE TREATMENT, TYPE IA	3,809.000	SYS
29	207-08267 SUBGRADE TREATMENT, TYPE IIIA	83.000	SYS
30	211-09264 STRUCTURAL BACKFILL, TYPE 1	667.000	CYS
31	211-09265 STRUCTURAL BACKFILL, TYPE 2	1,925.000	CYS
32	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,426.000	TON
33	303-01180 COMPACTED AGGREGATE, NO. 53	926.000	TON
34	304-07492 WIDENING WITH HMA, TYPE A	197.000	TON
35	306-08043 MILLING, TRANSITION	560.000	SYS
36	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
37	402-07433 HMA SURFACE, TYPE B	306.000	TON
38	402-07438 HMA INTERMEDIATE, TYPE B	542.000	TON
39	402-07441 HMA BASE, TYPE B	528.000	TON
40	404-05511 SEAL COAT, 2	811.000	SYS
41	406-05521 ASPHALT FOR TACK COAT	11,329.000	SYS
42	601-01839 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 6	1.000	EACH
43	601-94689 GUARDRAIL END TREATMENT, OS	7.000	EACH
44	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	1,093.750	LFT
45	610-07486 HMA FOR APPROACHES, TYPE A	376.000	TON
46	615-06505 MONUMENT, B	6.000	EACH
47	615-06510 MONUMENT, C	1.000	EACH
48	616-02320 GEOTEXTILES	1,038.000	SYS
49	616-05688 RIPRAP, CLASS 1	604.000	TON

CALL ORDER : 381

CONTRACT ID : B -29778-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	616-05689 RIPRAP, CLASS 2	342.000	TON
51	616-06451 RIPRAP, UNIFORM	222.000	TON
52	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
53	621-02770 EROSION CONTROL BLANKET	1,247.000	SYS
54	621-06545 FERTILIZER	0.400	TON
55	621-06553 SEED MIXTURE, R	121.000	LBS
56	621-06557 SEED MIXTURE, T	107.000	LBS
57	621-06565 MULCHING MATERIAL	2.900	TON
58	621-06567 WATER	27.500	KGAL
59	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH
60	622-91786 SEEDLING	30.000	EACH
61	622-98200 SIGN, DO NOT DISTURB	4.000	EACH
62	628-09401 FIELD OFFICE, A	12.000	MOS
63	702-51015 CONCRETE, B, FOOTINGS	33.300	CYS
64	702-93722 CONCRETE, C	20.400	CYS
65	703-06028 REINFORCING BARS	5,054.000	LBS
66	714-08514 WINGWALL	1,261.200	SFT
67	714-09726 HEADWALL	118.500	SFT
68	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	25.000	LFT
69	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN	43.000	LFT
70	715-05407 PIPE, END BENT DRAIN, 6 IN	50.000	LFT
71	715-46010 PIPE END SECTION, 18 IN	2.000	EACH
72	723-08118 STRUCTURE, PRECAST THREE-SIDED, 288 IN X 132 IN	71.000	LFT
73	723-09864 STRUCTURE, PRECAST THREE-SIDED, 312 IN. X 144 IN.	77.500	LFT
74	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.000	EACH
75	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
76	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
77	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
78	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9,345.000	LFT
79	801-06577 TEMPORARY PAVEMENT MARKING	24.000	LFT
80	801-06640 CONSTRUCTION SIGN, A	42.000	EACH
81	801-06645 CONSTRUCTION SIGN, B	8.000	EACH
82	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
83	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
84	801-07119 BARRICADE, III-B	168.000	LFT
85	801-08508 TEMP TRAFFIC BARRIER, TYPE 2, ANCHORED	1,680.000	LFT
86	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	56.000	LFT
87	802-07060 SIGN, SHEET, RELOCATE	8.000	EACH
88	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	13.000	SFT
89	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,100.000	LFT
90	808-06716 LINE, REMOVE	1,360.000	LFT
91	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	830.000	LFT
92	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	8,600.000	LFT
93	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	52.000	EACH
94	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	52.000	EACH

CALL ORDER : 411

CONTRACT ID : B -30244-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT, CONCRETE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	20.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE CONCRETE	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-02272 PAVED SIDE DITCH, REMOVE	185.000	LFT
14	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
15	203-02000 EXCAVATION, COMMON	215.000	CYS
16	203-02070 BORROW	8,146.000	CYS
17	203-51223 EXCAVATION, WATERWAY	128.000	CYS
18	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	67.500	TON
19	205-06934 TEMPORARY MULCHING	2.440	TON
20	205-06936 TEMPORARY SEDIMENT TRAP	58.800	TON
21	205-06937 TEMPORARY SILT FENCE	276.000	LFT
22	205-06938 TEMPORARY SLOPE DRAIN	200.000	LFT
23	207-08263 SUBGRADE TREATMENT, TYPE IA	465.000	SYS
24	211-06467 AGGREGATE FOR END BENT BACKFILL	79.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	206.000	TON
26	302-07455 DENSE GRADED SUBBASE	40.000	CYS
27	306-08039 MILLING, ASPHALT REMOVAL	1,423.000	SYS
28	306-08043 MILLING, TRANSITION	160.000	SYS
29	402-07434 HMA SURFACE, TYPE C	189.000	TON
30	402-07439 HMA INTERMEDIATE, TYPE C	284.000	TON
31	402-07442 HMA BASE, TYPE C	368.000	TON
32	406-05520 ASPHALT FOR TACK COAT	0.700	TON
33	601-01522 GUARDRAIL TRANSITION TYPE TGB	4.000	EACH
34	601-02241 GUARDRAIL, REMOVE	487.500	LFT
35	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
36	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	362.500	LFT
37	602-06729 BARRIER DELINEATOR	8.000	EACH
38	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	251.200	SYS
39	615-06490 RIGHT OF WAY MARKER	11.000	EACH
40	615-06505 MONUMENT, B	2.000	EACH
41	615-06510 MONUMENT, C	1.000	EACH
42	616-02320 GEOTEXTILES	2,476.000	SYS
43	616-06405 RIPRAP, REVETMENT	1,836.200	TON
44	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
45	621-02770 EROSION CONTROL BLANKET	4,722.000	SYS
46	621-06545 FERTILIZER	0.800	TON
47	621-06553 SEED MIXTURE, R	166.000	LBS
48	621-06565 MULCHING MATERIAL	2.000	TON
49	621-06574 SODDING	283.000	SYS

CALL ORDER : 411

CONTRACT ID : B -30244-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT, CONCRETE		
50	622-52436 SIGN, DO NOT MOW OR SPRAY	2.000	EACH
51	628-09401 FIELD OFFICE, A	10.000	MOS
52	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
53	701-06027 TEST PILE	2.000	EACH
54	701-09559 TEST PILE, DYNAMIC, RESTRIKE	2.000	EACH
55	701-91792 PILE TIP, STEEL H	18.000	EACH
56	701-93575 PILE, STEEL H, HP 14 IN X 73	1,669.000	LFT
57	702-04325 TEMPORARY SHORING	LUMP	LUMP
58	703-06029 REINFORCING BARS, EPOXY COATED	70,496.000	LBS
59	703-97703 THREADED BAR SPLICE, EPOXY COATED	400.000	EACH
60	704-51002 CONCRETE, C, SUPERSTRUCTURE	257.000	CYS
61	706-51020 CONCRETE, C, RAILING	27.200	CYS
62	707-08643 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	699.000	LFT
63	709-51821 SURFACE SEAL	LUMP	LUMP
64	715-05407 PIPE, END BENT DRAIN, 6 IN	400.000	LFT
65	715-09064 VIDEO INSPECTION FOR PIPE	550.000	LFT
66	720-03194 MANHOLE	1.000	EACH
67	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
68	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
69	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	842.000	LFT
70	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
71	801-06645 CONSTRUCTION SIGN, B	7.000	EACH
72	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
73	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	592.000	LFT
74	801-08508 TEMP TRAFFIC BARRIER, TYPE 2, ANCHORED	592.000	LFT
75	805-03162 TRAFFIC SIGNAL EQUIPMENT, REMOVAL, STORAGE AND INSTALLATION	LUMP	LUMP
76	808-01428 TEMPORARY TRANSVERSE MARKINGS, WHITE, STOP LINE, 24 IN	48.000	LFT
77	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,400.000	LFT
78	808-06716 LINE, REMOVE	842.000	LFT
79	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1,400.000	LFT

CALL ORDER : 421

CONTRACT ID : B -30552-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	16.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
13	203-02000 EXCAVATION, COMMON	49.000	CYS
14	203-51223 EXCAVATION, WATERWAY	190.000	CYS
15	205-03371 SEDIMENT, REMOVE	10.000	CYS
16	205-06934 TEMPORARY MULCHING	1.000	TON
17	205-06937 TEMPORARY SILT FENCE	678.000	LFT
18	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	16.000	CYS
19	207-08263 SUBGRADE TREATMENT, TYPE IA	540.000	SYS
20	303-01180 COMPACTED AGGREGATE, NO. 53	235.000	TON
21	402-07432 HMA SURFACE, TYPE A	20.000	TON
22	402-07440 HMA BASE, TYPE A	60.000	TON
23	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
24	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
25	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	137.500	LFT
26	616-02320 GEOTEXTILES	154.000	SYS
27	616-05689 RIPRAP, CLASS 2	250.000	TON
28	616-06405 RIPRAP, REVETMENT	16.000	TON
29	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
30	621-06559 MULCHED SEEDING, R	675.000	SYS
31	628-09401 FIELD OFFICE, A	8.000	MOS
32	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	8.000	MOS
33	702-51005 CONCRETE, A, SUBSTRUCTURE	3.500	CYS
34	702-51863 FIELD DRILLED HOLE IN CONCRETE	13.000	EACH
35	703-06029 REINFORCING BARS, EPOXY COATED	174.000	LBS
36	709-51821 SURFACE SEAL	LUMP	LUMP
37	729-51875 CONCRETE, A, PATCHING	15.000	SFT
38	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
39	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3,560.000	LFT
40	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
41	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
42	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
43	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	154.000	LFT
44	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	1,230.000	LFT
45	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	615.000	LFT
46	808-06716 LINE, REMOVE	700.000	LFT

CALL ORDER : 431

CONTRACT ID : B -31550-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE PAINTING			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	16.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	619-09423 CLEAN STEEL BRIDGE, TYPE 1, QP-2	7,452.000	SFT
11	619-09423 CLEAN STEEL BRIDGE, TYPE 1, QP-2	7,332.000	SFT
12	619-09423 CLEAN STEEL BRIDGE, TYPE 1, QP-2	6,307.000	SFT
13	619-09423 CLEAN STEEL BRIDGE, TYPE 1, QP-2	6,270.000	SFT
14	619-09423 CLEAN STEEL BRIDGE, TYPE 1, QP-2	7,260.000	SFT
15	619-09423 CLEAN STEEL BRIDGE, TYPE 1, QP-2	7,085.000	SFT
16	619-09423 CLEAN STEEL BRIDGE, TYPE 1, QP-2	6,674.000	SFT
17	619-09423 CLEAN STEEL BRIDGE, TYPE 1, QP-2	8,586.000	SFT
18	619-09423 CLEAN STEEL BRIDGE, TYPE 1, QP-2	15,787.000	SFT
19	619-09434 PAINT STEEL BRIDGE, TYPE 1	7,452.000	SFT
20	619-09434 PAINT STEEL BRIDGE, TYPE 1	7,332.000	SFT
21	619-09434 PAINT STEEL BRIDGE, TYPE 1	6,307.000	SFT
22	619-09434 PAINT STEEL BRIDGE, TYPE 1	6,270.000	SFT
23	619-09434 PAINT STEEL BRIDGE, TYPE 1	7,260.000	SFT
24	619-09434 PAINT STEEL BRIDGE, TYPE 1	7,085.000	SFT
25	619-09434 PAINT STEEL BRIDGE, TYPE 1	6,674.000	SFT
26	619-09434 PAINT STEEL BRIDGE, TYPE 1	8,586.000	SFT
27	619-09434 PAINT STEEL BRIDGE, TYPE 1	15,787.000	SFT
28	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	16.000	MOS
29	628-09409 MOBILE INTERNET SERVICE	16.000	MOS
30	709-51821 SURFACE SEAL	LUMP	LUMP
31	709-51821 SURFACE SEAL	LUMP	LUMP
32	709-51821 SURFACE SEAL	LUMP	LUMP
33	709-51821 SURFACE SEAL	LUMP	LUMP
34	709-51821 SURFACE SEAL	LUMP	LUMP
35	709-51821 SURFACE SEAL	LUMP	LUMP
36	709-51821 SURFACE SEAL	LUMP	LUMP
37	709-51821 SURFACE SEAL	LUMP	LUMP
38	709-51821 SURFACE SEAL	LUMP	LUMP
39	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
40	801-03290 CONSTRUCTION SIGN, C	30.000	EACH
41	801-06640 CONSTRUCTION SIGN, A	40.000	EACH
42	801-06710 FLASHING ARROW SIGN	400.000	DAY
43	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
44	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
45	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
46	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
47	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
48	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
49	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

SCHEDULE OF PAY ITEMS

CALL ORDER : 431

CONTRACT ID : B -31550-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE PAINTING		
50 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
51 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
52 801-09133	TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH



CALL ORDER : 461

CONTRACT ID : M -31165-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
8 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 471

CONTRACT ID : M -33183-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEBRIS REMOVAL FROM CHANNEL		
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	3.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
10	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
11	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	3.000	MOS
12	628-09409 MOBILE INTERNET SERVICE	3.000	MOS
13	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
14	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
15	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
16	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
17	801-06710 FLASHING ARROW SIGN	30.000	DAY
18	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 481

CONTRACT ID : M -33324-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE		
1	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	202-96531 FENCE, RIGHT-OF-WAY, REMOVE	100.000	LFT
9	601-01128 GUARDRAIL TRANSITION TYPE WGB	1.000	EACH
10	601-01522 GUARDRAIL TRANSITION TYPE TGB	1.000	EACH
11	601-01846 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 3	1.000	EACH
12	601-02208 GUARDRAIL TERMINAL SECTION, GALVANIZED, 11 IN., INSTALLED	1.000	EACH
13	601-02211 GUARDRAIL POST, 8.5 LBS PER LFT, 7 FT O IN LONG, GALVANIZED	200.000	EACH
14	601-02241 GUARDRAIL, REMOVE	500.000	LFT
15	601-03457 GUARDRAIL W THRIE BEAM RAIL SECTION, 12FT-6 IN	3.000	EACH
16	601-03463 GUARDRAIL, STEEL CURVED TERMINAL END SECTION, LABOR ONLY	5.000	EACH
17	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	12.000	EACH
18	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	5.000	EACH
19	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	2.000	EACH
20	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	1.000	EACH
21	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	2.000	EACH
22	601-03677 ANCHOR, TYPE 5	3.000	EACH
23	601-05856 CAT	2.000	EACH
24	601-05856 CAT	2.000	EACH
25	601-05856 CAT	2.000	EACH
26	601-05856 CAT	10.000	EACH
27	601-05856 CAT	2.000	EACH
28	601-05856 CAT	1.000	EACH
29	601-05856 CAT	5.000	EACH
30	601-05856 CAT	5.000	EACH
31	601-05856 CAT	10.000	EACH
32	601-05856 CAT	1.000	EACH
33	601-05856 CAT	1.000	EACH
34	601-05856 CAT	1.000	EACH
35	601-05856 CAT	1.000	EACH
36	601-06037 GUARDRAIL END TREATMENT, I	1.000	EACH
37	601-06053 GUARDRAIL	200.000	EACH
38	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
39	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
40	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
41	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
42	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
43	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
44	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
45	601-06273 GUARDRAIL END TREATMENT, SKT-350	1.000	EACH
46	601-06854 GUARDRAIL, W-BEAM, NESTED	1.000	EACH
47	601-06854 GUARDRAIL, W-BEAM, NESTED	1.000	EACH
48	601-09238 HAND DIG GUARDRAIL POST HOLES	5.000	EACH
49	601-52540 GUARDRAIL TERMINAL SECTION, W BEAM	1.000	EACH

CALL ORDER : 481

CONTRACT ID : M -33324-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE		
50	601-61320 CURVED SECTION, STEEL BEAM GUARDRAIL GALVANIZED, 12 GA.	400.000	LFT
51	601-61340 GUARDRAIL POST, 15.5 LBS PER FT., GALVANIZED, 6 FT. 3 IN.	70.000	EACH
52	601-61380 GUARDRAIL TERMINAL SECTION, FLAT END, GALVANIZED	1.000	EACH
53	601-61390 GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE,	5.000	EACH
54	601-61410 GUARDRAIL TERMINAL SECTION, DOUBLE FACE, GALVANIZED	1.000	EACH
55	601-61550 GUARDRAIL TERMINAL END SECTION, ALUMINUM	1.000	EACH
56	601-62070 GUARDRAIL, STEEL BEAM, GALVANIZED	3,200.000	LFT
57	601-62090 GUARDRAIL, STEEL BEAM, INSTALL	250.000	LFT
58	601-62100 GUARDRAIL POST, STEEL, INSTALL	10.000	EACH
59	601-62110 GUARDRAIL, CHANNEL, 6.7 LBS PER LFT., INSTALL	100.000	LFT
60	601-62120 GUARDRAIL POST BRACKET, INSTALL	10.000	EACH
61	601-62297 GUARDRAIL STANDARD TERMINAL CONNECTOR, MICHIGAN END SHOE	2.000	EACH
62	601-62530 GUARDRAIL PIER CONNECTION, ES	1.000	EACH
63	601-62540 GUARDRAIL POST, PLUMB	400.000	EACH
64	601-62554 GUARDRAIL, TUBING, ELLIPTICAL, ALUMINUM, INSTALL	100.000	LFT
65	601-62570 GUARDRAIL DIAPHRAGM, ALUMINUM	1.000	EACH
66	601-62600 GUARDRAIL POST BRACKET, A, ALUMINUM	1.000	EACH
67	601-62720 GUARDRAIL, TUBING, 1, ALUMINUM	50.000	LFT
68	601-62770 GUARDRAIL ANCHOR, 0.75 IN. BOLT, GALVANIZED THRU CONCRETE	10.000	EACH
69	601-90382 GUARDRAIL POST, ALUMINUM, 7 FT.	1.000	EACH
70	601-90389 GUARDRAIL TERMINAL SECTION, GALVANIZED, 11 IN.	5.000	EACH
71	601-90677 DRILLED BRACKET, INSTALL	1.000	EACH
72	601-90960 GUARDRAIL, TUBE, ALUMINUM, III	40.000	LFT
73	601-90962 GUARDRAIL EXPANSION ANCHORS, REPLACEMENT	5.000	EACH
74	601-91504 GUARDRAIL POST, W1, 10 IN X 10 IN	1.000	EACH
75	601-91505 GUARDRAIL POST, W2, 8 IN. X 8 IN.	1.000	EACH
76	601-91542 GUARDRAIL BLOCK, 6 IN. X 8 IN., B1	1.000	EACH
77	601-91576 GUARDRAIL BLOCK, 6 IN. X 8 IN., B3	1.000	EACH
78	601-91649 GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	1.000	EACH
79	601-91650 GUARDRAIL THRIE BEAM EXPANSION RAIL, GALVANIZED	5.000	LFT
80	601-91653 GUARDRAIL THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	1.000	EACH
81	601-92973 GUARDRAIL END TREATMENT, LABOR ONLY	2.000	EACH
82	601-93346 GUARDRAIL CONNECTOR, AS	2.000	EACH
83	601-94689 GUARDRAIL END TREATMENT, OS	5.000	EACH
84	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
85	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
86	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
87	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
88	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
89	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
90	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
91	601-94689 GUARDRAIL END TREATMENT, OS	5.000	EACH
92	601-94690 GUARDRAIL END TREATMENT, MS	1.000	EACH
93	601-95342 GUARDRAIL SPLICE PLATE, C, GALVANIZED	1.000	EACH
94	601-95342 GUARDRAIL SPLICE PLATE, C, GALVANIZED	1.000	EACH
95	601-95924 GUARDRAIL TERMINAL PIECE, ALUMINUM, INSTALL	1.000	EACH
96	601-95927 GUARDRAIL TERMINAL SECTION, SINGLEFACE, BURIED END,	3.000	EACH
97	601-95928 GUARDRAIL TERMINAL SECTION, DOUBLEFACE, BURIED END,	3.000	EACH
98	601-95972 GUARDRAIL POST (CRT), 8 IN X 6 IN TREATED LUMBER,	15.000	EACH

CALL ORDER : 481

CONTRACT ID : M -33324-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE		
99	601-98636 GUARDRAIL CHANNEL, 6.7 LBS PER LFT., GALVANIZED, 5 IN.	300.000	LFT
100	601-98826 BREAKAWAY CABLE TERMINAL, A, BASE PADDLE POST OR ALTERNATE	1.000	EACH
101	601-98836 BREAKAWAY CABLE TERMINAL, A, TERMINAL TUBE POST OR POST	1.000	EACH
102	601-98837 BREAKAWAY CABLE TERMINAL, 1, PUNCHED GUARDRAIL SECTION,	25.000	LFT
103	601-98838 BREAKAWAY CABLE TERMINAL, A, FOUNDATION POST, INCLUDING	1.000	EACH
104	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	100.000	LFT
105	601-99106 GUARDRAIL, W BEAM, 3 FT 1.5 IN SPACING	50.000	LFT
106	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	50.000	LFT
107	601-99109 GUARDRAIL, W BEAM, DOUBLE FACED, 3 FT 1.5 IN SPACING	50.000	LFT
108	601-99132 GUARDRAIL TRANSITION, VH, 6FT-3 IN SPACING	1.000	EACH
109	601-99133 GUARDRAIL TRANSITION VH, 12FT-6 IN SPACING	1.000	EACH
110	603-01932 FENCE, CHAIN LINK, 96 IN	100.000	LFT
111	603-01932 FENCE, CHAIN LINK, 96 IN	100.000	LFT
112	603-06040 FENCE, FARM FIELD, 47 IN	990.000	LFT
113	603-06040 FENCE, FARM FIELD, 47 IN	660.000	LFT
114	603-06042 FENCE, FARM FIELD, BARBED WIRE	1,000.000	LFT
115	603-06045 FENCE, CHAIN LINK, 48 IN	800.000	LFT
116	603-06045 FENCE, CHAIN LINK, 48 IN	1,000.000	LFT
117	603-06060 FENCE, FARM FIELD, RESET	150.000	LFT
118	603-06065 FENCE, CHAIN LINK, RESET	150.000	LFT
119	603-06065 FENCE, CHAIN LINK, RESET	100.000	LFT
120	603-06065 FENCE, CHAIN LINK, RESET	100.000	LFT
121	603-92636 FENCE, CHAIN LINK, 72 IN	100.000	LFT
122	603-92636 FENCE, CHAIN LINK, 72 IN	100.000	LFT
123	603-98842 POST, LINE, 3.65 LBS PER LFT.	75.000	EACH
124	603-98842 POST, LINE, 3.65 LBS PER LFT.	1.000	EACH
125	603-98842 POST, LINE, 3.65 LBS PER LFT.	1.000	EACH
126	603-98848 POST, LINE, CHAIN LINK	5.000	EACH
127	603-98848 POST, LINE, CHAIN LINK	5.000	EACH
128	603-98848 POST, LINE, CHAIN LINK	5.000	EACH
129	603-98848 POST, LINE, CHAIN LINK	75.000	EACH
130	603-98849 POST, LINE, FARM FIELD	30.000	EACH
131	603-98849 POST, LINE, FARM FIELD	10.000	EACH
132	603-98851 WIRE, TENSION, 7 GAUGE	1,000.000	LFT
133	603-98853 FENCE, TRUSS ROD, .375 IN.	4.000	EACH
134	603-98854 FENCE, BRACE, 1.25 IN, 2.27 LBS PER LFT	25.000	EACH
135	603-98855 FENCH, FLAT STRETCHER BAR, 0.1875 IN. X 0.75 IN.	4.000	EACH
136	620-08428 SOUND BARRIER PANELS	100.000	SFT
137	620-08428 SOUND BARRIER PANELS	150.000	SFT
138	702-06850 SOUND BARRIER	1.000	EACH
139	702-06850 SOUND BARRIER	1.000	EACH
140	702-06850 SOUND BARRIER	1.000	EACH
141	702-06850 SOUND BARRIER	1.000	EACH
142	702-06850 SOUND BARRIER	3.000	EACH
143	702-90915 CONCRETE, CLASS A	1.000	CYS
144	706-62390 BRIDGE RAILING POST, 6	1.000	EACH
145	706-62400 BRIDGE RAILING POST, 7	1.000	EACH
146	706-95929 BRIDGE RAILING POST, 5, ALUMINUM, INSTALL	1.000	EACH
147	706-95930 BRIDGE RAILING POST, 5A, ALUMINUM, INSTALL	1.000	EACH

CALL ORDER : 481

CONTRACT ID : M -33324-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE		
148 711-91047	EXPANSION ANCHOR, 1 IN	1.000	EACH
149 711-98839	ANCHOR ASSEMBLY, AS1, REPAIR	1.000	EACH
150 803-61430	BRIDGE BRACKET A, GALVANIZED	1.000	EACH
151 807-06796	ELECTRIC	1.000	EACH

CALL ORDER : 501

CONTRACT ID : TM-33260-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LIGHTING MAINTENANCE		
1	105-08520 CELLULAR TELEPHONE/RADIO	1.000	EACH
2	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
3	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-01845 CONDUIT, REMOVE	300.000	LFT
10	202-86946 HANDHOLE, REMOVE	5.000	EACH
11	202-95579 SERVICE POINT, REMOVE	1.000	EACH
12	202-98370 POLE, REMOVE	1.000	EACH
13	702-90915 CONCRETE, CLASS A	1.000	CYS
14	711-95290 FIELD WELDING	1.000	LFT
15	715-04612 PIPE	1.000	LFT
16	732-04994 METER	1.000	EACH
17	732-04994 METER	1.000	EACH
18	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
19	801-06710 FLASHING ARROW SIGN	10.000	DAY
20	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
21	803-87715 GROUND ROD WITH CONNECTOR	1.000	EACH
22	805_95520 EXPANSION FITTING, 2.0 IN.	1.000	EACH
23	805-02202 SIGNAL DETECTOR HOUSING, DOUBLE	2.000	EACH
24	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA	1,000.000	LFT
25	805-78510 SIGNAL CABLE, 2C 16GA., SHIELDED	1,000.000	LFT
26	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
27	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	500.000	LFT
28	805-87746 AERIAL CABLE, TRIPLEX	200.000	LFT
29	805-87780 CIRCUIT BREAKER	5.000	EACH
30	805-91694 NAVIGATION LIGHT PIER	1.000	EACH
31	805-91696 NAVIGATION LIGHT CENTRE CHANNEL	1.000	EACH
32	805-91696 NAVIGATION LIGHT CENTRE CHANNEL	1.000	EACH
33	805-91698 NAVIGATION LIGHT, FRESNEL LENS, 180	1.000	EACH
34	805-91699 NAVIGATION LIGHT, FRESNEL LENS, 360	1.000	EACH
35	805-91703 CONDUIT, STEEL, GALVANIZED, 1.5 IN	10.000	LFT
36	805-91706 ANCHOR BOLT, REPAIR	4.000	EACH
37	805-91711 EXPANSION FITTING, 1.5 IN.	1.000	EACH
38	805-95521 EXPANSION FITTING, 0.75 IN.	2.000	EACH
39	805-95524 HANDHOLE COVER	1.000	EACH
40	807-01560 REPAIR CALLOUT	2.000	EACH
41	807-01562 POWER DISCONNECT PLUG FOR HIGH MAST TOWER	5.000	EACH
42	807-01563 HIGH MAST TOWER LOCATING PIN, STAINLESS STEEL	1.000	EACH
43	807-01564 HIGH MAST TOWER, SMALL GEAR OF CHAIN DRIVE	1.000	EACH
44	807-02105 ROUTINE MAINTENANCE LUMINAIRE HIGH PRESSURE SODIUM, 150 W	648.000	MOS
45	807-02109 LUMINAIRE, SIGN, MERCURY VAPOR, WITH GLARE SHIELD	2.000	EACH
46	807-02191 HANDHOLE, LIGHTING	1.000	EACH
47	807-02579 MAST ARM, 15FT	1.000	EACH
48	807-02778 LUMINAIRE MAST ARM, 5 FT	1.000	EACH
49	807-02780 LUMINAIRE MAST ARM, 8 FT.	1.000	EACH

CALL ORDER : 501

CONTRACT ID : TM-33260-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LIGHTING MAINTENANCE		
50	807-02781 LUMINAIRE MAST ARM, 10 FT.	1.000	EACH
51	807-02782 LUMINAIRE MAST ARM, 12 FT.	1.000	EACH
52	807-02784 LUMINAIRE MAST ARM, 20 FT	1.000	EACH
53	807-02785 LUMINAIRE MAST ARM, 25 FT	1.000	EACH
54	807-04507 TRANSFORMER	1.000	EACH
55	807-04651 WIRE,	100.000	LFT
56	807-04651 WIRE,	100.000	LFT
57	807-04652 SERVICE POINT	5.000	EACH
58	807-04654 LIGHT POLE	1.000	EACH
59	807-04654 LIGHT POLE	1.000	EACH
60	807-04654 LIGHT POLE	1.000	EACH
61	807-04654 LIGHT POLE	1.000	EACH
62	807-04654 LIGHT POLE	1.000	EACH
63	807-04654 LIGHT POLE	1.000	EACH
64	807-04654 LIGHT POLE	1.000	EACH
65	807-04940 MAST ARM	10.000	EACH
66	807-04962 LIGHT	1.000	EACH
67	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	25.000	LFT
68	807-07703 HIGH MAST TOWER	2.000	EACH
69	807-86615 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	5.000	EACH
70	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	5.000	EACH
71	807-86665 LUMINAIRE, HIGH MAST, HIGH PRESSURE SODIUM, 1000 WATT	1.000	EACH
72	807-86750 LUMINAIRE UNDERPASS, WALL MOUNTED, HIGH PRESSURE, 150	2.000	EACH
73	807-86790 LUMINAIRE, SIGN, MERCURY VAPOR, WITH GLARE SHIELD, 250 WATT	2.000	EACH
74	807-86805 SERVICE POINT, I	1.000	EACH
75	807-86810 SERVICE POINT, II	1.000	EACH
76	807-86842 WIRE, AWG, MTW, THHW, THWN, AWM, GASOLINE AND OIL RESISTANT,	100.000	LFT
77	807-86843 WIRE, NO 4 COPPER, 1/C	250.000	LFT
78	807-86889 POLE CIRCUIT CABLE, 1C NO. 10 STRANDED	150.000	LFT
79	807-86898 CONDUIT, STEEL, GALVANIZED, 0.75 IN	50.000	LFT
80	807-86910 CONNECTOR KIT, UNFUSED	20.000	EACH
81	807-86915 CONNECTOR KIT, FUSED	20.000	EACH
82	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	10.000	EACH
83	807-86930 INSULATION LINK, NON-WATERPROOFED	10.000	EACH
84	807-86950 SIGN UNDERPASS AND ROADWAY LIGHTING LOCATION IDENTIFICATION	5.000	EACH
85	807-86955 CABLE-DUCT MARKER	2.000	EACH
86	807-87022 ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM,	10,968.000	MOS
87	807-87028 ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM,	9,216.000	MOS
88	807-87042 ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM,	2,700.000	MOS
89	807-87085 ELECTRICIAN	25.000	HRS
90	807-87595 REPLACEMENT OF CABLE CLAMPS ON HIGHMAST TOWER LUMINAIRE RING	2.000	EACH
91	807-87640 BREAKAWAY COUPLING	5.000	SET
92	807-87800 CABLE DUCT, INSTALL	500.000	LFT
93	807-91704 LIGHT POLE HANDHOLE COVER	5.000	EACH
94	807-91705 CONDUIT, POLYETHYLENE, REPAIR	2.000	EACH
95	807-91708 ROUTINE MAINTENANCE, NAVIGATION LIGHT	324.000	EACH
96	807-92870 TRANSFORMER BASE HANDHOLE	2.000	EACH
97	807-93647 LUMINAIRE POST TOP, HIGH PRESSURE SODIUM, 150 WATT	1.000	EACH
98	807-93649 SHAFT FOR POST TOP LUMINAIRE, 16 FT. M.H.	1.000	EACH



CALL ORDER : 501

CONTRACT ID : TM-33260-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LIGHTING MAINTENANCE		
99	807-93650 FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR ROADWAY	1.000	SET
100	807-93651 FOUNDATION, ANCHOR BOLTS & REINFORCING STEEL	1.000	SET
101	807-94480 LIGHT STANDARD, INSTALL	12.000	EACH
102	807-95508 VANDAL SHIELD, LEXAN	1.000	EACH
103	807-95513 SERVICE POINT MAIN BREAKER	1.000	EACH
104	807-95514 SERVICE POINT RISER	1.000	EACH
105	807-95515 SERVICE POINT WEATHERHEAD	1.000	EACH
106	807-95516 RELAY SWITCH	5.000	EACH
107	807-95518 FLEXIBLE CONDUIT, 2 IN.	100.000	LFT
108	807-95519 FLEXIBLE CONDUIT, 0.75 IN.	100.000	LFT
109	807-95522 PIPE STRAP	10.000	EACH
110	807-95523 WATERPROOFING OF ELECTRICAL CONNECTOR	10.000	EACH
111	807-95525 LIGHTING, HIGHWAY SUPPORT, REPAIR	2.000	EACH
112	807-95705 BREAKAWAY ALUMINUM TRANSFORMER BASE	7.000	EACH
113	807-95709 PHOTOCELLS	1.000	EACH
114	807-96183 SHAFT FOR 30 FT. M.H., TWIN 10 FT. M.A.	1.000	EACH
115	807-96184 SHAFT FOR 30 FT. M.H. TWIN 12 FT. M.A.	1.000	EACH
116	807-96194 ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM,	6,852.000	MOS
117	807-96197 WIRE, AWG, MTW, THHW, THWN, AWM, GASOLINE AND OIL	100.000	LFT
118	807-96203 LIGHT POLE, HIGH MAST, TOWER SUSPENSION CABLE	3.000	EACH
119	807-96204 LOWERING AND RAISING OF TOWER	1.000	EACH
120	807-96236 LIGHT POLE, HIGH MAST, TOWER POWER CABLE	2.000	EACH
121	807-96868 LUMINAIRE, INSTALL	5.000	EACH
122	807-98716 KELLUM GRIP, STAINLESS STEEL	1.000	EACH

