

CALL ORDER : 286

CONTRACT ID : R -33296-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT PATCH AND REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	12.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	4,288.000	SYS
13	203-02000 EXCAVATION, COMMON	10,800.000	CYS
14	205-06933 TEMPORARY DITCH INLET PROTECTION	5.000	EACH
15	205-06937 TEMPORARY SILT FENCE	11,426.000	LFT
16	207-08263 SUBGRADE TREATMENT, TYPE IA	23,675.000	SYS
17	211-09264 STRUCTURAL BACKFILL, TYPE 1	121.000	CYS
18	214-07202 GEOGRID, TYPE I	4,735.100	SYS
19	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,433.900	TON
20	302-06464 SUBBASE FOR PCCP	3,040.000	CYS
21	303-01180 COMPACTED AGGREGATE, NO. 53	860.000	TON
22	304-07491 HMA PATCHING, TYPE C	47.000	TON
23	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,067.000	SYS
24	306-08037 MILLING, ASPHALT, 3 IN	1,067.000	SYS
25	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
26	402-07785 HMA INTERMEDIATE, TYPE D	2,104.000	TON
27	402-07786 HMA BASE, TYPE D	2,169.000	TON
28	402-07787 HMA WEDGE AND LEVEL, TYPE D	88.000	TON
29	406-05520 ASPHALT FOR TACK COAT	3.750	TON
30	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
31	502-06331 PCCP, 14 IN	12,160.000	SYS
32	503-05240 D-1 CONTRACTION JOINT	5,144.000	LFT
33	503-05310 TERMINAL JOINT	96.000	LFT
34	606-07485 MILLED PCCP SHOULDER CORRUGATIONS	9,280.000	LFT
35	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
36	621-06545 FERTILIZER	1.440	TON
37	621-06553 SEED MIXTURE, R	614.000	LBS
38	621-06557 SEED MIXTURE, T	384.000	LBS
39	621-06565 MULCHING MATERIAL	13.000	TON
40	621-06567 WATER	1.000	KGAL
41	621-06574 SODDING	249.000	SYS
42	628-09401 FIELD OFFICE, A	6.000	MOS
43	702-51863 FIELD DRILLED HOLE IN CONCRETE	200.000	EACH
44	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	9,156.000	LFT
45	715-91361 PIPE, PVC, 6 IN	1,060.000	LFT
46	718-06531 OUTLET PROTECTOR, 3	8.000	EACH
47	718-52610 AGGREGATE FOR UNDERDRAINS	1,186.900	CYS
48	718-99153 GEOTEXTILES FOR UNDERDRAIN	8,307.800	SYS
49	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.000	EACH

CALL ORDER : 286

CONTRACT ID : R -33296-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT PATCH AND REHABILITATION		
50	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
51	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	6,280.000	LFT
52	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	47,080.000	LFT
53	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
54	801-06710 FLASHING ARROW SIGN	20.000	DAY
55	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
56	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	5,240.000	LFT
57	801-08508 TEMP TRAFFIC BARRIER, TYPE 2, ANCHORED	2,288.000	LFT
58	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	2.000	EACH
59	801-97643 TEMPORARY BUZZ STRIPS	144.000	LFT
60	804-06770 DELINEATOR POST	8.000	EACH
61	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN	6,280.000	LFT
62	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN	6,280.000	LFT
63	808-06716 LINE, REMOVE	18,840.000	LFT
64	808-74811 LINE, EPOXY, BROKEN, WHITE, 5 IN	1,570.000	LFT
65	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	39.000	EACH
66	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	39.000	EACH

