

CALL ORDER : 141

CONTRACT ID : SIR-30709-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
3	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
4	105-08520 CELLULAR TELEPHONE/RADIO	3.000	EACH
5	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	45.000	MOS
6	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
7	109-08359 LIQUIDATED DAMAGES	1.000	DOL
8	109-08360 CONTRACT LIENS	1.000	DOL
9	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
10	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
11	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
12	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
13	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
14	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
15	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
16	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
17	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
18	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
19	202-02240 PAVEMENT REMOVAL	13,731.000	SYS
20	202-02273 CENTER CURB, CONCRETE, REMOVE	374.000	SYS
21	202-02278 CURB, CONCRETE, REMOVE	3,484.000	LFT
22	202-02279 CURB AND GUTTER, REMOVE	3,758.000	LFT
23	202-02286 PRESENT STRUCTURE, REMOVE	1.000	EACH
24	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
25	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
26	202-91385 INLET, REMOVE	17.000	EACH
27	202-91840 FENCE, CHAIN LINK, REMOVE	545.000	LFT
28	202-92953 CURB AND GUTTER TURNOUT, REMOVE	5.000	SYS
29	202-94793 BARRIER, MEDIAN, CONCRETE, REMOVE	200.000	LFT
30	202-96133 PIPE, REMOVE	749.000	LFT
31	203-02000 EXCAVATION, COMMON	43,495.000	CYS
32	205-03371 SEDIMENT, REMOVE	1,210.000	CYS
33	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	45.000	TON
34	205-06936 TEMPORARY SEDIMENT TRAP	220.000	TON
35	205-06937 TEMPORARY SILT FENCE	2,313.000	LFT
36	205-06938 TEMPORARY SLOPE DRAIN	36.000	LFT
37	205-09543 NO 2 STONE	710.000	TON
38	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	682.000	CYS
39	207-08263 SUBGRADE TREATMENT, TYPE IA	17,648.000	SYS
40	207-08267 SUBGRADE TREATMENT, TYPE IIIA	4,207.000	SYS
41	211-02050 B BORROW	13,472.000	CYS
42	211-09264 STRUCTURAL BACKFILL, TYPE 1	1,633.000	CYS
43	211-09266 STRUCTURAL BACKFILL, TYPE 3	21,044.000	CYS
44	213-08068 DRILLED HOLE FOR FLOWABLE BACKFILL	2.000	EACH
45	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	40.000	CYS
46	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,388.000	TON
47	302-07455 DENSE GRADED SUBBASE	178.000	CYS
48	306-08034 MILLING, ASPHALT, 1 1/2 IN	3,856.000	SYS
49	306-08037 MILLING, ASPHALT, 3 IN	1,190.000	SYS

CALL ORDER : 141

CONTRACT ID : SIR-30709-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,549.000	TON
51	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,953.000	TON
52	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	6,544.000	TON
53	402-07453 HMA FOR TEMPORARY PAVEMENT	926.000	TON
54	406-05520 ASPHALT FOR TACK COAT	13.200	TON
55	503-03489 RETROFITTED TIE BARS	338.000	EACH
56	503-05240 D-1 CONTRACTION JOINT	1,078.000	LFT
57	506-06333 PCCP PATCHING, FULL DEPTH	378.000	SYS
58	506-06333 PCCP PATCHING, FULL DEPTH	235.000	SYS
59	601-01522 GUARDRAIL TRANSITION TYPE TGB	2.000	EACH
60	601-02241 GUARDRAIL, REMOVE	1,839.000	LFT
61	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
62	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	250.000	LFT
63	602-06729 BARRIER DELINEATOR	61.000	EACH
64	602-08605 CONCRETE BARRIER, 33 IN	50.000	LFT
65	603-06045 FENCE, CHAIN LINK, 48 IN	459.000	LFT
66	604-07902 CURB RAMP, CONCRETE, H	30.800	SYS
67	604-91531 SIDEWALK, CONCRETE, 4 IN	574.000	SYS
68	605-06120 CURB, CONCRETE	3,130.000	LFT
69	605-06150 CURB AND GUTTER, C, CONCRETE	3,523.000	LFT
70	605-06160 CURB AND GUTTER, B, CONCRETE, MODIFIED	203.000	LFT
71	605-06250 CENTER CURB, C, CONCRETE	491.000	SYS
72	605-08636 CURB AND GUTTER, TURNOUT, COMBINED	14.000	LFT
73	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	1,060.000	SYS
74	610-07488 HMA FOR APPROACHES, TYPE C	361.000	TON
75	615-06510 MONUMENT, C	6.000	EACH
76	615-06515 MONUMENT, D	3.000	EACH
77	616-02320 GEOTEXTILES	315.000	SYS
78	616-05689 RIPRAP, CLASS 2	171.000	TON
79	616-06405 RIPRAP, REVETMENT	122.000	TON
80	616-51367 SLOPEWALL, CONCRETE, 4 IN	70.000	SYS
81	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
82	621-06557 SEED MIXTURE, T	236.000	LBS
83	621-06565 MULCHING MATERIAL	3.000	TON
84	621-06567 WATER	54.800	KGAL
85	621-06574 SODDING	2,374.000	SYS
86	621-06575 SODDING, NURSERY	12,831.000	SYS
87	628-09402 FIELD OFFICE, B	15.000	MOS
88	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	15.000	MOS
89	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	15.000	MOS
90	628-09409 MOBILE INTERNET SERVICE	15.000	MOS
91	701-06011 DYNAMIC PILE LOAD TEST	6.000	EACH
92	701-09557 TEST PILE, DYNAMIC, PRODUCTION	422.000	LFT
93	701-09559 TEST PILE, DYNAMIC, RESTRIKE	6.000	EACH
94	701-09770 PILE SHOE, HP 14 X 73	96.000	EACH
95	701-93575 PILE, STEEL H, HP 14 IN X 73	5,142.000	LFT
96	702-51005 CONCRETE, A, SUBSTRUCTURE	731.300	CYS
97	702-51015 CONCRETE, B, FOOTINGS	140.400	CYS
98	702-51100 DRAIN PIPE, CAST IRON, 6 IN	6,190.000	LBS

CALL ORDER : 141

CONTRACT ID : SIR-30709-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
99	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	1,290.000	LBS
100	702-51863 FIELD DRILLED HOLE IN CONCRETE	668.000	EACH
101	703-06028 REINFORCING BARS	67,755.000	LBS
102	703-06029 REINFORCING BARS, EPOXY COATED	464,259.000	LBS
103	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	1,463.000	EACH
104	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,712.500	CYS
105	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	4.000	EACH
106	706-06342 RAILING, PS-1	686.000	LFT
107	706-06353 CONCRETE BRIDGE RAILING TRANSITION, TPS-1	2.000	EACH
108	706-06353 CONCRETE BRIDGE RAILING TRANSITION, TPS-1	2.000	EACH
109	706-08502 REINFORCED CONCRETE MOMENT SLAB, 15 IN	1,865.000	SYS
110	706-09545 COARSE AGGREGATE, NO 8	456.000	CYS
111	706-51020 CONCRETE, C, RAILING	60.000	CYS
112	706-51025 CONCRETE, C, RAILING	264.000	LFT
113	707-09384 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	3,948.000	LFT
114	709-07733 ANTI-GRAFFITI COAT	LUMP	LUMP
115	709-51821 SURFACE SEAL	LUMP	LUMP
116	709-51821 SURFACE SEAL	LUMP	LUMP
117	709-51821 SURFACE SEAL	LUMP	LUMP
118	709-51821 SURFACE SEAL	LUMP	LUMP
119	709-51821 SURFACE SEAL	LUMP	LUMP
120	709-51821 SURFACE SEAL	LUMP	LUMP
121	714-26702 STRUCTURE, PRECAST, RC, BOX SECTION 6FT X 3FT	320.000	LFT
122	715-01354 CLEAN EXISTING PIPE	106.000	LFT
123	715-05128 PIPE, TYPE 1, CIRCULAR, 48 IN	54.000	LFT
124	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN	1,058.000	LFT
125	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN	38.000	LFT
126	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN	173.000	LFT
127	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN	302.000	LFT
128	715-06004 CONCRETE ANCHOR, 48 IN	2.000	EACH
129	715-09064 VIDEO INSPECTION FOR PIPE	1,254.000	LFT
130	715-46000 PIPE END SECTION, 12 IN	4.000	EACH
131	715-46005 PIPE END SECTION, 15 IN	1.000	EACH
132	715-46010 PIPE END SECTION, 18 IN	1.000	EACH
133	715-46020 PIPE END SECTION, 24 IN	1.000	EACH
134	716-07637 PIPE INSTALLATION, TRENCHLESS, 48 IN	136.000	LFT
135	718-08308 UNDERDRAIN, PATCHING	350.000	LFT
136	720-07301 INLET, TYPE HA	2.000	EACH
137	720-45080 INLET, S14	2.000	EACH
138	720-45085 INLET, T14	1.000	EACH
139	720-45410 MANHOLE, C4	4.000	EACH
140	720-91246 INLET, N12A	2.000	EACH
141	720-98174 INLET, B15	17.000	EACH
142	720-98555 INLET, C15	4.000	EACH
143	731-93945 FACE PANELS, CONCRETE	44,270.000	SFT
144	731-93946 WALL ERECTION	44,270.000	SFT
145	731-93947 LEVELING PAD, CONCRETE	2,790.000	LFT
146	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	6.000	EACH
147	801-03290 CONSTRUCTION SIGN, C	7.000	EACH

CALL ORDER : 141

CONTRACT ID : SIR-30709-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
148	801-04308 ROAD CLOSURE SIGN ASSEMBLY	12.000	EACH
149	801-06198 PATROLLER	300.000	DAY
150	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN.	11,225.000	LFT
151	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	30,289.000	LFT
152	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	11.000	EACH
153	801-06640 CONSTRUCTION SIGN, A	51.000	EACH
154	801-06645 CONSTRUCTION SIGN, B	32.000	EACH
155	801-06710 FLASHING ARROW SIGN	570.000	DAY
156	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
157	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	2.000	EACH
158	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	2.000	EACH
159	801-07117 TEMPORARY WORKSITE FLASHING LIGHT SIGN ASSEMBLY	5.000	EACH
160	801-07118 BARRICADE, III-A	356.000	LFT
161	801-07119 BARRICADE, III-B	96.000	LFT
162	801-08400 TEMPORARY TRAFFIC BARRIER, TYPE 1	2,484.000	LFT
163	801-08507 TEMP TRAFFIC BARRIER, TYPE 1, ANCHORED	2,292.000	LFT
164	801-08509 TEMP TRAFFIC BARRIER, TYPE 3, ANCHORED	150.000	LFT
165	801-09133 TEMPORARY CHANGEABLE MESSAGE SIGN	4.000	EACH
166	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	65.000	LFT
167	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	32.000	SFT
168	802-74085 OVERHEAD SIGN STR, TWIN CANT, REMOVE	2.000	EACH
169	802-93389 BARRIER WALL SIGN BRACKET, SHOULDER	1.000	EACH
170	805-01842 HANDHOLE, SIGNAL	8.000	EACH
171	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C 14GA	705.000	LFT
172	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
173	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	241.000	LFT
174	805-95209 TRUCK, TOW	300.000	DAY
175	807-02191 HANDHOLE, LIGHTING	4.000	EACH
176	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	2,800.000	LFT
177	807-08214 CONDUIT, PVC, 2 IN., SCHEDULE 40, FOR ELECTRIC	991.000	LFT
178	807-97114 CABLE, INTERCONNECT, 6 PAIR 19	3,229.000	LFT
179	807-97114 CABLE, INTERCONNECT, 6 PAIR 19	3,203.000	LFT
180	808-03002 LINE, EPOXY, BROKEN, WHITE, 4 IN	324.000	LFT
181	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN	431.000	LFT
182	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN	862.000	LFT
183	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	1,921.000	LFT
184	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	745.000	LFT
185	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,624.000	LFT
186	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	348.000	LFT
187	808-06716 LINE, REMOVE	6,930.000	LFT
188	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
189	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5,498.000	LFT
190	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	44.000	LFT
191	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	4.000	EACH
192	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	1.000	EACH
193	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	200.000	EACH
194	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	253.000	EACH

CALL ORDER : 241

CONTRACT ID : SRS-32882-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	16.000	MOS
4	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5	109-08359 LIQUIDATED DAMAGES	1.000	DOL
6	109-08360 CONTRACT LIENS	1.000	DOL
7	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
8	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
9	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	303-01180 COMPACTED AGGREGATE, NO. 53	50.000	TON
12	304-07783 HMA PATCHING, TYPE D	460.000	TON
13	306-08042 MILLING, SCARIFICATION/PROFILE	108,000.000	SYS
14	306-08043 MILLING, TRANSITION	1,850.000	SYS
15	306-08432 MILLING, APPROACH	1,400.000	SYS
16	401-09717 QC/QA-HMA, 3, 64, SURFACE 4.75 mm	4,800.000	TON
17	406-05520 ASPHALT FOR TACK COAT	30.000	TON
18	506-06333 PCCP PATCHING, FULL DEPTH	50.000	SYS
19	628-09403 FIELD OFFICE, C	8.000	MOS
20	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	8.000	MOS
21	720-44000 CASTING, ADJUST TO GRADE	75.000	EACH
22	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
23	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	55,600.000	LFT
24	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	19.000	EACH
25	801-06640 CONSTRUCTION SIGN, A	76.000	EACH
26	801-06710 FLASHING ARROW SIGN	250.000	DAY
27	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
28	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	4.000	EACH
29	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	6,400.000	LFT
30	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	46,000.000	LFT
31	808-74815 TRANSVERSE MARKING THERMOPLASTIC	1,200.000	LFT
32	808-75278 TRANSVERSE MARKING, THERMOPLASTIC, SOLID, YELLOW,	1,600.000	LFT
33	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	400.000	LFT
34	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, LANE INDICATION	25.000	EACH
35	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, ONLY	18.000	EACH
36	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	900.000	EACH
37	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	930.000	EACH

CALL ORDER : 341

CONTRACT ID : SB -28994-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-08520 CELLULAR TELEPHONE/RADIO	2.000	EACH
3	105-08521 CELLULAR TELEPHONE/RADIO SERVICE	10.000	MOS
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08442 QUALITY ADJUSTMENTS, SUPERSTRUCTURE CONCRETE	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	216.000	SYS
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	202-51368 SLOPEWALL, REMOVE	810.000	SYS
14	203-02000 EXCAVATION, COMMON	1,375.000	CYS
15	203-51223 EXCAVATION, WATERWAY	415.000	CYS
16	205-03371 SEDIMENT, REMOVE	8.000	CYS
17	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	132.000	TON
18	205-06933 TEMPORARY DITCH INLET PROTECTION	1.000	EACH
19	205-06936 TEMPORARY SEDIMENT TRAP	85.000	TON
20	205-06937 TEMPORARY SILT FENCE	1,160.000	LFT
21	206-09750 TURBIDITY CURTAIN	4.000	EACH
22	206-51220 EXCAVATION, WET	200.000	CYS
23	206-51235 COFFERDAM	LUMP	LUMP
24	207-08265 SUBGRADE TREATMENT, TYPE IIA	461.000	SYS
25	211-06467 AGGREGATE FOR END BENT BACKFILL	34.400	CYS
26	211-09264 STRUCTURAL BACKFILL, TYPE 1	209.000	CYS
27	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	837.000	TON
28	302-07455 DENSE GRADED SUBBASE	52.000	CYS
29	306-08036 MILLING, ASPHALT, 2 IN	1,165.000	SYS
30	402-07432 HMA SURFACE, TYPE A	190.000	TON
31	402-07435 HMA INTERMEDIATE, TYPE A	325.000	TON
32	406-05520 ASPHALT FOR TACK COAT	0.700	TON
33	601-01128 GUARDRAIL TRANSITION TYPE WGB	3.000	EACH
34	601-01128 GUARDRAIL TRANSITION TYPE WGB	1.000	EACH
35	601-01848 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 5	1.000	EACH
36	601-02241 GUARDRAIL, REMOVE	262.000	LFT
37	601-06037 GUARDRAIL END TREATMENT, I	1.000	EACH
38	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
39	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	187.500	LFT
40	602-06729 BARRIER DELINEATOR	8.000	EACH
41	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	310.000	SYS
42	615-06490 RIGHT OF WAY MARKER	16.000	EACH
43	615-06505 MONUMENT, B	2.000	EACH
44	616-02320 GEOTEXTILES	999.000	SYS
45	616-06405 RIPRAP, REVETMENT	666.000	TON
46	621-06545 FERTILIZER	0.300	TON
47	621-06553 SEED MIXTURE, R	150.000	LBS
48	621-06557 SEED MIXTURE, T	130.000	LBS
49	621-06565 MULCHING MATERIAL	4.000	TON

CALL ORDER : 341

CONTRACT ID : SB -28994-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-06567 WATER	1.000	KGAL
51	621-06574 SODDING	25.000	SYS
52	621-52448 SIGN, DO NOT SPRAY	4.000	EACH
53	622-98200 SIGN, DO NOT DISTURB	4.000	EACH
54	628-09402 FIELD OFFICE, B	10.000	MOS
55	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	10.000	MOS
56	701-06027 TEST PILE	4.000	EACH
57	701-09559 TEST PILE, DYNAMIC, RESTRIKE	4.000	EACH
58	701-51195 PILE, STEEL H, HP 12 IN X 53	2,805.000	LFT
59	701-91792 PILE TIP, STEEL H	33.000	EACH
60	702-51005 CONCRETE, A, SUBSTRUCTURE	109.200	CYS
61	702-51015 CONCRETE, B, FOOTINGS	11.800	CYS
62	703-06028 REINFORCING BARS	19,401.000	LBS
63	703-06029 REINFORCING BARS, EPOXY COATED	61,388.000	LBS
64	704-51002 CONCRETE, C, SUPERSTRUCTURE	212.400	CYS
65	706-05733 CONCRETE BRIDGE RAILING TRANSITION, WBC	4.000	EACH
66	706-51020 CONCRETE, C, RAILING	17.000	CYS
67	707-07776 STRUCTURAL MEMBERS, CONCRETE BOX BEAM	1,860.000	LFT
68	709-51821 SURFACE SEAL	LUMP	LUMP
69	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN	196.000	LFT
70	715-05173 PIPE, TYPE 3, CIRCULAR, 24 IN	65.000	LFT
71	715-05407 PIPE, END BENT DRAIN, 6 IN	150.000	LFT
72	715-46020 PIPE END SECTION, 24 IN	5.000	EACH
73	720-45030 INLET, E7	1.000	EACH
74	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
75	801-06625 DETOUR ROUTE MARKER ASSEMBLY	16.000	EACH
76	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
77	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
78	801-07118 BARRICADE, III-A	48.000	LFT
79	801-07119 BARRICADE, III-B	144.000	LFT
80	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	18.000	SFT
81	802-76055 SIGN POST, A	44.000	LFT
82	808-03631 LINE, EPOXY, SOLID, WHITE, 4 IN	1,250.000	LFT
83	808-03632 LINE, EPOXY, SOLID, YELLOW, 4 IN	1,250.000	LFT
84	808-06716 LINE, REMOVE	2,150.000	LFT

