

CALL ORDER : 155

CONTRACT ID : IR-33045-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION HMA			
1	207-08263 SUBGRADE TREATMENT, TYPE IA	529,585.000	SYS
2	207-08265 SUBGRADE TREATMENT, TYPE IIA	43,153.000	SYS
3	207-08267 SUBGRADE TREATMENT, TYPE IIIA	87,312.000	SYS
4	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	97,105.000	TON
5	303-01180 COMPACTED AGGREGATE, NO. 53	97,597.000	TON
6	303-02125 AGGREGATE, 23	56.000	CYS
7	306-08043 MILLING, TRANSITION	1,648.000	SYS
8	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
9	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	10,070.000	TON
10	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,929.000	TON
11	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	3,385.000	TON
12	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	27,669.000	TON
13	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	12,206.000	TON
14	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	3,214.000	TON
15	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	5,641.000	TON
16	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	46,413.000	TON
17	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	27,792.000	TON
18	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	4,500.000	TON
19	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	13,539.000	TON
20	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	50,867.000	TON
21	401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM	132,415.000	TON
22	406-05520 ASPHALT FOR TACK COAT	511.000	TON
23	606-07484 MILLED HMA SHOULDER CORRUGATIONS	200,312.000	LFT
SECTION NO. 0002 NEW ROAD CONSTRUCTION PCCP			
24	207-08263 SUBGRADE TREATMENT, TYPE IA	512,298.000	SYS
25	207-08265 SUBGRADE TREATMENT, TYPE IIA	43,153.000	SYS
26	207-08267 SUBGRADE TREATMENT, TYPE IIIA	87,312.000	SYS
27	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	78,331.000	TON
28	302-06464 SUBBASE FOR PCCP	91,809.000	CYS
29	303-01180 COMPACTED AGGREGATE, NO. 53	90,533.000	TON
30	303-02125 AGGREGATE, 23	56.000	CYS
31	306-08043 MILLING, TRANSITION	1,648.000	SYS
32	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
33	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	14,045.000	TON
34	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	2,512.000	TON
35	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	26,737.000	TON
36	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	4,215.000	TON
37	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	32,292.000	TON
38	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	3,903.000	TON
39	401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM	8,933.000	TON
40	406-05520 ASPHALT FOR TACK COAT	152.000	TON
41	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
42	501-06321 QC/QA-PCCP, 10 IN	33,940.000	SYS
43	501-06322 QC/QA-PCCP, 11 IN	267,182.000	SYS
44	501-06727 CORING, PCCP	LUMP	LUMP
45	501-09749 QC/QA PCCP, 9.5"	23,375.000	SYS
46	503-05240 D-1 CONTRACTION JOINT	180,671.000	LFT

CALL ORDER : 155

CONTRACT ID : IR-33045-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002 NEW ROAD CONSTRUCTION PCCP			
47 503-05310	TERMINAL JOINT	1,069.000	LFT
48 606-07484	MILLED HMA SHOULDER CORRUGATIONS	150,252.000	LFT
49 606-07485	MILLED PCCP SHOULDER CORRUGATIONS	74,859.000	LFT
SECTION NO. 0003 NEW ROAD AND BRIDGE CONSTRUCTION			
50 105-06845	CONSTRUCTION ENGINEERING	LUMP	LUMP
51 105-06899	RADIO	4.000	EACH
52 105-08520	CELLULAR TELEPHONE/RADIO	4.000	EACH
53 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	136.000	MOS
54 105-08523	RADIO ONLY SERVICE	136.000	MOS
55 105-09645	CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
56 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
57 201-52370	CLEARING RIGHT OF WAY	LUMP	LUMP
58 202-01405	CONTAMINATED SOIL, REMOVE AND DISPOSE	6,204.000	CYS
59 202-02240	PAVEMENT REMOVAL	6,738.400	SYS
60 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
61 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
62 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
63 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
64 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
65 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
66 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
67 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
68 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
69 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
70 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
71 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
72 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
73 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
74 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
75 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
76 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
77 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
78 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
79 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
80 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
81 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
82 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
83 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
84 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
85 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
86 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
87 202-04089	SIGN, SHEET, REMOVE	7.000	EACH
88 202-09957	PLUG AND ABANDON OIL OR GAS WELL	5.000	EACH
89 202-51330	PRESENT STRUCTURE, REMOVE	LUMP	LUMP
90 202-74035	SIGN, REMOVE	1.000	EACH
91 202-96133	PIPE, REMOVE	173.000	LFT
92 203-02020	EXCAVATION, UNCLASSIFIED	2,357,025.000	CYS

CALL ORDER : 155

CONTRACT ID : IR-33045-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 NEW ROAD AND BRIDGE CONSTRUCTION			
93	203-02070 BORROW	2,010,052.000	CYS
94	203-02070 BORROW	103,097.000	CYS
95	203-10106 AGGREGATE COLUMN	LUMP	LUMP
96	203-10106 AGGREGATE COLUMN	LUMP	LUMP
97	203-10106 AGGREGATE COLUMN	LUMP	LUMP
98	203-10106 AGGREGATE COLUMN	LUMP	LUMP
99	203-10106 AGGREGATE COLUMN	LUMP	LUMP
100	203-10106 AGGREGATE COLUMN	LUMP	LUMP
101	203-10106 AGGREGATE COLUMN	LUMP	LUMP
102	203-10106 AGGREGATE COLUMN	LUMP	LUMP
103	203-10106 AGGREGATE COLUMN	LUMP	LUMP
104	203-10106 AGGREGATE COLUMN	LUMP	LUMP
105	203-10106 AGGREGATE COLUMN	LUMP	LUMP
106	203-10106 AGGREGATE COLUMN	LUMP	LUMP
107	203-10106 AGGREGATE COLUMN	LUMP	LUMP
108	204-02290 SETTLEMENT PLATE	15.000	EACH
109	205-02770 EROSION CONTROL BLANKET	44,493.000	SYS
110	205-06934 TEMPORARY MULCHING	127.450	TON
111	205-09543 NO 2 STONE	200.000	TON
112	205-09942 CLAY CAPPED DITCH	4,986.000	LFT
113	205-09952 DESIGN BUILD EROSION AND SEDIMENT CONTROL	LUMP	LUMP
114	206-51220 EXCAVATION, WET	11,059.000	CYS
115	206-51225 EXCAVATION, DRY	38,600.000	CYS
116	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	47,851.000	CYS
117	206-51235 COFFERDAM	LUMP	LUMP
118	206-51235 COFFERDAM	LUMP	LUMP
119	206-51235 COFFERDAM	LUMP	LUMP
120	206-51235 COFFERDAM	LUMP	LUMP
121	206-51235 COFFERDAM	LUMP	LUMP
122	211-02050 B BORROW	116,361.000	CYS
123	211-06467 AGGREGATE FOR END BENT BACKFILL	829.000	CYS
124	211-09264 STRUCTURAL BACKFILL, TYPE 1	30,645.400	CYS
125	211-09265 STRUCTURAL BACKFILL, TYPE 2	41,657.000	CYS
126	211-09266 STRUCTURAL BACKFILL, TYPE 3	82,564.000	CYS
127	214-07202 GEOGRID, TYPE I	1,950.000	SYS
128	214-07202 GEOGRID, TYPE I	835.000	SYS
129	215-07043 CHEMICAL MODIFICATION, SOILS	729,559.000	SYS
130	302-07455 DENSE GRADED SUBBASE	1,059.000	CYS
131	303-01180 COMPACTED AGGREGATE, NO. 53	1,112.000	TON
132	303-07449 COMPACTED AGGREGATE, NO. 73	12,077.000	TON
133	402-07432 HMA SURFACE, TYPE A	4,842.000	TON
134	402-07433 HMA SURFACE, TYPE B	665.000	TON
135	402-07435 HMA INTERMEDIATE, TYPE A	8,079.000	TON
136	402-07438 HMA INTERMEDIATE, TYPE B	1,117.000	TON
137	402-07451 HMA WEDGE AND LEVEL, TYPE B	70.000	TON
138	402-07453 HMA FOR TEMPORARY PAVEMENT	2,129.000	TON
139	601-01522 GUARDRAIL TRANSITION TYPE TGB	76.000	EACH
140	601-02241 GUARDRAIL, REMOVE	800.000	LFT
141	601-06233 IMPACT ATTENUATOR, ED, W1, TL-3	6.000	EACH

CALL ORDER : 155

CONTRACT ID : IR-33045-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 NEW ROAD AND BRIDGE CONSTRUCTION			
142	601-06246 IMPACT ATTENUATOR, R2, W1, TL-3	1.000	EACH
143	601-94689 GUARDRAIL END TREATMENT, OS	56.000	EACH
144	601-94690 GUARDRAIL END TREATMENT, MS	15.000	EACH
145	601-99105 GUARDRAIL, W BEAM, 6 FT 3 IN SPACING	13,522.400	LFT
146	601-99108 GUARDRAIL, W BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	3,700.000	LFT
147	602-06729 BARRIER DELINEATOR	336.000	EACH
148	602-08606 CONCRETE BARRIER, 33 IN, MODIFIED	1,111.000	LFT
149	603-06040 FENCE, FARM FIELD, 47 IN	106,753.000	LFT
150	603-96042 FENCE GATE, FARM FIELD, 47 IN X 24FT	3.000	EACH
151	605-05523 CURB, HMA	197.000	LFT
152	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	1,019.000	SYS
153	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	5,274.000	SYS
154	610-08446 PCCP FOR APPROACHES, 6 IN	234.000	SYS
155	615-06490 RIGHT OF WAY MARKER	220.000	EACH
156	615-06505 MONUMENT, B	22.000	EACH
157	615-06510 MONUMENT, C	93.000	EACH
158	615-06515 MONUMENT, D	22.000	EACH
159	615-06527 MONUMENT, SECTION CORNER	4.000	EACH
160	615-06530 BENCH MARK POST	17.000	EACH
161	616-02320 GEOTEXTILES	68,694.000	SYS
162	616-05688 RIPRAP, CLASS 1	6,772.000	TON
163	616-05689 RIPRAP, CLASS 2	69.000	TON
164	616-06405 RIPRAP, REVETMENT	52,569.300	TON
165	616-07656 RIPRAP	324.500	TON
166	616-51367 SLOPEWALL, CONCRETE, 4 IN	143.000	SYS
167	619-09437 PAINT STEEL BRIDGE, PARTIAL, TYPE 1	1,178.000	SFT
168	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	19.000	EACH
169	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	3,190.000	SYS
170	621-02770 EROSION CONTROL BLANKET	7,418.000	SYS
171	621-04258 SEED MIXTURE	43.130	LBS
172	621-04258 SEED MIXTURE	153.140	LBS
173	621-06545 FERTILIZER	152.700	TON
174	621-06553 SEED MIXTURE, R	51,854.000	LBS
175	621-06557 SEED MIXTURE, T	25,512.550	LBS
176	621-06559 MULCHED SEEDING, R	3,028.000	SYS
177	621-06565 MULCHING MATERIAL	628.170	TON
178	621-06567 WATER	385.800	KGAL
179	621-06574 SODDING	102,528.000	SYS
180	622-52436 SIGN, DO NOT MOW OR SPRAY	61.000	EACH
181	622-91786 SEEDLING	865.000	EACH
182	622-91786 SEEDLING	1,731.000	EACH
183	622-91786 SEEDLING	3,086.000	EACH
184	628-09403 FIELD OFFICE, C	34.000	MOS
185	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	136.000	MOS
186	701-02936 PILE, STEEL H, HP 14 IN X 89	16,612.000	LFT
187	701-02938 CORED HOLE IN ROCK, 24 IN	206.000	LFT
188	701-06011 DYNAMIC PILE LOAD TEST	64.000	EACH
189	701-08253 PILE SLEEVES	267.000	EACH
190	701-09557 TEST PILE, DYNAMIC, PRODUCTION	4,670.900	LFT

CALL ORDER : 155

CONTRACT ID : IR-33045-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 NEW ROAD AND BRIDGE CONSTRUCTION			
191	701-09559 TEST PILE, DYNAMIC, RESTRIKE	64.000	EACH
192	701-09683 PILE SHOE, HP 12 X 74	300.000	EACH
193	701-09684 PILE SHOE, HP 14 X 89	259.000	EACH
194	701-91792 PILE TIP, STEEL H	70.000	EACH
195	701-95780 PILE, STEEL H, HP 12 IN X 74	18,150.600	LFT
196	702-01724 CONCRETE, C, FOOTINGS	456.000	CYS
197	702-04325 TEMPORARY SHORING	LUMP	LUMP
198	702-04325 TEMPORARY SHORING	LUMP	LUMP
199	702-51005 CONCRETE, A, SUBSTRUCTURE	2,830.000	CYS
200	702-51015 CONCRETE, B, FOOTINGS	2,905.000	CYS
201	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	3,988.000	LBS
202	702-90915 CONCRETE, CLASS A	881.000	CYS
203	702-92857 CONCRETE, C, SUBSTRUCTURE	1,800.000	CYS
204	703-06028 REINFORCING BARS	1,140,481.000	LBS
205	703-06029 REINFORCING BARS, EPOXY COATED	3,080,880.000	LBS
206	704-51002 CONCRETE, C, SUPERSTRUCTURE	10,021.900	CYS
207	706-05732 CONCRETE BRIDGE RAILING TRANSITION, TBC	40.000	EACH
208	706-05734 CONCRETE BRIDGE RAILING TRANSITION, TBT	64.000	EACH
209	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	151.000	SYS
210	706-09545 COARSE AGGREGATE, NO 8	67.000	CYS
211	706-51020 CONCRETE, C, RAILING	1,269.100	CYS
212	707-05984 STRUCTURAL MEMBERS, CONCRETE I-BEAM	3,698.000	LFT
213	707-05997 STRUCTURAL MEMBERS, CONCRETE BULB-T	1,480.000	LFT
214	707-07605 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	6,423.600	LFT
215	707-08476 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	3,355.000	LFT
216	707-08643 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	1,950.000	LFT
217	707-09316 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	2,485.000	LFT
218	707-09332 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	491.800	LFT
219	707-09384 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	1,480.000	LFT
220	707-09634 STRUCTURAL MEMBERS, CONCRETE BULB-T BEAM,	417.000	LFT
221	707-09921 STRUCTURAL MEMBERS, CONCRETE, BULB-T BEAM,	462.400	LFT
222	709-51821 SURFACE SEAL	LUMP	LUMP
223	709-51821 SURFACE SEAL	LUMP	LUMP
224	709-51821 SURFACE SEAL	LUMP	LUMP
225	709-51821 SURFACE SEAL	LUMP	LUMP
226	709-51821 SURFACE SEAL	LUMP	LUMP
227	709-51821 SURFACE SEAL	LUMP	LUMP
228	709-51821 SURFACE SEAL	LUMP	LUMP
229	709-51821 SURFACE SEAL	LUMP	LUMP
230	709-51821 SURFACE SEAL	LUMP	LUMP
231	709-51821 SURFACE SEAL	LUMP	LUMP
232	709-51821 SURFACE SEAL	LUMP	LUMP
233	709-51821 SURFACE SEAL	LUMP	LUMP
234	709-51821 SURFACE SEAL	LUMP	LUMP
235	709-51821 SURFACE SEAL	LUMP	LUMP
236	709-51821 SURFACE SEAL	LUMP	LUMP
237	709-51821 SURFACE SEAL	LUMP	LUMP
238	709-51821 SURFACE SEAL	LUMP	LUMP
239	709-51821 SURFACE SEAL	LUMP	LUMP

CALL ORDER : 155

CONTRACT ID : IR-33045-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 NEW ROAD AND BRIDGE CONSTRUCTION			
240	709-51821 SURFACE SEAL	LUMP	LUMP
241	709-51821 SURFACE SEAL	LUMP	LUMP
242	709-51821 SURFACE SEAL	LUMP	LUMP
243	709-51821 SURFACE SEAL	LUMP	LUMP
244	709-51821 SURFACE SEAL	LUMP	LUMP
245	709-51821 SURFACE SEAL	LUMP	LUMP
246	709-51821 SURFACE SEAL	LUMP	LUMP
247	709-51821 SURFACE SEAL	LUMP	LUMP
248	711-51038 STRUCTURAL STEEL	LUMP	LUMP
249	714-04661 STRUCTURE, PRECAST, RC, BOX SECTION 11FT X 6FT	120.000	LFT
250	714-04875 STRUCTURE, PRECAST, REINFORCED CONCRETE BOX SECTIONS	206.000	LFT
251	714-05760 STRUCTURE, PRECAST, RC, BOX SECTION 12FT X 5FT	200.000	LFT
252	714-06278 STRUCTURE, PRECAST, RC, BOX SECTION 9FT X 4FT	318.000	LFT
253	714-07537 STRUCTURE, PRECAST, RC, BOX SECTION 18FT X 7FT	211.000	LFT
254	714-08514 WINGWALL	1,820.000	SFT
255	714-09726 HEADWALL	469.000	SFT
256	714-09995 STRUCTURE, PRECAST REINFORCED CONCRETE BOX	278.000	LFT
257	714-26707 STRUCTURE, PRECAST REINFORCED CONCRETE	213.000	LFT
258	714-26708 STRUCTURE, PRECAST, RC, BOX SECTION 8FT X 4FT	797.000	LFT
259	714-26709 STRUCTURE, PRECAST, RC, BOX SECTION 8FT X 5FT	340.000	LFT
260	714-26714 STRUCTURE, PRECAST, RC, BOX SECTION 8FT X 8FT	344.000	LFT
261	714-93638 STRUCTURE, PRECAST, RC, BOX SECTION 5FT X 4FT	224.000	LFT
262	714-93641 STRUCTURE, PRECAST, RC, BOX SECTION 4FT X 3FT	169.000	LFT
263	714-93978 STRUCTURE, PRECAST, RC, BOX SECTION 4FT X 2FT	59.000	LFT
264	714-99194 STRUCTURE, PRECAST REINFORCED CONCRETE	289.000	LFT
265	714-99348 STRUCTURE, PRECAST, RC, BOX SECTION 5FT X 3FT	495.000	LFT
266	715-02246 PIPE END SECTION, 48 IN	4.000	EACH
267	715-05019 PIPE, TYPE 1, CIRCULAR, 36 IN	2,890.000	LFT
268	715-05048 PIPE, TYPE 4, CIRCULAR, 6 IN	231,693.000	LFT
269	715-05053 PIPE, UNDERDRAIN OUTLET, 6 IN	24,966.000	LFT
270	715-05119 PIPE, TYPE 1, CIRCULAR, 15 IN	96.000	LFT
271	715-05121 PIPE, TYPE 1, CIRCULAR, 18 IN	63.000	LFT
272	715-05123 PIPE, TYPE 1, CIRCULAR, 24 IN	389.000	LFT
273	715-05125 PIPE, TYPE 1, CIRCULAR, 30 IN	88.000	LFT
274	715-05128 PIPE, TYPE 1, CIRCULAR, 48 IN	766.000	LFT
275	715-05129 PIPE, TYPE 1, CIRCULAR, 54 IN	618.000	LFT
276	715-05133 PIPE, TYPE 1, CIRCULAR, 60 IN	284.000	LFT
277	715-05136 PIPE, TYPE 1, CIRCULAR, 72 IN	181.000	LFT
278	715-05149 PIPE, TYPE 2, CIRCULAR, 12 IN	4,618.000	LFT
279	715-05151 PIPE, TYPE 2, CIRCULAR, 15 IN	3,781.000	LFT
280	715-05152 PIPE, TYPE 2, CIRCULAR, 18 IN	3,171.000	LFT
281	715-05154 PIPE, TYPE 2, CIRCULAR, 24 IN	154.000	LFT
282	715-05169 PIPE, TYPE 3, CIRCULAR, 15 IN	366.000	LFT
283	715-05171 PIPE, TYPE 3, CIRCULAR, 18 IN	154.000	LFT
284	715-05173 PIPE, TYPE 3, CIRCULAR, 24 IN	226.000	LFT
285	715-05175 PIPE, TYPE 3, CIRCULAR, 30 IN	140.000	LFT
286	715-05407 PIPE, END BENT DRAIN, 6 IN	1,177.600	LFT
287	715-46000 PIPE END SECTION, 12 IN	42.000	EACH
288	715-46005 PIPE END SECTION, 15 IN	53.000	EACH

CALL ORDER : 155

CONTRACT ID : IR-33045-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	NEW ROAD AND BRIDGE CONSTRUCTION		
289 715-46010	PIPE END SECTION, 18 IN	18.000	EACH
290 715-46020	PIPE END SECTION, 24 IN	7.000	EACH
291 715-46030	PIPE END SECTION, 30 IN	4.000	EACH
292 715-46040	PIPE END SECTION, 36 IN	20.000	EACH
293 715-96881	PIPE END SECTION, 54 IN	2.000	EACH
294 718-06528	OUTLET PROTECTOR, 1	117.000	EACH
295 718-06529	OUTLET PROTECTOR, 2	278.000	EACH
296 718-06532	VIDEO INSPECTION FOR UNDERDRAINS	10,000.000	LFT
297 718-34000	PIPE, UNDERDRAIN, PERFORATED, 0.052 IN., 6 IN.	1,534.000	LFT
298 718-52610	AGGREGATE FOR UNDERDRAINS	23,363.000	CYS
299 718-99153	GEOTEXTILES FOR UNDERDRAIN	172,605.000	SYS
300 720-45041	INLET, H5	8.000	EACH
301 720-45065	INLET, N12	25.000	EACH
302 720-45066	INLET, N12, MODIFIED	70.000	EACH
303 720-90349	MANHOLE, C8	4.000	EACH
304 722-95883	BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
305 722-95883	BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
306 722-95883	BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
307 722-95883	BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
308 722-95883	BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
309 723-06660	WINGWALL	198.000	SFT
310 723-06927	STRUCTURE, PRECAST THREE-SIDED,	166.000	LFT
311 731-08252	LEVELING PAD	94.000	LFT
312 731-93945	FACE PANELS, CONCRETE	73,035.000	SFT
313 731-93946	WALL ERECTION	73,035.000	SFT
314 731-93947	LEVELING PAD, CONCRETE	3,371.000	LFT
315 801-03290	CONSTRUCTION SIGN, C	2.000	EACH
316 801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
317 801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	45,700.000	LFT
318 801-06625	DETOUR ROUTE MARKER ASSEMBLY	42.000	EACH
319 801-06640	CONSTRUCTION SIGN, A	39.000	EACH
320 801-06645	CONSTRUCTION SIGN, B	10.000	EACH
321 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
322 801-07118	BARRICADE, III-A	408.000	LFT
323 801-07119	BARRICADE, III-B	984.000	LFT
324 801-07606	TEMPORARY CROSSOVER DRAINAGE PIPE	500.000	LFT
325 801-52817	TEMPORARY CROSSOVER, B	1.000	EACH
326 802-04893	REFERENCE POST	38.000	EACH
327 802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	1,233.000	LFT
328 802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	74.000	LFT
329 802-07057	SIGN, PANEL, WITH LEGEND	2,882.500	SFT
330 802-07138	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, IX	6.000	EACH
331 802-07151	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	10.000	EACH
332 802-07153	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XI	6.000	EACH
333 802-07154	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XII	8.000	EACH
334 802-08456	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VIII	2.000	EACH
335 802-09577	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE E	1.000	EACH
336 802-09581	CANTILEVER SIGN SUPPORT FOUNDATION,	1.000	EACH
337 802-09838	SIGN, SHEET, WITH LEGEND 0.080"	511.130	SFT

CALL ORDER : 155

CONTRACT ID : IR-33045-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 NEW ROAD AND BRIDGE CONSTRUCTION			
338	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	271.000	SFT
339	802-76095 STRUCTURAL STEEL, BREAKAWAY	8,868.000	LBS
340	802-76160 BRIDGE BRACKET ASSEMBLY	2.000	EACH
341	802-76160 BRIDGE BRACKET ASSEMBLY	1.000	EACH
342	802-76160 BRIDGE BRACKET ASSEMBLY	1.000	EACH
343	804-06725 DELINEATOR WITH POST, D1	234.000	EACH
344	804-06740 DELINEATOR WITH POST, D2	60.000	EACH
345	804-06770 DELINEATOR POST	627.000	EACH
346	805-01842 HANDHOLE, SIGNAL	8.000	EACH
347	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	1,360.000	LFT
348	808-01329 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, WRONG WAY RAMP	2.000	EACH
349	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	28,997.000	LFT
350	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	29,053.000	LFT
351	808-06716 LINE, REMOVE	29,500.000	LFT
352	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
353	808-10031 LINE, MULTI-COMP, BROKEN, WHITE, 4 IN	3,218.000	LFT
354	808-10033 LINE, MULTI-COMP, SOLID, WHITE, 4 IN	128,917.000	LFT
355	808-10034 LINE, MULTI-COMP, SOLID, YELLOW, 4 IN	112,733.000	LFT
356	808-10038 TRANSVERSE MKGS MULTI-COMP SOLID WHITE,	3,495.000	LFT
357	808-10047 TRANSVERSE MKGS MULTI-COMP, SOLID, WHITE,	234.000	LFT
358	808-10051 TRANSVERSE MKG MULTI-COMP,	174.000	LFT
359	808-10052 PAVEMENT MESSAGE MKG, MULTI-COMP, (ONLY)	5.000	EACH
360	808-10054 LINE, MULTI-COMP, BROKEN, WHITE, 5 IN	25,268.000	LFT
361	808-10058 LINE, MULTI-COMP, SOLID, YELLOW, 8 IN	9,097.000	LFT
362	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	5.000	EACH
363	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	261.000	LFT
364	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,624.000	EACH
SECTION NO. 0004 NEW ROAD AND BRIDGE CONSTRUCTION			
365	105-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
366	109-08360 CONTRACT LIENS	1.000	DOL
367	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
368	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
369	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
370	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
371	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL

SCHEDULE OF PAY ITEMS

PAGE 9

CALL ORDER : 181

CONTRACT ID : IR-33649-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEMOLITION		
1 105-06845	CONSTRUCTION ENGINEERING	LUMP	LUMP
2 105-08520	CELLULAR TELEPHONE/RADIO	1.000	EACH
3 105-08521	CELLULAR TELEPHONE/RADIO SERVICE	6.000	MOS
4 105-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
5 109-08359	LIQUIDATED DAMAGES	1.000	DOL
6 109-08360	CONTRACT LIENS	1.000	DOL
7 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9 110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10 202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
11 202-03135	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	310.000	SFT
12 205-06937	TEMPORARY SILT FENCE	200.000	LFT
13 621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
14 621-06559	MULCHED SEEDING, R	300.000	SYS
15 628-09402	FIELD OFFICE, B	6.000	MOS
16 801-03290	CONSTRUCTION SIGN, C	2.000	EACH
17 801-06640	CONSTRUCTION SIGN, A	6.000	EACH
18 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

