

CALL ORDER : 311

CONTRACT ID : R -33668-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|-----------|-------|
| SECTION NO. 0001 | INTERSECTION IMPROVEMENT | | |
| 1 | 105-06845 CONSTRUCTION ENGINEERING | LUMP | LUMP |
| 2 | 109-08359 LIQUIDATED DAMAGES | 1.000 | DOL |
| 3 | 109-08360 CONTRACT LIENS | 1.000 | DOL |
| 4 | 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.000 | DOL |
| 5 | 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.000 | DOL |
| 6 | 109-08463 PROJECT ESTIMATE ADJUSTMENT | 1.000 | DOL |
| 7 | 110-01001 MOBILIZATION AND DEMOBILIZATION | LUMP | LUMP |
| 8 | 201-52370 CLEARING RIGHT OF WAY | LUMP | LUMP |
| 9 | 203-02000 EXCAVATION, COMMON | 6,043.000 | CYS |
| 10 | 203-02000 EXCAVATION, COMMON | 300.000 | CYS |
| 11 | 203-02010 EXCAVATION, ROCK | 100.000 | CYS |
| 12 | 203-02070 BORROW | 8,792.000 | CYS |
| 13 | 205-02234 TEMPORARY EROSION AND SEDIMENT CONTROL, CULVERT PIPE | 5.000 | EACH |
| 14 | 205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET | 30.000 | EACH |
| 15 | 205-06932 TEMPORARY CHECK DAM, STRAW BALES | 50.000 | LFT |
| 16 | 205-06933 TEMPORARY DITCH INLET PROTECTION | 3.000 | EACH |
| 17 | 205-06937 TEMPORARY SILT FENCE | 1,800.000 | LFT |
| 18 | 207-08262 SUBGRADE TREATMENT, TYPE I | 7,538.000 | SYS |
| 19 | 207-08267 SUBGRADE TREATMENT, TYPE IIIA | 116.000 | SYS |
| 20 | 211-02050 B BORROW | 2,400.000 | CYS |
| 21 | 211-09265 STRUCTURAL BACKFILL, TYPE 2 | 1,822.000 | CYS |
| 22 | 211-09268 STRUCTURAL BACKFILL, TYPE 5 | 225.000 | CYS |
| 23 | 213-09269 FLOWABLE BACKFILL, NON-REMOVABLE | 26.000 | CYS |
| 24 | 214-07202 GEOGRID, TYPE I | 7,400.000 | SYS |
| 25 | 301-07448 COMPACTED AGGREGATE, NO. 53, BASE | 744.000 | TON |
| 26 | 302-06464 SUBBASE FOR PCCP | 1,280.000 | CYS |
| 27 | 303-93506 AGGREGATE, 2 | 300.000 | CYS |
| 28 | 304-07493 WIDENING WITH HMA, TYPE B | 86.000 | TON |
| 29 | 306-08033 MILLING, ASPHALT, 1 IN | 2,493.000 | SYS |
| 30 | 401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm | 363.000 | TON |
| 31 | 402-07433 HMA SURFACE, TYPE B | 501.000 | TON |
| 32 | 402-07438 HMA INTERMEDIATE, TYPE B | 767.000 | TON |
| 33 | 402-07441 HMA BASE, TYPE B | 1,159.000 | TON |
| 34 | 402-07451 HMA WEDGE AND LEVEL, TYPE B | 187.000 | TON |
| 35 | 406-05520 ASPHALT FOR TACK COAT | 3.000 | TON |
| 36 | 502-06457 PCCP, 9 IN | 4,843.000 | SYS |
| 37 | 503-05240 D-1 CONTRACTION JOINT | 3,596.000 | LFT |
| 38 | 503-05310 TERMINAL JOINT | 318.000 | LFT |
| 39 | 604-01527 PAVERS, BRICK | 755.000 | SYS |
| 40 | 604-06367 JOINT MATERIAL | 2,419.000 | LFT |
| 41 | 604-07897 CURB RAMP, CONCRETE, C | 113.000 | SYS |
| 42 | 604-07901 CURB RAMP, CONCRETE, G | 30.500 | SYS |
| 43 | 604-07903 CURB RAMP, CONCRETE, K | 21.500 | SYS |
| 44 | 604-07904 CURB RAMP, CONCRETE, L | 6.000 | SYS |
| 45 | 604-44251 STEPS, CONCRETE | 2.000 | CYS |
| 46 | 604-91404 SIDEWALK, CONCRETE, 5 IN | 2,244.000 | SYS |
| 47 | 604-91531 SIDEWALK, CONCRETE, 4 IN | 1,106.000 | SYS |
| 48 | 604-95344 HANDRAIL, PEDESTRIAN | 325.000 | LFT |
| 49 | 605-06095 CURB, INTEGRAL, B, CONCRETE | 534.000 | LFT |

CALL ORDER : 311

CONTRACT ID : R -33668-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|------------|-------|
| SECTION NO. 0001 | INTERSECTION IMPROVEMENT | | |
| 50 | 605-06100 CURB, INTEGRAL, C, CONCRETE | 1,983.000 | LFT |
| 51 | 605-06120 CURB, CONCRETE | 1,085.000 | LFT |
| 52 | 605-06140 CURB AND GUTTER, CONCRETE | 3,477.000 | LFT |
| 53 | 605-06155 CURB AND GUTTER, CONCRETE, MODIFIED | 166.000 | LFT |
| 54 | 605-06210 CENTER CURB, C, CONCRETE | 30.000 | LFT |
| 55 | 609-11506 REINFORCED CONCRETE BRIDGE APPROACH, 9 IN. | 36.000 | SYS |
| 56 | 610-07486 HMA FOR APPROACHES, TYPE A | 53.000 | TON |
| 57 | 610-08446 PCCP FOR APPROACHES, 6 IN | 36.000 | SYS |
| 58 | 610-09108 PCCP FOR APPROACHES, 9 IN | 80.000 | SYS |
| 59 | 615-06505 MONUMENT, B | 19.000 | EACH |
| 60 | 615-06510 MONUMENT, C | 4.000 | EACH |
| 61 | 615-06515 MONUMENT, D | 7.000 | EACH |
| 62 | 615-06527 MONUMENT, SECTION CORNER | 1.000 | EACH |
| 63 | 616-02320 GEOTEXTILES | 82.000 | SYS |
| 64 | 616-06405 RIPRAP, REVETMENT | 47.000 | TON |
| 65 | 621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 1.000 | EACH |
| 66 | 621-02770 EROSION CONTROL BLANKET | 336.000 | SYS |
| 67 | 621-06567 WATER | 2,000.000 | KGAL |
| 68 | 621-06570 TOPSOIL | 1,325.000 | CYS |
| 69 | 621-06575 SODDING, NURSERY | 10,796.000 | SYS |
| 70 | 621-90853 TAPPING SLEEVE WITH VALVE | 2.000 | EACH |
| 71 | 621-90853 TAPPING SLEEVE WITH VALVE | 1.000 | EACH |
| 72 | 621-98038 MULCH, HARDWOOD SHREDDED BARK | 39.000 | CYS |
| 73 | 622-04648 TREE GRATE | 5.000 | EACH |
| 74 | 622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN | 132.000 | EACH |
| 75 | 622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN | 5.000 | EACH |
| 76 | 622-05653 PLANT, GROUND COVER | 1,878.000 | EACH |
| 77 | 628-09401 FIELD OFFICE, A | 8.000 | MOS |
| 78 | 702-90915 CONCRETE, CLASS A | 1.000 | CYS |
| 79 | 715-01472 PIPE END SECTION, PRECAST CONCRETE, 18 IN | 1.000 | EACH |
| 80 | 715-01765 PIPE END SECTION, PRECAST CONCRETE, 12 IN | 2.000 | EACH |
| 81 | 715-01841 PIPE DUCTILE IRON 15 IN | 301.000 | LFT |
| 82 | 715-02532 VALVE WITH BOX, RESTRAINED GATE, DUCTILE IRON, 8 IN | 1.000 | EACH |
| 83 | 715-03475 SAFETY METAL END SECTION, 4:1 15 IN | 2.000 | EACH |
| 84 | 715-03877 PIPE DUCTILE IRON 18" | 346.000 | LFT |
| 85 | 715-04612 PIPE | 170.000 | LFT |
| 86 | 715-04612 PIPE | 645.000 | LFT |
| 87 | 715-04612 PIPE | 168.000 | LFT |
| 88 | 715-04612 PIPE | 16.000 | LFT |
| 89 | 715-04612 PIPE | 10.000 | LFT |
| 90 | 715-04612 PIPE | 159.000 | LFT |
| 91 | 715-04612 PIPE | 4.000 | LFT |
| 92 | 715-04612 PIPE | 19.000 | LFT |
| 93 | 715-04926 VALVE | 2.000 | EACH |
| 94 | 715-04964 WATER MAIN | 50.000 | LFT |
| 95 | 715-04964 WATER MAIN | 35.000 | LFT |
| 96 | 715-05149 PIPE, TYPE 2 CIRCULAR 12 IN | 517.000 | LFT |
| 97 | 715-05154 PIPE, TYPE 2 CIRCULAR 24 IN | 329.000 | LFT |
| 98 | 715-05156 PIPE, TYPE 2 CIRCULAR 30 IN | 48.000 | LFT |

CALL ORDER : 311

CONTRACT ID : R -33668-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|---|-----------|-------|
| SECTION NO. 0001 | INTERSECTION IMPROVEMENT | | |
| 99 | 715-05157 PIPE, TYPE 2 CIRCULAR 33 IN | 70.000 | LFT |
| 100 | 715-06690 PIPE, RCP, III, D001=1500, 12 IN | 340.000 | LFT |
| 101 | 715-08250 PIPE DUCTILE IRON 11.8" | 395.000 | LFT |
| 102 | 715-46035 PIPE END SECTION, 33 IN | 1.000 | EACH |
| 103 | 715-96389 PIPE END SECTION, PRECAST CONCRETE, 24 IN | 1.000 | EACH |
| 104 | 715-98485 WATER MAIN, 24 IN. | 1,432.000 | LFT |
| 105 | 718-03277 PIPE, UNDERDRAIN, CORRUGATED PLASTIC, PERFORATED, 6 IN. | 3,347.000 | LFT |
| 106 | 718-04986 CLEANOUT | 3.000 | EACH |
| 107 | 718-52610 AGGREGATE FOR UNDERDRAINS | 487.000 | CYS |
| 108 | 718-99153 GEOTEXTILES FOR UNDERDRAIN | 2,264.000 | SYS |
| 109 | 720-03194 MANHOLE | 5.000 | EACH |
| 110 | 720-10257 MANHOLE, D10 | 3.000 | EACH |
| 111 | 720-45030 INLET, E7 | 3.000 | EACH |
| 112 | 720-45045 INLET, J10 | 11.000 | EACH |
| 113 | 720-45055 INLET, M10 | 27.000 | EACH |
| 114 | 720-45416 MANHOLE, E4 | 1.000 | EACH |
| 115 | 720-45520 MANHOLE, E4, MODIFIED | 1.000 | EACH |
| 116 | 720-94208 MANHOLE, C10 | 8.000 | EACH |
| 117 | 720-94840 CASTING, WATER VALVE, ADJUST TO GRADE | 4.000 | EACH |
| 118 | 720-96999 FIRE HYDRANT ASSEMBLY | 3.000 | EACH |
| 119 | 731-93947 LEVELING PAD, CONCRETE | 220.000 | LFT |
| 120 | 732-08419 MODULAR BLOCK WALL | 116.000 | SYS |
| 121 | 801-06625 DETOUR ROUTE MARKER ASSEMBLY | 74.000 | EACH |
| 122 | 801-06640 CONSTRUCTION SIGN, A | 44.000 | EACH |
| 123 | 801-06645 CONSTRUCTION SIGN, B | 11.000 | EACH |
| 124 | 801-06775 MAINTAINING TRAFFIC | LUMP | LUMP |
| 125 | 801-07119 BARRICADE, III-B | 260.000 | LFT |
| 126 | 802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE | 720.000 | LFT |
| 127 | 802-07058 SIGN, SHEET ASSEMBLY, RELOCATE | 11.000 | EACH |
| 128 | 802-09838 SIGN, SHEET, WITH LEGEND 0.080" | 200.000 | SFT |
| 129 | 802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN THICKNESS | 189.000 | SFT |
| 130 | 805-95568 CONDUIT, PVC, 4 IN. | 3,158.000 | LFT |
| 131 | 807-02191 HANDHOLE, LIGHTING | 9.000 | EACH |
| 132 | 807-06595 CONDUIT, PVC, 2 IN | 1,681.000 | LFT |
| 133 | 807-10029 CONDUIT, PVC, 1.25 IN | 320.000 | LFT |
| 134 | 807-78590 HANDHOLE | 4.000 | EACH |
| 135 | 807-78590 HANDHOLE | 2.000 | EACH |
| 136 | 808-03178 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, LANE ARROW | 6.000 | EACH |
| 137 | 808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY) | 2.000 | EACH |
| 138 | 808-03439 TRANSVERSE MARKING THERMOPLASTIC | 215.000 | LFT |
| 139 | 808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 176.000 | LFT |
| 140 | 808-10097 TRANSVERSE MARKINGS, MULTI-COMPONENT, | 119.000 | LFT |
| 141 | 808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN | 730.000 | LFT |
| 142 | 808-75054 LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN | 1,881.000 | LFT |
| 143 | 808-75059 LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN | 678.000 | LFT |
| 144 | 808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN | 3,977.000 | LFT |
| 145 | 808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 3.000 | EACH |
| 146 | 808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, | 3.000 | EACH |
| 147 | 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER | 3.000 | EACH |

SCHEDULE OF PAY ITEMS

CALL ORDER : 311

CONTRACT ID : R -33668-A

| ITEM NO. | DESCRIPTION | QUANTITY | UNITS |
|------------------|--|----------|-------|
| SECTION NO. 0001 | INTERSECTION IMPROVEMENT | | |
| 148 808-96016 | LINE, THERMOPLASTIC, SOLID, YELLOW, 12 IN | 565.000 | LFT |
| 149 808-99077 | LINE, PREFORMED PLASTIC, SOLID, WHITE, 24 IN | 368.000 | LFT |

