

CALL ORDER : 181

CONTRACT ID : R -30269-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 LOCAL ROAD PROJECT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	38,004.000	SYS
12	202-02278 CURB, CONCRETE, REMOVE	1,096.000	LFT
13	202-02637 PIPE, ABANDON AND GROUT FILL	13.000	LFT
14	202-02928 CATCH BASIN, REMOVE	15.000	EACH
15	202-52710 SIDEWALK, CONCRETE, REMOVE	2,335.000	SYS
16	202-86946 HANDHOLE, REMOVE	2.000	EACH
17	202-91385 INLET, REMOVE	2.000	EACH
18	202-93047 MANHOLE, REMOVE	2.000	EACH
19	202-93995 SIGNAL POLE FOUNDATION, REMOVE	2.000	EACH
20	202-93999 SIGNAL POLE, REMOVE	2.000	EACH
21	202-96133 PIPE, REMOVE	2,850.000	LFT
22	203-02000 EXCAVATION, COMMON	12,144.900	CYS
23	203-02055 EMBANKMENT	5,346.600	CYS
24	205-06933 TEMPORARY INLET PROTECTION	112.000	EACH
25	205-06937 TEMPORARY SILT FENCE	13,121.000	LFT
26	205-09543 NO 2 STONE	100.000	TON
27	207-08263 SUBGRADE TREATMENT, TYPE IA	33,977.800	SYS
28	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,127.100	SYS
29	211-09264 STRUCTURAL BACKFILL, TYPE 1	5,117.700	CYS
30	214-07202 GEOGRID, TYPE I	500.000	SYS
31	303-01180 COMPACTED AGGREGATE, NO. 53	4,944.500	TON
32	304-07491 HMA PATCHING, TYPE C	639.400	TON
33	304-07494 WIDENING WITH HMA, TYPE C	813.500	TON
34	306-08034 MILLING, ASPHALT, 1 1/2 IN	7,510.000	SYS
35	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,889.400	TON
36	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	619.600	TON
37	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	3,149.000	TON
38	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	1,032.600	TON
39	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	5,038.400	TON
40	402-07432 HMA SURFACE, TYPE A	332.200	TON
41	402-07433 HMA SURFACE, TYPE B	11.300	TON
42	402-07435 HMA INTERMEDIATE, TYPE A	553.600	TON
43	402-07438 HMA INTERMEDIATE, TYPE B	26.400	TON
44	402-07440 HMA BASE, TYPE A	275.800	TON
45	405-05517 ASPHALT FOR PRIME COAT	85.100	TON
46	406-05520 ASPHALT FOR TACK COAT	2.800	TON
47	601-02241 GUARDRAIL, REMOVE	688.000	LFT
48	604-06070 SIDEWALK, CONCRETE	2,096.700	SYS
49	604-07894 CURB RAMP, CONCRETE, A	33.000	SYS

CALL ORDER : 181

CONTRACT ID : R -30269-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL ROAD PROJECT		
50 604-07897	CURB RAMP, CONCRETE, C	44.000	SYS
51 604-07898	CURB RAMP, CONCRETE, D	14.000	SYS
52 604-07900	CURB RAMP, CONCRETE, F	15.000	SYS
53 604-07901	CURB RAMP, CONCRETE, G	77.000	SYS
54 604-07902	CURB RAMP, CONCRETE, H	64.000	SYS
55 605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	11,698.000	LFT
56 610-08446	PCCP FOR APPROACHES, 6 IN	1,496.900	SYS
57 610-09108	PCCP FOR APPROACHES, 9 IN	1,647.000	SYS
58 611-06497	MAILBOX ASSEMBLY, SINGLE	23.000	EACH
59 611-06498	MAILBOX ASSEMBLY, DOUBLE	3.000	EACH
60 615-06505	MONUMENT, B	10.000	EACH
61 615-06527	MONUMENT, SECTION CORNER	2.000	EACH
62 621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
63 621-06575	SODDING, NURSERY	3,282.000	SYS
64 621-06626	MULCHED SEEDING, D	15,464.000	SYS
65 628-09402	FIELD OFFICE, B	14.000	MOS
66 628-09407	FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	28.000	MOS
67 715-05146	PIPE, TYPE 2 CIRCULAR 6 IN	82.000	LFT
68 715-05149	PIPE, TYPE 2 CIRCULAR 12 IN	3,484.000	LFT
69 715-05151	PIPE, TYPE 2 CIRCULAR 15 IN	1,235.000	LFT
70 715-05152	PIPE, TYPE 2 CIRCULAR 18 IN	401.000	LFT
71 715-05153	PIPE, TYPE 2 CIRCULAR 21 IN	608.000	LFT
72 715-05154	PIPE, TYPE 2 CIRCULAR 24 IN	750.000	LFT
73 715-05155	PIPE, TYPE 2 CIRCULAR 27 IN	255.000	LFT
74 715-06696	PIPE, PVC, 10 IN	15.000	LFT
75 715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	239.900	TON
76 715-09475	STORMWATER QUALITY STRUCTURE	1.000	EACH
77 715-46000	PIPE END SECTION, DIA 12"	10.000	EACH
78 715-46005	PIPE END SECTION, DIA 15"	2.000	EACH
79 715-46010	PIPE END SECTION, DIA 18"	1.000	EACH
80 715-46025	PIPE END SECTION, DIA 27"	1.000	EACH
81 720-45425	MANHOLE, F4	1.000	EACH
82 720-44000	CASTING, ADJUST TO GRADE	1.000	EACH
83 720-44000	CASTING, ADJUST TO GRADE	1.000	EACH
84 720-44000	CASTING, ADJUST TO GRADE	14.000	EACH
85 720-44015	CASTING, 2, FURNISH AND ADJUST TO GRADE	7.000	EACH
86 720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	1.000	EACH
87 720-44296	INLET, CAP	4.000	EACH
88 720-45030	INLET, E7	3.000	EACH
89 720-45035	INLET, F7	7.000	EACH
90 720-45045	INLET, J10	38.000	EACH
91 720-45055	INLET, M10	44.000	EACH
92 720-45270	PIPE CATCH BASIN, 18 IN	23.000	EACH
93 720-45410	MANHOLE, C4	21.000	EACH
94 720-90984	MANHOLE, C2	4.000	EACH
95 720-91973	MANHOLE, H4	3.000	EACH
96 801-03290	CONSTRUCTION SIGN, C	7.000	EACH
97 801-06203	TEMPORARY PAVEMENT MARKING, 4 IN	11,550.000	LFT
98 801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	47.000	LFT

CALL ORDER : 181

CONTRACT ID : R -30269-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL ROAD PROJECT		
99	801-06625	DETOUR ROUTE MARKER ASSEMBLY	30.000 EACH
100	801-06640	CONSTRUCTION SIGN, A	45.000 EACH
101	801-06775	MAINTAINING TRAFFIC	LUMP LUMP
102	801-07118	BARRICADE, III-A	534.000 LFT
103	801-07119	BARRICADE, III-B	72.000 LFT
104	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	16.000 LFT
105	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	450.500 LFT
106	802-07058	SIGN, SHEET ASSEMBLY, RELOCATE	4.000 EACH
107	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	33.000 EACH
108	802-09838	SIGN, SHEET, WITH LEGEND 0.080"	256.750 SFT
109	802-09840	SIGN, SHEET, WITH LEGEND 0.100 IN	167.000 SFT
110	802-76235	INSTALL OVERHEAD SIGN	8.000 EACH
111	805-01842	HANDHOLE, SIGNAL	3.000 EACH
112	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	350.000 LFT
113	805-02065	SIGNAL SUPPORT FOUNDATION, 3 FT X 3 FT X 7 FT	2.000 EACH
114	805-02152	PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	4.000 EACH
115	805-78010	CONTROLLER AND CABINET, FLASHER, SOLID STATE	6.000 EACH
116	805-78100	CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000 EACH
117	805-78215	TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	3.000 EACH
118	805-78230	TRAFFIC SIGNAL HEAD, 5 FACE, 12"	5.000 EACH
119	805-78370	PEDESTRIAN PUSH BUTTON	4.000 EACH
120	805-78415	SPAN, CATENARY, AND TETHER	4.000 EACH
121	805-78420	DISCONNECT HANGER	4.000 EACH
122	805-78470	SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	1,230.000 LFT
123	805-78485	SIGNAL CABLE, 5C/14GA	1,730.000 LFT
124	805-78490	SIGNAL CABLE, 7C/14GA	820.000 LFT
125	805-78510	SIGNAL CABLE, 2C/16GA., SHIELDED	3,370.000 LFT
126	805-78785	SIGNAL DETECTOR HOUSING	3.000 EACH
127	805-78795	SAW CUT FOR ROADWAY LOOP AND SEALANT	380.000 LFT
128	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.000 EACH
129	805-81032	SIGNAL STRAIN POLE, STEEL, 30 FT	2.000 EACH
130	807-01603	SERVICE POINT, TYPE II	2.000 EACH
131	807-01878	LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	32.000 EACH
132	807-02191	HANDHOLE, LIGHTING	6.000 EACH
133	807-02193	LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT	32.000 EACH
134	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN	2,151.000 LFT
135	807-83752	LIGHT POLE, 40FT E.M.H., 10FT MAST ARM, ANCHOR BASE	32.000 EACH
136	807-86805	SERVICE POINT, I	6.000 EACH
137	807-86955	CABLE-DUCT MARKER	6.000 EACH
138	807-98335	WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN TRENCH, 4 1/C	9,085.000 LFT
139	808-03439	TRANSVERSE MARKING THERMOPLASTIC	220.000 LFT
140	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,835.000 LFT
141	808-09381	RETRO-REFLECTIVITY TESTING	LUMP LUMP
142	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,860.000 LFT
143	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	17,233.000 LFT
144	808-75274	TRANSVERSE MARKING, THERMOPLASTIC,	342.000 LFT
145	808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	346.000 LFT
146	808-75300	TRANSVERSE MARKING, THERMOPLASTIC,	705.000 LFT
147	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	30.000 EACH

CALL ORDER : 191

CONTRACT ID : R -30485-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SMALL STRUCTURE PROJECT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	134.000	SYS
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	203-02000 EXCAVATION, COMMON	357.000	CYS
14	203-02070 BORROW	507.000	CYS
15	205-03371 SEDIMENT, REMOVE	5.000	CYS
16	205-06933 TEMPORARY INLET PROTECTION	1.000	EACH
17	205-06937 TEMPORARY SILT FENCE	2,366.000	LFT
18	205-09543 NO 2 STONE	100.000	TON
19	206-93520 TEMPORARY SHEET PILING	252.000	SFT
20	207-09935 SUBGRADE TREATMENT, TYPE 1C	1,671.000	SYS
21	211-09264 STRUCTURAL BACKFILL, TYPE 1	4.000	CYS
22	211-09265 STRUCTURAL BACKFILL, TYPE 2	50.000	CYS
23	211-09268 STRUCTURAL BACKFILL, TYPE 5	442.000	CYS
24	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	452.000	TON
25	303-01180 COMPACTED AGGREGATE, NO. 53	195.000	TON
26	304-07494 WIDENING WITH HMA, TYPE C	183.000	TON
27	306-08034 MILLING, ASPHALT, 1 1/2 IN	267.000	SYS
28	306-08043 MILLING, TRANSITION	625.000	SYS
29	401-10258 JOINT ADHESIVE, SURFACE	1,428.000	LFT
30	401-10259 JOINT ADHESIVE, INTERMEDIATE	1,068.000	LFT
31	402-07434 HMA SURFACE, TYPE C	169.000	TON
32	402-07439 HMA INTERMEDIATE, TYPE C	217.000	TON
33	402-07442 HMA BASE, TYPE C	329.000	TON
34	406-05521 ASPHALT FOR TACK COAT	3,666.000	SYS
35	601-02241 GUARDRAIL, REMOVE	1,569.000	LFT
36	601-06854 GUARDRAIL, W-BEAM, NESTED	4.000	EACH
37	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
38	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	850.000	LFT
39	616-02320 GEOTEXTILES	155.000	SYS
40	616-06405 RIPRAP, REVETMENT	206.000	TON
41	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
42	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	1,880.000	SYS
43	621-02770 EROSION CONTROL BLANKET	676.000	SYS
44	621-06559 MULCHED SEEDING, R	1,410.000	SYS
45	621-09867 MULCHED SEEDING,	939.000	SYS
46	628-09402 FIELD OFFICE, B	6.000	MOS
47	714-11182 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	45.000	LFT
48	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	42.000	LFT
49	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	30.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 5

CALL ORDER : 191

CONTRACT ID : R -30485-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE PROJECT		
50 720-45235	CATCH BASIN, E7	1.000	EACH
51 723-11690	STRUCTURE, COATED REINFORCED CONCRETE,	50.000	LFT
52 801-01851	TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
53 801-03290	CONSTRUCTION SIGN, C	2.000	EACH
54 801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	8,224.000	LFT
55 801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	24.000	LFT
56 801-06640	CONSTRUCTION SIGN, A	26.000	EACH
57 801-06645	CONSTRUCTION SIGN, B	6.000	EACH
58 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
59 801-07118	BARRICADE, III-A	24.000	LFT
60 801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	250.000	LFT
61 801-08508	TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	302.000	LFT
62 801-53072	TEMPORARY TRAFFIC SIGNAL	LUMP	LUMP
63 808-01428	TEMPORARY TRANSVERSE MARKINGS, WHITE, STOP LINE, 24 IN	24.000	LFT
64 808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,228.000	LFT
65 808-06716	LINE, REMOVE	1,739.000	LFT
66 808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	391.000	LFT
67 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	3.000	EACH
68 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	3.000	EACH

CALL ORDER : 231

CONTRACT ID : R -31894-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITIES, ENHANCEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	686.100	CYS
10	205-02234 TEMPORARY EROSION AND SEDIMENT CONTROL, CULVERT PIPE	1.000	EACH
11	205-06933 TEMPORARY INLET PROTECTION	1.000	EACH
12	205-06937 TEMPORARY SILT FENCE	1,359.000	LFT
13	205-09543 NO 2 STONE	100.000	TON
14	205-11587 TEMPORARY GEOTEXTILE	235.000	SYS
15	206-51220 EXCAVATION, WET	130.000	CYS
16	206-51225 EXCAVATION, DRY	152.000	CYS
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	817.200	SYS
18	211-02050 B BORROW	61.000	CYS
19	211-06467 AGGREGATE FOR END BENT BACKFILL	117.000	CYS
20	211-09266 STRUCTURAL BACKFILL, TYPE 3	154.000	CYS
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	21.800	TON
22	303-04470 CRUSHED STONE, 11	4.200	TON
23	402-07432 HMA SURFACE, TYPE A	74.800	TON
24	402-07435 HMA INTERMEDIATE, TYPE A	149.600	TON
25	402-07440 HMA BASE, TYPE A	26.400	TON
26	406-05520 ASPHALT FOR TACK COAT	0.360	TON
27	603-01932 FENCE, CHAIN LINK, 96 IN	55.000	LFT
28	603-03692 FENCE, WOOD,	103.300	LFT
29	604-06070 SIDEWALK, CONCRETE	316.700	SYS
30	604-07894 CURB RAMP, CONCRETE, A	7.000	SYS
31	604-92237 HAND RAIL, STEEL	114.000	LFT
32	616-02320 GEOTEXTILES	145.700	SYS
33	616-06405 RIPRAP, REVETMENT	96.000	TON
34	618-03812 BENCH	1.000	EACH
35	621-04978 SEED MIXTURE	1,786.700	SYS
36	621-06570 TOPSOIL	8.200	CYS
37	621-06575 SODDING, NURSERY	17.800	SYS
38	621-07643 TREE PROTECTION	7.000	EACH
39	622-05748 TIMBER	600.000	LFT
40	625-09373 GABIONS, METALLIC COATED	134.500	CYS
41	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
42	628-09402 FIELD OFFICE, B	9.000	MOS
43	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	9.000	MOS
44	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	9.000	MOS
45	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
46	702-51005 CONCRETE, A, SUBSTRUCTURE	26.200	CYS
47	702-51015 CONCRETE, B, FOOTINGS	16.800	CYS
48	703-06028 REINFORCING BARS	4,322.000	LBS
49	703-06029 REINFORCING BARS, EPOXY COATED	600.000	LBS

CALL ORDER : 231

CONTRACT ID : R -31894-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BIKE/PEDESTRIAN FACILITIES, ENHANCEMENT		
50 704-51002	CONCRETE, C, SUPERSTRUCTURE	9.700	CYS
51 707-08458	STRUCTURAL MEMBERS	43.330	SFT
52 709-51821	SURFACE SEAL	LUMP	LUMP
53 712-06852	BOARDWALK	675.000	SFT
54 712-08257	PREFABRICATED	LUMP	LUMP
55 712-09730	BOARDWALK	265.500	LFT
56 712-09730	BOARDWALK	80.900	LFT
57 715-05169	PIPE, TYPE 3 CIRCULAR 15 IN	14.300	LFT
58 715-46005	PIPE END SECTION, DIA 15"	1.000	EACH
59 720-44000	CASTING, ADJUST TO GRADE	1.000	EACH
60 720-45410	MANHOLE, C4	1.000	EACH
61 801-03290	CONSTRUCTION SIGN, C	3.000	EACH
62 801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.000	EACH
63 801-06640	CONSTRUCTION SIGN, A	6.000	EACH
64 801-06710	FLASHING ARROW SIGN	20.000	DAY
65 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP
66 801-07119	BARRICADE, III-B	36.000	LFT
67 801-92448	CONSTRUCTION SIGNS, MOBILE	40.000	DAY
68 802-03896	BOLLARD	4.000	EACH
69 802-03896	BOLLARD	6.000	EACH
70 802-04314	SIGN	1.000	EACH
71 802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	136.000	LFT
72 802-09840	SIGN, SHEET, WITH LEGEND 0.100 IN	87.520	SFT
73 808-03442	PAVEMENT MESSAGE MARKING, PAINT, BIKE SYMBOL	2.000	EACH
74 808-06609	PAVEMENT MESSAGE MARKING,	1.000	EACH
75 808-06609	PAVEMENT MESSAGE MARKING,	1.000	EACH
76 808-06609	PAVEMENT MESSAGE MARKING,	2.000	EACH
77 808-75035	LINE, PAINT, SOLID, WHITE, 24 IN	60.000	LFT

CALL ORDER : 241

CONTRACT ID : R -32610-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGHT DISTANCE IMPROVEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	113-01614 PARTNERING OVERHEAD	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
11	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	2,750.000	SFT
12	203-02000 EXCAVATION, COMMON	37,475.000	CYS
13	205-03371 SEDIMENT, REMOVE	569.000	CYS
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	460.000	TON
15	205-06933 TEMPORARY INLET PROTECTION	1.000	EACH
16	205-06936 TEMPORARY SEDIMENT TRAP	569.000	TON
17	207-08263 SUBGRADE TREATMENT, TYPE IA	10,873.000	SYS
18	207-08267 SUBGRADE TREATMENT, TYPE IIIA	379.000	SYS
19	211-09264 STRUCTURAL BACKFILL, TYPE 1	152.000	CYS
20	303-01180 COMPACTED AGGREGATE, NO. 53	3,601.000	TON
21	303-07449 COMPACTED AGGREGATE, NO. 73	37.000	TON
22	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
23	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	748.000	TON
24	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	2,299.000	TON
25	406-05520 ASPHALT FOR TACK COAT	2.500	TON
26	605-97937 CURB AND GUTTER, ROLL CURB	400.000	LFT
27	610-07486 HMA FOR APPROACHES, TYPE A	173.000	TON
28	610-07487 HMA FOR APPROACHES, TYPE B	105.000	TON
29	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
30	615-06490 RIGHT OF WAY MARKER	28.000	EACH
31	615-06505 MONUMENT, B	10.000	EACH
32	616-02320 GEOTEXTILES	1,467.000	SYS
33	616-05688 RIPRAP, CLASS 1	10.000	TON
34	616-06405 RIPRAP, REVETMENT	918.000	TON
35	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
36	621-06545 FERTILIZER	2.000	TON
37	621-06553 SEED MIXTURE, R	791.000	LBS
38	621-06557 SEED MIXTURE, T	698.000	LBS
39	621-06565 MULCHING MATERIAL	19.000	TON
40	621-06567 WATER	14.000	KGAL
41	621-06574 SODDING	3,281.000	SYS
42	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
43	628-09402 FIELD OFFICE, B	14.000	MOS
44	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	28.000	MOS
45	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
46	715-05032 PIPE, TYPE 2 CIRCULAR 15 IN	151.000	LFT
47	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	83.000	LFT
48	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	62.000	LFT
49	715-09064 VIDEO INSPECTION FOR PIPE	50.000	LFT

SCHEDULE OF PAY ITEMS

PAGE 9

CALL ORDER : 241

CONTRACT ID : R -32610-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGHT DISTANCE IMPROVEMENT		
50	715-46005 PIPE END SECTION, DIA 15"	5.000	EACH
51	715-46020 PIPE END SECTION, DIA 24"	2.000	EACH
52	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
53	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
54	801-06625 DETOUR ROUTE MARKER ASSEMBLY	35.000	EACH
55	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
56	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
57	801-07119 BARRICADE, III-B	90.000	LFT
58	801-99182 TEMPORARY CHANGEABLE MESSAGE SIGN, INSTALL AND MAINTAIN	2.000	EACH
59	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	18.000	LFT
60	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	2.000	EACH
61	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	5,612.000	LFT
62	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	5,656.000	LFT
63	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	67.000	LFT
64	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	68.000	EACH

CALL ORDER : 381

CONTRACT ID : RS-31388-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	1,428.000	SYS
12	202-02273 CENTER CURB, CONCRETE, REMOVE	51.000	SYS
13	202-02676 TRANSPORTATION OF SALVAGEABLE MILLED MATERIAL	3,000.000	TON
14	202-05545 REGULATED MATERIALS, DISPOSE, C	20.000	CYS
15	202-05550 REGULATED MATERIALS, REMOVE, C	20.000	CYS
16	202-05555 REGULATED MATERIALS, TRANSPORT, C	20.000	CYS
17	202-07603 TESTING FOR WASTES, C	5.000	EACH
18	202-86946 HANDHOLE, REMOVE	1.000	EACH
19	202-90277 DETECTOR HOUSING, REMOVE	163.000	EACH
20	202-93741 GUARDRAIL END TREATMENT, REMOVE	2.000	EACH
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	227.000	TON
22	304-07783 HMA PATCHING, TYPE D	1,100.000	TON
23	304-07783 HMA PATCHING, TYPE D	540.000	TON
24	306-08034 MILLING, ASPHALT, 1 1/2 IN	436,704.000	SYS
25	306-08432 MILLING, APPROACH	35,758.000	SYS
26	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	32,358.000	TON
27	401-10258 JOINT ADHESIVE, SURFACE	246,613.000	LFT
28	402-07784 HMA SURFACE, TYPE D	3,463.000	TON
29	406-05520 ASPHALT FOR TACK COAT	122.000	TON
30	601-09238 HAND DIG GUARDRAIL POST HOLES	8.000	EACH
31	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
32	604-06070 SIDEWALK, CONCRETE	70.000	SYS
33	604-07900 CURB RAMP, CONCRETE, F	44.000	SYS
34	604-07900 CURB RAMP, CONCRETE, F	152.000	SYS
35	604-07901 CURB RAMP, CONCRETE, G	10.000	SYS
36	604-07902 CURB RAMP, CONCRETE, H	38.000	SYS
37	605-06120 CURB, CONCRETE	15.000	LFT
38	605-06215 CENTER CURB, D, CONCRETE	160.000	LFT
39	605-06255 CENTER CURB, D, CONCRETE	43.000	SYS
40	610-07788 HMA FOR APPROACHES, TYPE D	2,952.000	TON
41	615-06520 MONUMENT, RE-ESTABLISH	1.000	EACH
42	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
43	628-09402 FIELD OFFICE, B	14.000	MOS
44	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	28.000	MOS
45	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	48.000	MOS
46	628-11066 RADIO	4.000	EACH
47	628-11068 CELLULAR TELEPHONE/RADIO	4.000	EACH
48	628-11071 RADIO ONLY SERVICE	48.000	MOS
49	720-44000 CASTING, ADJUST TO GRADE	25.000	EACH

CALL ORDER : 381

CONTRACT ID : RS-31388-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
50	720-44000 CASTING, ADJUST TO GRADE	25.000	EACH
51	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	10.000	LFT
52	720-45615 STRUCTURE, INLET, RECONSTRUCTED	10.000	LFT
53	720-94840 CASTING, WATER VALVE, ADJUST TO GRADE	25.000	EACH
54	801-03290 CONSTRUCTION SIGN, C	15.000	EACH
55	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	52,359.000	LFT
56	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	52,359.000	LFT
57	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	3,927.000	LFT
58	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	3,927.000	LFT
59	801-06640 CONSTRUCTION SIGN, A	130.000	EACH
60	801-06710 FLASHING ARROW SIGN	300.000	DAY
61	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
62	801-92448 CONSTRUCTION SIGNS, MOBILE	1,800.000	DAY
63	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	29.000	LFT
64	802-07060 SIGN, SHEET, RELOCATE	3.000	EACH
65	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	4.000	SFT
66	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
67	805-01843 SIGNAL HANDHOLE ADJUST TO GRADE	2.000	EACH
68	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	442.000	LFT
69	805-04952 CONTROLLER AND CABINET	1.000	EACH
70	805-78445 SIGNAL SERVICE	1.000	EACH
71	805-78467 SIGNAL CABLE, 3C/8GA	50.000	LFT
72	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	71,745.000	LFT
73	805-78485 SIGNAL CABLE, 5C/14GA	110.000	LFT
74	805-78490 SIGNAL CABLE, 7C/14GA	1,352.000	LFT
75	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	6,764.000	LFT
76	805-78785 SIGNAL DETECTOR HOUSING	171.000	EACH
77	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	24,874.000	LFT
78	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
79	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
80	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	31,419.000	LFT
81	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	124,304.000	LFT
82	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	98,176.000	LFT
83	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	2,882.000	LFT
84	808-10037 LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	9,313.000	LFT
85	808-10058 LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN	1,890.000	LFT
86	808-11481 LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	694.000	LFT
87	808-11548 LINE MULTI-COMPONENT DOTTED YELLOW 4"	454.000	LFT
88	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	759.000	LFT
89	808-75272 TRANSVERSE MARKING, THERMOPLASTIC,	341.000	LFT
90	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	3,927.000	LFT
91	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	543.000	LFT
92	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	272.000	EACH
93	808-75340 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
94	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	488.000	EACH
95	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	488.000	EACH

CALL ORDER : 411

CONTRACT ID : RS-34794-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SURFACE TREATMENT, ULTRATHIN BONDED WEARING COURSE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	306-08034 MILLING, ASPHALT, 1 1/2 IN	3,200.000	SYS
10	306-08043 MILLING, TRANSITION	1,660.000	SYS
11	402-07434 HMA SURFACE, TYPE C	275.000	TON
12	406-05520 ASPHALT FOR TACK COAT	1.000	TON
13	408-07504 CRACKS AND JOINTS IN ASPHALT PAVEMENT, SEAL	7.000	TON
14	412-09355 FOG SEAL	98,287.000	SYS
15	414-11468 ULTRATHIN BONDED WEARING COURSE, 9.5 mm	250,177.000	SYS
16	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
17	628-09402 FIELD OFFICE, B	9.000	MOS
18	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	18.000	MOS
19	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
20	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	42.000	EACH
21	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
22	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	7,600.000	LFT
23	801-06640 CONSTRUCTION SIGN, A	31.000	EACH
24	801-06710 FLASHING ARROW SIGN	80.000	DAY
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
26	808-05866 PAVEMENT MESSAGE MARKING, REMOVE	128.100	SYS
27	808-06368 TRANSVERSE MARKING, REMOVE	262.000	LFT
28	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	18,560.000	LFT
29	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	90,478.000	LFT
30	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	903.000	LFT
31	808-06716 LINE, REMOVE	184,179.000	LFT
32	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
33	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	74,238.000	LFT
34	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	40.000	LFT
35	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	262.000	LFT
36	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	68.000	EACH
37	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,384.000	EACH
38	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,384.000	EACH

CALL ORDER : 461

CONTRACT ID : B -30912-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09542 UTILITY RELOCATION ENGINEERING	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	665.000	m3
12	203-02040 EXCAVATION, Y	305.000	m3
13	203-02070 BORROW	4,670.000	m3
14	203-51223 EXCAVATION, WATERWAY	305.000	m3
15	205-03371 SEDIMENT, REMOVE	23.000	m3
16	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	30.000	Mg
17	205-06934 TEMPORARY MULCH	1.000	Mg
18	205-06936 TEMPORARY SEDIMENT TRAP	18.000	Mg
19	205-06937 TEMPORARY SILT FENCE	495.000	m
20	206-51215 EXCAVATION, X	137.000	m3
21	206-51220 EXCAVATION, WET	25.000	m3
22	207-08266 SUBGRADE TREATMENT, TYPE III	3,762.000	m2
23	211-06467 AGGREGATE FOR END BENT BACKFILL	44.000	m3
24	211-09264 STRUCTURAL BACKFILL, TYPE 1	14.000	m3
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,889.000	Mg
26	302-07455 DENSE GRADED SUBBASE	19.000	m3
27	402-07432 HMA SURFACE, TYPE A	228.000	Mg
28	402-07435 HMA INTERMEDIATE, TYPE A	385.000	Mg
29	406-05521 ASPHALT FOR TACK COAT	2,979.000	m2
30	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
31	601-06037 GUARDRAIL END TREATMENT, I	3.000	EACH
32	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
33	601-99105 GUARDRAIL, W-BEAM, 1.905 m SPACING	44.000	m
34	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 250 mm	124.000	m2
35	610-07486 HMA FOR APPROACHES, TYPE A	121.000	Mg
36	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
37	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
38	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
39	616-02320 GEOTEXTILES	1,357.000	m2
40	616-06405 RIPRAP, REVETMENT	854.000	Mg
41	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
42	621-01956 SEED MIXTURE, LEGUME, 1	12.000	kg
43	621-02770 EROSION CONTROL BLANKET	2,621.000	m2
44	621-03909 SEED MIXTURE, NATIVE	7.000	kg
45	621-06545 FERTILIZER	1.000	Mg
46	621-06553 SEED MIXTURE, R	42.000	kg
47	621-06557 SEED MIXTURE, T	42.000	kg
48	621-06565 MULCHING MATERIAL	2.000	Mg
49	621-06567 WATER	18.000	kL

CALL ORDER : 461

CONTRACT ID : B -30912-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-06575 SODDING, NURSERY	978.000	m2
51	622-52436 SIGN, DO NOT MOW OR SPRAY	7.000	EACH
52	622-91786 SEEDLING	204.000	EACH
53	622-98200 SIGN, DO NOT DISTURB	8.000	EACH
54	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
55	628-09401 FIELD OFFICE, A	10.000	MOS
56	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	10.000	MOS
57	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
58	702-51005 CONCRETE, A, SUBSTRUCTURE	83.700	m3
59	702-51015 CONCRETE, B, FOOTINGS	126.800	m3
60	703-06028 REINFORCING BARS	13,823.000	kg
61	703-06029 REINFORCING BARS, EPOXY COATED	22,198.000	kg
62	704-51002 CONCRETE, C, SUPERSTRUCTURE	147.600	m3
63	706-06344 RAILING, STEEL TS-1	127.000	m
64	707-05984 STRUCTURAL MEMBER, CONCRETE I-BEAM, 1143 mm X 406 mm	256.000	m
65	709-51821 SURFACE SEAL	LUMP	LUMP
66	715-02048 MISC EQUIPMENT FOR WATER RELOCATION/ADJ	LUMP	LUMP
67	715-02185 WATER SERVICE LINE, 37.5 mm	19.000	m
68	715-05169 PIPE, TYPE 3 CIRCULAR 375 mm	28.500	m
69	715-46005 PIPE END SECTION, 375 mm	4.000	EACH
70	716-04832 PIPE CASING	15.000	m
71	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
72	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
73	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
74	801-07119 BARRICADE, III-B	21.600	m
75	802-09838 SIGN, SHEET, WITH LEGEND 2.03mm THICKNESS	2.300	m2
76	802-76055 SIGN POST, A	17.900	m