

CALL ORDER : 121

CONTRACT ID : IR-33066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD CONSTRUCTION - COMMON			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
4	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	36,111.000	SYS
12	202-02272 PAVED SIDE DITCH, REMOVE	2,369.000	LFT
13	202-02637 PIPE, ABANDON AND GROUT FILL	589.000	LFT
14	202-02859 GRATED BOX END SECTION, REMOVE	1.000	EACH
15	202-02928 CATCH BASIN, REMOVE	3.000	EACH
16	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
17	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
18	202-51368 SLOPEWALL, REMOVE	575.000	SYS
19	202-62420 BRIDGE RAILING, REMOVE	516.000	LFT
20	202-74055 OVERHEAD SIGN STRUCTURE, BOX	4.000	EACH
21	202-74080 OVERHEAD SIGN STRUCTURE,	5.000	EACH
22	202-74095 BRIDGE BRACKET ASSEMBLY, REMOVE	11.000	EACH
23	202-82065 SIGN CIRCUITRY, BOX TRUSS, REMOVE	6.000	EACH
24	202-82066 SIGN CIRCUITRY, CANTILEVER, REMOVE	6.000	EACH
25	202-82067 SIGN CIRCUITRY, BRIDGE BRACKET, REMOVE	2.000	EACH
26	202-86946 HANDHOLE, REMOVE	7.000	EACH
27	202-91385 INLET, REMOVE	5.000	EACH
28	202-91840 FENCE, CHAIN LINK, REMOVE	3,049.000	LFT
29	202-93615 CONCRETE, REMOVE	152.000	SYS
30	202-93741 GUARDRAIL END TREATMENT, REMOVE	1.000	EACH
31	202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE	11.000	EACH
32	202-94954 BARRIER WALL, CONCRETE, REMOVE	5,718.000	LFT
33	202-95027 IMPACT ATTENUATOR, REMOVE	1.000	EACH
34	202-95579 SERVICE POINT, REMOVE	1.000	EACH
35	202-96022 CONCRETE FOUNDATION, REMOVE	5.000	EACH
36	202-96133 PIPE, REMOVE	2,379.000	LFT
37	202-99187 FENCE, FARM FIELD, REMOVE	144.000	LFT
38	203-02000 EXCAVATION, COMMON	2,321.000	CYS
39	203-02070 BORROW	4,206.000	CYS
40	205-03371 SEDIMENT, REMOVE	3,914.000	CYS
41	205-06930 SPLASHPAD	7.500	TON
42	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	406.000	TON
43	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	346.000	TON
44	205-06933 TEMPORARY INLET PROTECTION	132.000	EACH
45	205-06934 TEMPORARY MULCH	200.400	TON
46	205-06935 TEMPORARY SEDIMENT BASIN	2.000	EACH
47	205-06936 TEMPORARY SEDIMENT TRAP	1,307.000	TON
48	205-06937 TEMPORARY SILT FENCE	24,158.000	LFT
49	205-06938 TEMPORARY SLOPE DRAIN	652.000	LFT

CALL ORDER : 121

CONTRACT ID : IR-33066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION - COMMON		
50	205-09543 NO 2 STONE	200.000	TON
51	205-11584 TEMPORARY CHECK DAM, TRAVERSABLE	195.000	LFT
52	205-11585 TEMPORARY FILTER BERM	335.000	LFT
53	205-11586 TEMPORARY FILTER STONE	22.500	TON
54	205-11587 TEMPORARY GEOTEXTILE	2,792.000	SYS
55	205-11591 TEMPORARY SEED MIXTURE	11,995.000	LBS
56	206-51220 EXCAVATION, WET	84.000	CYS
57	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	3,855.000	CYS
58	206-51817 SHEET PILING, STEEL	942.000	SFT
59	207-08263 SUBGRADE TREATMENT, TYPE IA	120,651.000	SYS
60	207-08267 SUBGRADE TREATMENT, TYPE IIIA	21,533.000	SYS
61	208-02046 GRADING IN GORE AREA	5.000	EACH
62	211-02050 B BORROW	12,846.000	CYS
63	211-06467 AGGREGATE FOR END BENT BACKFILL	8.000	CYS
64	211-09264 STRUCTURAL BACKFILL, TYPE 1	11,446.000	CYS
65	211-09266 STRUCTURAL BACKFILL, TYPE 3	32,381.000	CYS
66	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	9.000	CYS
67	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	6,293.000	TON
68	302-07455 DENSE GRADED SUBBASE	257.000	CYS
69	302-08562 COARSE AGGREGATE, NO 8	3,167.000	TON
70	303-01180 COMPACTED AGGREGATE, NO. 53	263.000	TON
71	306-08034 MILLING, ASPHALT, 1 1/2 IN	73.000	SYS
72	306-08039 MILLING, ASPHALT REMOVAL	2,231.000	SYS
73	306-08041 MILLING, PCCP	26,736.000	SYS
74	306-08043 MILLING, TRANSITION	484.000	SYS
75	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
76	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	1,072.000	TON
77	401-07399 QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	1,799.000	TON
78	401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM	4,163.000	TON
79	401-10258 JOINT ADHESIVE, SURFACE	1,518.000	LFT
80	401-10259 JOINT ADHESIVE, INTERMEDIATE	1,458.000	LFT
81	402-07433 HMA SURFACE, TYPE B	5.000	TON
82	402-07434 HMA SURFACE, TYPE C	222.000	TON
83	402-07438 HMA INTERMEDIATE, TYPE B	44.000	TON
84	402-07439 HMA INTERMEDIATE, TYPE C	361.000	TON
85	402-07442 HMA BASE, TYPE C	497.000	TON
86	402-10087 HMA FOR TEMPORARY PAVEMENT, D	9,506.000	TON
87	406-05520 ASPHALT FOR TACK COAT	2.000	TON
88	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
89	501-06727 CORING, PCCP	LUMP	LUMP
90	501-06914 QC/QA PCCP	26,736.000	SYS
91	503-05310 TERMINAL JOINT	112.000	LFT
92	503-09261 PCCP STITCHING	3,975.000	EACH
93	506-06333 PCCP PATCHING, FULL DEPTH	102.000	SYS
94	507-07505 RETROFIT LOAD TRANSFER	2,678.000	EACH
95	601-01522 GUARDRAIL, TRANSITION TYPE TGB	36.000	EACH
96	601-01848 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 5	1.000	EACH
97	601-02241 GUARDRAIL, REMOVE	9,175.000	LFT
98	601-02625 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 2, MODIFIED	1.000	EACH

CALL ORDER : 121

CONTRACT ID : IR-33066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION - COMMON		
99	601-02625 GUARDRAIL CONNECTOR SYSTEM, W BEAM, CURVED, 2, MODIFIED	1.000	EACH
100	601-05071 GUARDRAIL TERMINAL SYSTEM, W-BEAM, CURVED, 7	1.000	EACH
101	601-06035 GUARDRAIL, RESET	1,754.000	LFT
102	601-06037 GUARDRAIL END TREATMENT, I	1.000	EACH
103	601-06854 GUARDRAIL, W-BEAM, NESTED	3.000	EACH
104	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	16.000	EACH
105	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	16.000	EACH
106	601-08435 GUARDRAIL END TREATMENT, TYPE MS, SPARE PARTS	1.000	EACH
107	601-08436 GUARDRAIL END TREATMENT, TYPE MS, SPARE PARTS	1.000	EACH
108	601-09149 IMPACT ATTENUATOR, CR1, W1, TL-3	1.000	EACH
109	601-94689 GUARDRAIL END TREATMENT, OS	16.000	EACH
110	601-94690 GUARDRAIL END TREATMENT, MS	1.000	EACH
111	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	20,023.750	LFT
112	601-99123 GUARDRAIL, TRANSITION, GP	1.000	EACH
113	601-99132 GUARDRAIL, TRANSITION, VH, 6 FT-3 IN SPACING	7.000	EACH
114	602-02098 MEDIAN BARRIER RAIL TRANSITION	10.000	EACH
115	602-06729 BARRIER DELINEATOR	674.000	EACH
116	602-08603 CONCRETE BARRIER, 45 IN	3,520.000	LFT
117	602-08604 CONCRETE BARRIER, 45 IN, MODIFIED	3,701.000	LFT
118	603-06040 FENCE, FARM FIELD, 47 IN	93.000	LFT
119	603-92636 FENCE, CHAIN LINK, 72 IN	3,093.000	LFT
120	605-05523 CURB, HMA	52.000	LFT
121	607-06335 PAVED SIDE DITCH, A	5,961.000	LFT
122	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	769.400	SYS
123	609-06260 REINFORCED CONCRETE BRIDGE APPROACH, 13 IN	66.000	SYS
124	610-07487 HMA FOR APPROACHES, TYPE B	185.000	TON
125	615-06505 MONUMENT, B	2.000	EACH
126	615-06510 MONUMENT, C	22.000	EACH
127	616-02320 GEOTEXTILES	8,468.000	SYS
128	616-05688 RIPRAP, CLASS 1	227.000	TON
129	616-05689 RIPRAP, CLASS 2	34.000	TON
130	616-06405 RIPRAP, REVETMENT	4,801.000	TON
131	616-06451 RIPRAP, UNIFORM	51.000	TON
132	616-51367 SLOPEWALL, CONCRETE, 4 IN	21.000	SYS
133	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.000	EACH
134	621-01597 EROSION CONTROL, MAT	81.000	SYS
135	621-02770 EROSION CONTROL BLANKET	80,534.000	SYS
136	621-06545 FERTILIZER	26.300	TON
137	621-06554 SEED MIXTURE, U	6,579.000	LBS
138	621-06560 MULCHED SEEDING, U	3,810.000	SYS
139	621-06565 MULCHING MATERIAL	119.200	TON
140	621-06567 WATER	104.000	KGAL
141	621-06574 SODDING	26,421.000	SYS
142	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	5.000	EACH
143	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
144	628-09403 FIELD OFFICE, C	24.000	MOS
145	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
146	628-11069 CELLULAR TELEPHONE/RADIO SERVICE, ANYTIME MINUTES	48.000	MOS
147	701-02936 PILE, STEEL H, HP 14 IN X 89	966.000	LFT

CALL ORDER : 121

CONTRACT ID : IR-33066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD CONSTRUCTION - COMMON			
148	701-06011 DYNAMIC PILE LOAD TEST	4.000	EACH
149	701-09557 TEST PILE, DYNAMIC, PRODUCTION	311.000	LFT
150	701-09559 TEST PILE, DYNAMIC, RESTRIKE	4.000	EACH
151	701-09684 PILE SHOE, HP 14 X 89	15.000	EACH
152	701-09739 PILE SHOE, HP 12 X 53	16.000	EACH
153	701-09770 PILE SHOE, HP 14 X 73	24.000	EACH
154	701-51195 PILE, STEEL H, HP 12 IN X 53	795.000	LFT
155	701-93575 PILE, STEEL H, HP 14 IN X 73	1,622.000	LFT
156	702-04325 TEMPORARY SHORING	LUMP	LUMP
157	702-44240 CONCRETE, A, STRUCTURES	1,267.500	CYS
158	702-51005 CONCRETE, A, SUBSTRUCTURE	142.300	CYS
159	702-51015 CONCRETE, B, FOOTINGS	999.300	CYS
160	702-51863 FIELD DRILLED HOLE IN CONCRETE	620.000	EACH
161	702-92857 CONCRETE, C, SUBSTRUCTURE	54.800	CYS
162	703-01540 THREADED TIE BAR ASSEMBLY	336.000	EACH
163	703-06028 REINFORCING BARS	71,978.000	LBS
164	703-06029 REINFORCING BARS, EPOXY COATED	499,601.000	LBS
165	704-51002 CONCRETE, C, SUPERSTRUCTURE	570.700	CYS
166	704-51106 DECK DRAIN	17.000	EACH
167	706-06351 CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.000	EACH
168	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	1,692.000	SYS
169	706-08500 REINFORCED CONCRETE MOMENT SLAB, 14 IN	1,535.000	SYS
170	706-09545 COARSE AGGREGATE, NO 8	10.000	CYS
171	706-09959 RAILING, CONCRETE, FT	208.000	LFT
172	706-09959 RAILING, CONCRETE, FT	227.000	LFT
173	706-09962 RAILING, CONCRETE, PF-1	579.500	LFT
174	706-11404 RAILING, STEEL, PF-1	596.800	LFT
175	706-11601 RAILING, CONCRETE, FT	3,738.300	CYS
176	706-11621 CONCRETE BRIDGE RAILING TRANSITION, TFT	28.000	EACH
177	706-11621 CONCRETE BRIDGE RAILING TRANSITION, TFT	4.000	EACH
178	709-51821 SURFACE SEAL	LUMP	LUMP
179	709-51821 SURFACE SEAL	LUMP	LUMP
180	709-51821 SURFACE SEAL	LUMP	LUMP
181	709-51821 SURFACE SEAL	LUMP	LUMP
182	709-51821 SURFACE SEAL	LUMP	LUMP
183	709-51821 SURFACE SEAL	LUMP	LUMP
184	710-09158 PATCHING CONCRETE STRUCTURES	30.000	SFT
185	711-51038 STRUCTURAL STEEL	LUMP	LUMP
186	715-03025 SANITARY MANHOLE	1.000	EACH
187	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	104.000	LFT
188	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	148.000	LFT
189	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	91,996.000	LFT
190	715-05052 PIPE, TYPE 4 CIRCULAR 12 IN	444.000	LFT
191	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	7,133.000	LFT
192	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	108.000	LFT
193	715-05141 PIPE, TYPE 1 CIRCULAR 84 IN	322.000	LFT
194	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,630.000	LFT
195	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	2,085.000	LFT
196	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	1,447.000	LFT

CALL ORDER : 121

CONTRACT ID : IR-33066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD CONSTRUCTION - COMMON			
197	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	2,311.000	LFT
198	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	601.000	LFT
199	715-05162 PIPE, TYPE 2 CIRCULAR 54 IN	246.000	LFT
200	715-05163 PIPE, TYPE 2 CIRCULAR 60 IN	236.000	LFT
201	715-05239 PIPE, TYPE 1 DEFORMED MIN AREA 7.4 SFT	125.000	LFT
202	715-05407 PIPE, END BENT DRAIN, 6 IN	70.000	LFT
203	715-05415 PIPE SANITARY SEWER 24 IN	488.000	LFT
204	715-05422 PIPE, SLOTTED DRAIN, 12 IN	3,720.000	LFT
205	715-05423 PIPE, SLOTTED DRAIN, 15 IN	940.000	LFT
206	715-05424 PIPE, SLOTTED DRAIN, 18 IN	520.000	LFT
207	715-05595 PIPE EXTENSION, CIRCULAR 15 IN	35.000	LFT
208	715-05596 PIPE EXTENSION, CIRCULAR 18 IN	53.000	LFT
209	715-05756 PIPE EXTENSION, CIRCULAR 12 IN	73.000	LFT
210	715-05841 CONCRETE ANCHOR 60 IN	2.000	EACH
211	715-05842 CONCRETE ANCHOR 42 IN	2.000	EACH
212	715-05889 PIPE EXTENSION, CIRCULAR 30 IN	20.000	LFT
213	715-05890 PIPE EXTENSION, CIRCULAR 42 IN	25.000	LFT
214	715-05908 PIPE EXTENSION, CIRCULAR, 60 IN	8.000	LFT
215	715-06398 CONCRETE ANCHOR, MIN AREA 6.4 SF	4.000	EACH
216	715-06939 CONCRETE ANCHOR MIN AREA 29.5 SFT	2.000	EACH
217	715-07150 CONCRETE ANCHOR 84 IN	2.000	EACH
218	715-08069 CONCRETE ANCHOR MIN AREA 5.1 SFT	5.000	EACH
219	715-09064 VIDEO INSPECTION FOR PIPE	8,998.000	LFT
220	715-09064 VIDEO INSPECTION FOR PIPE	923.000	LFT
221	715-09064 VIDEO INSPECTION FOR PIPE	923.000	LFT
222	715-09843 BYPASS PUMPING	LUMP	LUMP
223	715-09843 BYPASS PUMPING	LUMP	LUMP
224	715-09843 BYPASS PUMPING	LUMP	LUMP
225	715-09843 BYPASS PUMPING	LUMP	LUMP
226	715-09843 BYPASS PUMPING	LUMP	LUMP
227	715-09992 PIPE, TYPE 1 DEFORMED MIN AREA 29.5 SFT	120.000	LFT
228	715-11739 GRATED BOX END SECTION II, 10:1 MIN AREA 6.4 SFT	1.000	EACH
229	715-11745 PIPE EXTENSION, DEFORMED MIN AREA 6.4 SFT	90.000	LFT
230	715-46000 PIPE END SECTION, DIA 12"	15.000	EACH
231	715-46005 PIPE END SECTION, DIA 15"	9.000	EACH
232	715-46010 PIPE END SECTION, DIA 18"	4.000	EACH
233	715-46015 PIPE END SECTION, DIA 21"	1.000	EACH
234	715-46020 PIPE END SECTION, DIA 24"	4.000	EACH
235	715-46030 PIPE END SECTION, DIA 30"	1.000	EACH
236	715-46040 PIPE END SECTION, DIA 36 IN	3.000	EACH
237	716-07630 PIPE INSTALLATION, TRENCHLESS, 12 IN	113.000	LFT
238	716-07631 PIPE INSTALLATION, TRENCHLESS, 15 IN	24.000	LFT
239	716-07632 PIPE INSTALLATION, TRENCHLESS, 18 IN	84.000	LFT
240	716-07654 PIPE INSTALLATION, TRENCHLESS, 6 IN	417.000	LFT
241	716-09396 PIPE INSTALLATION, TRENCHLESS, 2 IN	220.000	LFT
242	716-09631 PIPE INSTALLATION, TRENCHLESS, 21 IN	84.000	LFT
243	716-11716 PIPE INSTALLATION, TRENCHLESS,	24.000	LFT
244	718-06528 OUTLET PROTECTOR, 1	43.000	EACH
245	718-06529 OUTLET PROTECTOR, 2	53.000	EACH

CALL ORDER : 121

CONTRACT ID : IR-33066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION - COMMON		
246	718-06531 OUTLET PROTECTOR, 3	35.000	EACH
247	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	10,000.000	LFT
248	718-52610 AGGREGATE FOR UNDERDRAINS	7,883.000	CYS
249	718-99153 GEOTEXTILES FOR UNDERDRAIN	82,092.000	SYS
250	720-03194 MANHOLE	1.000	EACH
251	720-03988 MANHOLE, J4, DROP	3.000	EACH
252	720-07299 INLET, H	3.000	EACH
253	720-07301 INLET, TYPE HA	25.000	EACH
254	720-07302 INLET, TYPE HA, WITH SLOTTED DRAIN	11.000	EACH
255	720-09079 INLET, HA5, MODIFIED	1.000	EACH
256	720-10114 SANITARY DROP MANHOLE	1.000	EACH
257	720-44000 CASTING, ADJUST TO GRADE	25.000	EACH
258	720-45030 INLET, E7	8.000	EACH
259	720-45035 INLET, F7	4.000	EACH
260	720-45040 INLET, G7	5.000	EACH
261	720-45069 INLET, P12	1.000	EACH
262	720-45130 INLET, E7, MODIFIED	10.000	EACH
263	720-45135 INLET, F7, MODIFIED	1.000	EACH
264	720-45140 INLET, G7, MODIFIED	1.000	EACH
265	720-45141 INLET, H5, MODIFIED	5.000	EACH
266	720-45265 PIPE CATCH BASIN, 15 IN	1.000	EACH
267	720-45275 PIPE CATCH BASIN, 24 IN	1.000	EACH
268	720-45410 MANHOLE, C4	2.000	EACH
269	720-45425 MANHOLE, F4	1.000	EACH
270	720-91110 MANHOLE, N4	1.000	EACH
271	720-93501 MANHOLE, L4	1.000	EACH
272	720-94612 MANHOLE, K4	1.000	EACH
273	720-95335 MANHOLE, M4	3.000	EACH
274	720-95422 MANHOLE, J4	1.000	EACH
275	720-98625 MANHOLE, C4, DROP	4.000	EACH
276	722-51842 BRIDGE DECK OVERLAY	2,478.000	SYS
277	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	15.200	CYS
278	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	1,400.000	SFT
279	722-60824 SURFACE MILLING	2,155.000	SYS
280	724-51927 STRUCTURAL EXPANSION JOINT, M	48.000	LFT
281	725-08293 PIPE LINER, CURED-IN-PLACE, 36 IN	923.000	LFT
282	731-93945 FACE PANELS, CONCRETE	33,209.000	SFT
283	731-93946 WALL ERECTION	33,209.000	SFT
284	731-93947 LEVELING PAD, CONCRETE	1,810.000	LFT
285	734-10240 CUT-WALL, NO.	1,781.000	SFT
286	734-10240 CUT-WALL, NO.	14,215.000	SFT
287	734-10240 CUT-WALL, NO.	2,343.000	SFT
288	734-10240 CUT-WALL, NO.	241.000	SFT
289	734-10240 CUT-WALL, NO.	922.000	SFT
290	734-10240 CUT-WALL, NO.	267.000	SFT
291	734-10240 CUT-WALL, NO.	680.000	SFT
292	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	46.000	EACH
293	801-03290 CONSTRUCTION SIGN, C	10.000	EACH
294	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH

CALL ORDER : 121

CONTRACT ID : IR-33066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD CONSTRUCTION - COMMON			
295	801-06201 TEMPORARY PANEL SIGNS	754.000	SFT
296	801-06202 TEMPORARY PANEL SIGN SUPPORTS	394.000	LFT
297	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	368,919.000	LFT
298	801-06625 DETOUR ROUTE MARKER ASSEMBLY	47.000	EACH
299	801-06640 CONSTRUCTION SIGN, A	130.000	EACH
300	801-06645 CONSTRUCTION SIGN, B	15.000	EACH
301	801-06710 FLASHING ARROW SIGN	945.000	DAY
302	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
303	801-07118 BARRICADE, III-A	132.000	LFT
304	801-07119 BARRICADE, III-B	48.000	LFT
305	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	42,350.000	LFT
306	801-08402 TEMPORARY TRAFFIC BARRIER, TYPE 3	270.000	LFT
307	801-08403 TEMPORARY TRAFFIC BARRIER, TYPE 4	2,020.000	LFT
308	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	3,120.000	LFT
309	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	12.000	EACH
310	802-02475 SIGN, PANEL, RELOCATE	4.000	EACH
311	802-04893 REFERENCE POST	74.000	EACH
312	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	224.750	LFT
313	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	534.500	LFT
314	802-06402 DYNAMIC MESSAGE SIGN	1.000	EACH
315	802-07057 SIGN, PANEL, WITH LEGEND	6,877.000	SFT
316	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	86.000	EACH
317	802-07060 SIGN, SHEET, RELOCATE	5.000	EACH
318	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	20.000	EACH
319	802-07152 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, X	4.000	EACH
320	802-07153 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XI	2.000	EACH
321	802-08456 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VIII	2.000	EACH
322	802-09221 OVERHEAD SIGN STRUCTURE,BOX TRUSS TYPE A	2.000	EACH
323	802-09221 OVERHEAD SIGN STRUCTURE,BOX TRUSS TYPE A	1.000	EACH
324	802-09224 OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE D	2.000	EACH
325	802-09225 OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE E	4.000	EACH
326	802-09536 BOX TRUSS SIGN STRUCTURE FOUNDATION, 45 IN.	5.000	EACH
327	802-09537 BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN.	11.000	EACH
328	802-09578 OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	1.000	EACH
329	802-09581 CANTILEVER SIGN SUPPORT FOUNDATION,	3.000	EACH
330	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	369.190	SFT
331	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	498.400	SFT
332	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	13.000	SFT
333	802-09861 OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE I	2.000	EACH
334	802-09898 BOX TRUSS SIGN STRUCTURE FOUNDATION, DMS, 36 IN HEIGHT	1.000	EACH
335	802-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	20.000	EACH
336	802-74050 SIGN, OVERHEAD, REMOVE	6.000	EACH
337	802-76095 STRUCTURAL STEEL, BREAKAWAY	7,500.000	LBS
338	804-06770 DELINEATOR POST	127.000	EACH
339	804-06771 DELINEATOR POST, FLEXIBLE	91.000	EACH
340	805-02262 FLASHER INSTALLATION	LUMP	LUMP
341	805-03793 DETECTOR CARD RACK AND DETECTOR MODULES	3.000	EACH
342	805-04973 CONDUIT	528.000	LFT
343	805-04973 CONDUIT	428.000	LFT

CALL ORDER : 121

CONTRACT ID : IR-33066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD CONSTRUCTION - COMMON		
344	805-06483 CONTROLLER	3.000	EACH
345	805-06595 CONDUIT, PVC, 2 IN	289.000	LFT
346	805-06616 PIEZO, CLASS II	16.000	EACH
347	805-09540 LOOP DETECTOR RACK	1.000	EACH
348	805-11540 MICROLOOP DETECTOR PROBE	12.000	EACH
349	805-78445 SIGNAL SERVICE	1.000	EACH
350	805-78467 SIGNAL CABLE, 3C/8GA	2,120.000	LFT
351	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	1,970.000	LFT
352	805-78480 SIGNAL CABLE, 3C/14GA	320.000	LFT
353	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	1,072.000	LFT
354	805-78785 SIGNAL DETECTOR HOUSING	12.000	EACH
355	805-78790 LOOP DETECTOR DELAY AMPLIFIER, 4 CHANNEL	2.000	EACH
356	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	996.000	LFT
357	807-01413 POWER DISCONNECT PLUG FOR HIGH MAST TOWER	12.000	EACH
358	807-01603 SERVICE POINT, TYPE II	2.000	EACH
359	807-02191 HANDHOLE, LIGHTING	4.000	EACH
360	807-02193 LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT	13.000	EACH
361	807-02194 SERVICE POINT, II, MODIFIED	1.000	EACH
362	807-02426 WIRE, THW, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	1,405.000	LFT
363	807-02603 LIGHT STANDARD, RELOCATE	1.000	EACH
364	807-02618 WIRE, NO 2 COPPER, 3 1/C	90.000	LFT
365	807-02781 LUMINAIRE, MAST ARM, 10 FT	4.000	EACH
366	807-02934 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING	1.000	EACH
367	807-03934 LIGHT STRUCTURE, REMOVE	5.000	EACH
368	807-04653 LIGHTING FOUNDATION,	9.000	EACH
369	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	17,100.000	LFT
370	807-78590 HANDHOLE	15.000	EACH
371	807-82360 LIGHT POLE, HIGH MAST, 120 FT E.M.H.	6.000	EACH
372	807-82400 LIGHT POLE, HIGH MAST, 125 FT E.M.H.	3.000	EACH
373	807-82480 LIGHT POLE, HIGH MAST, 135 FT E.M.H.	3.000	EACH
374	807-83648 LIGHT POLE, 36 FT E.M.H., 10.0 FT MAST ARM, ANCHOR BASE	9.000	EACH
375	807-85752 LIGHT POLE, 40 FT E.M.H., 10.0 FT MAST ARM, BREAKAWAY BASE	13.000	EACH
376	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	26.000	EACH
377	807-86665 LUMINAIRE, HIGH MAST, HIGH PRESSURE SODIUM, 1000 WATT	22.000	EACH
378	807-86830 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING, 4FT X 20FT	12.000	EACH
379	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	5,960.000	LFT
380	807-86910 CONNECTOR KIT, UNFUSED	22.000	EACH
381	807-86915 CONNECTOR KIT, FUSED	22.000	EACH
382	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	27.000	EACH
383	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	16.000	EACH
384	807-86930 INSULATION LINK, NON-WATERPROOFED	44.000	EACH
385	807-86935 INSULATION LINK, WATERPROOFED	16.000	EACH
386	807-86950 SIGN UNDERPASS AND ROADWAY LIGHTING LOCATION IDENTIFICATION	34.000	EACH
387	807-86955 CABLE-DUCT MARKER	14.000	EACH
388	807-87235 LUMINAIRE, HIGH MAST, HIGH PRESSURE SODIUM 1000 WATT	24.000	EACH
389	807-92155 WIRE, XHHW, NO 6 COPPER, 1/C	90.000	LFT
390	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,024.000	LFT
391	808-06716 LINE, REMOVE	90,535.000	LFT
392	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	686.000	LFT

CALL ORDER : 121

CONTRACT ID : IR-33066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD CONSTRUCTION - COMMON			
393	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	686.000 LFT
394	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	114.000 LFT
395	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	834.000 LFT
396	808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	47.000 LFT
397	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,800.000 EACH
398	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2,072.000 EACH
399	809-04652	SERVICE POINT	1.000 EACH
400	809-04652	SERVICE POINT	1.000 EACH
401	809-04652	SERVICE POINT	2.000 EACH
402	809-04982	CABLE	5,246.000 LFT
403	809-04989	POWER SUPPLY	1.000 EACH
404	809-09343	ITS	1.000 EACH
405	809-09343	ITS	1.000 EACH
406	809-09343	ITS	2.000 EACH
SECTION NO. 0002 ROAD CONSTRUCTION - PCCP			
407	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP LUMP
408	203-02000	EXCAVATION, COMMON	151,325.000 CYS
409	203-02070	BORROW	18,330.000 CYS
410	302-06464	SUBBASE FOR PCCP	22,802.000 CYS
411	303-01180	COMPACTED AGGREGATE, NO. 53	20,412.000 TON
412	401-07429	QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	1,872.000 TON
413	401-10258	JOINT ADHESIVE, SURFACE	7,666.000 LFT
414	401-10259	JOINT ADHESIVE, INTERMEDIATE	7,666.000 LFT
415	406-05520	ASPHALT FOR TACK COAT	26.000 TON
416	415-11527	BASE SEAL	12.000 TON
417	501-06325	QC/QA-PCCP, 14 IN	92,937.000 SYS
418	503-03489	RETROFITTED TIE BARS	12,323.000 EACH
419	503-05240	D-1 CONTRACTION JOINT	43,293.000 LFT
420	615-06505	MONUMENT, B	8.000 EACH
421	615-06515	MONUMENT, D	47.000 EACH
422	808-06702	LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	11,010.000 LFT
423	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,611.000 LFT
424	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	1,393.000 LFT
425	808-10032	LINE, MULTI-COMPONENT, DOTTED, WHITE, 8 IN	1,480.000 LFT
426	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	46,464.000 LFT
427	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	28,727.000 LFT
428	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	8,788.000 LFT
429	808-10038	TRANSVERSE MARKINGS MULTI-COMPONENT,	614.000 LFT
430	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	21,400.000 LFT
431	808-11478	LINE, THERMOPLASTIC, DOTTED, WHITE 8 IN	80.000 LFT
432	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	24,264.000 LFT
433	808-75272	TRANSVERSE MARKING, THERMOPLASTIC,	72.000 LFT
SECTION NO. 0003 ROAD CONSTRUCTION - HMA			
434	110-01001	MOBILIZATION AND DEMOBILIZATION	LUMP LUMP
435	203-02000	EXCAVATION, COMMON	132,835.000 CYS

CALL ORDER : 121

CONTRACT ID : IR-33066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 ROAD CONSTRUCTION - HMA			
436	203-02070 BORROW	46,945.000	CYS
437	302-06464 SUBBASE FOR PCCP	2,119.000	CYS
438	303-01180 COMPACTED AGGREGATE, NO. 53	18,028.000	TON
439	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	6,447.000	TON
440	401-07405 QC/QA-HMA, 5, 76, INTERMEDIATE, 19.0 mm	10,805.000	TON
441	401-07410 QC/QA-HMA, 5, 64, BASE, 25.0 mm	9,505.000	TON
442	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	16,658.000	TON
443	401-08365 QC/QA-HMA, 5, 64, BASE, 19.0 mm	21,473.000	TON
444	401-10258 JOINT ADHESIVE, SURFACE	44,600.000	LFT
445	401-10259 JOINT ADHESIVE, INTERMEDIATE	44,600.000	LFT
446	406-05520 ASPHALT FOR TACK COAT	104.000	TON
447	415-11527 BASE SEAL	86.000	TON
448	501-06325 QC/QA-PCCP, 14 IN	15,042.000	SYS
449	503-03489 RETROFITTED TIE BARS	2,589.000	EACH
450	503-05240 D-1 CONTRACTION JOINT	8,044.000	LFT
451	615-06505 MONUMENT, B	25.000	EACH
452	615-06515 MONUMENT, D	32.000	EACH
453	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	16,240.000	LFT
454	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	32,662.000	LFT
455	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	5,155.000	LFT
456	808-10032 LINE, MULTI-COMPONENT, DOTTED, WHITE, 8 IN	870.000	LFT
457	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	16,966.000	LFT
458	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	28,235.000	LFT
459	808-10037 LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	5,193.000	LFT
460	808-10038 TRANSVERSE MARKINGS MULTI-COMPONENT,	400.000	LFT
461	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	16,460.000	LFT
462	808-11478 LINE, THERMOPLASTIC, DOTTED, WHITE 8 IN	690.000	LFT
463	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	24,756.000	LFT
464	808-75272 TRANSVERSE MARKING, THERMOPLASTIC,	286.000	LFT
SECTION NO. 0004 NEW BRIDGE CONSTRUCTION - STEEL			
465	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	1,500.000	CYS
466	211-02050 B BORROW	755.000	CYS
467	701-02936 PILE, STEEL H, HP 14 IN X 89	12,307.000	LFT
468	701-06011 DYNAMIC PILE LOAD TEST	10.000	EACH
469	701-09557 TEST PILE, DYNAMIC, PRODUCTION	929.000	LFT
470	701-09559 TEST PILE, DYNAMIC, RESTRIKE	11.000	EACH
471	701-09684 PILE SHOE, HP 14 X 89	180.000	EACH
472	702-51005 CONCRETE, A, SUBSTRUCTURE	1,144.700	CYS
473	702-51015 CONCRETE, B, FOOTINGS	616.600	CYS
474	702-92857 CONCRETE, C, SUBSTRUCTURE	42.800	CYS
475	703-06028 REINFORCING BARS	259,555.000	LBS
476	703-06029 REINFORCING BARS, EPOXY COATED	1,217,180.000	LBS
477	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,885.000	CYS
478	711-51038 STRUCTURAL STEEL	LUMP	LUMP
SECTION NO. 0005 NEW BRIDGE CONSTRUCTION - CONCRETE			

CALL ORDER : 121

CONTRACT ID : IR-33066-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0005	NEW BRIDGE CONSTRUCTION - CONCRETE		
479	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	3,099.600	CYS
480	211-02050 B BORROW	1,711.800	CYS
481	701-02936 PILE, STEEL H, HP 14 IN X 89	21,821.300	LFT
482	701-06011 DYNAMIC PILE LOAD TEST	12.000	EACH
483	701-09557 TEST PILE, DYNAMIC, PRODUCTION	1,057.500	LFT
484	701-09559 TEST PILE, DYNAMIC, RESTRIKE	11.000	EACH
485	701-09684 PILE SHOE, HP 14 X 89	288.000	EACH
486	701-09770 PILE SHOE, HP 14 X 73	20.000	EACH
487	701-93575 PILE, STEEL H, HP 14 IN X 73	1,363.000	LFT
488	702-51005 CONCRETE, A, SUBSTRUCTURE	1,774.200	CYS
489	702-51015 CONCRETE, B, FOOTINGS	1,188.700	CYS
490	702-92857 CONCRETE, C, SUBSTRUCTURE	54.400	CYS
491	703-06028 REINFORCING BARS	406,685.000	LBS
492	703-06029 REINFORCING BARS, EPOXY COATED	1,138,931.000	LBS
493	704-51002 CONCRETE, C, SUPERSTRUCTURE	2,426.800	CYS
494	707-09598 STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 84 IN X 48 IN	8,617.500	LFT
495	711-51038 STRUCTURAL STEEL	LUMP	LUMP

CALL ORDER : 151

CONTRACT ID : R -29555-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN TRAIL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
11	202-52710 SIDEWALK, CONCRETE, REMOVE	184.000	SYS
12	202-99080 CONCRETE, REMOVE	0.400	CYS
13	203-02000 EXCAVATION, COMMON	1,809.000	CYS
14	203-02100 EXCAVATION, PEAT	503.000	CYS
15	205-06932 TEMPORARY CHECK DAM, STRAW BALES	85.000	LFT
16	205-06937 TEMPORARY SILT FENCE	6,604.000	LFT
17	205-09543 NO 2 STONE	500.000	TON
18	206-04301 SHEET PILING, STEEL, S=18.1	4,045.000	SFT
19	206-11761 SHEET PILING, STEEL, S=48.5	5,913.000	SFT
20	207-08267 SUBGRADE TREATMENT, TYPE IIIA	5,487.000	SYS
21	211-02050 B BORROW	529.000	CYS
22	211-09264 STRUCTURAL BACKFILL, TYPE 1	12.000	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,162.000	TON
24	304-07490 HMA PATCHING, TYPE B	102.000	TON
25	306-08034 MILLING, ASPHALT, 1 1/2 IN	3,399.000	SYS
26	402-07432 HMA SURFACE, TYPE A	519.000	TON
27	402-07433 HMA SURFACE, TYPE B	91.000	TON
28	402-07435 HMA INTERMEDIATE, TYPE A	385.000	TON
29	402-07438 HMA INTERMEDIATE, TYPE B	172.000	TON
30	402-07441 HMA BASE, TYPE B	458.000	TON
31	406-05520 ASPHALT FOR TACK COAT	2.260	TON
32	603-01159 FENCE, CHAIN LINK, PVC COATED 42 IN	160.000	LFT
33	603-01932 FENCE, CHAIN LINK, 96 IN	200.000	LFT
34	603-91714 FENCE, RAIL, WOOD	250.000	LFT
35	603-92636 FENCE, CHAIN LINK, 72 IN	60.000	LFT
36	604-06070 SIDEWALK, CONCRETE	693.000	SYS
37	604-07896 CURB RAMP, CONCRETE, B	40.000	SYS
38	604-07897 CURB RAMP, CONCRETE, C	4.000	SYS
39	604-07901 CURB RAMP, CONCRETE, G	30.000	SYS
40	604-95344 HAND RAIL, PEDESTRIAN	156.000	LFT
41	605-06120 CURB, CONCRETE	60.000	LFT
42	618-03812 BENCH	2.000	EACH
43	618-03827 FOUNTAIN, DRINKING	1.000	EACH
44	618-97672 TRASH RECEPTACLE	2.000	EACH
45	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
46	621-06545 FERTILIZER	0.200	TON
47	621-06557 SEED MIXTURE, T	255.000	LBS
48	621-06560 MULCHED SEEDING, U	2,087.000	SYS
49	621-06567 WATER	44.000	KGAL

CALL ORDER : 151

CONTRACT ID : R -29555-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE/PEDESTRIAN TRAIL		
50	621-06570 TOPSOIL	94.700	CYS
51	621-06574 SODDING	244.000	SYS
52	621-06575 SODDING, NURSERY	611.000	SYS
53	628-09401 FIELD OFFICE, A	10.000	MOS
54	702-90915 CONCRETE, CLASS A	3.000	CYS
55	711-10103 ARCHITECTURAL	LUMP	LUMP
56	715-02743 GATE VALVE WITH VALVE BOX 4 IN	1.000	EACH
57	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	24.000	LFT
58	715-05596 PIPE EXTENSION, CIRCULAR 18 IN	10.000	LFT
59	715-46000 PIPE END SECTION, DIA 12"	1.000	EACH
60	715-91739 WATER SERVICE LINE, 0.75 IN	200.000	LFT
61	720-45270 PIPE CATCH BASIN, 18 IN	1.000	EACH
62	801-06640 CONSTRUCTION SIGN, A	50.000	EACH
63	801-06645 CONSTRUCTION SIGN, B	10.000	EACH
64	801-06735 TUBULAR MARKER, PERMANENT	30.000	EACH
65	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
66	801-07118 BARRICADE, III-A	144.000	LFT
67	802-03896 BOLLARD	4.000	EACH
68	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	477.000	LFT
69	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	196.250	SFT
70	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	54.000	SFT
71	805-01842 HANDHOLE, SIGNAL	6.000	EACH
72	805-02645 SIGNAL PEDESTAL FOUNDATION, A	4.000	EACH
73	805-04133 SIGNAL PEDESTAL, 12FT	4.000	EACH
74	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
75	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN AMBER	8.000	EACH
76	805-78445 SIGNAL SERVICE	1.000	EACH
77	805-78467 SIGNAL CABLE, 3C/8GA	100.000	LFT
78	805-78480 SIGNAL CABLE, 3C/14GA	1,067.000	LFT
79	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	703.000	LFT
80	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	921.000	LFT
81	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	4,040.000	LFT
82	808-06726 TRANSVERSE MARKING, PAINT,	63.000	LFT
83	808-75100 TRANSVERSE MARKING, PAINT,	523.000	LFT
84	808-97222 PAVEMENT MESSAGE MARKING, PAINT, HANDICAP SYMBOL	2.000	EACH

CALL ORDER : 161

CONTRACT ID : R -30291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	465.000	SYS
13	202-02278 CURB, CONCRETE, REMOVE	409.000	LFT
14	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
15	202-74035 SIGN, REMOVE	23.000	EACH
16	202-94747 POST, REMOVE	2.000	EACH
17	203-02000 EXCAVATION, COMMON	34,318.000	CYS
18	205-06933 TEMPORARY INLET PROTECTION	4.000	EACH
19	205-06934 TEMPORARY MULCH	7.000	TON
20	205-06937 TEMPORARY SILT FENCE	5,328.000	LFT
21	205-09543 NO 2 STONE	300.000	TON
22	207-08266 SUBGRADE TREATMENT, TYPE III	4,723.000	SYS
23	207-08267 SUBGRADE TREATMENT, TYPE IIIA	5,465.000	SYS
24	207-09934 SUBGRADE TREATMENT, TYPE 1B	28,429.000	SYS
25	211-09264 STRUCTURAL BACKFILL, TYPE 1	4,889.000	CYS
26	211-09266 STRUCTURAL BACKFILL, TYPE 3	103.000	CYS
27	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,925.000	TON
28	302-07455 DENSE GRADED SUBBASE	44.000	CYS
29	303-07449 COMPACTED AGGREGATE, NO. 73	722.000	TON
30	306-08043 MILLING, TRANSITION	1,044.000	SYS
31	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2,048.000	TON
32	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	3,208.000	TON
33	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	5,132.000	TON
34	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	4,076.000	TON
35	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	3,261.000	TON
36	401-10258 JOINT ADHESIVE, SURFACE	15,330.000	LFT
37	401-10259 JOINT ADHESIVE, INTERMEDIATE	15,330.000	LFT
38	402-07451 HMA WEDGE AND LEVEL, TYPE B	208.000	TON
39	402-10084 HMA FOR TEMPORARY PAVEMENT, B	149.000	TON
40	406-05520 ASPHALT FOR TACK COAT	34.000	TON
41	502-06999 PCCP, 8 IN	260.000	SYS
42	603-01932 FENCE, CHAIN LINK, 96 IN	1,651.000	LFT
43	603-02009 FENCE GATE, CHAIN LINK, 96 IN X 20 FT	1.000	EACH
44	603-03692 FENCE, WOOD,	529.000	LFT
45	603-04847 FENCE GATE,	4.000	EACH
46	604-04740 PAVERS	579.000	SFT
47	604-06070 SIDEWALK, CONCRETE	6,061.000	SYS
48	604-06367 JOINT MATERIAL	4,660.000	LFT
49	604-07897 CURB RAMP, CONCRETE, C	127.000	SYS

CALL ORDER : 161

CONTRACT ID : R -30291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
50	604-07901 CURB RAMP, CONCRETE, G	55.000	SYS
51	604-07902 CURB RAMP, CONCRETE, H	22.000	SYS
52	604-07904 CURB RAMP, CONCRETE, L	39.000	SYS
53	605-06120 CURB, CONCRETE	1,470.000	LFT
54	605-06140 CURB AND GUTTER, CONCRETE	7,345.000	LFT
55	605-06145 CURB AND GUTTER, B, CONCRETE	236.000	LFT
56	610-07487 HMA FOR APPROACHES, TYPE B	124.000	TON
57	610-08446 PCCP FOR APPROACHES, 6 IN	949.000	SYS
58	610-09108 PCCP FOR APPROACHES, 9 IN	191.000	SYS
59	611-06497 MAILBOX ASSEMBLY, SINGLE	20.000	EACH
60	611-06498 MAILBOX ASSEMBLY, DOUBLE	6.000	EACH
61	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
62	616-02320 GEOTEXTILES	167.000	SYS
63	616-06405 RIPRAP, REVETMENT	29.000	TON
64	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
65	621-02468 SEED MIXTURE, GRASS, 1	33.000	LBS
66	621-03787 SEED MIXTURE, D	16.000	LBS
67	621-06545 FERTILIZER	2.000	TON
68	621-06554 SEED MIXTURE, U	840.000	LBS
69	621-06557 SEED MIXTURE, T	390.000	LBS
70	621-06565 MULCHING MATERIAL	15.000	TON
71	621-06567 WATER	55.000	KGAL
72	621-06574 SODDING	2,242.000	SYS
73	621-06575 SODDING, NURSERY	12,289.000	SYS
74	622-05626 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT	1.000	EACH
75	622-05626 PLANT, CONIFEROUS EVERGREEN, CONE, BROAD UPRIGHT	2.000	EACH
76	622-05630 PLANT, CONIFEROUS EVERGREEN, GLOBE, DWARF, OVER 18 TO 24 IN	54.000	EACH
77	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	5.000	EACH
78	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	5.000	EACH
79	622-05641 PLANT, DECIDUOUS SHRUB, 36 TO 48 IN	50.000	EACH
80	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	1.000	EACH
81	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN	100.000	EACH
82	622-05653 PLANT, GROUND COVER	27.000	EACH
83	622-05653 PLANT, GROUND COVER	135.000	EACH
84	622-05654 PLANT, PERENNIAL	25.000	EACH
85	622-05654 PLANT, PERENNIAL	18.000	EACH
86	628-09401 FIELD OFFICE, A	12.000	MOS
87	715-04522 PIPE END SECTION DIA 42"	1.000	EACH
88	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	9,229.000	LFT
89	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	148.000	LFT
90	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	2,031.000	LFT
91	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	573.000	LFT
92	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	625.000	LFT
93	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	91.000	LFT
94	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	2,587.000	LFT
95	715-05159 PIPE, TYPE 2 CIRCULAR 42 IN	201.000	LFT
96	718-52610 AGGREGATE FOR UNDERDRAINS	7,595.000	CYS
97	718-99153 GEOTEXTILES FOR UNDERDRAIN	6,783.000	SYS
98	720-01092 MANHOLE, J15, MODIFIED	21.000	EACH

CALL ORDER : 161

CONTRACT ID : R -30291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
99	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
100	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
101	720-45030 INLET, E7	3.000	EACH
102	720-45035 INLET, F7	1.000	EACH
103	720-45410 MANHOLE, C4	4.000	EACH
104	720-94612 MANHOLE, K4	2.000	EACH
105	720-94840 CASTING, WATER VALVE, ADJUST TO GRADE	1.000	EACH
106	720-95422 MANHOLE, J4	2.000	EACH
107	720-98174 INLET, B15	31.000	EACH
108	720-98555 INLET, C15	9.000	EACH
109	732-08419 MODULAR BLOCK WALL	308.000	SYS
110	732-08421 MODULAR BLOCK WALL ERECTION	308.000	SYS
111	801-04308 ROAD CLOSURE SIGN ASSEMBLY	21.000	EACH
112	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	12,628.000	LFT
113	801-06469 TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN	266.000	LFT
114	801-06625 DETOUR ROUTE MARKER ASSEMBLY	37.000	EACH
115	801-06640 CONSTRUCTION SIGN, A	67.000	EACH
116	801-06645 CONSTRUCTION SIGN, B	13.000	EACH
117	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
118	801-07118 BARRICADE, III-A	270.000	LFT
119	801-07119 BARRICADE, III-B	150.000	LFT
120	801-09087 TEMPORARY PAVEMENT MARKING, REMOVABLE, 12 IN	175.000	LFT
121	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	740.000	LFT
122	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	52.000	LFT
123	802-05703 SIGN POST, SQUARE, TYPE 3, REINFORCED ANCHOR BASE	64.000	LFT
124	802-07060 SIGN, SHEET, RELOCATE	3.000	EACH
125	802-09837 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.080 IN THICKNESS	3.000	SFT
126	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	349.000	SFT
127	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	24.000	SFT
128	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	159.000	SFT
129	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	46.000	SFT
130	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	630.000	LFT
131	807-02191 HANDHOLE, LIGHTING	9.000	EACH
132	807-02428 LIGHTING FOUNDATION, CONCRETE, WITH GROUND	8.000	EACH
133	807-85502 LIGHT POLE, 30 FT E.M.H., 15.0 FT MAST ARM, BREAKAWAY BASE	8.000	EACH
134	807-86615 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	8.000	EACH
135	807-86810 SERVICE POINT, II	2.000	EACH
136	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	960.000	LFT
137	807-86910 CONNECTOR KIT, UNFUSED	8.000	EACH
138	807-86915 CONNECTOR KIT, FUSED	8.000	EACH
139	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	19.000	EACH
140	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.000	EACH
141	807-86930 INSULATION LINK, NON-WATERPROOFED	19.000	EACH
142	807-86935 INSULATION LINK, WATERPROOFED	40.000	EACH
143	807-98335 WIRE, NO. 4 COPPER IN PLASTIC DUCT, IN TRENCH, 4 1/C	1,784.000	LFT
144	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	509.000	LFT
145	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	515.000	LFT
146	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	6,657.000	LFT
147	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	1,329.000	LFT

CALL ORDER : 161

CONTRACT ID : R -30291-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
148	808-10037 LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	381.000	LFT
149	808-10039 LINE, MULTI-COMPONENT, SOLID, WHITE, 12 IN	111.000	LFT
150	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	71.000	LFT
151	808-10052 PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, (ONLY)	12.000	EACH
152	808-10059 LINE, MULTI-COMPONENT, SOLID, YELLOW, 12 IN	115.000	LFT
153	808-10074 TRANSVERSE MARKINGS, MULTI-COMPONENT,	388.000	LFT
154	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	18.000	EACH
155	808-10089 LINE, MULTI-COMPONENT, BROKEN, WHITE	58.000	LFT
156	808-10094 TRANSVERSE MARKINGS, MULTI-COMPONENT,	639.000	LFT
157	808-10097 TRANSVERSE MARKINGS, MULTI-COMPONENT,	62.000	LFT

CALL ORDER : 171

CONTRACT ID : R -30328-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT PROJECT WITH ADDED TURN LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-91385 INLET, REMOVE	1.000	EACH
11	202-99187 FENCE, FARM FIELD, REMOVE	2,003.000	LFT
12	203-02000 EXCAVATION, COMMON	8,496.000	CYS
13	203-02070 BORROW	5,145.000	CYS
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	74.000	TON
15	205-06932 TEMPORARY CHECK DAM, STRAW BALES	196.000	LFT
16	205-06933 TEMPORARY INLET PROTECTION	10.000	EACH
17	205-06934 TEMPORARY MULCH	8.000	TON
18	205-06936 TEMPORARY SEDIMENT TRAP	187.000	TON
19	205-06937 TEMPORARY SILT FENCE	726.000	LFT
20	207-08263 SUBGRADE TREATMENT, TYPE IA	18,185.000	SYS
21	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,334.000	SYS
22	211-09264 STRUCTURAL BACKFILL, TYPE 1	1,991.400	CYS
23	303-01180 COMPACTED AGGREGATE, NO. 53	1,513.000	TON
24	306-08034 MILLING, ASPHALT, 1 1/2 IN	8,087.000	SYS
25	306-08042 MILLING, SCARIFICATION/PROFILE	5,106.000	SYS
26	402-07434 HMA SURFACE, TYPE C	2,363.000	TON
27	402-07439 HMA INTERMEDIATE, TYPE C	2,143.000	TON
28	402-07442 HMA BASE, TYPE C	6,579.000	TON
29	402-10086 HMA FOR TEMPORARY PAVEMENT, C	1,286.000	TON
30	406-05520 ASPHALT FOR TACK COAT	14.500	TON
31	605-52807 CURB AND GUTTER, COMBINED	3,419.000	LFT
32	610-07487 HMA FOR APPROACHES, TYPE B	859.000	TON
33	610-08446 PCCP FOR APPROACHES, 6 IN	88.000	SYS
34	610-09108 PCCP FOR APPROACHES, 9 IN	945.000	SYS
35	611-06497 MAILBOX ASSEMBLY, SINGLE	4.000	EACH
36	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
37	615-06490 RIGHT OF WAY MARKER	34.000	EACH
38	615-06505 MONUMENT, B	1.000	EACH
39	615-06510 MONUMENT, C	4.000	EACH
40	615-06527 MONUMENT, SECTION CORNER	2.000	EACH
41	616-02320 GEOTEXTILES	98.000	SYS
42	616-06405 RIPRAP, REVETMENT	38.000	TON
43	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
44	621-02770 EROSION CONTROL BLANKET	4,266.000	SYS
45	621-06545 FERTILIZER	1.000	TON
46	621-06553 SEED MIXTURE, R	410.000	LBS
47	621-06557 SEED MIXTURE, T	479.000	LBS
48	621-06565 MULCHING MATERIAL	5.000	TON
49	621-06567 WATER	15.000	KGAL

CALL ORDER : 171

CONTRACT ID : R -30328-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT PROJECT WITH ADDED TURN LANES		
50	621-06575 SODDING, NURSERY	4,754.000	SYS
51	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
52	628-09402 FIELD OFFICE, B	12.000	MOS
53	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	24.000	MOS
54	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
55	715-03475 SAFETY METAL END SECTION 4:1 DIA 15"	2.000	EACH
56	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,576.000	LFT
57	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	420.000	LFT
58	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	990.000	LFT
59	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	595.000	LFT
60	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	241.000	LFT
61	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	421.000	TON
62	715-46005 PIPE END SECTION, DIA 15"	7.000	EACH
63	720-02442 PIPE, PLUG EXISTING	3.000	EACH
64	720-45030 INLET, E7	7.000	EACH
65	720-45070 INLET, P12A	2.000	EACH
66	720-45410 MANHOLE, C4	9.000	EACH
67	720-90984 MANHOLE, C2	1.000	EACH
68	720-91973 MANHOLE, H4	2.000	EACH
69	720-98174 INLET, B15	14.000	EACH
70	720-98555 INLET, C15	12.000	EACH
71	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
72	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	27,730.000	LFT
73	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	51.000	LFT
74	801-06640 CONSTRUCTION SIGN, A	26.000	EACH
75	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
76	801-07119 BARRICADE, III-B	197.000	LFT
77	801-94295 SIGNAL HEAD, RELOCATE	8.000	EACH
78	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	118.000	LFT
79	802-05705 SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	97.000	LFT
80	802-05706 SIGN POST, SQUARE, TYPE 3, UNREINFORCED ANCHOR BASE	32.000	LFT
81	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	227.400	SFT
82	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	62.500	SFT
83	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
84	805-01815 SIGNAL SUPPORT FOUNDATION, 36 IN X 144 IN	4.000	EACH
85	805-01842 HANDHOLE, SIGNAL	10.000	EACH
86	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
87	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
88	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	8.000	EACH
89	805-78215 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	2.000	EACH
90	805-78230 TRAFFIC SIGNAL HEAD, 5 FACE, 12"	2.000	EACH
91	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
92	805-78420 DISCONNECT HANGER	4.000	EACH
93	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	3,500.000	LFT
94	805-78485 SIGNAL CABLE, 5C/14GA	2,074.000	LFT
95	805-78490 SIGNAL CABLE, 7C/14GA	524.000	LFT
96	805-78785 SIGNAL DETECTOR HOUSING	12.000	EACH
97	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,350.000	LFT
98	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH

CALL ORDER : 171

CONTRACT ID : R -30328-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT PROJECT WITH ADDED TURN LANES		
99	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	4.000	EACH
100	807-01878 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	8.000	EACH
101	807-02193 LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT	8.000	EACH
102	807-03745 WIRE, XHHW, NO 4 COPPER, IN CABLE DUCT, IN TRENCH, 1/C	1,500.000	LFT
103	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	2,017.000	LFT
104	807-84752 LIGHT POLE, 40 FT E.M.H., 10.0 FT MAST ARM, TRANSFORMER BASE	8.000	EACH
105	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	2,579.000	LFT
106	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	8,750.000	LFT
107	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	540.000	LFT
108	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	6,679.000	LFT
109	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	115.000	LFT
110	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	168.000	LFT
111	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	38.000	EACH
112	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	16.000	EACH
113	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	503.000	LFT

CALL ORDER : 191

CONTRACT ID : R -31286-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	203-02000 EXCAVATION, COMMON	5,210.000	CYS
14	203-02070 BORROW	9,495.000	CYS
15	203-51223 EXCAVATION, WATERWAY	275.000	CYS
16	205-03371 SEDIMENT, REMOVE	50.000	CYS
17	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	191.000	TON
18	205-06934 TEMPORARY MULCH	10.000	TON
19	205-06937 TEMPORARY SILT FENCE	6,901.000	LFT
20	205-09543 NO 2 STONE	100.000	TON
21	206-51220 EXCAVATION, WET	60.000	CYS
22	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	15.000	CYS
23	207-08265 SUBGRADE TREATMENT, TYPE IIA	28,824.000	SYS
24	207-08267 SUBGRADE TREATMENT, TYPE IIIA	967.000	SYS
25	211-02050 B BORROW	100.000	CYS
26	211-09264 STRUCTURAL BACKFILL, TYPE 1	34.000	CYS
27	211-09265 STRUCTURAL BACKFILL, TYPE 2	341.000	CYS
28	211-09267 STRUCTURAL BACKFILL, TYPE 4	18.000	CYS
29	211-09268 STRUCTURAL BACKFILL, TYPE 5	229.000	CYS
30	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,639.000	TON
31	302-07455 DENSE GRADED SUBBASE	36.000	CYS
32	303-01180 COMPACTED AGGREGATE, NO. 53	761.000	TON
33	303-07449 COMPACTED AGGREGATE, NO. 73	188.000	TON
34	304-07492 WIDENING WITH HMA, TYPE A	6.000	TON
35	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
36	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1,710.000	TON
37	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	2,868.000	TON
38	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	6,788.000	TON
39	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	2,928.000	TON
40	401-10258 JOINT ADHESIVE, SURFACE	20,316.000	LFT
41	401-10259 JOINT ADHESIVE, INTERMEDIATE	19,570.000	LFT
42	402-07432 HMA SURFACE, TYPE A	191.000	TON
43	402-07433 HMA SURFACE, TYPE B	475.000	TON
44	402-07435 HMA INTERMEDIATE, TYPE A	148.000	TON
45	402-07441 HMA BASE, TYPE B	1,418.000	TON
46	406-05520 ASPHALT FOR TACK COAT	13.000	TON
47	415-11527 BASE SEAL	19.000	TON
48	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
49	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH

CALL ORDER : 191

CONTRACT ID : R -31286-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE CONSTRUCTION		
50	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
51	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	281.250	LFT
52	602-06729 BARRIER DELINEATOR	6.000	EACH
53	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	214.000	SYS
54	610-07487 HMA FOR APPROACHES, TYPE B	483.000	TON
55	610-08446 PCCP FOR APPROACHES, 6 IN	59.000	SYS
56	615-06490 RIGHT OF WAY MARKER	2.000	EACH
57	615-06505 MONUMENT, B	14.000	EACH
58	615-06510 MONUMENT, C	1.000	EACH
59	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
60	616-02320 GEOTEXTILES	737.000	SYS
61	616-06405 RIPRAP, REVETMENT	4,165.000	TON
62	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
63	621-06545 FERTILIZER	3.000	TON
64	621-06553 SEED MIXTURE, R	1,122.000	LBS
65	621-06557 SEED MIXTURE, T	1,020.000	LBS
66	621-06565 MULCHING MATERIAL	27.000	TON
67	621-06567 WATER	4.000	KGAL
68	621-06574 SODDING	12.000	SYS
69	621-06575 SODDING, NURSERY	1,034.000	SYS
70	628-09401 FIELD OFFICE, A	18.000	MOS
71	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
72	701-09557 TEST PILE, DYNAMIC, PRODUCTION	130.000	LFT
73	701-09559 TEST PILE, DYNAMIC, RESTRIKE	2.000	EACH
74	701-09739 PILE SHOE, HP 12 X 53	18.000	EACH
75	701-51195 PILE, STEEL H, HP 12 IN X 53	890.000	LFT
76	702-51005 CONCRETE, A, SUBSTRUCTURE	84.100	CYS
77	703-06028 REINFORCING BARS	10,574.000	LBS
78	703-06029 REINFORCING BARS, EPOXY COATED	47,402.000	LBS
79	704-51002 CONCRETE, C, SUPERSTRUCTURE	163.700	CYS
80	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH
81	706-51020 RAILING, CONCRETE, C	13.700	CYS
82	709-51821 SURFACE SEAL	LUMP	LUMP
83	714-11089 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	42.000	LFT
84	714-11186 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	92.000	LFT
85	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	12,629.000	LFT
86	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	723.000	LFT
87	715-05115 PIPE, TYPE 1 CIRCULAR 6 IN	500.000	LFT
88	715-05116 PIPE, TYPE 1 CIRCULAR 8 IN	100.000	LFT
89	715-05118 PIPE, TYPE 1 CIRCULAR 12 IN	100.000	LFT
90	715-05119 PIPE, TYPE 1 CIRCULAR 15 IN	72.000	LFT
91	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	100.000	LFT
92	715-05125 PIPE, TYPE 1 CIRCULAR 30 IN	100.000	LFT
93	715-05168 PIPE, TYPE 3 CIRCULAR 12 IN	24.000	LFT
94	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	186.000	LFT
95	715-09936 PIPE, TYPE 1 CIRCULAR 10 IN	100.000	LFT
96	715-46000 PIPE END SECTION, DIA 12"	2.000	EACH
97	715-46005 PIPE END SECTION, DIA 15"	10.000	EACH
98	718-06529 OUTLET PROTECTOR, 2	23.000	EACH

CALL ORDER : 191

CONTRACT ID : R -31286-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW BRIDGE CONSTRUCTION		
99	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
100	718-52610 AGGREGATE FOR UNDERDRAINS	1,137.000	CYS
101	718-99153 GEOTEXTILES FOR UNDERDRAIN	11,619.000	SYS
102	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
103	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
104	801-06625 DETOUR ROUTE MARKER ASSEMBLY	17.000	EACH
105	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
106	801-06645 CONSTRUCTION SIGN, B	1.000	EACH
107	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
108	801-07119 BARRICADE, III-B	190.000	LFT
109	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	105.000	LFT
110	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	52.000	SFT
111	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	6.000	SFT
112	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	13,764.000	LFT
113	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
114	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	230.000	LFT
115	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	230.000	LFT
116	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	526.000	LFT
117	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	11,233.000	LFT
118	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	60.000	LFT
119	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH

CALL ORDER : 201

CONTRACT ID : R -32276-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09542 UTILITY RELOCATION ENGINEERING	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	8,035.000	CYS
13	203-02070 BORROW	11,784.000	CYS
14	204-02290 SETTLEMENT PLATE	4.000	EACH
15	205-03371 SEDIMENT, REMOVE	107.000	CYS
16	205-06933 TEMPORARY INLET PROTECTION	4.000	EACH
17	205-06937 TEMPORARY SILT FENCE	1,799.000	LFT
18	207-08262 SUBGRADE TREATMENT, TYPE I	12,269.000	SYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,239.000	SYS
20	211-02050 B BORROW	82.000	CYS
21	211-09264 STRUCTURAL BACKFILL, TYPE 1	1,092.000	CYS
22	211-09266 STRUCTURAL BACKFILL, TYPE 3	74.000	CYS
23	215-07043 CHEMICAL MODIFICATION, SOILS	4,950.000	SYS
24	302-07455 DENSE GRADED SUBBASE	9.000	CYS
25	303-01180 COMPACTED AGGREGATE, NO. 53	3,712.000	TON
26	303-07449 COMPACTED AGGREGATE, NO. 73	113.000	TON
27	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	1,000.000	TON
28	304-07489 HMA PATCHING, TYPE A	215.000	TON
29	306-08034 MILLING, ASPHALT, 1 1/2 IN	128.000	SYS
30	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	770.000	TON
31	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,781.000	TON
32	401-10258 JOINT ADHESIVE, SURFACE	2,960.000	LFT
33	406-05520 ASPHALT FOR TACK COAT	23.390	TON
34	601-01128 GUARDRAIL, TRANSITION TYPE WGB	2.000	EACH
35	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
36	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	50.000	LFT
37	604-06070 SIDEWALK, CONCRETE	2,821.000	SYS
38	604-07897 CURB RAMP, CONCRETE, C	2.700	SYS
39	604-07901 CURB RAMP, CONCRETE, G	29.400	SYS
40	604-07902 CURB RAMP, CONCRETE, H	29.400	SYS
41	604-92237 HAND RAIL, STEEL	206.000	LFT
42	605-06140 CURB AND GUTTER, CONCRETE	4,740.000	LFT
43	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	88.000	LFT
44	605-97937 CURB AND GUTTER, ROLL CURB	205.000	LFT
45	607-06335 PAVED SIDE DITCH, A	307.000	LFT
46	609-06257 REINFORCED CONCRETE BRIDGE APPROACH, 10 IN	54.300	SYS
47	610-07486 HMA FOR APPROACHES, TYPE A	214.000	TON
48	610-08446 PCCP FOR APPROACHES, 6 IN	1,239.000	SYS
49	611-06497 MAILBOX ASSEMBLY, SINGLE	7.000	EACH

CALL ORDER : 201

CONTRACT ID : R -32276-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	611-06498 MAILBOX ASSEMBLY, DOUBLE	5.000	EACH
51	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
52	616-02320 GEOTEXTILES	1,159.000	SYS
53	616-06405 RIPRAP, REVETMENT	668.000	TON
54	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
55	621-01935 SEED MIXTURE, A	2.400	LBS
56	621-02770 EROSION CONTROL BLANKET	497.000	SYS
57	621-04258 SEED MIXTURE	79.000	LBS
58	621-06545 FERTILIZER	1.260	TON
59	621-06554 SEED MIXTURE, U	474.000	LBS
60	621-06557 SEED MIXTURE, T	832.000	LBS
61	621-06565 MULCHING MATERIAL	17.400	TON
62	621-06567 WATER	10.700	KGAL
63	621-06570 TOPSOIL	74.000	CYS
64	621-06575 SODDING, NURSERY	2,625.000	SYS
65	621-09400 SEED MIXTURE, SEDGE MEADOW	3.400	LBS
66	622-52436 SIGN, DO NOT MOW OR SPRAY	8.000	EACH
67	622-91786 SEEDLING	45.000	EACH
68	622-91786 SEEDLING	100.000	EACH
69	628-09402 FIELD OFFICE, B	12.000	MOS
70	702-90915 CONCRETE, CLASS A	0.400	CYS
71	703-06029 REINFORCING BARS, EPOXY COATED	1,983.000	LBS
72	706-09545 COARSE AGGREGATE, NO 8	159.000	CYS
73	715-01336 GATE VALVE, 12 IN	2.000	EACH
74	715-03025 SANITARY MANHOLE	1.000	EACH
75	715-03795 PIPE DUCTILE IRON 6"	55.000	LFT
76	715-04947 TAPPING TEE	3.000	EACH
77	715-04995 LINE STOP	2.000	EACH
78	715-05032 PIPE, TYPE 2 CIRCULAR 15 IN	201.000	LFT
79	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	5,982.000	LFT
80	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	56.000	LFT
81	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,166.000	LFT
82	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	205.000	LFT
83	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	548.000	LFT
84	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	110.000	LFT
85	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	67.000	LFT
86	715-05408 PIPE SANITARY SEWER 8 IN	390.000	LFT
87	715-08250 PIPE DUCTILE IRON 12"	1,600.000	LFT
88	715-09064 VIDEO INSPECTION FOR PIPE	2,269.000	LFT
89	715-46000 PIPE END SECTION, DIA 12"	3.000	EACH
90	715-46005 PIPE END SECTION, DIA 15"	2.000	EACH
91	715-46010 PIPE END SECTION, DIA 18"	5.000	EACH
92	715-46030 PIPE END SECTION, DIA 30"	3.000	EACH
93	715-95866 GATE VALVE, 6 IN.	2.000	EACH
94	715-98961 FORCE MAIN	465.000	LFT
95	718-06529 OUTLET PROTECTOR, 2	1.000	EACH
96	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
97	718-52610 AGGREGATE FOR UNDERDRAINS	463.000	CYS
98	718-99153 GEOTEXTILES FOR UNDERDRAIN	3,495.000	SYS

CALL ORDER : 201

CONTRACT ID : R -32276-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
99	720-44000 CASTING, ADJUST TO GRADE	9.000	EACH
100	720-44025 CASTING, 4, FURNISH AND ADJUST TO GRADE	1.000	EACH
101	720-45030 INLET, E7	4.000	EACH
102	720-45040 INLET, G7	1.000	EACH
103	720-45075 INLET, R13	2.000	EACH
104	720-45410 MANHOLE, C4	11.000	EACH
105	720-45515 MANHOLE, D4, MODIFIED	2.000	EACH
106	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	15.000	LFT
107	720-98174 INLET, B15	19.000	EACH
108	720-98555 INLET, C15	6.000	EACH
109	732-08419 MODULAR BLOCK WALL	183.000	SYS
110	732-08420 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	100.000	SYS
111	732-08421 MODULAR BLOCK WALL ERECTION	283.000	SYS
112	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
113	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
114	801-06625 DETOUR ROUTE MARKER ASSEMBLY	6.000	EACH
115	801-06640 CONSTRUCTION SIGN, A	13.000	EACH
116	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
117	801-07119 BARRICADE, III-B	120.000	LFT
118	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	144.000	LFT
119	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	61.750	SFT
120	808-02977 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	15.000	EACH
121	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	50.000	LFT
122	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	5,590.000	LFT
123	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	60.000	LFT
124	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	292.000	LFT
125	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	15.000	EACH
126	808-97127 LINE, THERMOPLASTIC, SOLID, WHITE, 5 IN	5,422.000	LFT

CALL ORDER : 211

CONTRACT ID : R -32731-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
11	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
12	203-02070 BORROW	23.000	CYS
13	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	20.000	TON
14	205-06932 TEMPORARY CHECK DAM, STRAW BALES	126.000	LFT
15	205-06934 TEMPORARY MULCH	1.000	TON
16	205-06937 TEMPORARY SILT FENCE	350.000	LFT
17	207-09935 SUBGRADE TREATMENT, TYPE 1C	95.000	SYS
18	211-09265 STRUCTURAL BACKFILL, TYPE 2	215.000	CYS
19	302-08562 COARSE AGGREGATE, NO 8	62.000	TON
20	303-01180 COMPACTED AGGREGATE, NO. 53	9.000	TON
21	306-08034 MILLING, ASPHALT, 1 1/2 IN	570.000	SYS
22	401-10258 JOINT ADHESIVE, SURFACE	175.000	LFT
23	402-07433 HMA SURFACE, TYPE B	49.000	TON
24	402-07438 HMA INTERMEDIATE, TYPE B	12.000	TON
25	402-07441 HMA BASE, TYPE B	28.000	TON
26	406-05521 ASPHALT FOR TACK COAT	850.000	SYS
27	616-02320 GEOTEXTILES	130.000	SYS
28	616-06405 RIPRAP, REVETMENT	32.000	TON
29	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
30	621-02770 EROSION CONTROL BLANKET	100.000	SYS
31	621-03909 SEED MIXTURE, NATIVE	2.000	LBS
32	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
33	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	4.000	MOS
34	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
35	714-11076 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	60.000	LFT
36	715-04596 WATER SERVICE	1.000	EACH
37	715-05408 PIPE SANITARY SEWER 8 IN	50.000	LFT
38	715-07794 WATER MAIN CONNECTIONS	2.000	EACH
39	715-07806 PIPE STEEL CASING	50.000	LFT
40	715-92525 WATER MAIN, 10 IN	120.000	LFT
41	715-98479 GATE VALVE AND BOX, 10 IN.	2.000	EACH
42	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
43	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
44	801-06625 DETOUR ROUTE MARKER ASSEMBLY	26.000	EACH
45	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
46	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
47	801-07118 BARRICADE, III-A	48.000	LFT
48	801-07119 BARRICADE, III-B	48.000	LFT
49	804-06771 DELINEATOR POST, FLEXIBLE	2.000	EACH

CALL ORDER : 211

CONTRACT ID : R -32731-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50 808-06713	LINE, PAINT, SOLID, WHITE, 4 IN	350.000	LFT
51 808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN	175.000	LFT

CALL ORDER : 221

CONTRACT ID : R -33058-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
15	203-02000 EXCAVATION, COMMON	20,880.000	CYS
16	203-02070 BORROW	820.000	CYS
17	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	8.000	EACH
18	205-03371 SEDIMENT, REMOVE	100.000	CYS
19	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	67.000	TON
20	205-06937 TEMPORARY SILT FENCE	3,139.000	LFT
21	205-09543 NO 2 STONE	100.000	TON
22	207-08264 SUBGRADE TREATMENT, TYPE II	7,105.000	SYS
23	207-08265 SUBGRADE TREATMENT, TYPE IIA	2,795.000	SYS
24	207-08267 SUBGRADE TREATMENT, TYPE IIIA	173.000	SYS
25	211-02050 B BORROW	2,870.000	CYS
26	211-09264 STRUCTURAL BACKFILL, TYPE 1	1,105.000	CYS
27	211-09264 STRUCTURAL BACKFILL, TYPE 1	1,145.000	CYS
28	211-09264 STRUCTURAL BACKFILL, TYPE 1	1,353.000	CYS
29	214-07202 GEOGRID, TYPE IA	2,150.000	SYS
30	215-07043 CHEMICAL MODIFICATION, SOILS	2,150.000	SYS
31	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	292.000	TON
32	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,105.000	TON
33	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	100.000	TON
34	304-07493 WIDENING WITH HMA, TYPE B	120.000	TON
35	306-08034 MILLING, ASPHALT, 1 1/2 IN	630.000	SYS
36	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	690.000	TON
37	401-07397 QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	1,030.000	TON
38	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	1,145.000	TON
39	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	1,310.000	TON
40	401-10258 JOINT ADHESIVE, SURFACE	5,253.000	LFT
41	401-10259 JOINT ADHESIVE, INTERMEDIATE	5,638.000	LFT
42	402-10084 HMA FOR TEMPORARY PAVEMENT, B	730.000	TON
43	406-05520 ASPHALT FOR TACK COAT	4.000	TON
44	415-11527 BASE SEAL	7.620	TON
45	604-06070 SIDEWALK, CONCRETE	2,047.000	SYS
46	604-07901 CURB RAMP, CONCRETE, G	18.000	SYS
47	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	4,825.000	LFT
48	605-09131 CURB AND GUTTER TURNOUT CONCRETE	35.000	LFT
49	610-08446 PCCP FOR APPROACHES, 6 IN	100.000	SYS

CALL ORDER : 221

CONTRACT ID : R -33058-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
50	610-09108 PCCP FOR APPROACHES, 9 IN	73.000	SYS
51	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
52	615-06505 MONUMENT, B	12.000	EACH
53	616-02320 GEOTEXTILES	96.000	SYS
54	616-06405 RIPRAP, REVETMENT	39.000	TON
55	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
56	621-06545 FERTILIZER	7.000	TON
57	621-06554 SEED MIXTURE, U	2,462.000	LBS
58	621-06557 SEED MIXTURE, T	2,544.000	LBS
59	621-06565 MULCHING MATERIAL	67.000	TON
60	621-06567 WATER	12.000	KGAL
61	621-06574 SODDING	2,969.000	SYS
62	621-90853 TAPPING SLEEVE WITH VALVE	1.000	EACH
63	628-09402 FIELD OFFICE, B	16.000	MOS
64	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	18.000	MOS
65	715-04612 PIPE	40.000	LFT
66	715-04964 WATER MAIN	2,818.000	LFT
67	715-04987 CONNECTION	3.000	EACH
68	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	4,111.000	LFT
69	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	75.000	LFT
70	715-05115 PIPE, TYPE 1 CIRCULAR 6 IN	1,000.000	LFT
71	715-05116 PIPE, TYPE 1 CIRCULAR 8 IN	100.000	LFT
72	715-05118 PIPE, TYPE 1 CIRCULAR 12 IN	100.000	LFT
73	715-05119 PIPE, TYPE 1 CIRCULAR 15 IN	37.000	LFT
74	715-05122 PIPE, TYPE 1 CIRCULAR 21 IN	110.000	LFT
75	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	565.000	LFT
76	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	1,104.000	LFT
77	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	342.000	LFT
78	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	89.000	LFT
79	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	39.000	LFT
80	715-05331 PIPE, TYPE 2 DEFORMED MIN AREA 3.3 SFT	83.000	LFT
81	715-05408 PIPE SANITARY SEWER 8 IN	2,851.000	LFT
82	715-05711 PIPE SANITARY SEWER 6 IN	133.000	LFT
83	715-06471 PIPE END SECTION, MIN AREA 3.3 SFT	1.000	EACH
84	715-07806 PIPE STEEL CASING	176.000	LFT
85	715-07806 PIPE STEEL CASING	66.000	LFT
86	715-09064 VIDEO INSPECTION FOR PIPE	2,242.000	LFT
87	715-09936 PIPE, TYPE 1 CIRCULAR 10 IN	100.000	LFT
88	715-46000 PIPE END SECTION, DIA 12"	1.000	EACH
89	715-46005 PIPE END SECTION, DIA 15"	4.000	EACH
90	715-46010 PIPE END SECTION, DIA 18"	3.000	EACH
91	715-46015 PIPE END SECTION, DIA 21"	2.000	EACH
92	715-46030 PIPE END SECTION, DIA 30"	2.000	EACH
93	715-90052 LIFT STATION	LUMP	LUMP
94	715-96948 GATE VALVE, 8 IN	8.000	EACH
95	715-98961 FORCE MAIN	958.000	LFT
96	718-04986 CLEANOUT	1.000	EACH
97	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
98	718-52610 AGGREGATE FOR UNDERDRAINS	370.000	CYS

CALL ORDER : 221

CONTRACT ID : R -33058-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
99	718-99153 GEOTEXTILES FOR UNDERDRAIN	2,817.000	SYS
100	720-45030 INLET, E7	4.000	EACH
101	720-45035 INLET, F7	2.000	EACH
102	720-45265 PIPE CATCH BASIN, 15 IN	1.000	EACH
103	720-45270 PIPE CATCH BASIN, 18 IN	1.000	EACH
104	720-45410 MANHOLE, C4	16.000	EACH
105	720-45410 MANHOLE, C4	12.000	EACH
106	720-91742 FIRE HYDRANT	7.000	EACH
107	720-95422 MANHOLE, J4	2.000	EACH
108	720-98174 INLET, B15	10.000	EACH
109	720-98555 INLET, C15	12.000	EACH
110	720-98625 MANHOLE, C4, DROP	2.000	EACH
111	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
112	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
113	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	6,020.000	LFT
114	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	5,430.000	LFT
115	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	11.000	LFT
116	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24"	20.000	LFT
117	801-06640 CONSTRUCTION SIGN, A	15.000	EACH
118	801-06645 CONSTRUCTION SIGN, B	3.000	EACH
119	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
120	801-07119 BARRICADE, III-B	140.000	LFT
121	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	65.000	LFT
122	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	94.000	LFT
123	802-09837 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.080 IN THICKNESS	2.000	SFT
124	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	27.500	SFT
125	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	2.250	SFT
126	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	12.000	SFT
127	805-06595 CONDUIT, PVC, 2 IN	7,380.000	LFT
128	807-78590 HANDHOLE	24.000	EACH
129	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	197.000	LFT
130	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	1,800.000	LFT
131	808-06716 LINE, REMOVE	570.000	LFT
132	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	6,677.000	LFT
133	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	151.000	LFT
134	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
135	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
136	808-75340 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH

CALL ORDER : 231

CONTRACT ID : R -33080-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION AND RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	258.000	SYS
13	203-02000 EXCAVATION, COMMON	8,612.000	CYS
14	207-08265 SUBGRADE TREATMENT, TYPE IIA	6,815.000	SYS
15	207-08267 SUBGRADE TREATMENT, TYPE IIIA	906.000	SYS
16	211-09264 STRUCTURAL BACKFILL, TYPE 1	881.000	CYS
17	302-06464 SUBBASE FOR PCCP	1,476.000	CYS
18	303-07449 COMPACTED AGGREGATE, NO. 73	52.000	TON
19	306-08034 MILLING, ASPHALT, 1 1/2 IN	5,270.000	SYS
20	402-07433 HMA SURFACE, TYPE B	435.000	TON
21	406-05520 ASPHALT FOR TACK COAT	1.500	TON
22	501-06727 CORING, PCCP	LUMP	LUMP
23	501-09107 QC/QA-PCCP, 9 IN	5,790.000	SYS
24	503-05240 D-1 CONTRACTION JOINT	3,742.000	LFT
25	604-06070 SIDEWALK, CONCRETE	1,371.000	SYS
26	604-07897 CURB RAMP, CONCRETE, C	18.700	SYS
27	604-07899 CURB RAMP, CONCRETE, E	11.700	SYS
28	604-07901 CURB RAMP, CONCRETE, G	17.700	SYS
29	604-07903 CURB RAMP, CONCRETE, K	18.900	SYS
30	605-06090 CURB, INTEGRAL, CONCRETE	3,076.000	LFT
31	610-07487 HMA FOR APPROACHES, TYPE B	214.000	TON
32	610-08446 PCCP FOR APPROACHES, 6 IN	48.000	SYS
33	610-09108 PCCP FOR APPROACHES, 9 IN	645.000	SYS
34	615-06505 MONUMENT, B	2.000	EACH
35	615-06515 MONUMENT, D	1.000	EACH
36	621-06545 FERTILIZER	0.200	TON
37	621-06567 WATER	14.100	KGAL
38	621-06575 SODDING, NURSERY	3,915.000	SYS
39	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	16.000	EACH
40	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
41	628-09402 FIELD OFFICE, B	15.000	MOS
42	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	15.000	MOS
43	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
44	715-05032 PIPE, TYPE 2 CIRCULAR 15 IN	1,414.000	LFT
45	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	3,541.000	LFT
46	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	249.000	LFT
47	715-05163 PIPE, TYPE 2 CIRCULAR 60 IN	40.000	LFT
48	715-09064 VIDEO INSPECTION FOR PIPE	1,663.000	LFT
49	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT

CALL ORDER : 231

CONTRACT ID : R -33080-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION AND RESURFACE		
50	718-52610 AGGREGATE FOR UNDERDRAINS	320.000	CYS
51	718-99153 GEOTEXTILES FOR UNDERDRAIN	3,192.000	SYS
52	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
53	720-44000 CASTING, ADJUST TO GRADE	12.000	EACH
54	720-45045 INLET, J10	22.000	EACH
55	720-45275 PIPE CATCH BASIN, 24 IN	1.000	EACH
56	720-45410 MANHOLE, C4	10.000	EACH
57	720-95335 MANHOLE, M4	1.000	EACH
58	720-98174 INLET, B15	2.000	EACH
59	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
60	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
61	801-06640 CONSTRUCTION SIGN, A	24.000	EACH
62	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
63	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
64	801-07119 BARRICADE, III-B	144.000	LFT
65	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	124.800	LFT
66	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	42.800	SFT
67	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	24.400	SFT
68	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	2,724.000	LFT
69	808-06726 TRANSVERSE MARKING, PAINT,	18.000	LFT
70	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	4,100.000	LFT
71	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	90.000	LFT
72	808-10056 TRANSVERSE MARKING, MULTI-COMPONENT,	112.000	LFT

CALL ORDER : 241

CONTRACT ID : R -33102-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	2,000.000	SYS
13	202-91385 INLET, REMOVE	14.000	EACH
14	202-93047 MANHOLE, REMOVE	1.000	EACH
15	202-96133 PIPE, REMOVE	1,308.000	LFT
16	202-99187 FENCE, FARM FIELD, REMOVE	1,856.000	LFT
17	203-02000 EXCAVATION, COMMON	9,103.000	CYS
18	205-03371 SEDIMENT, REMOVE	22.000	CYS
19	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	22.000	TON
20	205-06933 TEMPORARY INLET PROTECTION	105.000	EACH
21	205-06934 TEMPORARY MULCH	1.000	TON
22	205-06937 TEMPORARY SILT FENCE	9,928.000	LFT
23	205-09543 NO 2 STONE	650.000	TON
24	205-11591 TEMPORARY SEED MIXTURE	49.000	LBS
25	207-08263 SUBGRADE TREATMENT, TYPE IA	24,729.000	SYS
26	207-08267 SUBGRADE TREATMENT, TYPE IIIA	12,472.000	SYS
27	207-08268 SUBGRADE TREATMENT, TYPE IV	500.000	SYS
28	211-02050 B BORROW	100.000	CYS
29	211-09264 STRUCTURAL BACKFILL, TYPE 1	20,756.000	CYS
30	211-09268 STRUCTURAL BACKFILL, TYPE 5	421.000	CYS
31	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,285.000	TON
32	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	466.000	TON
33	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,596.000	TON
34	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	2,660.000	TON
35	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	3,116.000	TON
36	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	3,291.000	TON
37	401-10258 JOINT ADHESIVE, SURFACE	8,944.000	LFT
38	401-10259 JOINT ADHESIVE, INTERMEDIATE	8,944.000	LFT
39	402-07432 HMA SURFACE, TYPE A	289.000	TON
40	402-07435 HMA INTERMEDIATE, TYPE A	471.000	TON
41	402-07453 HMA FOR TEMPORARY PAVEMENT, TYPE	427.000	TON
42	406-05520 ASPHALT FOR TACK COAT	11.000	TON
43	415-11527 BASE SEAL	2.000	TON
44	603-06065 FENCE, CHAIN LINK, RESET	20.000	LFT
45	604-07901 CURB RAMP, CONCRETE, G	48.000	SYS
46	604-07902 CURB RAMP, CONCRETE, H	12.000	SYS
47	605-06120 CURB, CONCRETE	108.000	LFT
48	605-06140 CURB AND GUTTER, CONCRETE	10,413.000	LFT
49	610-07487 HMA FOR APPROACHES, TYPE B	477.000	TON

CALL ORDER : 241

CONTRACT ID : R -33102-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
50	610-08446 PCCP FOR APPROACHES, 6 IN	1,621.000	SYS
51	610-09108 PCCP FOR APPROACHES, 9 IN	171.000	SYS
52	611-06497 MAILBOX ASSEMBLY, SINGLE	21.000	EACH
53	611-06498 MAILBOX ASSEMBLY, DOUBLE	5.000	EACH
54	615-06490 RIGHT OF WAY MARKER	48.000	EACH
55	615-06505 MONUMENT, B	10.000	EACH
56	615-06527 MONUMENT, SECTION CORNER	4.000	EACH
57	616-02320 GEOTEXTILES	1,343.000	SYS
58	616-06405 RIPRAP, REVETMENT	158.000	TON
59	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.000	EACH
60	621-06545 FERTILIZER	1.000	TON
61	621-06553 SEED MIXTURE, R	55.000	LBS
62	621-06565 MULCHING MATERIAL	1.000	TON
63	621-06567 WATER	30.000	kgAL
64	621-06575 SODDING, NURSERY	8,232.000	SYS
65	628-09402 FIELD OFFICE, B	15.000	MOS
66	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	628.000	LFT
67	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	10,515.000	LFT
68	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	3,058.000	LFT
69	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	110.000	LFT
70	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	331.000	LFT
71	715-05153 PIPE, TYPE 2 CIRCULAR 21 IN	8.000	LFT
72	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	824.000	LFT
73	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	47.000	LFT
74	715-05159 PIPE, TYPE 2 CIRCULAR 42 IN	1,545.000	LFT
75	715-05161 PIPE, TYPE 2 CIRCULAR 48 IN	1,434.000	LFT
76	715-05711 PIPE SANITARY SEWER 6 IN	100.000	LFT
77	715-09064 VIDEO INSPECTION FOR PIPE	11,601.000	LFT
78	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
79	718-52610 AGGREGATE FOR UNDERDRAINS	1,159.000	CYS
80	718-99153 GEOTEXTILES FOR UNDERDRAIN	19,005.000	SYS
81	720-07301 INLET, TYPE HA	2.000	EACH
82	720-44000 CASTING, ADJUST TO GRADE	10.000	EACH
83	720-44296 INLET, CAP	3.000	EACH
84	720-45030 INLET, E7	8.000	EACH
85	720-45035 INLET, F7	3.000	EACH
86	720-45260 PIPE CATCH BASIN, 12 IN	11.000	EACH
87	720-91973 MANHOLE, H4	11.000	EACH
88	720-93409 INLET, B15, MODIFIED	1.000	EACH
89	720-93411 INLET, C15, MODIFIED	6.000	EACH
90	720-94612 MANHOLE, K4	17.000	EACH
91	720-95422 MANHOLE, J4	6.000	EACH
92	720-98174 INLET, B15	45.000	EACH
93	720-98555 INLET, C15	29.000	EACH
94	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
95	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
96	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	12,301.000	LFT
97	801-06625 DETOUR ROUTE MARKER ASSEMBLY	20.000	EACH
98	801-06640 CONSTRUCTION SIGN, A	41.000	EACH

CALL ORDER : 241

CONTRACT ID : R -33102-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ADDED TRAVEL LANES		
99	801-06645 CONSTRUCTION SIGN, B	30.000	EACH
100	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
101	801-07118 BARRICADE, III-A	176.000	LFT
102	801-07119 BARRICADE, III-B	216.000	LFT
103	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	740.000	LFT
104	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH
105	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	324.000	LFT
106	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	141.000	SFT
107	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	72.000	SFT
108	805-01842 HANDHOLE, SIGNAL	4.000	EACH
109	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	247.000	LFT
110	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	78.000	LFT
111	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	10,102.000	LFT
112	808-06716 LINE, REMOVE	3,132.000	LFT
113	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	841.000	LFT
114	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	9,375.000	LFT
115	808-75274 TRANSVERSE MARKING, THERMOPLASTIC,	1,064.000	LFT
116	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	266.000	LFT
117	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	252.000	LFT
118	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	372.000	LFT
119	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	12.000	EACH
120	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	11.000	EACH

CALL ORDER : 251

CONTRACT ID : R -33387-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
13	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
14	203-02000 EXCAVATION, COMMON	8,343.000	CYS
15	203-02070 BORROW	6,144.000	CYS
16	203-02100 EXCAVATION, PEAT	1,975.000	CYS
17	203-51223 EXCAVATION, WATERWAY	273.000	CYS
18	204-08415 STAKE, SETTLEMENT	7.000	EACH
19	205-06932 TEMPORARY CHECK DAM, STRAW BALES	258.000	LFT
20	205-06933 TEMPORARY INLET PROTECTION	13.000	EACH
21	205-06937 TEMPORARY SILT FENCE	2,685.000	LFT
22	206-51220 EXCAVATION, WET	204.000	CYS
23	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	190.000	CYS
24	206-51235 COFFERDAM	LUMP	LUMP
25	207-08264 SUBGRADE TREATMENT, TYPE II	18,196.000	SYS
26	207-08267 SUBGRADE TREATMENT, TYPE IIIA	842.000	SYS
27	211-02050 B BORROW	2,652.000	CYS
28	211-06467 AGGREGATE FOR END BENT BACKFILL	42.000	CYS
29	211-09264 STRUCTURAL BACKFILL, TYPE 1	1,113.000	CYS
30	211-09267 STRUCTURAL BACKFILL, TYPE 4	162.400	CYS
31	214-07202 GEOGRID, TYPE IA	767.000	SYS
32	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	3,853.000	TON
33	302-07455 DENSE GRADED SUBBASE	65.000	CYS
34	303-01180 COMPACTED AGGREGATE, NO. 53	59.000	TON
35	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	2,050.000	TON
36	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	1,732.000	TON
37	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	4,246.000	TON
38	401-10258 JOINT ADHESIVE, SURFACE	13,650.000	LFT
39	401-10259 JOINT ADHESIVE, INTERMEDIATE	13,650.000	LFT
40	406-05520 ASPHALT FOR TACK COAT	8.000	TON
41	601-01522 GUARDRAIL, TRANSITION TYPE TGB	6.000	EACH
42	601-01839 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 6	1.000	EACH
43	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	4.000	EACH
44	601-02024 GUARDRAIL, TRANSITION, TGB, MODIFIED	2.000	EACH
45	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
46	601-94689 GUARDRAIL END TREATMENT, OS	5.000	EACH
47	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	1,269.000	LFT
48	604-01268 HAND RAIL, ALUMINUM	23.000	LFT
49	604-44251 STEPS, CONCRETE	2.100	CYS

CALL ORDER : 251

CONTRACT ID : R -33387-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	605-06120 CURB, CONCRETE	1,219.000	LFT
51	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	384.000	SYS
52	610-07487 HMA FOR APPROACHES, TYPE B	179.000	TON
53	610-08446 PCCP FOR APPROACHES, 6 IN	105.000	SYS
54	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
55	611-06498 MAILBOX ASSEMBLY, DOUBLE	4.000	EACH
56	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	7.000	EACH
57	615-06490 RIGHT OF WAY MARKER	54.000	EACH
58	615-06520 MONUMENT, RE-ESTABLISH	2.000	EACH
59	615-06530 BENCH MARK POST	1.000	EACH
60	616-02320 GEOTEXTILES	1,853.000	SYS
61	616-05688 RIPRAP, CLASS 1	949.000	TON
62	616-06405 RIPRAP, REVETMENT	540.000	TON
63	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
64	621-02770 EROSION CONTROL BLANKET	1,364.000	SYS
65	621-06545 FERTILIZER	1.700	TON
66	621-06553 SEED MIXTURE, R	728.000	LBS
67	621-06557 SEED MIXTURE, T	400.000	LBS
68	621-06565 MULCHING MATERIAL	13.400	TON
69	621-06567 WATER	4.000	KGAL
70	621-06574 SODDING	1,154.000	SYS
71	621-08161 PERMANENT TURF REINFORCEMENT MAT	2,234.000	SYS
72	621-09399 SEED MIXTURE, WET MESIC	17.000	LBS
73	622-05641 PLANT, DECIDUOUS SHRUB, 36 TO 48 IN	8.000	EACH
74	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	9.000	EACH
75	622-52436 SIGN, DO NOT MOW OR SPRAY	4.000	EACH
76	622-91786 SEEDLING	152.000	EACH
77	628-09401 FIELD OFFICE, A	20.000	MOS
78	701-06011 DYNAMIC PILE LOAD TEST	1.000	EACH
79	701-09557 TEST PILE, DYNAMIC, PRODUCTION	65.000	LFT
80	701-09559 TEST PILE, DYNAMIC, RESTRIKE	1.000	EACH
81	701-09654 PILE, STEEL PIPE, 0.184 IN, 12 IN	156.000	LFT
82	701-09663 PILE, STEEL PIPE, 0.312 IN, 14 IN	495.000	LFT
83	701-51195 PILE, STEEL H, HP 12 IN X 53	440.000	LFT
84	702-51005 CONCRETE, A, SUBSTRUCTURE	65.500	CYS
85	702-51015 CONCRETE, B, FOOTINGS	4.800	CYS
86	702-51863 FIELD DRILLED HOLE IN CONCRETE	464.000	EACH
87	703-06028 REINFORCING BARS	5,140.000	LBS
88	703-06029 REINFORCING BARS, EPOXY COATED	89,272.000	LBS
89	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	32.000	EACH
90	704-51002 CONCRETE, C, SUPERSTRUCTURE	228.100	CYS
91	706-06352 CONCRETE BRIDGE RAILING TRANSITION, TPF-2	8.000	EACH
92	706-11405 RAILING, STEEL, PF-2	386.000	LFT
93	706-51020 RAILING, CONCRETE, C	16.900	CYS
94	707-08158 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 42 IN X 49 IN	515.000	LFT
95	709-51821 SURFACE SEAL	LUMP	LUMP
96	709-51821 SURFACE SEAL	LUMP	LUMP
97	711-51070 ANCHOR PLATE, AP 1	20.000	EACH
98	714-11475 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	128.000	LFT

CALL ORDER : 251

CONTRACT ID : R -33387-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
99	715-05147 PIPE, TYPE 2 CIRCULAR 8 IN	71.000	LFT
100	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,280.000	LFT
101	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	409.000	LFT
102	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	134.000	LFT
103	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	1,325.000	LFT
104	715-05162 PIPE, TYPE 2 CIRCULAR 54 IN	38.000	LFT
105	715-05168 PIPE, TYPE 3 CIRCULAR 12 IN	72.000	LFT
106	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	313.000	LFT
107	715-05407 PIPE, END BENT DRAIN, 6 IN	120.000	LFT
108	715-06492 CONCRETE ANCHOR, 54 IN	2.000	EACH
109	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	10.000	TON
110	715-46000 PIPE END SECTION, DIA 12"	5.000	EACH
111	715-46005 PIPE END SECTION, DIA 15"	2.000	EACH
112	720-11717 DRY HYDRANT, RELOCATE	1.000	EACH
113	720-45035 INLET, F7	7.000	EACH
114	720-45270 PIPE CATCH BASIN, 18 IN	1.000	EACH
115	720-45410 MANHOLE, C4	3.000	EACH
116	720-90984 MANHOLE, C2	6.000	EACH
117	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	84.000	SFT
118	722-51842 BRIDGE DECK OVERLAY	292.000	SYS
119	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	5.200	CYS
120	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	420.000	SFT
121	722-60824 SURFACE MILLING	187.000	SYS
122	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
123	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
124	801-06625 DETOUR ROUTE MARKER ASSEMBLY	16.000	EACH
125	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
126	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
127	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
128	801-07118 BARRICADE, III-A	144.000	LFT
129	801-07119 BARRICADE, III-B	96.000	LFT
130	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	40.000	SFT
131	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	16.000	SFT
132	802-76065 SIGN POST, B	172.000	LFT
133	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN	31.000	LFT
134	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	9,427.000	LFT
135	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	9,332.000	LFT

CALL ORDER : 271

CONTRACT ID : R -33792-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 AUXILIARY LANES			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-02250 TREE, 10 IN, REMOVE	21.000	EACH
10	201-02255 TREE, 18 IN, REMOVE	2.000	EACH
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02279 CURB AND GUTTER, REMOVE	1,600.000	LFT
13	202-02928 CATCH BASIN, REMOVE	8.000	EACH
14	202-93615 CONCRETE, REMOVE	968.000	SYS
15	203-02000 EXCAVATION, COMMON	262.000	CYS
16	205-06933 TEMPORARY INLET PROTECTION	14.000	EACH
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,645.000	SYS
18	211-09264 STRUCTURAL BACKFILL, TYPE 1	76.000	CYS
19	304-07491 HMA PATCHING, TYPE C	40.000	TON
20	304-07494 WIDENING WITH HMA, TYPE C	1,070.000	TON
21	406-05520 ASPHALT FOR TACK COAT	0.220	TON
22	604-06070 SIDEWALK, CONCRETE	527.000	SYS
23	604-07897 CURB RAMP, CONCRETE, C	31.000	SYS
24	604-07902 CURB RAMP, CONCRETE, H	30.000	SYS
25	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	1,560.000	LFT
26	610-08446 PCCP FOR APPROACHES, 6 IN	396.000	SYS
27	610-09108 PCCP FOR APPROACHES, 9 IN	409.000	SYS
28	621-06567 WATER	3.500	KGAL
29	621-06575 SODDING, NURSERY	961.000	SYS
30	622-05650 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 TO 2.5 IN	17.000	EACH
31	628-09402 FIELD OFFICE, B	6.000	MOS
32	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	6.000	MOS
33	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	161.000	LFT
34	715-05756 PIPE EXTENSION, CIRCULAR 12 IN	31.000	LFT
35	715-94530 ADJUST WATER VALVE TO GRADE	7.000	EACH
36	720-45005 INLET, A2	1.000	EACH
37	720-45400 MANHOLE, A4	1.000	EACH
38	720-99416 CATCH BASIN, B15	8.000	EACH
39	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
40	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	430.000	LFT
41	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
42	801-06710 FLASHING ARROW SIGN	60.000	DAY
43	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
44	801-07118 BARRICADE, III-A	20.000	LFT
45	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	48.000	LFT
46	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
47	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	34.000	SFT
48	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	691.000	LFT
49	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN	28.000	LFT

CALL ORDER : 271

CONTRACT ID : R -33792-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	AUXILIARY LANES		
50	808-06716 LINE, REMOVE	3,500.000	LFT
51	808-75043 LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN	143.000	LFT
52	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	440.000	LFT
53	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	3,220.000	LFT
54	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH
55	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH

CALL ORDER : 281

CONTRACT ID : R -33814-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE AND PEDESTRIAN FACILITIES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-51133 RAILING, REMOVE	7.000	LFT
10	202-99080 CONCRETE, REMOVE	0.700	CYS
11	203-02000 EXCAVATION, COMMON	32.000	CYS
12	205-03371 SEDIMENT, REMOVE	58.000	CYS
13	205-06937 TEMPORARY SILT FENCE	1,578.000	LFT
14	206-04301 SHEET PILING, STEEL, S=18.1	4,827.000	SFT
15	207-08267 SUBGRADE TREATMENT, TYPE IIIA	339.000	SYS
16	211-09266 STRUCTURAL BACKFILL, TYPE 3	254.000	CYS
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	73.000	TON
18	502-11543 PCCP, 4 IN.	320.000	SYS
19	601-01704 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, MODIFIED	1.000	EACH
20	601-02241 GUARDRAIL, REMOVE	115.000	LFT
21	601-06035 GUARDRAIL, RESET	1,310.000	LFT
22	601-06728 GUARDRAIL, WR-BEAM	50.000	LFT
23	603-97461 TEMPORARY FENCE	230.000	LFT
24	604-01268 HAND RAIL, ALUMINUM	2,533.000	LFT
25	615-06490 RIGHT OF WAY MARKER	5.000	EACH
26	621-06559 MULCHED SEEDING, R	313.000	SYS
27	622-05653 PLANT, GROUND COVER	711.000	EACH
28	628-09402 FIELD OFFICE, B	12.000	MOS
29	701-06011 DYNAMIC PILE LOAD TEST	4.000	EACH
30	701-09557 TEST PILE, DYNAMIC, PRODUCTION	220.000	LFT
31	701-09559 TEST PILE, DYNAMIC, RESTRIKE	4.000	EACH
32	701-11004 PILE, STEEL PIPE, 0.312 IN, 16 IN.	4,218.000	LFT
33	701-11345 CONICAL PILE TIP, 16 IN.	92.000	EACH
34	702-51005 CONCRETE, A, SUBSTRUCTURE	139.100	CYS
35	702-51863 FIELD DRILLED HOLE IN CONCRETE	4.000	EACH
36	703-06029 REINFORCING BARS, EPOXY COATED	25,049.000	LBS
37	704-51002 CONCRETE, C, SUPERSTRUCTURE	146.300	CYS
38	707-11715 STRUCTURAL MEMBERS	2,367.000	LFT
39	709-51821 SURFACE SEAL	LUMP	LUMP
40	711-04845 BRIDGE, STEEL TRUSS, PRE-ENGINEERED	LUMP	LUMP
41	711-91981 TIE ROD	14.000	EACH
42	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	297.000	LFT
43	731-03133 CONCRETE FACING	1,394.000	SFT
44	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
45	801-03290 CONSTRUCTION SIGN, C	9.000	EACH
46	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
47	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	1,617.000	LFT
48	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24"	24.000	LFT
49	801-06625 DETOUR ROUTE MARKER ASSEMBLY	3.000	EACH

CALL ORDER : 281

CONTRACT ID : R -33814-B

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ENHANCEMENT, BIKE AND PEDESTRIAN FACILITIES		
50	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
51	801-06645 CONSTRUCTION SIGN, B	26.000	EACH
52	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
53	801-07118 BARRICADE, III-A	24.000	LFT
54	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	925.000	LFT
55	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	610.000	LFT
56	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	8.000	LFT
57	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	2.250	SFT
58	805-04973 CONDUIT	2,850.000	LFT
59	805-04973 CONDUIT	2,433.000	LFT
60	807-03950 LUMINAIRE, ORNAMENTAL	22.000	EACH
61	807-03951 LIGHT POLE, ORNAMENTAL	22.000	EACH
62	807-86810 SERVICE POINT, II	3.000	EACH
63	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	3,302.000	LFT
64	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	1,651.000	LFT
65	808-06716 LINE, REMOVE	300.000	LFT

CALL ORDER : 291

CONTRACT ID : R -34077-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT AND ROADWAY REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02273 CENTER CURB, CONCRETE, REMOVE	1,153.000	SYS
12	202-02278 CURB, CONCRETE, REMOVE	905.000	LFT
13	202-52710 SIDEWALK, CONCRETE, REMOVE	29.000	SYS
14	202-91385 INLET, REMOVE	1.000	EACH
15	202-96133 PIPE, REMOVE	135.000	LFT
16	203-02000 EXCAVATION, COMMON	2,775.000	CYS
17	203-02070 BORROW	1,705.000	CYS
18	203-07042 EMBANKMENT FOUNDATION SOILS TREATMENT	2,031.000	SYS
19	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	21.000	EACH
20	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	5.000	TON
21	205-06937 TEMPORARY SILT FENCE	4,587.000	LFT
22	205-09543 NO 2 STONE	50.000	TON
23	207-08263 SUBGRADE TREATMENT, TYPE IA	8,124.000	SYS
24	207-08267 SUBGRADE TREATMENT, TYPE IIIA	412.000	SYS
25	211-09264 STRUCTURAL BACKFILL, TYPE 1	296.000	CYS
26	211-09268 STRUCTURAL BACKFILL, TYPE 5	20.000	CYS
27	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	92.000	TON
28	306-08034 MILLING, ASPHALT, 1 1/2 IN	12,223.000	SYS
29	306-08043 MILLING, TRANSITION	1,606.000	SYS
30	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	1,586.000	TON
31	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	950.000	TON
32	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	1,515.000	TON
33	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	1,262.000	TON
34	402-07440 HMA BASE, TYPE A	374.000	TON
35	406-05520 ASPHALT FOR TACK COAT	8.500	TON
36	502-06457 PCCP, 9 IN	224.000	SYS
37	503-05240 D-1 CONTRACTION JOINT	180.000	LFT
38	601-01522 GUARDRAIL, TRANSITION TYPE TGB	1.000	EACH
39	601-02103 GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN SPACING	31.250	LFT
40	601-02241 GUARDRAIL, REMOVE	280.800	LFT
41	601-06035 GUARDRAIL, RESET	62.500	LFT
42	601-94689 GUARDRAIL END TREATMENT, OS	2.000	EACH
43	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	137.500	LFT
44	604-06070 SIDEWALK, CONCRETE	883.000	SYS
45	604-07900 CURB RAMP, CONCRETE, F	24.000	SYS
46	604-07901 CURB RAMP, CONCRETE, G	8.000	SYS
47	605-06120 CURB, CONCRETE	4,822.000	LFT
48	605-06121 CURB, CONCRETE, B	302.000	LFT
49	605-06125 CURB, CONCRETE, MODIFIED	325.000	LFT

CALL ORDER : 291

CONTRACT ID : R -34077-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT AND ROADWAY REHABILITATION		
50	605-06255 CENTER CURB, D, CONCRETE	40.000	SYS
51	605-08636 CURB AND GUTTER, TURNOUT, COMBINED	36.000	LFT
52	605-52807 CURB AND GUTTER, COMBINED	5,196.000	LFT
53	605-94811 CURB TURNOUT	5.000	EACH
54	610-09108 PCCP FOR APPROACHES, 9 IN	105.000	SYS
55	616-02320 GEOTEXTILES	30.000	SYS
56	616-06405 RIPRAP, REVETMENT	30.000	TON
57	618-99085 FLAG POLE	2.000	EACH
58	618-99085 FLAG POLE	1.000	EACH
59	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.000	EACH
60	621-02770 EROSION CONTROL BLANKET	1,678.000	SYS
61	621-03909 SEED MIXTURE, NATIVE	23.000	LBS
62	621-04316 SPADE EDGE	1,275.000	LFT
63	621-06553 SEED MIXTURE, R	185.000	LBS
64	621-06570 TOPSOIL	180.000	CYS
65	621-06575 SODDING, NURSERY	1,165.000	SYS
66	621-98038 MULCH, HARDWOOD SHREDDED BARK	232.000	CYS
67	622-01937 PLANT	4,365.000	EACH
68	622-01937 PLANT	3,590.000	EACH
69	622-04992 DRAIN	12.000	EACH
70	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	234.000	EACH
71	622-05641 PLANT, DECIDUOUS SHRUB, 36 TO 48 IN	10.000	EACH
72	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	99.000	EACH
73	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN	31.000	EACH
74	622-05654 PLANT, PERENNIAL	5,396.000	EACH
75	622-52436 SIGN, DO NOT MOW OR SPRAY	5.000	EACH
76	628-09401 FIELD OFFICE, A	18.000	MOS
77	706-09545 COARSE AGGREGATE, NO 8	31.000	CYS
78	715-05147 PIPE, TYPE 2 CIRCULAR 8 IN	259.000	LFT
79	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	910.000	LFT
80	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	263.000	LFT
81	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	550.000	LFT
82	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	25.000	TON
83	715-09064 VIDEO INSPECTION FOR PIPE	1,635.000	LFT
84	715-46000 PIPE END SECTION, DIA 12"	2.000	EACH
85	715-46005 PIPE END SECTION, DIA 15"	2.000	EACH
86	720-44000 CASTING, ADJUST TO GRADE	12.000	EACH
87	720-44296 INLET, CAP	1.000	EACH
88	720-45030 INLET, E7	1.000	EACH
89	720-45035 INLET, F7	1.000	EACH
90	720-45045 INLET, J10	6.000	EACH
91	720-45055 INLET, M10	6.000	EACH
92	720-45410 MANHOLE, C4	2.000	EACH
93	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
94	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
95	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	12,809.000	LFT
96	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	9.000	EACH
97	801-06212 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (ONLY)	2.000	EACH
98	801-06625 DETOUR ROUTE MARKER ASSEMBLY	38.000	EACH

CALL ORDER : 291

CONTRACT ID : R -34077-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT AND ROADWAY REHABILITATION		
99	801-06640 CONSTRUCTION SIGN, A	31.000	EACH
100	801-06645 CONSTRUCTION SIGN, B	5.000	EACH
101	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
102	801-07118 BARRICADE, III-A	168.000	LFT
103	801-07119 BARRICADE, III-B	312.000	LFT
104	802-04089 SIGN, SHEET, REMOVE	13.000	EACH
105	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	296.000	LFT
106	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	175.000	LFT
107	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	82.250	SFT
108	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	160.880	SFT
109	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	34.500	SFT
110	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
111	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
112	805-06595 CONDUIT, PVC, 2 IN	3,271.000	LFT
113	805-06595 CONDUIT, PVC, 2 IN	799.000	LFT
114	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	1,040.000	LFT
115	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	720.000	LFT
116	805-96014 SAW CUT, FULL DEPTH	5,837.000	LFT
117	807-02191 HANDHOLE, LIGHTING	15.000	EACH
118	807-02934 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING	33.000	EACH
119	807-03950 LUMINAIRE, ORNAMENTAL	66.000	EACH
120	807-03950 LUMINAIRE, ORNAMENTAL	4.000	EACH
121	807-03950 LUMINAIRE, ORNAMENTAL	6.000	EACH
122	807-03951 LIGHT POLE, ORNAMENTAL	33.000	EACH
123	807-86805 SERVICE POINT, I	2.000	EACH
124	807-86838 WIRE, NO 4 COPPER IN CONDUIT, 1/C	16,580.000	LFT
125	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	8.000	EACH
126	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,727.000	LFT
127	808-06716 LINE, REMOVE	755.000	LFT
128	808-09083 LINE THERMOPLASTIC BROKEN WHITE 8 IN	52.000	LFT
129	808-10118 TRANSVERSE MARKING, THERMOPLASTIC, YIELD, WHITE,	48.000	LFT
130	808-74812 TRANSVERSE MARKING, PREFORMED PLASTIC, YELLOW	174.000	LFT
131	808-75051 LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN	329.000	LFT
132	808-75071 PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC,	15.000	EACH
133	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	198.000	LFT
134	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	3,054.000	LFT
135	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	134.000	LFT

CALL ORDER : 301

CONTRACT ID : R -34085-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PIPE LINING			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	205-06937 TEMPORARY SILT FENCE	200.000	LFT
9	205-11584 TEMPORARY CHECK DAM, TRAVERSABLE	40.000	LFT
10	616-02320 GEOTEXTILES	65.000	SYS
11	616-05689 RIPRAP, CLASS 2	30.000	TON
12	616-06405 RIPRAP, REVETMENT	20.000	TON
13	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
14	621-06559 MULCHED SEEDING, R	200.000	SYS
15	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
16	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	9.000	MOS
17	628-09409 MOBILE INTERNET SERVICE	9.000	MOS
18	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	9.000	MOS
19	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
20	725-11399 PIPE LINER, CURED-IN-PLACE, 84 IN	176.000	LFT
21	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
22	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
23	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 321

CONTRACT ID : R -34383-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SMALL STRUCTURE PIPE LINING			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-96133 PIPE, REMOVE	22.000	LFT
10	203-02000 EXCAVATION, COMMON	125.000	CYS
11	203-02070 BORROW	28.000	CYS
12	205-06937 TEMPORARY SILT FENCE	500.000	LFT
13	206-93520 TEMPORARY SHEET PILING	960.000	SFT
14	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	20.000	CYS
15	616-02320 GEOTEXTILES	70.000	SYS
16	616-05689 RIPRAP, CLASS 2	40.000	TON
17	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
18	621-06559 MULCHED SEEDING, R	2,000.000	SYS
19	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
20	628-09402 FIELD OFFICE, B	5.000	MOS
21	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	5.000	MOS
22	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	10.000	MOS
23	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
24	715-06492 CONCRETE ANCHOR, 54 IN	1.000	EACH
25	725-11038 LINER PIPE THERMOPLASTIC CIRCULAR 15.9-16.0 SFT	380.000	LFT
26	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
27	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
28	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
29	801-06710 FLASHING ARROW SIGN	120.000	DAY
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH

CALL ORDER : 331

CONTRACT ID : R -34470-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-91385 INLET, REMOVE	2.000	EACH
12	202-93047 MANHOLE, REMOVE	2.000	EACH
13	202-96133 PIPE, REMOVE	50.000	LFT
14	203-02020 EXCAVATION, UNCLASSIFIED	1,800.000	CYS
15	205-06933 TEMPORARY INLET PROTECTION	13.000	EACH
16	205-06937 TEMPORARY SILT FENCE	975.000	LFT
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	180.000	SYS
18	207-09935 SUBGRADE TREATMENT, TYPE 1C	3,300.000	SYS
19	211-09264 STRUCTURAL BACKFILL, TYPE 1	175.000	CYS
20	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	165.000	TON
21	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	42.000	TON
22	306-08043 MILLING, TRANSITION	325.000	SYS
23	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
24	401-10258 JOINT ADHESIVE, SURFACE	900.000	LFT
25	401-10259 JOINT ADHESIVE, INTERMEDIATE	775.000	LFT
26	402-07433 HMA SURFACE, TYPE B	250.000	TON
27	402-07438 HMA INTERMEDIATE, TYPE B	350.000	TON
28	402-07441 HMA BASE, TYPE B	425.000	TON
29	604-02007 SIDEWALK, CONCRETE, RECONSTRUCT	275.000	SYS
30	604-07896 CURB RAMP, CONCRETE, B	20.000	SYS
31	604-07897 CURB RAMP, CONCRETE, C	5.000	SYS
32	604-07899 CURB RAMP, CONCRETE, E	20.000	SYS
33	604-07900 CURB RAMP, CONCRETE, F	20.000	SYS
34	604-07901 CURB RAMP, CONCRETE, G	25.000	SYS
35	605-06140 CURB AND GUTTER, CONCRETE	1,400.000	LFT
36	610-08446 PCCP FOR APPROACHES, 6 IN	50.000	SYS
37	610-09108 PCCP FOR APPROACHES, 9 IN	160.000	SYS
38	621-06567 WATER	1.000	KGAL
39	621-06575 SODDING, NURSERY	300.000	SYS
40	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	325.000	LFT
41	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	50.000	LFT
42	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	25.000	LFT
43	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
44	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
45	720-45415 MANHOLE, D4	5.000	EACH
46	720-98174 INLET, B15	6.000	EACH
47	720-98555 INLET, C15	6.000	EACH
48	801-04308 ROAD CLOSURE SIGN ASSEMBLY	18.000	EACH
49	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	1,839.000	LFT

CALL ORDER : 331

CONTRACT ID : R -34470-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	801-06625	DETOUR ROUTE MARKER ASSEMBLY	18.000 EACH
51	801-06645	CONSTRUCTION SIGN, B	10.000 EACH
52	801-06775	MAINTAINING TRAFFIC	LUMP LUMP
53	801-07118	BARRICADE, III-A	50.000 LFT
54	801-07119	BARRICADE, III-B	200.000 LFT
55	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	6.000 EACH
56	805-01815	SIGNAL SUPPORT FOUNDATION, 36 IN X 144 IN	1.000 EACH
57	805-01842	HANDHOLE, SIGNAL	4.000 EACH
58	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	165.000 LFT
59	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP LUMP
60	805-02152	PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	6.000 EACH
61	805-78100	CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000 EACH
62	805-78415	SPAN, CATENARY, AND TETHER	2.000 EACH
63	805-78420	DISCONNECT HANGER	2.000 EACH
64	805-78445	SIGNAL SERVICE	1.000 EACH
65	805-78470	SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	600.000 LFT
66	805-78485	SIGNAL CABLE, 5C/14GA	200.000 LFT
67	805-78490	SIGNAL CABLE, 7C/14GA	425.000 LFT
68	805-78510	SIGNAL CABLE, 2C/16GA., SHIELDED	1,350.000 LFT
69	805-78785	SIGNAL DETECTOR HOUSING	2.000 EACH
70	805-78795	SAW CUT FOR ROADWAY LOOP AND SEALANT	330.000 LFT
71	805-81060	SIGNAL STRAIN POLE, STEEL, 36 FT	1.000 EACH
72	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	22.000 EACH
73	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	164.000 LFT
74	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN	324.000 LFT
75	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN	664.000 LFT
76	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	3.000 EACH
77	808-06724	PAVEMENT MESSAGE MARKING, PAINT, ONLY	1.000 EACH
78	808-06726	TRANSVERSE MARKING, PAINT,	70.000 LFT
79	808-75074	TRANSVERSE MARKING, PAINT,	465.000 LFT
80	808-75078	TRANSVERSE MARKING, PAINT,	90.000 LFT
81	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	328.000 LFT
82	808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	48.000 LFT
83	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000 EACH
84	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000 EACH

CALL ORDER : 341

CONTRACT ID : R -34568-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PATCH AND REHAB PAVEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
9	203-08279 EXPANDED POLYSTYRENE FILL	7.800	CYS
10	207-08263 SUBGRADE TREATMENT, TYPE IA	6,439.000	SYS
11	216-08528 HDPE GEO-MEMBRANE	936.000	SYS
12	302-07455 DENSE GRADED SUBBASE	80.000	CYS
13	304-07783 HMA PATCHING, TYPE D	854.000	TON
14	306-08039 MILLING, ASPHALT REMOVAL	1,827.000	SYS
15	406-05520 ASPHALT FOR TACK COAT	2.000	TON
16	503-05240 D-1 CONTRACTION JOINT	2,052.000	LFT
17	506-06333 PCCP PATCHING, FULL DEPTH	6,439.000	SYS
18	507-07482 CRACKS IN PCCP, ROUT AND SEAL	13,723.000	LFT
19	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	468.000	SYS
20	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
21	628-09403 FIELD OFFICE, C	15.000	MOS
22	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	45.000	MOS
23	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
24	702-51863 FIELD DRILLED HOLE IN CONCRETE	135.000	EACH
25	703-06029 REINFORCING BARS, EPOXY COATED	16,718.000	LBS
26	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	100.000	LFT
27	718-03277 PIPE, UNDERDRAIN, CORRUGATED PLASTIC, PERFORATED, 6 IN.	1,730.000	LFT
28	718-06526 HMA FOR UNDERDRAINS	288.000	TON
29	718-06531 OUTLET PROTECTOR, 3	5.000	EACH
30	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	1,730.000	LFT
31	718-52610 AGGREGATE FOR UNDERDRAINS	160.200	CYS
32	718-99153 GEOTEXTILES FOR UNDERDRAIN	929.000	SYS
33	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	139.000	LFT
34	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
35	801-06640 CONSTRUCTION SIGN, A	57.000	EACH
36	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
37	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	236.000	EACH
38	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	236.000	EACH

CALL ORDER : 351

CONTRACT ID : R -34605-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT, ROUNDABOUT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	107-09358 INSPECTION HOLE, GREATER THAN 3'	25.000	EACH
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	3,400.000	SYS
12	203-02000 EXCAVATION, COMMON	3,573.000	CYS
13	203-08607 LINEAR GRADING	1,280.000	LFT
14	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	12.000	EACH
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	58.000	TON
16	205-06933 TEMPORARY INLET PROTECTION	14.000	EACH
17	205-06937 TEMPORARY SILT FENCE	4,105.000	LFT
18	207-08263 SUBGRADE TREATMENT, TYPE IA	7,429.000	SYS
19	211-09264 STRUCTURAL BACKFILL, TYPE 1	706.400	CYS
20	303-01180 COMPACTED AGGREGATE, NO. 53	729.000	TON
21	306-08432 MILLING, APPROACH	280.000	SYS
22	402-07432 HMA SURFACE, TYPE A	126.000	TON
23	402-07433 HMA SURFACE, TYPE B	490.000	TON
24	402-07435 HMA INTERMEDIATE, TYPE A	210.000	TON
25	402-07438 HMA INTERMEDIATE, TYPE B	886.000	TON
26	402-07441 HMA BASE, TYPE B	2,366.000	TON
27	402-10084 HMA FOR TEMPORARY PAVEMENT, B	75.000	TON
28	406-05520 ASPHALT FOR TACK COAT	3.140	TON
29	502-06328 PCCP, 11 IN	516.000	SYS
30	604-07897 CURB RAMP, CONCRETE, C	27.000	SYS
31	604-07903 CURB RAMP, CONCRETE, K	36.000	SYS
32	604-07904 CURB RAMP, CONCRETE, L	24.000	SYS
33	605-06120 CURB, CONCRETE	189.000	LFT
34	605-06165 CURB AND GUTTER, C, CONCRETE, MODIFIED	1,335.000	LFT
35	605-97937 CURB AND GUTTER, ROLL CURB	1,147.000	LFT
36	610-07487 HMA FOR APPROACHES, TYPE B	15.000	TON
37	615-01469 MONUMENT, SECTION CORNER, INSTALL	1.000	EACH
38	615-06490 RIGHT OF WAY MARKER	13.000	EACH
39	616-02320 GEOTEXTILES	96.000	SYS
40	616-06405 RIPRAP, REVETMENT	72.500	TON
41	621-02770 EROSION CONTROL BLANKET	1,661.000	SYS
42	621-06545 FERTILIZER	1.000	TON
43	621-06554 SEED MIXTURE, U	12,000.000	LBS
44	621-06565 MULCHING MATERIAL	5.000	TON
45	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	660.000	LFT
46	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,423.000	LFT
47	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	917.000	LFT
48	715-05233 PIPE, TYPE 1 DEFORMED MIN AREA 3.3 SFT	42.000	LFT
49	715-06471 PIPE END SECTION, MIN AREA 3.3 SFT	2.000	EACH

CALL ORDER : 351

CONTRACT ID : R -34605-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT, ROUNDABOUT		
50	715-08048 STORMWATER TREATMENT SYSTEM	1.000	EACH
51	715-46010 PIPE END SECTION, DIA 18"	1.000	EACH
52	718-52610 AGGREGATE FOR UNDERDRAINS	78.250	CYS
53	718-99153 GEOTEXTILES FOR UNDERDRAIN	487.900	SYS
54	720-01091 MANHOLE, C10, MODIFIED	3.000	EACH
55	720-45030 INLET, E7	5.000	EACH
56	720-45035 INLET, F7	4.000	EACH
57	720-45045 INLET, J10	2.000	EACH
58	720-45055 INLET, M10	4.000	EACH
59	720-45135 INLET, F7, MODIFIED	1.000	EACH
60	720-45155 INLET, M10, MODIFIED	3.000	EACH
61	720-45410 MANHOLE, C4	1.000	EACH
62	720-90984 MANHOLE, C2	5.000	EACH
63	720-91973 MANHOLE, H4	1.000	EACH
64	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
65	802-05705 SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	281.320	LFT
66	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	89.140	SFT
67	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	89.440	SFT
68	804-06771 DELINEATOR POST, FLEXIBLE	4.000	EACH
69	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,508.000	LFT
70	808-09506 PAVEMENT MESSAGE MARKINGS, THERMOPLASTIC,	4.000	EACH
71	808-11691 LINE, THERMOPLASTIC, DOTTED, WHITE, 12"	72.000	LFT
72	808-11698 TRANSVERSE MARKINGS, THERMOPLASTIC	33.000	LFT
73	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	2,275.000	LFT
74	808-75274 TRANSVERSE MARKING, THERMOPLASTIC,	600.000	LFT
75	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	127.000	LFT
76	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH

CALL ORDER : 381

CONTRACT ID : R -35190-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BIKE/PEDESTRIAN FACILITIES			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	185.000	CYS
10	203-02070 BORROW	70.000	CYS
11	207-08267 SUBGRADE TREATMENT, TYPE IIIA	273.000	SYS
12	303-07449 COMPACTED AGGREGATE, NO. 73	117.000	TON
13	305-07456 PCC BASE, 8 IN	94.000	SYS
14	402-07433 HMA SURFACE, TYPE B	8.000	TON
15	604-06070 SIDEWALK, CONCRETE	777.000	SYS
16	604-07896 CURB RAMP, CONCRETE, B	7.000	SYS
17	604-07900 CURB RAMP, CONCRETE, F	9.000	SYS
18	604-07901 CURB RAMP, CONCRETE, G	179.000	SYS
19	604-07902 CURB RAMP, CONCRETE, H	63.000	SYS
20	604-07903 CURB RAMP, CONCRETE, K	11.000	SYS
21	605-92578 CURB WALK, CONCRETE	302.000	SYS
22	610-08446 PCCP FOR APPROACHES, 6 IN	99.000	SYS
23	610-09108 PCCP FOR APPROACHES, 9 IN	175.000	SYS
24	621-06567 WATER	2.200	KGAL
25	621-06575 SODDING, NURSERY	555.000	SYS
26	715-97544 PIPE, DUCTILE IRON, 8 IN	101.000	LFT
27	720-07309 TRENCH DRAIN	5.000	LFT
28	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
29	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
30	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	186.000	LFT
33	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	2.000	EACH
34	802-07060 SIGN, SHEET, RELOCATE	4.000	EACH
35	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	15.000	SFT

CALL ORDER : 391

CONTRACT ID : R -35316-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-04345 UNDERGROUND STORAGE TANK, LIQUID WASTE	3,000.000	GAL
13	202-05823 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE,	1.000	EACH
14	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
15	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
16	203-02000 EXCAVATION, COMMON	1,706.000	CYS
17	203-02010 EXCAVATION, ROCK	50.000	CYS
18	203-02040 EXCAVATION, Y	10.000	CYS
19	203-02070 BORROW	7,854.000	CYS
20	203-51223 EXCAVATION, WATERWAY	1,726.000	CYS
21	205-06930 SPLASHPAD	3.000	TON
22	205-06936 TEMPORARY SEDIMENT TRAP	220.000	TON
23	205-06937 TEMPORARY SILT FENCE	1,933.000	LFT
24	205-06938 TEMPORARY SLOPE DRAIN	130.000	LFT
25	205-09543 NO 2 STONE	100.000	TON
26	206-51215 EXCAVATION, X	167.500	CYS
27	206-51220 EXCAVATION, WET	73.100	CYS
28	207-08265 SUBGRADE TREATMENT, TYPE IIA	3,257.000	SYS
29	207-08267 SUBGRADE TREATMENT, TYPE IIIA	100.000	SYS
30	211-02050 B BORROW	1,045.400	CYS
31	211-06467 AGGREGATE FOR END BENT BACKFILL	28.000	CYS
32	211-09264 STRUCTURAL BACKFILL, TYPE 1	50.600	CYS
33	211-09265 STRUCTURAL BACKFILL, TYPE 2	362.000	CYS
34	211-09266 STRUCTURAL BACKFILL, TYPE 3	1,971.300	CYS
35	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	672.000	TON
36	302-07455 DENSE GRADED SUBBASE	35.900	CYS
37	303-01180 COMPACTED AGGREGATE, NO. 53	273.000	TON
38	401-10258 JOINT ADHESIVE, SURFACE	2,236.000	LFT
39	401-10259 JOINT ADHESIVE, INTERMEDIATE	2,236.000	LFT
40	402-07433 HMA SURFACE, TYPE B	231.000	TON
41	402-07438 HMA INTERMEDIATE, TYPE B	386.000	TON
42	402-07441 HMA BASE, TYPE B	466.000	TON
43	406-05521 ASPHALT FOR TACK COAT	5,587.000	SYS
44	601-01115 GUARDRAIL, W-BEAM, 1 FT 6.75 IN SPACING	12.500	LFT
45	601-01522 GUARDRAIL, TRANSITION TYPE TGB	3.000	EACH
46	601-01522 GUARDRAIL, TRANSITION TYPE TGB	1.000	EACH
47	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
48	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	393.800	LFT
49	604-06070 SIDEWALK, CONCRETE	12.000	SYS

CALL ORDER : 391

CONTRACT ID : R -35316-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	604-95344 HAND RAIL, PEDESTRIAN	286.000	LFT
51	605-06121 CURB, CONCRETE, B	32.000	LFT
52	605-06145 CURB AND GUTTER, B, CONCRETE	480.000	LFT
53	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	221.900	SYS
54	610-09108 PCCP FOR APPROACHES, 9 IN	100.000	SYS
55	615-06490 RIGHT OF WAY MARKER	15.000	EACH
56	615-06505 MONUMENT, B	6.000	EACH
57	616-02320 GEOTEXTILES	2,666.000	SYS
58	616-05688 RIPRAP, CLASS 1	27.000	TON
59	616-06405 RIPRAP, REVETMENT	810.000	TON
60	616-06451 RIPRAP, UNIFORM	433.000	TON
61	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
62	621-02770 EROSION CONTROL BLANKET	817.000	SYS
63	621-06554 SEED MIXTURE, U	34.000	LBS
64	621-06557 SEED MIXTURE, T	135.000	LBS
65	621-06559 MULCHED SEEDING, R	1,932.000	SYS
66	621-06560 MULCHED SEEDING, U	480.000	SYS
67	621-06565 MULCHING MATERIAL	1.800	TON
68	621-06567 WATER	6.100	KGAL
69	621-06574 SODDING	213.000	SYS
70	621-06575 SODDING, NURSERY	1,465.000	SYS
71	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	114.000	EACH
72	622-52436 SIGN, DO NOT MOW OR SPRAY	12.000	EACH
73	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
74	628-09402 FIELD OFFICE, B	12.000	MOS
75	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	24.000	MOS
76	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
77	701-02938 CORED HOLE IN ROCK, 24 IN	18.000	LFT
78	701-09558 TEST PILE, INDICATOR, PRODUCTION	72.000	LFT
79	701-09560 TEST PILE, INDICATOR, RESTRIKE	2.000	EACH
80	701-09891 PILE SHOE, 12 X 84, HP	11.000	EACH
81	701-95782 PILE, STEEL H, HP 12 X 84	230.000	LFT
82	702-04325 TEMPORARY SHORING	LUMP	LUMP
83	702-51005 CONCRETE, A, SUBSTRUCTURE	57.800	CYS
84	702-51015 CONCRETE, B, FOOTINGS	40.300	CYS
85	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	322.000	LBS
86	702-92857 CONCRETE, C, SUBSTRUCTURE	41.200	CYS
87	703-06028 REINFORCING BARS	13,650.000	LBS
88	703-06029 REINFORCING BARS, EPOXY COATED	100,217.000	LBS
89	704-51002 CONCRETE, C, SUPERSTRUCTURE	266.200	CYS
90	706-06372 CONCRETE BRIDGE RAILING TRANSITION, TTX	4.000	EACH
91	706-09545 COARSE AGGREGATE, NO 8	5.500	CYS
92	706-09965 RAILING, CONCRETE, TX	360.000	LFT
93	707-08158 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 42 IN X 49 IN	714.000	LFT
94	709-51821 SURFACE SEAL	LUMP	LUMP
95	714-11087 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	98.000	LFT
96	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	88.000	LFT
97	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	79.000	LFT
98	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	10.000	LFT

CALL ORDER : 391

CONTRACT ID : R -35316-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
99	715-05407 PIPE, END BENT DRAIN, 6 IN	65.000	LFT
100	715-10238 PIPE ROADWAY DRAIN CASTING EXTENSION	1.000	EACH
101	715-46010 PIPE END SECTION, DIA 18"	1.000	EACH
102	720-02442 PIPE, PLUG EXISTING	1.000	EACH
103	720-44006 SPRING BOX	1.000	EACH
104	720-45270 PIPE CATCH BASIN, 18 IN	1.000	EACH
105	720-45410 MANHOLE, C4	1.000	EACH
106	720-98174 INLET, B15	3.000	EACH
107	720-98555 INLET, C15	1.000	EACH
108	720-99417 CATCH BASIN, C15	2.000	EACH
109	731-93945 FACE PANELS, CONCRETE	4,252.000	SFT
110	731-93946 WALL ERECTION	4,252.000	SFT
111	731-93947 LEVELING PAD, CONCRETE	326.000	LFT
112	732-08420 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	16.600	SYS
113	732-08421 MODULAR BLOCK WALL ERECTION	16.600	SYS
114	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
115	801-04308 ROAD CLOSURE SIGN ASSEMBLY	7.000	EACH
116	801-06625 DETOUR ROUTE MARKER ASSEMBLY	12.000	EACH
117	801-06640 CONSTRUCTION SIGN, A	7.000	EACH
118	801-07118 BARRICADE, III-A	120.000	LFT
119	801-07119 BARRICADE, III-B	24.000	LFT
120	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	100.000	LFT
121	802-07060 SIGN, SHEET, RELOCATE	2.000	EACH
122	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	46.300	SFT
123	807-02191 HANDHOLE, LIGHTING	2.000	EACH
124	807-02426 WIRE, THW, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	365.000	LFT
125	807-02817 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING	4.000	EACH
126	807-03950 LUMINAIRE, ORNAMENTAL	7.000	EACH
127	807-03951 LIGHT POLE, ORNAMENTAL	7.000	EACH
128	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	430.000	LFT
129	807-86805 SERVICE POINT, I	1.000	EACH
130	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	210.000	LFT
131	807-86910 CONNECTOR KIT, UNFUSED	7.000	EACH
132	807-86915 CONNECTOR KIT, FUSED	7.000	EACH
133	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	9.000	EACH
134	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.000	EACH
135	807-86930 INSULATION LINK, NON-WATERPROOFED	14.000	EACH
136	807-86935 INSULATION LINK, WATERPROOFED	8.000	EACH
137	807-86955 CABLE-DUCT MARKER	2.000	EACH
138	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,487.000	LFT
139	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	464.000	LFT
140	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	464.000	LFT
141	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,487.000	LFT
142	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	8.000	LFT

CALL ORDER : 401

CONTRACT ID : R -35343-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 CONCRETE PAVEMENT RESTORATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	305-60400 COMPACTED AGGREGATE FOR PATCHING	110.000	TON
9	503-03489 RETROFITTED TIE BARS	140.000	EACH
10	503-05240 D-1 CONTRACTION JOINT	390.000	LFT
11	503-09261 PCCP STITCHING	30.000	EACH
12	506-06333 PCCP PATCHING, FULL DEPTH	1,340.000	SYS
13	506-06334 PCCP PATCHING, PARTIAL DEPTH	5.000	SYS
14	507-07482 CRACKS IN PCCP, ROUT AND SEAL	780.000	LFT
15	507-07505 RETROFIT LOAD TRANSFER	1,640.000	EACH
16	507-08269 CRACKS IN PCCP, FILLED	110.000	LFT
17	507-08272 JOINTS IN PCCP, SAW AND SEAL	550.000	LFT
18	605-02278 CURB, REMOVE	330.000	LFT
19	605-06100 CURB, INTEGRAL, C, CONCRETE	330.000	LFT
20	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
21	628-09401 FIELD OFFICE, A	5.000	MOS
22	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	15.000	MOS
23	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
24	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
25	801-04308 ROAD CLOSURE SIGN ASSEMBLY	1.000	EACH
26	801-06625 DETOUR ROUTE MARKER ASSEMBLY	8.000	EACH
27	801-06640 CONSTRUCTION SIGN, A	22.000	EACH
28	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
29	801-07118 BARRICADE, III-A	28.000	LFT

CALL ORDER : 411

CONTRACT ID : R -35344-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 CONCRETE PAVEMENT RESTORATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	304-07490 HMA PATCHING, TYPE B	290.000	TON
9	503-03489 RETROFITTED TIE BARS	50.000	EACH
10	503-05240 D-1 CONTRACTION JOINT	340.000	LFT
11	503-09261 PCCP STITCHING	200.000	EACH
12	506-06333 PCCP PATCHING, FULL DEPTH	1,030.000	SYS
13	506-06334 PCCP PATCHING, PARTIAL DEPTH	130.000	SYS
14	507-07482 CRACKS IN PCCP, ROUT AND SEAL	50.000	LFT
15	507-07505 RETROFIT LOAD TRANSFER	390.000	EACH
16	507-08272 JOINTS IN PCCP, SAW AND SEAL	51,240.000	LFT
17	628-09403 FIELD OFFICE, C	4.000	MOS
18	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	13.000	EACH
20	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
21	805-02328 SIGNAL CABLE, 1C/14 GA	175.000	LFT
22	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
23	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	80.000	LFT
24	808-75994 PRISMATIC REFLECTOR	40.000	EACH
25	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	120.000	EACH

CALL ORDER : 421

CONTRACT ID : R -35376-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	135.000	SYS
13	202-52710 SIDEWALK, CONCRETE, REMOVE	43.000	SYS
14	202-91385 INLET, REMOVE	1.000	EACH
15	203-02000 EXCAVATION, COMMON	76.000	CYS
16	203-02070 BORROW	164.000	CYS
17	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	6.000	EACH
18	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	6.000	EACH
19	205-06934 TEMPORARY MULCH	1.000	TON
20	205-06937 TEMPORARY SILT FENCE	1,736.000	LFT
21	205-11584 TEMPORARY CHECK DAM, TRAVERSABLE	60.000	LFT
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	135.000	SYS
23	211-09265 STRUCTURAL BACKFILL, TYPE 2	18.000	CYS
24	304-07783 HMA PATCHING, TYPE D	885.000	TON
25	305-07464 PCC BASE PATCHING, 9 IN	838.000	SYS
26	306-08034 MILLING, ASPHALT, 1 1/2 IN	59,722.000	SYS
27	306-08037 MILLING, ASPHALT, 3 IN	31,409.000	SYS
28	306-08432 MILLING, APPROACH	3,628.000	SYS
29	401-07329 QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	7,672.000	TON
30	401-07380 QC/QA-HMA, 4, 70, INTERMEDIATE, 12.5 mm	3,615.000	TON
31	406-05520 ASPHALT FOR TACK COAT	24.000	TON
32	501-03489 TIE BAR, RETROFIT	383.000	EACH
33	503-05240 D-1 CONTRACTION JOINT	402.000	LFT
34	604-07894 CURB RAMP, CONCRETE, A	9.000	SYS
35	604-07897 CURB RAMP, CONCRETE, C	11.000	SYS
36	604-07900 CURB RAMP, CONCRETE, F	43.000	SYS
37	605-02278 CURB, REMOVE	425.000	LFT
38	605-06120 CURB, CONCRETE	313.000	LFT
39	605-06140 CURB AND GUTTER, CONCRETE	112.000	LFT
40	610-07788 HMA FOR APPROACHES, TYPE D	242.000	TON
41	610-09108 PCCP FOR APPROACHES, 9 IN	135.000	SYS
42	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
43	621-06557 SEED MIXTURE, T	30.000	LBS
44	621-06560 MULCHED SEEDING, U	4,252.000	SYS
45	621-06567 WATER	2.000	KGAL
46	621-06570 TOPSOIL	355.000	CYS
47	621-06574 SODDING	444.000	SYS
48	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	5.000	MOS
49	628-09409 MOBILE INTERNET SERVICE	5.000	MOS

CALL ORDER : 421

CONTRACT ID : R -35376-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION			
50	715-01354 CLEAN EXISTING PIPE	404.000	LFT
51	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	8.000	LFT
52	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	117.000	LFT
53	715-08307 HMA FOR STRUCTURE INSTALLATION, TYPE D	1.000	TON
54	715-46000 PIPE END SECTION, DIA 12"	2.000	EACH
55	715-46005 PIPE END SECTION, DIA 15"	12.000	EACH
56	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
57	720-44000 CASTING, ADJUST TO GRADE	26.000	EACH
58	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
59	720-44000 CASTING, ADJUST TO GRADE	19.000	EACH
60	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
61	720-45035 INLET, F7	1.000	EACH
62	720-96995 CLEAN INLET	3.000	EACH
63	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
64	801-06640 CONSTRUCTION SIGN, A	68.000	EACH
65	801-06710 FLASHING ARROW SIGN	180.000	DAY
66	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
67	805-01842 HANDHOLE, SIGNAL	5.000	EACH
68	805-01843 SIGNAL HANDHOLE ADJUST TO GRADE	5.000	EACH
69	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	6.000	EACH
70	805-02328 SIGNAL CABLE, 1C/14 GA	10,179.000	LFT
71	805-02645 SIGNAL PEDESTAL FOUNDATION, A	6.000	EACH
72	805-04602 CONTROLLER, REWIRE	1.000	EACH
73	805-78370 PEDESTRIAN PUSH BUTTON	6.000	EACH
74	805-78480 SIGNAL CABLE, 3C/14GA	96.000	LFT
75	805-78485 SIGNAL CABLE, 5C/14GA	830.000	LFT
76	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	100.000	LFT
77	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	3,318.000	LFT
78	805-92951 SIGNAL DETECTOR HOUSING, ADJUST TO GRADE	24.000	EACH
79	805-99162 SIGNAL PEDESTAL, 11 FT	6.000	EACH
80	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	442.000	LFT
81	808-03439 TRANSVERSE MARKING THERMOPLASTIC	606.000	LFT
82	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	6,771.000	LFT
83	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	25,953.000	LFT
84	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
85	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	36,065.000	LFT
86	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	550.000	LFT
87	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	32.000	EACH
88	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	26.000	EACH
89	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	610.000	EACH
90	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	934.000	EACH

CALL ORDER : 461

CONTRACT ID : R -35550-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02273 CENTER CURB, CONCRETE, REMOVE	154.700	SYS
13	202-02278 CURB, CONCRETE, REMOVE	377.000	LFT
14	202-02279 CURB AND GUTTER, REMOVE	2,113.000	LFT
15	202-52710 SIDEWALK, CONCRETE, REMOVE	572.900	SYS
16	202-91385 INLET, REMOVE	12.000	EACH
17	202-93047 MANHOLE, REMOVE	3.000	EACH
18	202-96133 PIPE, REMOVE	1,867.000	LFT
19	203-02000 EXCAVATION, COMMON	3,006.000	CYS
20	203-02070 BORROW	15,630.000	CYS
21	205-02234 TEMPORARY EROSION AND SEDIMENT CONTROL, CULVERT PIPE	2.000	EACH
22	205-02236 TEMPORARY EROSION & SEDIMENT CONTROL, DROP INLET	6.000	EACH
23	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	43.000	EACH
24	205-06937 TEMPORARY SILT FENCE	2,687.000	LFT
25	207-08263 SUBGRADE TREATMENT, TYPE IA	8,806.500	SYS
26	207-08267 SUBGRADE TREATMENT, TYPE IIIA	127.600	SYS
27	211-09265 STRUCTURAL BACKFILL, TYPE 2	1,778.400	CYS
28	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	10.000	CYS
29	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,057.900	TON
30	302-06464 SUBBASE FOR PCCP	67.000	CYS
31	303-01180 COMPACTED AGGREGATE, NO. 53	44.200	TON
32	303-02172 TEMPORARY AGGREGATE	60.000	TON
33	306-08159 MILLING ASPHALT	149.900	SYS
34	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	1,045.000	TON
35	402-07432 HMA SURFACE, TYPE A	161.000	TON
36	402-07433 HMA SURFACE, TYPE B	537.000	TON
37	402-07435 HMA INTERMEDIATE, TYPE A	266.000	TON
38	402-07438 HMA INTERMEDIATE, TYPE B	895.000	TON
39	402-07440 HMA BASE, TYPE A	12.000	TON
40	402-07441 HMA BASE, TYPE B	1,174.000	TON
41	406-05520 ASPHALT FOR TACK COAT	5.416	TON
42	501-08193 QC/QA-PCCP, 10.5 IN	168.900	SYS
43	503-05240 D-1 CONTRACTION JOINT	90.000	LFT
44	604-06070 SIDEWALK, CONCRETE	624.200	SYS
45	604-07894 CURB RAMP, CONCRETE, A	138.200	SYS
46	604-07904 CURB RAMP, CONCRETE, L	87.600	SYS
47	605-06120 CURB, CONCRETE	1,305.000	LFT
48	605-06140 CURB AND GUTTER, CONCRETE	2,140.000	LFT
49	605-06255 CENTER CURB, D, CONCRETE	25.100	SYS

CALL ORDER : 461

CONTRACT ID : R -35550-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	605-97937 CURB AND GUTTER, ROLL CURB	365.000	LFT
51	610-09108 PCCP FOR APPROACHES, 9 IN	127.600	SYS
52	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
53	621-04316 SPADE EDGE	350.000	LFT
54	621-06557 SEED MIXTURE, T	304.000	LBS
55	621-06560 MULCHED SEEDING, U	4,208.000	SYS
56	621-06565 MULCHING MATERIAL	4.300	TON
57	621-06567 WATER	22.400	KGAL
58	621-06575 SODDING, NURSERY	5,591.400	SYS
59	621-06626 MULCHED SEEDING, D	327.000	SYS
60	621-07762 COMPOST AMENDED SOIL	403.000	CYS
61	621-09908 SOIL	296.000	CYS
62	621-98038 MULCH, HARDWOOD SHREDDED BARK	34.000	CYS
63	622-01937 PLANT	358.000	EACH
64	622-05635 PLANT, CONIFEROUS EVERGREEN, PROSTATE, BROAD SPREADING	48.000	EACH
65	622-05639 PLANT, DECIDUOUS SHRUB, 18 TO 24 IN	86.000	EACH
66	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	158.000	EACH
67	622-05651 PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN	6.000	EACH
68	622-07764 IRRIGATION SYSTEM	LUMP	LUMP
69	622-93712 PLANT, BULBS	900.000	EACH
70	628-09402 FIELD OFFICE, B	17.000	MOS
71	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	75.000	LFT
72	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	2,153.000	LFT
73	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,267.000	LFT
74	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	404.000	LFT
75	715-05157 PIPE, TYPE 2 CIRCULAR 33 IN	274.000	LFT
76	715-46000 PIPE END SECTION, DIA 12"	1.000	EACH
77	715-90714 PIPE, PVC, 12 IN	19.000	LFT
78	715-96960 PIPE, PVC, 15 IN	19.000	LFT
79	718-52610 AGGREGATE FOR UNDERDRAINS	193.730	CYS
80	718-99153 GEOTEXTILES FOR UNDERDRAIN	139.020	SYS
81	720-04466 MANHOLE, K8	1.000	EACH
82	720-08559 BEST MANAGEMENT PRACTICES	2.000	EACH
83	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
84	720-45035 INLET, F7	1.000	EACH
85	720-45145 INLET, J10, MODIFIED	2.000	EACH
86	720-45410 MANHOLE, C4	1.000	EACH
87	720-92884 MANHOLE, K4, MODIFIED	1.000	EACH
88	720-93501 MANHOLE, L4	1.000	EACH
89	720-94612 MANHOLE, K4	2.000	EACH
90	720-95422 MANHOLE, J4	9.000	EACH
91	720-98006 MANHOLE, J8	2.000	EACH
92	720-98174 INLET, B15	12.000	EACH
93	720-98555 INLET, C15	14.000	EACH
94	720-98869 MANHOLE, L4, MODIFIED	1.000	EACH
95	732-08419 MODULAR BLOCK WALL	58.630	SYS
96	732-08421 MODULAR BLOCK WALL ERECTION	58.630	SYS
97	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
98	801-06625 DETOUR ROUTE MARKER ASSEMBLY	11.000	EACH

CALL ORDER : 461

CONTRACT ID : R -35550-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
99	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
100	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
101	801-07118 BARRICADE, III-A	183.000	LFT
102	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	225.000	LFT
103	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	9.000	EACH
104	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	69.000	SFT
105	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	72.670	SFT
106	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	9.170	SFT
107	805-06595 CONDUIT, PVC, 2 IN	250.000	LFT
108	805-95519 CONDUIT FLEXIBLE 0.75"	200.000	LFT
109	805-95568 CONDUIT, PVC, 4"	1,394.000	LFT
110	807-02428 LIGHTING FOUNDATION, CONCRETE, WITH GROUND	16.000	EACH
111	807-03950 LUMINAIRE, ORNAMENTAL	16.000	EACH
112	807-03951 LIGHT POLE, ORNAMENTAL	16.000	EACH
113	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	2,290.000	LFT
114	807-86805 SERVICE POINT, I	1.000	EACH
115	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	2,880.000	LFT
116	807-86910 CONNECTOR KIT, UNFUSED	16.000	EACH
117	807-86915 CONNECTOR KIT, FUSED	16.000	EACH
118	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	43.000	EACH
119	807-86935 INSULATION LINK, WATERPROOFED	41.000	EACH
120	807-90714 PIPE, PVC, 4 IN	994.000	LFT
121	807-97237 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN CONDUIT, 4 1/C	2,290.000	LFT
122	808-03439 TRANSVERSE MARKING THERMOPLASTIC	420.000	LFT
123	808-06609 PAVEMENT MESSAGE MARKING,	8.000	EACH
124	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	169.000	LFT
125	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,135.000	LFT
126	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	162.000	LFT
127	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	47.000	EACH
128	808-11478 LINE, THERMOPLASTIC, DOTTED, WHITE 8 IN	133.000	LFT
129	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	2,394.000	LFT
130	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	300.000	LFT
131	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	6.000	EACH
132	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	273.000	LFT

CALL ORDER : 521

CONTRACT ID : RS-35750-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SURFACE TREATMENT, MICROSURFACE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	100.000	SYS
10	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	30.000	TON
11	304-07783 HMA PATCHING, TYPE D	500.000	TON
12	304-07783 HMA PATCHING, TYPE D	500.000	TON
13	306-08042 MILLING, SCARIFICATION/PROFILE	2,000.000	SYS
14	406-05520 ASPHALT FOR TACK COAT	1.500	TON
15	411-09521 MICRO-SURFACING, WARRANTED, MULTIPLE COURSE	130,000.000	SYS
16	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
17	628-09402 FIELD OFFICE, B	4.000	MOS
18	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	4.000	MOS
19	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
20	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
21	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
22	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	5,500.000	LFT
23	801-06640 CONSTRUCTION SIGN, A	60.000	EACH
24	801-06710 FLASHING ARROW SIGN	250.000	DAY
25	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
26	801-92448 CONSTRUCTION SIGNS, MOBILE	500.000	DAY
27	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	104,000.000	LFT
28	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
29	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	145.000	EACH
30	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	145.000	EACH

CALL ORDER : 531

CONTRACT ID : RS-35751-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SURFACE TREATMENT, MICROSURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	1,500.000	SYS
10	202-93741 GUARDRAIL END TREATMENT, REMOVE	5.000	EACH
11	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	250.000	TON
12	303-07449 COMPACTED AGGREGATE, NO. 73	4,725.000	TON
13	304-07783 HMA PATCHING, TYPE D	2,400.000	TON
14	304-07783 HMA PATCHING, TYPE D	500.000	TON
15	406-05520 ASPHALT FOR TACK COAT	4.000	TON
16	411-09521 MICRO-SURFACING, WARRANTED, MULTIPLE COURSE	183,400.000	SYS
17	601-02241 GUARDRAIL, REMOVE	1,100.000	LFT
18	601-09238 HAND DIG GUARDRAIL POST HOLES	4.000	EACH
19	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
20	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
21	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
22	628-09402 FIELD OFFICE, B	9.000	MOS
23	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	18.000	MOS
24	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
25	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
26	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	8,300.000	LFT
27	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	5.000	EACH
28	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	200.000	LFT
29	801-06640 CONSTRUCTION SIGN, A	47.000	EACH
30	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
31	801-92448 CONSTRUCTION SIGNS, MOBILE	500.000	DAY
32	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	1,100.000	LFT
33	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	104,600.000	LFT
34	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	200.000	LFT
35	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
36	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	11,000.000	LFT
37	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	23,000.000	LFT
38	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	250.000	LFT
39	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	150.000	LFT
40	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	200.000	LFT
41	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	5.000	EACH
42	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,011.000	EACH
43	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,011.000	EACH
44	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	710.000	LFT

CALL ORDER : 571

CONTRACT ID : B -31764-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE WIDENING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
11	202-93741 GUARDRAIL END TREATMENT, REMOVE	4.000	EACH
12	203-02000 EXCAVATION, COMMON	466.000	CYS
13	205-06937 TEMPORARY SILT FENCE	1,050.000	LFT
14	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	27.000	CYS
15	206-51817 SHEET PILING, STEEL	6,608.000	SFT
16	207-08265 SUBGRADE TREATMENT, TYPE IIA	944.000	SYS
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	48.000	SYS
18	211-02050 B BORROW	12.000	CYS
19	211-06467 AGGREGATE FOR END BENT BACKFILL	24.000	CYS
20	211-09266 STRUCTURAL BACKFILL, TYPE 3	100.000	CYS
21	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	192.000	TON
22	302-07455 DENSE GRADED SUBBASE	21.200	CYS
23	303-07449 COMPACTED AGGREGATE, NO. 73	180.000	TON
24	306-08034 MILLING, ASPHALT, 1 1/2 IN	444.000	SYS
25	401-10258 JOINT ADHESIVE, SURFACE	390.000	LFT
26	402-07433 HMA SURFACE, TYPE B	93.600	TON
27	402-07438 HMA INTERMEDIATE, TYPE B	132.900	TON
28	406-05521 ASPHALT FOR TACK COAT	1,920.000	SYS
29	601-01740 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 4	1.000	EACH
30	601-06374 GUARDRAIL TRANSITION, TGS-1	4.000	EACH
31	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
32	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	200.000	LFT
33	601-99106 GUARDRAIL, W-BEAM, 3 FT 1.5 IN SPACING	150.000	LFT
34	603-02736 FENCE, WOOD, RESET	50.000	LFT
35	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	130.000	SYS
36	610-07487 HMA FOR APPROACHES, TYPE B	13.100	TON
37	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
38	616-02320 GEOTEXTILES	524.000	SYS
39	616-05688 RIPRAP, CLASS 1	15.000	TON
40	616-06405 RIPRAP, REVETMENT	196.000	TON
41	619-11050 CLEAN STEEL BRIDGE, PARTIAL, QP-2, BR. NO.	LUMP	LUMP
42	619-51860 PAINT STEEL BRIDGE, PARTIAL, BR. NO.	LUMP	LUMP
43	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
44	621-06559 MULCHED SEEDING, R	369.400	SYS
45	628-09401 FIELD OFFICE, A	6.000	MOS
46	701-09665 PILE, STEEL PIPE, 0.375 IN, 14 IN	296.000	LFT
47	701-09677 PILE STEEL PIPE EPOXY COATED 0.375 IN, 14 IN	48.000	LFT
48	702-51005 CONCRETE, A, SUBSTRUCTURE	17.100	CYS
49	702-51863 FIELD DRILLED HOLE IN CONCRETE	40.000	EACH

CALL ORDER : 571

CONTRACT ID : B -31764-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE WIDENING		
50	702-92857 CONCRETE, C, SUBSTRUCTURE	28.300	CYS
51	703-06029 REINFORCING BARS, EPOXY COATED	23,807.000	LBS
52	704-51002 CONCRETE, C, SUPERSTRUCTURE	56.900	CYS
53	706-06344 RAILING, STEEL TS-1	130.000	LFT
54	709-51821 SURFACE SEAL	LUMP	LUMP
55	711-51038 STRUCTURAL STEEL	LUMP	LUMP
56	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	46.000	LFT
57	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	289.000	LFT
58	715-05407 PIPE, END BENT DRAIN, 6 IN	100.000	LFT
59	715-46005 PIPE END SECTION, DIA 15"	2.000	EACH
60	726-92406 BEARING ASSEMBLY, ELASTOMERIC	20.000	EACH
61	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
62	801-06625 DETOUR ROUTE MARKER ASSEMBLY	19.000	EACH
63	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
64	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
65	801-07118 BARRICADE, III-A	48.000	LFT
66	801-07119 BARRICADE, III-B	36.000	LFT
67	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	989.000	LFT
68	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	989.000	LFT

CALL ORDER : 591

CONTRACT ID : B -32437-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	336.000	CYS
12	203-02070 BORROW	11,474.000	CYS
13	203-51223 EXCAVATION, WATERWAY	4,204.000	CYS
14	205-03371 SEDIMENT, REMOVE	5.000	CYS
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	16.000	TON
16	205-06934 TEMPORARY MULCH	760.000	TON
17	205-06937 TEMPORARY SILT FENCE	2,900.000	LFT
18	205-08517 ROCK FILTER BERM	549.000	TON
19	205-09543 NO 2 STONE	356.000	TON
20	206-51220 EXCAVATION, WET	62.000	CYS
21	206-51235 COFFERDAM	LUMP	LUMP
22	207-08264 SUBGRADE TREATMENT, TYPE II	5,662.000	SYS
23	211-06467 AGGREGATE FOR END BENT BACKFILL	52.000	CYS
24	211-09264 STRUCTURAL BACKFILL, TYPE 1	66.000	CYS
25	211-09267 STRUCTURAL BACKFILL, TYPE 4	37.000	CYS
26	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,868.000	TON
27	302-07455 DENSE GRADED SUBBASE	26.000	CYS
28	306-08033 MILLING, ASPHALT, 1 IN	419.000	SYS
29	401-10258 JOINT ADHESIVE, SURFACE	2,841.000	LFT
30	401-10259 JOINT ADHESIVE, INTERMEDIATE	2,841.000	LFT
31	402-07432 HMA SURFACE, TYPE A	436.000	TON
32	402-07435 HMA INTERMEDIATE, TYPE A	670.000	TON
33	406-05520 ASPHALT FOR TACK COAT	1.300	TON
34	601-02241 GUARDRAIL, REMOVE	125.000	LFT
35	601-03871 RAILING, WOOD, END TREATMENT	2.000	EACH
36	601-03871 RAILING, WOOD, END TREATMENT	1.000	EACH
37	601-03871 RAILING, WOOD, END TREATMENT	1.000	EACH
38	601-03871 RAILING, WOOD, END TREATMENT	1.000	EACH
39	601-03871 RAILING, WOOD, END TREATMENT	1.000	EACH
40	601-03871 RAILING, WOOD, END TREATMENT	2.000	EACH
41	601-90027 GUARDRAIL, WOOD BEAM	60.000	LFT
42	601-90027 GUARDRAIL, WOOD BEAM	20.000	LFT
43	601-90027 GUARDRAIL, WOOD BEAM	440.000	LFT
44	601-90027 GUARDRAIL, WOOD BEAM	93.700	LFT
45	601-90027 GUARDRAIL, WOOD BEAM	18.750	LFT
46	601-90027 GUARDRAIL, WOOD BEAM	43.700	LFT
47	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	153.000	SYS
48	615-06490 RIGHT OF WAY MARKER	14.000	EACH
49	615-06505 MONUMENT, B	7.000	EACH

CALL ORDER : 591

CONTRACT ID : B -32437-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	615-06510 MONUMENT, C	1.000	EACH
51	615-06530 BENCH MARK POST	1.000	EACH
52	615-11537 PARKING BARRIER, CONCRETE	4.000	EACH
53	616-02320 GEOTEXTILES	2,165.000	SYS
54	616-05688 RIPRAP, CLASS 1	228.000	TON
55	616-06405 RIPRAP, REVETMENT	1,111.000	TON
56	616-07051 BOULDERS	26.000	TON
57	616-07051 BOULDERS	89.000	TON
58	616-07266 COIR ROLL	344.000	LFT
59	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
60	621-02770 EROSION CONTROL BLANKET	717.000	SYS
61	621-04978 SEED MIXTURE	878.000	SYS
62	621-04978 SEED MIXTURE	3,794.000	SYS
63	621-06545 FERTILIZER	1.000	TON
64	621-06553 SEED MIXTURE, R	311.000	LBS
65	621-06557 SEED MIXTURE, T	393.000	LBS
66	621-06565 MULCHING MATERIAL	9.000	TON
67	621-06574 SODDING	20.000	SYS
68	621-08161 PERMANENT TURF REINFORCEMENT MAT	476.000	SYS
69	621-09867 MULCHED SEEDING,	760.000	SYS
70	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN OR UNDER	85.000	EACH
71	622-05648 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN OR UNDER	340.000	EACH
72	622-05653 PLANT, GROUND COVER	85.000	EACH
73	622-52436 SIGN, DO NOT MOW OR SPRAY	10.000	EACH
74	622-52436 SIGN, DO NOT MOW OR SPRAY	11.000	EACH
75	701-06011 DYNAMIC PILE LOAD TEST	1.000	EACH
76	701-09557 TEST PILE, DYNAMIC, PRODUCTION	68.000	LFT
77	701-09559 TEST PILE, DYNAMIC, RESTRIKE	1.000	EACH
78	701-09683 PILE SHOE, HP 12 X 74	8.000	EACH
79	701-09739 PILE SHOE, HP 12 X 53	12.000	EACH
80	701-51195 PILE, STEEL H, HP 12 IN X 53	798.000	LFT
81	701-95780 PILE, STEEL H, HP 12 IN X 74	406.000	LFT
82	702-51005 CONCRETE, A, SUBSTRUCTURE	89.000	CYS
83	702-51015 CONCRETE, B, FOOTINGS	5.600	CYS
84	703-06028 REINFORCING BARS	6,225.000	LBS
85	703-06029 REINFORCING BARS, EPOXY COATED	74,976.000	LBS
86	704-51002 CONCRETE, C, SUPERSTRUCTURE	306.100	CYS
87	706-04683 RAILING,	440.000	LFT
88	707-09382 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 54 IN X 61 IN	882.000	LFT
89	709-51821 SURFACE SEAL	LUMP	LUMP
90	710-51870 REPOINTING MASONRY IN STRUCTURES	175.000	SFT
91	711-51070 ANCHOR PLATE, AP 1	16.000	EACH
92	711-51876 JACKING AND SUPPORTING TRUSSES	LUMP	LUMP
93	712-03820 TIMBER SIDING	5,088.000	SFT
94	712-04272 LUMBER AND TIMBER, UNTREATED	15.200	MFBM
95	712-04686 FIRE PROTECTION	LUMP	LUMP
96	712-04704 PAINT BRIDGE	LUMP	LUMP
97	712-05097 METAL PARTS	100.000	LBS
98	712-11615 ROOF, CORRUGATED METAL	5,500.000	SFT

CALL ORDER : 591

CONTRACT ID : B -32437-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
99	712-94725 STRUCTURAL TIMBER	800.000	BDFT
100	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	60.000	LFT
101	715-05407 PIPE, END BENT DRAIN, 6 IN	100.000	LFT
102	715-46020 PIPE END SECTION, DIA 24"	2.000	EACH
103	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
104	801-06625 DETOUR ROUTE MARKER ASSEMBLY	21.000	EACH
105	801-06640 CONSTRUCTION SIGN, A	23.000	EACH
106	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
107	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
108	801-07118 BARRICADE, III-A	72.000	LFT
109	801-07119 BARRICADE, III-B	48.000	LFT
110	802-03896 BOLLARD	12.000	EACH
111	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	179.000	LFT
112	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	83.500	SFT
113	804-06725 DELINEATOR WITH POST, D1	20.000	EACH
114	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3,310.000	LFT
115	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	530.000	LFT
116	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	530.000	LFT
117	808-75056 TRANSVERSE MARKING, PAINT,	83.000	LFT
118	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	3,301.000	LFT
119	808-97664 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	1.000	EACH

CALL ORDER : 601

CONTRACT ID : B -32628-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE PAINTING		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
7	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
8	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
9	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
10	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
11	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
12	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
13	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	6.000	MOS
14	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
15	709-51821 SURFACE SEAL	LUMP	LUMP
16	709-51821 SURFACE SEAL	LUMP	LUMP
17	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
18	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
20	801-06710 FLASHING ARROW SIGN	180.000	DAY
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
22	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH

CALL ORDER : 611

CONTRACT ID : B -32633-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEBRIS REMOVAL FROM CHANNEL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
8	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
9	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
10	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
11	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
12	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
13	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
14	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
15	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	6.000	MOS
16	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
17	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
18	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
19	801-06710 FLASHING ARROW SIGN	100.000	DAY
20	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
21	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH

CALL ORDER : 621

CONTRACT ID : B -32637-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DEBRIS REMOVAL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
8	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
9	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
10	201-90788 DEBRIS, REMOVE, STRUCTURE NO	LUMP	LUMP
11	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
12	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
13	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
14	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	6.000	MOS
15	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
16	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
17	801-06640 CONSTRUCTION SIGN, A	18.000	EACH
18	801-06710 FLASHING ARROW SIGN	100.000	DAY
19	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
20	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH

CALL ORDER : 641

CONTRACT ID : B -33644-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK RECONSTRUCTION & WIDENING		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	203-02000 EXCAVATION, COMMON	2,160.000	CYS
14	203-02070 BORROW	2,277.000	CYS
15	203-51223 EXCAVATION, WATERWAY	5,360.000	CYS
16	205-03371 SEDIMENT, REMOVE	42.600	CYS
17	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	90.000	TON
18	205-06933 TEMPORARY INLET PROTECTION	1.000	EACH
19	205-06937 TEMPORARY SILT FENCE	3,065.000	LFT
20	205-06938 TEMPORARY SLOPE DRAIN	60.000	LFT
21	205-09543 NO 2 STONE	100.000	TON
22	205-11587 TEMPORARY GEOTEXTILE	235.000	SYS
23	206-51220 EXCAVATION, WET	163.500	CYS
24	207-08263 SUBGRADE TREATMENT, TYPE IA	4,330.000	SYS
25	207-08267 SUBGRADE TREATMENT, TYPE IIIA	611.000	SYS
26	211-02050 B BORROW	50.000	CYS
27	211-06467 AGGREGATE FOR END BENT BACKFILL	179.000	CYS
28	211-09264 STRUCTURAL BACKFILL, TYPE 1	246.000	CYS
29	211-09265 STRUCTURAL BACKFILL, TYPE 2	224.000	CYS
30	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	819.000	TON
31	302-07455 DENSE GRADED SUBBASE	79.500	CYS
32	303-01180 COMPACTED AGGREGATE, NO. 53	27.000	TON
33	401-07427 QC/QA-HMA, 2, 70, BASE, 19.0 mm	430.000	TON
34	401-10258 JOINT ADHESIVE, SURFACE	2,484.000	LFT
35	401-10259 JOINT ADHESIVE, INTERMEDIATE	2,484.000	LFT
36	402-07434 HMA SURFACE, TYPE C	309.000	TON
37	402-07439 HMA INTERMEDIATE, TYPE C	332.000	TON
38	402-07442 HMA BASE, TYPE C	1,030.000	TON
39	406-05520 ASPHALT FOR TACK COAT	3.000	TON
40	601-01128 GUARDRAIL, TRANSITION TYPE WGB	4.000	EACH
41	601-01704 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, MODIFIED	1.000	EACH
42	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
43	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	200.000	LFT
44	602-06729 BARRIER DELINEATOR	12.000	EACH
45	605-06095 CURB, INTEGRAL, B, CONCRETE	34.000	LFT
46	605-06145 CURB AND GUTTER, B, CONCRETE	293.000	LFT
47	605-09131 CURB AND GUTTER TURNOUT CONCRETE	9.000	LFT
48	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	477.000	SYS
49	610-07486 HMA FOR APPROACHES, TYPE A	143.700	TON

CALL ORDER : 641

CONTRACT ID : B -33644-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK RECONSTRUCTION & WIDENING		
50	610-07487 HMA FOR APPROACHES, TYPE B	284.800	TON
51	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
52	615-06490 RIGHT OF WAY MARKER	30.000	EACH
53	615-06505 MONUMENT, B	2.000	EACH
54	616-02320 GEOTEXTILES	2,718.000	SYS
55	616-06405 RIPRAP, REVETMENT	1,874.000	TON
56	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
57	621-02770 EROSION CONTROL BLANKET	4,961.000	SYS
58	621-04258 SEED MIXTURE	15.000	LBS
59	621-06545 FERTILIZER	0.500	TON
60	621-06553 SEED MIXTURE, R	153.000	LBS
61	621-06557 SEED MIXTURE, T	103.000	LBS
62	621-06565 MULCHING MATERIAL	1.000	TON
63	621-06574 SODDING	38.000	SYS
64	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	58.000	EACH
65	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	115.000	EACH
66	622-52436 SIGN, DO NOT MOW OR SPRAY	13.000	EACH
67	628-09401 FIELD OFFICE, A	15.000	MOS
68	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
69	701-09557 TEST PILE, DYNAMIC, PRODUCTION	79.000	LFT
70	701-09559 TEST PILE, DYNAMIC, RESTRIKE	2.000	EACH
71	701-09679 CONICAL PILE TIP, 14 IN	58.000	EACH
72	701-09826 PILE, STEEL PIPE, 0.5 IN., 14 IN.	1,659.000	LFT
73	702-51005 CONCRETE, A, SUBSTRUCTURE	242.000	CYS
74	702-51015 CONCRETE, B, FOOTINGS	18.600	CYS
75	702-92857 CONCRETE, C, SUBSTRUCTURE	97.000	CYS
76	703-06028 REINFORCING BARS	32,554.000	LBS
77	703-06029 REINFORCING BARS, EPOXY COATED	159,539.000	LBS
78	704-51002 CONCRETE, C, SUPERSTRUCTURE	474.000	CYS
79	706-11622 CONCRETE BRIDGE RAILING TRANSITION, WFC	4.000	EACH
80	706-51020 RAILING, CONCRETE, C	35.400	CYS
81	707-05984 STRUCTURAL MEMBER, CONCRETE I-BEAM , 45 IN X 16 IN	1,362.000	LFT
82	709-51821 SURFACE SEAL	LUMP	LUMP
83	714-11087 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	56.000	LFT
84	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	94.000	LFT
85	715-05173 PIPE, TYPE 3 CIRCULAR 24 IN	185.000	LFT
86	715-05407 PIPE, END BENT DRAIN, 6 IN	160.000	LFT
87	715-46005 PIPE END SECTION, DIA 15"	4.000	EACH
88	715-46020 PIPE END SECTION, DIA 24"	1.000	EACH
89	720-44040 CASTING, 7, FURNISH AND ADJUST TO GRADE	1.000	EACH
90	720-92566 INLET, E, MODIFIED	1.000	EACH
91	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
92	801-04308 ROAD CLOSURE SIGN ASSEMBLY	4.000	EACH
93	801-06625 DETOUR ROUTE MARKER ASSEMBLY	8.000	EACH
94	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
95	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
96	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
97	801-07118 BARRICADE, III-A	48.000	LFT
98	801-07119 BARRICADE, III-B	48.000	LFT

CALL ORDER : 641

CONTRACT ID : B -33644-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK RECONSTRUCTION & WIDENING		
99 808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,932.000	LFT
100 808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	620.000	LFT
101 808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	620.000	LFT
102 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,820.000	LFT
103 808-75297	TRANSVERSE MARKING, THERMOPLASTIC,	26.000	LFT
104 808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	1.000	EACH

CALL ORDER : 661

CONTRACT ID : B -34464-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	91.200	SYS
12	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
13	203-02000 EXCAVATION, COMMON	46.000	CYS
14	203-02070 BORROW	83.000	CYS
15	205-06937 TEMPORARY SILT FENCE	448.000	LFT
16	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	24.000	TON
17	302-07455 DENSE GRADED SUBBASE	16.000	CYS
18	303-01180 COMPACTED AGGREGATE, NO. 53	44.000	TON
19	306-08033 MILLING, ASPHALT, 1 IN	372.000	SYS
20	401-10258 JOINT ADHESIVE, SURFACE	187.000	LFT
21	402-07433 HMA SURFACE, TYPE B	36.000	TON
22	402-07438 HMA INTERMEDIATE, TYPE B	7.000	TON
23	402-07441 HMA BASE, TYPE B	17.000	TON
24	406-05521 ASPHALT FOR TACK COAT	470.000	SYS
25	601-02024 GUARDRAIL, TRANSITION, TGB, MODIFIED	4.000	EACH
26	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
27	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	50.000	LFT
28	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	96.000	SYS
29	615-06490 RIGHT OF WAY MARKER	11.000	EACH
30	615-06505 MONUMENT, B	4.000	EACH
31	616-02320 GEOTEXTILES	239.000	SYS
32	616-05688 RIPRAP, CLASS 1	147.000	TON
33	616-06451 RIPRAP, UNIFORM	34.500	TON
34	619-11052 CLEAN STEEL BRIDGE, QP-2, BR. NO.	LUMP	LUMP
35	619-51859 PAINT STEEL BRIDGE, BR. NO.	LUMP	LUMP
36	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
37	621-06557 SEED MIXTURE, T	17.000	LBS
38	621-06560 MULCHED SEEDING, U	291.000	SYS
39	621-06565 MULCHING MATERIAL	0.300	TON
40	621-06567 WATER	1.000	KGAL
41	621-06575 SODDING, NURSERY	234.000	SYS
42	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	15.000	EACH
43	628-09401 FIELD OFFICE, A	8.000	MOS
44	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	8.000	MOS
45	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	1,056.000	LBS
46	702-51863 FIELD DRILLED HOLE IN CONCRETE	44.000	EACH
47	703-06029 REINFORCING BARS, EPOXY COATED	22,716.000	LBS
48	704-51002 CONCRETE, C, SUPERSTRUCTURE	63.400	CYS
49	709-51821 SURFACE SEAL	LUMP	LUMP

CALL ORDER : 661

CONTRACT ID : B -34464-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
50	711-51035 STRUCTURAL STEEL	1,302.000	LBS
51	711-51866 RIVET, REMOVE	158.000	EACH
52	711-93754 JACKING AND SUPPORTING TRUSS AND STEEL BEAMS	LUMP	LUMP
53	715-10238 PIPE ROADWAY DRAIN CASTING EXTENSION	12.000	EACH
54	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	42.000	LFT
55	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
56	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
57	801-06625 DETOUR ROUTE MARKER ASSEMBLY	10.000	EACH
58	801-06640 CONSTRUCTION SIGN, A	9.000	EACH
59	801-07118 BARRICADE, III-A	48.000	LFT
60	801-07119 BARRICADE, III-B	72.000	LFT
61	802-07060 SIGN, SHEET, RELOCATE	4.000	EACH

CALL ORDER : 681

CONTRACT ID : B -35410-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
7	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
8	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
9	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	4.000	MOS
10	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
11	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	1,860.000	SFT
12	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	1,244.000	LFT
13	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
14	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
15	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
16	801-06710 FLASHING ARROW SIGN	24.000	DAY
17	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
18	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH

CALL ORDER : 701

CONTRACT ID : B -35603-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	11.000	SYS
11	202-05823 UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE,	1.000	EACH
12	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
13	203-02000 EXCAVATION, COMMON	2,412.000	CYS
14	203-02070 BORROW	4,722.000	CYS
15	203-02132 EXPLORATORY DRILLING	45.000	LFT
16	205-02237 TEMPORARY EROSION & SEDIMENT CONTROL, CURB INLET	9.000	EACH
17	205-03371 SEDIMENT, REMOVE	7.000	CYS
18	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	5.500	TON
19	205-06934 TEMPORARY MULCH	2.000	TON
20	205-06937 TEMPORARY SILT FENCE	2,023.000	LFT
21	205-09543 NO 2 STONE	50.000	TON
22	207-08263 SUBGRADE TREATMENT, TYPE IA	3,378.000	SYS
23	207-08267 SUBGRADE TREATMENT, TYPE IIIA	999.000	SYS
24	211-02050 B BORROW	2,494.000	CYS
25	211-09265 STRUCTURAL BACKFILL, TYPE 2	935.000	CYS
26	211-09266 STRUCTURAL BACKFILL, TYPE 3	511.000	CYS
27	215-11477 CHEMICAL STABILIZATION	578.000	TON
28	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	119.000	TON
29	302-08562 COARSE AGGREGATE, NO 8	100.000	TON
30	303-01180 COMPACTED AGGREGATE, NO. 53	361.000	TON
31	306-08034 MILLING, ASPHALT, 1 1/2 IN	301.000	SYS
32	306-08043 MILLING, TRANSITION	98.000	SYS
33	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	265.900	TON
34	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	389.000	TON
35	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	470.500	TON
36	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	451.000	TON
37	401-10258 JOINT ADHESIVE, SURFACE	2,424.000	LFT
38	401-10259 JOINT ADHESIVE, INTERMEDIATE	2,424.000	LFT
39	402-07432 HMA SURFACE, TYPE A	29.500	TON
40	402-07433 HMA SURFACE, TYPE B	84.000	TON
41	402-07435 HMA INTERMEDIATE, TYPE A	59.000	TON
42	402-07438 HMA INTERMEDIATE, TYPE B	195.000	TON
43	406-05521 ASPHALT FOR TACK COAT	7,249.000	SYS
44	415-11527 BASE SEAL	2.800	TON
45	503-05240 D-1 CONTRACTION JOINT	113.400	LFT
46	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
47	601-06854 GUARDRAIL, W-BEAM, NESTED	1.000	EACH
48	601-06856 MODIFIED POSTS, NESTED GUARDRAIL	4.000	EACH
49	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH

CALL ORDER : 701

CONTRACT ID : B -35603-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE MAINTENANCE AND REPAIR		
50	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	268.750	LFT
51	602-06729 BARRIER DELINEATOR	7.000	EACH
52	604-07902 CURB RAMP, CONCRETE, H	25.000	SYS
53	605-06150 CURB AND GUTTER, C, CONCRETE	646.000	LFT
54	615-06490 RIGHT OF WAY MARKER	23.000	EACH
55	616-02320 GEOTEXTILES	1,519.000	SYS
56	616-05688 RIPRAP, CLASS 1	634.000	TON
57	616-06405 RIPRAP, REVETMENT	363.000	TON
58	616-06451 RIPRAP, UNIFORM	191.000	TON
59	616-11736 DECORATIVE STONE	124.000	TON
60	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
61	621-02770 EROSION CONTROL BLANKET	3,832.000	SYS
62	621-06545 FERTILIZER	0.320	TON
63	621-06554 SEED MIXTURE, U	120.000	LBS
64	621-06557 SEED MIXTURE, T	120.000	LBS
65	621-09398 SEED MIXTURE, SLOPE STABILIZATION	38.000	LBS
66	621-90853 TAPPING SLEEVE WITH VALVE	1.000	EACH
67	621-90853 TAPPING SLEEVE WITH VALVE	1.000	EACH
68	622-05638 PLANT, DECIDUOUS SHRUB, 18 IN OR UNDER	141.000	EACH
69	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	129.000	EACH
70	628-09402 FIELD OFFICE, B	6.000	MOS
71	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
72	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
73	703-06029 REINFORCING BARS, EPOXY COATED	3,695.000	LBS
74	706-06354 CONCRETE BRIDGE RAILING TRANSITION, TPS-2	2.000	EACH
75	706-08502 REINFORCED CONCRETE MOMENT SLAB, 15 IN	272.000	SYS
76	706-09964 RAILING, CONCRETE, PS-2	153.400	LFT
77	706-11419 RAILING, STEEL, PS-2	162.100	LFT
78	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	2.000	EACH
79	709-51821 SURFACE SEAL	LUMP	LUMP
80	715-04987 CONNECTION	2.000	EACH
81	715-04987 CONNECTION	2.000	EACH
82	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	635.000	LFT
83	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	229.000	LFT
84	715-05153 PIPE, TYPE 2 CIRCULAR 21 IN	231.000	LFT
85	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	45.000	LFT
86	715-06379 SEWER	1.000	EACH
87	715-11360 INSERTION VALVE, 12 IN.	1.000	EACH
88	715-46000 PIPE END SECTION, DIA 12"	1.000	EACH
89	715-46020 PIPE END SECTION, DIA 24"	1.000	EACH
90	715-91742 WATER METER, RELOCATE	1.000	EACH
91	715-96670 WATER MAIN, DUCTILE IRON, 12 IN	370.000	LFT
92	715-97419 WATER MAIN, DUCTILE IRON, 24 IN	365.000	LFT
93	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	635.000	LFT
94	718-52610 AGGREGATE FOR UNDERDRAINS	57.100	CYS
95	718-99153 GEOTEXTILES FOR UNDERDRAIN	423.000	SYS
96	720-44000 CASTING, ADJUST TO GRADE	2.000	EACH
97	720-44015 CASTING, 2, FURNISH AND ADJUST TO GRADE	2.000	EACH
98	720-44296 INLET, CAP	1.000	EACH

CALL ORDER : 701

CONTRACT ID : B -35603-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 BRIDGE MAINTENANCE AND REPAIR			
99	720-45235 CATCH BASIN, E7	1.000	EACH
100	720-45410 MANHOLE, C4	5.000	EACH
101	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	3.000	LFT
102	720-94840 CASTING, WATER VALVE, ADJUST TO GRADE	1.000	EACH
103	720-96999 FIRE HYDRANT ASSEMBLY	2.000	EACH
104	720-97008 FIRE HYDRANT ASSEMBLY, RELOCATE	2.000	EACH
105	720-97009 FIRE HYDRANT ASSEMBLY, REMOVE	2.000	EACH
106	720-98174 INLET, B15	6.000	EACH
107	723-11203 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	76.600	LFT
108	732-08419 MODULAR BLOCK WALL	8.000	SYS
109	732-08420 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	191.000	SYS
110	732-08421 MODULAR BLOCK WALL ERECTION	199.000	SYS
111	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
112	801-06625 DETOUR ROUTE MARKER ASSEMBLY	37.000	EACH
113	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
114	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
115	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
116	801-07118 BARRICADE, III-A	48.000	LFT
117	801-07119 BARRICADE, III-B	96.000	LFT
118	802-07060 SIGN, SHEET, RELOCATE	9.000	EACH
119	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	28.000	SFT
120	802-76055 SIGN POST, A	90.000	LFT
121	808-06540 TRANSVERSE MARKING, PREFORMED PLASTIC	180.000	LFT
122	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	910.000	LFT
123	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	1,594.000	LFT
124	808-75067 TRANSVERSE MARKING, PREFORMED PLASTIC,	72.000	LFT
125	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	2.000	EACH

CALL ORDER : 721

CONTRACT ID : B -35820-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
8	202-62420 BRIDGE RAILING, REMOVE	40.000	LFT
9	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
10	628-09403 FIELD OFFICE, C	4.000	MOS
11	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	8.000	MOS
12	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
13	703-06029 REINFORCING BARS, EPOXY COATED	3,139.000	LBS
14	704-51002 CONCRETE, C, SUPERSTRUCTURE	14.000	CYS
15	711-04297 STRUCTURAL STEEL, FIELD CUT	114.000	SQIN
16	711-51035 STRUCTURAL STEEL	17,131.000	LBS
17	711-51864 DRILLED HOLE	148.000	EACH
18	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
19	801-06640 CONSTRUCTION SIGN, A	2.000	EACH
20	801-06710 FLASHING ARROW SIGN	45.000	DAY
21	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 751

CONTRACT ID : M -31255-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	REPAIR OR REPLACE BARRIER WALL		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-07025 MOBILIZATION AND DEMOBILIZATION	6.000	EACH
6	702-51863 FIELD DRILLED HOLE IN CONCRETE	24.000	EACH
7	702-93722 CONCRETE, C	10.000	CYS
8	703-06029 REINFORCING BARS, EPOXY COATED	150.000	LBS
9	801-03290 CONSTRUCTION SIGN, C	6.000	EACH
10	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	50.000	LFT
11	801-06640 CONSTRUCTION SIGN, A	30.000	EACH
12	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
13	801-06710 FLASHING ARROW SIGN	14.000	DAY
14	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	1.000	EACH
15	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	1.000	EACH
16	801-07119 BARRICADE, III-B	48.000	LFT
17	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	50.000	LFT
18	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	100.000	LFT
19	801-99182 TEMPORARY CHANGEABLE MESSAGE SIGN, INSTALL AND MAINTAIN	2.000	EACH

CALL ORDER : 761

CONTRACT ID : M -31256-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, TREE REMOVE AND TRIMMING		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	201-02250 TREE, 10 IN, REMOVE	14.000	EACH
7	201-02250 TREE, 10 IN, REMOVE	1.000	EACH
8	201-02255 TREE, 18 IN, REMOVE	30.000	EACH
9	201-02255 TREE, 18 IN, REMOVE	1.000	EACH
10	201-02260 TREE, 30 IN, REMOVE	29.000	EACH
11	201-02260 TREE, 30 IN, REMOVE	1.000	EACH
12	201-02265 TREE, 48 IN, REMOVE	19.000	EACH
13	201-02265 TREE, 48 IN, REMOVE	1.000	EACH
14	201-02270 TREE, 60 IN, REMOVE	2.000	EACH
15	201-02270 TREE, 60 IN, REMOVE	1.000	EACH
16	202-91922 STUMP, REMOVE	95.000	EACH
17	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
18	801-06640 CONSTRUCTION SIGN, A	4.000	EACH
19	801-06710 FLASHING ARROW SIGN	20.000	DAY
20	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 771

CONTRACT ID : M -35607-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT MAINTENANCE WORK PROJECT (GENERAL MAINTENANCE)		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
5 628-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
6 628-09408	MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
7 628-09409	MOBILE INTERNET SERVICE	6.000	MOS
8 628-10246	CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	6.000	MOS
9 628-11068	CELLULAR TELEPHONE/RADIO	1.000	EACH

CALL ORDER : 781

CONTRACT ID : M -35818-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	WEDGE AND LEVEL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	306-08034 MILLING, ASPHALT, 1 1/2 IN	237,300.000	SYS
9	402-07434 HMA SURFACE, TYPE C	13,720.000	TON
10	402-07784 HMA SURFACE, TYPE D	6,760.000	TON
11	406-05520 ASPHALT FOR TACK COAT	620.000	TON
12	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
13	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	5.000	MOS
14	628-09409 MOBILE INTERNET SERVICE	5.000	MOS
15	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	5.000	MOS
16	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
17	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
18	801-06710 FLASHING ARROW SIGN	90.000	DAY
19	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
20	801-92448 CONSTRUCTION SIGNS, MOBILE	90.000	DAY
21	808-06711 LINE, PAINT, BROKEN, WHITE, 4 IN	23,950.000	LFT
22	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	23,860.000	LFT
23	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	123,127.000	LFT
24	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	125,000.000	LFT
25	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2,000.000	EACH
26	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	2,000.000	EACH

CALL ORDER : 791

CONTRACT ID : M -35855-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	GUARDRAIL MAINTENANCE OR REPAIR		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	601-01128 GUARDRAIL, TRANSITION TYPE WGB	1.000	EACH
7	601-01522 GUARDRAIL, TRANSITION TYPE TGB	1.000	EACH
8	601-02103 GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN SPACING	600.000	LFT
9	601-02212 GUARDRAIL POST, BRACKET, 8.5 LBS PER FT, GALVANIZED,	50.000	EACH
10	601-03444 CAT TRANSITION STEEL POST, MK 9	5.000	EACH
11	601-03445 CAT TRANSITION PANEL, MK WC	5.000	EACH
12	601-03446 CAT TRANSITION CABLE, MK CA	5.000	EACH
13	601-03447 CAT BRACKET MK BK, FOR TRANSITION CABLE, MK CA	5.000	EACH
14	601-03448 CAT TRANSITION STEEL POST BRACKET, MK D	5.000	EACH
15	601-03462 GUARDRAIL, POST STEEL, 8.5 LBS PER LFT, 7 FT. 0 IN.	75.000	EACH
16	601-03471 CAT UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES,	8.000	EACH
17	601-03599 GUARDRAIL, THRIE BEAM, RAIL SECTION, 12 FT. 6 IN	5.000	EACH
18	601-03683 COMBINATION ATTENUATING TERMINAL, REPAIR, LABOR ONLY	50.000	HRS
19	601-61340 GUARDRAIL POST, 15.5 LBS PER FT., GALVANIZED, 6 FT. 3 IN.	75.000	EACH
20	601-61350 GUARDRAIL POST BRACKET, 15.5 LBS PER LFT., GALVANIZED,	50.000	EACH
21	601-61390 GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE,	5.000	EACH
22	601-61400 GUARDRAIL BURIED END, GALVANIZED, SINGLE FACE	5.000	EACH
23	601-62530 GUARDRAIL PIER CONNECTION, ES	2.000	EACH
24	601-62540 GUARDRAIL POST, PLUMB	500.000	EACH
25	601-62555 GUARDRAIL, TUBING, ELLIPTICAL, ALUMINUM, LABOR ONLY	250.000	LFT
26	601-62580 GUARDRAIL SPLICE BAR, ALUMINUM	10.000	EACH
27	601-90678 CONCRETE, A, BURIED END SECTION	11.000	CYS
28	601-90745 GUARDRAIL POST ALUMINUM	25.000	EACH
29	601-91428 GUARDRAIL ATTENUATING TERMINAL, NOSE ASSEMBLY, MKN	6.000	EACH
30	601-91432 GUARDRAIL ATTENUATING TERMINAL, SIDE PLATE, MKSD	6.000	EACH
31	601-91504 GUARDRAIL POST, W1, 10 IN X 10 IN	5.000	EACH
32	601-91505 GUARDRAIL POST, W2, 8 IN. X 8 IN.	5.000	EACH
33	601-91542 GUARDRAIL BLOCK, 6 IN. X 8 IN., B1	5.000	EACH
34	601-91649 GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	2.000	EACH
35	601-91653 GUARDRAIL THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	2.000	EACH
36	601-93346 GUARDRAIL CONNECTOR, AS	5.000	EACH
37	601-94645 GUARDRAIL END TREATMENT, SENTRE	1.000	EACH
38	601-94689 GUARDRAIL END TREATMENT, OS	8.000	EACH
39	601-94690 GUARDRAIL END TREATMENT, MS	5.000	EACH
40	601-95972 GUARDRAIL POST (CRT), 8 IN X 6 IN TREATED LUMBER,	5.000	EACH
41	601-96591 GUARDRAIL PANEL, STEEL BEAM	4,950.000	LFT
42	601-97947 GUARDRAIL CLAMP BAR, ALUMINUM	100.000	EACH
43	601-97950 GUARDRAIL POST BRACKET, TREATED TIMBER, 6 IN. X 6 IN.	5.000	EACH
44	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	2,000.000	LFT
45	601-99109 GUARDRAIL, W-BEAM, DOUBLE FACED, 3 FT 1.5 IN SPACING	250.000	LFT
46	601-99123 GUARDRAIL, TRANSITION, GP	1.000	EACH
47	628-09401 FIELD OFFICE, A	12.000	MOS
48	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 811

CONTRACT ID : T -34596-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGNAL PROJECT (NEW/MODERNIZED)		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
7	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	11.000	MOS
8	628-09409 MOBILE INTERNET SERVICE	11.000	MOS
9	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	11.000	MOS
10	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
11	711-05395 REPLACE	11.000	EACH
12	711-05396 REPLACE	LUMP	LUMP
13	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
14	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	39.000	EACH
15	805-01842 HANDHOLE, SIGNAL	57.000	EACH
16	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	7,304.000	LFT
17	805-02328 SIGNAL CABLE, 1C/14 GA	27,145.000	LFT
18	805-02373 SIGNAL INTERCONNECT CABLE, FIBER OPTIC	28,866.000	LFT
19	805-02596 CONDUIT RISER WITH WEATHERHEAD, STEEL	12.000	EACH
20	805-04602 CONTROLLER, REWIRE	39.000	EACH
21	805-04973 CONDUIT	7,304.000	LFT
22	805-06483 CONTROLLER	39.000	EACH
23	805-06483 CONTROLLER	39.000	EACH
24	805-06483 CONTROLLER	39.000	EACH
25	805-06483 CONTROLLER	39.000	EACH
26	805-06997 CAMERA	145.000	EACH
27	805-07212 SPLICE KIT	40.000	EACH
28	805-08493 RADIO, INTERCONNECTION SYSTEM TESTING	LUMP	LUMP
29	805-09089 RADIO, YAGI ANTENNA	28.000	EACH
30	805-10108 WIRELESS REPEATER	10.000	EACH
31	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	57,004.000	LFT
32	805-78785 SIGNAL DETECTOR HOUSING	171.000	EACH
33	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	8,209.000	LFT
34	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	148.000	EACH
35	805-97042 SIGNAL POLE, WOOD, 5, 35 FT	3.000	EACH
36	807-02783 LUMINAIRE, MAST ARM, 15 FT	2.000	EACH
37	807-02784 LUMINAIRE, MAST ARM, 20 FT	4.000	EACH
38	807-04940 MAST ARM	21.000	EACH
39	807-04967 CABLE	30,315.000	LFT
40	807-04967 CABLE	30,315.000	LFT
41	807-04967 CABLE	3,756.000	LFT
42	807-06796 ELECTRIC	39.000	EACH

CALL ORDER : 821

CONTRACT ID : T -34768-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PAVEMENT MARKING			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-75997 PRISMATIC REFLECTOR, REMOVE	2,260.000	EACH
9	408-07504 CRACKS AND JOINTS IN ASPHALT PAVEMENT, SEAL	11.000	TON
10	412-09355 FOG SEAL	51,189.000	SYS
11	606-07484 MILLED HMA CORRUGATIONS	122,313.000	LFT
12	606-09729 MILLED CENTERLINE CORRUGATIONS	108,034.000	LFT
13	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
14	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	6.000	MOS
15	628-09409 MOBILE INTERNET SERVICE	6.000	MOS
16	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	6.000	MOS
17	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
18	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
19	801-03290 CONSTRUCTION SIGN, C	20.000	EACH
20	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	11,200.000	LFT
21	801-06640 CONSTRUCTION SIGN, A	103.000	EACH
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	8.000	EACH
24	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	18,934.000	LFT
25	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	131,011.000	LFT
26	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	107,339.000	LFT
27	808-06716 LINE, REMOVE	239,852.000	LFT
28	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP

CALL ORDER : 831

CONTRACT ID : T -34774-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INSTALL NEW GUARDRAIL		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	203-02070 BORROW	9,106.000	CYS
9	203-08607 LINEAR GRADING	800.000	LFT
10	205-06933 TEMPORARY INLET PROTECTION	25.000	EACH
11	205-11591 TEMPORARY SEED MIXTURE	4,350.000	LBS
12	303-01180 COMPACTED AGGREGATE, NO. 53	556.000	TON
13	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
14	621-06553 SEED MIXTURE, R	4,930.000	LBS
15	627-09327 CABLE BARRIER SYSTEM, TYPE TL-4	30,311.000	LFT
16	627-09329 CABLE BARRIER, TYPE TL-4, SPARE PARTS	1.000	EACH
17	627-09331 SAFETY TERMINAL, TYPE TL-4	16.000	EACH
18	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
19	628-09402 FIELD OFFICE, B	12.000	MOS
20	628-11068 CELLULAR TELEPHONE/RADIO	3.000	EACH
21	628-11069 CELLULAR TELEPHONE/RADIO SERVICE, ANYTIME MINUTES	36.000	MOS
22	720-44000 CASTING, ADJUST TO GRADE	25.000	EACH
23	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.000	EACH
24	801-03290 CONSTRUCTION SIGN, C	8.000	EACH
25	801-06640 CONSTRUCTION SIGN, A	40.000	EACH
26	801-06710 FLASHING ARROW SIGN	90.000	DAY
27	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
28	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	4.000	EACH
29	804-06740 DELINEATOR WITH POST, D2	16.000	EACH

CALL ORDER : 851

CONTRACT ID : T -35288-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	DISTRICT PAVEMENT MARKING PROJECT		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
7	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	4.000	MOS
8	628-09409 MOBILE INTERNET SERVICE	4.000	MOS
9	628-10246 CELLULAR TELEPHONE/RADIO SERVICE, 1000 MIN	4.000	MOS
10	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
11	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
12	801-06710 FLASHING ARROW SIGN	50.000	DAY
13	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
14	808-75994 PRISMATIC REFLECTOR	28,353.000	EACH
15	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1,072.000	EACH
16	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	4,289.000	EACH

CALL ORDER : 861

CONTRACT ID : T -35336-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW SIGNAL INSTALLATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	306-08034 MILLING, ASPHALT, 1 1/2 IN	277.000	SYS
9	402-07433 HMA SURFACE, TYPE B	32.000	TON
10	406-05520 ASPHALT FOR TACK COAT	0.100	TON
11	605-06121 CURB, CONCRETE, B	95.000	LFT
12	628-09401 FIELD OFFICE, A	4.000	MOS
13	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
14	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
16	802-04089 SIGN, SHEET, REMOVE	5.000	EACH
17	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	78.000	LFT
18	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	70.000	SFT
19	804-06771 DELINEATOR POST, FLEXIBLE	25.000	EACH
20	805-01842 HANDHOLE, SIGNAL	11.000	EACH
21	805-02645 SIGNAL PEDESTAL FOUNDATION, A	1.000	EACH
22	805-04133 SIGNAL PEDESTAL, 12FT	1.000	EACH
23	805-06595 CONDUIT, PVC, 2 IN	1,476.000	LFT
24	805-09539 LOOP DETECTOR DELAY COUNTING AMPLIFIER, 2 CHANNEL	2.000	EACH
25	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
26	805-78190 TRAFFIC SIGNAL HEAD, 1 FACE, 12 IN AMBER	2.000	EACH
27	805-78205 TRAFFIC SIGNAL HEAD, 3 FACE, 12 IN	8.000	EACH
28	805-78415 SPAN, CATENARY, AND TETHER	3.000	EACH
29	805-78420 DISCONNECT HANGER	3.000	EACH
30	805-78445 SIGNAL SERVICE	1.000	EACH
31	805-78467 SIGNAL CABLE, 3C/8GA	183.000	LFT
32	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	731.000	LFT
33	805-78480 SIGNAL CABLE, 3C/14GA	1,206.000	LFT
34	805-78485 SIGNAL CABLE, 5C/14GA	351.000	LFT
35	805-78490 SIGNAL CABLE, 7C/14GA	791.000	LFT
36	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	2,535.000	LFT
37	805-78785 SIGNAL DETECTOR HOUSING	4.000	EACH
38	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	229.000	LFT
39	805-78906 SIGNAL SUPPORT FOUNDATION, 3 FT X 3 FT X 12 FT	3.000	EACH
40	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
41	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT	3.000	EACH
42	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,297.000	LFT
43	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	367.000	LFT
44	808-06716 LINE, REMOVE	2,160.000	LFT
45	808-75215 LINE, THERMOPLASTIC, SOLID, WHITE 12 IN	163.000	LFT
46	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,186.000	LFT
47	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	45.000	LFT
48	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	1.000	EACH
49	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	74.000	LFT

CALL ORDER : 861

CONTRACT ID : T -35336-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW SIGNAL INSTALLATION		
50 808-96016	LINE, THERMOPLASTIC, SOLID, YELLOW, 12 IN	23.000	LFT

CALL ORDER : 871

CONTRACT ID : T -35390-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SIGN MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	628-09401 FIELD OFFICE, A	6.000	MOS
7	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
8	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	6,720.000	LFT
9	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	684.000	EACH
10	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	3,260.000	SFT
11	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	513.000	SFT

CALL ORDER : 881

CONTRACT ID : T -35504-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LOCAL SAFETY PROJECT		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	628-09402 FIELD OFFICE, B	4.000	MOS
7	801-06710 FLASHING ARROW SIGN	80.000	DAY
8	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
9	801-92448 CONSTRUCTION SIGNS, MOBILE	320.000	DAY
10	802-04089 SIGN, SHEET, REMOVE	463.000	EACH
11	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	15,103.000	LFT
12	802-05705 SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	563.000	LFT
13	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	1,537.000	EACH
14	802-07060 SIGN, SHEET, RELOCATE	87.000	EACH
15	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	8,216.810	SFT
16	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	5,553.480	SFT
17	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	1,024.500	SFT

CALL ORDER : 891

CONTRACT ID : T -35532-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SIGNING			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	202-07083 REMOVAL	LUMP	LUMP
8	202-94954 BARRIER WALL, CONCRETE, REMOVE	15.000	LFT
9	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
10	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	1,000.000	LFT
11	801-06640 CONSTRUCTION SIGN, A	8.000	EACH
12	801-06710 FLASHING ARROW SIGN	9.000	DAY
13	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
14	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	1.000	EACH
15	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	1,000.000	LFT
16	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
17	802-09578 OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	1.000	EACH
18	802-09580 CANTILEVER SIGN SUPPORT FOUNDATION,	1.000	EACH
19	802-76235 INSTALL OVERHEAD SIGN	2.000	EACH

CALL ORDER : 901

CONTRACT ID : TM-35577-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LIGHTING MAINTENANCE		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	202-01845 CONDUIT, REMOVE	300.000	LFT
7	202-86946 HANDHOLE, REMOVE	5.000	EACH
8	202-95579 SERVICE POINT, REMOVE	1.000	EACH
9	202-98370 POLE, REMOVE	1.000	EACH
10	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
11	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	7.000	MOS
12	628-11068 CELLULAR TELEPHONE/RADIO	1.000	EACH
13	702-90915 CONCRETE, CLASS A	1.000	CYS
14	711-95290 FIELD WELDING	1.000	LFT
15	715-04612 PIPE	1.000	LFT
16	715-04994 METER	1.000	EACH
17	715-04994 METER	5.000	EACH
18	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
19	801-06710 FLASHING ARROW SIGN	10.000	DAY
20	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
21	805-02202 SIGNAL DETECTOR HOUSING, DOUBLE	2.000	EACH
22	805-78445 SIGNAL SERVICE	10.000	EACH
23	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	3,000.000	LFT
24	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	1,000.000	LFT
25	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
26	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	1,000.000	LFT
27	805-86898 CONDUIT, STEEL, GALVANIZED, 0.75 IN	50.000	LFT
28	805-87715 GROUND ROD WITH CONNECTOR	1.000	EACH
29	805-87780 CIRCUIT BREAKER	5.000	EACH
30	805-91703 CONDUIT, STEEL, GALVANIZED, 1.5 IN	10.000	LFT
31	805-91706 ANCHOR BOLT, REPAIR	4.000	EACH
32	805-91711 EXPANSION FITTING, 1.5 IN.	1.000	EACH
33	805-95518 CONDUIT FLEXIBLE 2"	100.000	LFT
34	805-95519 CONDUIT FLEXIBLE 0.75"	100.000	LFT
35	805-95520 EXPANSION FITTING, 2.0 IN.	1.000	EACH
36	805-95521 EXPANSION FITTING, 0.75 IN.	2.000	EACH
37	807-01562 POWER DISCONNECT PLUG FOR HIGH MAST TOWER	5.000	EACH
38	807-01563 HIGH MAST TOWER LOCATING PIN, STAINLESS STEEL	1.000	EACH
39	807-01564 HIGH MAST TOWER, SMALL GEAR OF CHAIN DRIVE	1.000	EACH
40	807-01617 HANDHOLE COVER AND RING	1.000	EACH
41	807-02105 ROUTINE MAINTENANCE LUMINAIRE, HIGH PRESSURE SODIUM, 150 W	648.000	MOS
42	807-02109 LUMINAIRE, SIGN, MERCURY VAPOR, WITH GLARE SHIELD	2.000	EACH
43	807-02191 HANDHOLE, LIGHTING	1.000	EACH
44	807-02579 MAST ARM, 15FT	1.000	EACH
45	807-02778 LUMINAIRE, MAST ARM, 5 FT	1.000	EACH
46	807-02780 LUMINAIRE, MAST ARM, 8 FT	1.000	EACH
47	807-02781 LUMINAIRE, MAST ARM, 10 FT	1.000	EACH
48	807-02782 LUMINAIRE, MAST ARM, 12 FT	1.000	EACH
49	807-02784 LUMINAIRE, MAST ARM, 20 FT	1.000	EACH

CALL ORDER : 901

CONTRACT ID : TM-35577-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LIGHTING MAINTENANCE		
50	807-02785 LUMINAIRE, MAST ARM, 25 FT	1.000	EACH
51	807-04507 TRANSFORMER	1.000	EACH
52	807-04651 WIRE,	100.000	LFT
53	807-04651 WIRE,	100.000	LFT
54	807-04654 LIGHT POLE	1.000	EACH
55	807-04654 LIGHT POLE	1.000	EACH
56	807-04654 LIGHT POLE	1.000	EACH
57	807-04654 LIGHT POLE	1.000	EACH
58	807-04654 LIGHT POLE	1.000	EACH
59	807-04654 LIGHT POLE	1.000	EACH
60	807-04654 LIGHT POLE	1.000	EACH
61	807-04940 MAST ARM	10.000	EACH
62	807-04962 LIGHT	1.000	EACH
63	807-04967 CABLE	200.000	LFT
64	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	25.000	LFT
65	807-07703 HIGH MAST TOWER	2.000	EACH
66	807-11367 ASSIGNED MAINTENANCE, NAVIGATION LIGHT	324.000	EACH
67	807-86615 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	24.000	EACH
68	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	17.000	EACH
69	807-86665 LUMINAIRE, HIGH MAST, HIGH PRESSURE SODIUM, 1000 WATT	1.000	EACH
70	807-86750 LUMINAIRE, UNDERPASS, WALL MOUNTED, HIGH PRESSURE, 150	2.000	EACH
71	807-86790 LUMINAIRE, SIGN, MERCURY VAPOR, WITH GLARE SHIELD, 250 WATT	2.000	EACH
72	807-86805 SERVICE POINT, I	1.000	EACH
73	807-86810 SERVICE POINT, II	1.000	EACH
74	807-86842 WIRE, AWG, MTW, THHW, THWN, AWM, GASOLINE AND OIL RESISTANT,	100.000	LFT
75	807-86843 WIRE, NO 4 COPPER, 1/C	250.000	LFT
76	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	2,000.000	LFT
77	807-86910 CONNECTOR KIT, UNFUSED	20.000	EACH
78	807-86915 CONNECTOR KIT, FUSED	20.000	EACH
79	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	30.000	EACH
80	807-86930 INSULATION LINK, NON-WATERPROOFED	30.000	EACH
81	807-86950 SIGN UNDERPASS AND ROADWAY LIGHTING LOCATION IDENTIFICATION	5.000	EACH
82	807-86955 CABLE-DUCT MARKER	2.000	EACH
83	807-87022 ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM,	10,968.000	MOS
84	807-87028 ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM,	9,216.000	MOS
85	807-87042 ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM,	2,700.000	MOS
86	807-87085 ELECTRICIAN	25.000	HRS
87	807-87098 CALLOUT, REPAIR	2.000	EACH
88	807-87595 REPLACEMENT OF CABLE CLAMPS ON HIGHMAST TOWER LUMINAIRE, RIN	2.000	EACH
89	807-87640 BREAKAWAY COUPLING	5.000	SET
90	807-87800 CABLE DUCT, INSTALL	1,000.000	LFT
91	807-91694 NAVIGATION LIGHT PIER	1.000	EACH
92	807-91696 NAVIGATION LIGHT CENTRE CHANNEL	1.000	EACH
93	807-91696 NAVIGATION LIGHT CENTRE CHANNEL	1.000	EACH
94	807-91698 NAVIGATION LIGHT, FRESNEL LENS, 180	6.000	EACH
95	807-91699 NAVIGATION LIGHT, FRESNEL LENS, 360	2.000	EACH
96	807-91704 LIGHT POLE HANDHOLE COVER	5.000	EACH
97	807-91705 CONDUIT, POLYETHYLENE, REPAIR	2.000	EACH
98	807-92870 TRANSFORMER BASE HANDHOLE	2.000	EACH

CALL ORDER : 901

CONTRACT ID : TM-35577-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	LIGHTING MAINTENANCE		
99 807-93647	LUMINAIRE, POST TOP, HIGH PRESSURE SODIUM, 150 WATT	1.000	EACH
100 807-93649	SHAFT FOR POST TOP LUMINAIRE, 16 FT M.H.	1.000	EACH
101 807-93650	FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR ROADWAY	1.000	SET
102 807-93651	FOUNDATION, ANCHOR BOLTS & REINFORCING STEEL	1.000	SET
103 807-94480	LIGHT STANDARD, INSTALL	12.000	EACH
104 807-95508	VANDAL SHIELD, LEXAN	1.000	EACH
105 807-95513	SERVICE POINT MAIN BREAKER	2.000	EACH
106 807-95514	SERVICE POINT RISER	1.000	EACH
107 807-95515	SERVICE POINT WEATHERHEAD	1.000	EACH
108 807-95516	RELAY SWITCH	5.000	EACH
109 807-95522	PIPE STRAP	10.000	EACH
110 807-95523	WATERPROOFING OF ELECTRICAL CONNECTOR	25.000	EACH
111 807-95525	LIGHTING, HIGHWAY SUPPORT, REPAIR	2.000	EACH
112 807-95705	BREAKAWAY ALUMINUM TRANSFORMER BASE	15.000	EACH
113 807-95709	PHOTOCELLS	1.000	EACH
114 807-96183	SHAFT FOR 30 FT M.H., TWIN 10 FT MAST ARM	1.000	EACH
115 807-96184	SHAFT FOR 30 FT M.H. TWIN 12 FT MAST ARM	1.000	EACH
116 807-96194	ROUTINE MAINTENANCE, LUMINAIRE, HIGH PRESSURE SODIUM,	6,852.000	MOS
117 807-96197	WIRE, AWG, MTW, THHW, THWN, AWM, GASOLINE AND OIL	100.000	LFT
118 807-96203	LIGHT POLE, HIGH MAST, TOWER SUSPENSION CABLE	3.000	EACH
119 807-96204	LOWERING AND RAISING OF TOWER	1.000	EACH
120 807-96236	LIGHT POLE, HIGH MAST, TOWER POWER CABLE	2.000	EACH
121 807-96868	LUMINAIRE, INSTALL	5.000	EACH
122 807-98716	KELLUM GRIP, STAINLESS STEEL	1.000	EACH
123 809-04652	SERVICE POINT	5.000	EACH

