

CALL ORDER : 200

CONTRACT ID : IR-35574-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	108-09283 CPM SCHEDULE	LUMP	LUMP
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	203-02020 EXCAVATION, UNCLASSIFIED	4,213,509.000	CYS
14	203-09567 SPILL CONTAINMENT DAM	10.000	EACH
15	203-11546 NATURAL STONE MATERIAL 12-18"	90.000	CYS
16	203-11546 NATURAL STONE MATERIAL 12-18"	90.000	CYS
17	203-11547 STREAM SUBSTRATE MATERIAL, LESS THAN 12"	126.000	CYS
18	204-02290 SETTLEMENT PLATE	27.000	EACH
19	204-08396 STANDPIPE PIEZOMETER	8.000	EACH
20	204-08414 STAKE, LATERAL	66.000	EACH
21	204-08415 STAKE, SETTLEMENT	99.000	EACH
22	204-08552 VIBRATING WIRE SETTLEMENT SYSTEM	20.000	EACH
23	204-08553 DATA LOGGING SYSTEM	2.000	EACH
24	204-11633 VIBRATING WIRE PIEZOMETER	51.000	EACH
25	204-11653 MAGNETIC EXTENSOMETER	6.000	EACH
26	205-09543 NO 2 STONE	400,982.000	TON
27	205-09952 DESIGN BUILD EROSION AND SEDIMENT CONTROL	LUMP	LUMP
28	205-11545 FILTER BERM	4,294.000	LFT
29	207-08263 SUBGRADE TREATMENT, TYPE IA	122,424.000	SYS
30	207-08265 SUBGRADE TREATMENT, TYPE IIA	1,669.000	SYS
31	211-02050 B BORROW	304,353.000	CYS
32	211-06467 AGGREGATE FOR END BENT BACKFILL	306.000	CYS
33	211-09264 STRUCTURAL BACKFILL, TYPE 1	6,719.000	CYS
34	211-09265 STRUCTURAL BACKFILL, TYPE 2	9,705.000	CYS
35	211-09266 STRUCTURAL BACKFILL, TYPE 3	148,292.000	CYS
36	214-07202 GEOGRID, TYPE I	260,222.000	SYS
37	215-07043 CHEMICAL MODIFICATION, SOILS	204,545.000	SYS
38	215-11477 CHEMICAL STABILIZATION	176,908.000	TON
39	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	9,985.000	TON
40	302-07455 DENSE GRADED SUBBASE	84.000	CYS
41	302-08562 COARSE AGGREGATE, NO 8	4.000	TON
42	303-01180 COMPACTED AGGREGATE, NO. 53	16,133.000	TON
43	303-02125 AGGREGATE, 23	99,942.000	CYS
44	303-07449 COMPACTED AGGREGATE, NO. 73	371.000	TON
45	304-07489 HMA PATCHING, TYPE A	8.000	TON
46	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
47	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	2,000.000	TON
48	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	6,764.000	TON
49	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	11,886.000	TON

CALL ORDER : 200

CONTRACT ID : IR-35574-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
50	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	6,000.000	TON
51	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	14,608.000	TON
52	401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM	44,711.000	TON
53	406-05520 ASPHALT FOR TACK COAT	109.000	TON
54	601-01522 GUARDRAIL, TRANSITION TYPE TGB	6.000	EACH
55	601-94689 GUARDRAIL END TREATMENT, OS	7.000	EACH
56	601-94690 GUARDRAIL END TREATMENT, MS	2.000	EACH
57	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	11,168.750	LFT
58	601-99108 GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN SPACING	700.000	LFT
59	602-06729 BARRIER DELINEATOR	196.000	EACH
60	603-06040 FENCE, FARM FIELD, 47 IN	26,449.000	LFT
61	605-06121 CURB, CONCRETE, B	767.000	LFT
62	606-07484 MILLED HMA SHOULDER CORRUGATIONS	48,775.000	LFT
63	608-05741 WICK DRAIN	3,319,294.000	LFT
64	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	488.000	SYS
65	610-07486 HMA FOR APPROACHES, TYPE A	55.000	TON
66	615-06490 RIGHT OF WAY MARKER	20.000	EACH
67	615-06510 MONUMENT, C	31.000	EACH
68	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
69	616-02320 GEOTEXTILES	65,550.000	SYS
70	616-05688 RIPRAP, CLASS 1	2,547.000	TON
71	616-05689 RIPRAP, CLASS 2	7,285.000	TON
72	616-06405 RIPRAP, REVETMENT	36,953.000	TON
73	616-06451 RIPRAP, UNIFORM	6,392.000	TON
74	616-09395 GEOMEMBRANE	108.000	SYS
75	616-11632 HIGH STRENGTH GEOTEXTILES	522,670.000	SYS
76	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
77	621-02770 EROSION CONTROL BLANKET	97,937.000	SYS
78	621-02770 EROSION CONTROL BLANKET	40,042.000	SYS
79	621-06545 FERTILIZER	39.000	TON
80	621-06553 SEED MIXTURE, R	16,376.000	LBS
81	621-06565 MULCHING MATERIAL	193.000	TON
82	621-06567 WATER	83.000	KGAL
83	621-06574 SODDING	25,120.000	SYS
84	622-52436 SIGN, DO NOT MOW OR SPRAY	72.000	EACH
85	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
86	628-09403 FIELD OFFICE, C	36.000	MOS
87	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	360.000	MOS
88	628-11068 CELLULAR TELEPHONE/RADIO	10.000	EACH
89	628-11069 CELLULAR TELEPHONE/RADIO SERVICE, ANYTIME MINUTES	360.000	MOS
90	701-05561 DRILLED SHAFT	2,970.000	LFT
91	701-05561 DRILLED SHAFT	6,676.000	LFT
92	701-05561 DRILLED SHAFT	5,065.000	LFT
93	701-05785 EXPLORATION (SHAFT EXCAVATION)	3,319.000	LFT
94	702-51005 CONCRETE, A, SUBSTRUCTURE	2,355.000	CYS
95	702-51005 CONCRETE, A, SUBSTRUCTURE	10,489.000	CYS
96	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	6,000.000	LBS
97	702-76240 CONCRETE	4.000	CYS
98	703-06028 REINFORCING BARS	1,261,902.000	LBS

CALL ORDER : 200

CONTRACT ID : IR-35574-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
99	703-06029 REINFORCING BARS, EPOXY COATED	2,151,239.000	LBS
100	704-51002 CONCRETE, C, SUPERSTRUCTURE	4,943.000	CYS
101	706-11621 CONCRETE BRIDGE RAILING TRANSITION, TFT	8.000	EACH
102	706-51020 RAILING, CONCRETE, C	926.000	CYS
103	709-51821 SURFACE SEAL	LUMP	LUMP
104	709-51821 SURFACE SEAL	LUMP	LUMP
105	711-07857 INCLINOMETER	23.000	EACH
106	711-51038 STRUCTURAL STEEL	LUMP	LUMP
107	711-51038 STRUCTURAL STEEL	LUMP	LUMP
108	714-11092 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	30.000	LFT
109	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	67,565.000	LFT
110	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	6,959.000	LFT
111	715-05125 PIPE, TYPE 1 CIRCULAR 30 IN	24.000	LFT
112	715-05146 PIPE, TYPE 2 CIRCULAR 6 IN	28.000	LFT
113	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	659.000	LFT
114	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	1,697.000	LFT
115	715-05218 PIPE, TYPE 5 CIRCULAR 15 IN	231.000	LFT
116	715-05407 PIPE, END BENT DRAIN, 6 IN	180.000	LFT
117	715-09938 PIPE, BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
118	715-09938 PIPE, BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
119	718-03277 PIPE, UNDERDRAIN, CORRUGATED PLASTIC, PERFORATED, 6 IN.	47.000	LFT
120	718-06528 OUTLET PROTECTOR, 1	8.000	EACH
121	718-06529 OUTLET PROTECTOR, 2	100.000	EACH
122	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	6,500.000	LFT
123	718-52610 AGGREGATE FOR UNDERDRAINS	3,610.000	CYS
124	718-99153 GEOTEXTILES FOR UNDERDRAIN	39,711.000	SYS
125	720-03905 CATCH BASIN, A	3.000	EACH
126	720-45065 INLET, N12	22.000	EACH
127	720-45070 INLET, P12A	1.000	EACH
128	720-45090 INLET, UA	1.000	EACH
129	720-45095 INLET, WA	1.000	EACH
130	720-45095 INLET, WA	2.000	EACH
131	720-94157 MANHOLE, C	1.000	EACH
132	720-94847 INLET, R13, MODIFIED	2.000	EACH
133	723-11212 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	525.000	LFT
134	723-11225 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	635.000	LFT
135	724-51927 STRUCTURAL EXPANSION JOINT, M	267.000	LFT
136	728-11672 DRILLED SHAFT, EXPLORATORY CORE	3,319.000	LFT
137	734-09917 CUT-WALL, NO.	1,039.000	SYS
138	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
139	801-06640 CONSTRUCTION SIGN, A	9.000	EACH
140	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
141	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	200.000	LFT
142	802-04893 REFERENCE POST	10.000	EACH
143	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	70.000	LFT
144	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	48.000	SFT
145	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	1,869.000	LFT
146	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	29,900.000	LFT
147	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	29,900.000	LFT

CALL ORDER : 200

CONTRACT ID : IR-35574-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD AND BRIDGE CONSTRUCTION		
148 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	374.000	EACH
SECTION NO. 0002	NEW ROAD AND BRIDGE CONSTRUCTION		
149 104-05404	DESIGN/BUILD	LUMP	LUMP
150 109-08359	LIQUIDATED DAMAGES	1.000	DOL
151 109-08360	CONTRACT LIENS	1.000	DOL
152 109-08440	QUALITY ADJUSTMENTS, HMA	1.000	DOL
153 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
154 109-09489	PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
155 628-08524	CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
156 628-09403	FIELD OFFICE, C	36.000	MOS
157 628-09407	FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	360.000	MOS
158 628-11068	CELLULAR TELEPHONE/RADIO	10.000	EACH
159 628-11069	CELLULAR TELEPHONE/RADIO SERVICE, ANYTIME MINUTES	360.000	MOS