

CALL ORDER : 150

CONTRACT ID : R -29957-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT AND TRAFFIC SIGNAL MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
9	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
10	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
11	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
12	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
13	202-06541 REMOVE	1.000	EACH
14	205-06933 TEMPORARY INLET PROTECTION	10.000	EACH
15	205-06937 TEMPORARY SILT FENCE	2,548.000	LFT
16	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,953.000	SYS
17	211-09264 STRUCTURAL BACKFILL, TYPE 1	1,405.000	CYS
18	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,078.000	SYS
19	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	3.000	EACH
20	601-02241 GUARDRAIL, REMOVE	752.000	LFT
21	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	710.000	LFT
22	604-06070 SIDEWALK, CONCRETE	2,672.000	SYS
23	604-07894 CURB RAMP, CONCRETE, A	77.000	SYS
24	604-07900 CURB RAMP, CONCRETE, F	45.000	SYS
25	604-07902 CURB RAMP, CONCRETE, H	13.000	SYS
26	605-06120 CURB, CONCRETE	167.000	LFT
27	605-94755 CURB, RESET	280.000	LFT
28	610-07788 HMA FOR APPROACHES, TYPE D	1,162.000	TON
29	610-09108 PCCP FOR APPROACHES, 9 IN	1,905.000	SYS
30	615-06510 MONUMENT, C	1.000	EACH
31	616-02320 GEOTEXTILES	657.000	SYS
32	616-06405 RIPRAP, REVETMENT	547.000	TON
33	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
34	621-02770 EROSION CONTROL BLANKET	887.000	SYS
35	621-06567 WATER	15.800	KGAL
36	621-06575 SODDING, NURSERY	3,952.000	SYS
37	621-52448 SIGN, DO NOT SPRAY	4.000	EACH
38	621-90853 TAPPING SLEEVE WITH VALVE	2.000	EACH
39	622-05643 PLANT, DECIDUOUS TREE, MULTI-STEM, 48 IN OR UNDER	15.000	EACH
40	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	15.000	EACH
41	628-08524 CELLULAR TELEPHONE/RADIO, ADDITIONAL MINUTES	1.000	DOL
42	628-09402 FIELD OFFICE, B	18.000	MOS
43	628-11006 CELLULAR TELEPHONE/RADIO SERVICE, 500 MIN	36.000	MOS
44	628-11068 CELLULAR TELEPHONE/RADIO	2.000	EACH
45	702-90915 CONCRETE, CLASS A	2.300	CYS
46	715-01898 WATER MAIN, DUCTILE IRON, 10 IN	40.000	LFT
47	715-02574 WATER SERVICE CONNECTION, 2 IN.	1.000	EACH
48	715-02743 GATE VALVE WITH VALVE BOX 4 IN	7.000	EACH
49	715-02745 GATE VALVE WITH VALVE BOXES, 8 IN	1.000	EACH

CALL ORDER : 150

CONTRACT ID : R -29957-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PAVEMENT REPLACEMENT AND TRAFFIC SIGNAL MODERNIZATION		
50	715-03033 BLOW OFF ASSEMBLY	9.000	EACH
51	715-04965 WATER SERVICE LINE	30.000	LFT
52	715-04995 LINE STOP	1.000	EACH
53	715-04995 LINE STOP	2.000	EACH
54	715-04995 LINE STOP	5.000	EACH
55	715-04995 LINE STOP	2.000	EACH
56	715-04995 LINE STOP	2.000	EACH
57	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	350.000	LFT
58	715-05147 PIPE, TYPE 2 CIRCULAR 8 IN	26.000	LFT
59	715-05148 PIPE, TYPE 2 CIRCULAR 10 IN	6.000	LFT
60	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	66.000	LFT
61	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	1,240.000	LFT
62	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	446.000	LFT
63	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	494.000	LFT
64	715-11571 WATER MAIN, DUCTILE IRON 8 IN	70.000	LFT
65	715-46005 PIPE END SECTION, DIA 15"	3.000	EACH
66	715-46020 PIPE END SECTION, DIA 24"	2.000	EACH
67	715-46040 PIPE END SECTION, DIA 36 IN	1.000	EACH
68	715-92544 WATER MAIN, DUCTILE IRON, 12 IN	20.000	LFT
69	715-93403 WATER SERVICE CONNECTION, 0.75 IN.	18.000	EACH
70	715-94780 WATER MAIN, DUCTILE IRON, 6 IN	995.000	LFT
71	715-95866 GATE VALVE, 6 IN.	3.000	EACH
72	715-98265 WATER MAIN, DUCTILE IRON, 4 IN	1,565.000	LFT
73	715-98479 GATE VALVE AND BOX, 10 IN.	1.000	EACH
74	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
75	720-44000 CASTING, ADJUST TO GRADE	10.000	EACH
76	720-44296 INLET, CAP	2.000	EACH
77	720-45030 INLET, E7	1.000	EACH
78	720-45035 INLET, F7	1.000	EACH
79	720-45265 PIPE CATCH BASIN, 15 IN	8.000	EACH
80	720-45410 MANHOLE, C4	16.000	EACH
81	720-91973 MANHOLE, H4	3.000	EACH
82	720-96999 FIRE HYDRANT ASSEMBLY	4.000	EACH
83	720-96999 FIRE HYDRANT ASSEMBLY	2.000	EACH
84	720-97008 FIRE HYDRANT ASSEMBLY, RELOCATE	4.000	EACH
85	720-97009 FIRE HYDRANT ASSEMBLY, REMOVE	1.000	EACH
86	720-98174 INLET, B15	19.000	EACH
87	720-98555 INLET, C15	22.000	EACH
88	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
89	801-04308 ROAD CLOSURE SIGN ASSEMBLY	13.000	EACH
90	801-06625 DETOUR ROUTE MARKER ASSEMBLY	50.000	EACH
91	801-06640 CONSTRUCTION SIGN, A	11.000	EACH
92	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
93	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
94	801-07118 BARRICADE, III-A	250.000	LFT
95	801-07119 BARRICADE, III-B	90.000	LFT
96	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	177.000	LFT
97	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	41.000	LFT
98	802-07058 SIGN, SHEET ASSEMBLY, RELOCATE	7.000	EACH

CALL ORDER : 150

CONTRACT ID : R -29957-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PAVEMENT REPLACEMENT AND TRAFFIC SIGNAL MODERNIZATION			
99	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	157.500	SFT
100	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	15.100	SFT
101	805-01815 SIGNAL SUPPORT FOUNDATION, 36 IN X 144 IN	1.000	EACH
102	805-01842 HANDHOLE, SIGNAL	9.000	EACH
103	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN, UNDERGROUND	414.000	LFT
104	805-02032 PEDESTRIAN SIGNAL HEAD, 12 IN., RELOCATE	2.000	EACH
105	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
106	805-02152 PEDESTRIAN SIGNAL HEAD WITH INTERNATIONAL SYMBOL, 18 IN	8.000	EACH
107	805-02645 SIGNAL PEDESTAL FOUNDATION, A	4.000	EACH
108	805-09471 SIGNAL CABLE, PREFORMED PAVE-OVER LOOP	49.000	EACH
109	805-78370 PEDESTRIAN PUSH BUTTON	10.000	EACH
110	805-78415 SPAN, CATENARY, AND TETHER	2.000	EACH
111	805-78470 SIGNAL CABLE, ROADWAY LOOP, 1C/14GA	880.000	LFT
112	805-78480 SIGNAL CABLE, 3C/14GA	558.000	LFT
113	805-78485 SIGNAL CABLE, 5C/14GA	598.000	LFT
114	805-78490 SIGNAL CABLE, 7C/14GA	270.000	LFT
115	805-78510 SIGNAL CABLE, 2C/16GA., SHIELDED	1,617.000	LFT
116	805-78785 SIGNAL DETECTOR HOUSING	2.000	EACH
117	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	276.000	LFT
118	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	1.000	EACH
119	805-90005 SIGNAL PEDESTAL, 10 FT	4.000	EACH
120	805-94295 SIGNAL HEAD, RELOCATE	10.000	EACH
121	808-75007 LINE, PAINT, SOLID, WHITE, 6 IN	714.000	LFT
SECTION NO. 0002 PAVEMENT REPLACEMENT			
122	203-02000 EXCAVATION, COMMON	4,537.000	CYS
123	207-09935 SUBGRADE TREATMENT, TYPE 1C	14,648.000	SYS
124	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	956.000	TON
125	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1,839.000	TON
126	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	4,162.000	TON
127	404-05511 SEAL COAT, 2	476.000	SYS
128	406-05520 ASPHALT FOR TACK COAT	10.240	TON
129	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	433.000	LFT
130	605-52807 CURB AND GUTTER, COMBINED	3,122.000	LFT
131	615-06505 MONUMENT, B	15.000	EACH
132	808-04298 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (RXR)	2.000	EACH
133	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,258.000	LFT
134	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	594.000	LFT
135	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	5,574.000	LFT
136	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	75.000	LFT
137	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	360.000	LFT
138	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	1,206.000	LFT
139	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	12.000	EACH
140	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	8.000	EACH
SECTION NO. 0003 PAVEMENT REPLACEMENT			
141	203-02000 EXCAVATION, COMMON	6,116.000	CYS

CALL ORDER : 150

CONTRACT ID : R -29957-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 PAVEMENT REPLACEMENT			
142	207-09935 SUBGRADE TREATMENT, TYPE 1C	14,738.000	SYS
143	302-07455 DENSE GRADED SUBBASE	2,105.000	CYS
144	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	39.000	TON
145	406-05520 ASPHALT FOR TACK COAT	0.120	TON
146	501-09749 QC/QA PCCP, 9.5"	11,737.000	SYS
147	503-05240 D-1 CONTRACTION JOINT	9,959.000	LFT
148	605-06090 CURB, INTEGRAL, CONCRETE	2,834.000	LFT
149	615-06515 MONUMENT, D	15.000	EACH
150	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	1,258.000	LFT
151	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	5,574.000	LFT
152	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	594.000	LFT
153	808-10042 TRANSVERSE MARKING MULTI-COMPONENT,	75.000	LFT
154	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	360.000	LFT
155	808-10052 PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, (ONLY)	8.000	EACH
156	808-10053 PAVEMENT MESSAGE MARKING, MULTI-COMPONENT,	2.000	EACH
157	808-10056 TRANSVERSE MARKING, MULTI-COMPONENT,	1,206.000	LFT
158	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	12.000	EACH