

CALL ORDER : 110

CONTRACT ID : IR-30091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-11823 CONSTRUCTION ENGINEERING, GPS ROVER	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
10	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
11	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
12	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
13	113-01614 PARTNERING OVERHEAD	LUMP	LUMP
14	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
15	202-01261 TESTING FOR ASBESTOS	6.000	EACH
16	202-02240 PAVEMENT REMOVAL	51,862.000	SYS
17	202-02273 CENTER CURB, CONCRETE, REMOVE	1,468.000	SYS
18	202-02278 CURB, CONCRETE, REMOVE	768.000	LFT
19	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
20	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
21	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
22	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
23	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
24	202-03000 HOUSES AND BUILDINGS, REMOVE, PARCEL NO	LUMP	LUMP
25	202-03135 REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	500.000	SFT
26	202-05546 REGULATED MATERIALS, DISPOSE, C	5.000	TON
27	202-05551 REGULATED MATERIALS, REMOVE, C	5.000	TON
28	202-05556 REGULATED MATERIALS, TRANSPORT, C	5.000	TON
29	202-06580 CONTAMINATED SOIL, REMOVE	500.000	CYS
30	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
31	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
32	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
33	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
34	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
35	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
36	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
37	202-74080 OVERHEAD SIGN STRUCTURE,	4.000	EACH
38	202-90413 SLOPEWALL, CONCRETE, 4 IN, REMOVE	1,039.000	SYS
39	202-93763 LIGHT STANDARD AND FOUNDATION, REMOVE	24.000	EACH
40	203-02000 EXCAVATION, COMMON	31,458.000	CYS
41	203-11864 SOIL EMBANKMENT QUALITY CONTROL	LUMP	LUMP
42	203-51223 EXCAVATION, WATERWAY	169,561.000	CYS
43	205-06930 SPLASHPAD	41.000	TON
44	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	1,848.000	TON
45	205-06933 TEMPORARY INLET PROTECTION	97.000	EACH
46	205-06935 TEMPORARY SEDIMENT BASIN	5.000	EACH
47	205-06936 TEMPORARY SEDIMENT TRAP	886.000	TON
48	205-06937 TEMPORARY SILT FENCE	45,644.000	LFT
49	205-06938 TEMPORARY SLOPE DRAIN	1,148.000	LFT

CALL ORDER : 110

CONTRACT ID : IR-30091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
50	205-08594 FILTER SOCK	29,550.000	LFT
51	205-11625 TEMPORARY DIVERSION CHANNEL	1,972.000	LFT
52	205-11626 PUMP AROUND	10.000	EACH
53	206-51220 EXCAVATION, WET	2,320.000	CYS
54	206-51220 EXCAVATION, WET	447.000	CYS
55	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	524.000	CYS
56	207-08263 SUBGRADE TREATMENT, TYPE IA	194,917.000	SYS
57	207-08264 SUBGRADE TREATMENT, TYPE II	45,557.000	SYS
58	207-08265 SUBGRADE TREATMENT, TYPE IIA	5,610.000	SYS
59	207-08267 SUBGRADE TREATMENT, TYPE IIIA	17,405.000	SYS
60	207-09935 SUBGRADE TREATMENT, TYPE IC	1,130.000	SYS
61	211-02050 B BORROW	29,729.000	CYS
62	211-02050 B BORROW	447.000	CYS
63	211-06467 AGGREGATE FOR END BENT BACKFILL	166.000	CYS
64	211-09264 STRUCTURAL BACKFILL, TYPE 1	659.000	CYS
65	211-09265 STRUCTURAL BACKFILL, TYPE 2	1,893.000	CYS
66	211-09266 STRUCTURAL BACKFILL, TYPE 3	9,137.000	CYS
67	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	5,042.000	TON
68	302-07455 DENSE GRADED SUBBASE	373.200	CYS
69	303-07662 STONE	147.000	TON
70	303-07662 STONE	232.000	TON
71	303-07662 STONE	2,833.000	TON
72	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	245.000	TON
73	306-08039 MILLING, ASPHALT REMOVAL	985.000	SYS
74	306-10163 MILLING ASPHALT, 2 1/2 IN	56,057.000	SYS
75	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
76	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	5,793.000	TON
77	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	4,279.000	TON
78	401-07405 QC/QA-HMA, 5, 76, INTERMEDIATE, 19.0 mm	15,120.000	TON
79	401-07410 QC/QA-HMA, 5, 64, BASE, 25.0 mm	10,520.000	TON
80	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	7,230.000	TON
81	401-08365 QC/QA-HMA, 5, 64, BASE, 19.0 mm	4,697.000	TON
82	402-10086 HMA FOR TEMPORARY PAVEMENT, C	10,758.000	TON
83	402-10087 HMA FOR TEMPORARY PAVEMENT, D	8,379.000	TON
84	410-09086 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm - SMA	6,829.000	TON
85	503-03489 RETROFITTED TIE BARS	243.000	EACH
86	506-06333 PCCP PATCHING, FULL DEPTH	1,130.000	SYS
87	601-01522 GUARDRAIL, TRANSITION TYPE TGB	16.000	EACH
88	601-02241 GUARDRAIL, REMOVE	6,419.000	LFT
89	601-06238 IMPACT ATTENUATOR, R1, W1, TL-3	3.000	EACH
90	601-06242 IMPACT ATTENUATOR, R2, W1, TL-2	3.000	EACH
91	601-06246 IMPACT ATTENUATOR, R2, W1, TL-3	8.000	EACH
92	601-06854 GUARDRAIL, W-BEAM, NESTED	10.000	EACH
93	601-06855 GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	7.000	EACH
94	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	4.000	EACH
95	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	4.000	EACH
96	601-11530 IMPACT ATTENUATOR SPARE PARTS PACKAGE,	4.000	EACH
97	601-11531 IMPACT ATTENUATOR SPARE PARTS PACKAGE,	4.000	EACH
98	601-11532 IMPACT ATTENUATOR SPARE PARTS PACKAGE,	4.000	EACH

CALL ORDER : 110

CONTRACT ID : IR-30091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
99	601-11533 IMPACT ATTENUATOR SPARE PARTS PACKAGE,	4.000	EACH
100	601-11534 IMPACT ATTENUATOR SPARE PARTS PACKAGE,	4.000	EACH
101	601-11535 IMPACT ATTENUATOR SPARE PARTS PACKAGE,	4.000	EACH
102	601-94689 GUARDRAIL END TREATMENT, OS	38.000	EACH
103	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	7,913.000	LFT
104	602-01064 CONCRETE BARRIER	12,348.000	LFT
105	602-06729 BARRIER DELINEATOR	65.000	EACH
106	603-06045 FENCE, CHAIN LINK, 48 IN	8,337.000	LFT
107	603-97283 FENCE GATE, CHAIN LINK, 48 IN X 24 FT	1.000	EACH
108	603-97461 TEMPORARY FENCE	16,171.000	LFT
109	605-02493 CURB ISLAND, CONCRETE	19.000	SYS
110	605-05523 CURB, HMA	80.000	LFT
111	605-06095 CURB, INTEGRAL, B, CONCRETE	2.000	LFT
112	605-06120 CURB, CONCRETE	109.000	LFT
113	605-06255 CENTER CURB, D, CONCRETE	28.000	SYS
114	605-94811 CURB TURNOUT	4.000	EACH
115	607-06385 PAVED SIDE DITCH, L	361.000	LFT
116	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	1,151.000	SYS
117	610-07487 HMA FOR APPROACHES, TYPE B	271.000	TON
118	610-09108 PCCP FOR APPROACHES, 9 IN	304.000	SYS
119	611-06497 MAILBOX ASSEMBLY, SINGLE	8.000	EACH
120	611-06498 MAILBOX ASSEMBLY, DOUBLE	1.000	EACH
121	615-06490 RIGHT OF WAY MARKER	72.000	EACH
122	615-06510 MONUMENT, C	34.000	EACH
123	615-06527 MONUMENT, SECTION CORNER	4.000	EACH
124	615-06530 BENCH MARK POST	14.000	EACH
125	616-01763 RIPRAP, RELAID	212.000	SYS
126	616-02320 GEOTEXTILES	32,182.000	SYS
127	616-05688 RIPRAP, CLASS 1	3,680.000	TON
128	616-05689 RIPRAP, CLASS 2	671.000	TON
129	616-06405 RIPRAP, REVETMENT	8,534.000	TON
130	616-06451 RIPRAP, UNIFORM	15.000	TON
131	616-11349 ROOTWAD REVETMENT	1,350.000	LFT
132	616-51367 SLOPEWALL, CONCRETE, 4 IN	344.000	SYS
133	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	16.000	EACH
134	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	14,516.000	SYS
135	621-02770 EROSION CONTROL BLANKET	46,257.000	SYS
136	621-04258 SEED MIXTURE	35.000	LBS
137	621-04258 SEED MIXTURE	171.000	LBS
138	621-04258 SEED MIXTURE	97.000	LBS
139	621-06545 FERTILIZER	28.000	TON
140	621-06554 SEED MIXTURE, U	1,941.000	LBS
141	621-06557 SEED MIXTURE, T	3,664.000	LBS
142	621-06565 MULCHING MATERIAL	153.000	TON
143	621-06567 WATER	126.000	KGAL
144	621-06570 TOPSOIL	27,890.000	CYS
145	621-06574 SODDING	20,895.000	SYS
146	621-06575 SODDING, NURSERY	15,171.000	SYS
147	621-07642 SOIL PREPARATION	95,446.000	CYS

CALL ORDER : 110

CONTRACT ID : IR-30091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
148	621-08161 PERMANENT TURF REINFORCEMENT MAT	28,353.000	SYS
149	622-10003 LIVE PLANT STAKING	15,100.000	EACH
150	622-91786 SEEDLING	2,062.000	EACH
151	622-91786 SEEDLING	2,062.000	EACH
152	622-91786 SEEDLING	15,289.000	EACH
153	622-98200 SIGN, DO NOT DISTURB	135.000	EACH
154	622-98200 SIGN, DO NOT DISTURB	32.000	EACH
155	628-09403 FIELD OFFICE, C	36.000	MOS
156	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	144.000	MOS
157	628-11729 CELLULAR TELEPHONE TYPE A	6.000	EACH
158	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
159	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
160	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	216.000	MOS
161	701-06011 DYNAMIC PILE LOAD TEST	13.000	EACH
162	701-08122 PILE, STEEL PIPE, 0.375", 14"	8,030.000	LFT
163	701-09557 TEST PILE, DYNAMIC, PRODUCTION	984.000	LFT
164	701-09559 TEST PILE, DYNAMIC, RESTRIKE	13.000	EACH
165	701-09679 CONICAL PILE TIP, 14 IN	146.000	EACH
166	701-09739 PILE SHOE, HP 12 X 53	16.000	EACH
167	701-51195 PILE, STEEL H, HP 12 IN X 53	1,064.000	LFT
168	702-04325 TEMPORARY SHORING	LUMP	LUMP
169	702-51005 CONCRETE, A, SUBSTRUCTURE	816.200	CYS
170	702-51015 CONCRETE, B, FOOTINGS	115.600	CYS
171	702-51110 GRATES, BASINS, AND FITTINGS, CAST IRON	3,864.000	LBS
172	702-92857 CONCRETE, C, SUBSTRUCTURE	213.500	CYS
173	703-06028 REINFORCING BARS	79,162.000	LBS
174	703-06029 REINFORCING BARS, EPOXY COATED	566,549.000	LBS
175	704-51002 CONCRETE, C, SUPERSTRUCTURE	1,294.200	CYS
176	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	730.000	SYS
177	706-09960 RAILING, CONCRETE, FC	660.000	LFT
178	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	10.000	EACH
179	706-11621 CONCRETE BRIDGE RAILING TRANSITION, TFT	8.000	EACH
180	706-51020 RAILING, CONCRETE, C	216.900	CYS
181	707-09183 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 66 IN X 60 IN	465.200	LFT
182	707-09634 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 48 IN X 49 IN	882.000	LFT
183	709-51821 SURFACE SEAL	LUMP	LUMP
184	709-51821 SURFACE SEAL	LUMP	LUMP
185	709-51821 SURFACE SEAL	LUMP	LUMP
186	709-51821 SURFACE SEAL	LUMP	LUMP
187	709-51821 SURFACE SEAL	LUMP	LUMP
188	711-51038 STRUCTURAL STEEL	LUMP	LUMP
189	711-51038 STRUCTURAL STEEL	LUMP	LUMP
190	713-04509 TEMPORARY PIPE	LUMP	LUMP
191	714-11094 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	345.000	LFT
192	714-11174 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	74.000	LFT
193	714-11177 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	82.000	LFT
194	714-11414 STRUCTURE, COATED REINFORCED CONCRETE,	63.000	LFT
195	715-01336 GATE VALVE, 12 IN	14.000	EACH
196	715-01902 WATER SERVICE LINE 2 IN	48.000	LFT

CALL ORDER : 110

CONTRACT ID : IR-30091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
197	715-02388 WATER MAIN	4.000	EACH
198	715-02629 SAFETY METAL END SECTION 6:1 DIA 18"	1.000	EACH
199	715-02630 SAFETY METAL END SECTION 6:1 DIA 24"	1.000	EACH
200	715-03475 SAFETY METAL END SECTION 4:1 DIA 15"	4.000	EACH
201	715-04965 WATER SERVICE LINE	39.000	LFT
202	715-04985 VAULT	1.000	EACH
203	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	246.000	LFT
204	715-05024 PIPE, TYPE 2 CIRCULAR 36 IN	304.000	LFT
205	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	75,473.000	LFT
206	715-05049 PIPE, TYPE 4 CIRCULAR 8 IN	300.000	LFT
207	715-05051 PIPE, TYPE 4 CIRCULAR 10 IN	300.000	LFT
208	715-05052 PIPE, TYPE 4 CIRCULAR 12 IN	300.000	LFT
209	715-05121 PIPE, TYPE 1 CIRCULAR 18 IN	337.000	LFT
210	715-05133 PIPE, TYPE 1 CIRCULAR 60 IN	93.000	LFT
211	715-05136 PIPE, TYPE 1 CIRCULAR 72 IN	178.000	LFT
212	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	2,337.000	LFT
213	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	2,852.000	LFT
214	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	1,137.000	LFT
215	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	964.000	LFT
216	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	79.000	LFT
217	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	200.000	LFT
218	715-05177 PIPE, TYPE 3 CIRCULAR 36 IN	42.000	LFT
219	715-05203 PIPE, TYPE 4 CIRCULAR 4 IN	300.000	LFT
220	715-05407 PIPE, END BENT DRAIN, 6 IN	204.000	LFT
221	715-05408 PIPE SANITARY SEWER 8 IN	363.000	LFT
222	715-05408 PIPE SANITARY SEWER 8 IN	99.000	LFT
223	715-05408 PIPE SANITARY SEWER 8 IN	336.000	LFT
224	715-05408 PIPE SANITARY SEWER 8 IN	277.000	LFT
225	715-05408 PIPE SANITARY SEWER 8 IN	81.000	LFT
226	715-05408 PIPE SANITARY SEWER 8 IN	389.000	LFT
227	715-05408 PIPE SANITARY SEWER 8 IN	116.000	LFT
228	715-05408 PIPE SANITARY SEWER 8 IN	50.000	LFT
229	715-05408 PIPE SANITARY SEWER 8 IN	316.000	LFT
230	715-05408 PIPE SANITARY SEWER 8 IN	404.000	LFT
231	715-05408 PIPE SANITARY SEWER 8 IN	308.000	LFT
232	715-05409 PIPE SANITARY SEWER 10 IN	23.000	LFT
233	715-05409 PIPE SANITARY SEWER 10 IN	13.000	LFT
234	715-05409 PIPE SANITARY SEWER 10 IN	194.000	LFT
235	715-05409 PIPE SANITARY SEWER 10 IN	37.000	LFT
236	715-05409 PIPE SANITARY SEWER 10 IN	624.000	LFT
237	715-05409 PIPE SANITARY SEWER 10 IN	129.000	LFT
238	715-05409 PIPE SANITARY SEWER 10 IN	275.000	LFT
239	715-05409 PIPE SANITARY SEWER 10 IN	30.000	LFT
240	715-05413 PIPE SANITARY SEWER 18 IN	494.000	LFT
241	715-05413 PIPE SANITARY SEWER 18 IN	20.000	LFT
242	715-05413 PIPE SANITARY SEWER 18 IN	74.000	LFT
243	715-05413 PIPE SANITARY SEWER 18 IN	204.000	LFT
244	715-05413 PIPE SANITARY SEWER 18 IN	709.000	LFT
245	715-05413 PIPE SANITARY SEWER 18 IN	267.000	LFT

CALL ORDER : 110

CONTRACT ID : IR-30091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
246	715-05413 PIPE SANITARY SEWER 18 IN	274.000	LFT
247	715-05413 PIPE SANITARY SEWER 18 IN	535.000	LFT
248	715-05417 PIPE SANITARY SEWER 30 IN	72.000	LFT
249	715-05417 PIPE SANITARY SEWER 30 IN	301.000	LFT
250	715-05417 PIPE SANITARY SEWER 30 IN	214.000	LFT
251	715-05596 PIPE EXTENSION, CIRCULAR 18 IN	16.000	LFT
252	715-05597 PIPE EXTENSION, CIRCULAR 24 IN	53.000	LFT
253	715-05756 PIPE EXTENSION, CIRCULAR 12 IN	142.000	LFT
254	715-05841 CONCRETE ANCHOR 60 IN	2.000	EACH
255	715-05842 CONCRETE ANCHOR 42 IN	1.000	EACH
256	715-05890 PIPE EXTENSION, CIRCULAR 42 IN	87.000	LFT
257	715-06173 SAFETY METAL END SECTION 6:1 DIA 60"	2.000	EACH
258	715-06338 PIPE EXTENSION, CIRCULAR, 66"	106.000	LFT
259	715-06357 CONCRETE ANCHOR, 72 IN	2.000	EACH
260	715-06691 CONCRETE ANCHOR, 96 IN	1.000	EACH
261	715-07626 CONCRETE ANCHOR 66 IN	2.000	EACH
262	715-07806 PIPE STEEL CASING	608.000	LFT
263	715-07806 PIPE STEEL CASING	146.000	LFT
264	715-08181 PIPE END SECTION, MIN AREA 4.1 SFT	2.000	EACH
265	715-08282 HMA FOR STRUCTURE INSTALLATION, TYPE A	32.000	TON
266	715-09064 VIDEO INSPECTION FOR PIPE	19,774.000	LFT
267	715-09252 PIPE, SANITARY SEWER, 20 IN	30.000	LFT
268	715-09252 PIPE, SANITARY SEWER, 20 IN	20.000	LFT
269	715-09920 PIPE, TYPE 3 DEFORMED MIN AREA 4.1 SFT	40.000	LFT
270	715-09938 PIPE, BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
271	715-09938 PIPE, BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
272	715-10253 PIPE, TYPE 1, DEFORMED, MIN. AREA 40.1 SFT	164.000	LFT
273	715-11529 PIPE END SECTION, MIN AREA 6.3 SFT	2.000	EACH
274	715-11774 PIPE, TYPE 1 DEFORMED MIN AREA 6.3 SFT	59.000	LFT
275	715-11775 PIPE EXTENSION, CIRCULAR, 96", HDPE	73.000	LFT
276	715-11822 TEST, WATER QUALITY	LUMP	LUMP
277	715-46000 PIPE END SECTION, DIA 12"	7.000	EACH
278	715-46005 PIPE END SECTION, DIA 15"	26.000	EACH
279	715-46010 PIPE END SECTION, DIA 18"	13.000	EACH
280	715-46020 PIPE END SECTION, DIA 24"	4.000	EACH
281	715-46040 PIPE END SECTION, DIA 36 IN	9.000	EACH
282	715-90714 PIPE, PVC, 12 IN	195.000	LFT
283	715-90714 PIPE, PVC, 12 IN	4,942.000	LFT
284	715-91739 WATER SERVICE LINE, 0.75 IN	14.000	LFT
285	715-91742 WATER METER, RELOCATE	2.000	EACH
286	715-92037 PIPE, PVC, 4 IN	20.000	LFT
287	715-92037 PIPE, PVC, 4 IN	102.000	LFT
288	715-92253 SEWER, SANITARY LATERAL, RECONNECT	685.000	EACH
289	715-96670 WATER MAIN, DUCTILE IRON, 12 IN	4,828.000	LFT
290	715-96670 WATER MAIN, DUCTILE IRON, 12 IN	102.000	LFT
291	716-01382 AIR RELEASE VALVE	6.000	EACH
292	716-07630 PIPE INSTALLATION, TRENCHLESS, 12 IN	254.000	LFT
293	716-07630 PIPE INSTALLATION, TRENCHLESS, 12 IN	1,295.000	LFT
294	716-07631 PIPE INSTALLATION, TRENCHLESS, 15 IN	192.000	LFT

CALL ORDER : 110

CONTRACT ID : IR-30091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
295	716-07633 PIPE INSTALLATION, TRENCHLESS, 24 IN	2,733.000	LFT
296	716-07634 PIPE INSTALLATION, TRENCHLESS, 30 IN	170.000	LFT
297	716-09822 PIPE INSTALLATION, TRENCHLESS, 66 IN	192.000	LFT
298	718-06528 OUTLET PROTECTOR, 1	149.000	EACH
299	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	6,500.000	LFT
300	718-52610 AGGREGATE FOR UNDERDRAINS	66.000	CYS
301	718-99153 GEOTEXTILES FOR UNDERDRAIN	665.000	SYS
302	719-05438 PIPE, DRAIN TILE TERMINAL SECTION, 4 IN	100.000	LFT
303	719-05439 PIPE, DRAIN TILE TERMINAL SECTION, 6 IN	100.000	LFT
304	719-05440 PIPE, DRAIN TILE TERMINAL SECTION, 8 IN	110.000	LFT
305	719-05442 PIPE, DRAIN TILE TERMINAL SECTION, 10 IN	100.000	LFT
306	719-05443 PIPE, DRAIN TILE TERMINAL SECTION, 12 IN	100.000	LFT
307	720-01092 MANHOLE, J15, MODIFIED	1.000	EACH
308	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
309	720-45040 INLET, G7	5.000	EACH
310	720-45041 INLET, H5	29.000	EACH
311	720-45075 INLET, R13	2.000	EACH
312	720-45080 INLET, S14	1.000	EACH
313	720-45085 INLET, T14	1.000	EACH
314	720-45270 PIPE CATCH BASIN, 18 IN	3.000	EACH
315	720-45275 PIPE CATCH BASIN, 24 IN	1.000	EACH
316	720-45410 MANHOLE, C4	20.000	EACH
317	720-45415 MANHOLE, D4	2.000	EACH
318	720-45415 MANHOLE, D4	1.000	EACH
319	720-45415 MANHOLE, D4	1.000	EACH
320	720-45510 MANHOLE, C4, MODIFIED	1.000	EACH
321	720-45510 MANHOLE, C4, MODIFIED	3.000	EACH
322	720-45510 MANHOLE, C4, MODIFIED	7.000	EACH
323	720-45510 MANHOLE, C4, MODIFIED	2.000	EACH
324	720-45510 MANHOLE, C4, MODIFIED	4.000	EACH
325	720-45510 MANHOLE, C4, MODIFIED	1.000	EACH
326	720-45510 MANHOLE, C4, MODIFIED	3.000	EACH
327	720-45510 MANHOLE, C4, MODIFIED	7.000	EACH
328	720-45510 MANHOLE, C4, MODIFIED	1.000	EACH
329	720-45510 MANHOLE, C4, MODIFIED	3.000	EACH
330	720-45605 STRUCTURE, MANHOLE, RECONSTRUCTED	6.000	LFT
331	720-95422 MANHOLE, J4	1.000	EACH
332	720-96999 FIRE HYDRANT ASSEMBLY	8.000	EACH
333	720-97009 FIRE HYDRANT ASSEMBLY, REMOVE	2.000	EACH
334	720-98174 INLET, B15	22.000	EACH
335	720-98555 INLET, C15	5.000	EACH
336	720-98625 MANHOLE, C4, DROP	4.000	EACH
337	720-98625 MANHOLE, C4, DROP	3.000	EACH
338	723-11214 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	108.000	LFT
339	723-11313 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	189.000	LFT
340	723-11416 STRUCTURE, COATED REINFORCED CONCRETE,	71.000	LFT
341	723-11541 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	210.000	LFT
342	725-11036 LINER PIPE THERMOPLASTIC CIRCULAR 9.6-9.7 SFT	209.000	LFT
343	731-93945 FACE PANELS, CONCRETE	13,318.000	SFT

CALL ORDER : 110

CONTRACT ID : IR-30091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
344	731-93946 WALL ERECTION	13,318.000	SFT
345	731-93947 LEVELING PAD, CONCRETE	626.000	LFT
346	734-10240 CUT-WALL, NO.	892.000	SFT
347	734-10240 CUT-WALL, NO.	770.000	SFT
348	735-10241 TEMPORARY WIRE FACING	1,800.000	SFT
349	735-10242 TEMPORARY WALL ERECTION	1,800.000	SFT
350	801-03290 CONSTRUCTION SIGN, C	9.000	EACH
351	801-03291 CONSTRUCTION SIGN, D	4.000	EACH
352	801-06539 TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	LUMP	LUMP
353	801-06625 DETOUR ROUTE MARKER ASSEMBLY	10.000	EACH
354	801-06640 CONSTRUCTION SIGN, A	47.000	EACH
355	801-06645 CONSTRUCTION SIGN, B	25.000	EACH
356	801-06710 FLASHING ARROW SIGN	3,600.000	DAY
357	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
358	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	4.000	EACH
359	801-07118 BARRICADE, III-A	1,092.000	LFT
360	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	13,094.000	LFT
361	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	503.000	LFT
362	801-11598 ARIES FIELD PROCESSOR FOR PCMS	4.000	EACH
363	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	4.000	EACH
364	801-52817 TEMPORARY CROSSOVER, B	4.000	EACH
365	802-02475 SIGN, PANEL, RELOCATE	4.000	EACH
366	802-03866 MILE MARKER	18.000	EACH
367	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	801.000	LFT
368	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	614.000	LFT
369	802-07057 SIGN, PANEL, WITH LEGEND	5,545.000	SFT
370	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	122.000	EACH
371	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	38.000	EACH
372	802-07154 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, XII	10.000	EACH
373	802-08456 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VIII	8.000	EACH
374	802-09221 OVERHEAD SIGN STRUCTURE, BOX TRUSS TYPE A	5.000	EACH
375	802-09535 BOX TRUSS SIGN STRUCTURE FOUNDATION, 33 IN.	3.000	EACH
376	802-09537 BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN.	7.000	EACH
377	802-09577 OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE E	1.000	EACH
378	802-09578 OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	4.000	EACH
379	802-09579 CANTILEVER SIGN SUPPORT FOUNDATION,	1.000	EACH
380	802-09581 CANTILEVER SIGN SUPPORT FOUNDATION,	4.000	EACH
381	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	349.533	SFT
382	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	1,232.750	SFT
383	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	78.000	SFT
384	802-74040 SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	23.000	EACH
385	802-76095 STRUCTURAL STEEL, BREAKAWAY	10,933.100	LBS
386	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	3.000	EACH
387	805-01815 SIGNAL POLE FOUNDATION, 36 IN X 144 IN	10.000	EACH
388	805-01842 HANDHOLE, SIGNAL, TYPE 1	25.000	EACH
389	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
390	805-02658 CABLE, COAXIAL	215.000	LFT
391	805-03174 SYSTEM MASTER AND RELATED EQUIPMENT	LUMP	LUMP
392	805-04602 CONTROLLER, REWIRE	3.000	EACH

CALL ORDER : 110

CONTRACT ID : IR-30091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
393	805-06483 CONTROLLER	3.000	EACH
394	805-06595 CONDUIT, PVC, 2 IN	766.000	LFT
395	805-06595 CONDUIT, PVC, 2 IN	2,134.000	LFT
396	805-06595 CONDUIT, PVC, 2 IN	28.000	LFT
397	805-06595 CONDUIT, PVC, 2 IN	2,128.000	LFT
398	805-06600 CONDUIT, PVC, 3 IN.	6.000	LFT
399	805-08487 BACKPLATE, SIGNAL	27.000	EACH
400	805-08493 RADIO, INTERCONNECTION SYSTEM TESTING	LUMP	LUMP
401	805-09089 RADIO, YAGI ANTENNA	3.000	EACH
402	805-78106 CONTROLLER AND CABINET, MASTER, MENU DRIVEN, 8 PHASE	3.000	EACH
403	805-78205 TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN	21.000	EACH
404	805-78230 TRAFFIC SIGNAL HEAD, 5 SECTION, 12"	6.000	EACH
405	805-78415 SPAN, CATENARY, AND TETHER	10.000	EACH
406	805-78420 DISCONNECT HANGER	9.000	EACH
407	805-78445 SIGNAL SERVICE	3.000	EACH
408	805-78467 SIGNAL CABLE, SERVICE, COPPER. 3C/8GA	203.000	LFT
409	805-78470 SIGNAL CABLE, ROADWAY LOOP, COPPER 1C/14GA	7,460.000	LFT
410	805-78485 SIGNAL CABLE, CONTROL, COPPER 5C/14GA	543.000	LFT
411	805-78490 SIGNAL CABLE, CONTROL, COPPER 7C/14GA	3,388.000	LFT
412	805-78510 SIGNAL CABLE, DETECTOR LEAD-IN COPPER 2C/16GA	11,057.000	LFT
413	805-78785 SIGNAL DETECTOR HOUSING	25.000	EACH
414	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	2,457.000	LFT
415	805-78925 CONTROLLER CABINET FOUNDATION, P1	3.000	EACH
416	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	10.000	EACH
417	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	17.000	EACH
418	807-01603 SERVICE POINT, TYPE II	2.000	EACH
419	807-02194 SERVICE POINT, II, MODIFIED	2.000	EACH
420	807-02428 LIGHTING FOUNDATION, CONCRETE, WITH GROUND	46.000	EACH
421	807-03609 LIGHT POLE, HIGH MAST, 80 FT, E.M.H.	2.000	EACH
422	807-03802 LIGHT STANDARDS	1.000	EACH
423	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	2,074.000	LFT
424	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	38,476.000	LFT
425	807-07703 HIGH MAST TOWER	3.000	EACH
426	807-07703 HIGH MAST TOWER	1.000	EACH
427	807-09141 LIGHT POLE, HIGH MAST, 85 FT E.M.H.	1.000	EACH
428	807-11476 LIGHT POLE, ROADWAY, 38 FT. E.M.H., 8 FT. MAST	1.000	EACH
429	807-11489 LIGHT POLE, ROADWAY, 38 FT. E.M.H., 6 FT. MAST	1.000	EACH
430	807-78590 HANDHOLE	2.000	EACH
431	807-82160 LIGHT POLE, HIGH MAST, 95 FT E.M.H.	2.000	EACH
432	807-84762 LIGHT POLE, 40 FT E.M.H., 15.0 FT MAST ARM, TRANSFORMER BASE	1.000	EACH
433	807-84814 LIGHT POLE, 42 FT E.M.H., 15.0 FT MAST ARM, TRANSFORMER BASE	35.000	EACH
434	807-84866 LIGHT POLE, 44 FT E.M.H., 15.0 FT MAST ARM, TRANSFORMER BASE	7.000	EACH
435	807-86620 LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	46.000	EACH
436	807-86665 LUMINAIRE, HIGH MAST, HIGH PRESSURE SODIUM, 1000 WATT	48.000	EACH
437	807-86830 LIGHTING FOUNDATION, CONCRETE, WITH GROUNDING, 48"DIA X 240"	9.000	EACH
438	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	9,224.000	LFT
439	807-86910 CONNECTOR KIT, UNFUSED	55.000	EACH
440	807-86915 CONNECTOR KIT, FUSED	55.000	EACH
441	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	108.000	EACH

CALL ORDER : 110

CONTRACT ID : IR-30091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
442	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.000	EACH
443	807-86930 INSULATION LINK, NON-WATERPROOFED	118.000	EACH
444	807-86955 CABLE-DUCT MARKER	27.000	EACH
445	807-97237 WIRE, NO 4 COPPER, IN PLASTIC DUCT, 4 1/C	2,074.000	LFT
446	808-06716 LINE, REMOVE	61,760.000	LFT
447	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
448	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	1,098.000	EACH
449	809-08372 ROADWAY WEATHER INFORMATION SYSTEM	1.000	EACH
SECTION NO. 0002 NEW ROAD CONSTRUCTION			
450	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
451	203-02055 EMBANKMENT	271,962.000	CYS
452	211-09264 STRUCTURAL BACKFILL, TYPE 1	4,666.000	CYS
453	211-09265 STRUCTURAL BACKFILL, TYPE 2	3,588.000	CYS
454	211-09268 STRUCTURAL BACKFILL, TYPE 5	3,294.000	CYS
455	303-01180 COMPACTED AGGREGATE, NO. 53	27,450.000	TON
456	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	2,226.000	TON
457	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2,669.000	TON
458	401-07335 QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	3,991.000	TON
459	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	10,325.000	TON
460	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	4,544.000	TON
461	401-07404 QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	6,687.000	TON
462	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	17,282.000	TON
463	401-07409 QC/QA-HMA, 4, 64, BASE, 25.0 mm	10,788.000	TON
464	401-07422 QC/QA-HMA, 1, 64, BASE, 19.0 mm	9,622.000	TON
465	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	11,223.000	TON
466	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	25,818.000	TON
467	401-08364 QC/QA-HMA, 4, 64, BASE, 19.0 MM	8,183.000	TON
468	401-10258 JOINT ADHESIVE, SURFACE	157,343.000	LFT
469	401-10259 JOINT ADHESIVE, INTERMEDIATE	157,343.000	LFT
470	401-11785 LIQUID ASPHALT SEALANT	157,343.000	LFT
471	406-05520 ASPHALT FOR TACK COAT	219.000	TON
472	415-11527 BASE SEAL	197.000	TON
473	503-05240 D-1 CONTRACTION JOINT	72.000	LFT
474	605-06140 CURB AND GUTTER, CONCRETE	4,784.000	LFT
475	606-07484 MILLED HMA CORRUGATIONS	90,310.000	LFT
476	615-06505 MONUMENT, B	92.000	EACH
477	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	4,101.000	LFT
478	718-52610 AGGREGATE FOR UNDERDRAINS	7,034.000	CYS
479	718-99153 GEOTEXTILES FOR UNDERDRAIN	75,719.000	SYS
480	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	15.000	EACH
481	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	376,069.000	LFT
482	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	203,299.000	LFT
483	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	12.000	EACH
484	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	341.000	LFT
485	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	742.000	LFT
486	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	10,317.000	LFT
487	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	72,604.000	LFT

CALL ORDER : 110

CONTRACT ID : IR-30091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0002 NEW ROAD CONSTRUCTION			
488	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	11,146.000	LFT
489	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	1,724.000	LFT
490	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	2,584.000	LFT
491	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	104.000	LFT
492	808-11482 LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	376.000	LFT
493	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	62,423.000	LFT
494	808-75260 TRANSVERSE MARKING, THERMOPLASTIC,	39.000	LFT
495	808-75272 TRANSVERSE MARKING, THERMOPLASTIC,	1,627.000	LFT
496	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	420.000	LFT
497	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	11.000	EACH
498	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	1.000	EACH
SECTION NO. 0003 NEW ROAD CONSTRUCTION			
499	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
500	203-02055 EMBANKMENT	263,895.000	CYS
501	211-09264 STRUCTURAL BACKFILL, TYPE 1	4,648.000	CYS
502	211-09265 STRUCTURAL BACKFILL, TYPE 2	3,561.000	CYS
503	211-09268 STRUCTURAL BACKFILL, TYPE 5	3,237.000	CYS
504	302-06464 SUBBASE FOR PCCP	28,970.000	CYS
505	303-01180 COMPACTED AGGREGATE, NO. 53	17,808.000	TON
506	401-07320 QC/QA-HMA, 1, 64, SURFACE, 9.5 mm	1,444.000	TON
507	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	9,582.000	TON
508	401-07406 QC/QA-HMA, 1, 64, BASE, 25.0 mm	17,293.000	TON
509	401-07422 QC/QA-HMA, 1, 64, BASE, 19.0 mm	5,666.000	TON
510	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	11,523.000	TON
511	401-10258 JOINT ADHESIVE, SURFACE	82,160.000	LFT
512	401-10259 JOINT ADHESIVE, INTERMEDIATE	82,160.000	LFT
513	401-11785 LIQUID ASPHALT SEALANT	82,160.000	LFT
514	406-05520 ASPHALT FOR TACK COAT	117.000	TON
515	415-11527 BASE SEAL	91.000	TON
516	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
517	501-06321 QC/QA-PCCP, 10 IN	57,921.000	SYS
518	501-09749 QC/QA PCCP, 9.5"	31,927.000	SYS
519	503-05240 D-1 CONTRACTION JOINT	53,058.000	LFT
520	605-06090 CURB, INTEGRAL, CONCRETE	4,784.000	LFT
521	606-07484 MILLED HMA CORRUGATIONS	65,350.000	LFT
522	606-11064 MILLED PCCP CORRUGATIONS	8,321.000	LFT
523	615-06505 MONUMENT, B	32.000	EACH
524	615-06515 MONUMENT, D	60.000	EACH
525	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	4,101.000	LFT
526	718-52610 AGGREGATE FOR UNDERDRAINS	7,034.000	CYS
527	718-99153 GEOTEXTILES FOR UNDERDRAIN	74,489.000	SYS
528	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	230,346.000	LFT
529	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	349,022.000	LFT
530	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	29.000	EACH
531	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	1,083.000	LFT
532	808-03179 PAVEMENT MESSAGE MARKINGS, PREFORMED PLASTIC, WORD (ONLY)	1.000	EACH
533	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	6,575.000	LFT

CALL ORDER : 110

CONTRACT ID : IR-30091-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003	NEW ROAD CONSTRUCTION		
534	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	48,894.000	LFT
535	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	6,690.000	LFT
536	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	25,412.000	LFT
537	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	22,021.000	LFT
538	808-10037 LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	4,456.000	LFT
539	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	3,742.000	LFT
540	808-11481 LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	91.000	LFT
541	808-11482 LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	285.000	LFT
542	808-75067 TRANSVERSE MARKING, PREFORMED PLASTIC,	354.000	LFT
543	808-75071 PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC,	11.000	EACH
544	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	42,985.000	LFT
545	808-75272 TRANSVERSE MARKING, THERMOPLASTIC,	1,453.000	LFT
546	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	66.000	LFT
547	808-75510 TRANSVERSE MARKINGS, PREFORMED PLASTIC,	174.000	LFT
548	808-91662 TRANSVERSE MARKING, PREFORMED PLASTIC,	39.000	LFT

CALL ORDER : 150

CONTRACT ID : IR-36950-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO 2	1.000	CYCL

CALL ORDER : 160

CONTRACT ID : IR-36951-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, SEEDING		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
7	621-06545 FERTILIZER	200.000	TON
8	621-06553 SEED MIXTURE, R	125,000.000	LBS
9	621-06565 MULCHING MATERIAL	250.000	TON
10	621-11491 LIME, SOIL AMENDMENT	250.000	TON
11	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
12	801-06640 CONSTRUCTION SIGN, A	14.000	EACH
13	801-06710 FLASHING ARROW SIGN	40.000	DAY
14	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 190

CONTRACT ID : R -28896-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	337.000	CYS
13	205-06937 TEMPORARY SILT FENCE	669.000	LFT
14	205-11584 TEMPORARY CHECK DAM, TRAVERSABLE	40.000	LFT
15	207-09935 SUBGRADE TREATMENT, TYPE IC	585.000	SYS
16	211-09265 STRUCTURAL BACKFILL, TYPE 2	325.000	CYS
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	128.000	TON
18	303-01180 COMPACTED AGGREGATE, NO. 53	107.000	TON
19	304-07493 WIDENING WITH HMA, TYPE B	19.000	TON
20	306-08034 MILLING, ASPHALT, 1 1/2 IN	280.000	SYS
21	306-08036 MILLING, ASPHALT, 2 IN	280.000	SYS
22	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	85.000	TON
23	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	71.000	TON
24	401-10258 JOINT ADHESIVE, SURFACE	557.000	LFT
25	401-10259 JOINT ADHESIVE, INTERMEDIATE	452.000	LFT
26	401-11785 LIQUID ASPHALT SEALANT	557.000	LFT
27	402-07451 HMA WEDGE AND LEVEL, TYPE B	34.000	TON
28	406-05520 ASPHALT FOR TACK COAT	0.400	TON
29	615-06490 RIGHT OF WAY MARKER	8.000	EACH
30	616-02320 GEOTEXTILES	192.000	SYS
31	616-06405 RIPRAP, REVETMENT	144.000	TON
32	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
33	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	2,100.000	SYS
34	621-02770 EROSION CONTROL BLANKET	139.000	SYS
35	621-06559 MULCHED SEEDING, R	675.000	SYS
36	621-06567 WATER	0.600	KGAL
37	621-06570 TOPSOIL	79.000	CYS
38	621-06575 SODDING, NURSERY	155.000	SYS
39	621-06626 MULCHED SEEDING, D	220.000	SYS
40	628-09402 FIELD OFFICE, B	4.000	MOS
41	714-11166 STRUCTURE, COATED REINFORCED CONCRETE BOX SECTIONS,	100.000	LFT
42	715-05052 PIPE, TYPE 4 CIRCULAR 12 IN	9.000	LFT
43	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
44	801-06625 DETOUR ROUTE MARKER ASSEMBLY	39.000	EACH
45	801-06640 CONSTRUCTION SIGN, A	31.000	EACH
46	801-06645 CONSTRUCTION SIGN, B	11.000	EACH
47	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
48	801-07118 BARRICADE, III-A	76.000	LFT
49	801-07119 BARRICADE, III-B	80.000	LFT

CALL ORDER : 190

CONTRACT ID : R -28896-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50 808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	550.000	LFT
51 808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	69.000	LFT

CALL ORDER : 210

CONTRACT ID : R -29352-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09542 UTILITY RELOCATION ENGINEERING	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-08463 PROJECT ESTIMATE ADJUSTMENT	0.500	DOL
9	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
10	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
11	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
12	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
15	203-02000 EXCAVATION, COMMON	20,355.000	CYS
16	203-02070 BORROW	25,575.000	CYS
17	203-51223 EXCAVATION, WATERWAY	1,190.000	CYS
18	205-03371 SEDIMENT, REMOVE	100.000	CYS
19	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	276.000	TON
20	205-06933 TEMPORARY INLET PROTECTION	4.000	EACH
21	205-06934 TEMPORARY MULCH	58.000	TON
22	205-06936 TEMPORARY SEDIMENT TRAP	228.000	TON
23	205-06937 TEMPORARY SILT FENCE	7,341.000	LFT
24	205-09543 NO 2 STONE	100.000	TON
25	205-11585 TEMPORARY FILTER BERM	254.000	LFT
26	206-51220 EXCAVATION, WET	225.000	CYS
27	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	65.000	CYS
28	207-08263 SUBGRADE TREATMENT, TYPE IA	33,174.000	SYS
29	207-08267 SUBGRADE TREATMENT, TYPE IIIA	2,352.000	SYS
30	211-02050 B BORROW	5,000.000	CYS
31	211-06467 AGGREGATE FOR END BENT BACKFILL	28.000	CYS
32	211-09264 STRUCTURAL BACKFILL, TYPE 1	1,090.000	CYS
33	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,846.000	TON
34	302-07455 DENSE GRADED SUBBASE	39.000	CYS
35	303-01180 COMPACTED AGGREGATE, NO. 53	6,814.000	TON
36	303-07449 COMPACTED AGGREGATE, NO. 73	1,445.000	TON
37	304-07489 HMA PATCHING, TYPE A	32.000	TON
38	306-08043 MILLING, TRANSITION	1,325.000	SYS
39	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	460.000	TON
40	401-07327 QC/QA-HMA, 2, 70, SURFACE, 9.5 mm	1,544.000	TON
41	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	744.000	TON
42	401-07397 QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	2,493.000	TON
43	401-07423 QC/QA-HMA, 2, 64, BASE, 19.0 mm	3,315.000	TON
44	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	2,581.000	TON
45	401-10258 JOINT ADHESIVE, SURFACE	9,303.000	LFT
46	401-10259 JOINT ADHESIVE, INTERMEDIATE	9,303.000	LFT
47	401-11785 LIQUID ASPHALT SEALANT	9,303.000	LFT
48	402-07450 HMA WEDGE AND LEVEL, TYPE A	34.000	TON
49	406-05520 ASPHALT FOR TACK COAT	16.000	TON

CALL ORDER : 210

CONTRACT ID : R -29352-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
51	601-01626 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 2	2.000	EACH
52	601-01740 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 4	2.000	EACH
53	601-01839 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 6	4.000	EACH
54	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	2.000	EACH
55	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
56	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	5,798.000	LFT
57	602-06729 BARRIER DELINEATOR	16.000	EACH
58	603-06040 FENCE, FARM FIELD, 47 IN	2,550.000	LFT
59	603-97603 FENCE, CHAIN LINK, 60 IN	650.000	LFT
60	605-06145 CURB AND GUTTER, B, CONCRETE	114.000	LFT
61	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	225.000	SYS
62	610-07487 HMA FOR APPROACHES, TYPE B	962.000	TON
63	611-06497 MAILBOX ASSEMBLY, SINGLE	5.000	EACH
64	615-06505 MONUMENT, B	24.000	EACH
65	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
66	616-02320 GEOTEXTILES	24,746.000	SYS
67	616-05688 RIPRAP, CLASS 1	1,185.000	TON
68	616-06405 RIPRAP, REVETMENT	13,261.000	TON
69	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.000	EACH
70	621-04258 SEED MIXTURE	40.000	LBS
71	621-06545 FERTILIZER	4.000	TON
72	621-06553 SEED MIXTURE, R	1,276.000	LBS
73	621-06557 SEED MIXTURE, T	1,803.000	LBS
74	621-06565 MULCHING MATERIAL	16.000	TON
75	621-06567 WATER	24.000	KGAL
76	621-06574 SODDING	1,268.000	SYS
77	621-06575 SODDING, NURSERY	5,243.000	SYS
78	621-92968 SEED MIXTURE, WILD FLOWER	50.000	LBS
79	622-05639 PLANT, DECIDUOUS SHRUB, 18 TO 24 IN	520.000	EACH
80	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	2,055.000	EACH
81	622-52436 SIGN, DO NOT MOW OR SPRAY	22.000	EACH
82	622-98200 SIGN, DO NOT DISTURB	22.000	EACH
83	628-09402 FIELD OFFICE, B	24.000	MOS
84	701-06011 DYNAMIC PILE LOAD TEST	3.000	EACH
85	701-09557 TEST PILE, DYNAMIC, PRODUCTION	197.000	LFT
86	701-09559 TEST PILE, DYNAMIC, RESTRIKE	3.000	EACH
87	701-09739 PILE SHOE, HP 12 X 53	46.000	EACH
88	701-51195 PILE, STEEL H, HP 12 IN X 53	2,588.000	LFT
89	702-51005 CONCRETE, A, SUBSTRUCTURE	212.300	CYS
90	703-06028 REINFORCING BARS	33,451.000	LBS
91	703-06029 REINFORCING BARS, EPOXY COATED	126,059.000	LBS
92	704-51002 CONCRETE, C, SUPERSTRUCTURE	371.100	CYS
93	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH
94	706-51020 RAILING, CONCRETE, C	54.000	CYS
95	707-11428 STRUCTURAL MEMBER, CONCRETE BOX BEAM, 33 IN X 48 IN	1,558.000	LFT
96	709-51821 SURFACE SEAL	LUMP	LUMP
97	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	78.000	LFT
98	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	12,091.000	LFT

CALL ORDER : 210

CONTRACT ID : R -29352-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
99	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	532.000	LFT
100	715-05118 PIPE, TYPE 1 CIRCULAR 12 IN	300.000	LFT
101	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	100.000	LFT
102	715-05125 PIPE, TYPE 1 CIRCULAR 30 IN	93.000	LFT
103	715-05128 PIPE, TYPE 1 CIRCULAR 48 IN	99.000	LFT
104	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	110.000	LFT
105	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	661.000	LFT
106	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	210.000	LFT
107	715-05234 PIPE, TYPE 1 DEFORMED MIN AREA 4.1 SFT	53.000	LFT
108	715-05237 PIPE, TYPE 1 DEFORMED MIN AREA 6.4 SFT	54.000	LFT
109	715-05407 PIPE, END BENT DRAIN, 6 IN	118.000	LFT
110	715-06004 CONCRETE ANCHOR, 48 IN	2.000	EACH
111	715-08181 PIPE END SECTION, MIN AREA 4.1 SFT	2.000	EACH
112	715-46005 PIPE END SECTION, DIA 15"	10.000	EACH
113	715-46030 PIPE END SECTION, DIA 30"	2.000	EACH
114	715-46040 PIPE END SECTION, DIA 36 IN	2.000	EACH
115	715-46095 PIPE END SECTION, MIN AREA 6.4 SFT	2.000	EACH
116	718-06531 OUTLET PROTECTOR, 3	22.000	EACH
117	718-52610 AGGREGATE FOR UNDERDRAINS	1,089.000	CYS
118	718-99153 GEOTEXTILES FOR UNDERDRAIN	8,290.000	SYS
119	719-05443 PIPE, DRAIN TILE TERMINAL SECTION, 12 IN	30.000	LFT
120	719-09447 PIPE, DRAIN TILE TERMINAL SECTION, 24 IN	10.000	LFT
121	720-08617 INLET, INTAKE RISER	3.000	EACH
122	720-45030 INLET, E7	4.000	EACH
123	720-45035 INLET, F7	1.000	EACH
124	720-45065 INLET, N12	2.000	EACH
125	720-45075 INLET, R13	1.000	EACH
126	720-45410 MANHOLE, C4	5.000	EACH
127	801-06624 STANDARD BARRICADE, IIIB, WITH SIGNS	8.000	EACH
128	801-06625 DETOUR ROUTE MARKER ASSEMBLY	79.000	EACH
129	801-06640 CONSTRUCTION SIGN, A	21.000	EACH
130	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	200.000	LFT
131	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	60.000	LFT
132	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	87.000	SFT
133	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	32.000	SFT
134	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	32.000	SFT
135	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	12,373.000	LFT
136	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	3,777.000	LFT
137	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
138	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	738.000	LFT
139	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	738.000	LFT
140	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,165.000	LFT
141	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	10,750.000	LFT
142	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	131.000	LFT

CALL ORDER : 230

CONTRACT ID : R -32594-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 CONCRETE PAVEMENT RESTORATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	302-06464 SUBBASE FOR PCCP	2,000.000	CYS
10	305-09888 RELIEF JOINT	432.000	LFT
11	401-11507 QC/QA-HMA, 5, 64, INTERMEDIATE, OG, 9.5 mm	187.000	TON
12	503-05240 D-1 CONTRACTION JOINT	226.000	LFT
13	506-06333 PCCP PATCHING, FULL DEPTH	9,708.000	SYS
14	506-06333 PCCP PATCHING, FULL DEPTH	3,230.000	SYS
15	506-06333 PCCP PATCHING, FULL DEPTH	170.000	SYS
16	506-06334 PCCP PATCHING, PARTIAL DEPTH	225.000	SYS
17	507-07482 CRACKS IN PCCP, ROUT AND SEAL	5,000.000	LFT
18	507-07505 RETROFIT LOAD TRANSFER	50.000	EACH
19	628-09403 FIELD OFFICE, C	19.000	MOS
20	628-09409 MOBILE INTERNET SERVICE	40.000	MOS
21	628-11729 CELLULAR TELEPHONE TYPE A	3.000	EACH
22	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
23	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
24	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	50.000	MOS
25	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	200.000	LFT
26	718-03277 PIPE, UNDERDRAIN, CORRUGATED PLASTIC, PERFORATED, 6 IN.	2,517.000	LFT
27	718-06526 HMA FOR UNDERDRAINS	277.000	TON
28	718-06529 OUTLET PROTECTOR, 2	8.000	EACH
29	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	2,517.000	LFT
30	718-52610 AGGREGATE FOR UNDERDRAINS	393.000	CYS
31	718-99153 GEOTEXTILES FOR UNDERDRAIN	700.000	SYS
32	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.000	EACH
33	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
34	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
35	801-06710 FLASHING ARROW SIGN	360.000	DAY
36	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
37	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	6.000	EACH
38	801-92448 CONSTRUCTION SIGNS, MOBILE	360.000	DAY
39	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	1,790.000	LFT
40	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	1,429.000	LFT
41	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	6,483.000	LFT
42	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	100.000	EACH
43	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	100.000	EACH

CALL ORDER : 240

CONTRACT ID : R -33076-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	200.000	SYS
12	203-02000 EXCAVATION, COMMON	11,549.000	CYS
13	205-06933 TEMPORARY INLET PROTECTION	1.000	EACH
14	205-06936 TEMPORARY SEDIMENT TRAP	32.000	TON
15	205-06937 TEMPORARY SILT FENCE	1,082.000	LFT
16	205-09543 NO 2 STONE	100.000	TON
17	205-11584 TEMPORARY CHECK DAM, TRAVERSABLE	590.000	LFT
18	205-11585 TEMPORARY FILTER BERM	17.000	LFT
19	207-08263 SUBGRADE TREATMENT, TYPE IA	13,756.000	SYS
20	207-08267 SUBGRADE TREATMENT, TYPE IIIA	1,576.000	SYS
21	207-09935 SUBGRADE TREATMENT, TYPE IC	547.000	SYS
22	211-09264 STRUCTURAL BACKFILL, TYPE 1	179.000	CYS
23	211-09265 STRUCTURAL BACKFILL, TYPE 2	17.000	CYS
24	215-07043 CHEMICAL MODIFICATION, SOILS	2,751.000	SYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	2,489.000	TON
26	303-01180 COMPACTED AGGREGATE, NO. 53	1,003.000	TON
27	303-07449 COMPACTED AGGREGATE, NO. 73	100.000	TON
28	304-07494 WIDENING WITH HMA, TYPE C	38.000	TON
29	306-10163 MILLING ASPHALT, 2 1/2 IN	5,271.000	SYS
30	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
31	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	135.000	TON
32	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1,568.000	TON
33	401-07371 QC/QA-HMA, 2, 64, INTERMEDIATE, 12.5 mm	39.000	TON
34	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	248.000	TON
35	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	2,591.000	TON
36	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	86.000	TON
37	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	2,518.000	TON
38	401-10258 JOINT ADHESIVE, SURFACE	9,760.000	LFT
39	401-10259 JOINT ADHESIVE, INTERMEDIATE	9,760.000	LFT
40	401-11785 LIQUID ASPHALT SEALANT	9,760.000	LFT
41	402-10086 HMA FOR TEMPORARY PAVEMENT, C	96.000	TON
42	406-05520 ASPHALT FOR TACK COAT	11.000	TON
43	605-06145 CURB AND GUTTER, B, CONCRETE	90.000	LFT
44	611-06497 MAILBOX ASSEMBLY, SINGLE	8.000	EACH
45	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
46	611-08233 MAILBOX ASSEMBLY, DOUBLE, RESET	1.000	EACH
47	615-06490 RIGHT OF WAY MARKER	39.000	EACH
48	615-06505 MONUMENT, B	7.000	EACH
49	615-06527 MONUMENT, SECTION CORNER	1.000	EACH

CALL ORDER : 240

CONTRACT ID : R -33076-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
50	616-02320 GEOTEXTILES	686.000	SYS
51	616-06451 RIPRAP, UNIFORM	268.000	TON
52	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.000	EACH
53	621-06545 FERTILIZER	0.300	TON
54	621-06554 SEED MIXTURE, U	122.000	LBS
55	621-06557 SEED MIXTURE, T	244.000	LBS
56	621-06565 MULCHING MATERIAL	5.000	TON
57	621-06567 WATER	22.000	KGAL
58	621-06574 SODDING	1,552.000	SYS
59	621-06575 SODDING, NURSERY	4,631.000	SYS
60	628-09402 FIELD OFFICE, B	12.000	MOS
61	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
62	628-11730 CELLULAR TELEPHONE TYPE B	3.000	EACH
63	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
64	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
65	628-11780 CELLULAR TELEPHONE SERVICE 500 MIN	36.000	MOS
66	715-02397 SAFETY METAL END SECTION 4:1 DIA 36"	2.000	EACH
67	715-03475 SAFETY METAL END SECTION 4:1 DIA 15"	10.000	EACH
68	715-05019 PIPE, TYPE 1 CIRCULAR 36 IN	120.000	LFT
69	715-05119 PIPE, TYPE 1 CIRCULAR 15 IN	38.000	LFT
70	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	39.000	LFT
71	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	397.000	LFT
72	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	16.000	LFT
73	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	5.000	TON
74	715-46000 PIPE END SECTION, DIA 12"	1.000	EACH
75	715-46005 PIPE END SECTION, DIA 15"	8.000	EACH
76	715-46010 PIPE END SECTION, DIA 18"	2.000	EACH
77	720-02442 PIPE, PLUG EXISTING	1.000	EACH
78	720-45270 PIPE CATCH BASIN, 18 IN	1.000	EACH
79	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	1.000	EACH
80	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
81	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
82	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	6,000.000	LFT
83	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	14,600.000	LFT
84	801-06625 DETOUR ROUTE MARKER ASSEMBLY	21.000	EACH
85	801-06640 CONSTRUCTION SIGN, A	19.000	EACH
86	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
87	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
88	801-07119 BARRICADE, III-B	136.000	LFT
89	801-07612 TEMPORARY PAVEMENT MARKING, 24 IN	32.000	LFT
90	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	115.000	LFT
91	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	47.000	SFT
92	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	16.000	SFT
93	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	22.000	SFT
94	805-01815 SIGNAL POLE FOUNDATION, 36 IN X 144 IN	4.000	EACH
95	805-01842 HANDHOLE, SIGNAL, TYPE 1	13.000	EACH
96	805-09471 SIGNAL CABLE, PREFORMED PAVE-OVER LOOP	10.000	EACH
97	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
98	805-78205 TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN	8.000	EACH

CALL ORDER : 240

CONTRACT ID : R -33076-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT		
99	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
100	805-78420 DISCONNECT HANGER	4.000	EACH
101	805-78445 SIGNAL SERVICE	1.000	EACH
102	805-78467 SIGNAL CABLE, SERVICE, COPPER. 3C/8GA	67.000	LFT
103	805-78470 SIGNAL CABLE, ROADWAY LOOP, COPPER 1C/14GA	2,033.000	LFT
104	805-78485 SIGNAL CABLE, CONTROL, COPPER 5C/14GA	298.000	LFT
105	805-78490 SIGNAL CABLE, CONTROL, COPPER 7C/14GA	711.000	LFT
106	805-78510 SIGNAL CABLE, DETECTOR LEAD-IN COPPER 2C/16GA	3,870.000	LFT
107	805-78785 SIGNAL DETECTOR HOUSING	6.000	EACH
108	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	742.000	LFT
109	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
110	805-81032 SIGNAL STRAIN POLE, STEEL, 30 FT	4.000	EACH
111	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	1,866.000	LFT
112	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	9,294.000	LFT
113	808-06716 LINE, REMOVE	4,850.000	LFT
114	808-11482 LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	105.000	LFT
115	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	10,024.000	LFT
116	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	155.000	LFT
117	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	150.000	LFT
118	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	7.000	EACH
119	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	7.000	EACH
120	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	88.000	EACH
121	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	902.000	LFT

CALL ORDER : 250

CONTRACT ID : R -33253-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT WITH ADDED TURN LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	687.000	CYS
12	203-02070 BORROW	1,008.000	CYS
13	205-03371 SEDIMENT, REMOVE	25.000	CYS
14	205-06933 TEMPORARY INLET PROTECTION	5.000	EACH
15	205-06937 TEMPORARY SILT FENCE	1,065.000	LFT
16	207-08262 SUBGRADE TREATMENT, TYPE I	5,317.000	SYS
17	207-08267 SUBGRADE TREATMENT, TYPE IIIA	461.000	SYS
18	211-02050 B BORROW	500.000	CYS
19	211-09264 STRUCTURAL BACKFILL, TYPE 1	200.000	CYS
20	211-09264 STRUCTURAL BACKFILL, TYPE 1	59.000	CYS
21	211-09264 STRUCTURAL BACKFILL, TYPE 1	72.000	CYS
22	214-11796 GEOGRID, TYPE IB	150.000	SYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	825.000	TON
24	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	154.000	TON
25	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	352.000	TON
26	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	586.000	TON
27	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	938.000	TON
28	401-10258 JOINT ADHESIVE, SURFACE	2,018.000	LFT
29	401-10259 JOINT ADHESIVE, INTERMEDIATE	2,018.000	LFT
30	406-05520 ASPHALT FOR TACK COAT	2.000	TON
31	604-06070 SIDEWALK, CONCRETE	270.000	SYS
32	604-07900 CURB RAMP, CONCRETE, F	54.000	SYS
33	604-07902 CURB RAMP, CONCRETE, H	19.000	SYS
34	605-06140 CURB AND GUTTER, CONCRETE	1,654.000	LFT
35	605-09131 CURB AND GUTTER TURNOUT CONCRETE	26.000	LFT
36	610-08446 PCCP FOR APPROACHES, 6 IN	412.000	SYS
37	610-09108 PCCP FOR APPROACHES, 9 IN	50.000	SYS
38	611-06497 MAILBOX ASSEMBLY, SINGLE	4.000	EACH
39	615-06505 MONUMENT, B	6.000	EACH
40	616-02320 GEOTEXTILES	30.000	SYS
41	616-06405 RIPRAP, REVETMENT	10.000	TON
42	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.000	EACH
43	621-06545 FERTILIZER	2.000	TON
44	621-06557 SEED MIXTURE, T	89.000	LBS
45	621-06560 MULCHED SEEDING, U	1,400.000	SYS
46	621-06565 MULCHING MATERIAL	2.000	TON
47	621-06567 WATER	4.000	KGAL
48	621-06575 SODDING, NURSERY	1,689.000	SYS
49	628-09401 FIELD OFFICE, A	5.000	MOS

CALL ORDER : 250

CONTRACT ID : R -33253-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT WITH ADDED TURN LANES		
50	715-05115 PIPE, TYPE 1 CIRCULAR 6 IN	50.000	LFT
51	715-05116 PIPE, TYPE 1 CIRCULAR 8 IN	50.000	LFT
52	715-05118 PIPE, TYPE 1 CIRCULAR 12 IN	50.000	LFT
53	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	59.000	LFT
54	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	631.000	LFT
55	715-06813 PIPE, SANITARY SEWER, 2 IN	150.000	LFT
56	715-09064 VIDEO INSPECTION FOR PIPE	451.000	LFT
57	715-46005 PIPE END SECTION, DIA 15"	5.000	EACH
58	715-92543 WATER MAIN, 8 IN, RELOCATE	150.000	LFT
59	720-44000 CASTING, ADJUST TO GRADE	1.000	EACH
60	720-45130 INLET, E7, MODIFIED	1.000	EACH
61	720-45135 INLET, F7, MODIFIED	2.000	EACH
62	720-45265 PIPE CATCH BASIN, 15 IN	1.000	EACH
63	720-45270 PIPE CATCH BASIN, 18 IN	1.000	EACH
64	720-45410 MANHOLE, C4	1.000	EACH
65	720-93409 INLET, B15, MODIFIED	4.000	EACH
66	720-93411 INLET, C15, MODIFIED	7.000	EACH
67	720-97008 FIRE HYDRANT ASSEMBLY, RELOCATE	1.000	EACH
68	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
69	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
70	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	3,840.000	LFT
71	801-06577 TEMPORARY PAVEMENT MARKING, REMOVABLE, 24"	400.000	LFT
72	801-06625 DETOUR ROUTE MARKER ASSEMBLY	22.000	EACH
73	801-06640 CONSTRUCTION SIGN, A	21.000	EACH
74	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
75	801-07119 BARRICADE, III-B	72.000	LFT
76	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	173.500	LFT
77	802-07151 WIDE FLANGE SIGN POST SUPPORT FOUNDATION, VII	2.000	EACH
78	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	58.500	SFT
79	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	6.500	SFT
80	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	34.000	SFT
81	802-76095 STRUCTURAL STEEL, BREAKAWAY	278.000	LBS
82	805-01815 SIGNAL POLE FOUNDATION, 36 IN X 144 IN	4.000	EACH
83	805-01842 HANDHOLE, SIGNAL, TYPE 1	4.000	EACH
84	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN	412.000	LFT
85	805-07190 TRAFFIC SIGNAL HEAD, 1 SECTION, 12 IN	1.000	EACH
86	805-78010 CONTROLLER AND CABINET, FLASHER, SOLID STATE	1.000	EACH
87	805-78445 SIGNAL SERVICE	1.000	EACH
88	805-78467 SIGNAL CABLE, SERVICE, COPPER. 3C/8GA	16.000	LFT
89	805-78480 SIGNAL CABLE, CONTROL, COPPER 3C/14GA	22.000	LFT
90	805-78785 SIGNAL DETECTOR HOUSING	1.000	EACH
91	805-94069 CONDUIT, STEEL, GALVANIZED, 1 IN	16.000	LFT
92	808-03114 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (XING) 8 FT	1.000	EACH
93	808-03775 PAVEMENT MESSAGE MARKING, THERMOPLASTIC, (BIKE)	1.000	EACH
94	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	274.000	LFT
95	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	38.000	LFT
96	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,918.000	LFT
97	808-75256 TRANSVERSE MARKING, THERMOPLASTIC,	267.000	LFT
98	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	100.000	LFT

CALL ORDER : 250

CONTRACT ID : R -33253-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT WITH ADDED TURN LANES		
99 808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	3.000	EACH
100 808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	3.000	EACH

CALL ORDER : 260

CONTRACT ID : R -33385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	11,505.000	CYS
13	203-02070 BORROW	5,270.000	CYS
14	205-03371 SEDIMENT, REMOVE	500.000	CYS
15	205-06930 SPLASHPAD	2.000	TON
16	205-06933 TEMPORARY INLET PROTECTION	66.000	EACH
17	205-06934 TEMPORARY MULCH	5.000	TON
18	205-06936 TEMPORARY SEDIMENT TRAP	215.000	TON
19	205-06937 TEMPORARY SILT FENCE	1,035.000	LFT
20	205-06938 TEMPORARY SLOPE DRAIN	71.000	LFT
21	205-09543 NO 2 STONE	100.000	TON
22	205-11584 TEMPORARY CHECK DAM, TRAVERSABLE	12.000	LFT
23	205-11585 TEMPORARY FILTER BERM	215.000	LFT
24	205-11591 TEMPORARY SEED MIXTURE	285.000	LBS
25	207-08265 SUBGRADE TREATMENT, TYPE IIA	34,332.000	SYS
26	207-08267 SUBGRADE TREATMENT, TYPE IIIA	3,188.000	SYS
27	211-02050 B BORROW	2,500.000	CYS
28	211-09264 STRUCTURAL BACKFILL, TYPE 1	11,714.000	CYS
29	211-09265 STRUCTURAL BACKFILL, TYPE 2	193.000	CYS
30	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	356.000	TON
31	303-01180 COMPACTED AGGREGATE, NO. 53	1,491.000	TON
32	303-07449 COMPACTED AGGREGATE, NO. 73	370.000	TON
33	304-07493 WIDENING WITH HMA, TYPE B	129.000	TON
34	306-08039 MILLING, ASPHALT REMOVAL	3,104.000	SYS
35	306-08043 MILLING, TRANSITION	111.000	SYS
36	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
37	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2,164.000	TON
38	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	3,528.000	TON
39	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	3,816.000	TON
40	401-10258 JOINT ADHESIVE, SURFACE	8,442.000	LFT
41	401-10259 JOINT ADHESIVE, INTERMEDIATE	8,442.000	LFT
42	401-11785 LIQUID ASPHALT SEALANT	8,442.000	LFT
43	406-05520 ASPHALT FOR TACK COAT	21.000	TON
44	604-06070 SIDEWALK, CONCRETE	1,095.000	SYS
45	604-07901 CURB RAMP, CONCRETE, G	27.000	SYS
46	605-52807 CURB AND GUTTER, COMBINED	5,323.000	LFT
47	610-07487 HMA FOR APPROACHES, TYPE B	975.000	TON
48	610-08446 PCCP FOR APPROACHES, 6 IN	661.000	SYS
49	610-09108 PCCP FOR APPROACHES, 9 IN	942.000	SYS

CALL ORDER : 260

CONTRACT ID : R -33385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD RECONSTRUCTION		
50	611-06497 MAILBOX ASSEMBLY, SINGLE	35.000	EACH
51	611-06498 MAILBOX ASSEMBLY, DOUBLE	2.000	EACH
52	615-06490 RIGHT OF WAY MARKER	74.000	EACH
53	615-06505 MONUMENT, B	29.000	EACH
54	615-06510 MONUMENT, C	1.000	EACH
55	616-02320 GEOTEXTILES	385.000	SYS
56	616-06405 RIPRAP, REVETMENT	2.000	TON
57	616-06451 RIPRAP, UNIFORM	78.000	TON
58	616-07210 FIBER ROLL	1,281.000	LFT
59	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
60	621-02770 EROSION CONTROL BLANKET	1,984.000	SYS
61	621-04258 SEED MIXTURE	1.000	LBS
62	621-06545 FERTILIZER	2.000	TON
63	621-06554 SEED MIXTURE, U	570.000	LBS
64	621-06565 MULCHING MATERIAL	8.000	TON
65	621-06567 WATER	37.000	KGAL
66	621-06570 TOPSOIL	167.000	CYS
67	621-06574 SODDING	2,177.000	SYS
68	621-06575 SODDING, NURSERY	7,083.000	SYS
69	621-07642 SOIL PREPARATION	15.000	CYS
70	621-08161 PERMANENT TURF REINFORCEMENT MAT	15.000	SYS
71	621-09398 SEED MIXTURE, SLOPE STABILIZATION	5.000	LBS
72	621-90853 TAPPING SLEEVE WITH VALVE	2.000	EACH
73	621-90853 TAPPING SLEEVE WITH VALVE	13.000	EACH
74	628-09402 FIELD OFFICE, B	12.000	MOS
75	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
76	628-11729 CELLULAR TELEPHONE TYPE A	2.000	EACH
77	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
78	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
79	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	24.000	MOS
80	715-02388 WATER MAIN	1.000	EACH
81	715-02388 WATER MAIN	18.000	EACH
82	715-03475 SAFETY METAL END SECTION 4:1 DIA 15"	2.000	EACH
83	715-04596 WATER SERVICE	3.000	EACH
84	715-04964 WATER MAIN	2,987.000	LFT
85	715-04965 WATER SERVICE LINE	849.000	LFT
86	715-04995 LINE STOP	10.000	EACH
87	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	13,665.000	LFT
88	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	259.000	LFT
89	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	1,843.000	LFT
90	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	363.000	LFT
91	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	1,221.000	LFT
92	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	750.000	LFT
93	715-05156 PIPE, TYPE 2 CIRCULAR 30 IN	2,673.000	LFT
94	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	106.000	LFT
95	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	43.000	TON
96	715-09064 VIDEO INSPECTION FOR PIPE	6,850.000	LFT
97	715-09475 STORMWATER QUALITY STRUCTURE	1.000	EACH
98	715-46005 PIPE END SECTION, DIA 15"	4.000	EACH

CALL ORDER : 260

CONTRACT ID : R -33385-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD RECONSTRUCTION			
99	715-46010 PIPE END SECTION, DIA 18"	1.000	EACH
100	715-46040 PIPE END SECTION, DIA 36 IN	1.000	EACH
101	715-91742 WATER METER, RELOCATE	33.000	EACH
102	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
103	718-52610 AGGREGATE FOR UNDERDRAINS	1,227.000	CYS
104	720-01092 MANHOLE, J15, MODIFIED	20.000	EACH
105	720-07301 INLET, TYPE HA	1.000	EACH
106	720-08242 MANHOLE, L15, MODIFIED	1.000	EACH
107	720-44000 CASTING, ADJUST TO GRADE	3.000	EACH
108	720-44000 CASTING, ADJUST TO GRADE	12.000	EACH
109	720-45270 PIPE CATCH BASIN, 18 IN	18.000	EACH
110	720-45410 MANHOLE, C4	9.000	EACH
111	720-45415 MANHOLE, D4	1.000	EACH
112	720-90984 MANHOLE, C2	2.000	EACH
113	720-91742 FIRE HYDRANT	4.000	EACH
114	720-95422 MANHOLE, J4	7.000	EACH
115	720-96999 FIRE HYDRANT ASSEMBLY	4.000	EACH
116	720-97008 FIRE HYDRANT ASSEMBLY, RELOCATE	6.000	EACH
117	720-98174 INLET, B15	20.000	EACH
118	720-98555 INLET, C15	4.000	EACH
119	801-03290 CONSTRUCTION SIGN, C	7.000	EACH
120	801-04308 ROAD CLOSURE SIGN ASSEMBLY	16.000	EACH
121	801-06625 DETOUR ROUTE MARKER ASSEMBLY	18.000	EACH
122	801-06640 CONSTRUCTION SIGN, A	25.000	EACH
123	801-06645 CONSTRUCTION SIGN, B	6.000	EACH
124	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
125	801-07118 BARRICADE, III-A	48.000	LFT
126	801-07119 BARRICADE, III-B	372.000	LFT
127	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	2,500.000	LFT
128	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	221.000	LFT
129	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	78.000	SFT
130	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	68.000	SFT
131	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	9,284.000	LFT
132	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
133	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	15,540.000	LFT
134	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	187.000	LFT
135	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	65.000	LFT
136	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH
137	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
138	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	100.000	EACH

CALL ORDER : 270

CONTRACT ID : R -34078-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 SMALL STRUCTURE REPLACEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
7	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	1,822.000	CYS
11	203-02070 BORROW	297.000	CYS
12	205-03371 SEDIMENT, REMOVE	10.000	CYS
13	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	13.000	TON
14	205-06934 TEMPORARY MULCH	3.200	TON
15	205-06937 TEMPORARY SILT FENCE	2,256.000	LFT
16	205-09543 NO 2 STONE	100.000	TON
17	205-11584 TEMPORARY CHECK DAM, TRAVERSABLE	10.000	LFT
18	207-08265 SUBGRADE TREATMENT, TYPE IIA	134.000	SYS
19	211-02050 B BORROW	187.000	CYS
20	211-09265 STRUCTURAL BACKFILL, TYPE 2	99.500	CYS
21	211-09268 STRUCTURAL BACKFILL, TYPE 5	489.000	CYS
22	303-01180 COMPACTED AGGREGATE, NO. 53	474.000	TON
23	303-07449 COMPACTED AGGREGATE, NO. 73	292.000	TON
24	406-05521 ASPHALT FOR TACK COAT	218.000	SYS
25	601-06854 GUARDRAIL, W-BEAM, NESTED	2.000	EACH
26	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
27	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	1,457.000	LFT
28	615-06490 RIGHT OF WAY MARKER	17.000	EACH
29	616-02320 GEOTEXTILES	452.000	SYS
30	616-05689 RIPRAP, CLASS 2	253.000	TON
31	616-06405 RIPRAP, REVETMENT	117.000	TON
32	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
33	621-02318 SEED MIXTURE, PRAIRIE GRASS	16.000	LBS
34	621-02770 EROSION CONTROL BLANKET	2,619.000	SYS
35	621-06545 FERTILIZER	0.400	TON
36	621-06553 SEED MIXTURE, R	119.000	LBS
37	621-06557 SEED MIXTURE, T	341.000	LBS
38	621-06559 MULCHED SEEDING, R	1,705.000	SYS
39	621-06565 MULCHING MATERIAL	2.600	TON
40	621-06567 WATER	22.000	KGAL
41	621-06574 SODDING	89.000	SYS
42	621-07657 FIBER MAT, COCONUT	2,774.000	SYS
43	621-09399 SEED MIXTURE, WET MESIC	11.000	LBS
44	622-52436 SIGN, DO NOT MOW OR SPRAY	20.000	EACH
45	628-09402 FIELD OFFICE, B	12.000	MOS
46	628-11729 CELLULAR TELEPHONE TYPE A	2.000	EACH
47	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
48	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
49	628-11780 CELLULAR TELEPHONE SERVICE 500 MIN	24.000	MOS

CALL ORDER : 270

CONTRACT ID : R -34078-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50	714-11138 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	62.000	LFT
51	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	10.000	LFT
52	715-05146 PIPE, TYPE 2 CIRCULAR 6 IN	26.000	LFT
53	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	45.000	TON
54	718-06529 OUTLET PROTECTOR, 2	2.000	EACH
55	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
56	801-04308 ROAD CLOSURE SIGN ASSEMBLY	7.000	EACH
57	801-06625 DETOUR ROUTE MARKER ASSEMBLY	19.000	EACH
58	801-06640 CONSTRUCTION SIGN, A	7.000	EACH
59	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
60	801-07118 BARRICADE, III-A	100.000	LFT
61	801-07119 BARRICADE, III-B	125.000	LFT
62	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	3.000	EACH
63	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	22.000	LFT
64	802-07060 SIGN, SHEET, RELOCATE	1.000	EACH
65	802-11648 SIGN POST	27.000	EACH
66	808-06712 LINE, PAINT, BROKEN, YELLOW, 4 IN	4.000	LFT
67	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	84.000	LFT
68	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	42.000	LFT

CALL ORDER : 280

CONTRACT ID : R -34396-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08441 QUALITY ADJUSTMENTS, PCCP	1.000	DOL
7	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
8	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
9	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
10	109-09377 QUALITY ADJUSTMENT, PAVEMENT TRAFFIC MARKINGS	1.000	DOL
11	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
12	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
13	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
14	203-02000 EXCAVATION, COMMON	15.000	CYS
15	203-02070 BORROW	882.000	CYS
16	203-02100 EXCAVATION, PEAT	7,263.000	CYS
17	203-51223 EXCAVATION, WATERWAY	219.000	CYS
18	204-08415 STAKE, SETTLEMENT	9.000	EACH
19	205-03371 SEDIMENT, REMOVE	3,500.000	CYS
20	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	1,223.000	TON
21	205-06933 TEMPORARY INLET PROTECTION	12.000	EACH
22	205-06934 TEMPORARY MULCH	71.000	TON
23	205-06936 TEMPORARY SEDIMENT TRAP	661.000	TON
24	205-06937 TEMPORARY SILT FENCE	3,870.000	LFT
25	205-09543 NO 2 STONE	1,035.000	TON
26	205-11584 TEMPORARY CHECK DAM, TRAVERSABLE	108.000	LFT
27	207-08262 SUBGRADE TREATMENT, TYPE I	49,337.000	SYS
28	207-08265 SUBGRADE TREATMENT, TYPE IIA	3,232.000	SYS
29	207-08266 SUBGRADE TREATMENT, TYPE III	4,000.000	SYS
30	207-08267 SUBGRADE TREATMENT, TYPE IIIA	569.000	SYS
31	207-09935 SUBGRADE TREATMENT, TYPE IC	10,817.000	SYS
32	211-06467 AGGREGATE FOR END BENT BACKFILL	54.000	CYS
33	211-09194 B BORROW	7,626.000	TON
34	211-09264 STRUCTURAL BACKFILL, TYPE 1	2,889.000	CYS
35	211-09265 STRUCTURAL BACKFILL, TYPE 2	1,203.000	CYS
36	215-07043 CHEMICAL MODIFICATION, SOILS	26,100.000	SYS
37	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	12,362.000	TON
38	302-07455 DENSE GRADED SUBBASE	40.000	CYS
39	303-08210 COMPACTED AGGREGATE NO. 53, TEMPORARY FOR DRIVEWAYS	635.000	TON
40	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	234.000	TON
41	401-07334 QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	536.000	TON
42	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	389.000	TON
43	401-07403 QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	893.000	TON
44	401-07427 QC/QA-HMA, 2, 70, BASE, 19.0 mm	467.000	TON
45	402-10083 HMA FOR TEMPORARY PAVEMENT, A	779.000	TON
46	502-09531 PCCP	466.000	SYS
47	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
48	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
49	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	163.000	LFT

CALL ORDER : 280

CONTRACT ID : R -34396-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
50	605-06120 CURB, CONCRETE	362.000	LFT
51	605-06145 CURB AND GUTTER, B, CONCRETE	868.000	LFT
52	605-06155 CURB AND GUTTER, CONCRETE, MODIFIED	1,075.000	LFT
53	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	230.000	SYS
54	610-07487 HMA FOR APPROACHES, TYPE B	268.000	TON
55	611-06497 MAILBOX ASSEMBLY, SINGLE	2.000	EACH
56	615-06490 RIGHT OF WAY MARKER	57.000	EACH
57	615-06510 MONUMENT, C	3.000	EACH
58	615-06527 MONUMENT, SECTION CORNER	3.000	EACH
59	615-06530 BENCH MARK POST	4.000	EACH
60	616-02320 GEOTEXTILES	2,145.000	SYS
61	616-05688 RIPRAP, CLASS 1	155.000	TON
62	616-06405 RIPRAP, REVETMENT	712.000	TON
63	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
64	621-02318 SEED MIXTURE, PRAIRIE GRASS	1.000	LBS
65	621-02770 EROSION CONTROL BLANKET	234.000	SYS
66	621-06545 FERTILIZER	27.900	TON
67	621-06554 SEED MIXTURE, U	5,152.000	LBS
68	621-06557 SEED MIXTURE, T	5,325.000	LBS
69	621-06565 MULCHING MATERIAL	140.000	TON
70	621-06567 WATER	70.000	KGAL
71	621-06574 SODDING	53.000	SYS
72	621-06575 SODDING, NURSERY	4,154.000	SYS
73	628-09403 FIELD OFFICE, C	15.000	MOS
74	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	15.000	MOS
75	701-09558 TEST PILE, INDICATOR, PRODUCTION	128.000	LFT
76	701-09560 TEST PILE, INDICATOR, RESTRIKE	2.000	EACH
77	701-09739 PILE SHOE, HP 12 X 53	16.000	EACH
78	701-51195 PILE, STEEL H, HP 12 IN X 53	756.000	LFT
79	703-06029 REINFORCING BARS, EPOXY COATED	54,883.000	LBS
80	704-51002 CONCRETE, C, SUPERSTRUCTURE	169.500	CYS
81	706-06351 CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.000	EACH
82	706-11404 RAILING, STEEL, PF-1	154.000	LFT
83	706-51020 RAILING, CONCRETE, C	8.400	CYS
84	707-09865 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 36 IN X 49 IN	338.000	LFT
85	709-51821 SURFACE SEAL	LUMP	LUMP
86	713-11199 TEMPORARY PIPE	19.000	LFT
87	714-11172 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	123.000	LFT
88	714-11173 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	100.000	LFT
89	715-03584 SAFETY METAL END SECTION 4:1 DIA 18"	1.000	EACH
90	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	20,748.000	LFT
91	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	2,063.000	LFT
92	715-05119 PIPE, TYPE 1 CIRCULAR 15 IN	267.000	LFT
93	715-05121 PIPE, TYPE 1 CIRCULAR 18 IN	215.000	LFT
94	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	100.000	LFT
95	715-05147 PIPE, TYPE 2 CIRCULAR 8 IN	62.000	LFT
96	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	471.000	LFT
97	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	207.000	LFT
98	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	3,441.000	LFT

CALL ORDER : 280

CONTRACT ID : R -34396-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
99	715-05168 PIPE, TYPE 3 CIRCULAR 12 IN	125.000	LFT
100	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	286.000	LFT
101	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	277.000	LFT
102	715-05407 PIPE, END BENT DRAIN, 6 IN	130.000	LFT
103	715-46000 PIPE END SECTION, DIA 12"	4.000	EACH
104	715-46005 PIPE END SECTION, DIA 15"	12.000	EACH
105	715-46010 PIPE END SECTION, DIA 18"	9.000	EACH
106	715-46020 PIPE END SECTION, DIA 24"	2.000	EACH
107	715-90836 PIPE END SECTION, DIA 8"	1.000	EACH
108	718-06528 OUTLET PROTECTOR, 1	32.000	EACH
109	718-06529 OUTLET PROTECTOR, 2	2.000	EACH
110	718-06531 OUTLET PROTECTOR, 3	8.000	EACH
111	718-06532 VIDEO INSPECTION FOR UNDERDRAINS	3,000.000	LFT
112	718-52610 AGGREGATE FOR UNDERDRAINS	1,716.000	CYS
113	718-99153 GEOTEXTILES FOR UNDERDRAIN	17,615.000	SYS
114	720-45030 INLET, E7	2.000	EACH
115	720-45275 PIPE CATCH BASIN, 24 IN	1.000	EACH
116	720-45410 MANHOLE, C4	13.000	EACH
117	720-98174 INLET, B15	7.000	EACH
118	720-98555 INLET, C15	3.000	EACH
119	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
120	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	18,300.000	LFT
121	801-06640 CONSTRUCTION SIGN, A	22.000	EACH
122	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
123	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
124	801-07119 BARRICADE, III-B	360.000	LFT
125	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	327.000	LFT
126	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	131.000	SFT
127	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	120.000	SFT
128	807-02191 HANDHOLE, LIGHTING	2.000	EACH
129	807-02193 LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT	7.000	EACH
130	807-04654 LIGHT POLE	7.000	EACH
131	807-04866 LUMINAIRE,	7.000	EACH
132	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	160.000	LFT
133	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	955.000	LFT
134	807-86805 SERVICE POINT, I	1.000	EACH
135	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	1,225.000	LFT
136	807-86910 CONNECTOR KIT, UNFUSED	7.000	EACH
137	807-86915 CONNECTOR KIT, FUSED	7.000	EACH
138	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	15.000	EACH
139	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	4.000	EACH
140	807-86930 INSULATION LINK, NON-WATERPROOFED	16.000	EACH
141	807-86935 INSULATION LINK, WATERPROOFED	4.000	EACH
142	807-86950 SIGN UNDERPASS AND ROADWAY LIGHTING LOCATION IDENTIFICATION	7.000	EACH
143	807-86955 CABLE-DUCT MARKER	4.000	EACH
144	807-97237 WIRE, NO 4 COPPER, IN PLASTIC DUCT, 4 1/C	160.000	LFT
145	808-06716 LINE, REMOVE	4,575.000	LFT
146	808-09381 RETRO-REFLECTIVITY TESTING	LUMP	LUMP
147	808-11401 TRANSVERSE MARKING, PREFORMED PLASTIC,	60.000	LFT

CALL ORDER : 280

CONTRACT ID : R -34396-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
148	808-11478 LINE, THERMOPLASTIC, DOTTED, WHITE 8 IN	50.000	LFT
149	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	209.000	EACH
SECTION NO. 0002 NEW ROAD CONSTRUCTION			
150	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
151	203-02000 EXCAVATION, COMMON	94,736.000	CYS
152	203-02070 BORROW	18,614.000	CYS
153	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
154	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	3,962.000	TON
155	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	6,603.000	TON
156	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	6,235.000	TON
157	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	5,668.000	TON
158	401-10258 JOINT ADHESIVE, SURFACE	36,136.000	LFT
159	401-10259 JOINT ADHESIVE, INTERMEDIATE	36,136.000	LFT
160	401-11785 LIQUID ASPHALT SEALANT	36,136.000	LFT
161	406-05520 ASPHALT FOR TACK COAT	35.000	TON
162	615-06505 MONUMENT, B	22.000	EACH
163	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	23,990.000	LFT
164	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	220.000	LFT
165	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	110.000	LFT
166	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	30.000	LFT
167	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	1,370.000	LFT
168	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	17,640.000	LFT
169	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	370.000	LFT
170	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	95.000	LFT
171	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	14.000	EACH
172	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	6.000	EACH
173	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	1,205.000	LFT
SECTION NO. 0003 NEW ROAD CONSTRUCTION			
174	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
175	203-02000 EXCAVATION, COMMON	96,877.000	CYS
176	203-02070 BORROW	12,895.000	CYS
177	302-06464 SUBBASE FOR PCCP	7,824.000	CYS
178	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	1,380.000	TON
179	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	2,300.000	TON
180	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	1,071.000	TON
181	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	974.000	TON
182	401-10258 JOINT ADHESIVE, SURFACE	8,364.000	LFT
183	401-10259 JOINT ADHESIVE, INTERMEDIATE	8,364.000	LFT
184	401-11785 LIQUID ASPHALT SEALANT	8,364.000	LFT
185	406-05520 ASPHALT FOR TACK COAT	8.000	TON
186	501-06266 PROFILOGRAPH, PCCP	LUMP	LUMP
187	501-06727 CORING, PCCP	LUMP	LUMP
188	501-09107 QC/QA-PCCP, 9 IN	31,293.000	SYS
189	503-05240 D-1 CONTRACTION JOINT	15,650.000	LFT
190	503-05310 TERMINAL JOINT	96.000	LFT

CALL ORDER : 280

CONTRACT ID : R -34396-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0003 NEW ROAD CONSTRUCTION			
191	615-06505 MONUMENT, B	6.000	EACH
192	615-06515 MONUMENT, D	16.000	EACH
193	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4,189.000	LFT
194	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	20,021.000	LFT
195	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	13,213.000	LFT
196	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	1,320.000	LFT
197	808-10042 TRANSVERSE MARKING MULTI-COMPONENT,	370.000	LFT
198	808-10051 TRANSVERSE MARKING MULTI-COMPONENT,	95.000	LFT
199	808-10052 PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, (ONLY)	6.000	EACH
200	808-10058 LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN	1,205.000	LFT
201	808-10077 PAVEMENT MESSAGE MARKINGS, MULTI-COMPONENT,	14.000	EACH
202	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	80.000	LFT
203	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	4,537.000	LFT

CALL ORDER : 290

CONTRACT ID : R -34524-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	202-02240 PAVEMENT REMOVAL	280.000	SYS
10	202-02273 CENTER CURB, CONCRETE, REMOVE	18.000	SYS
11	203-02000 EXCAVATION, COMMON	150.000	CYS
12	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	10.000	TON
13	205-06937 TEMPORARY SILT FENCE	140.000	LFT
14	207-09935 SUBGRADE TREATMENT, TYPE IC	402.000	SYS
15	211-02050 B BORROW	87.000	CYS
16	211-09265 STRUCTURAL BACKFILL, TYPE 2	88.000	CYS
17	211-09268 STRUCTURAL BACKFILL, TYPE 5	89.000	CYS
18	302-06464 SUBBASE FOR PCCP	84.000	CYS
19	406-05521 ASPHALT FOR TACK COAT	170.000	SYS
20	503-05240 D-1 CONTRACTION JOINT	126.000	LFT
21	605-06250 CENTER CURB, C, CONCRETE	18.000	SYS
22	616-02320 GEOTEXTILES	82.000	SYS
23	616-05688 RIPRAP, CLASS 1	100.000	TON
24	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
25	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	1,030.000	SYS
26	621-02770 EROSION CONTROL BLANKET	50.000	SYS
27	621-06559 MULCHED SEEDING, R	1,030.000	SYS
28	628-09402 FIELD OFFICE, B	12.000	MOS
29	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	24.000	MOS
30	628-11730 CELLULAR TELEPHONE TYPE B	1.000	EACH
31	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
32	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	12.000	MOS
33	714-11192 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	108.000	LFT
34	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	102.000	LFT
35	715-08283 PCCP FOR STRUCTURE INSTALLATION	280.000	SYS
36	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	29.000	TON
37	718-52610 AGGREGATE FOR UNDERDRAINS	6.000	CYS
38	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
39	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	7,132.000	LFT
40	801-06469 TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN	290.000	LFT
41	801-06625 DETOUR ROUTE MARKER ASSEMBLY	1.000	EACH
42	801-06640 CONSTRUCTION SIGN, A	7.000	EACH
43	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
44	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	673.000	LFT
45	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	9.000	LFT
46	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	8.000	SFT
47	808-06716 LINE, REMOVE	3,415.000	LFT
48	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	460.000	LFT
49	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	1,155.000	LFT

CALL ORDER : 290

CONTRACT ID : R -34524-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50 808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	712.000	LFT
51 808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN	1,050.000	LFT

CALL ORDER : 300

CONTRACT ID : R -34552-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02272 PAVED SIDE DITCH, REMOVE	92.000	LFT
13	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
14	203-02000 EXCAVATION, COMMON	952.000	CYS
15	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	33.000	TON
16	205-06934 TEMPORARY MULCH	4.000	TON
17	205-09543 NO 2 STONE	100.000	TON
18	205-11584 TEMPORARY CHECK DAM, TRAVERSABLE	74.000	LFT
19	205-11586 TEMPORARY FILTER STONE	3.000	TON
20	205-11587 TEMPORARY GEOTEXTILE	406.000	SYS
21	205-11591 TEMPORARY SEED MIXTURE	190.000	LBS
22	207-08265 SUBGRADE TREATMENT, TYPE IIA	1,914.000	SYS
23	211-09265 STRUCTURAL BACKFILL, TYPE 2	126.000	CYS
24	211-09268 STRUCTURAL BACKFILL, TYPE 5	482.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	467.000	TON
26	303-01180 COMPACTED AGGREGATE, NO. 53	375.000	TON
27	306-08034 MILLING, ASPHALT, 1 1/2 IN	168.000	SYS
28	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	122.000	TON
29	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	260.000	TON
30	401-10258 JOINT ADHESIVE, SURFACE	845.000	LFT
31	401-10259 JOINT ADHESIVE, INTERMEDIATE	655.000	LFT
32	401-11785 LIQUID ASPHALT SEALANT	1,500.000	LFT
33	406-05521 ASPHALT FOR TACK COAT	1,477.000	SYS
34	601-02103 GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN SPACING	87.500	LFT
35	601-02241 GUARDRAIL, REMOVE	462.500	LFT
36	601-06854 GUARDRAIL, W-BEAM, NESTED	1.000	EACH
37	601-91198 GUARDRAIL POST, MODIFIED	3.000	EACH
38	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
39	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	287.500	LFT
40	615-06490 RIGHT OF WAY MARKER	9.000	EACH
41	615-06505 MONUMENT, B	4.000	EACH
42	616-02320 GEOTEXTILES	790.000	SYS
43	616-05688 RIPRAP, CLASS 1	411.000	TON
44	616-06405 RIPRAP, REVETMENT	63.000	TON
45	616-06451 RIPRAP, UNIFORM	89.000	TON
46	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
47	621-02770 EROSION CONTROL BLANKET	1,225.000	SYS
48	621-06559 MULCHED SEEDING, R	3,000.000	SYS
49	628-09402 FIELD OFFICE, B	12.000	MOS

CALL ORDER : 300

CONTRACT ID : R -34552-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
51	628-11729 CELLULAR TELEPHONE TYPE A	2.000	EACH
52	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
53	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
54	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	24.000	MOS
55	714-11174 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	80.000	LFT
56	714-11338 STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS,	70.000	LFT
57	715-05169 PIPE, TYPE 3 CIRCULAR 15 IN	36.000	LFT
58	715-46005 PIPE END SECTION, DIA 15"	2.000	EACH
59	801-01851 TEMPORARY TRAFFIC SIGNAL WITH DETECTORS	LUMP	LUMP
60	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
61	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
62	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	4,166.000	LFT
63	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	15.000	EACH
64	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	65.000	LFT
65	801-06625 DETOUR ROUTE MARKER ASSEMBLY	33.000	EACH
66	801-06640 CONSTRUCTION SIGN, A	23.000	EACH
67	801-06645 CONSTRUCTION SIGN, B	10.000	EACH
68	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
69	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	2.000	EACH
70	801-07118 BARRICADE, III-A	144.000	LFT
71	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	690.000	LFT
72	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	178.000	LFT
73	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,901.000	LFT
74	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	165.000	LFT
75	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN	12.000	LFT
76	808-06716 LINE, REMOVE	1,142.000	LFT
77	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	133.000	LFT
78	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,876.000	LFT
79	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.000	EACH
80	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	4.000	EACH

CALL ORDER : 310

CONTRACT ID : R -34591-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PIPE LINING			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
9	601-06035 GUARDRAIL, RESET	150.000	LFT
10	616-02320 GEOTEXTILES	260.000	SYS
11	616-05688 RIPRAP, CLASS 1	32.000	TON
12	616-05689 RIPRAP, CLASS 2	265.000	TON
13	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
14	621-06559 MULCHED SEEDING, R	12,000.000	SYS
15	628-11730 CELLULAR TELEPHONE TYPE B	2.000	EACH
16	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
17	725-08296 PIPE LINER, CURED-IN-PLACE, 48 IN	293.000	LFT
18	725-10198 LINER PIPE, THERMOPLASTIC, DEFORMED, 26.6-28.3 SFT	271.000	LFT
19	725-10206 PIPE LINER, CURED-IN-PLACE, 96 IN	82.000	LFT
20	725-10227 LINER PIPE, THERMOPLASTIC, CIRCULAR, 18.9-19.0 SFT	200.000	LFT
21	725-10245 PERPETUATION, EXISTING PIPE	2.000	EACH
22	725-11038 LINER PIPE THERMOPLASTIC CIRCULAR 15.9-16.0 SFT	250.000	LFT
23	725-11651 PIPE LINER, CURED-IN-PLACE, 9.4 SFT	265.400	LFT
24	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	22.000	EACH
25	801-03290 CONSTRUCTION SIGN, C	10.000	EACH
26	801-06640 CONSTRUCTION SIGN, A	60.000	EACH
27	801-06710 FLASHING ARROW SIGN	55.000	DAY
28	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
29	804-06771 DELINEATOR POST, FLEXIBLE	10.000	EACH

CALL ORDER : 320

CONTRACT ID : R -34735-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	203-02000 EXCAVATION, COMMON	167,856.000	CYS
13	203-02010 EXCAVATION, ROCK	56,343.000	CYS
14	203-02070 BORROW	33,025.000	CYS
15	203-51223 EXCAVATION, WATERWAY	1,050.000	CYS
16	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	795.000	TON
17	205-06934 TEMPORARY MULCH	144.000	TON
18	205-06935 TEMPORARY SEDIMENT BASIN	1.000	EACH
19	205-06936 TEMPORARY SEDIMENT TRAP	300.000	TON
20	205-06937 TEMPORARY SILT FENCE	22,310.000	LFT
21	205-06938 TEMPORARY SLOPE DRAIN	1,038.000	LFT
22	205-09543 NO 2 STONE	400.000	TON
23	205-11586 TEMPORARY FILTER STONE	66.000	TON
24	206-51215 EXCAVATION, X	137.000	CYS
25	206-51220 EXCAVATION, WET	67.000	CYS
26	207-08266 SUBGRADE TREATMENT, TYPE III	37,887.000	SYS
27	207-08267 SUBGRADE TREATMENT, TYPE IIIA	131.000	SYS
28	211-06467 AGGREGATE FOR END BENT BACKFILL	24.000	CYS
29	211-09264 STRUCTURAL BACKFILL, TYPE 1	429.000	CYS
30	211-09265 STRUCTURAL BACKFILL, TYPE 2	1,490.000	CYS
31	211-09266 STRUCTURAL BACKFILL, TYPE 3	343.000	CYS
32	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	9,073.000	TON
33	302-07455 DENSE GRADED SUBBASE	24.000	CYS
34	303-01180 COMPACTED AGGREGATE, NO. 53	5,509.000	TON
35	303-07449 COMPACTED AGGREGATE, NO. 73	1,800.000	TON
36	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2,229.000	TON
37	401-07322 QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	338.000	TON
38	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	5,200.000	TON
39	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	787.000	TON
40	401-10258 JOINT ADHESIVE, SURFACE	10,896.000	LFT
41	401-10259 JOINT ADHESIVE, INTERMEDIATE	10,896.000	LFT
42	406-05521 ASPHALT FOR TACK COAT	31,234.000	SYS
43	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
44	601-01626 GUARDRAIL CONNECTOR SYSTEM, W-BEAM, CURVED, 2	2.000	EACH
45	601-05999 CURVED TERMINAL END	1.000	EACH
46	601-08433 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	3.000	EACH
47	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	3.000	EACH
48	601-94689 GUARDRAIL END TREATMENT, OS	13.000	EACH
49	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	3,300.000	LFT

CALL ORDER : 320

CONTRACT ID : R -34735-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW ROAD CONSTRUCTION		
50	602-06729 BARRIER DELINEATOR	8.000	EACH
51	603-06065 FENCE, CHAIN LINK, RESET	800.000	LFT
52	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	146.000	SYS
53	610-07487 HMA FOR APPROACHES, TYPE B	36.000	TON
54	615-06505 MONUMENT, B	30.000	EACH
55	615-06510 MONUMENT, C	5.000	EACH
56	616-02320 GEOTEXTILES	14,386.000	SYS
57	616-05688 RIPRAP, CLASS 1	2,531.000	TON
58	616-06405 RIPRAP, REVETMENT	4,995.000	TON
59	616-06451 RIPRAP, UNIFORM	28.000	TON
60	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.000	EACH
61	621-02770 EROSION CONTROL BLANKET	36,010.000	SYS
62	621-04258 SEED MIXTURE	7.000	LBS
63	621-06545 FERTILIZER	16.000	TON
64	621-06553 SEED MIXTURE, R	6,188.000	LBS
65	621-06557 SEED MIXTURE, T	10,920.000	LBS
66	621-06557 SEED MIXTURE, T	130.000	LBS
67	621-06565 MULCHING MATERIAL	72.000	TON
68	621-06567 WATER	17,001.000	KGAL
69	621-06574 SODDING	4,766.000	SYS
70	621-09398 SEED MIXTURE, SLOPE STABILIZATION	35.000	LBS
71	622-05649 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN	382.000	EACH
72	622-52436 SIGN, DO NOT MOW OR SPRAY	6.000	EACH
73	622-98200 SIGN, DO NOT DISTURB	6.000	EACH
74	628-09402 FIELD OFFICE, B	18.000	MOS
75	628-11729 CELLULAR TELEPHONE TYPE A	2.000	EACH
76	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
77	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
78	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	36.000	MOS
79	701-09558 TEST PILE, INDICATOR, PRODUCTION	70.000	LFT
80	701-09560 TEST PILE, INDICATOR, RESTRIKE	2.000	EACH
81	701-09683 PILE SHOE, HP 12 X 74	8.000	EACH
82	701-95780 PILE, STEEL H, HP 12 IN X 74	150.000	LFT
83	702-51005 CONCRETE, A, SUBSTRUCTURE	69.600	CYS
84	702-51015 CONCRETE, B, FOOTINGS	37.700	CYS
85	703-06028 REINFORCING BARS	15,043.000	LBS
86	703-06029 REINFORCING BARS, EPOXY COATED	52,813.000	LBS
87	704-51002 CONCRETE, C, SUPERSTRUCTURE	168.600	CYS
88	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH
89	706-51020 RAILING, CONCRETE, C	25.300	CYS
90	707-09865 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 36 IN X 49 IN	524.000	LFT
91	709-51821 SURFACE SEAL	LUMP	LUMP
92	714-11179 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	105.000	LFT
93	715-05121 PIPE, TYPE 1 CIRCULAR 18 IN	218.000	LFT
94	715-05123 PIPE, TYPE 1 CIRCULAR 24 IN	256.000	LFT
95	715-05124 PIPE, TYPE 1, CIRCULAR, 27 IN	85.000	LFT
96	715-05125 PIPE, TYPE 1 CIRCULAR 30 IN	46.000	LFT
97	715-05133 PIPE, TYPE 1 CIRCULAR 60 IN	50.000	LFT
98	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	72.000	LFT

CALL ORDER : 320

CONTRACT ID : R -34735-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 NEW ROAD CONSTRUCTION			
99	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	55.000	LFT
100	715-05163 PIPE, TYPE 2 CIRCULAR 60 IN	89.000	LFT
101	715-05407 PIPE, END BENT DRAIN, 6 IN	92.000	LFT
102	715-46010 PIPE END SECTION, DIA 18"	6.000	EACH
103	715-46020 PIPE END SECTION, DIA 24"	6.000	EACH
104	715-46025 PIPE END SECTION, DIA 27"	2.000	EACH
105	715-46030 PIPE END SECTION, DIA 30"	2.000	EACH
106	720-45410 MANHOLE, C4	4.000	EACH
107	720-45416 MANHOLE, E4	2.000	EACH
108	723-11225 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	240.000	LFT
109	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
110	801-06625 DETOUR ROUTE MARKER ASSEMBLY	12.000	EACH
111	801-06640 CONSTRUCTION SIGN, A	22.000	EACH
112	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
113	801-07118 BARRICADE, III-A	96.000	LFT
114	801-07119 BARRICADE, III-B	72.000	LFT
115	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	196.000	LFT
116	802-05706 SIGN POST, SQUARE, TYPE 3, UNREINFORCED ANCHOR BASE	48.000	LFT
117	802-07059 SIGN, SHEET, AND SUPPORTS, REMOVE	2.000	EACH
118	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	83.000	SFT
119	802-09839 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.100 IN THICKNESS	28.000	SFT
120	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	4.000	SFT
121	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	51.000	SFT
122	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	21,757.000	LFT
123	808-06716 LINE, REMOVE	213.000	LFT
124	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	352.000	LFT
125	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	352.000	LFT
126	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	21,289.000	LFT
127	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	87.000	LFT
128	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	258.000	EACH

CALL ORDER : 330

CONTRACT ID : R -34760-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ASPHALT RESURFACE AND SIGN IMPROVEMENTS			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	201-01015 CLEARING AND GRUBBING	LUMP	LUMP
10	203-02000 EXCAVATION, COMMON	1,056.000	CYS
11	207-09935 SUBGRADE TREATMENT, TYPE IC	5,676.000	SYS
12	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	1,339.000	TON
13	304-07489 HMA PATCHING, TYPE A	516.000	TON
14	306-08042 MILLING, SCARIFICATION/PROFILE	4,066.000	SYS
15	306-08043 MILLING, TRANSITION	1,300.000	SYS
16	306-08432 MILLING, APPROACH	472.000	SYS
17	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	743.000	TON
18	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	759.000	TON
19	401-10258 JOINT ADHESIVE, SURFACE	4,165.000	LFT
20	401-10259 JOINT ADHESIVE, INTERMEDIATE	1,729.000	LFT
21	401-11785 LIQUID ASPHALT SEALANT	4,165.000	LFT
22	402-07450 HMA WEDGE AND LEVEL, TYPE A	179.000	TON
23	404-05511 SEAL COAT, 2	14,094.000	SYS
24	406-05520 ASPHALT FOR TACK COAT	3.000	TON
25	601-02103 GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN SPACING	262.500	LFT
26	601-02241 GUARDRAIL, REMOVE	335.000	LFT
27	601-05586 GUARDRAIL TERMINAL SYSTEM, W BEAM, CURVED, 9	1.000	EACH
28	601-94689 GUARDRAIL END TREATMENT, OS	3.000	EACH
29	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	112.500	LFT
30	610-07486 HMA FOR APPROACHES, TYPE A	39.000	TON
31	628-09402 FIELD OFFICE, B	7.000	MOS
32	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
33	801-04308 ROAD CLOSURE SIGN ASSEMBLY	3.000	EACH
34	801-06625 DETOUR ROUTE MARKER ASSEMBLY	21.000	EACH
35	801-06640 CONSTRUCTION SIGN, A	7.000	EACH
36	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
37	801-07119 BARRICADE, III-B	40.000	LFT
38	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	341.000	LFT
39	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	178.000	SFT
40	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	17.000	SFT
41	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	11,833.000	LFT
42	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	130.000	LFT
43	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	490.000	LFT
44	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	19,402.000	LFT
45	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	122.000	LFT
46	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	46.000	EACH

CALL ORDER : 340

CONTRACT ID : R -34950-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
9	203-02000 EXCAVATION, COMMON	1,428.000	CYS
10	203-02070 BORROW	554.000	CYS
11	203-51223 EXCAVATION, WATERWAY	20.000	CYS
12	205-03371 SEDIMENT, REMOVE	20.000	CYS
13	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	32.000	TON
14	205-06933 TEMPORARY INLET PROTECTION	1.000	EACH
15	205-06934 TEMPORARY MULCH	2.700	TON
16	205-06937 TEMPORARY SILT FENCE	1,601.000	LFT
17	205-09543 NO 2 STONE	200.000	TON
18	207-09935 SUBGRADE TREATMENT, TYPE IC	187.000	SYS
19	211-09265 STRUCTURAL BACKFILL, TYPE 2	387.700	CYS
20	211-09268 STRUCTURAL BACKFILL, TYPE 5	186.000	CYS
21	214-07202 GEOGRID, TYPE IA	44.400	SYS
22	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	63.000	TON
23	303-01180 COMPACTED AGGREGATE, NO. 53	436.000	TON
24	303-07449 COMPACTED AGGREGATE, NO. 73	260.000	TON
25	406-05521 ASPHALT FOR TACK COAT	374.000	SYS
26	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	1.000	EACH
27	601-02241 GUARDRAIL, REMOVE	1,527.000	LFT
28	601-06854 GUARDRAIL, W-BEAM, NESTED	4.000	EACH
29	601-94689 GUARDRAIL END TREATMENT, OS	7.000	EACH
30	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	1,285.000	LFT
31	615-06490 RIGHT OF WAY MARKER	32.000	EACH
32	616-02320 GEOTEXTILES	264.000	SYS
33	616-05688 RIPRAP, CLASS 1	35.000	TON
34	616-06405 RIPRAP, REVETMENT	98.000	TON
35	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.000	EACH
36	621-02770 EROSION CONTROL BLANKET	3,388.000	SYS
37	621-06545 FERTILIZER	0.300	TON
38	621-06553 SEED MIXTURE, R	121.000	LBS
39	621-06557 SEED MIXTURE, T	309.000	LBS
40	621-06559 MULCHED SEEDING, R	1,082.000	SYS
41	621-06574 SODDING	825.000	SYS
42	628-09402 FIELD OFFICE, B	8.000	MOS
43	628-11729 CELLULAR TELEPHONE TYPE A	2.000	EACH
44	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
45	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
46	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	16.000	MOS
47	702-51015 CONCRETE, B, FOOTINGS	40.000	CYS
48	714-11073 STRUCTURE, REINFORCED CONCRETE BOX SECTIONS,	56.000	LFT
49	714-11078 STRUCTURE REINFORCED CONCRETE BOX SECTIONS,	62.000	LFT

CALL ORDER : 340

CONTRACT ID : R -34950-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	SMALL STRUCTURE REPLACEMENT		
50	715-03584 SAFETY METAL END SECTION 4:1 DIA 18"	1.000	EACH
51	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	90.000	LFT
52	715-08305 HMA FOR STRUCTURE INSTALLATION, TYPE B	78.000	TON
53	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
54	801-04308 ROAD CLOSURE SIGN ASSEMBLY	12.000	EACH
55	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	8.000	LFT
56	801-06625 DETOUR ROUTE MARKER ASSEMBLY	28.000	EACH
57	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
58	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
59	801-07118 BARRICADE, III-A	100.000	LFT
60	801-07119 BARRICADE, III-B	125.000	LFT
61	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH
62	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	40.000	LFT
63	802-07060 SIGN, SHEET, RELOCATE	4.000	EACH
64	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	160.000	LFT
65	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	160.000	LFT

CALL ORDER : 370

CONTRACT ID : R -35389-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ASPHALT RESURFACE		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	207-08267 SUBGRADE TREATMENT, TYPE IIIA	75.000	SYS
10	304-07490 HMA PATCHING, TYPE B	75.000	TON
11	306-08042 MILLING, SCARIFICATION/PROFILE	4,000.000	SYS
12	306-08043 MILLING, TRANSITION	100.000	SYS
13	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	330.000	TON
14	406-05520 ASPHALT FOR TACK COAT	1.000	TON
15	615-11537 PARKING BARRIER, CONCRETE	2.000	EACH
16	615-97768 PARKING BARRIER, RESET	20.000	EACH
17	628-09401 FIELD OFFICE, A	4.000	MOS
18	628-11730 CELLULAR TELEPHONE TYPE B	2.000	EACH
19	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
20	628-11780 CELLULAR TELEPHONE SERVICE 500 MIN	8.000	MOS
21	801-06640 CONSTRUCTION SIGN, A	2.000	EACH
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	808-06713 LINE, PAINT, SOLID, WHITE, 4 IN	750.000	LFT

CALL ORDER : 380

CONTRACT ID : R -35496-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PIPE LINING			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	107-09358 INSPECTION HOLE, GREATER THAN 3'	1.000	EACH
3	107-09367 INSPECTION HOLE, 3 FT DEPTH OR LESS	1.000	EACH
4	109-08359 LIQUIDATED DAMAGES	1.000	DOL
5	109-08360 CONTRACT LIENS	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	205-06937 TEMPORARY SILT FENCE	150.000	LFT
11	616-02320 GEOTEXTILES	53.300	SYS
12	616-05688 RIPRAP, CLASS 1	53.300	TON
13	725-11032 LINER PIPE THERMOPLASTIC CIRCULAR 3.1-3.2 SFT	220.000	LFT
14	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
15	801-06640 CONSTRUCTION SIGN, A	6.000	EACH
16	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 430

CONTRACT ID : R -36405-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 ROAD REHABILITATION			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	203-02000 EXCAVATION, COMMON	50.000	CYS
12	203-08607 LINEAR GRADING	1,471.000	LFT
13	205-06933 TEMPORARY INLET PROTECTION	20.000	EACH
14	207-08267 SUBGRADE TREATMENT, TYPE IIIA	68.000	SYS
15	207-09935 SUBGRADE TREATMENT, TYPE IC	2,000.000	SYS
16	211-09268 STRUCTURAL BACKFILL, TYPE 5	25.000	CYS
17	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	396.000	TON
18	305-07464 PCC BASE PATCHING, 9 IN	1,722.000	SYS
19	305-07468 PCC BASE PATCHING, 12 IN	25.000	SYS
20	306-08041 MILLING, PCCP	7,360.000	SYS
21	306-08043 MILLING, TRANSITION	208.000	SYS
22	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	794.000	TON
23	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1,536.000	TON
24	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	605.000	TON
25	402-07451 HMA WEDGE AND LEVEL, TYPE B	128.000	TON
26	406-05521 ASPHALT FOR TACK COAT	1,968.000	SYS
27	503-05240 D-1 CONTRACTION JOINT	64.000	LFT
28	604-05250 PREFORMED JOINT MATERIAL, 1/2 IN	554.000	LFT
29	604-06070 SIDEWALK, CONCRETE	1,394.000	SYS
30	604-07894 CURB RAMP, CONCRETE, A	24.000	SYS
31	604-07899 CURB RAMP, CONCRETE, E	6.000	SYS
32	604-07900 CURB RAMP, CONCRETE, F	10.000	SYS
33	604-07902 CURB RAMP, CONCRETE, H	4.000	SYS
34	604-07903 CURB RAMP, CONCRETE, K	16.000	SYS
35	605-06090 CURB, INTEGRAL, CONCRETE	2,363.000	LFT
36	605-06120 CURB, CONCRETE	754.000	LFT
37	605-06215 CENTER CURB, D, CONCRETE	535.000	LFT
38	605-92578 CURB WALK, CONCRETE	206.000	SYS
39	610-07487 HMA FOR APPROACHES, TYPE B	136.000	TON
40	610-09108 PCCP FOR APPROACHES, 9 IN	68.000	SYS
41	621-06560 MULCHED SEEDING, U	787.000	SYS
42	715-05217 PIPE, TYPE 5 CIRCULAR 12 IN	24.000	LFT
43	715-05218 PIPE, TYPE 5 CIRCULAR 15 IN	3.000	LFT
44	720-01355 INLET, CLEAN EXISTING	13.000	EACH
45	720-44000 CASTING, ADJUST TO GRADE	4.000	EACH
46	720-44000 CASTING, ADJUST TO GRADE	11.000	EACH
47	720-44055 CASTING, 10, FURNISH AND ADJUST TO GRADE	2.000	EACH
48	720-45250 CATCH BASIN, K10	7.000	EACH
49	720-45615 STRUCTURE, INLET, RECONSTRUCTED	1.000	LFT

CALL ORDER : 430

CONTRACT ID : R -36405-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD REHABILITATION		
50	720-94840 CASTING, WATER VALVE, ADJUST TO GRADE	7.000	EACH
51	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	7.000	EACH
52	801-03290 CONSTRUCTION SIGN, C	3.000	EACH
53	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	3,015.000	LFT
54	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	4,353.000	LFT
55	801-06211 TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE	7.000	EACH
56	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	48.000	LFT
57	801-06218 TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN	102.000	LFT
58	801-06640 CONSTRUCTION SIGN, A	21.000	EACH
59	801-06645 CONSTRUCTION SIGN, B	10.000	EACH
60	801-06710 FLASHING ARROW SIGN	90.000	DAY
61	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
62	801-07118 BARRICADE, III-A	420.000	LFT
63	801-94295 SIGNAL HEAD, RELOCATE	6.000	EACH
64	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	204.000	LFT
65	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	10.000	SFT
66	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	45.000	SFT
67	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	26.000	SFT
68	802-91122 SIGN, GROUND MOUNTED, RESET	21.000	EACH
69	805-01842 HANDHOLE, SIGNAL, TYPE 1	3.000	EACH
70	805-01843 SIGNAL HANDHOLE ADJUST TO GRADE	4.000	EACH
71	805-02150 PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN	4.000	EACH
72	805-02645 SIGNAL PEDESTAL FOUNDATION, A	3.000	EACH
73	805-03793 DETECTOR CARD RACK AND DETECTOR MODULES	2.000	EACH
74	805-03978 EMERGENCY VEHICLE PREEMPTION DETECTOR,	1.000	EACH
75	805-03979 EMERGENCY VEHICLE PREEMPTION DETECTOR,	4.000	EACH
76	805-09451 SIGNAL POLE, PEDESTAL, 15 FT	3.000	EACH
77	805-11817 PEDESTRIAN PUSH BUTTON, APS	2.000	EACH
78	805-78470 SIGNAL CABLE, ROADWAY LOOP, COPPER 1C/14GA	1,848.000	LFT
79	805-78480 SIGNAL CABLE, CONTROL, COPPER 3C/14GA	889.000	LFT
80	805-78485 SIGNAL CABLE, CONTROL, COPPER 5C/14GA	689.000	LFT
81	805-78510 SIGNAL CABLE, DETECTOR LEAD-IN COPPER 2C/16GA	72.000	LFT
82	805-78785 SIGNAL DETECTOR HOUSING	5.000	EACH
83	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	604.000	LFT
84	807-06592 CONDUIT, STEEL, GALVANIZED, 2 IN	489.000	LFT
85	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	585.000	LFT
86	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	665.000	LFT
87	808-06705 LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN	1,439.000	LFT
88	808-06706 LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN	492.000	LFT
89	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	620.000	LFT
90	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	10.000	EACH
91	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	5.000	EACH
92	808-92027 LINE, THERMOPLASTIC, SOLID, YELLOW, 8"	261.000	LFT
93	809-03983 PHASE SELECTORS	2.000	EACH
94	809-04982 CABLE	1,510.000	LFT

CALL ORDER : 480

CONTRACT ID : RS-36495-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INSTITUTIONAL ROAD PROJECT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	304-07490 HMA PATCHING, TYPE B	8.000	TON
8	404-05511 SEAL COAT, 2	1,250.000	SYS
9	408-07478 CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	7.000	TON
10	412-09355 FOG SEAL	30,500.000	SYS

CALL ORDER : 500

CONTRACT ID : B -30528-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
13	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
14	202-96133 PIPE, REMOVE	50.000	LFT
15	203-02000 EXCAVATION, COMMON	571.000	CYS
16	203-51223 EXCAVATION, WATERWAY	21.000	CYS
17	205-03371 SEDIMENT, REMOVE	46.000	CYS
18	205-06937 TEMPORARY SILT FENCE	821.000	LFT
19	206-51230 EXCAVATION, FOUNDATION, UNCLASSIFIED	692.000	CYS
20	206-51817 SHEET PILING, STEEL	948.000	SFT
21	207-09935 SUBGRADE TREATMENT, TYPE IC	461.000	SYS
22	211-02050 B BORROW	12.000	CYS
23	211-06467 AGGREGATE FOR END BENT BACKFILL	126.000	CYS
24	211-09264 STRUCTURAL BACKFILL, TYPE 1	10.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	109.000	TON
26	302-07455 DENSE GRADED SUBBASE	65.000	CYS
27	303-01180 COMPACTED AGGREGATE, NO. 53	362.000	TON
28	304-07493 WIDENING WITH HMA, TYPE B	45.000	TON
29	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,168.000	SYS
30	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	122.000	TON
31	401-10258 JOINT ADHESIVE, SURFACE	1,093.000	LFT
32	401-10259 JOINT ADHESIVE, INTERMEDIATE	663.000	LFT
33	401-11785 LIQUID ASPHALT SEALANT	1,093.000	LFT
34	402-07451 HMA WEDGE AND LEVEL, TYPE B	4.000	TON
35	406-05520 ASPHALT FOR TACK COAT	0.200	TON
36	406-05521 ASPHALT FOR TACK COAT	0.200	SYS
37	601-01522 GUARDRAIL, TRANSITION TYPE TGB	8.000	EACH
38	601-01704 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, MODIFIED	2.000	EACH
39	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	5.000	EACH
40	601-02241 GUARDRAIL, REMOVE	400.000	LFT
41	601-08434 GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS	1.000	EACH
42	601-09238 HAND DIG GUARDRAIL POST HOLES	12.000	EACH
43	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
44	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	43.750	LFT
45	602-06729 BARRIER DELINEATOR	13.000	EACH
46	605-06090 CURB, INTEGRAL, CONCRETE	79.000	LFT
47	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	384.000	SYS
48	615-06505 MONUMENT, B	4.000	EACH
49	616-02320 GEOTEXTILES	1,267.000	SYS

CALL ORDER : 500

CONTRACT ID : B -30528-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	616-06405 RIPRAP, REVETMENT	866.000	TON
51	621-02770 EROSION CONTROL BLANKET	165.000	SYS
52	621-06559 MULCHED SEEDING, R	2,140.000	SYS
53	621-06567 WATER	0.100	KGAL
54	621-06574 SODDING	43.000	SYS
55	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
56	701-09557 TEST PILE, DYNAMIC, PRODUCTION	142.000	LFT
57	701-09559 TEST PILE, DYNAMIC, RESTRIKE	6.000	EACH
58	701-09665 PILE, STEEL PIPE, 0.375 IN, 14 IN	180.000	LFT
59	701-09739 PILE SHOE, HP 12 X 53	14.000	EACH
60	701-51195 PILE, STEEL H, HP 12 IN X 53	806.000	LFT
61	702-51005 CONCRETE, A, SUBSTRUCTURE	56.700	CYS
62	702-92857 CONCRETE, C, SUBSTRUCTURE	81.200	CYS
63	703-06029 REINFORCING BARS, EPOXY COATED	103,819.000	LBS
64	704-51002 CONCRETE, C, SUPERSTRUCTURE	231.300	CYS
65	706-11600 RAILING, CONCRETE, FC	25.500	CYS
66	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	8.000	EACH
67	707-09865 STRUCTURAL MEMBER, CONCRETE BULB-T BEAM, 36 IN X 49 IN	277.000	LFT
68	707-11494 STRUCTURAL MEMBER, CONCRETE BOX BEAM, 21 IN. X 48 IN.	491.000	LFT
69	708-51814 WELDED STEEL WIRE FABRIC	100.000	SFT
70	709-51821 SURFACE SEAL	LUMP	LUMP
71	709-51821 SURFACE SEAL	LUMP	LUMP
72	711-51035 STRUCTURAL STEEL	120.000	LBS
73	715-05171 PIPE, TYPE 3 CIRCULAR 18 IN	58.000	LFT
74	715-05407 PIPE, END BENT DRAIN, 6 IN	232.000	LFT
75	715-46010 PIPE END SECTION, DIA 18"	2.000	EACH
76	801-04308 ROAD CLOSURE SIGN ASSEMBLY	12.000	EACH
77	801-06625 DETOUR ROUTE MARKER ASSEMBLY	28.000	EACH
78	801-06640 CONSTRUCTION SIGN, A	37.000	EACH
79	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
80	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
81	801-07118 BARRICADE, III-A	144.000	LFT
82	801-07119 BARRICADE, III-B	96.000	LFT
83	802-05704 SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	49.000	LFT
84	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	24.000	SFT
85	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	858.000	LFT
86	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	492.000	LFT
87	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	124.000	LFT
88	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	175.000	LFT

CALL ORDER : 510

CONTRACT ID : B -31714-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	674.000	SYS
13	202-02272 PAVED SIDE DITCH, REMOVE	82.000	LFT
14	202-02637 PIPE, ABANDON AND GROUT FILL	250.000	LFT
15	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
16	203-02000 EXCAVATION, COMMON	183.000	CYS
17	203-51223 EXCAVATION, WATERWAY	852.000	CYS
18	205-06933 TEMPORARY INLET PROTECTION	1.000	EACH
19	205-06937 TEMPORARY SILT FENCE	442.000	LFT
20	205-09543 NO 2 STONE	150.000	TON
21	206-93520 TEMPORARY SHEET PILING	720.000	SFT
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	95.000	SYS
23	207-09935 SUBGRADE TREATMENT, TYPE IC	1,720.000	SYS
24	211-09264 STRUCTURAL BACKFILL, TYPE 1	396.570	CYS
25	211-09265 STRUCTURAL BACKFILL, TYPE 2	208.000	CYS
26	211-09268 STRUCTURAL BACKFILL, TYPE 5	436.000	CYS
27	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	149.000	TON
28	306-08034 MILLING, ASPHALT, 1 1/2 IN	1,583.000	SYS
29	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	227.000	TON
30	401-07389 QC/QA-HMA, 1, 64, INTERMEDIATE, 19.0 mm	395.000	TON
31	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	204.000	TON
32	401-10258 JOINT ADHESIVE, SURFACE	1,945.000	LFT
33	401-10259 JOINT ADHESIVE, INTERMEDIATE	584.000	LFT
34	401-11785 LIQUID ASPHALT SEALANT	1,945.000	LFT
35	406-05520 ASPHALT FOR TACK COAT	3.000	TON
36	503-05240 D-1 CONTRACTION JOINT	11.000	LFT
37	601-01701 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 2	1.000	EACH
38	601-01846 GUARDRAIL, TERMINAL SYSTEM, W-BEAM, CURVED, 3	2.000	EACH
39	601-02241 GUARDRAIL, REMOVE	313.000	LFT
40	601-02800 GUARDRAIL TRANSITION, TGT	2.000	EACH
41	601-06854 GUARDRAIL, W-BEAM, NESTED	1.000	EACH
42	601-06856 MODIFIED POSTS, NESTED GUARDRAIL	2.000	EACH
43	601-94689 GUARDRAIL END TREATMENT, OS	1.000	EACH
44	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	107.000	LFT
45	610-07487 HMA FOR APPROACHES, TYPE B	26.000	TON
46	611-06497 MAILBOX ASSEMBLY, SINGLE	1.000	EACH
47	616-02320 GEOTEXTILES	892.000	SYS
48	616-06405 RIPRAP, REVETMENT	501.000	TON
49	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH

CALL ORDER : 510

CONTRACT ID : B -31714-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	1,000.000	SYS
51	621-06567 WATER	7.000	KGAL
52	621-06575 SODDING, NURSERY	1,905.000	SYS
53	628-09402 FIELD OFFICE, B	5.000	MOS
54	628-11729 CELLULAR TELEPHONE TYPE A	2.000	EACH
55	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
56	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
57	628-11781 CELLULAR TELEPHONE SERVICE, 750 MIN	10.000	MOS
58	701-06011 DYNAMIC PILE LOAD TEST	2.000	EACH
59	701-09557 TEST PILE, DYNAMIC, PRODUCTION	135.000	LFT
60	701-09559 TEST PILE, DYNAMIC, RESTRIKE	2.000	EACH
61	701-09739 PILE SHOE, HP 12 X 53	40.000	EACH
62	701-51195 PILE, STEEL H, HP 12 IN X 53	2,185.000	LFT
63	706-06347 RAILING, STEEL CF-1	30.000	LFT
64	706-08496 REINFORCED CONCRETE MOMENT SLAB, 12 IN	42.000	SYS
65	706-51020 RAILING, CONCRETE, C	2.000	CYS
66	715-01336 GATE VALVE, 12 IN	2.000	EACH
67	715-02889 SERVICE LINE 1"	5.000	LFT
68	715-04987 CONNECTION	1.000	EACH
69	715-04987 CONNECTION	2.000	EACH
70	715-05411 PIPE SANITARY SEWER 12 IN	186.500	LFT
71	715-05411 PIPE SANITARY SEWER 12 IN	40.000	LFT
72	715-05711 PIPE SANITARY SEWER 6 IN	10.000	LFT
73	715-92253 SEWER, SANITARY LATERAL, RECONNECT	1.000	EACH
74	715-97873 WATER SERVICE LINE, 1 IN	1.000	EACH
75	715-98165 WATER MAIN, 12 IN	302.000	LFT
76	720-45275 PIPE CATCH BASIN, 24 IN	1.000	EACH
77	720-91742 FIRE HYDRANT	1.000	EACH
78	723-11229 STRUCTURE, REINFORCED CONCRETE THREE-SIDED SECTIONS,	84.000	LFT
79	732-05538 TESTING AND DISINFECTION	LUMP	LUMP
80	801-01504 TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	1.000	EACH
81	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
82	801-06203 TEMPORARY PAVEMENT MARKING, 4 IN	6,439.000	LFT
83	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	4,515.000	LFT
84	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
85	801-06645 CONSTRUCTION SIGN, B	16.000	EACH
86	801-06710 FLASHING ARROW SIGN	180.000	DAY
87	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
88	801-07023 ENERGY ABSORBING TERMINAL, CZ, TL-2	2.000	EACH
89	801-07119 BARRICADE, III-B	84.000	LFT
90	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	300.000	LFT
91	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	2.000	EACH
92	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	13.000	LFT
93	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	7.000	SFT
94	808-06701 LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN	188.000	LFT
95	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	778.000	LFT
96	808-06716 LINE, REMOVE	6,717.000	LFT
97	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	778.000	LFT
98	808-75994 PRISMATIC REFLECTOR	80.000	EACH

CALL ORDER : 510

CONTRACT ID : B -31714-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
99 808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	20.000	EACH
100 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	20.000	EACH

CALL ORDER : 520

CONTRACT ID : B -31720-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 REPLACE SUPERSTRUCTURE			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	202-02240 PAVEMENT REMOVAL	127.000	SYS
11	202-02279 CURB AND GUTTER, REMOVE	1,720.000	LFT
12	202-02637 PIPE, ABANDON AND GROUT FILL	30.000	LFT
13	202-51133 RAILING, REMOVE	428.000	LFT
14	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
15	202-51368 SLOPEWALL, REMOVE	111.000	SYS
16	202-91385 INLET, REMOVE	6.000	EACH
17	203-02000 EXCAVATION, COMMON	1,339.000	CYS
18	205-09543 NO 2 STONE	50.000	TON
19	206-51225 EXCAVATION, DRY	32.000	CYS
20	207-09935 SUBGRADE TREATMENT, TYPE IC	2,724.000	SYS
21	211-06467 AGGREGATE FOR END BENT BACKFILL	32.000	CYS
22	213-09270 FLOWABLE BACKFILL, REMOVABLE	4.000	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	265.000	TON
24	302-06464 SUBBASE FOR PCCP	392.000	CYS
25	302-07455 DENSE GRADED SUBBASE	28.000	CYS
26	303-01180 COMPACTED AGGREGATE, NO. 53	866.000	TON
27	306-08043 MILLING, TRANSITION	210.000	SYS
28	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	140.000	TON
29	401-07337 QC/QA-HMA, 5, 76, SURFACE, 9.5 mm	107.000	TON
30	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	237.000	TON
31	401-07405 QC/QA-HMA, 5, 76, INTERMEDIATE, 19.0 mm	182.000	TON
32	401-07410 QC/QA-HMA, 5, 64, BASE, 25.0 mm	376.000	TON
33	401-10258 JOINT ADHESIVE, SURFACE	4,126.000	LFT
34	401-10259 JOINT ADHESIVE, INTERMEDIATE	4,126.000	LFT
35	401-11785 LIQUID ASPHALT SEALANT	4,126.000	LFT
36	406-05521 ASPHALT FOR TACK COAT	5,092.000	SYS
37	415-11527 BASE SEAL	1.000	TON
38	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
39	601-02241 GUARDRAIL, REMOVE	1,440.000	LFT
40	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
41	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	1,163.000	LFT
42	602-06729 BARRIER DELINEATOR	14.000	EACH
43	603-06060 FENCE, FARM FIELD, RESET	128.000	LFT
44	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	170.000	SYS
45	616-02320 GEOTEXTILES	398.000	SYS
46	616-06405 RIPRAP, REVETMENT	172.000	TON
47	616-51367 SLOPEWALL, CONCRETE, 4 IN	115.000	SYS
48	616-93772 INSPECTION HOLE	4.000	EACH
49	621-06574 SODDING	109.000	SYS

CALL ORDER : 520

CONTRACT ID : B -31720-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 REPLACE SUPERSTRUCTURE			
50	628-09401 FIELD OFFICE, A	8.000	MOS
51	628-11729 CELLULAR TELEPHONE TYPE A	2.000	EACH
52	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
53	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
54	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	16.000	MOS
55	702-51005 CONCRETE, A, SUBSTRUCTURE	96.900	CYS
56	702-51863 FIELD DRILLED HOLE IN CONCRETE	84.000	EACH
57	703-06028 REINFORCING BARS	9,534.000	LBS
58	703-06029 REINFORCING BARS, EPOXY COATED	71,203.000	LBS
59	704-51002 CONCRETE, C, SUPERSTRUCTURE	236.300	CYS
60	706-09960 RAILING, CONCRETE, FC	431.000	LFT
61	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH
62	709-51821 SURFACE SEAL	LUMP	LUMP
63	711-51038 STRUCTURAL STEEL	LUMP	LUMP
64	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	1,440.000	LFT
65	715-05053 PIPE, UNDERDRAIN, OUTLET 6 IN	40.000	LFT
66	715-05407 PIPE, END BENT DRAIN, 6 IN	90.000	LFT
67	718-06529 OUTLET PROTECTOR, 2	2.000	EACH
68	718-52610 AGGREGATE FOR UNDERDRAINS	146.000	CYS
69	718-99153 GEOTEXTILES FOR UNDERDRAIN	1,148.000	SYS
70	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
71	801-04308 ROAD CLOSURE SIGN ASSEMBLY	2.000	EACH
72	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	3,240.000	LFT
73	801-06640 CONSTRUCTION SIGN, A	20.000	EACH
74	801-06645 CONSTRUCTION SIGN, B	4.000	EACH
75	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
76	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	4.000	EACH
77	801-07118 BARRICADE, III-A	72.000	LFT
78	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	2,800.000	LFT
79	808-06716 LINE, REMOVE	1,800.000	LFT
80	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	360.000	LFT
81	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	3,514.000	LFT
82	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	3,514.000	LFT

CALL ORDER : 530

CONTRACT ID : B -33276-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	105-09645 CONSTRUCTION ENGINEERING AND INSPECTION,	LUMP	LUMP
3	109-08359 LIQUIDATED DAMAGES	1.000	DOL
4	109-08360 CONTRACT LIENS	1.000	DOL
5	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
6	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
7	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
8	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
9	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
10	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
11	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	956.500	SYS
13	202-51330 PRESENT STRUCTURE, REMOVE	LUMP	LUMP
14	203-02000 EXCAVATION, COMMON	3,091.000	CYS
15	205-03371 SEDIMENT, REMOVE	750.000	CYS
16	205-06930 SPLASHPAD	2.800	TON
17	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	34.000	TON
18	205-06933 TEMPORARY INLET PROTECTION	6.000	EACH
19	205-06934 TEMPORARY MULCH	0.600	TON
20	205-06936 TEMPORARY SEDIMENT TRAP	86.000	TON
21	205-06937 TEMPORARY SILT FENCE	1,259.000	LFT
22	205-06938 TEMPORARY SLOPE DRAIN	80.000	LFT
23	205-11586 TEMPORARY FILTER STONE	5.000	TON
24	206-51220 EXCAVATION, WET	261.000	CYS
25	207-08263 SUBGRADE TREATMENT, TYPE IA	2,150.000	SYS
26	211-06467 AGGREGATE FOR END BENT BACKFILL	76.000	CYS
27	211-09264 STRUCTURAL BACKFILL, TYPE 1	949.000	CYS
28	211-09266 STRUCTURAL BACKFILL, TYPE 3	1,682.000	CYS
29	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	479.000	TON
30	302-07455 DENSE GRADED SUBBASE	33.700	CYS
31	303-01180 COMPACTED AGGREGATE, NO. 53	355.000	TON
32	306-08042 MILLING, SCARIFICATION/PROFILE	715.000	SYS
33	306-08043 MILLING, TRANSITION	585.000	SYS
34	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	245.000	TON
35	401-07398 QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	258.000	TON
36	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	153.000	TON
37	401-10258 JOINT ADHESIVE, SURFACE	989.000	LFT
38	401-10259 JOINT ADHESIVE, INTERMEDIATE	280.000	LFT
39	401-11785 LIQUID ASPHALT SEALANT	989.000	LFT
40	406-05520 ASPHALT FOR TACK COAT	1.000	TON
41	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
42	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
43	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	431.300	LFT
44	602-06729 BARRIER DELINEATOR	12.000	EACH
45	604-07092 BED COURSE MATERIAL	136.600	TON
46	605-06145 CURB AND GUTTER, B, CONCRETE	525.000	LFT
47	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	200.000	SYS
48	615-06490 RIGHT OF WAY MARKER	12.000	EACH
49	616-02320 GEOTEXTILES	5,430.500	SYS

CALL ORDER : 530

CONTRACT ID : B -33276-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
50	616-05688 RIPRAP, CLASS 1	1,414.000	TON
51	616-06451 RIPRAP, UNIFORM	1,463.000	TON
52	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
53	621-02363 MULCHED SEEDING T, CONVENTIONAL MIX	1,778.000	SYS
54	621-02770 EROSION CONTROL BLANKET	410.000	SYS
55	621-06557 SEED MIXTURE, T	1.880	LBS
56	621-06559 MULCHED SEEDING, R	1,037.000	SYS
57	621-06565 MULCHING MATERIAL	2.100	TON
58	621-06574 SODDING	148.000	SYS
59	621-09400 SEED MIXTURE, SEDGE MEADOW	0.300	LBS
60	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	6.000	EACH
61	622-05648 PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN OR UNDER	12.000	EACH
62	622-52436 SIGN, DO NOT MOW OR SPRAY	6.000	EACH
63	628-09401 FIELD OFFICE, A	9.000	MOS
64	628-11729 CELLULAR TELEPHONE TYPE A	1.000	EACH
65	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
66	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
67	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	9.000	MOS
68	701-09739 PILE SHOE, HP 12 X 53	42.000	EACH
69	701-51195 PILE, STEEL H, HP 12 IN X 53	1,830.000	LFT
70	702-51005 CONCRETE, A, SUBSTRUCTURE	107.800	CYS
71	702-51015 CONCRETE, B, FOOTINGS	46.600	CYS
72	702-92857 CONCRETE, C, SUBSTRUCTURE	39.200	CYS
73	703-06028 REINFORCING BARS	35,590.000	LBS
74	703-06029 REINFORCING BARS, EPOXY COATED	98,839.000	LBS
75	704-51002 CONCRETE, C, SUPERSTRUCTURE	276.600	CYS
76	706-11600 RAILING, CONCRETE, FC	36.000	CYS
77	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH
78	707-05984 STRUCTURAL MEMBER, CONCRETE I-BEAM , 45 IN X 16 IN	1,110.000	LFT
79	709-51821 SURFACE SEAL	LUMP	LUMP
80	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	8.000	LFT
81	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	596.000	LFT
82	715-05407 PIPE, END BENT DRAIN, 6 IN	166.000	LFT
83	715-46020 PIPE END SECTION, DIA 24"	1.000	EACH
84	715-46040 PIPE END SECTION, DIA 36 IN	1.000	EACH
85	720-45030 INLET, E7	2.000	EACH
86	720-45042 INLET, HA5	6.000	EACH
87	720-45410 MANHOLE, C4	2.000	EACH
88	732-11811 MODULAR BLOCK WALL ERECTION	3,974.000	SFT
89	732-11812 MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	3,974.000	SFT
90	801-04308 ROAD CLOSURE SIGN ASSEMBLY	6.000	EACH
91	801-06625 DETOUR ROUTE MARKER ASSEMBLY	12.000	EACH
92	801-06640 CONSTRUCTION SIGN, A	9.000	EACH
93	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
94	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
95	801-07118 BARRICADE, III-A	48.000	LFT
96	801-07119 BARRICADE, III-B	96.000	LFT
97	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1,524.000	LFT
98	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	454.000	LFT

CALL ORDER : 530

CONTRACT ID : B -33276-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REPLACEMENT		
99 808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	454.000	LFT
100 808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,524.000	LFT
101 808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	12.000	EACH

CALL ORDER : 540

CONTRACT ID : B -34503-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK OVERLAY		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-02240 PAVEMENT REMOVAL	141.000	SYS
12	202-02272 PAVED SIDE DITCH, REMOVE	62.000	LFT
13	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
14	203-02000 EXCAVATION, COMMON	631.000	CYS
15	203-02070 BORROW	189.000	CYS
16	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	24.000	TON
17	205-06934 TEMPORARY MULCH	1.000	TON
18	205-06936 TEMPORARY SEDIMENT TRAP	172.000	TON
19	205-06937 TEMPORARY SILT FENCE	1,015.000	LFT
20	205-09543 NO 2 STONE	100.000	TON
21	207-08263 SUBGRADE TREATMENT, TYPE IA	1,757.000	SYS
22	207-08267 SUBGRADE TREATMENT, TYPE IIIA	74.000	SYS
23	211-09267 STRUCTURAL BACKFILL, TYPE 4	4.000	CYS
24	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	6.000	CYS
25	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	547.000	TON
26	302-07455 DENSE GRADED SUBBASE	38.000	CYS
27	306-08432 MILLING, APPROACH	53.000	SYS
28	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	133.000	TON
29	401-07390 QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	310.000	TON
30	401-10258 JOINT ADHESIVE, SURFACE	1,218.000	LFT
31	401-10259 JOINT ADHESIVE, INTERMEDIATE	1,218.000	LFT
32	401-11785 LIQUID ASPHALT SEALANT	1,218.000	LFT
33	406-05521 ASPHALT FOR TACK COAT	3,054.000	SYS
34	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
35	601-94689 GUARDRAIL END TREATMENT, OS	4.000	EACH
36	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	231.300	LFT
37	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	225.400	SYS
38	610-07487 HMA FOR APPROACHES, TYPE B	26.000	TON
39	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	1.000	EACH
40	615-06490 RIGHT OF WAY MARKER	15.000	EACH
41	615-06505 MONUMENT, B	3.000	EACH
42	616-02320 GEOTEXTILES	1,396.000	SYS
43	616-05688 RIPRAP, CLASS 1	842.000	TON
44	616-06405 RIPRAP, REVETMENT	112.000	TON
45	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.000	EACH
46	621-02770 EROSION CONTROL BLANKET	180.000	SYS
47	621-06557 SEED MIXTURE, T	48.000	LBS
48	621-06560 MULCHED SEEDING, U	180.000	SYS
49	621-06567 WATER	4.900	KGAL

CALL ORDER : 540

CONTRACT ID : B -34503-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE DECK OVERLAY		
50	621-06574 SODDING	205.000	SYS
51	621-06575 SODDING, NURSERY	1,149.000	SYS
52	628-09402 FIELD OFFICE, B	8.000	MOS
53	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	8.000	MOS
54	628-11729 CELLULAR TELEPHONE TYPE A	1.000	EACH
55	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
56	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
57	628-11780 CELLULAR TELEPHONE SERVICE 500 MIN	8.000	MOS
58	701-02938 CORED HOLE IN ROCK, 24 IN	6.000	LFT
59	701-09739 PILE SHOE, HP 12 X 53	4.000	EACH
60	701-51195 PILE, STEEL H, HP 12 IN X 53	68.000	LFT
61	701-97874 PILE, STEEL H, REINFORCED CONCRETE ENCASED, HP 12 IN X 53	70.000	LFT
62	702-51005 CONCRETE, A, SUBSTRUCTURE	7.200	CYS
63	702-51863 FIELD DRILLED HOLE IN CONCRETE	180.000	EACH
64	703-06029 REINFORCING BARS, EPOXY COATED	38,292.000	LBS
65	704-51002 CONCRETE, C, SUPERSTRUCTURE	78.200	CYS
66	706-06352 CONCRETE BRIDGE RAILING TRANSITION, TPF-2	4.000	EACH
67	706-09963 RAILING, CONCRETE, PF-2	183.200	LFT
68	706-11405 RAILING, STEEL, PF-2	200.500	LFT
69	709-51821 SURFACE SEAL	LUMP	LUMP
70	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	12.000	SFT
71	722-51842 BRIDGE DECK OVERLAY	377.000	SYS
72	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	11.000	CYS
73	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	115.000	SFT
74	722-51874 OVERLAY DAM	156.000	SFT
75	722-60824 SURFACE MILLING	215.000	SYS
76	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
77	801-04308 ROAD CLOSURE SIGN ASSEMBLY	8.000	EACH
78	801-06625 DETOUR ROUTE MARKER ASSEMBLY	9.000	EACH
79	801-06640 CONSTRUCTION SIGN, A	10.000	EACH
80	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
81	801-07118 BARRICADE, III-A	96.000	LFT
82	801-07119 BARRICADE, III-B	144.000	LFT
83	801-08403 TEMPORARY TRAFFIC BARRIER, TYPE 4	290.000	LFT
84	802-05705 SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	23.000	LFT
85	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	6.000	SFT
86	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2,011.000	LFT
87	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	290.000	LFT
88	808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN	37.000	LFT
89	808-75240 LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN	47.000	LFT
90	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	1,640.000	LFT

CALL ORDER : 550

CONTRACT ID : B -34853-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION OR REPAIR		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
9	202-01066 HYDRO DEMOLITION	992.000	SYS
10	202-02240 PAVEMENT REMOVAL	302.900	SYS
11	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
12	202-51822 BRIDGE DECK OVERLAY, REMOVE	992.000	SYS
13	302-07455 DENSE GRADED SUBBASE	50.000	CYS
14	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1.300	TON
15	401-07407 QC/QA-HMA, 2, 64, BASE, 25.0 mm	21.600	TON
16	601-01522 GUARDRAIL, TRANSITION TYPE TGB	4.000	EACH
17	601-02241 GUARDRAIL, REMOVE	320.000	LFT
18	601-99105 GUARDRAIL, W-BEAM, 6 FT 3 IN SPACING	200.000	LFT
19	602-06729 BARRIER DELINEATOR	12.000	EACH
20	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	300.000	SYS
21	628-09402 FIELD OFFICE, B	12.000	MOS
22	628-09407 FIELD OFFICE COMPUTER SYSTEM, ADDITIONAL	12.000	MOS
23	628-11730 CELLULAR TELEPHONE TYPE B	3.000	EACH
24	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
25	628-11780 CELLULAR TELEPHONE SERVICE 500 MIN	36.000	MOS
26	702-51005 CONCRETE, A, SUBSTRUCTURE	1.400	CYS
27	702-51863 FIELD DRILLED HOLE IN CONCRETE	8.000	EACH
28	703-06029 REINFORCING BARS, EPOXY COATED	41,167.000	LBS
29	703-97936 THREADED TIE BAR ASSEMBLY, EPOXY COATED	208.000	EACH
30	704-51002 CONCRETE, C, SUPERSTRUCTURE	92.900	CYS
31	706-09960 RAILING, CONCRETE, FC	357.000	LFT
32	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	4.000	EACH
33	707-09862 STRUCTURAL MEMBER, CONCRETE BOX BEAM, 27 IN X 48 IN	175.000	LFT
34	709-51821 SURFACE SEAL	LUMP	LUMP
35	715-09938 PIPE, BRIDGE DECK DRAIN SYSTEM	LUMP	LUMP
36	722-51401 BRIDGE DECK PATCHING, FULL DEPTH	270.100	SFT
37	722-51842 BRIDGE DECK OVERLAY	1,255.000	SYS
38	722-51846 BRIDGE DECK OVERLAY, ADDITIONAL	5.000	CYS
39	722-60824 SURFACE MILLING	992.000	SYS
40	727-90308 EPOXY INJECTION, CRACK PREPARATION	34.000	LFT
41	727-90309 EPOXY INJECTION, EPOXY MATERIAL	1.000	GAL
42	727-93560 EPOXY INJECTION, FURNISHING EQUIPMENT	LUMP	LUMP
43	801-03290 CONSTRUCTION SIGN, C	2.000	EACH
44	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	9,700.000	LFT
45	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
46	801-06645 CONSTRUCTION SIGN, B	2.000	EACH
47	801-06710 FLASHING ARROW SIGN	240.000	DAY
48	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
49	801-07024 ENERGY ABSORBING TERMINAL, CZ, TL-3	2.000	EACH

CALL ORDER : 550

CONTRACT ID : B -34853-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	BRIDGE REHABILITATION OR REPAIR		
50	801-08401 TEMPORARY TRAFFIC BARRIER, TYPE 2	680.000	LFT
51	801-08508 TEMPORARY TRAFFIC BARRIER, TYPE 2, ANCHORED	520.000	LFT
52	808-06716 LINE, REMOVE	2,845.000	LFT
53	808-10031 LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN	955.000	LFT
54	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	2,020.000	LFT
55	808-10034 LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN	1,200.000	LFT

CALL ORDER : 560

CONTRACT ID : B -35489-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 REPAIRS TO APPROACH SLAB			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-02240 PAVEMENT REMOVAL	295.000	SYS
9	202-07083 REMOVAL	LUMP	LUMP
10	202-07083 REMOVAL	LUMP	LUMP
11	202-07083 REMOVAL	LUMP	LUMP
12	202-07083 REMOVAL	LUMP	LUMP
13	202-51328 PRESENT STRUCTURE, REMOVE PORTIONS	LUMP	LUMP
14	213-08068 DRILLED HOLE FOR FLOWABLE BACKFILL	14.000	EACH
15	213-09269 FLOWABLE BACKFILL, NON-REMOVABLE	13.000	CYS
16	213-09270 FLOWABLE BACKFILL, REMOVABLE	50.000	CYS
17	302-07455 DENSE GRADED SUBBASE	48.000	CYS
18	503-05310 TERMINAL JOINT	170.000	LFT
19	503-09261 PCCP STITCHING	38.000	EACH
20	609-06259 REINFORCED CONCRETE BRIDGE APPROACH 12 IN	295.000	SYS
21	609-09940 APPROACH SLAB JACKING	188.000	SYS
22	628-09402 FIELD OFFICE, B	12.000	MOS
23	702-51863 FIELD DRILLED HOLE IN CONCRETE	94.000	EACH
24	703-06029 REINFORCING BARS, EPOXY COATED	10,335.000	LBS
25	706-11620 CONCRETE BRIDGE RAILING TRANSITION, TFC	2.000	EACH
26	709-51821 SURFACE SEAL	LUMP	LUMP
27	722-51852 BRIDGE DECK PATCHING, PARTIAL DEPTH	30.000	SFT
28	724-03276 STRUCTURAL EXPANSION JOINT SEALING SYS	586.000	LFT
29	724-09626 STRUCTURAL EXPANSION JOINT SEAL, SS, REPLACE	492.000	LFT
30	801-01093 TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.000	EACH
31	801-03290 CONSTRUCTION SIGN, C	15.000	EACH
32	801-06640 CONSTRUCTION SIGN, A	35.000	EACH
33	801-06710 FLASHING ARROW SIGN	60.000	DAY
34	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
35	801-08400 TEMPORARY TRAFFIC BARRIER, TYPE 1	6,820.000	LFT
36	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	8.000	EACH
37	801-92448 CONSTRUCTION SIGNS, MOBILE	60.000	DAY
38	808-10033 LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN	64.000	LFT
39	808-10054 LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN	55.000	LFT

CALL ORDER : 600

CONTRACT ID : M -31261-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
8 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 610

CONTRACT ID : M -31262-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 620

CONTRACT ID : M -31263-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
8 623-04887	MOWING, CYCLE NO 4	1.000	CYCL
9 623-05684	MOWING, CYCLE NO 5	1.000	CYCL
10 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 630

CONTRACT ID : M -35925-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	PATCH AND REHAB PAVEMENT		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	450.000	TON
8	304-07783 HMA PATCHING, TYPE D	1,945.000	TON
9	503-03489 RETROFITTED TIE BARS	100.000	EACH
10	503-05240 D-1 CONTRACTION JOINT	2,420.000	LFT
11	506-06333 PCCP PATCHING, FULL DEPTH	100.000	SYS
12	506-06333 PCCP PATCHING, FULL DEPTH	850.000	SYS
13	628-09402 FIELD OFFICE, B	12.000	MOS
14	628-09409 MOBILE INTERNET SERVICE	12.000	MOS
15	628-11729 CELLULAR TELEPHONE TYPE A	3.000	EACH
16	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
17	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
18	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	36.000	MOS
19	801-03290 CONSTRUCTION SIGN, C	12.000	EACH
20	801-06640 CONSTRUCTION SIGN, A	40.000	EACH
21	801-06710 FLASHING ARROW SIGN	360.000	DAY
22	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
23	801-11642 PORTABLE CHANGEABLE MESSAGE SIGN	6.000	EACH

CALL ORDER : 640

CONTRACT ID : M -35926-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 PATCH AND REHAB PAVEMENT			
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	202-90277 DETECTOR HOUSING, REMOVE	3.000	EACH
9	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	61.000	TON
10	302-06464 SUBBASE FOR PCCP	8.000	CYS
11	303-01180 COMPACTED AGGREGATE, NO. 53	10.000	TON
12	304-07783 HMA PATCHING, TYPE D	178.000	TON
13	306-08034 MILLING, ASPHALT, 1 1/2 IN	2,989.000	SYS
14	306-08042 MILLING, SCARIFICATION/PROFILE	12,721.000	SYS
15	401-06264 PROFILOGRAPH, HMA	LUMP	LUMP
16	401-07328 QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	249.000	TON
17	401-10258 JOINT ADHESIVE, SURFACE	5,403.000	LFT
18	401-11785 LIQUID ASPHALT SEALANT	5,403.000	LFT
19	406-05520 ASPHALT FOR TACK COAT	1.000	TON
20	414-11464 ULTRATHIN BONDED WEARING COURSE FOR	314.000	SYS
21	414-11468 ULTRATHIN BONDED WEARING COURSE, 9.5 mm	12,591.000	SYS
22	503-05240 D-1 CONTRACTION JOINT	60.000	LFT
23	506-06333 PCCP PATCHING, FULL DEPTH	161.000	SYS
24	506-06334 PCCP PATCHING, PARTIAL DEPTH	107.000	SYS
25	628-11729 CELLULAR TELEPHONE TYPE A	2.000	EACH
26	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
27	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
28	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	12.000	MOS
29	801-03290 CONSTRUCTION SIGN, C	17.000	EACH
30	801-06640 CONSTRUCTION SIGN, A	66.000	EACH
31	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
32	805-78470 SIGNAL CABLE, ROADWAY LOOP, COPPER 1C/14GA	950.000	LFT
33	805-78785 SIGNAL DETECTOR HOUSING	3.000	EACH
34	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	300.000	LFT
35	808-06702 LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN	275.000	LFT
36	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	5,975.000	LFT
37	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	4,055.000	LFT
38	808-75272 TRANSVERSE MARKING, THERMOPLASTIC,	89.000	LFT
39	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	123.000	LFT
40	808-75300 TRANSVERSE MARKING, THERMOPLASTIC,	281.000	LFT
41	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH
42	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	2.000	EACH
43	808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	91.000	EACH
44	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	91.000	EACH

CALL ORDER : 650

CONTRACT ID : M -35983-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MECHANICAL SWEEPING		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	623-93708 SWEEPING	LUMP	LUMP
4	623-93708 SWEEPING	LUMP	LUMP
5	623-93708 SWEEPING	LUMP	LUMP
6	623-93708 SWEEPING	LUMP	LUMP
7	623-93708 SWEEPING	LUMP	LUMP
8	623-93708 SWEEPING	LUMP	LUMP
9	623-93708 SWEEPING	LUMP	LUMP
10	623-93708 SWEEPING	LUMP	LUMP
11	623-93708 SWEEPING	LUMP	LUMP
12	623-93708 SWEEPING	LUMP	LUMP
13	623-93708 SWEEPING	LUMP	LUMP

CALL ORDER : 660

CONTRACT ID : M -36449-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 670

CONTRACT ID : M -36450-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROAD MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 680

CONTRACT ID : M -36754-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO 2	1.000	CYCL

CALL ORDER : 690

CONTRACT ID : M -36755-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO 2	1.000	CYCL

CALL ORDER : 700

CONTRACT ID : M -36756-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO 2	1.000	CYCL

CALL ORDER : 710

CONTRACT ID : M -36757-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	202-04486 LITTER, REMOVE	25.000	MILE
4	202-04486 LITTER, REMOVE	25.000	MILE
5	202-04486 LITTER, REMOVE	25.000	MILE
6	202-04486 LITTER, REMOVE	25.000	MILE
7	623-04884 MOWING, CYCLE NO 1	1.000	CYCL
8	623-04885 MOWING, CYCLE NO 2	1.000	CYCL
9	623-04886 MOWING, CYCLE NO 3	1.000	CYCL
10	623-04887 MOWING, CYCLE NO 4	1.000	CYCL

CALL ORDER : 720

CONTRACT ID : M -36758-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO 2	1.000	CYCL

CALL ORDER : 730

CONTRACT ID : M -36759-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO 2	1.000	CYCL

CALL ORDER : 740

CONTRACT ID : M -36783-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 628-11730	CELLULAR TELEPHONE TYPE B	1.000	EACH
8 628-11732	CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
9 628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN	5.000	MOS
10 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 750

CONTRACT ID : M -36784-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
5 628-11730	CELLULAR TELEPHONE TYPE B	1.000	EACH
6 628-11731	CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
7 628-11732	CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
8 628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN	8.000	MOS
9 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 760

CONTRACT ID : M -36785-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 628-11730	CELLULAR TELEPHONE TYPE B	1.000	EACH
8 628-11732	CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
9 628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN	6.000	MOS
10 801-03290	CONSTRUCTION SIGN, C	4.000	EACH
11 801-06640	CONSTRUCTION SIGN, A	8.000	EACH
12 801-06710	FLASHING ARROW SIGN	5.000	DAY
13 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 770

CONTRACT ID : M -36786-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	623-04884 MOWING, CYCLE NO 1	1.000	CYCL
6	623-04885 MOWING, CYCLE NO 2	1.000	CYCL
7	628-11730 CELLULAR TELEPHONE TYPE B	1.000	EACH
8	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
9	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	6.000	MOS
10	801-03290 CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 780

CONTRACT ID : M -36787-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, HERBICED TREATMENT		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 624-92647	HERBICIDE TREATMENT	1,000.000	ACRE
6 628-11730	CELLULAR TELEPHONE TYPE B	1.000	EACH
7 628-11732	CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
8 628-11780	CELLULAR TELEPHONE SERVICE 500 MIN	1.000	MOS
9 801-06775	MAINTAINING TRAFFIC	LUMP	LUMP

CALL ORDER : 790

CONTRACT ID : M -36875-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 800

CONTRACT ID : M -36878-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
8 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 810

CONTRACT ID : M -36879-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 820

CONTRACT ID : M -36880-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4 109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
6 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
7 801-03290	CONSTRUCTION SIGN, C	4.000	EACH

CALL ORDER : 830

CONTRACT ID : M -36936-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO 2	1.000	CYCL

CALL ORDER : 840

CONTRACT ID : M -36937-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO 2	1.000	CYCL

CALL ORDER : 850

CONTRACT ID : M -36938-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	ROADSIDE MAINTENANCE, MOWING		
1 109-08359	LIQUIDATED DAMAGES	1.000	DOL
2 109-08360	CONTRACT LIENS	1.000	DOL
3 623-04884	MOWING, CYCLE NO 1	1.000	CYCL
4 623-04885	MOWING, CYCLE NO 2	1.000	CYCL
5 623-04886	MOWING, CYCLE NO 3	1.000	CYCL
6 623-06922	MOWING	9.000	CYCL

CALL ORDER : 880

CONTRACT ID : T -34380-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	TRAFFIC SIGNAL MODERNIZATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	109-08463 PROJECT ESTIMATE ADJUSTMENT	1.000	DOL
7	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
8	616-93772 INSPECTION HOLE	18.000	EACH
9	628-09402 FIELD OFFICE, B	7.000	MOS
10	801-06640 CONSTRUCTION SIGN, A	12.000	EACH
11	801-06645 CONSTRUCTION SIGN, B	12.000	EACH
12	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
13	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
14	805-01842 HANDHOLE, SIGNAL, TYPE 1	41.000	EACH
15	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN	7,200.000	LFT
16	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
17	805-02150 PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN	24.000	EACH
18	805-07842 VEHICLE DETECTION SYSTEM	1.000	EACH
19	805-07842 VEHICLE DETECTION SYSTEM	1.000	EACH
20	805-07842 VEHICLE DETECTION SYSTEM	1.000	EACH
21	805-09539 LOOP DETECTOR DELAY COUNTING AMPLIFIER, 2 CHANNEL	59.000	EACH
22	805-09540 LOOP DETECTOR RACK	20.000	EACH
23	805-78370 PEDESTRIAN PUSH BUTTON, NON-APS	24.000	EACH
24	805-78470 SIGNAL CABLE, ROADWAY LOOP, COPPER 1C/14GA	28,000.000	LFT
25	805-78510 SIGNAL CABLE, DETECTOR LEAD-IN COPPER 2C/16GA	22,000.000	LFT
26	805-78785 SIGNAL DETECTOR HOUSING	82.000	EACH
27	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	9,200.000	LFT
28	805-92504 LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	10.000	EACH

CALL ORDER : 890

CONTRACT ID : T -34741-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT WITH ADDED TURN LANES		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08440 QUALITY ADJUSTMENTS, HMA	1.000	DOL
5	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
6	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
7	109-09489 PAYMENT ADJUSTMENT, PG ASPHALT BINDER	1.000	DOL
8	109-11362 QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION	1.000	DOL
9	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
10	201-52370 CLEARING RIGHT OF WAY	LUMP	LUMP
11	202-01000 STRUCTURES AND OBSTRUCTIONS, REMOVE	LUMP	LUMP
12	202-02240 PAVEMENT REMOVAL	230.000	SYS
13	203-02000 EXCAVATION, COMMON	3,054.000	CYS
14	205-06931 TEMPORARY CHECK DAM, REVETMENT RIPRAP	45.000	TON
15	205-06933 TEMPORARY INLET PROTECTION	5.000	EACH
16	205-06937 TEMPORARY SILT FENCE	824.000	LFT
17	205-09543 NO 2 STONE	30.000	TON
18	207-08263 SUBGRADE TREATMENT, TYPE IA	2,233.000	SYS
19	207-08267 SUBGRADE TREATMENT, TYPE IIIA	6,051.000	SYS
20	207-09895 SUBGRADE TREATMENT, TYPE V	367.000	SYS
21	211-09264 STRUCTURAL BACKFILL, TYPE 1	612.000	CYS
22	211-09264 STRUCTURAL BACKFILL, TYPE 1	190.000	CYS
23	301-07448 COMPACTED AGGREGATE, NO. 53, BASE	123.000	TON
24	303-01180 COMPACTED AGGREGATE, NO. 53	87.000	TON
25	304-07491 HMA PATCHING, TYPE C	34.000	TON
26	304-07494 WIDENING WITH HMA, TYPE C	42.000	TON
27	306-08034 MILLING, ASPHALT, 1 1/2 IN	155.000	SYS
28	401-07321 QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	26.000	TON
29	401-07347 QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	409.000	TON
30	401-07357 QC/QA-HMA, 3, 64, INTERMEDIATE, 9.5 mm	24.000	TON
31	401-07371 QC/QA-HMA, 2, 64, INTERMEDIATE, 12.5 mm	41.000	TON
32	401-07392 QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	531.000	TON
33	401-07408 QC/QA-HMA, 3, 64, BASE, 25.0 mm	274.000	TON
34	401-07424 QC/QA-HMA, 3, 64, BASE, 19.0 mm	736.000	TON
35	401-07429 QC/QA-HMA, 5, 76, INTERMEDIATE, OG, 19.0 mm	562.000	TON
36	401-10258 JOINT ADHESIVE, SURFACE	1,465.000	LFT
37	401-10259 JOINT ADHESIVE, INTERMEDIATE	1,115.000	LFT
38	401-11785 LIQUID ASPHALT SEALANT	1,465.000	LFT
39	402-10086 HMA FOR TEMPORARY PAVEMENT, C	625.000	TON
40	406-05520 ASPHALT FOR TACK COAT	5.000	TON
41	502-11564 PCCP, 7 IN	605.000	SYS
42	604-07897 CURB RAMP, CONCRETE, C	62.000	SYS
43	604-07904 CURB RAMP, CONCRETE, L	28.000	SYS
44	605-06120 CURB, CONCRETE	782.000	LFT
45	605-06140 CURB AND GUTTER, CONCRETE	2,416.000	LFT
46	605-06215 CENTER CURB, D, CONCRETE	186.000	LFT
47	605-06240 CENTER CURB, A, CONCRETE	10.000	SYS
48	605-06255 CENTER CURB, D, CONCRETE	17.000	SYS
49	605-08636 CURB AND GUTTER, TURNOUT, COMBINED	20.000	LFT

CALL ORDER : 890

CONTRACT ID : T -34741-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	INTERSECTION IMPROVEMENT WITH ADDED TURN LANES		
50	605-97937 CURB AND GUTTER, ROLL CURB	343.000	LFT
51	610-07487 HMA FOR APPROACHES, TYPE B	46.000	TON
52	610-08446 PCCP FOR APPROACHES, 6 IN	112.000	SYS
53	610-09108 PCCP FOR APPROACHES, 9 IN	534.000	SYS
54	611-08232 MAILBOX ASSEMBLY, SINGLE, RESET	2.000	EACH
55	615-06505 MONUMENT, B	10.000	EACH
56	615-06510 MONUMENT, C	1.000	EACH
57	615-06527 MONUMENT, SECTION CORNER	1.000	EACH
58	616-02320 GEOTEXTILES	126.000	SYS
59	616-06405 RIPRAP, REVETMENT	19.000	TON
60	621-01004 MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.000	EACH
61	621-02770 EROSION CONTROL BLANKET	280.000	SYS
62	621-04316 SPADE EDGE	399.000	LFT
63	621-06560 MULCHED SEEDING, U	5,530.000	SYS
64	621-06570 TOPSOIL	163.000	CYS
65	621-06575 SODDING, NURSERY	494.000	SYS
66	621-90853 TAPPING SLEEVE WITH VALVE	1.000	EACH
67	621-98038 MULCH, HARDWOOD SHREDDED BARK	54.000	CYS
68	622-05639 PLANT, DECIDUOUS SHRUB, 18 TO 24 IN	41.000	EACH
69	622-05640 PLANT, DECIDUOUS SHRUB, 24 TO 36 IN	5.000	EACH
70	622-05642 PLANT, DECIDUOUS SHRUB, OVER 48 IN	1.000	EACH
71	622-05653 PLANT, GROUND COVER	164.000	EACH
72	622-05653 PLANT, GROUND COVER	18.000	EACH
73	622-05654 PLANT, PERENNIAL	19.000	EACH
74	622-05654 PLANT, PERENNIAL	108.000	EACH
75	622-06573 IRRIGATION	3.000	EACH
76	628-09401 FIELD OFFICE, A	6.000	MOS
77	715-02745 GATE VALVE WITH VALVE BOXES, 8 IN	1.000	EACH
78	715-03476 SAFETY METAL END SECTION 4:1 DIA 24"	1.000	EACH
79	715-05048 PIPE, TYPE 4 CIRCULAR 6 IN	2,322.000	LFT
80	715-05149 PIPE, TYPE 2 CIRCULAR 12 IN	589.000	LFT
81	715-05151 PIPE, TYPE 2 CIRCULAR 15 IN	507.000	LFT
82	715-05152 PIPE, TYPE 2 CIRCULAR 18 IN	103.000	LFT
83	715-05154 PIPE, TYPE 2 CIRCULAR 24 IN	44.000	LFT
84	715-08306 HMA FOR STRUCTURE INSTALLATION, TYPE C	26.000	TON
85	715-11571 WATER MAIN, DUCTILE IRON 8 IN	232.000	LFT
86	715-46020 PIPE END SECTION, DIA 24"	1.000	EACH
87	715-93403 WATER SERVICE CONNECTION, 0.75 IN.	3.000	EACH
88	715-94064 WATER LINE, COPPER, 0.75 IN	190.000	LFT
89	715-94780 WATER MAIN, DUCTILE IRON, 6 IN	8.000	LFT
90	718-06531 OUTLET PROTECTOR, 3	1.000	EACH
91	718-52610 AGGREGATE FOR UNDERDRAINS	171.000	CYS
92	718-99153 GEOTEXTILES FOR UNDERDRAIN	2,128.000	SYS
93	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
94	720-45005 INLET, A2	1.000	EACH
95	720-45030 INLET, E7	3.000	EACH
96	720-45035 INLET, F7	2.000	EACH
97	720-45410 MANHOLE, C4	4.000	EACH
98	720-91742 FIRE HYDRANT	1.000	EACH

CALL ORDER : 890

CONTRACT ID : T -34741-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES			
99	720-91742 FIRE HYDRANT	1.000	EACH
100	720-96999 FIRE HYDRANT ASSEMBLY	1.000	EACH
101	720-98174 INLET, B15	5.000	EACH
102	720-98555 INLET, C15	9.000	EACH
103	801-04308 ROAD CLOSURE SIGN ASSEMBLY	5.000	EACH
104	801-06207 TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN	3,363.000	LFT
105	801-06216 TEMPORARY TRANSVERSE PAVEMENT MARKING 24"	155.000	LFT
106	801-06625 DETOUR ROUTE MARKER ASSEMBLY	31.000	EACH
107	801-06640 CONSTRUCTION SIGN, A	53.000	EACH
108	801-06645 CONSTRUCTION SIGN, B	10.000	EACH
109	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
110	801-07119 BARRICADE, III-B	870.000	LFT
111	802-03776 SIGN POST, WOOD, 6 IN X 6 IN	77.000	LFT
112	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	285.000	LFT
113	802-05702 SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	56.000	LFT
114	802-07060 SIGN, SHEET, RELOCATE	12.000	EACH
115	802-09837 SIGN, DOUBLE-FACED, SHEET, WITH LEGEND 0.080 IN THICKNESS	5.000	SFT
116	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	246.000	SFT
117	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	60.000	SFT
118	805-08214 CONDUIT, PVC, 2 IN, SCHEDULE 40	331.000	LFT
119	807-02191 HANDHOLE, LIGHTING	6.000	EACH
120	807-02193 LIGHT STANDARD FOUNDATION, 3FT DIAMETER X 8FT	7.000	EACH
121	807-04866 LUMINAIRE,	7.000	EACH
122	807-07580 WIRE, NO 4 COPPER, IN PLASTIC DUCT, IN TRENCH 4 1/C	613.000	LFT
123	807-11425 LIGHT POLE, ROADWAY, 25 FT. EMH, 8 FT. MAST ARM,	7.000	EACH
124	807-86805 SERVICE POINT, I	1.000	EACH
125	807-86889 CABLE, POLE CIRCUIT THWN, NO 10 COPPER, STRANDED, 1/C	280.000	LFT
126	807-86910 CONNECTOR KIT, UNFUSED	7.000	EACH
127	807-86915 CONNECTOR KIT, FUSED	7.000	EACH
128	807-86920 MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	9.000	EACH
129	807-86925 MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.000	EACH
130	807-86930 INSULATION LINK, NON-WATERPROOFED	14.000	EACH
131	807-86935 INSULATION LINK, WATERPROOFED	24.000	EACH
132	807-97237 WIRE, NO 4 COPPER, IN PLASTIC DUCT, 4 1/C	241.000	LFT
133	807-99338 WIRE, NO 6 COPPER, GROUND, 1/C	210.000	LFT
134	808-03439 TRANSVERSE MARKING THERMOPLASTIC	204.000	LFT
135	808-06703 LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	570.000	LFT
136	808-06716 LINE, REMOVE	400.000	LFT
137	808-09083 LINE THERMOPLASTIC BROKEN WHITE 8 IN	192.000	LFT
138	808-10118 TRANSVERSE MARKING, THERMOPLASTIC, YIELD, WHITE,	80.000	LFT
139	808-75043 LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN	346.000	LFT
140	808-75054 LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN	133.000	LFT
141	808-75067 TRANSVERSE MARKING, PREFORMED PLASTIC,	31.000	LFT
142	808-75071 PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC,	1.000	EACH
143	808-75245 LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN	4,687.000	LFT
144	808-75278 TRANSVERSE MARKING, THERMOPLASTIC,	61.000	LFT
145	808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER	27.000	EACH

CALL ORDER : 910

CONTRACT ID : T -36007-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001	NEW SIGNAL INSTALLATION		
1	105-06845 CONSTRUCTION ENGINEERING	LUMP	LUMP
2	109-08359 LIQUIDATED DAMAGES	1.000	DOL
3	109-08360 CONTRACT LIENS	1.000	DOL
4	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
5	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
6	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
7	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
8	801-06640 CONSTRUCTION SIGN, A	16.000	EACH
9	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
10	802-05701 SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	13.000	LFT
11	802-09838 SIGN, SHEET, WITH LEGEND 0.080"	30.000	SFT
12	802-09840 SIGN, SHEET, WITH LEGEND 0.100 IN	13.500	SFT
13	802-09842 SIGN, SHEET, WITH LEGEND 0.125 IN THICKNESS	10.000	SFT
14	805-01300 TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.000	EACH
15	805-01842 HANDHOLE, SIGNAL, TYPE 1	1.000	EACH
16	805-02087 TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	LUMP	LUMP
17	805-08214 CONDUIT, PVC, 2 IN, SCHEDULE 40	50.000	LFT
18	805-09366 SIGNAL SUPPORT FOUNDATION, 36 IN DIAMETER X 120 IN	2.000	EACH
19	805-09845 CONTACT CLOSURE CARD	1.000	EACH
20	805-09846 RECEIVER PROCESSOR	2.000	EACH
21	805-10107 WIRELESS MAGNETOMETER DETECTOR TYPE	40.000	EACH
22	805-10108 WIRELESS REPEATER	2.000	EACH
23	805-78100 CONTROLLER AND CABINET, MENU DRIVEN, 8 PHASE	1.000	EACH
24	805-78205 TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN	7.000	EACH
25	805-78225 TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN	1.000	EACH
26	805-78415 SPAN, CATENARY, AND TETHER	4.000	EACH
27	805-78420 DISCONNECT HANGER	4.000	EACH
28	805-78445 SIGNAL SERVICE	1.000	EACH
29	805-78467 SIGNAL CABLE, SERVICE, COPPER. 3C/8GA	50.000	LFT
30	805-78485 SIGNAL CABLE, CONTROL, COPPER 5C/14GA	195.000	LFT
31	805-78490 SIGNAL CABLE, CONTROL, COPPER 7C/14GA	700.000	LFT
32	805-78495 SIGNAL CABLE CONTROL, COPPER 9C/14GA	200.000	LFT
33	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
34	805-81060 SIGNAL STRAIN POLE, STEEL, 36 FT	4.000	EACH
35	808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN	400.000	LFT
36	808-75056 TRANSVERSE MARKING, PAINT,	245.000	LFT
37	808-75060 TRANSVERSE MARKING, PAINT,	80.000	LFT
38	808-75297 TRANSVERSE MARKING, THERMOPLASTIC,	160.000	LFT
39	808-75320 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	4.000	EACH
40	808-75325 PAVEMENT MESSAGE MARKING, THERMOPLASTIC,	3.000	EACH

CALL ORDER : 920

CONTRACT ID : TM-36752-A

ITEM NO.	DESCRIPTION	QUANTITY	UNITS
SECTION NO. 0001 TRAFFIC SIGNAL MAINTENANCE			
1	109-08359 LIQUIDATED DAMAGES	1.000	DOL
2	109-08360 CONTRACT LIENS	1.000	DOL
3	109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.000	DOL
4	109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS	1.000	DOL
5	110-01001 MOBILIZATION AND DEMOBILIZATION	LUMP	LUMP
6	604-06070 SIDEWALK, CONCRETE	8.000	SYS
7	628-09408 MOBILE LAPTOP COMPUTER SYSTEM	12.000	MOS
8	628-09409 MOBILE INTERNET SERVICE	12.000	MOS
9	628-11729 CELLULAR TELEPHONE TYPE A	1.000	EACH
10	628-11731 CELLULAR TELEPHONE ADDITIONAL DATA	1.000	DOL
11	628-11732 CELLULAR TELEPHONE ADDITIONAL MINUTES	1.000	DOL
12	628-11782 CELLULAR TELEPHONE SERVICE, 1000 MIN	12.000	MOS
13	720-44000 CASTING, ADJUST TO GRADE	5.000	EACH
14	801-03290 CONSTRUCTION SIGN, C	4.000	EACH
15	801-06775 MAINTAINING TRAFFIC	LUMP	LUMP
16	805-01815 SIGNAL POLE FOUNDATION, 36 IN X 144 IN	1.000	EACH
17	805-01816 SIGNAL SUPPORT FOUNDATION, 36 IN X 36 IN X 96 IN	1.000	EACH
18	805-01842 HANDHOLE, SIGNAL, TYPE 1	5.000	EACH
19	805-01844 CONDUIT, STEEL, GALVANIZED, 2 IN	380.000	LFT
20	805-02645 SIGNAL PEDESTAL FOUNDATION, A	1.000	EACH
21	805-06364 FIBER OPTIC BREAKOUT KIT	6.000	EACH
22	805-78470 SIGNAL CABLE, ROADWAY LOOP, COPPER 1C/14GA	6,000.000	LFT
23	805-78510 SIGNAL CABLE, DETECTOR LEAD-IN COPPER 2C/16GA	500.000	LFT
24	805-78785 SIGNAL DETECTOR HOUSING	5.000	EACH
25	805-78795 SAW CUT FOR ROADWAY LOOP AND SEALANT	3,000.000	LFT
26	805-78925 CONTROLLER CABINET FOUNDATION, P1	1.000	EACH
27	805-91706 ANCHOR BOLT, REPAIR	2.000	EACH
28	807-08621 LOCATE UNDERGROUND LIGHTING FACILITIES	20.000	EACH
29	809-94971 FIBER OPTIC CABLE	9,000.000	LFT