

Schedule of Pay Items Letting Date April 11, 2018 Letting ID 180411

Call: 111

Contract: R -30582-A

Section No.: 1 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-91385	INLET, REMOVE	4.00	EACH
0012	202-93995	SIGNAL POLE FOUNDATION, REMOVE	2.00	EACH
0013	202-96133	PIPE, REMOVE	445.00	LFT
0014	203-02000	EXCAVATION, COMMON	6750.00	CYS
0015	205-11626	PUMP AROUND	2.00	EACH
0016	205-12108	STORM WATER MANAGEMENT BUDGET	18700.00	DOL
0017	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0018	207-08264	SUBGRADE TREATMENT, TYPE II	2758.00	SYS
0019	207-09934	SUBGRADE TREATMENT, TYPE IB	5087.00	SYS
0020	211-02050	B BORROW	125.00	CYS
0021	211-09264	STRUCTURE BACKFILL, TYPE 1	194.00	CYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	101.00	CYS
0023	211-09268	STRUCTURE BACKFILL, TYPE 5	108.00	CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	1797.00	TON
0025	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	95.00	TON
0026	304-07493	WIDENING WITH HMA, TYPE B	78.00	TON
0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	2011.00	SYS
0028	401-06264	PROFILOGRAPH, HMA	1.00	LS
0029	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	493.00	TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	740.00	TON
0031	401-10258	JOINT ADHESIVE, SURFACE	2925.00	LFT
0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	2344.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	1287.00	LFT
0034	402-07451	HMA WEDGE AND LEVEL, TYPE B	113.00	TON
0035	402-10084	HMA FOR TEMPORARY PAVEMENT, B	404.00	TON
0036	406-05520	ASPHALT FOR TACK COAT	1.40	TON

0037	601-02241	GUARDRAIL, REMOVE	200.00	LFT
0038	601-06035	GUARDRAIL, RESET	25.00	LFT
0039	601-06854	GUARDRAIL, W-BEAM, NESTED	2.00	EACH
0040	610-07487	HMA FOR APPROACHES, TYPE B	169.00	TON
0041	611-06497	MAILBOX ASSEMBLY, SINGLE	6.00	EACH
0042	611-06498	MAILBOX ASSEMBLY, DOUBLE	2.00	EACH
0043	615-06490	RIGHT-OF-WAY MARKER	17.00	EACH
0044	615-06505	MONUMENT, B	6.00	EACH
0045	616-05688	RIPRAP, CLASS 1	60.00	TON
0046	616-06405	RIPRAP, REVETMENT	304.00	TON
0047	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	574.00	SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0049	621-06545	FERTILIZER	2.00	TON
0050	621-06553	SEED MIXTURE R	700.00	LBS
0051	621-06565	MULCHING MATERIAL	7.00	TON
0052	621-06567	WATER	3.00	KGAL
0053	621-06574	SODDING	681.00	SYS
0054	628-09402	FIELD OFFICE, B	12.00	MOS
0055	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0056	713-04509	TEMPORARY PIPE	1.00	LS
0057	714-11635	STRUCTURE, COATED REINFORCED CONCRETE BOX SECTIONS, 12 FT X 5 FT	45.00	LFT
0058	715-03475	SAFETY METAL END SECTION, 4:1, DIA 15 IN.	4.00	EACH
0059	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	64.00	LFT
0060	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	67.00	LFT
0061	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	138.00	LFT
0062	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	100.00	LFT
0063	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0064	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	EACH
0065	715-46040	PIPE END SECTION, DIAMETER 36 IN.	2.00	EACH
0066	720-02442	PIPE PLUG EXISTING	2.00	EACH
0067	720-45030	INLET, E7	2.00	EACH
0068	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	15525.00	LFT
0069	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	170.00	LFT
0070	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	120.00	LFT
0071	801-06640	CONSTRUCTION SIGN, A	22.00	EACH
0072	801-06645	CONSTRUCTION SIGN, B	16.00	EACH
0073	801-06775	MAINTAINING TRAFFIC	1.00	LS
0074	801-07118	BARRICADE, III-A	44.00	LFT
0075	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	200.00	LFT
0076	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	450.00	LFT
0077	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0078	801-12081	PORTABLE SIGNAL	1.00	LS
0079	801-12081	PORTABLE SIGNAL	1.00	LS

0080	801-97643	TEMPORARY BUZZ STRIPS	504.00	LFT
0081	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	79.00	LFT
0082	802-05703	SIGN POST, SQUARE TYPE 3 REINFORCED ANCHOR BASE	19.00	LFT
0083	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	10.00	EACH
0084	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	3.00	SFT
0085	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	8.00	SFT
0086	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	36.00	SFT
0087	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	23.50	SFT
0088	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0089	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	4715.00	LFT
0090	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	4000.00	LFT
0091	808-06716	LINE, REMOVE	3740.00	LFT
0092	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	2.00	EACH
0093	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	61.00	LFT
0094	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	45.00	EACH
0095	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	45.00	EACH

Call: 131

Contract: R -33905-A

Section No.: 1 ADDED AUXILLIARY LANES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	562.00	SYS
0014	202-52710	SIDEWALK CONCRETE, REMOVE	10.00	SYS
0015	203-02000	EXCAVATION, COMMON	1555.00	CYS
0016	203-02070	BORROW	505.00	CYS
0017	205-12108	STORM WATER MANAGEMENT BUDGET	7550.00	DOL
0018	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	178.00	SYS
0020	207-08265	SUBGRADE TREATMENT, TYPE IIA	1000.00	SYS
0021	207-09934	SUBGRADE TREATMENT, TYPE IB	2025.00	SYS

0022	207-09935	SUBGRADE TREATMENT, TYPE IC	305.00	SYS
0023	211-02050	B BORROW	80.00	CYS
0024	211-09266	STRUCTURE BACKFILL, TYPE 3	52.00	CYS
0025	302-07455	DENSE GRADED SUBBASE	50.00	CYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	948.00	TON
0027	303-07449	COMPACTED AGGREGATE NO. 73	28.00	TON
0028	303-07449	COMPACTED AGGREGATE NO. 73	660.00	TON
0029	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	15.00	TON
0030	304-07490	HMA PATCHING, TYPE B	85.00	TON
0031	304-07493	WIDENING WITH HMA, TYPE B	285.00	TON
0032	306-08034	MILLING, ASPHALT, 1 1/2 IN.	43870.00	SYS
0033	306-08042	MILLING, SCARIFICATION	7822.00	SYS
0034	306-08432	MILLING, APPROACH	4040.00	SYS
0035	401-06264	PROFILOGRAPH, HMA	1.00	LS
0036	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	3620.00	TON
0037	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	649.00	TON
0038	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	868.00	TON
0039	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	599.00	TON
0040	401-10258	JOINT ADHESIVE, SURFACE	22570.00	LFT
0041	401-10259	JOINT ADHESIVE, INTERMEDIATE	2120.00	LFT
0042	401-11785	LIQUID ASPHALT SEALANT	22570.00	LFT
0043	406-05520	ASPHALT FOR TACK COAT	16.50	TON
0044	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	13.00	TON
0045	503-03489	RETROFITTED TIE BARS	72.00	EACH
0046	503-05240	D-1 CONTRACTION JOINT	112.00	LFT
0047	506-06333	PCCP PATCHING, FULL DEPTH	305.00	SYS
0048	604-08086	CURB RAMP, CONCRETE	5.00	SYS
0049	604-12083	DETECTABLE WARNING SURFACES	1.00	SYS
0050	606-07484	MILLED HMA CORRUGATIONS	7640.00	LFT
0051	610-07487	HMA FOR APPROACHES, TYPE B	366.00	TON
0052	611-08232	MAILBOX ASSEMBLY, SINGLE RESET	3.00	EACH
0053	615-01469	MONUMENT SECTION CORNER INSTALL	3.00	EACH
0054	615-06490	RIGHT-OF-WAY MARKER	18.00	EACH
0055	615-06500	MONUMENT, A	2.00	EACH
0056	615-06505	MONUMENT, B	15.00	EACH
0057	616-06405	RIPRAP, REVETMENT	135.00	TON
0058	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	331.00	SYS
0059	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0060	621-06545	FERTILIZER	1.00	TON
0061	621-06553	SEED MIXTURE R	69.00	LBS
0062	621-06565	MULCHING MATERIAL	1.00	TON
0063	621-06567	WATER	5.00	kGAL
0064	621-06575	SODDING, NURSERY	1143.00	SYS

0065	628-09402	FIELD OFFICE, B	6.00	MOS
0066	628-11729	CELLULAR TELEPHONE, TYPE A	2.00	EACH
0067	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0068	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0069	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	12.00	MOS
0070	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0071	732-11770	AGGREGATE FOR DRAINAGE FILL	24.00	CYS
0072	732-11810	MODULAR BLOCK WALL	640.00	SFT
0073	732-11811	MODULAR BLOCK WALL ERECTION	640.00	SFT
0074	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0075	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	24369.00	LFT
0076	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	116.00	LFT
0077	801-06625	DETOUR ROUTE MARKER ASSEMBLY	24.00	EACH
0078	801-06640	CONSTRUCTION SIGN, A	67.00	EACH
0079	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0080	801-06775	MAINTAINING TRAFFIC	1.00	LS
0081	801-07118	BARRICADE, III-A	48.00	LFT
0082	801-07119	BARRICADE, III-B	32.00	LFT
0083	802-04089	SIGN, SHEET, REMOVE	10.00	EACH
0084	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	102.00	LFT
0085	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0086	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	44.00	SFT
0087	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	29.25	SFT
0088	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4275.00	LFT
0089	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	3210.00	LFT
0090	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	30970.00	LFT
0091	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	6230.00	LFT
0092	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	116.00	LFT
0093	808-12032	GROOVING FOR PAVEMENT MARKINGS	8234.00	LFT
0094	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3914.00	LFT
0095	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	45.00	LFT
0096	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	2.00	EACH
0097	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	20.00	EACH
0098	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	35.00	EACH

Call: 141

Contract: R -34948-B

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL

0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02271	HEADWALL, REMOVE	2.00	EACH
0013	202-02272	PAVED SIDE DITCH, REMOVE	10.00	LFT
0014	202-02771	CONCRETE APRON, REMOVE	1.00	EACH
0015	202-96133	PIPE, REMOVE	36.00	LFT
0016	203-02000	EXCAVATION, COMMON	57.00	CYS
0017	205-11626	PUMP AROUND	5.00	EACH
0018	205-12108	STORM WATER MANAGEMENT BUDGET	15674.00	DOL
0019	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	254.00	SYS
0021	211-09264	STRUCTURE BACKFILL, TYPE 1	323.00	CYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	430.00	CYS
0023	301-12234	COMPACTED AGGREGATE NO 53	2.00	CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	21.00	TON
0025	306-08034	MILLING, ASPHALT, 1 1/2 IN.	211.00	SYS
0026	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	29.00	TON
0027	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	18.00	TON
0028	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	21.00	TON
0029	401-10258	JOINT ADHESIVE, SURFACE	193.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	193.00	LFT
0031	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0032	406-05521	ASPHALT FOR TACK COAT	394.00	SYS
0033	601-06035	GUARDRAIL, RESET	119.00	LFT
0034	616-05688	RIPRAP, CLASS 1	23.00	TON
0035	616-05689	RIPRAP, CLASS 2	207.00	TON
0036	616-06405	RIPRAP, REVETMENT	267.00	TON
0037	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	219.00	SYS
0038	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	420.00	SYS
0039	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	73.00	SYS
0040	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0041	621-06559	MULCHED SEEDING R	628.00	SYS
0042	621-06574	SODDING	1317.00	SYS
0043	628-09402	FIELD OFFICE, B	12.00	MOS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0045	702-51005	CONCRETE, A, SUBSTRUCTURE	2.20	CYS
0046	702-90915	CONCRETE, CLASS, A	2.00	CYS

0047	703-06029	REINFORCING BARS, EPOXY COATED	120.00	LBS
0048	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	101.00	LFT
0049	715-05136	PIPE, TYPE 1, CIRCULAR, 72 IN.	129.00	LFT
0050	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	35.00	LFT
0051	715-05840	CONCRETE ANCHOR, MIN. AREA 14.7SF	1.00	EACH
0052	715-06337	PIPE EXTENSION, CIRCULAR, 48 IN.	36.00	LFT
0053	715-06357	CONCRETE ANCHOR, 72 IN.	2.00	EACH
0054	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	48.00	TON
0055	715-09064	VIDEO INSPECTION FOR PIPE	136.00	LFT
0056	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0057	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH
0058	720-92566	INLET, E MODIFIED	1.00	EACH
0059	725-10212	LINER PIPE, THERMOPLASTIC, DEFORMED, 18.9-19.7 SFT	273.00	LFT
0060	725-10245	PERPETUATION, EXISTING PIPE	5.00	EACH
0061	725-11018	LINER PIPE, THERMOPLASTIC, DEFORMED, 8.2-8.8 SFT	257.00	LFT
0062	725-11861	PIPE LINER, CURED-IN-PLACE, MIN AREA 11.4 SFT	177.00	LFT
0063	725-11868	PIPE LINER, CURED-IN-PLACE, MIN AREA 18.1 SFT	110.00	LFT
0064	725-12063	PIPE LINER, CURED-IN-PLACE, MIN AREA 14.7 SFT	182.00	LFT
0065	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00	EACH
0066	801-06625	DETOUR ROUTE MARKER ASSEMBLY	72.00	EACH
0067	801-06640	CONSTRUCTION SIGN, A	52.00	EACH
0068	801-06710	FLASHING ARROW SIGN	10.00	DAY
0069	801-06775	MAINTAINING TRAFFIC	1.00	LS
0070	801-07118	BARRICADE, III-A	200.00	LFT
0071	801-07119	BARRICADE, III-B	64.00	LFT
0072	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	10.00	LFT
0073	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	186.00	LFT
0074	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	145.00	LFT
0075	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	11.00	LFT
0076	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	4.00	EACH
0077	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	4.00	EACH

Call: 151

Contract: R -35979-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL

0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02272	PAVED SIDE DITCH, REMOVE	116.00	LFT
0013	202-02279	CURB AND GUTTER, REMOVE	2847.00	LFT
0014	202-51133	RAILING, REMOVE	20.00	LFT
0015	202-52710	SIDEWALK CONCRETE, REMOVE	899.00	SYS
0016	202-74035	SIGN, REMOVE	11.00	EACH
0017	202-93615	CONCRETE, REMOVE	11.00	SYS
0018	202-93995	SIGNAL POLE FOUNDATION, REMOVE	4.00	EACH
0019	203-02000	EXCAVATION, COMMON	16004.00	CYS
0020	203-02070	BORROW	1200.00	CYS
0021	205-12108	STORM WATER MANAGEMENT BUDGET	28100.00	DOL
0022	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0023	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	34.00	CYS
0024	207-08264	SUBGRADE TREATMENT, TYPE II	1752.00	SYS
0025	207-08266	SUBGRADE TREATMENT, TYPE III	3382.00	SYS
0026	207-09934	SUBGRADE TREATMENT, TYPE IB	20636.00	SYS
0027	211-09264	STRUCTURE BACKFILL, TYPE 1	3815.00	CYS
0028	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	134.00	CYS
0029	301-12234	COMPACTED AGGREGATE NO 53	2740.00	CYS
0030	304-07490	HMA PATCHING, TYPE B	58.00	TON
0031	306-08036	MILLING, ASPHALT, 2 IN.	755.00	SYS
0032	401-07352	QC/QA-HMA, 3, 76, SURFACE, 12.5 mm	1974.00	TON
0033	401-07403	QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	2586.00	TON
0034	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	5106.00	TON
0035	401-10258	JOINT ADHESIVE, SURFACE	5054.00	LFT
0036	401-10259	JOINT ADHESIVE, INTERMEDIATE	4844.00	LFT
0037	401-11785	LIQUID ASPHALT SEALANT	5054.00	LFT
0038	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	2987.00	TON
0039	402-10086	HMA FOR TEMPORARY PAVEMENT, C	1223.00	TON
0040	406-05520	ASPHALT FOR TACK COAT	19.00	TON
0041	502-11543	PCCP, 4 IN.	1453.00	SYS
0042	502-11564	PCCP, 7 IN.	422.00	SYS
0043	503-05240	D-1 CONTRACTION JOINT	270.00	LFT
0044	601-02241	GUARDRAIL, REMOVE	950.00	LFT
0045	601-94690	GUARDRAIL, END TREATMENT, MS	2.00	EACH
0046	601-99108	GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN. SPACING	293.75	LFT
0047	604-06070	SIDEWALK, CONCRETE	447.00	SYS
0048	604-07823	STAMPED CONCRETE SIDEWALK	1315.00	SYS
0049	604-08086	CURB RAMP, CONCRETE	327.00	SYS

0050	604-12083	DETECTABLE WARNING SURFACES	58.00	SYS
0051	604-95344	HAND RAIL, PEDESTRIAN	36.00	LFT
0052	605-05523	CURB, HMA	172.00	LFT
0053	605-06120	CURB, CONCRETE	272.00	LFT
0054	605-06140	CURB AND GUTTER, CONCRETE	3819.00	LFT
0055	605-06140	CURB AND GUTTER, CONCRETE	175.00	LFT
0056	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	3334.00	LFT
0057	605-06160	CURB AND GUTTER, B, CONCRETE, MODIFIED	307.00	LFT
0058	610-07487	HMA FOR APPROACHES, TYPE B	82.00	TON
0059	610-09108	PCCP FOR APPROACHES, 9 IN.	480.00	SYS
0060	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0061	615-06490	RIGHT-OF-WAY MARKER	8.00	EACH
0062	616-06405	RIPRAP, REVETMENT	112.00	TON
0063	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	218.00	SYS
0064	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0065	621-06545	FERTILIZER	0.60	TON
0066	621-06554	SEED MIXTURE U	300.00	LBS
0067	621-06565	MULCHING MATERIAL	3.00	TON
0068	621-06570	TOPSOIL	1038.00	CYS
0069	621-06575	SODDING, NURSERY	2324.00	SYS
0070	628-09402	FIELD OFFICE, B	24.00	MOS
0071	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0072	628-11977	COMPUTER SYSTEM	1.00	EACH
0073	715-04987	CONNECTION	6.00	EACH
0074	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	257.00	LFT
0075	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	3024.00	LFT
0076	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1010.00	LFT
0077	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	42.00	LFT
0078	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	966.00	LFT
0079	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	53.00	LFT
0080	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	711.00	LFT
0081	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	57.00	LFT
0082	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	116.00	LFT
0083	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	72.00	LFT
0084	715-05408	PIPE, SANITARY SEWER, 8 IN.	105.00	LFT
0085	715-05411	PIPE, SANITARY SEWER, 12 IN.	38.00	LFT
0086	715-05415	PIPE, SANITARY SEWER, 24 IN.	841.00	LFT
0087	715-06050	CAP	2.00	EACH
0088	715-09064	VIDEO INSPECTION FOR PIPE	4179.00	LFT
0089	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0090	715-46010	PIPE END SECTION, DIAMETER 18 IN.	4.00	EACH
0091	715-94530	ADJUST WATER VALVE TO GRADE	12.00	EACH
0092	715-98165	WATER MAIN, 12 IN.	42.00	LFT

0093	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3024.00	LFT
0094	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	2899.00	SYS
0095	718-12309	GEOTEXTILE FOR UNDERDRAIN, TYPE 3	98.00	SYS
0096	718-52610	AGGREGATE FOR UNDERDRAINS	441.00	CYS
0097	720-01092	MANHOLE, J15 MODIFIED	24.00	EACH
0098	720-01092	MANHOLE, J15 MODIFIED	3.00	EACH
0099	720-03194	MANHOLE	2.00	EACH
0100	720-03194	MANHOLE	5.00	EACH
0101	720-08239	MANHOLE, J7 MODIFIED	1.00	EACH
0102	720-08241	MANHOLE, K15 MODIFIED	2.00	EACH
0103	720-10114	SANITARY DROP MANHOLE	2.00	EACH
0104	720-44000	CASTING, ADJUST TO GRADE	2.00	EACH
0105	720-45045	INLET, J10	1.00	EACH
0106	720-45235	CATCH BASIN, E7	1.00	EACH
0107	720-45235	CATCH BASIN, E7	1.00	EACH
0108	720-45270	PIPE CATCH BASIN, 18 IN.	1.00	EACH
0109	720-45275	PIPE CATCH BASIN, 24 IN.	1.00	EACH
0110	720-45275	PIPE CATCH BASIN, 24 IN.	1.00	EACH
0111	720-45410	MANHOLE, C4	1.00	EACH
0112	720-94612	MANHOLE, K4	1.00	EACH
0113	720-95422	MANHOLE, J4	3.00	EACH
0114	720-95422	MANHOLE, J4	2.00	EACH
0115	720-95422	MANHOLE, J4	1.00	EACH
0116	720-97008	FIRE HYDRANT ASSEMBLY RELOCATE	1.00	EACH
0117	720-98174	INLET, B15	6.00	EACH
0118	720-98174	INLET, B15	1.00	EACH
0119	720-98869	MANHOLE, L4 MODIFIED	1.00	EACH
0120	732-11770	AGGREGATE FOR DRAINAGE FILL	14.00	CYS
0121	732-11810	MODULAR BLOCK WALL	472.00	SFT
0122	732-11811	MODULAR BLOCK WALL ERECTION	472.00	SFT
0123	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	50.00	EACH
0124	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0125	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0126	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	57523.00	LFT
0127	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8074.00	LFT
0128	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	3.00	EACH
0129	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	825.00	LFT
0130	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	149.00	LFT
0131	801-06625	DETOUR ROUTE MARKER ASSEMBLY	54.00	EACH
0132	801-06640	CONSTRUCTION SIGN, A	45.00	EACH
0133	801-06645	CONSTRUCTION SIGN, B	21.00	EACH
0134	801-06710	FLASHING ARROW SIGN	540.00	DAY
0135	801-06775	MAINTAINING TRAFFIC	1.00	LS

0136	801-07118	BARRICADE, III-A	148.00	LFT
0137	801-07119	BARRICADE, III-B	72.00	LFT
0138	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	743.00	LFT
0139	801-53072	TEMPORARY TRAFFIC SIGNAL	1.00	LS
0140	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	493.50	LFT
0141	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	149.00	LFT
0142	802-07057	SIGN, PANEL, WITH LEGEND	100.75	SFT
0143	802-07060	SIGN, SHEET, RELOCATE	6.00	EACH
0144	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	201.00	SFT
0145	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	196.60	SFT
0146	802-11648	SIGN POST	4.00	EACH
0147	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0148	805-04952	CONTROLLER AND CABINET	1.00	EACH
0149	805-11377	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 35 FT.	1.00	EACH
0150	805-11382	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 60 FT.	1.00	EACH
0151	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, A	1.00	EACH
0152	805-11384	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, B	1.00	EACH
0153	807-03934	LIGHT STRUCTURE, REMOVE	5.00	EACH
0154	807-03950	LUMINAIRE ORNAMENTAL	28.00	EACH
0155	807-03951	LIGHT POLE ORNAMENTAL	28.00	EACH
0156	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	965.00	LFT
0157	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	3785.00	LFT
0158	807-11694	ILLUMINATED SIGN	4.00	EACH
0159	807-11981	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. DIA X 96 IN.	32.00	EACH
0160	807-86810	SERVICE POINT, II	1.00	EACH
0161	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	1480.00	LFT
0162	807-86910	CONNECTOR KIT, UNFUSED	32.00	EACH
0163	807-86915	CONNECTOR KIT, FUSED	32.00	EACH
0164	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	92.00	EACH
0165	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	28.00	EACH
0166	807-86930	INSULATION LINK, NON-WATERPROOFED	56.00	EACH
0167	807-86935	INSULATION LINK, WATERPROOFED	36.00	EACH
0168	807-98469	PULL BOX	9.00	EACH
0169	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	748.00	LFT
0170	808-10032	LINE, MULTI-COMPONENT, DOTTED, WHITE, 8 IN.	156.00	LFT
0171	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1274.00	LFT
0172	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	691.00	LFT
0173	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	2332.00	LFT
0174	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	89.00	LFT
0175	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	10.00	EACH
0176	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	2901.00	LFT
0177	808-10058	LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN.	1106.00	LFT
0178	808-10059	LINE, MULTI-COMPONENT, SOLID, YELLOW, 12 IN.	426.00	LFT

0179	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	42.00	EACH
0180	808-10099	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 24 IN.	690.00	LFT
0181	808-11776	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 24 IN.	143.00	LFT
0182	808-12032	GROOVING FOR PAVEMENT MARKINGS	9052.00	LFT
0183	808-12353	LINE MULTI-COMPONENT DOTTED WHITE 6 IN	88.00	LFT
0184	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	54.00	EACH
0185	809-06101	FOUNDATION	1.00	EACH

Call: 161

Contract: R -36124-B

Section No.: 1 SMALL STRUCTURE, PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	4.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-96133	PIPE, REMOVE	95.00	LFT
0012	203-02055	EMBANKMENT	25.00	CYS
0013	205-12108	STORM WATER MANAGEMENT BUDGET	7875.00	DOL
0014	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0015	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	119.00	CYS
0016	211-09265	STRUCTURE BACKFILL, TYPE 2	75.00	CYS
0017	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	108.00	SYS
0018	301-12232	COMPACTED AGGREGATE NO 5	18.00	CYS
0019	301-12234	COMPACTED AGGREGATE NO 53	18.00	CYS
0020	601-06035	GUARDRAIL, RESET	150.00	LFT
0021	616-05688	RIPRAP, CLASS 1	30.00	TON
0022	616-05689	RIPRAP, CLASS 2	402.00	TON
0023	616-06405	RIPRAP, REVETMENT	36.00	TON
0024	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	426.00	SYS
0025	616-95754	PAVED SIDE DITCH, BREAK	1400.00	LFT
0026	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.00	EACH
0027	621-02770	EROSION CONTROL BLANKET	105.00	SYS
0028	621-06559	MULCHED SEEDING R	525.00	SYS
0029	621-06567	WATER	10.00	KGAL
0030	628-09402	FIELD OFFICE, B	12.00	MOS

0031	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0032	702-90915	CONCRETE, CLASS, A	25.60	CYS
0033	703-06028	REINFORCING BARS	1786.00	LBS
0034	703-06029	REINFORCING BARS, EPOXY COATED	203.00	LBS
0035	715-06004	CONCRETE ANCHOR, 48 IN.	1.00	EACH
0036	715-06337	PIPE EXTENSION, CIRCULAR, 48 IN.	31.00	LFT
0037	715-06357	CONCRETE ANCHOR, 72 IN.	2.00	EACH
0038	715-06501	CONCRETE ANCHOR, MIN. AREA 8.9 SFT	3.00	EACH
0039	715-07251	PIPE EXTENSION, DEFORMED, MIN. AREA 8.9 SFT	4.00	LFT
0040	715-09370	PIPE EXTENSION, CIRCULAR, 72 IN.	30.00	LFT
0041	725-10014	PIPE LINER CURED-IN-PLACE MIN AREA 8.8 SFT	256.90	LFT
0042	725-10224	LINER PIPE, THERMOPLASTIC, CIRCULAR, 8.4-8.8 SFT	482.70	LFT
0043	725-11039	LINER PIPE, THERMOPLASTIC, CIRCULAR, 19.6-19.7 SFT	340.00	LFT
0044	725-11288	PIPE LINER, CURED-IN-PLACE, 60"	171.50	LFT
0045	801-06640	CONSTRUCTION SIGN, A	38.00	EACH
0046	801-06645	CONSTRUCTION SIGN, B	14.00	EACH
0047	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 171

Contract: R -36177-B

Section No.: 1 SLIDE CORRECTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	104-05404	DESIGN/BUILD	1.00	LS
0002	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	203-02000	EXCAVATION, COMMON	3582.00	CYS
0013	203-02070	BORROW	659.00	CYS
0014	205-12108	STORM WATER MANAGEMENT BUDGET	7976.25	DOL
0015	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0016	207-09935	SUBGRADE TREATMENT, TYPE IC	3996.00	SYS
0017	211-09264	STRUCTURE BACKFILL, TYPE 1	177.00	CYS
0018	301-12234	COMPACTED AGGREGATE NO 53	250.00	CYS
0019	303-01180	COMPACTED AGGREGATE NO. 53	70.00	TON
0020	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	200.00	TON

0021	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	860.00	TON
0022	401-10258	JOINT ADHESIVE, SURFACE	975.00	LFT
0023	401-10259	JOINT ADHESIVE, INTERMEDIATE	975.00	LFT
0024	401-11785	LIQUID ASPHALT SEALANT	975.00	LFT
0025	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0026	601-02241	GUARDRAIL, REMOVE	950.00	LFT
0027	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0028	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	950.00	LFT
0029	605-52807	CURB AND GUTTER, COMBINED	1750.00	LFT
0030	615-06490	RIGHT-OF-WAY MARKER	14.00	EACH
0031	615-06505	MONUMENT, B	6.00	EACH
0032	616-05688	RIPRAP, CLASS 1	17.00	TON
0033	616-06405	RIPRAP, REVETMENT	113.00	TON
0034	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	28.00	SYS
0035	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	168.00	SYS
0036	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0037	621-06553	SEED MIXTURE R	250.00	LBS
0038	621-06565	MULCHING MATERIAL	3.00	TON
0039	621-06567	WATER	1.00	KGAL
0040	621-06574	SODDING	44.00	SYS
0041	628-09403	FIELD OFFICE, C	12.00	MOS
0042	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0043	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	74.00	LFT
0044	715-05125	PIPE, TYPE 1, CIRCULAR, 30 IN.	46.00	LFT
0045	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	365.00	LFT
0046	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00	EACH
0047	715-46030	PIPE END SECTION, DIAMETER 30 IN.	1.00	EACH
0048	715-46040	PIPE END SECTION, DIAMETER 36 IN.	2.00	EACH
0049	720-03194	MANHOLE	1.00	EACH
0050	720-98174	INLET, B15	2.00	EACH
0051	720-98555	INLET, C15	4.00	EACH
0052	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0053	801-06625	DETOUR ROUTE MARKER ASSEMBLY	34.00	EACH
0054	801-06640	CONSTRUCTION SIGN, A	14.00	EACH
0055	801-06775	MAINTAINING TRAFFIC	1.00	LS
0056	801-07118	BARRICADE, III-A	48.00	LFT
0057	801-07119	BARRICADE, III-B	24.00	LFT
0058	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1950.00	LFT
0059	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1950.00	LFT
0060	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	12.00	EACH
0061	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	12.00	EACH

Call: 181

Contract: R -36658-A

Section No.: 1

SMALL STRUCTURE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	479.00	SYS
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0014	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0015	203-02020	EXCAVATION, UNCLASSIFIED	460.00	CYS
0016	203-02070	BORROW	144.00	CYS
0017	205-11626	PUMP AROUND	3.00	EACH
0018	205-12108	STORM WATER MANAGEMENT BUDGET	22723.50	DOL
0019	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	128.00	SYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	1587.00	SYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	524.00	CYS
0023	211-09268	STRUCTURE BACKFILL, TYPE 5	723.00	CYS
0024	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	91.00	SYS
0025	301-12232	COMPACTED AGGREGATE NO 5	65.00	CYS
0026	301-12234	COMPACTED AGGREGATE NO 53	303.00	CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	145.00	TON
0028	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	135.00	TON
0029	304-07494	WIDENING WITH HMA, TYPE C	116.00	TON
0030	306-08034	MILLING, ASPHALT, 1 1/2 IN.	249.00	SYS
0031	306-08043	MILLING, TRANSITION	534.00	SYS
0032	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	21.00	TON
0033	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	166.00	TON
0034	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	34.00	TON
0035	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	95.00	TON
0036	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	41.00	TON
0037	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	269.00	TON
0038	401-10258	JOINT ADHESIVE, SURFACE	1621.00	LFT
0039	401-10259	JOINT ADHESIVE, INTERMEDIATE	1341.00	LFT

0040	401-11785	LIQUID ASPHALT SEALANT	1649.00	LFT
0041	406-05521	ASPHALT FOR TACK COAT	3306.00	SYS
0042	601-02241	GUARDRAIL, REMOVE	580.00	LFT
0043	601-04150	GUARDRAIL, THRIE BEAM, 6 FT 3 IN SPACING	100.00	LFT
0044	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	306.30	LFT
0045	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	3.00	EACH
0046	601-91649	GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	4.00	EACH
0047	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0048	610-07487	HMA FOR APPROACHES, TYPE B	36.00	TON
0049	611-08232	MAILBOX ASSEMBLY, SINGLE RESET	1.00	EACH
0050	615-06490	RIGHT-OF-WAY MARKER	7.00	EACH
0051	615-06500	MONUMENT, A	2.00	EACH
0052	615-06505	MONUMENT, B	3.00	EACH
0053	616-01763	RIPRAP RELAID	99.00	SYS
0054	616-05688	RIPRAP, CLASS 1	976.00	TON
0055	616-06405	RIPRAP, REVETMENT	407.00	TON
0056	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	86.00	SYS
0057	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	1651.00	SYS
0058	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0059	621-02770	EROSION CONTROL BLANKET	522.00	SYS
0060	621-06545	FERTILIZER	0.10	TON
0061	621-06553	SEED MIXTURE R	3.00	LBS
0062	621-06559	MULCHED SEEDING R	916.00	SYS
0063	621-06565	MULCHING MATERIAL	0.10	TON
0064	621-06574	SODDING	303.00	SYS
0065	628-09402	FIELD OFFICE, B	10.00	MOS
0066	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0067	702-04325	TEMPORARY SHORING	1.00	LS
0068	703-06029	REINFORCING BARS, EPOXY COATED	454.00	LBS
0069	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	120.00	EACH
0070	704-51002	CONCRETE, C, SUPERSTRUCTURE	8.10	CYS
0071	706-04683	RAILING	37.50	LFT
0072	709-51821	SURFACE SEAL	1.00	LS
0073	714-11186	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 12 FT. X 4 FT.	48.00	LFT
0074	714-11192	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 4 FT X 3 FT	140.00	LFT
0075	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	65.00	LFT
0076	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	520.00	SYS
0077	718-52610	AGGREGATE FOR UNDERDRAINS	6.00	CYS
0078	723-12012	STRUCTURE, COATED REINFORCED CONCRETE THREE-SIDED SECTIONS, 216 IN X 120 IN	40.00	LFT
0079	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0080	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3476.00	LFT
0081	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	26.00	LFT
0082	801-06625	DETOUR ROUTE MARKER ASSEMBLY	31.00	EACH

0083	801-06640	CONSTRUCTION SIGN, A	45.00	EACH
0084	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0085	801-06775	MAINTAINING TRAFFIC	1.00	LS
0086	801-07118	BARRICADE, III-A	96.00	LFT
0087	801-07119	BARRICADE, III-B	138.00	LFT
0088	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	251.00	LFT
0089	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	380.00	LFT
0090	801-12081	PORTABLE SIGNAL	1.00	LS
0091	801-53072	TEMPORARY TRAFFIC SIGNAL	1.00	LS
0092	801-97643	TEMPORARY BUZZ STRIPS	1008.00	LFT
0093	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	36.00	LFT
0094	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	12.00	SFT
0095	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	6007.00	LFT
0096	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	6880.00	LFT
0097	808-06716	LINE, REMOVE	3109.00	LFT
0098	808-75994	PRISMATIC REFLECTOR	10.00	EACH
0099	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	9.00	EACH
0100	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	13.00	EACH

Call: 185

Contract: R -36673-B

Section No.: 1 SMALL STRUCTURE MAINTENANCE AND REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-02245	TREE 6 IN., REMOVE	2.00	EACH
0012	201-02250	TREE 10 IN., REMOVE	2.00	EACH
0013	201-02260	TREE 30 IN., REMOVE	1.00	EACH
0014	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0015	202-02240	PAVEMENT REMOVAL	704.00	SYS
0016	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0017	202-96133	PIPE, REMOVE	149.00	LFT
0018	203-02000	EXCAVATION, COMMON	520.10	CYS
0019	205-12108	STORM WATER MANAGEMENT BUDGET	10250.00	DOL

0020	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	43.40	SYS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	1468.80	SYS
0023	211-02050	B BORROW	10.00	CYS
0024	211-09264	STRUCTURE BACKFILL, TYPE 1	165.00	CYS
0025	211-09265	STRUCTURE BACKFILL, TYPE 2	1223.00	CYS
0026	211-09267	STRUCTURE BACKFILL, TYPE 4	480.00	CYS
0027	211-09268	STRUCTURE BACKFILL, TYPE 5	372.00	CYS
0028	214-12236	GEOTEXTILE FOR PAVEMENT TYPE 1A	123.40	SYS
0029	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	167.00	SYS
0030	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	241.00	SYS
0031	301-12232	COMPACTED AGGREGATE NO 5	137.00	CYS
0032	301-12234	COMPACTED AGGREGATE NO 53	94.10	CYS
0033	302-07455	DENSE GRADED SUBBASE	40.00	CYS
0034	303-01180	COMPACTED AGGREGATE NO. 53	364.60	TON
0035	303-07449	COMPACTED AGGREGATE NO. 73	60.00	TON
0036	304-07494	WIDENING WITH HMA, TYPE C	46.00	TON
0037	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1316.00	SYS
0038	306-08159	MILLING, ASPHALT	534.00	SYS
0039	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	64.00	TON
0040	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	55.00	TON
0041	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	42.00	TON
0042	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	44.00	TON
0043	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	20.00	TON
0044	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	26.00	TON
0045	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	60.00	TON
0046	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	105.00	TON
0047	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	102.00	TON
0048	401-10258	JOINT ADHESIVE, SURFACE	705.00	LFT
0049	401-10259	JOINT ADHESIVE, INTERMEDIATE	415.00	LFT
0050	401-11785	LIQUID ASPHALT SEALANT	705.00	LFT
0051	406-05521	ASPHALT FOR TACK COAT	3775.50	SYS
0052	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	0.40	TON
0053	501-06266	PROFILOGRAPH PCCP	1.00	LS
0054	501-06727	CORING, PCCP	1.00	LS
0055	502-06329	PCCP, 12 IN.	240.00	SYS
0056	502-09531	PCCP	534.00	SYS
0057	503-05240	D-1 CONTRACTION JOINT	36.00	LFT
0058	601-01704	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, MODIFIED	1.00	EACH
0059	601-02241	GUARDRAIL, REMOVE	230.00	LFT
0060	601-02625	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM, CURVED, 2, MODIFIED	1.00	EACH
0061	601-02800	GUARDRAIL, TRANSITION, TGT	3.00	EACH
0062	601-02800	GUARDRAIL, TRANSITION, TGT	1.00	EACH

0063	601-09238	HAND DIG GUARDRAIL POST HOLES	8.00	EACH
0064	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0065	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	12.50	LFT
0066	610-07487	HMA FOR APPROACHES, TYPE B	12.00	TON
0067	610-07488	HMA FOR APPROACHES, TYPE C	96.50	TON
0068	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0069	615-06490	RIGHT-OF-WAY MARKER	7.00	EACH
0070	615-06515	MONUMENT, D	2.00	EACH
0071	615-06530	BENCH MARK POST	1.00	EACH
0072	616-05688	RIPRAP, CLASS 1	124.00	TON
0073	616-05689	RIPRAP, CLASS 2	149.10	TON
0074	616-06405	RIPRAP, REVETMENT	317.00	TON
0075	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	301.40	SYS
0076	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	190.00	SYS
0077	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.00	EACH
0078	621-02770	EROSION CONTROL BLANKET	1851.00	SYS
0079	621-03787	SEED MIXTURE D	3.00	LBS
0080	621-03909	SEED MIXTURE, NATIVE	8.00	LBS
0081	621-06559	MULCHED SEEDING R	491.00	SYS
0082	621-06567	WATER	1.00	KGAL
0083	621-06574	SODDING	34.00	SYS
0084	628-09402	FIELD OFFICE, B	16.00	MOS
0085	628-11729	CELLULAR TELEPHONE, TYPE A	3.00	EACH
0086	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0087	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0088	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	30.00	MOS
0089	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0090	706-06347	RAILING, STEEL CF-1	23.30	LFT
0091	714-11163	STRUCTURE, REINFORCED CONCRETE BOX SECTIONS, 12 FT X 9 FT	39.79	LFT
0092	715-05129	PIPE, TYPE 1, CIRCULAR, 54 IN.	81.00	LFT
0093	715-05136	PIPE, TYPE 1, CIRCULAR, 72 IN.	124.00	LFT
0094	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	42.00	LFT
0095	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	37.00	LFT
0096	715-06357	CONCRETE ANCHOR, 72 IN.	2.00	EACH
0097	715-08256	PIPE, TYPE 1, DEFORMED, MIN. AREA 26.0 SFT	70.00	LFT
0098	715-09064	VIDEO INSPECTION FOR PIPE	79.00	LFT
0099	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0100	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH
0101	720-44000	CASTING, ADJUST TO GRADE	4.00	EACH
0102	801-04308	ROAD CLOSURE SIGN ASSEMBLY	29.00	EACH
0103	801-06625	DETOUR ROUTE MARKER ASSEMBLY	175.00	EACH
0104	801-06640	CONSTRUCTION SIGN, A	69.00	EACH
0105	801-06645	CONSTRUCTION SIGN, B	6.00	EACH

0106	801-06775	MAINTAINING TRAFFIC	1.00	LS
0107	801-07118	BARRICADE, III-A	264.00	LFT
0108	801-07119	BARRICADE, III-B	160.00	LFT
0109	804-11920	DELINEATOR POST FLEXIBLE, TYPE I	6.00	EACH
0110	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	200.00	LFT
0111	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	60.00	LFT
0112	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1120.00	LFT
0113	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	580.00	LFT
0114	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	559.00	LFT
0115	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2551.00	LFT
0116	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	75.00	LFT
0117	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	52.00	LFT
0118	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	200.00	LFT
0119	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6.00	EACH
0120	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	6.00	EACH

Call: 191

Contract: R -36692-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	202-96133	PIPE, REMOVE	4.00	LFT
0011	203-02000	EXCAVATION, COMMON	10.00	CYS
0012	205-12108	STORM WATER MANAGEMENT BUDGET	5200.00	DOL
0013	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0014	601-06035	GUARDRAIL, RESET	300.00	LFT
0015	603-06060	FENCE, FARM FIELD, RESET	100.00	LFT
0016	616-05689	RIPRAP, CLASS 2	183.00	TON
0017	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	312.00	SYS
0018	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0019	621-06559	MULCHED SEEDING R	2992.00	SYS
0020	628-09402	FIELD OFFICE, B	11.00	MOS
0021	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0022	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL

0023	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0024	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	11.00	MOS
0025	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0026	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	222.00	LFT
0027	715-05128	PIPE, TYPE 1, CIRCULAR, 48 IN.	185.00	LFT
0028	715-06004	CONCRETE ANCHOR, 48 IN.	2.00	EACH
0029	715-07679	CONCRETE ANCHOR, 36 IN.	2.00	EACH
0030	716-07635	PIPE INSTALLATION, TRENCHLESS, 36 IN.	222.00	LFT
0031	716-07637	PIPE INSTALLATION, TRENCHLESS, 48 IN.	185.00	LFT
0032	725-11021	LINER PIPE, THERMOPLASTIC, DEFORMED, 13.5-16.0 SFT	223.33	LFT
0033	725-11709	PIPE LINER, CURED-IN-PLACE, MIN AREA 12.5 SFT	179.00	LFT
0034	725-11762	LINER PIPE, THERMOPLASTIC, DEFORMED, 36.4-38.5 SFT	186.33	LFT
0035	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0036	801-06640	CONSTRUCTION SIGN, A	40.00	EACH
0037	801-06710	FLASHING ARROW SIGN	105.00	DAY
0038	801-06775	MAINTAINING TRAFFIC	1.00	LS
0039	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	320.00	LFT

Call: 201

Contract: R -37259-A

Section No.: 1 NEW ROAD CONSTRUCTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	6213.00	SYS
0012	202-91385	INLET, REMOVE	1.00	EACH
0013	202-96133	PIPE, REMOVE	61.00	LFT
0014	203-02000	EXCAVATION, COMMON	192920.00	CYS
0015	203-02010	EXCAVATION, ROCK	3257.20	CYS
0016	203-02070	BORROW	63660.00	CYS
0017	205-11626	PUMP AROUND	4.00	EACH
0018	205-12108	STORM WATER MANAGEMENT BUDGET	151704.55	DOL
0019	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	2131.00	SYS

0021	207-08266	SUBGRADE TREATMENT, TYPE III	8794.00	SYS
0022	207-09934	SUBGRADE TREATMENT, TYPE IB	44491.25	SYS
0023	211-02050	B BORROW	11236.00	CYS
0024	211-09264	STRUCTURE BACKFILL, TYPE 1	9313.00	CYS
0025	211-09266	STRUCTURE BACKFILL, TYPE 3	16473.00	CYS
0026	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	1.10	CYS
0027	214-11796	GEOGRID, TYPE IB	450.00	SYS
0028	301-12231	COMPACTED AGGREGATE NO 2	446.00	CYS
0029	301-12234	COMPACTED AGGREGATE NO 53	4393.00	CYS
0030	302-07455	DENSE GRADED SUBBASE	142.00	CYS
0031	303-01180	COMPACTED AGGREGATE NO. 53	4793.00	TON
0032	303-07449	COMPACTED AGGREGATE NO. 73	537.00	TON
0033	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	115.00	TON
0034	401-06264	PROFILOGRAPH, HMA	1.00	LS
0035	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	828.00	TON
0036	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	2299.97	TON
0037	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	3860.00	TON
0038	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	7833.00	TON
0039	401-10258	JOINT ADHESIVE, SURFACE	23293.00	LFT
0040	401-10259	JOINT ADHESIVE, INTERMEDIATE	23293.00	LFT
0041	401-11785	LIQUID ASPHALT SEALANT	23293.00	LFT
0042	402-10084	HMA FOR TEMPORARY PAVEMENT, B	1023.00	TON
0043	406-05520	ASPHALT FOR TACK COAT	15.00	TON
0044	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	4.00	EACH
0045	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	2.00	EACH
0046	601-05999	CURVED TERMINAL END	6.00	EACH
0047	601-08433	GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS PACKAGE, STAGE 1	1.00	EACH
0048	601-08434	GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS PACKAGE, STAGE 2	1.00	EACH
0049	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0050	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	1519.50	LFT
0051	602-06729	BARRIER, DELINEATOR	10.00	EACH
0052	606-07484	MILLED HMA CORRUGATIONS	16670.00	LFT
0053	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	220.00	SYS
0054	610-07487	HMA FOR APPROACHES, TYPE B	111.00	TON
0055	611-06497	MAILBOX ASSEMBLY, SINGLE	3.00	EACH
0056	615-06490	RIGHT-OF-WAY MARKER	98.00	EACH
0057	615-06505	MONUMENT, B	22.00	EACH
0058	615-06510	MONUMENT, C	4.00	EACH
0059	615-06527	MONUMENT, SECTION CORNER	2.00	EACH
0060	616-05688	RIPRAP, CLASS 1	2208.00	TON
0061	616-05689	RIPRAP, CLASS 2	655.00	TON
0062	616-06405	RIPRAP, REVETMENT	3502.00	TON
0063	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	9260.00	SYS

0064	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	460.00	SYS
0065	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.00	EACH
0066	621-02318	SEED MIXTURE, PRAIRIE GRASS	32.00	LBS
0067	621-02356	SEEDING WETLAND	128.00	LBS
0068	621-03909	SEED MIXTURE, NATIVE	99.00	LBS
0069	621-06545	FERTILIZER	3.00	TON
0070	621-06553	SEED MIXTURE R	4035.00	LBS
0071	621-06559	MULCHED SEEDING R	90068.81	SYS
0072	621-06565	MULCHING MATERIAL	40.00	TON
0073	621-06567	WATER	1.00	kGAL
0074	621-06570	TOPSOIL	200.00	CYS
0075	621-06574	SODDING	162.00	SYS
0076	621-06575	SODDING, NURSERY	3547.00	SYS
0077	621-52448	SIGN, DO NOT SPRAY	17.00	EACH
0078	622-05638	PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	766.00	EACH
0079	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	2736.00	EACH
0080	622-10003	LIVE PLANT STAKING	1427.00	EACH
0081	624-92647	HERBICIDE TREATMENT	5.00	ACRE
0082	628-09403	FIELD OFFICE, C	33.00	MOS
0083	628-11976	COMPUTER SYSTEM EQUIPMENT	6.00	EACH
0084	628-11977	COMPUTER SYSTEM	3.00	EACH
0085	701-02938	CORED HOLE IN ROCK, 24 IN	50.00	LFT
0086	701-09558	TEST PILE, INDICATOR, PRODUCTION	115.00	LFT
0087	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00	EACH
0088	701-09891	PILE SHOE, HP 12 X 84	10.00	EACH
0089	701-95782	PILE, STEEL H, HP, 12 X 84	380.00	LFT
0090	702-51005	CONCRETE, A, SUBSTRUCTURE	182.50	CYS
0091	702-51015	CONCRETE, B, FOOTINGS	10.30	CYS
0092	702-92857	CONCRETE, C, SUBSTRUCTURE	73.00	CYS
0093	703-06028	REINFORCING BARS	28097.00	LBS
0094	703-06029	REINFORCING BARS, EPOXY COATED	55694.00	LBS
0095	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	48.00	EACH
0096	704-51002	CONCRETE, C, SUPERSTRUCTURE	99.00	CYS
0097	706-09960	RAILING, CONCRETE FC	160.00	LFT
0098	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0099	707-09865	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 49 IN.	395.00	LFT
0100	709-51821	SURFACE SEAL	1.00	LS
0101	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	14958.00	LFT
0102	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	1420.10	LFT
0103	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	43.00	LFT
0104	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	81.00	LFT
0105	715-05141	PIPE, TYPE 1, CIRCULAR, 84 IN.	329.00	LFT
0106	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	388.00	LFT

0107	715-05248	PIPE, TYPE 1, DEFORMED, MIN. AREA 16.6 SFT	196.00	LFT
0108	715-05263	PIPE, TYPE 1, DEFORMED, MIN. AREA 29 SFT	129.00	LFT
0109	715-06939	CONCRETE ANCHOR, MIN. AREA 29.5 SFT	2.00	EACH
0110	715-07150	CONCRETE ANCHOR, 84 IN.	2.00	EACH
0111	715-07303	CONCRETE ANCHOR, MIN. AREA 16.7 SFT	4.00	EACH
0112	715-07625	PIPE, TYPE 1, CIRCULAR, 66 IN.	334.00	LFT
0113	715-07626	CONCRETE ANCHOR, 66 IN.	2.00	EACH
0114	715-46005	PIPE END SECTION, DIAMETER 15 IN.	15.00	EACH
0115	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	EACH
0116	718-06528	OUTLET PROTECTOR, 1	40.00	EACH
0117	718-06529	OUTLET PROTECTOR, 2	2.00	EACH
0118	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00	LFT
0119	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	10000.00	SYS
0120	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	286.00	SYS
0121	718-52610	AGGREGATE FOR UNDERDRAINS	1184.00	CYS
0122	720-45030	INLET, E7	1.00	EACH
0123	720-45130	INLET, E7 MODIFIED	1.00	EACH
0124	731-93945	FACE PANELS, CONCRETE	10720.00	SFT
0125	731-93946	WALL ERECTION	10720.00	SFT
0126	731-93947	LEVELING PAD, CONCRETE	393.00	LFT
0127	801-03290	CONSTRUCTION SIGN, C	4.00	EACH
0128	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0129	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1167.00	LFT
0130	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	52.00	LFT
0131	801-06625	DETOUR ROUTE MARKER ASSEMBLY	40.00	EACH
0132	801-06640	CONSTRUCTION SIGN, A	49.00	EACH
0133	801-06645	CONSTRUCTION SIGN, B	61.00	EACH
0134	801-06775	MAINTAINING TRAFFIC	1.00	LS
0135	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	3.00	EACH
0136	801-07118	BARRICADE, III-A	372.00	LFT
0137	801-07119	BARRICADE, III-B	24.00	LFT
0138	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	425.00	LFT
0139	801-12081	PORTABLE SIGNAL	1.00	LS
0140	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	562.00	LFT
0141	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	279.75	SFT
0142	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	113.50	SFT
0143	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	23.00	SFT
0144	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	16410.00	LFT
0145	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	3216.00	LFT
0146	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	3040.00	LFT
0147	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	250.00	LFT
0148	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	250.00	LFT
0149	808-12032	GROOVING FOR PAVEMENT MARKINGS	28335.00	LFT

0150	808-75035	LINE, PAINT, SOLID, WHITE, 24 IN.	52.00	LFT
0151	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1089.00	LFT
0152	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	10836.00	LFT
0153	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	155.00	LFT
0154	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	367.00	EACH

Call: 211

Contract: R -37627-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02278	CURB, CONCRETE, REMOVE	133.60	LFT
0012	202-52710	SIDEWALK CONCRETE, REMOVE	31.10	SYS
0013	202-91922	STUMP, REMOVE	1.00	EACH
0014	202-93615	CONCRETE, REMOVE	86.10	SYS
0015	202-94810	CURB TURNOUT, REMOVE	1.00	EACH
0016	203-02000	EXCAVATION, COMMON	834.10	CYS
0017	205-12108	STORM WATER MANAGEMENT BUDGET	7406.20	DOL
0018	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	516.40	SYS
0020	207-08266	SUBGRADE TREATMENT, TYPE III	2458.20	SYS
0021	301-12234	COMPACTED AGGREGATE NO 53	272.90	CYS
0022	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
0023	604-06070	SIDEWALK, CONCRETE	2458.20	SYS
0024	604-07092	BED COURSE MATERIAL	34.40	TON
0025	604-08086	CURB RAMP, CONCRETE	154.90	SYS
0026	604-12083	DETECTABLE WARNING SURFACES	24.90	SYS
0027	605-06090	CURB, INTEGRAL CONCRETE	18.20	LFT
0028	610-08446	PCCP FOR APPROACHES, 6 IN.	99.20	SYS
0029	610-09108	PCCP FOR APPROACHES, 9 IN.	417.30	SYS
0030	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00	EACH
0031	615-06495	RIGHT-OF-WAY MARKER, RESET	1.00	EACH
0032	616-06405	RIPRAP, REVETMENT	256.30	TON

0033	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	539.10	SYS
0034	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0035	621-06560	MULCHED SEEDING U	3667.00	SYS
0036	720-45260	PIPE CATCH BASIN, 12 IN.	1.00	EACH
0037	801-06640	CONSTRUCTION SIGN, A	76.00	EACH
0038	801-06775	MAINTAINING TRAFFIC	1.00	LS
0039	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	72.00	LFT
0040	802-07060	SIGN, SHEET, RELOCATE	2.00	EACH
0041	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	8.50	SFT
0042	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	18.00	SFT
0043	808-03114	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, XING 8 FT	2.00	EACH
0044	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	224.00	LFT
0045	808-06716	LINE, REMOVE	60.00	LFT
0046	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	52.00	LFT
0047	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	38.00	LFT
0048	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	288.00	LFT
0049	808-75330	PAVEMENT MESSAGE MARKING, THERMOPLASTIC PED XING	2.00	EACH

Call: 231

Contract: R -38404-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	203-02000	EXCAVATION, COMMON	102.00	CYS
0010	205-12108	STORM WATER MANAGEMENT BUDGET	7500.00	DOL
0011	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0012	207-08264	SUBGRADE TREATMENT, TYPE II	650.00	SYS
0013	303-07449	COMPACTED AGGREGATE NO. 73	5.00	TON
0014	604-06070	SIDEWALK, CONCRETE	532.00	SYS
0015	604-08086	CURB RAMP, CONCRETE	88.00	SYS
0016	604-12083	DETECTABLE WARNING SURFACES	17.00	SYS
0017	610-08446	PCCP FOR APPROACHES, 6 IN.	29.00	SYS
0018	621-02363	MULCHED SEEDING T, CONVENTIONAL MIX	278.00	SYS
0019	621-06560	MULCHED SEEDING U	278.00	SYS
0020	621-06567	WATER	2.00	KGAL

0021	621-06575	SODDING, NURSERY	560.00	SYS
0022	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0023	801-06710	FLASHING ARROW SIGN	60.00	DAY
0024	801-06775	MAINTAINING TRAFFIC	1.00	LS
0025	802-07060	SIGN, SHEET, RELOCATE	6.00	EACH
0026	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0027	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	2.00	EACH
0028	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	204.00	LFT
0029	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0030	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	1.00	EACH
0031	805-05405	SIGNAL POLE, PEDESTAL, 4FT	1.00	EACH
0032	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	6.00	EACH
0033	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	3.00	EACH
0034	805-78415	SPAN, CATENARY, AND TETHER	3.00	EACH
0035	805-78420	DISCONNECT HANGER	3.00	EACH
0036	805-78445	SIGNAL SERVICE	1.00	EACH
0037	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	46.00	LFT
0038	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	664.00	LFT
0039	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	112.00	LFT
0040	805-78500	SIGNAL CABLE, CONTROL, COPPER, 11C/14 GA	561.00	LFT
0041	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	2.00	EACH
0042	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	131.00	LFT
0043	808-75100	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 6 IN.	524.00	LFT

Call: 241

Contract: R -38578-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	202-99080	CONCRETE, REMOVE	2.00	CYS
0011	202-99187	FENCE, FARM FIELD, REMOVE	225.00	LFT
0012	203-02070	BORROW	26.00	CYS
0013	205-11626	PUMP AROUND	1.00	EACH
0014	205-11626	PUMP AROUND	1.00	EACH

0015	205-11626	PUMP AROUND	2.00	EACH
0016	205-11626	PUMP AROUND	2.00	EACH
0017	205-12108	STORM WATER MANAGEMENT BUDGET	19900.00	DOL
0018	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0019	206-51220	EXCAVATION, WET	25.00	CYS
0020	211-09267	STRUCTURE BACKFILL, TYPE 4	35.00	CYS
0021	601-06035	GUARDRAIL, RESET	100.00	LFT
0022	603-06040	FENCE, FARM FIELD, 47 IN.	375.00	LFT
0023	603-06060	FENCE, FARM FIELD, RESET	75.00	LFT
0024	615-06490	RIGHT-OF-WAY MARKER	4.00	EACH
0025	616-05688	RIPRAP, CLASS 1	247.00	TON
0026	616-05689	RIPRAP, CLASS 2	405.00	TON
0027	616-06405	RIPRAP, REVETMENT	8.00	TON
0028	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	597.00	SYS
0029	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00	EACH
0030	621-03787	SEED MIXTURE D	10.00	LBS
0031	621-06559	MULCHED SEEDING R	2500.00	SYS
0032	628-09402	FIELD OFFICE, B	6.00	MOS
0033	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0034	702-51015	CONCRETE, B, FOOTINGS	8.00	CYS
0035	702-92857	CONCRETE, C, SUBSTRUCTURE	8.00	CYS
0036	703-06028	REINFORCING BARS	1950.00	LBS
0037	709-51821	SURFACE SEAL	1.00	LS
0038	715-02246	PIPE END SECTION, DIA 48 IN.	1.00	EACH
0039	715-06004	CONCRETE ANCHOR, 48 IN.	1.00	EACH
0040	718-06529	OUTLET PROTECTOR, 2	1.00	EACH
0041	725-10198	LINER PIPE, THERMOPLASTIC, DEFORMED, 26.6-28.3 SFT	433.00	LFT
0042	725-10224	LINER PIPE, THERMOPLASTIC, CIRCULAR, 8.4-8.8 SFT	199.00	LFT
0043	725-10226	LINER PIPE, THERMOPLASTIC, CIRCULAR, 13.9-14.1 SFT	402.00	LFT
0044	725-10245	PERPETUATION, EXISTING PIPE	2.00	EACH
0045	725-11038	LINER PIPE, THERMOPLASTIC, CIRCULAR, 15.9-16.0 SFT	212.00	LFT
0046	801-06640	CONSTRUCTION SIGN, A	52.00	EACH
0047	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 251

Contract: R -38580-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL

0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	205-11626	PUMP AROUND	2.00	EACH
0011	205-12108	STORM WATER MANAGEMENT BUDGET	45400.00	DOL
0012	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0013	601-06035	GUARDRAIL, RESET	50.00	LFT
0014	616-05689	RIPRAP, CLASS 2	195.00	TON
0015	616-06405	RIPRAP, REVETMENT	147.00	TON
0016	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	393.00	SYS
0017	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0018	621-03787	SEED MIXTURE D	12.00	LBS
0019	621-06559	MULCHED SEEDING R	298.00	SYS
0020	628-09402	FIELD OFFICE, B	6.00	MOS
0021	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0022	725-10224	LINER PIPE, THERMOPLASTIC, CIRCULAR, 8.4-8.8 SFT	219.00	LFT
0023	725-10226	LINER PIPE, THERMOPLASTIC, CIRCULAR, 13.9-14.1 SFT	192.00	LFT
0024	801-06640	CONSTRUCTION SIGN, A	27.00	EACH
0025	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 261

Contract: R -38586-A

Section No.: 1 CULVERT CLEAN AND REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	203-02070	BORROW	1.50	CYS
0008	616-06405	RIPRAP, REVETMENT	6.30	TON
0009	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	21.00	SYS
0010	621-06574	SODDING	15.00	SYS
0011	628-09402	FIELD OFFICE, B	9.00	MOS
0012	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0013	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	67.00	LFT
0014	718-06529	OUTLET PROTECTOR, 2	286.00	EACH
0015	801-06640	CONSTRUCTION SIGN, A	14.00	EACH
0016	801-06710	FLASHING ARROW SIGN	560.00	DAY

0017	801-06775	MAINTAINING TRAFFIC	1.00	LS
------	-----------	---------------------	------	----

Call: 271

Contract: R -38748-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-02278	CURB, CONCRETE, REMOVE	2955.00	LFT
0011	202-06580	CONTAMINATED SOIL, REMOVE	10.00	CYS
0012	202-52710	SIDEWALK CONCRETE, REMOVE	527.00	SYS
0013	203-02000	EXCAVATION, COMMON	100.00	CYS
0014	205-12108	STORM WATER MANAGEMENT BUDGET	1200.00	DOL
0015	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0016	207-08266	SUBGRADE TREATMENT, TYPE III	82.00	SYS
0017	306-08034	MILLING, ASPHALT, 1 1/2 IN.	68.00	SYS
0018	306-08041	MILLING, PCCP	9388.00	SYS
0019	306-08595	MILLING, ASPHALT, 3 1/2 IN.	70335.00	SYS
0020	306-11872	MILLING, PROFILE	4166.00	SYS
0021	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	5795.00	TON
0022	401-07379	QC/QA-HMA, 3, 70, INTERMEDIATE, 12.5 mm	7961.00	TON
0023	401-10258	JOINT ADHESIVE, SURFACE	38812.00	LFT
0024	401-11785	LIQUID ASPHALT SEALANT	38812.00	LFT
0025	406-05520	ASPHALT FOR TACK COAT	35.00	TON
0026	506-06333	PCCP PATCHING, FULL DEPTH	2221.00	SYS
0027	604-06070	SIDEWALK, CONCRETE	393.00	SYS
0028	604-08086	CURB RAMP, CONCRETE	134.00	SYS
0029	604-12083	DETECTABLE WARNING SURFACES	33.00	SYS
0030	605-06120	CURB, CONCRETE	2987.00	LFT
0031	605-06140	CURB AND GUTTER, CONCRETE	188.00	LFT
0032	610-07487	HMA FOR APPROACHES, TYPE B	6.00	TON
0033	610-09108	PCCP FOR APPROACHES, 9 IN.	82.00	SYS
0034	628-09401	FIELD OFFICE, A	6.00	MOS
0035	628-11729	CELLULAR TELEPHONE, TYPE A	2.00	EACH
0036	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL

0037	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0038	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	15.00	MOS
0039	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0040	720-44000	CASTING, ADJUST TO GRADE	32.00	EACH
0041	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	57652.00	LFT
0042	801-06640	CONSTRUCTION SIGN, A	18.00	EACH
0043	801-06645	CONSTRUCTION SIGN, B	19.00	EACH
0044	801-06710	FLASHING ARROW SIGN	100.00	DAY
0045	801-06775	MAINTAINING TRAFFIC	1.00	LS
0046	801-07119	BARRICADE, III-B	48.00	LFT
0047	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	9888.00	LFT
0048	805-78785	SIGNAL DETECTOR HOUSING	24.00	EACH
0049	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	3299.00	LFT
0050	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	6005.00	LFT
0051	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	5698.00	LFT
0052	808-12032	GROOVING FOR PAVEMENT MARKINGS	35725.00	LFT
0053	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	24022.00	LFT
0054	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	537.00	LFT
0055	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	1869.00	LFT
0056	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	21.00	EACH
0057	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	9.00	EACH

Call: 281

Contract: R -38973-B

Section No.: 1 BIKE AND PEDESTRAIN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	202-02240	PAVEMENT REMOVAL	325.00	SYS
0011	203-02000	EXCAVATION, COMMON	561.00	CYS
0012	205-12108	STORM WATER MANAGEMENT BUDGET	5240.00	DOL
0013	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0014	207-08264	SUBGRADE TREATMENT, TYPE II	952.00	SYS
0015	207-08266	SUBGRADE TREATMENT, TYPE III	2187.00	SYS
0016	303-01180	COMPACTED AGGREGATE NO. 53	729.00	TON

0017	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0018	604-05528	HMA FOR SIDEWALK	329.00	TON
0019	604-08086	CURB RAMP, CONCRETE	90.00	SYS
0020	604-12083	DETECTABLE WARNING SURFACES	28.00	SYS
0021	605-06120	CURB, CONCRETE	263.00	LFT
0022	610-07487	HMA FOR APPROACHES, TYPE B	350.00	TON
0023	610-08446	PCCP FOR APPROACHES, 6 IN.	423.00	SYS
0024	611-06497	MAILBOX ASSEMBLY, SINGLE	3.00	EACH
0025	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0026	621-06545	FERTILIZER	1.00	TON
0027	621-06554	SEED MIXTURE U	276.00	LBS
0028	621-06565	MULCHING MATERIAL	3.00	TON
0029	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	18.00	LFT
0030	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	2.00	LFT
0031	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	99.00	SYS
0032	718-52610	AGGREGATE FOR UNDERDRAINS	2.00	CYS
0033	720-44296	INLET, CAP	1.00	EACH
0034	720-45030	INLET, E7	1.00	EACH
0035	801-06640	CONSTRUCTION SIGN, A	6.00	EACH
0036	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0037	801-06775	MAINTAINING TRAFFIC	1.00	LS
0038	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	265.00	LFT
0039	808-06716	LINE, REMOVE	313.00	LFT

Call: 291

Contract: R -39012-A

Section No.: 1 SIDEWALK IMPROVEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-02245	TREE 6 IN., REMOVE	3.00	EACH
0010	201-02250	TREE 10 IN., REMOVE	1.00	EACH
0011	201-02255	TREE 18 IN., REMOVE	2.00	EACH
0012	201-02260	TREE 30 IN., REMOVE	5.00	EACH
0013	201-02265	TREE 48 IN., REMOVE	1.00	EACH
0014	201-52370	CLEARING RIGHT OF WAY	1.00	LS

0015	202-02240	PAVEMENT REMOVAL	302.00	SYS
0016	202-52710	SIDEWALK CONCRETE, REMOVE	16.00	SYS
0017	203-02000	EXCAVATION, COMMON	601.00	CYS
0018	205-12108	STORM WATER MANAGEMENT BUDGET	7062.80	DOL
0019	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	926.00	SYS
0021	207-08266	SUBGRADE TREATMENT, TYPE III	721.00	SYS
0022	304-07490	HMA PATCHING, TYPE B	59.00	TON
0023	502-06627	PCCP, 6 IN.	879.00	SYS
0024	604-06070	SIDEWALK, CONCRETE	2701.00	SYS
0025	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0026	621-06560	MULCHED SEEDING U	133.00	SYS
0027	621-06570	TOPSOIL	617.00	CYS
0028	621-06575	SODDING, NURSERY	3528.00	SYS
0029	628-09401	FIELD OFFICE, A	6.00	MOS
0030	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0031	628-11977	COMPUTER SYSTEM	1.00	EACH
0032	720-01917	CASTING, MODIFIED	2.00	EACH
0033	720-44000	CASTING, ADJUST TO GRADE	6.00	EACH
0034	801-06640	CONSTRUCTION SIGN, A	8.00	EACH
0035	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0036	801-06775	MAINTAINING TRAFFIC	1.00	LS
0037	801-07119	BARRICADE, III-B	32.00	LFT

Call: 361

Contract: R -39561-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-99187	FENCE, FARM FIELD, REMOVE	320.00	LFT
0012	203-02000	EXCAVATION, COMMON	370.00	CYS
0013	203-04523	DEWATERING	1.00	LS
0014	205-12108	STORM WATER MANAGEMENT BUDGET	7543.00	DOL

0015	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0016	207-09935	SUBGRADE TREATMENT, TYPE IC	265.00	SYS
0017	211-09265	STRUCTURE BACKFILL, TYPE 2	325.00	CYS
0018	211-09268	STRUCTURE BACKFILL, TYPE 5	40.00	CYS
0019	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	287.00	SYS
0020	301-12232	COMPACTED AGGREGATE NO 5	45.00	CYS
0021	303-01180	COMPACTED AGGREGATE NO. 53	129.00	TON
0022	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	20.00	TON
0023	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	35.00	TON
0024	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	105.00	TON
0025	401-10258	JOINT ADHESIVE, SURFACE	70.00	LFT
0026	401-10259	JOINT ADHESIVE, INTERMEDIATE	70.00	LFT
0027	401-11785	LIQUID ASPHALT SEALANT	70.00	LFT
0028	406-05521	ASPHALT FOR TACK COAT	234.00	SYS
0029	603-06040	FENCE, FARM FIELD, 47 IN.	320.00	LFT
0030	615-06490	RIGHT-OF-WAY MARKER	8.00	EACH
0031	615-06505	MONUMENT, B	5.00	EACH
0032	616-05688	RIPRAP, CLASS 1	223.00	TON
0033	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	276.00	SYS
0034	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0035	621-06559	MULCHED SEEDING R	1200.00	SYS
0036	621-06574	SODDING	130.00	SYS
0037	714-11327	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 12 FT. X 6 FT.	78.00	LFT
0038	720-02442	PIPE PLUG EXISTING	2.00	EACH
0039	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0040	801-06625	DETOUR ROUTE MARKER ASSEMBLY	46.00	EACH
0041	801-06640	CONSTRUCTION SIGN, A	34.00	EACH
0042	801-06775	MAINTAINING TRAFFIC	1.00	LS
0043	801-07118	BARRICADE, III-A	72.00	LFT
0044	801-07119	BARRICADE, III-B	72.00	LFT
0045	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	5.00	LFT
0046	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	30.00	LFT
0047	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	140.00	LFT

Call: 371

Contract: R -40129-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	4.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	4.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL

0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0013	201-01015	CLEARING AND GRUBBING	1.00	LS
0014	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0015	202-01066	HYDRO DEMOLITION	254.00	SYS
0016	202-02240	PAVEMENT REMOVAL	230.00	SYS
0017	202-02271	HEADWALL, REMOVE	2.00	EACH
0018	202-07083	REMOVAL	1.00	LS
0019	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0020	203-02000	EXCAVATION, COMMON	270.00	CYS
0021	203-02070	BORROW	245.00	CYS
0022	203-08607	LINEAR GRADING	725.00	LFT
0023	205-11626	PUMP AROUND	6.00	EACH
0024	205-12108	STORM WATER MANAGEMENT BUDGET	9440.00	DOL
0025	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0026	206-51215	EXCAVATION, X	4.00	CYS
0027	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	185.00	CYS
0028	207-09935	SUBGRADE TREATMENT, TYPE IC	893.00	SYS
0029	211-06467	AGGREGATE FOR END BENT BACKFILL	72.00	CYS
0030	211-09264	STRUCTURE BACKFILL, TYPE 1	61.00	CYS
0031	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	10.00	CYS
0032	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	100.00	SYS
0033	301-12231	COMPACTED AGGREGATE NO 2	4.00	CYS
0034	301-12232	COMPACTED AGGREGATE NO 5	22.00	CYS
0035	301-12233	COMPACTED AGGREGATE NO 8	8.00	CYS
0036	302-07455	DENSE GRADED SUBBASE	42.00	CYS
0037	303-01180	COMPACTED AGGREGATE NO. 53	158.00	TON
0038	306-08042	MILLING, SCARIFICATION	499.00	SYS
0039	306-08043	MILLING, TRANSITION	856.00	SYS
0040	306-08159	MILLING, ASPHALT	294.00	SYS
0041	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	65.00	TON
0042	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	96.00	TON
0043	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	69.00	TON
0044	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	103.00	TON
0045	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	106.00	TON
0046	401-10258	JOINT ADHESIVE, SURFACE	962.00	LFT
0047	401-10259	JOINT ADHESIVE, INTERMEDIATE	932.00	LFT

0048	401-11785	LIQUID ASPHALT SEALANT	962.00	LFT
0049	406-05521	ASPHALT FOR TACK COAT	2670.00	SYS
0050	601-02241	GUARDRAIL, REMOVE	746.00	LFT
0051	601-09238	HAND DIG GUARDRAIL POST HOLES	9.00	EACH
0052	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	125.00	LFT
0053	601-12282	GUARDRAIL, MGS W-BEAM, 3 FT 1.5 IN SPACING	338.00	LFT
0054	601-12287	GUARDRAIL, MGS, LONG SPAN, TYPE 1	2.00	EACH
0055	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	2.00	EACH
0056	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0057	601-94689	GUARDRAIL, END TREATMENT, OS	6.00	EACH
0058	602-06729	BARRIER, DELINEATOR	8.00	EACH
0059	603-06060	FENCE, FARM FIELD, RESET	80.00	LFT
0060	603-97461	TEMPORARY FENCE	200.00	LFT
0061	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	247.00	SYS
0062	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0063	616-05688	RIPRAP, CLASS 1	54.00	TON
0064	616-05689	RIPRAP, CLASS 2	192.00	TON
0065	616-06405	RIPRAP, REVETMENT	385.00	TON
0066	616-06451	RIPRAP, UNIFORM	48.00	TON
0067	616-06941	GROUT	1.00	CYS
0068	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	689.00	SYS
0069	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	54.00	SYS
0070	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	418.00	SYS
0071	616-93772	INSPECTION HOLE	2.00	EACH
0072	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0073	621-02770	EROSION CONTROL BLANKET	645.00	SYS
0074	621-03787	SEED MIXTURE D	1.60	LBS
0075	621-06559	MULCHED SEEDING R	733.00	SYS
0076	621-06560	MULCHED SEEDING U	433.00	SYS
0077	621-06560	MULCHED SEEDING U	51.00	SYS
0078	621-06574	SODDING	42.00	SYS
0079	628-09402	FIELD OFFICE, B	10.00	MOS
0080	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0081	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0082	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0083	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	10.00	MOS
0084	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0085	628-11977	COMPUTER SYSTEM	1.00	EACH
0086	701-09556	PILE, HELICAL	10.00	EACH
0087	701-93790	CLEAN AND EPOXY COAT EXISTING PILES	1.00	LS
0088	702-04325	TEMPORARY SHORING	1.00	LS
0089	702-04325	TEMPORARY SHORING	1.00	LS
0090	702-51005	CONCRETE, A, SUBSTRUCTURE	65.50	CYS

0091	702-51863	FIELD DRILLED HOLE IN CONCRETE	172.00	EACH
0092	703-06028	REINFORCING BARS	2940.00	LBS
0093	703-06029	REINFORCING BARS, EPOXY COATED	30122.00	LBS
0094	703-08247	EMBEDDED GALVANIC ANODE	126.00	EACH
0095	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	12.00	EACH
0096	704-51002	CONCRETE, C, SUPERSTRUCTURE	18.30	CYS
0097	706-11600	RAILING, CONCRETE FC	11.40	CYS
0098	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0099	709-51821	SURFACE SEAL	1.00	LS
0100	711-51038	STRUCTURAL STEEL	1.00	LS
0101	715-05164	PIPE, TYPE 2, CIRCULAR, 66 IN.	58.00	LFT
0102	715-05841	CONCRETE ANCHOR, 60 IN.	1.00	EACH
0103	715-07150	CONCRETE ANCHOR, 84 IN.	1.00	EACH
0104	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	270.00	SFT
0105	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	9.00	CYS
0106	722-60824	SURFACE MILLING	286.00	SYS
0107	725-10203	PIPE LINER, CURED-IN-PLACE, 72 IN	99.00	LFT
0108	725-11288	PIPE LINER, CURED-IN-PLACE, 60"	173.00	LFT
0109	725-11399	PIPE LINER CURED-IN-PLACE 84 IN	82.00	LFT
0110	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00	EACH
0111	801-06625	DETOUR ROUTE MARKER ASSEMBLY	100.00	EACH
0112	801-06640	CONSTRUCTION SIGN, A	94.00	EACH
0113	801-06645	CONSTRUCTION SIGN, B	5.00	EACH
0114	801-06775	MAINTAINING TRAFFIC	1.00	LS
0115	801-07118	BARRICADE, III-A	96.00	LFT
0116	801-07119	BARRICADE, III-B	156.00	LFT
0117	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0118	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	515.00	LFT
0119	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	86.00	LFT
0120	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	686.00	LFT
0121	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	515.00	LFT

Call: 371

Contract: R -40129-A

Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0122	722-51842	BRIDGE DECK OVERLAY	286.00	SYS

Call: 371

Contract: R -40129-A

Section No.: 3 MICROSILICA CONCRETE OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit

0123 736-01061 BRIDGE DECK OVERLAY MICROSILICA

286.00 SYS

Call: 391

Contract: R -40350-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0012	202-96133	PIPE, REMOVE	225.00	LFT
0013	203-02000	EXCAVATION, COMMON	330.00	CYS
0014	205-12108	STORM WATER MANAGEMENT BUDGET	8176.00	DOL
0015	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0016	207-09935	SUBGRADE TREATMENT, TYPE IC	606.00	SYS
0017	211-09265	STRUCTURE BACKFILL, TYPE 2	269.00	CYS
0018	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	1045.00	SYS
0019	301-12232	COMPACTED AGGREGATE NO 5	236.00	CYS
0020	301-12234	COMPACTED AGGREGATE NO 53	76.00	CYS
0021	303-01180	COMPACTED AGGREGATE NO. 53	155.00	TON
0022	304-07493	WIDENING WITH HMA, TYPE B	112.00	TON
0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	838.00	SYS
0024	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	109.00	TON
0025	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	38.00	TON
0026	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	93.00	TON
0027	401-10258	JOINT ADHESIVE, SURFACE	999.00	LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	683.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	999.00	LFT
0030	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0031	601-01700	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 1	1.00	EACH
0032	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	1.00	EACH
0033	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	332.00	LFT
0034	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	1.00	EACH
0035	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	2.00	EACH
0036	601-12293	GUARDRAIL, MGS, STRUCTURE, TOP-MOUNTED POST	3.00	EACH

0037	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0038	611-08232	MAILBOX ASSEMBLY, SINGLE RESET	1.00	EACH
0039	615-06505	MONUMENT, B	2.00	EACH
0040	616-06405	RIPRAP, REVETMENT	166.00	TON
0041	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	221.00	SYS
0042	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0043	621-03787	SEED MIXTURE D	4.00	LBS
0044	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	10.00	EACH
0045	628-09402	FIELD OFFICE, B	6.00	MOS
0046	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0047	714-11103	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 16 FT X 7 FT	44.00	LFT
0048	715-05032	PIPE, TYPE 2, CIRCULAR, 15 IN.	20.00	LFT
0049	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	39.00	LFT
0050	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	71.00	LFT
0051	715-09064	VIDEO INSPECTION FOR PIPE	130.00	LFT
0052	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0053	715-46030	PIPE END SECTION, DIAMETER 30 IN.	1.00	EACH
0054	720-91973	MANHOLE, H4	2.00	EACH
0055	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0056	801-06625	DETOUR ROUTE MARKER ASSEMBLY	33.00	EACH
0057	801-06640	CONSTRUCTION SIGN, A	11.00	EACH
0058	801-06775	MAINTAINING TRAFFIC	1.00	LS
0059	801-07118	BARRICADE, III-A	64.00	LFT
0060	801-07119	BARRICADE, III-B	96.00	LFT
0061	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	98.00	LFT
0062	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	781.00	LFT
0063	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	391.00	LFT
0064	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	5.00	EACH
0065	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	5.00	EACH

Call: 401

Contract: R -40695-A

Section No.: 1 HIGH FRICTION SURFACE TREATMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	306-08042	MILLING, SCARIFICATION	8079.00	SYS
0008	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON

0009	617-12128	HIGH FRICTION SURFACE TREATMENT	8079.00	SYS
0010	801-06640	CONSTRUCTION SIGN, A	52.00	EACH
0011	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0012	801-06775	MAINTAINING TRAFFIC	1.00	LS
0013	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	7728.00	LFT
0014	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	7728.00	LFT

Call: 411

Contract: R -40696-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	203-02000	EXCAVATION, COMMON	5656.00	CYS
0013	203-02070	BORROW	5524.00	CYS
0014	205-12108	STORM WATER MANAGEMENT BUDGET	14204.00	DOL
0015	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0016	207-08264	SUBGRADE TREATMENT, TYPE II	2295.00	SYS
0017	207-08266	SUBGRADE TREATMENT, TYPE III	1321.00	SYS
0018	207-09934	SUBGRADE TREATMENT, TYPE IB	10042.00	SYS
0019	211-09264	STRUCTURE BACKFILL, TYPE 1	101.00	CYS
0020	211-09265	STRUCTURE BACKFILL, TYPE 2	155.00	CYS
0021	211-09268	STRUCTURE BACKFILL, TYPE 5	76.00	CYS
0022	301-12234	COMPACTED AGGREGATE NO 53	803.00	CYS
0023	302-06464	SUBBASE FOR PCCP	951.00	CYS
0024	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	456.00	TON
0025	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	759.00	TON
0026	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	1215.00	TON
0027	401-10258	JOINT ADHESIVE, SURFACE	4892.00	LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	4892.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	4892.00	LFT
0030	406-05521	ASPHALT FOR TACK COAT	12359.00	SYS
0031	501-09107	QC/QA-PCCP, 9 IN.	3306.00	SYS

0032	502-06457	PCCP, 9 IN.	222.00	SYS
0033	503-05240	D-1 CONTRACTION JOINT	2393.00	LFT
0034	503-05310	TERMINAL JOINT	399.00	LFT
0035	601-06035	GUARDRAIL, RESET	187.00	LFT
0036	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0037	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	56.00	LFT
0038	604-05528	HMA FOR SIDEWALK	238.00	TON
0039	604-08086	CURB RAMP, CONCRETE	63.00	SYS
0040	604-12083	DETECTABLE WARNING SURFACES	18.00	SYS
0041	605-04742	WALL	1.00	LS
0042	605-06095	CURB, INTEGRAL B CONCRETE	332.00	LFT
0043	605-06100	CURB, INTEGRAL C CONCRETE	1641.00	LFT
0044	605-06120	CURB, CONCRETE	285.00	LFT
0045	605-06255	CENTER CURB, D CONCRETE	28.00	SYS
0046	605-52807	CURB AND GUTTER, COMBINED	426.00	LFT
0047	605-52807	CURB AND GUTTER, COMBINED	390.00	LFT
0048	610-07487	HMA FOR APPROACHES, TYPE B	631.00	TON
0049	611-08233	MAILBOX ASSEMBLY, DOUBLE RESET	1.00	EACH
0050	616-05688	RIPRAP, CLASS 1	84.00	TON
0051	616-06405	RIPRAP, REVETMENT	80.00	TON
0052	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	397.00	SYS
0053	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0054	621-06545	FERTILIZER	1.00	TON
0055	621-06554	SEED MIXTURE U	425.00	LBS
0056	621-06565	MULCHING MATERIAL	5.00	TON
0057	621-06567	WATER	12.00	KGAL
0058	621-06575	SODDING, NURSERY	3273.00	SYS
0059	628-09401	FIELD OFFICE, A	6.00	MOS
0060	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0061	628-11977	COMPUTER SYSTEM	1.00	EACH
0062	714-11174	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 4 FT.	126.00	LFT
0063	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	1200.00	LFT
0064	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	90.00	LFT
0065	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	236.00	LFT
0066	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	26.00	LFT
0067	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	89.00	LFT
0068	715-05172	PIPE, TYPE 3, CIRCULAR, 21 IN.	48.00	LFT
0069	715-05424	PIPE, SLOTTED DRAIN, 18 IN.	55.00	LFT
0070	715-09064	VIDEO INSPECTION FOR PIPE	236.00	LFT
0071	715-46000	PIPE END SECTION, DIAMETER 12 IN.	5.00	EACH
0072	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0073	715-46010	PIPE END SECTION, DIAMETER 18 IN.	4.00	EACH
0074	715-46015	PIPE END SECTION, DIAMETER 21 IN.	2.00	EACH

0075	718-06531	OUTLET PROTECTOR, 3	1.00	EACH
0076	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	1200.00	LFT
0077	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	1003.00	SYS
0078	718-52610	AGGREGATE FOR UNDERDRAINS	107.00	CYS
0079	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0080	720-45410	MANHOLE, C4	1.00	EACH
0081	720-98174	INLET, B15	6.00	EACH
0082	720-98555	INLET, C15	2.00	EACH
0083	801-03290	CONSTRUCTION SIGN, C	6.00	EACH
0084	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00	EACH
0085	801-06625	DETOUR ROUTE MARKER ASSEMBLY	47.00	EACH
0086	801-06640	CONSTRUCTION SIGN, A	14.00	EACH
0087	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0088	801-06775	MAINTAINING TRAFFIC	1.00	LS
0089	801-07119	BARRICADE, III-B	192.00	LFT
0090	802-04314	SIGN	1.00	EACH
0091	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	265.50	LFT
0092	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	148.00	LFT
0093	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	13.00	EACH
0094	802-07060	SIGN, SHEET, RELOCATE	7.00	EACH
0095	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	105.25	SFT
0096	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	56.95	SFT
0097	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	45.26	SFT
0098	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0099	807-02193	LIGHT STANDARD FOUNDATION 3 FT DIAMETER X 8 FT	13.00	EACH
0100	807-02194	SERVICE POINT II MODIFIED	1.00	EACH
0101	807-02370	LIGHT STRUCTURE, REMOVE AND RESET	5.00	EACH
0102	807-03951	LIGHT POLE ORNAMENTAL	13.00	EACH
0103	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	595.00	LFT
0104	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1231.00	LFT
0105	807-86910	CONNECTOR KIT, UNFUSED	13.00	EACH
0106	807-86915	CONNECTOR KIT, FUSED	13.00	EACH
0107	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	26.00	EACH
0108	807-86930	INSULATION LINK, NON-WATERPROOFED	32.00	EACH
0109	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	595.00	LFT
0110	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2333.00	LFT
0111	808-10032	LINE, MULTI-COMPONENT, DOTTED, WHITE, 8 IN.	68.00	LFT
0112	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	167.00	LFT
0113	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1115.00	LFT
0114	808-10042	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW 12 IN.	30.00	LFT
0115	808-10097	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 27 IN.	79.00	LFT
0116	808-10099	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 24 IN.	190.00	LFT
0117	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	23.00	LFT

0118	808-11493	LINE, THERMOPLASTIC, DOTTED, YELLOW, 4 IN.	33.00	LFT
0119	808-12032	GROOVING FOR PAVEMENT MARKINGS	8080.00	LFT
0120	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4341.00	LFT
0121	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	47.00	LFT
0122	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	46.00	LFT
0123	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	3.00	EACH

Call: 421

Contract: R -40705-A

Section No.: 1 NOISE ABATEMENT

Line Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	620-01754	SOUND BARRIER PANELS GROUND MOUNTED TYPE	2466.00	SFT
0009	620-01754	SOUND BARRIER PANELS GROUND MOUNTED TYPE	741.00	SFT
0010	620-01754	SOUND BARRIER PANELS GROUND MOUNTED TYPE	435.00	SFT
0011	620-08422	SOUND BARRIER	1.00	LS
0012	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 431

Contract: R -40709-A

Section No.: 1 ENVIRONMENTAL MITIGATION

Line Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0006	201-01015	CLEARING AND GRUBBING	1.00	LS
0007	203-02000	EXCAVATION, COMMON	20000.00	CYS
0008	205-12108	STORM WATER MANAGEMENT BUDGET	22587.50	DOL
0009	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0010	303-01180	COMPACTED AGGREGATE NO. 53	112.00	TON
0011	616-06405	RIPRAP, REVETMENT	58.00	TON
0012	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	230.00	SYS
0013	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0014	621-02318	SEED MIXTURE, PRAIRIE GRASS	40.00	LBS

0015	621-02770	EROSION CONTROL BLANKET	9908.00	SYS
0016	621-03909	SEED MIXTURE, NATIVE	44.00	LBS
0017	621-06567	WATER	411.00	KGAL
0018	621-09399	SEED MIXTURE, WET MESIC	107.00	LBS
0019	622-05639	PLANT, DECIDUOUS SHRUB, 18 TO 24 IN.	394.00	EACH
0020	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	797.00	EACH
0021	622-52436	SIGN, DO NOT MOW OR SPRAY	22.00	EACH
0022	624-92647	HERBICIDE TREATMENT	1.00	ACRE
0023	628-09409	MOBILE INTERNET SERVICE	15.00	MOS
0024	628-11977	COMPUTER SYSTEM	1.00	EACH
0025	715-01765	PIPE END SECTION, PRECAST CONCRETE, 12 IN	1.00	EACH
0026	719-05439	PIPE, DRAIN. TILE TERMINAL SECTION, 6 IN.	60.00	LFT

Call: 441

Contract: R -40757-A

Section No.: 1 SMALL STRUCTURE - NEW

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-96133	PIPE, REMOVE	105.00	LFT
0013	202-99187	FENCE, FARM FIELD, REMOVE	244.00	LFT
0014	203-02000	EXCAVATION, COMMON	20980.00	CYS
0015	205-12108	STORM WATER MANAGEMENT BUDGET	57000.00	DOL
0016	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0017	207-08264	SUBGRADE TREATMENT, TYPE II	472.00	SYS
0018	207-09934	SUBGRADE TREATMENT, TYPE IB	18634.00	SYS
0019	211-09264	STRUCTURE BACKFILL, TYPE 1	159.00	CYS
0020	211-09268	STRUCTURE BACKFILL, TYPE 5	82.00	CYS
0021	301-12232	COMPACTED AGGREGATE NO 5	36.00	CYS
0022	301-12234	COMPACTED AGGREGATE NO 53	2512.00	CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	1793.00	TON
0024	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1286.00	SYS
0025	306-08043	MILLING, TRANSITION	337.00	SYS

0026	401-06264	PROFILOGRAPH, HMA	1.00	LS
0027	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1500.00	TON
0028	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	2352.00	TON
0029	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	2946.00	TON
0030	401-10258	JOINT ADHESIVE, SURFACE	6173.00	LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	5507.00	LFT
0032	401-11785	LIQUID ASPHALT SEALANT	6173.00	LFT
0033	406-05520	ASPHALT FOR TACK COAT	9.00	TON
0034	606-07484	MILLED HMA CORRUGATIONS	3792.00	LFT
0035	610-07487	HMA FOR APPROACHES, TYPE B	143.00	TON
0036	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00	EACH
0037	615-06490	RIGHT-OF-WAY MARKER	42.00	EACH
0038	615-06505	MONUMENT, B	10.00	EACH
0039	616-06405	RIPRAP, REVETMENT	853.00	TON
0040	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1912.00	SYS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0042	621-06545	FERTILIZER	2.00	TON
0043	621-06559	MULCHED SEEDING R	22446.00	SYS
0044	621-06567	WATER	5.90	KGAL
0045	621-06574	SODDING	1477.00	SYS
0046	622-52436	SIGN, DO NOT MOW OR SPRAY	6.00	EACH
0047	628-09402	FIELD OFFICE, B	12.00	MOS
0048	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0049	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0050	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	12.00	MOS
0051	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0052	714-11091	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 18 FT. X 4 FT.	97.00	LFT
0053	715-05052	PIPE, TYPE 4, CIRCULAR, 12 IN.	50.00	LFT
0054	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	191.00	LFT
0055	715-05125	PIPE, TYPE 1, CIRCULAR, 30 IN.	70.00	LFT
0056	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	202.00	LFT
0057	715-46005	PIPE END SECTION, DIAMETER 15 IN.	16.00	EACH
0058	715-46030	PIPE END SECTION, DIAMETER 30 IN.	2.00	EACH
0059	801-04308	ROAD CLOSURE SIGN ASSEMBLY	14.00	EACH
0060	801-06625	DETOUR ROUTE MARKER ASSEMBLY	26.00	EACH
0061	801-06640	CONSTRUCTION SIGN, A	13.00	EACH
0062	801-06775	MAINTAINING TRAFFIC	1.00	LS
0063	801-07118	BARRICADE, III-A	144.00	LFT
0064	801-07119	BARRICADE, III-B	192.00	LFT
0065	802-04089	SIGN, SHEET, REMOVE	21.00	EACH
0066	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	374.40	LFT
0067	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	1.00	EACH
0068	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	190.80	SFT

0069	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	11310.00	LFT
0070	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	11438.00	LFT
0071	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	142.00	LFT
0072	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	103.00	EACH

Call: 451

Contract: R -40758-A

Section No.: 1 SIDEWALK IMPROVEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	3.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	6.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-02278	CURB, CONCRETE, REMOVE	27.00	LFT
0011	202-02279	CURB AND GUTTER, REMOVE	31.00	LFT
0012	202-52710	SIDEWALK CONCRETE, REMOVE	10.00	SYS
0013	203-02000	EXCAVATION, COMMON	15.00	CYS
0014	203-02055	EMBANKMENT	43.00	CYS
0015	205-12108	STORM WATER MANAGEMENT BUDGET	1.00	DOL
0016	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0017	214-11796	GEOGRID, TYPE IB	40.00	SYS
0018	301-12233	COMPACTED AGGREGATE NO 8	16.00	CYS
0019	301-12234	COMPACTED AGGREGATE NO 53	2.00	CYS
0020	604-02007	SIDEWALK, CONCRETE, RECONSTRUCT	199.20	SYS
0021	604-06070	SIDEWALK, CONCRETE	82.50	SYS
0022	604-07092	BED COURSE MATERIAL	2.50	TON
0023	604-08086	CURB RAMP, CONCRETE	224.90	SYS
0024	604-12083	DETECTABLE WARNING SURFACES	33.50	SYS
0025	604-95344	HAND RAIL, PEDESTRIAN	54.00	LFT
0026	605-06120	CURB, CONCRETE	32.00	LFT
0027	605-06140	CURB AND GUTTER, CONCRETE	31.00	LFT
0028	621-06560	MULCHED SEEDING U	288.00	SYS
0029	621-06567	WATER	20.00	kGAL
0030	628-09402	FIELD OFFICE, B	12.00	MOS
0031	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0032	711-02554	PEDESTRIAN BRIDGE	1.00	LS
0033	715-05407	PIPE, END BENT DRAIN, 6 IN.	54.00	LFT

0034	732-11812	MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	64.00	SFT
0035	801-06640	CONSTRUCTION SIGN, A	38.00	EACH
0036	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
0037	801-06775	MAINTAINING TRAFFIC	1.00	LS
0038	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0039	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.00	EACH
0040	805-01842	HANDHOLE SIGNAL TYPE 1	9.00	EACH
0041	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	644.00	LFT
0042	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	21.00	EACH
0043	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	22.00	EACH
0044	805-05405	SIGNAL POLE, PEDESTAL, 4FT	1.00	EACH
0045	805-11817	PEDESTRIAN PUSH BUTTON, APS	22.00	EACH
0046	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	2217.00	LFT
0047	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	11222.00	LFT
0048	805-99162	SIGNAL POLE, PEDESTAL, 11 FT	21.00	EACH
0049	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	1510.00	LFT
0050	808-06716	LINE, REMOVE	559.00	LFT
0051	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	223.00	LFT
0052	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	678.00	LFT

Call: 461

Contract: R -40824-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	202-02272	PAVED SIDE DITCH, REMOVE	16.00	LFT
0011	203-08607	LINEAR GRADING	100.00	LFT
0012	205-11626	PUMP AROUND	9.00	EACH
0013	205-12108	STORM WATER MANAGEMENT BUDGET	15139.00	DOL
0014	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0015	616-05688	RIPRAP, CLASS 1	254.00	TON
0016	616-06405	RIPRAP, REVETMENT	157.00	TON
0017	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	280.00	SYS
0018	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	296.00	SYS

0019	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00	EACH
0020	621-06559	MULCHED SEEDING R	489.00	SYS
0021	628-09402	FIELD OFFICE, B	8.00	MOS
0022	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0023	702-90915	CONCRETE, CLASS, A	14.00	CYS
0024	703-06029	REINFORCING BARS, EPOXY COATED	1081.00	LBS
0025	715-11643	PIPE END SECTION, ENERGY DISSIPATOR	1.00	EACH
0026	720-08239	MANHOLE, J7 MODIFIED	1.00	EACH
0027	725-08296	PIPE LINER, CURED-IN-PLACE, 48 IN	488.00	LFT
0028	725-10203	PIPE LINER, CURED-IN-PLACE, 72 IN	220.00	LFT
0029	801-06640	CONSTRUCTION SIGN, A	27.00	EACH
0030	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 501

Contract: RS-37819-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02271	HEADWALL, REMOVE	2.00	EACH
0014	202-96133	PIPE, REMOVE	131.00	LFT
0015	203-02000	EXCAVATION, COMMON	50.00	CYS
0016	203-08607	LINEAR GRADING	63360.00	LFT
0017	205-11626	PUMP AROUND	2.00	EACH
0018	205-12108	STORM WATER MANAGEMENT BUDGET	2400.00	DOL
0019	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0020	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	355.00	CYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	1397.00	SYS
0022	211-02050	B BORROW	13.00	CYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	120.00	CYS
0024	211-09268	STRUCTURE BACKFILL, TYPE 5	45.00	CYS
0025	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	120.00	SYS

0026	301-12232	COMPACTED AGGREGATE NO 5	91.00	CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	2631.00	TON
0028	304-07491	HMA PATCHING, TYPE C	4605.00	TON
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	172301.00	SYS
0030	306-08432	MILLING, APPROACH	12672.00	SYS
0031	401-06264	PROFILOGRAPH, HMA	1.00	LS
0032	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	14226.00	TON
0033	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	17.00	TON
0034	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	40.00	TON
0035	401-10258	JOINT ADHESIVE, SURFACE	77206.00	LFT
0036	401-10259	JOINT ADHESIVE, INTERMEDIATE	49.00	LFT
0037	401-11785	LIQUID ASPHALT SEALANT	77045.00	LFT
0038	406-05520	ASPHALT FOR TACK COAT	48.20	TON
0039	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	7.00	TON
0040	412-09355	FOG SEAL	2900.00	SYS
0041	606-07484	MILLED HMA CORRUGATIONS	57566.00	LFT
0042	610-07487	HMA FOR APPROACHES, TYPE B	1045.00	TON
0043	615-06505	MONUMENT, B	4.00	EACH
0044	616-05688	RIPRAP, CLASS 1	181.00	TON
0045	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	182.00	SYS
0046	628-09402	FIELD OFFICE, B	6.00	MOS
0047	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0048	702-02925	WATERPROOFING MEMBRANE SYSTEM	1585.00	SFT
0049	714-11178	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 8 FT. X 5 FT.	53.00	LFT
0050	714-11191	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 5 FT. X 4 FT.	39.00	LFT
0051	714-96273	HEADWALL RECONSTRUCT	1.00	LS
0052	715-05032	PIPE, TYPE 2, CIRCULAR, 15 IN.	36.00	LFT
0053	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0054	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00	EACH
0055	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	6388.00	LFT
0056	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6388.00	LFT
0057	801-06625	DETOUR ROUTE MARKER ASSEMBLY	63.00	EACH
0058	801-06640	CONSTRUCTION SIGN, A	74.00	EACH
0059	801-06775	MAINTAINING TRAFFIC	1.00	LS
0060	801-07118	BARRICADE, III-A	60.00	LFT
0061	801-07119	BARRICADE, III-B	80.00	LFT
0062	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0063	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	2.00	EACH
0064	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	419.00	LFT
0065	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	11110.00	LFT
0066	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	125121.00	LFT
0067	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	55441.00	LFT
0068	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS

0069	808-12032	GROOVING FOR PAVEMENT MARKINGS	714.00	LFT
0070	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	20.00	LFT
0071	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	275.00	LFT
0072	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	36.00	LFT
0073	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1146.00	EACH
0074	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1146.00	EACH

Call: 511

Contract: RS-38646-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	64.00	SYS
0014	202-02273	CENTER CURB, CONCRETE, REMOVE	248.00	SYS
0015	202-02278	CURB, CONCRETE, REMOVE	2949.00	LFT
0016	202-02279	CURB AND GUTTER, REMOVE	476.00	LFT
0017	202-52710	SIDEWALK CONCRETE, REMOVE	2092.00	SYS
0018	202-90277	DETECTOR HOUSING, REMOVE	27.00	EACH
0019	203-02000	EXCAVATION, COMMON	664.00	CYS
0020	203-08607	LINEAR GRADING	1864.00	LFT
0021	205-12108	STORM WATER MANAGEMENT BUDGET	11954.00	DOL
0022	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	4636.00	SYS
0024	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	4.00	EACH
0025	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	11.00	CYS
0026	302-06464	SUBBASE FOR PCCP	180.00	CYS
0027	302-07455	DENSE GRADED SUBBASE	216.00	CYS
0028	303-01180	COMPACTED AGGREGATE NO. 53	10.00	TON
0029	304-07783	HMA PATCHING, TYPE D	1243.00	TON
0030	304-07789	WIDENING WITH HMA, TYPE D	9.00	TON
0031	306-08034	MILLING, ASPHALT, 1 1/2 IN.	164225.00	SYS

0032	306-08432	MILLING, APPROACH	6773.00	SYS
0033	401-06264	PROFILOGRAPH, HMA	1.00	LS
0034	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	13549.00	TON
0035	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	232.00	TON
0036	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	296.00	TON
0037	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	736.00	TON
0038	401-10258	JOINT ADHESIVE, SURFACE	108808.00	LFT
0039	401-11785	LIQUID ASPHALT SEALANT	108808.00	LFT
0040	406-05520	ASPHALT FOR TACK COAT	45.00	TON
0041	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	16.00	TON
0042	503-03489	RETROFITTED TIE BARS	830.00	EACH
0043	503-05240	D-1 CONTRACTION JOINT	528.00	LFT
0044	506-06333	PCCP PATCHING, FULL DEPTH	2366.00	SYS
0045	507-08271	JOINTS IN PCCP, FILLED	26500.00	LFT
0046	507-12191	JOINT REPAIR, PARTIAL DEPTH	4200.00	SFT
0047	604-06070	SIDEWALK, CONCRETE	511.00	SYS
0048	604-08086	CURB RAMP, CONCRETE	1793.00	SYS
0049	604-12083	DETECTABLE WARNING SURFACES	214.00	SYS
0050	605-06120	CURB, CONCRETE	84.00	LFT
0051	605-06140	CURB AND GUTTER, CONCRETE	3333.00	LFT
0052	605-06245	CENTER CURB, B CONCRETE	221.00	SYS
0053	610-07788	HMA FOR APPROACHES, TYPE D	559.00	TON
0054	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0055	621-06553	SEED MIXTURE R	20.00	LBS
0056	621-06565	MULCHING MATERIAL	2.00	TON
0057	621-06570	TOPSOIL	96.00	CYS
0058	621-06575	SODDING, NURSERY	1153.00	SYS
0059	628-09402	FIELD OFFICE, B	12.00	MOS
0060	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0061	709-51821	SURFACE SEAL	1.00	LS
0062	709-51821	SURFACE SEAL	1.00	LS
0063	710-09158	PATCHING CONCRETE STRUCTURES	60.00	SFT
0064	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	2.00	EACH
0065	720-44000	CASTING, ADJUST TO GRADE	8.00	EACH
0066	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0067	720-44000	CASTING, ADJUST TO GRADE	2.00	EACH
0068	720-44000	CASTING, ADJUST TO GRADE	16.00	EACH
0069	720-44000	CASTING, ADJUST TO GRADE	52.00	EACH
0070	720-44000	CASTING, ADJUST TO GRADE	5.00	EACH
0071	720-44020	CASTING, 3, FURNISH AND ADJUST TO GRADE	4.00	EACH
0072	720-44045	CASTING, 8, FURNISH AND ADJUST TO GRADE	13.00	EACH
0073	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	235.00	SFT
0074	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1445.00	SFT

0075	727-90308	EPOXY INJECTION, CRACK PREPARATION	1128.00	LFT
0076	727-90309	EPOXY INJECTION, EPOXY MATERIAL	32.00	GAL
0077	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0078	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0079	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	4849.00	SYS
0080	801-03290	CONSTRUCTION SIGN, C	6.00	EACH
0081	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	22540.00	LFT
0082	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	38091.00	LFT
0083	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	2144.00	LFT
0084	801-06217	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 6 IN.	4697.00	LFT
0085	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	2144.00	LFT
0086	801-06640	CONSTRUCTION SIGN, A	163.00	EACH
0087	801-06645	CONSTRUCTION SIGN, B	91.00	EACH
0088	801-06710	FLASHING ARROW SIGN	510.00	DAY
0089	801-06775	MAINTAINING TRAFFIC	1.00	LS
0090	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00	EACH
0091	801-07118	BARRICADE, III-A	224.00	LFT
0092	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	3177.00	LFT
0093	801-11598	ARIES FIELD PROCESSOR FOR PCMS	7.00	EACH
0094	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	7.00	EACH
0095	801-12031	TEMPORARY PORTABLE RUMBLE STRIPS	160.00	DAY
0096	801-12348	TEMPORARY WORKSITE SPEED DISPLAY ASSEMBLY	1.00	EACH
0097	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	36.00	SFT
0098	805-01842	HANDHOLE SIGNAL TYPE 1	1.00	EACH
0099	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	765.00	LFT
0100	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	24.00	EACH
0101	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	25.00	EACH
0102	805-05405	SIGNAL POLE, PEDESTAL, 4FT	16.00	EACH
0103	805-09451	SIGNAL POLE, PEDESTAL, 15 FT	9.00	EACH
0104	805-10107	WIRELESS MAGNETOMETER DETECTOR	106.00	EACH
0105	805-11817	PEDESTRIAN PUSH BUTTON, APS	38.00	EACH
0106	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	10895.00	LFT
0107	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	5490.00	LFT
0108	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	3525.00	LFT
0109	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	10705.00	LFT
0110	805-78785	SIGNAL DETECTOR HOUSING	29.00	EACH
0111	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	3880.00	LFT
0112	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	969.00	LFT
0113	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2371.00	LFT
0114	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2434.00	LFT
0115	808-06716	LINE, REMOVE	7932.00	LFT
0116	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0117	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	16760.00	LFT

0118	808-10032	LINE, MULTI-COMPONENT, DOTTED, WHITE, 8 IN.	153.00	LFT
0119	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	14092.00	LFT
0120	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	12264.00	LFT
0121	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	1680.00	LFT
0122	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	760.00	LFT
0123	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	2144.00	LFT
0124	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	8.00	EACH
0125	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	13.00	EACH
0126	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	4697.00	LFT
0127	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	82.00	EACH
0128	808-10102	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW, 8 IN.	130.00	LFT
0129	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	138.00	LFT
0130	808-12032	GROOVING FOR PAVEMENT MARKINGS	45709.00	LFT
0131	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	126.00	EACH
0132	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	6.00	EACH

Call: 521

Contract: RS-38668-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	12.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	8.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0010	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0011	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0012	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0014	202-02279	CURB AND GUTTER, REMOVE	1912.00	LFT
0015	202-06580	CONTAMINATED SOIL, REMOVE	5.00	CYS
0016	202-52710	SIDEWALK CONCRETE, REMOVE	1397.00	SYS
0017	202-90277	DETECTOR HOUSING, REMOVE	48.00	EACH
0018	202-92222	TESTING FOR CONTAMINATED MATERIALS,	4.00	EACH
0019	202-93996	PEDESTAL BASE, REMOVE	2.00	EACH
0020	205-12108	STORM WATER MANAGEMENT BUDGET	20000.00	DOL
0021	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	700.00	SYS

0023	303-01180	COMPACTED AGGREGATE NO. 53	186.00	TON
0024	304-07491	HMA PATCHING, TYPE C	648.00	TON
0025	306-08034	MILLING, ASPHALT, 1 1/2 IN.	74549.00	SYS
0026	306-08432	MILLING, APPROACH	6159.00	SYS
0027	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	6150.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	37228.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	37228.00	LFT
0030	406-05520	ASPHALT FOR TACK COAT	21.00	TON
0031	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	10.00	TON
0032	507-07479	HMA PARTIAL DEPTH PATCH	104.00	TON
0033	604-06070	SIDEWALK, CONCRETE	195.00	SYS
0034	604-08086	CURB RAMP, CONCRETE	1431.00	SYS
0035	604-12083	DETECTABLE WARNING SURFACES	195.00	SYS
0036	605-06140	CURB AND GUTTER, CONCRETE	1922.00	LFT
0037	610-07488	HMA FOR APPROACHES, TYPE C	509.00	TON
0038	615-06525	CASTING ADJUST TO GRADE, MONUMENT	13.00	EACH
0039	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0040	621-06567	WATER	3.00	KGAL
0041	621-06575	SODDING, NURSERY	419.00	SYS
0042	628-09402	FIELD OFFICE, B	12.00	MOS
0043	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0044	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0045	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0046	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0047	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	24.00	MOS
0048	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0049	628-11977	COMPUTER SYSTEM	1.00	EACH
0050	720-44000	CASTING, ADJUST TO GRADE	24.00	EACH
0051	720-44080	CASTING, 15, FURNISH AND ADJUST TO GRADE	25.00	EACH
0052	732-11810	MODULAR BLOCK WALL	30.00	SFT
0053	732-11811	MODULAR BLOCK WALL ERECTION	30.00	SFT
0054	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0055	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3878.00	LFT
0056	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	1249.00	LFT
0057	801-06640	CONSTRUCTION SIGN, A	64.00	EACH
0058	801-06710	FLASHING ARROW SIGN	480.00	DAY
0059	801-06775	MAINTAINING TRAFFIC	1.00	LS
0060	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0061	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	38.00	SFT
0062	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	5.00	EACH
0063	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1500.00	LFT
0064	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	40.00	EACH
0065	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	24.00	EACH

0066	805-04602	CONTROLLER, REWIRE	2.00	EACH
0067	805-05405	SIGNAL POLE, PEDESTAL, 4FT	8.00	EACH
0068	805-11817	PEDESTRIAN PUSH BUTTON, APS	40.00	EACH
0069	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	23250.00	LFT
0070	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	6898.00	LFT
0071	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	3449.00	LFT
0072	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	2066.00	LFT
0073	805-78785	SIGNAL DETECTOR HOUSING	48.00	EACH
0074	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	8370.00	LFT
0075	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	16.00	EACH
0076	805-93611	MAGNETOMETER DETECTOR	68.00	EACH
0077	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	4317.00	LFT
0078	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	8584.00	LFT
0079	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0080	808-12032	GROOVING FOR PAVEMENT MARKINGS	35258.00	LFT
0081	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE 4 IN.	760.00	LFT
0082	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	75.00	LFT
0083	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	22282.00	LFT
0084	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	1249.00	LFT
0085	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	6200.00	LFT
0086	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	39.00	EACH
0087	808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC R X R	4.00	EACH
0088	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	145.00	EACH
0089	808-95638	CENTER CURB PAINTING	460.00	SFT
0090	808-95933	CURB, PAINTING, YELLOW	5404.00	LFT

Call: 531

Contract: RS-38677-A

Section No.: 1 CONCRETE PAVEMENT RESTORATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	202-02240	PAVEMENT REMOVAL	29.50	SYS
0010	207-09935	SUBGRADE TREATMENT, TYPE IC	1228.00	SYS
0011	211-09266	STRUCTURE BACKFILL, TYPE 3	615.00	CYS
0012	302-06464	SUBBASE FOR PCCP	308.00	CYS

0013	304-07491	HMA PATCHING, TYPE C	207.10	TON
0014	304-07783	HMA PATCHING, TYPE D	31.00	TON
0015	306-08038	MILLING, ASPHALT, 4 IN.	136.00	SYS
0016	406-05521	ASPHALT FOR TACK COAT	1300.00	SYS
0017	503-03489	RETROFITTED TIE BARS	120.00	EACH
0018	503-05240	D-1 CONTRACTION JOINT	288.00	LFT
0019	503-05310	TERMINAL JOINT	1609.00	LFT
0020	503-09261	PCCP STITCHING	16.00	EACH
0021	506-06333	PCCP PATCHING, FULL DEPTH	1228.00	SYS
0022	507-07505	RETROFIT LOAD TRANSFER	120.00	EACH
0023	507-08272	JOINTS IN PCCP, SAW AND SEAL	1536.00	LFT
0024	507-12099	PCCP GROOVING	284982.00	SYS
0025	602-06729	BARRIER, DELINEATOR	128.00	EACH
0026	609-06260	REINFORCED CONCRETE BRIDGE APPROACH, 13 IN.	28.60	SYS
0027	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	2753.00	SYS
0028	702-51863	FIELD DRILLED HOLE IN CONCRETE	55.00	EACH
0029	703-06029	REINFORCING BARS, EPOXY COATED	2144.00	LBS
0030	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	8.00	EACH
0031	709-51821	SURFACE SEAL	1.00	LS
0032	709-51821	SURFACE SEAL	1.00	LS
0033	709-51821	SURFACE SEAL	1.00	LS
0034	709-51821	SURFACE SEAL	1.00	LS
0035	709-51821	SURFACE SEAL	1.00	LS
0036	709-51821	SURFACE SEAL	1.00	LS
0037	709-51821	SURFACE SEAL	1.00	LS
0038	709-51821	SURFACE SEAL	1.00	LS
0039	710-09158	PATCHING CONCRETE STRUCTURES	260.00	SFT
0040	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	2309.00	SFT
0041	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	25636.00	SYS
0042	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	41.00	EACH
0043	801-03290	CONSTRUCTION SIGN, C	14.00	EACH
0044	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0045	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	101799.00	LFT
0046	801-06625	DETOUR ROUTE MARKER ASSEMBLY	63.00	EACH
0047	801-06640	CONSTRUCTION SIGN, A	247.00	EACH
0048	801-06710	FLASHING ARROW SIGN	63.00	DAY
0049	801-06775	MAINTAINING TRAFFIC	1.00	LS
0050	801-07118	BARRICADE, III-A	552.00	LFT
0051	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	17.00	EACH
0052	801-12042	TRUCK MOUNTED ATTENUATOR	135.00	DAY
0053	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	2060.00	LFT
0054	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	3174.00	LFT
0055	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	3174.00	LFT

0056	808-06716	LINE, REMOVE	41035.00	LFT
0057	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	13020.00	LFT
0058	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	14148.00	LFT
0059	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	12861.00	LFT
0060	808-12032	GROOVING FOR PAVEMENT MARKINGS	28490.00	LFT
0061	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	119.00	EACH
0062	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	29.00	EACH

Call: 541

Contract: RS-39149-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-02278	CURB, CONCRETE, REMOVE	10.00	LFT
0011	202-52710	SIDEWALK CONCRETE, REMOVE	5.00	SYS
0012	211-09266	STRUCTURE BACKFILL, TYPE 3	50.00	CYS
0013	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	225.00	SYS
0014	304-07491	HMA PATCHING, TYPE C	356.00	TON
0015	306-08034	MILLING, ASPHALT, 1 1/2 IN.	153168.00	SYS
0016	306-08043	MILLING, TRANSITION	200.00	SYS
0017	306-08432	MILLING, APPROACH	6484.00	SYS
0018	306-11872	MILLING, PROFILE	100.00	SYS
0019	401-06264	PROFILOGRAPH, HMA	1.00	LS
0020	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	12636.00	TON
0021	401-10258	JOINT ADHESIVE, SURFACE	33960.00	LFT
0022	401-11785	LIQUID ASPHALT SEALANT	33960.00	LFT
0023	402-07452	HMA WEDGE AND LEVEL, TYPE C	50.00	TON
0024	406-05520	ASPHALT FOR TACK COAT	44.00	TON
0025	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	10.00	TON
0026	604-02007	SIDEWALK, CONCRETE, RECONSTRUCT	10.00	SYS
0027	604-06070	SIDEWALK, CONCRETE	5.00	SYS
0028	604-08086	CURB RAMP, CONCRETE	30.00	SYS
0029	604-12083	DETECTABLE WARNING SURFACES	6.00	SYS
0030	605-01870	CURB, CONCRETE A	10.00	LFT

0031	606-07484	MILLED HMA CORRUGATIONS	24570.00	LFT
0032	610-07488	HMA FOR APPROACHES, TYPE C	657.00	TON
0033	621-06567	WATER	1.00	KGAL
0034	621-06574	SODDING	10.00	SYS
0035	628-09402	FIELD OFFICE, B	6.00	MOS
0036	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0037	702-90915	CONCRETE, CLASS, A	1.00	CYS
0038	703-06029	REINFORCING BARS, EPOXY COATED	73.00	LBS
0039	720-44000	CASTING, ADJUST TO GRADE	7.00	EACH
0040	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	7270.00	LFT
0041	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7270.00	LFT
0042	801-06640	CONSTRUCTION SIGN, A	35.00	EACH
0043	801-06775	MAINTAINING TRAFFIC	1.00	LS
0044	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	383.00	LFT
0045	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	3269.00	LFT
0046	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	57926.00	LFT
0047	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	40010.00	LFT
0048	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0049	808-75008	LINE, PAINT, SOLID, WHITE, 8 IN.	1638.00	LFT
0050	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	246.00	LFT
0051	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	45.00	LFT
0052	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	60.00	LFT
0053	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	1.00	EACH
0054	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	679.00	EACH
0055	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	679.00	EACH

Call: 551

Contract: RS-39787-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-90277	DETECTOR HOUSING, REMOVE	20.00	EACH
0011	303-01180	COMPACTED AGGREGATE NO. 53	3044.00	TON
0012	304-07491	HMA PATCHING, TYPE C	1509.00	TON

0013	306-08036	MILLING, ASPHALT, 2 IN.	490033.00	SYS
0014	306-08432	MILLING, APPROACH	2086.00	SYS
0015	401-06264	PROFILOGRAPH, HMA	1.00	LS
0016	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	53904.00	TON
0017	401-10258	JOINT ADHESIVE, SURFACE	324870.00	LFT
0018	401-11785	LIQUID ASPHALT SEALANT	324870.00	LFT
0019	406-05520	ASPHALT FOR TACK COAT	123.00	TON
0020	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	10.00	TON
0021	606-07484	MILLED HMA CORRUGATIONS	175231.00	LFT
0022	610-07488	HMA FOR APPROACHES, TYPE C	304.00	TON
0023	628-09402	FIELD OFFICE, B	12.00	MOS
0024	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	30.00	EACH
0025	801-03290	CONSTRUCTION SIGN, C	10.00	EACH
0026	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	211200.00	LFT
0027	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	211200.00	LFT
0028	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	30.00	EACH
0029	801-06640	CONSTRUCTION SIGN, A	120.00	EACH
0030	801-06710	FLASHING ARROW SIGN	60.00	DAY
0031	801-06775	MAINTAINING TRAFFIC	1.00	LS
0032	801-07118	BARRICADE, III-A	60.00	LFT
0033	801-07119	BARRICADE, III-B	60.00	LFT
0034	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0035	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	5477.00	LFT
0036	805-78785	SIGNAL DETECTOR HOUSING	20.00	EACH
0037	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1766.00	LFT
0038	808-06702	LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	19178.00	LFT
0039	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	125776.00	LFT
0040	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	18730.00	LFT
0041	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0042	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	2177.00	LFT
0043	808-12032	GROOVING FOR PAVEMENT MARKINGS	279341.00	LFT
0044	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1069.00	LFT
0045	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	112411.00	LFT
0046	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	1205.00	LFT
0047	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	1225.00	LFT
0048	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	651.00	LFT
0049	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	366.00	LFT
0050	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	30.00	EACH
0051	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2348.00	EACH
0052	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2348.00	EACH
0053	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	468.00	LFT

Call: 561

Contract: RS-40016-A

Section No.: 1

PCC THIN OVERLAY

Line				Quantity	Unit
Item No	Item Code	Description			
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS	
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL	
0003	109-08360	CONTRACT LIENS	1.00	DOL	
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL	
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL	
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL	
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL	
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL	
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL	
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL	
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL	
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS	
0013	201-52370	CLEARING RIGHT OF WAY	1.00	LS	
0014	202-02277	GUTTER LIP, REMOVE	4200.00	LFT	
0015	202-90277	DETECTOR HOUSING, REMOVE	6.00	EACH	
0016	202-91385	INLET, REMOVE	13.00	EACH	
0017	202-93741	GUARDRAIL, END TREATMENT, REMOVE	13.00	EACH	
0018	202-94810	CURB TURNOUT, REMOVE	3.00	EACH	
0019	203-02000	EXCAVATION, COMMON	5831.00	CYS	
0020	205-12108	STORM WATER MANAGEMENT BUDGET	66806.00	DOL	
0021	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS	
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	17272.00	SYS	
0023	211-09264	STRUCTURE BACKFILL, TYPE 1	104.00	CYS	
0024	211-09266	STRUCTURE BACKFILL, TYPE 3	1587.00	CYS	
0025	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	5055.00	SYS	
0026	301-12234	COMPACTED AGGREGATE NO 53	158.00	CYS	
0027	303-01180	COMPACTED AGGREGATE NO. 53	557.00	TON	
0028	304-07491	HMA PATCHING, TYPE C	932.00	TON	
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	9978.00	SYS	
0030	306-08036	MILLING, ASPHALT, 2 IN.	42350.00	SYS	
0031	306-08043	MILLING, TRANSITION	4583.00	SYS	
0032	306-08432	MILLING, APPROACH	1170.00	SYS	
0033	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	1906.00	TON	
0034	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	3286.00	TON	
0035	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	1492.00	TON	
0036	401-10258	JOINT ADHESIVE, SURFACE	21556.00	LFT	
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	21556.00	LFT	
0038	401-11785	LIQUID ASPHALT SEALANT	34784.00	LFT	
0039	406-05520	ASPHALT FOR TACK COAT	14.00	TON	

0040	501-12171	INERTIAL PROFILER, PCCP	1.00	LS
0041	501-12178	QC/QA-PCC, THIN BONDED OVERLAY, 4.5 IN.	37345.00	SYS
0042	501-12183	QC/QA PCC ADDITIONAL	1581.00	CYS
0043	601-02241	GUARDRAIL, REMOVE	8901.00	LFT
0044	601-06035	GUARDRAIL, RESET	200.00	LFT
0045	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	7113.00	LFT
0046	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	1295.00	LFT
0047	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	8.00	EACH
0048	601-94689	GUARDRAIL, END TREATMENT, OS	10.00	EACH
0049	601-94690	GUARDRAIL, END TREATMENT, MS	3.00	EACH
0050	606-07484	MILLED HMA CORRUGATIONS	13228.00	LFT
0051	606-11064	MILLED PCCP CORRUGATIONS	10187.00	LFT
0052	610-07487	HMA FOR APPROACHES, TYPE B	296.00	TON
0053	616-05689	RIPRAP, CLASS 2	37.00	TON
0054	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	38.00	SYS
0055	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0056	621-02770	EROSION CONTROL BLANKET	1000.00	SYS
0057	621-06559	MULCHED SEEDING R	7568.00	SYS
0058	628-09402	FIELD OFFICE, B	12.00	MOS
0059	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0060	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0061	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0062	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	12.00	MOS
0063	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0064	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	4097.00	LFT
0065	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	510.00	LFT
0066	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	20.00	LFT
0067	718-06526	HMA FOR UNDERDRAINS	88.00	TON
0068	718-06528	OUTLET PROTECTOR, 1	17.00	EACH
0069	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	2795.00	SYS
0070	718-52610	AGGREGATE FOR UNDERDRAINS	369.00	CYS
0071	720-02442	PIPE PLUG EXISTING	9.00	EACH
0072	725-10014	PIPE LINER CURED-IN-PLACE MIN AREA 8.8 SFT	182.00	LFT
0073	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	24.00	EACH
0074	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	5.00	EACH
0075	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	77574.00	LFT
0076	801-06640	CONSTRUCTION SIGN, A	59.00	EACH
0077	801-06710	FLASHING ARROW SIGN	210.00	DAY
0078	801-06775	MAINTAINING TRAFFIC	1.00	LS
0079	801-07118	BARRICADE, III-A	44.00	LFT
0080	804-06725	DELINEATOR WITH POST, D1	2.00	EACH
0081	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	2407.00	LFT
0082	805-78785	SIGNAL DETECTOR HOUSING	6.00	EACH

0083	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	805.00	LFT
0084	808-06716	LINE, REMOVE	28900.00	LFT
0085	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0086	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	3320.00	LFT
0087	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	13382.00	LFT
0088	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	12865.00	LFT
0089	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	488.00	LFT
0090	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	65.00	LFT
0091	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	139.00	LFT
0092	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	5.00	EACH
0093	808-12032	GROOVING FOR PAVEMENT MARKINGS	30055.00	LFT
0094	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	195.00	EACH
0095	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	195.00	EACH

Call: 571

Contract: RS-40265-A

Section No.: 1 PATCH AND REHAB PAVEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	203-08607	LINEAR GRADING	13147.00	LFT
0010	207-08264	SUBGRADE TREATMENT, TYPE II	893.00	SYS
0011	214-11796	GEOGRID, TYPE IB	300.00	SYS
0012	304-07491	HMA PATCHING, TYPE C	295.00	TON
0013	306-08036	MILLING, ASPHALT, 2 IN.	25652.00	SYS
0014	306-08432	MILLING, APPROACH	3425.00	SYS
0015	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	3199.00	TON
0016	401-10258	JOINT ADHESIVE, SURFACE	12204.00	LFT
0017	401-11785	LIQUID ASPHALT SEALANT	12204.00	LFT
0018	406-05520	ASPHALT FOR TACK COAT	7.00	TON
0019	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.50	TON
0020	628-09401	FIELD OFFICE, A	5.00	MOS
0021	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0022	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0023	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0024	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	5.00	MOS

0025	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0026	628-11977	COMPUTER SYSTEM	1.00	EACH
0027	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	26.00	LFT
0028	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	26.00	LFT
0029	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	36.00	LFT
0030	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	36.00	LFT
0031	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0032	801-06775	MAINTAINING TRAFFIC	1.00	LS
0033	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	510.00	LFT
0034	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	36.00	LFT

Call: 581

Contract: RS-40641-A

Section No.: 1 PATCH AND REHAB PAVEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-06580	CONTAMINATED SOIL, REMOVE	100.00	CYS
0014	202-90277	DETECTOR HOUSING, REMOVE	4.00	EACH
0015	205-12108	STORM WATER MANAGEMENT BUDGET	6000.00	DOL
0016	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0017	207-09935	SUBGRADE TREATMENT, TYPE IC	625.00	SYS
0018	302-07455	DENSE GRADED SUBBASE	105.00	CYS
0019	303-01180	COMPACTED AGGREGATE NO. 53	459.00	TON
0020	304-07783	HMA PATCHING, TYPE D	533.00	TON
0021	306-08036	MILLING, ASPHALT, 2 IN.	6829.00	SYS
0022	306-08038	MILLING, ASPHALT, 4 IN.	805.00	SYS
0023	306-08041	MILLING, PCCP	21037.00	SYS
0024	401-06264	PROFILOGRAPH, HMA	1.00	LS
0025	401-07353	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm	3162.00	TON
0026	401-07387	QC/QA-HMA, 4, 76, INTERMEDIATE, 12.5 mm	89.00	TON
0027	401-10258	JOINT ADHESIVE, SURFACE	15753.00	LFT

0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	2631.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	15753.00	LFT
0030	406-05520	ASPHALT FOR TACK COAT	11.00	TON
0031	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	3.00	TON
0032	503-03489	RETROFITTED TIE BARS	40.00	EACH
0033	503-05240	D-1 CONTRACTION JOINT	144.00	LFT
0034	506-06333	PCCP PATCHING, FULL DEPTH	625.00	SYS
0035	507-08269	CRACKS IN PCCP, FILLED	8500.00	LFT
0036	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	2.00	SYS
0037	628-09401	FIELD OFFICE, A	12.00	MOS
0038	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0039	801-03290	CONSTRUCTION SIGN, C	3.00	EACH
0040	801-04308	ROAD CLOSURE SIGN ASSEMBLY	30.00	EACH
0041	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	17132.00	LFT
0042	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	2.00	EACH
0043	801-06625	DETOUR ROUTE MARKER ASSEMBLY	93.00	EACH
0044	801-06640	CONSTRUCTION SIGN, A	92.00	EACH
0045	801-06645	CONSTRUCTION SIGN, B	32.00	EACH
0046	801-06710	FLASHING ARROW SIGN	12.00	DAY
0047	801-06775	MAINTAINING TRAFFIC	1.00	LS
0048	801-07118	BARRICADE, III-A	417.00	LFT
0049	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	2114.00	LFT
0050	805-78785	SIGNAL DETECTOR HOUSING	4.00	EACH
0051	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	914.00	LFT
0052	805-92951	SIGNAL DETECTOR HOUSING ADJUST TO GRADE	4.00	EACH
0053	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	155.00	LFT
0054	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	890.00	LFT
0055	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	8657.00	LFT
0056	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	552.00	LFT
0057	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0058	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	140.00	LFT
0059	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1489.00	LFT
0060	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	759.00	LFT
0061	808-12032	GROOVING FOR PAVEMENT MARKINGS	14723.00	LFT
0062	808-75067	TRANSVERSE MARKING, PREFORMED PLASTIC, STOP LINE, WHITE, 24 IN.	80.00	LFT
0063	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	7.00	EACH
0064	808-75073	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, ONLY	2.00	EACH
0065	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7555.00	LFT
0066	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	627.00	LFT
0067	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	181.00	LFT
0068	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	255.00	LFT
0069	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	24.00	EACH
0070	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	2.00	EACH

0071	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	244.00	EACH
0072	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	233.00	EACH

Call: 591

Contract: RS-40756-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	202-90277	DETECTOR HOUSING, REMOVE	13.00	EACH
0013	207-08264	SUBGRADE TREATMENT, TYPE II	362.00	SYS
0014	303-01180	COMPACTED AGGREGATE NO. 53	2957.00	TON
0015	304-07491	HMA PATCHING, TYPE C	4625.00	TON
0016	304-07491	HMA PATCHING, TYPE C	3655.00	TON
0017	306-08034	MILLING, ASPHALT, 1 1/2 IN.	299924.00	SYS
0018	306-08432	MILLING, APPROACH	19287.00	SYS
0019	401-06264	PROFILOGRAPH, HMA	1.00	LS
0020	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	24746.00	TON
0021	401-10258	JOINT ADHESIVE, SURFACE	140088.00	LFT
0022	401-11785	LIQUID ASPHALT SEALANT	270807.00	LFT
0023	406-05520	ASPHALT FOR TACK COAT	18.00	TON
0024	406-12347	ASPHALT EMULSION FOR TACK COAT	229.00	TON
0025	606-07484	MILLED HMA CORRUGATIONS	199348.00	LFT
0026	610-07488	HMA FOR APPROACHES, TYPE C	1733.00	TON
0027	615-06525	CASTING ADJUST TO GRADE, MONUMENT	2.00	EACH
0028	628-09402	FIELD OFFICE, B	12.00	MOS
0029	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0030	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	2.00	EACH
0031	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	1.00	EACH
0032	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	23.00	EACH
0033	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	22460.00	LFT
0034	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	22460.00	LFT
0035	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	23.00	EACH

0036	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	319.00	LFT
0037	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	319.00	LFT
0038	801-06640	CONSTRUCTION SIGN, A	87.00	EACH
0039	801-06710	FLASHING ARROW SIGN	200.00	DAY
0040	801-06775	MAINTAINING TRAFFIC	1.00	LS
0041	801-92448	CONSTRUCTION SIGNS MOBILE	1200.00	DAY
0042	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	4701.00	LFT
0043	805-78785	SIGNAL DETECTOR HOUSING	13.00	EACH
0044	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1636.00	LFT
0045	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	164393.00	LFT
0046	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	1550.00	LFT
0047	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0048	808-12032	GROOVING FOR PAVEMENT MARKINGS	75229.00	LFT
0049	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	11650.00	LFT
0050	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	90666.00	LFT
0051	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	291.00	LFT
0052	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	1151.00	LFT
0053	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	319.00	LFT
0054	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	23.00	EACH
0055	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2157.00	EACH
0056	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	6318.00	LFT

Call: 601

Contract: RS-40829-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	202-90277	DETECTOR HOUSING, REMOVE	16.00	EACH
0012	205-12108	STORM WATER MANAGEMENT BUDGET	1500.00	DOL
0013	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0014	302-07455	DENSE GRADED SUBBASE	151.00	CYS
0015	304-07783	HMA PATCHING, TYPE D	17.00	TON
0016	306-08033	MILLING, ASPHALT, 1 IN.	711.00	SYS

0017	306-08041	MILLING, PCCP	63754.00	SYS
0018	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	5320.00	TON
0019	401-07387	QC/QA-HMA, 4, 76, INTERMEDIATE, 12.5 mm	6689.00	TON
0020	401-10258	JOINT ADHESIVE, SURFACE	45572.00	LFT
0021	401-10259	JOINT ADHESIVE, INTERMEDIATE	44971.00	LFT
0022	401-11785	LIQUID ASPHALT SEALANT	45572.00	LFT
0023	406-05520	ASPHALT FOR TACK COAT	32.00	TON
0024	503-03489	RETROFITTED TIE BARS	1065.00	EACH
0025	503-05240	D-1 CONTRACTION JOINT	63.00	LFT
0026	506-06333	PCCP PATCHING, FULL DEPTH	2354.00	SYS
0027	604-06070	SIDEWALK, CONCRETE	33.00	SYS
0028	604-08086	CURB RAMP, CONCRETE	22.00	SYS
0029	604-12083	DETECTABLE WARNING SURFACES	5.00	SYS
0030	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	2.00	SYS
0031	605-06090	CURB, INTEGRAL CONCRETE	519.00	LFT
0032	615-06527	MONUMENT, SECTION CORNER	3.00	EACH
0033	628-09402	FIELD OFFICE, B	6.00	MOS
0034	628-11729	CELLULAR TELEPHONE, TYPE A	2.00	EACH
0035	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0036	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0037	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	12.00	MOS
0038	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0039	628-11977	COMPUTER SYSTEM	1.00	EACH
0040	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	2.00	EACH
0041	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	3.00	EACH
0042	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0043	720-44000	CASTING, ADJUST TO GRADE	7.00	EACH
0044	720-44000	CASTING, ADJUST TO GRADE	26.00	EACH
0045	720-44045	CASTING, 8, FURNISH AND ADJUST TO GRADE	4.00	EACH
0046	720-44080	CASTING, 15, FURNISH AND ADJUST TO GRADE	10.00	EACH
0047	720-45615	STRUCTURE, INLET, RECONSTRUCTED	10.00	LFT
0048	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	30.00	EACH
0049	720-96995	CLEAN INLET	10.00	EACH
0050	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	57.00	EACH
0051	801-01506	TEMPORARY PAVEMENT MESSAGE MARKING, (RXR)	4.00	EACH
0052	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	5404.00	LFT
0053	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5404.00	LFT
0054	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	57.00	EACH
0055	801-06213	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (RXR)	4.00	EACH
0056	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	945.00	LFT
0057	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	945.00	LFT
0058	801-06640	CONSTRUCTION SIGN, A	42.00	EACH
0059	801-06645	CONSTRUCTION SIGN, B	10.00	EACH

0060	801-06710	FLASHING ARROW SIGN	300.00	DAY
0061	801-06775	MAINTAINING TRAFFIC	1.00	LS
0062	801-07118	BARRICADE, III-A	40.00	LFT
0063	801-92448	CONSTRUCTION SIGNS MOBILE	1260.00	DAY
0064	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	12.00	LFT
0065	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0066	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	7185.00	LFT
0067	805-78785	SIGNAL DETECTOR HOUSING	12.00	EACH
0068	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2772.00	LFT
0069	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	4.00	EACH
0070	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	4510.00	LFT
0071	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	18005.00	LFT
0072	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0073	808-12032	GROOVING FOR PAVEMENT MARKINGS	40623.00	LFT
0074	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	2520.00	LFT
0075	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	15084.00	LFT
0076	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	154.00	LFT
0077	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	945.00	LFT
0078	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	2147.00	LFT
0079	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	57.00	EACH
0080	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	16.00	EACH
0081	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	504.00	LFT

Call: 651

Contract: B -34424-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	1364.00	SYS
0013	202-02278	CURB, CONCRETE, REMOVE	586.00	LFT
0014	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0015	202-52710	SIDEWALK CONCRETE, REMOVE	426.00	SYS

0016	202-93763	LIGHT STANDARD AND FOUNDATION, REMOVE	1.00	EACH
0017	203-02000	EXCAVATION, COMMON	253.40	CYS
0018	205-12108	STORM WATER MANAGEMENT BUDGET	3527.33	DOL
0019	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0020	206-51215	EXCAVATION, X	205.00	CYS
0021	206-51220	EXCAVATION, WET	335.00	CYS
0022	206-51225	EXCAVATION, DRY	819.20	CYS
0023	206-51235	COFFERDAM	1.00	LS
0024	207-08264	SUBGRADE TREATMENT, TYPE II	62.20	SYS
0025	207-09935	SUBGRADE TREATMENT, TYPE IC	702.40	SYS
0026	211-06467	AGGREGATE FOR END BENT BACKFILL	96.00	CYS
0027	301-12234	COMPACTED AGGREGATE NO 53	4.00	CYS
0028	302-07455	DENSE GRADED SUBBASE	82.20	CYS
0029	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	59.00	TON
0030	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	116.00	TON
0031	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	251.00	TON
0032	401-10258	JOINT ADHESIVE, SURFACE	448.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	448.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	896.00	LFT
0035	406-05520	ASPHALT FOR TACK COAT	0.53	TON
0036	601-06234	IMPACT ATTENUATOR, R1-W1, TL-2	2.00	EACH
0037	604-06070	SIDEWALK, CONCRETE	128.90	SYS
0038	604-08086	CURB RAMP, CONCRETE	111.70	SYS
0039	604-12083	DETECTABLE WARNING SURFACES	20.70	SYS
0040	605-06120	CURB, CONCRETE	357.00	LFT
0041	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	493.00	SYS
0042	610-09108	PCCP FOR APPROACHES, 9 IN.	62.20	SYS
0043	616-06405	RIPRAP, REVETMENT	155.00	TON
0044	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	273.00	SYS
0045	621-06575	SODDING, NURSERY	102.00	SYS
0046	628-09402	FIELD OFFICE, B	11.00	MOS
0047	628-11729	CELLULAR TELEPHONE, TYPE A	2.00	EACH
0048	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0049	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0050	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	18.00	MOS
0051	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0052	701-02938	CORED HOLE IN ROCK, 24 IN	115.00	LFT
0053	701-06011	DYNAMIC PILE LOAD TEST	2.00	EACH
0054	701-09557	TEST PILE, DYNAMIC, PRODUCTION	58.00	LFT
0055	701-09683	PILE SHOE, HP 12 X 74	16.00	EACH
0056	701-11898	PILE, STEEL H, HP 14 X 117	595.00	LFT
0057	701-11899	PILE SHOE, HP 14 x 117	23.00	EACH
0058	701-12360	PREBORED HOLE, 21 IN	180.00	LFT

0059	701-12361	PREBORED HOLE, 24 IN	525.00	LFT
0060	701-92043	CORED HOLE IN ROCK, 18 IN	128.00	LFT
0061	701-95780	PILE, STEEL H, HP 12 X 74	263.00	LFT
0062	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	8.00	EACH
0063	702-51005	CONCRETE, A, SUBSTRUCTURE	554.00	CYS
0064	702-51015	CONCRETE, B, FOOTINGS	187.00	CYS
0065	702-51863	FIELD DRILLED HOLE IN CONCRETE	81.00	EACH
0066	702-92857	CONCRETE, C, SUBSTRUCTURE	144.00	CYS
0067	703-06028	REINFORCING BARS	103835.00	LBS
0068	703-06029	REINFORCING BARS, EPOXY COATED	353798.00	LBS
0069	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	52.00	EACH
0070	704-51002	CONCRETE, C, SUPERSTRUCTURE	1216.00	CYS
0071	706-06372	CONCRETE BRIDGE RAILING TRANSITION, TTX	4.00	EACH
0072	706-11607	RAILING, CONCRETE TX	110.00	CYS
0073	707-08158	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 42 IN. X 49 IN.	2805.00	LFT
0074	709-51821	SURFACE SEAL	1.00	LS
0075	709-51821	SURFACE SEAL	1.00	LS
0076	709-51821	SURFACE SEAL	1.00	LS
0077	709-51821	SURFACE SEAL	1.00	LS
0078	709-51821	SURFACE SEAL	1.00	LS
0079	709-51821	SURFACE SEAL	1.00	LS
0080	709-51821	SURFACE SEAL	1.00	LS
0081	709-51821	SURFACE SEAL	1.00	LS
0082	709-51821	SURFACE SEAL	1.00	LS
0083	711-51038	STRUCTURAL STEEL	1.00	LS
0084	711-96800	STUD SHEAR CONNECTORS	179.00	EACH
0085	712-04272	LUMBER AND TIMBER, UNTREATED	2.19	MFB
0086	715-05407	PIPE, END BENT DRAIN, 6 IN.	173.00	LFT
0087	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0088	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	214.00	SYS
0089	720-44000	CASTING, ADJUST TO GRADE	3.00	EACH
0090	720-98174	INLET, B15	1.00	EACH
0091	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0092	801-06625	DETOUR ROUTE MARKER ASSEMBLY	33.00	EACH
0093	801-06640	CONSTRUCTION SIGN, A	10.00	EACH
0094	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
0095	801-06710	FLASHING ARROW SIGN	10.00	DAY
0096	801-06775	MAINTAINING TRAFFIC	1.00	LS
0097	801-07118	BARRICADE, III-A	164.00	LFT
0098	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	205.00	LFT
0099	801-92448	CONSTRUCTION SIGNS MOBILE	16.00	DAY
0100	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	36.00	LFT
0101	802-07060	SIGN, SHEET, RELOCATE	10.00	EACH

0102	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	20.50	SFT
0103	807-01653	WIRE, NO. 4 COPPER, IN CONDUIT, BRIDGE 1/C	4686.00	LFT
0104	807-02191	HANDHOLE LIGHTING	2.00	EACH
0105	807-02352	WIRE, XHHW, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C.	358.00	LFT
0106	807-02428	LIGHTING FOUNDATION, CONCRETE WITH GROUND 30 IN. X 30 IN. X 96 IN.	3.00	EACH
0107	807-03934	LIGHT STRUCTURE, REMOVE	10.00	EACH
0108	807-03950	LUMINAIRE ORNAMENTAL	15.00	EACH
0109	807-03951	LIGHT POLE ORNAMENTAL	15.00	EACH
0110	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	66.00	LFT
0111	807-86910	CONNECTOR KIT, UNFUSED	30.00	EACH
0112	807-86915	CONNECTOR KIT, FUSED	30.00	EACH
0113	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	39.00	EACH
0114	807-86930	INSULATION LINK, NON-WATERPROOFED	30.00	EACH
0115	807-95889	WIRE, NO. 10 COPPER, 1/C	2161.00	LFT
0116	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	4989.00	LFT
0117	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	4666.00	LFT
0118	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	15.00	EACH

Call: 661

Contract: B -35239-A

Section No.: 1 BRIDGE REHABILITATION OR REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	166.00	SYS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0013	203-02000	EXCAVATION, COMMON	148.00	CYS
0014	205-12108	STORM WATER MANAGEMENT BUDGET	5525.00	DOL
0015	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0016	206-51220	EXCAVATION, WET	42.00	CYS
0017	207-09935	SUBGRADE TREATMENT, TYPE IC	505.00	SYS
0018	211-06467	AGGREGATE FOR END BENT BACKFILL	20.00	CYS
0019	301-12234	COMPACTED AGGREGATE NO 53	29.00	CYS
0020	302-07455	DENSE GRADED SUBBASE	28.00	CYS

0021	303-01180	COMPACTED AGGREGATE NO. 53	270.00	TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1014.00	SYS
0023	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	111.00	TON
0024	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	52.00	TON
0025	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	64.00	TON
0026	401-10258	JOINT ADHESIVE, SURFACE	412.00	LFT
0027	401-10259	JOINT ADHESIVE, INTERMEDIATE	364.00	LFT
0028	401-11785	LIQUID ASPHALT SEALANT	412.00	LFT
0029	406-05521	ASPHALT FOR TACK COAT	1715.00	SYS
0030	503-05310	TERMINAL JOINT	68.00	LFT
0031	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	4.00	EACH
0032	601-01626	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 2	1.00	EACH
0033	601-06037	GUARDRAIL, END TREATMENT, I	1.00	EACH
0034	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0035	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	238.00	LFT
0036	602-06729	BARRIER, DELINEATOR	10.00	EACH
0037	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	166.00	SYS
0038	610-07487	HMA FOR APPROACHES, TYPE B	4.00	TON
0039	611-08232	MAILBOX ASSEMBLY, SINGLE RESET	1.00	EACH
0040	615-06490	RIGHT-OF-WAY MARKER	17.00	EACH
0041	615-06505	MONUMENT, B	3.00	EACH
0042	616-05688	RIPRAP, CLASS 1	1133.00	TON
0043	616-05689	RIPRAP, CLASS 2	604.00	TON
0044	616-06405	RIPRAP, REVETMENT	238.00	TON
0045	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	2077.00	SYS
0046	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0047	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0048	621-06567	WATER	1.00	kGAL
0049	621-06574	SODDING	27.00	SYS
0050	628-09402	FIELD OFFICE, B	12.00	MOS
0051	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0052	702-04325	TEMPORARY SHORING	1.00	LS
0053	702-51005	CONCRETE, A, SUBSTRUCTURE	40.00	CYS
0054	702-51863	FIELD DRILLED HOLE IN CONCRETE	192.00	EACH
0055	703-06029	REINFORCING BARS, EPOXY COATED	21254.00	LBS
0056	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	256.00	EACH
0057	704-51002	CONCRETE, C, SUPERSTRUCTURE	36.00	CYS
0058	706-11600	RAILING, CONCRETE FC	3.40	CYS
0059	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0060	709-51821	SURFACE SEAL	1.00	LS
0061	711-51038	STRUCTURAL STEEL	1.00	LS
0062	711-51864	DRILLED HOLE	66.00	EACH
0063	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS

0064	711-96800	STUD SHEAR CONNECTORS	6.00	EACH
0065	715-05407	PIPE, END BENT DRAIN, 6 IN.	108.00	LFT
0066	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	81.00	SYS
0067	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	50.00	SFT
0068	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	250.00	SFT
0069	724-12103	PRE-COMPRESSED FOAM JOINT	68.00	LFT
0070	726-92406	BEARING ASSEMBLY ELASTOMERIC	18.00	EACH
0071	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	554.00	SYS
0072	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2200.00	LFT
0073	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	42.00	LFT
0074	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0075	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0076	801-06775	MAINTAINING TRAFFIC	1.00	LS
0077	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	220.00	LFT
0078	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	250.00	LFT
0079	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0080	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	32.00	LFT
0081	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	12.00	SFT
0082	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1400.00	LFT
0083	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1400.00	LFT
0084	808-06716	LINE, REMOVE	2014.00	LFT
0085	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	5.00	EACH
0086	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	5.00	EACH

Call: 671

Contract: B -35538-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0013	202-96133	PIPE, REMOVE	85.00	LFT
0014	203-02000	EXCAVATION, COMMON	5725.00	CYS

0015	203-02070	BORROW	5383.00	CYS
0016	203-51223	EXCAVATION, WATERWAY	461.00	CYS
0017	205-12108	STORM WATER MANAGEMENT BUDGET	47260.50	DOL
0018	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0019	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	362.00	CYS
0020	207-08262	SUBGRADE TREATMENT, TYPE I	1635.00	SYS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	197.00	SYS
0022	207-08266	SUBGRADE TREATMENT, TYPE III	80.00	SYS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	1937.00	SYS
0024	211-06467	AGGREGATE FOR END BENT BACKFILL	149.00	CYS
0025	211-09264	STRUCTURE BACKFILL, TYPE 1	21.00	CYS
0026	211-09265	STRUCTURE BACKFILL, TYPE 2	42.00	CYS
0027	301-12234	COMPACTED AGGREGATE NO 53	441.00	CYS
0028	302-07455	DENSE GRADED SUBBASE	28.00	CYS
0029	303-01180	COMPACTED AGGREGATE NO. 53	198.00	TON
0030	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	257.00	TON
0031	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	601.00	TON
0032	401-10258	JOINT ADHESIVE, SURFACE	1233.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	1233.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	1233.00	LFT
0035	406-05520	ASPHALT FOR TACK COAT	0.90	TON
0036	601-05071	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 7	1.00	EACH
0037	601-06037	GUARDRAIL, END TREATMENT, I	3.00	EACH
0038	601-06374	GUARDRAIL, TRANSITION, TGS-1	4.00	EACH
0039	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	400.00	LFT
0040	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	166.00	SYS
0041	610-07487	HMA FOR APPROACHES, TYPE B	38.00	TON
0042	610-08446	PCCP FOR APPROACHES, 6 IN.	61.00	SYS
0043	611-06498	MAILBOX ASSEMBLY, DOUBLE	2.00	EACH
0044	615-06490	RIGHT-OF-WAY MARKER	23.00	EACH
0045	615-06505	MONUMENT, B	6.00	EACH
0046	616-05688	RIPRAP, CLASS 1	1375.00	TON
0047	616-06405	RIPRAP, REVETMENT	124.00	TON
0048	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1656.00	SYS
0049	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0050	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0051	621-02770	EROSION CONTROL BLANKET	1069.00	SYS
0052	621-03787	SEED MIXTURE D	2.00	LBS
0053	621-06545	FERTILIZER	0.60	TON
0054	621-06553	SEED MIXTURE R	305.00	LBS
0055	621-06554	SEED MIXTURE U	8.30	LBS
0056	621-06565	MULCHING MATERIAL	3.00	TON
0057	621-06574	SODDING	114.00	SYS

0058	628-09402	FIELD OFFICE, B	18.00	MOS
0059	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0060	628-11977	COMPUTER SYSTEM	2.00	EACH
0061	701-09557	TEST PILE, DYNAMIC, PRODUCTION	77.00	LFT
0062	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.00	EACH
0063	701-09663	PILE, STEEL PIPE, 0.312 IN., 14 IN.	456.00	LFT
0064	701-09679	CONICAL PILE TIP, 14 IN.	18.00	EACH
0065	701-09824	PREBORED HOLE, 18 IN.	198.00	LFT
0066	701-09948	PILE SHOE, HP 10 X 42	8.00	EACH
0067	701-51190	PILE, STEEL H HP 10 X 42	192.00	LFT
0068	702-90915	CONCRETE, CLASS, A	28.00	CYS
0069	703-06029	REINFORCING BARS, EPOXY COATED	48535.00	LBS
0070	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	28.00	EACH
0071	704-51002	CONCRETE, C, SUPERSTRUCTURE	229.40	CYS
0072	706-06344	RAILING, STEEL TS-1	250.00	LFT
0073	707-09634	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 48 IN. X 49 IN.	480.00	LFT
0074	709-51821	SURFACE SEAL	1.00	LS
0075	709-51821	SURFACE SEAL	1.00	LS
0076	711-91996	REPAIR EXISTING STRUCTURE	1.00	LS
0077	712-94080	TIMBER DECK	1304.00	SFT
0078	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	72.00	LFT
0079	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	157.00	LFT
0080	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	87.00	LFT
0081	715-05407	PIPE, END BENT DRAIN, 6 IN.	180.00	LFT
0082	715-06050	CAP	2.00	EACH
0083	715-46005	PIPE END SECTION, DIAMETER 15 IN.	4.00	EACH
0084	715-46020	PIPE END SECTION, DIAMETER 24 IN.	4.00	EACH
0085	715-46040	PIPE END SECTION, DIAMETER 36 IN.	2.00	EACH
0086	716-07635	PIPE INSTALLATION, TRENCHLESS, 36 IN.	44.00	LFT
0087	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	250.00	SYS
0088	720-45030	INLET, E7	1.00	EACH
0089	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0090	801-06625	DETOUR ROUTE MARKER ASSEMBLY	16.00	EACH
0091	801-06640	CONSTRUCTION SIGN, A	10.00	EACH
0092	801-06775	MAINTAINING TRAFFIC	1.00	LS
0093	801-07118	BARRICADE, III-A	72.00	LFT
0094	801-07119	BARRICADE, III-B	48.00	LFT
0095	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	72.00	LFT
0096	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	23.60	SFT
0097	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	9.00	SFT
0098	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2552.00	LFT
0099	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2600.00	LFT
0100	808-75035	LINE, PAINT, SOLID, WHITE, 24 IN.	10.00	LFT

Call: 681
Contract: B -36182-A
Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-01066	HYDRO DEMOLITION	2348.00	SYS
0013	202-02240	PAVEMENT REMOVAL	557.00	SYS
0014	202-51133	RAILING, REMOVE	268.00	LFT
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0018	202-51822	BRIDGE DECK OVERLAY, REMOVE	1783.00	SYS
0019	202-96133	PIPE, REMOVE	51.00	LFT
0020	203-02000	EXCAVATION, COMMON	520.00	CYS
0021	203-02070	BORROW	1231.00	CYS
0022	205-12108	STORM WATER MANAGEMENT BUDGET	14864.00	DOL
0023	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0024	206-93520	TEMPORARY SHEET PILING	1500.00	SFT
0025	207-08264	SUBGRADE TREATMENT, TYPE II	645.00	SYS
0026	207-09935	SUBGRADE TREATMENT, TYPE IC	1160.00	SYS
0027	211-02050	B BORROW	90.00	CYS
0028	211-09264	STRUCTURE BACKFILL, TYPE 1	86.00	CYS
0029	211-09265	STRUCTURE BACKFILL, TYPE 2	641.00	CYS
0030	211-09267	STRUCTURE BACKFILL, TYPE 4	40.00	CYS
0031	211-09268	STRUCTURE BACKFILL, TYPE 5	316.00	CYS
0032	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	399.00	SYS
0033	301-12231	COMPACTED AGGREGATE NO 2	105.00	CYS
0034	301-12232	COMPACTED AGGREGATE NO 5	106.00	CYS
0035	301-12234	COMPACTED AGGREGATE NO 53	230.10	CYS
0036	302-07455	DENSE GRADED SUBBASE	66.00	CYS
0037	303-01180	COMPACTED AGGREGATE NO. 53	276.00	TON

0038	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	21.00	TON
0039	304-07493	WIDENING WITH HMA, TYPE B	220.00	TON
0040	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1710.00	SYS
0041	306-08043	MILLING, TRANSITION	880.00	SYS
0042	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	282.20	TON
0043	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	90.00	TON
0044	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	128.00	TON
0045	401-10258	JOINT ADHESIVE, SURFACE	2942.00	LFT
0046	401-10259	JOINT ADHESIVE, INTERMEDIATE	3100.00	LFT
0047	401-11785	LIQUID ASPHALT SEALANT	5942.00	LFT
0048	402-10084	HMA FOR TEMPORARY PAVEMENT, B	157.00	TON
0049	404-05516	SEAL COAT, 7	100.00	SYS
0050	406-05521	ASPHALT FOR TACK COAT	5666.00	SYS
0051	503-05310	TERMINAL JOINT	88.00	LFT
0052	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	4.00	EACH
0053	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	2.00	EACH
0054	601-02241	GUARDRAIL, REMOVE	641.50	LFT
0055	601-06854	GUARDRAIL, W-BEAM, NESTED	2.00	EACH
0056	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	50.00	LFT
0057	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0058	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	2.00	EACH
0059	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0060	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0061	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	187.50	LFT
0062	602-06729	BARRIER, DELINEATOR	12.00	EACH
0063	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	416.00	SYS
0064	610-07487	HMA FOR APPROACHES, TYPE B	8.00	TON
0065	610-09108	PCCP FOR APPROACHES, 9 IN.	129.00	SYS
0066	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0067	615-06490	RIGHT-OF-WAY MARKER	24.00	EACH
0068	615-06505	MONUMENT, B	9.00	EACH
0069	616-05688	RIPRAP, CLASS 1	280.00	TON
0070	616-06405	RIPRAP, REVETMENT	54.00	TON
0071	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	269.00	SYS
0072	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	491.00	SYS
0073	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	110.00	SYS
0074	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0075	621-02770	EROSION CONTROL BLANKET	245.00	SYS
0076	621-06559	MULCHED SEEDING R	3162.00	SYS
0077	621-06574	SODDING	260.00	SYS
0078	628-09403	FIELD OFFICE, C	12.00	MOS
0079	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0080	702-51863	FIELD DRILLED HOLE IN CONCRETE	528.00	EACH

0081	703-06029	REINFORCING BARS, EPOXY COATED	58865.00	LBS
0082	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	146.00	EACH
0083	704-51002	CONCRETE, C, SUPERSTRUCTURE	82.80	CYS
0084	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00	EACH
0085	706-51020	RAILING, CONCRETE C	26.60	CYS
0086	709-51821	SURFACE SEAL	1.00	LS
0087	709-51821	SURFACE SEAL	1.00	LS
0088	714-11109	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 16 FT. X 5 FT.	86.00	LFT
0089	714-11143	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 16 FT. X 8 FT.	70.00	LFT
0090	715-02630	SAFETY METAL END SECTION, 6:1, DIA 24 IN.	2.00	EACH
0091	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	175.00	LFT
0092	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	102.00	LFT
0093	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	230.00	LFT
0094	715-09064	VIDEO INSPECTION FOR PIPE	405.00	LFT
0095	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	3.00	EACH
0096	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH
0097	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	EACH
0098	720-45035	INLET, F7	1.00	EACH
0099	720-45070	INLET, P12A	1.00	EACH
0100	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	810.00	SFT
0101	722-51842	BRIDGE DECK OVERLAY	2678.00	SYS
0102	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	32.00	CYS
0103	722-51874	OVERLAY DAM	145.00	SFT
0104	722-60824	SURFACE MILLING	2355.00	SYS
0105	724-51925	STRUCTURAL EXPANSION JOINT, SS	67.00	LFT
0106	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0107	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00	EACH
0108	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	1112.00	LFT
0109	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3156.00	LFT
0110	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	54.00	LFT
0111	801-06625	DETOUR ROUTE MARKER ASSEMBLY	77.00	EACH
0112	801-06640	CONSTRUCTION SIGN, A	98.00	EACH
0113	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
0114	801-06775	MAINTAINING TRAFFIC	1.00	LS
0115	801-07118	BARRICADE, III-A	108.00	LFT
0116	801-07119	BARRICADE, III-B	168.00	LFT
0117	801-07612	TEMPORARY PAVEMENT MARKING, 24 IN.	24.00	LFT
0118	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	640.00	LFT
0119	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	50.00	LFT
0120	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0121	801-12081	PORTABLE SIGNAL	1.00	LS
0122	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0123	802-04089	SIGN, SHEET, REMOVE	6.00	EACH

0124	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	92.00	LFT
0125	802-07060	SIGN, SHEET, RELOCATE	5.00	EACH
0126	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	26.25	SFT
0127	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	24.00	SFT
0128	808-06368	TRANSVERSE MARKING, REMOVE	24.00	LFT
0129	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	205.00	LFT
0130	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	4175.00	LFT
0131	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	3359.00	LFT
0132	808-06716	LINE, REMOVE	2464.00	LFT
0133	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	8.00	EACH
0134	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	4.00	EACH

Call: 691

Contract: B -36670-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	202-01066	HYDRO DEMOLITION	1655.00	SYS
0011	202-02279	CURB AND GUTTER, REMOVE	80.00	LFT
0012	306-08034	MILLING, ASPHALT, 1 1/2 IN.	867.00	SYS
0013	306-11872	MILLING, PROFILE	232.00	SYS
0014	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	91.00	TON
0015	401-10258	JOINT ADHESIVE, SURFACE	760.00	LFT
0016	401-11785	LIQUID ASPHALT SEALANT	760.00	LFT
0017	406-05521	ASPHALT FOR TACK COAT	1098.00	SYS
0018	604-02007	SIDEWALK, CONCRETE, RECONSTRUCT	58.00	SYS
0019	604-95344	HAND RAIL, PEDESTRIAN	130.00	LFT
0020	605-06140	CURB AND GUTTER, CONCRETE	80.00	LFT
0021	628-09401	FIELD OFFICE, A	5.00	MOS
0022	628-11729	CELLULAR TELEPHONE, TYPE A	2.00	EACH
0023	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0024	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0025	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	10.00	MOS
0026	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH

0027	709-51821	SURFACE SEAL	1.00	LS
0028	710-09158	PATCHING CONCRETE STRUCTURES	25.00	SFT
0029	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	126.00	SFT
0030	722-51842	BRIDGE DECK OVERLAY	1655.00	SYS
0031	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	13.00	CYS
0032	722-51874	OVERLAY DAM	113.00	SFT
0033	722-60824	SURFACE MILLING	1655.00	SYS
0034	724-03276	STRUCTURAL EXPANSION JOINT SEALING SYS	167.00	LFT
0035	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0036	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	13056.00	LFT
0037	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0038	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0039	801-06775	MAINTAINING TRAFFIC	1.00	LS
0040	801-07118	BARRICADE, III-A	64.00	LFT
0041	801-07119	BARRICADE, III-B	64.00	LFT
0042	808-06716	LINE, REMOVE	4067.00	LFT
0043	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	800.00	LFT
0044	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	4200.00	LFT
0045	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	4200.00	LFT

Call: 701

Contract: B -36679-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	108-11945	PERFORMANCE TESTING	1.00	LS
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0013	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0014	202-01066	HYDRO DEMOLITION	3617.00	SYS
0015	202-02240	PAVEMENT REMOVAL	4803.00	SYS
0016	202-02273	CENTER CURB, CONCRETE, REMOVE	187.00	SYS
0017	202-02274	CURB, CONCRETE INTEGRAL, REMOVE	327.00	LFT
0018	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS

0019	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0020	202-51368	SLOPEWALL, REMOVE	797.00	SYS
0021	202-51822	BRIDGE DECK OVERLAY, REMOVE	1217.00	SYS
0022	202-94954	BARRIER WALL, CONCRETE, REMOVE	102.00	LFT
0023	202-95027	IMPACT ATTENUATOR, REMOVE	1.00	EACH
0024	202-96133	PIPE, REMOVE	200.00	LFT
0025	203-02000	EXCAVATION, COMMON	1301.00	CYS
0026	203-02070	BORROW	385.00	CYS
0027	205-09387	TEMPORARY TURBIDITY CURTAIN	544.00	LFT
0028	205-12108	STORM WATER MANAGEMENT BUDGET	6080.00	DOL
0029	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0030	207-09935	SUBGRADE TREATMENT, TYPE IC	4874.00	SYS
0031	211-02050	B BORROW	4.00	CYS
0032	211-09267	STRUCTURE BACKFILL, TYPE 4	179.00	CYS
0033	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	54.00	CYS
0034	213-09270	FLOWABLE BACKFILL, REMOVABLE	46.00	CYS
0035	301-12234	COMPACTED AGGREGATE NO 53	294.00	CYS
0036	302-07455	DENSE GRADED SUBBASE	128.00	CYS
0037	302-07455	DENSE GRADED SUBBASE	82.00	CYS
0038	306-08034	MILLING, ASPHALT, 1 1/2 IN.	82.00	SYS
0039	306-08043	MILLING, TRANSITION	6023.00	SYS
0040	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	182.00	TON
0041	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	322.00	TON
0042	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	379.00	TON
0043	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	156.00	TON
0044	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	461.00	TON
0045	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	1474.00	TON
0046	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	267.00	TON
0047	401-10258	JOINT ADHESIVE, SURFACE	8729.00	LFT
0048	401-10259	JOINT ADHESIVE, INTERMEDIATE	3521.00	LFT
0049	401-11785	LIQUID ASPHALT SEALANT	4769.00	LFT
0050	402-10086	HMA FOR TEMPORARY PAVEMENT, C	103.00	TON
0051	406-05520	ASPHALT FOR TACK COAT	5.30	TON
0052	502-06327	PCCP, 10 IN.	360.00	SYS
0053	503-05310	TERMINAL JOINT	377.00	LFT
0054	506-06333	PCCP PATCHING, FULL DEPTH	54.00	SYS
0055	507-07482	CRACKS IN PCCP, ROUT AND SEAL	500.00	LFT
0056	507-08272	JOINTS IN PCCP, SAW AND SEAL	145.00	LFT
0057	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	2.00	EACH
0058	601-02103	GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN. SPACING	68.75	LFT
0059	601-02241	GUARDRAIL, REMOVE	117.00	LFT
0060	601-05999	CURVED TERMINAL END	1.00	EACH
0061	601-06035	GUARDRAIL, RESET	1804.00	LFT

0062	601-06244	IMPACT ATTENUATOR, R2-W3, TL-2	1.00	EACH
0063	601-07050	GUARDRAIL END TREATMENT, OS RESET	1.00	EACH
0064	602-01064	CONCRETE BARRIER	97.00	LFT
0065	602-06729	BARRIER, DELINEATOR	32.00	EACH
0066	603-97461	TEMPORARY FENCE	65.00	LFT
0067	605-06100	CURB, INTEGRAL C CONCRETE	331.00	LFT
0068	605-06210	CENTER CURB, C CONCRETE	502.00	LFT
0069	606-07484	MILLED HMA CORRUGATIONS	3521.00	LFT
0070	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	8.00	SYS
0071	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	881.00	SYS
0072	615-06535	BENCH MARK POST, RESET	1.00	EACH
0073	615-08351	PLAQUE	1.00	EACH
0074	616-05688	RIPRAP, CLASS 1	55.00	TON
0075	616-06405	RIPRAP, REVETMENT	1374.00	TON
0076	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	775.00	SYS
0077	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	534.00	SYS
0078	616-51367	SLOPEWALL, CONCRETE, 4 IN.	990.00	SYS
0079	616-93772	INSPECTION HOLE	16.00	EACH
0080	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0081	619-11051	CLEAN STEEL BRIDGE, QP-1, BRIDGE NO.	1.00	LS
0082	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0083	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0084	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0085	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0086	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0087	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0088	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0089	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0090	619-98427	CLEAN DRAINS	12.00	EACH
0091	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0092	621-06560	MULCHED SEEDING U	2500.00	SYS
0093	621-06574	SODDING	182.00	SYS
0094	628-09403	FIELD OFFICE, C	14.00	MOS
0095	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0096	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	24.00	EACH
0097	702-51863	FIELD DRILLED HOLE IN CONCRETE	38.00	EACH
0098	703-06029	REINFORCING BARS, EPOXY COATED	433620.00	LBS
0099	703-08247	EMBEDDED GALVANIC ANODE	1042.00	EACH
0100	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	275.00	EACH
0101	704-51002	CONCRETE, C, SUPERSTRUCTURE	1340.20	CYS
0102	706-05732	CONCRETE BRIDGE RAILING TRANSITION, TBC	4.00	EACH
0103	706-11600	RAILING, CONCRETE FC	103.50	CYS
0104	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	3.00	EACH

0105	708-51813	PNEUMATICALLY PLACED MORTAR	300.00	SFT
0106	708-51814	WELDED STEEL WIRE FABRIC	300.00	SFT
0107	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0108	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0109	709-51821	SURFACE SEAL	1.00	LS
0110	709-51821	SURFACE SEAL	1.00	LS
0111	709-51821	SURFACE SEAL	1.00	LS
0112	709-51821	SURFACE SEAL	1.00	LS
0113	709-51821	SURFACE SEAL	1.00	LS
0114	709-51821	SURFACE SEAL	1.00	LS
0115	709-51821	SURFACE SEAL	1.00	LS
0116	709-51821	SURFACE SEAL	1.00	LS
0117	709-51821	SURFACE SEAL	1.00	LS
0118	709-51821	SURFACE SEAL	1.00	LS
0119	709-51821	SURFACE SEAL	1.00	LS
0120	709-51821	SURFACE SEAL	1.00	LS
0121	710-09158	PATCHING CONCRETE STRUCTURES	4202.00	SFT
0122	711-05728	REPAIR	199.00	EACH
0123	711-05728	REPAIR	624.00	EACH
0124	711-51035	STRUCTURAL STEEL	263.00	LBS
0125	711-51035	STRUCTURAL STEEL	21131.00	LBS
0126	711-51864	DRILLED HOLE	323.00	EACH
0127	711-93035	JACKING AND SUPPORTING, STRUCTURAL STEEL	1.00	LS
0128	711-96800	STUD SHEAR CONNECTORS	10131.00	EACH
0129	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	720.00	LFT
0130	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	120.00	LFT
0131	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	301.00	LFT
0132	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0133	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	14.00	EACH
0134	715-46000	PIPE END SECTION, DIAMETER 12 IN.	4.00	EACH
0135	718-06526	HMA FOR UNDERDRAINS	42.00	TON
0136	718-06528	OUTLET PROTECTOR, 1	4.00	EACH
0137	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	840.00	LFT
0138	718-12309	GEOTEXTILE FOR UNDERDRAIN, TYPE 3	400.00	SYS
0139	718-52610	AGGREGATE FOR UNDERDRAINS	21.00	CYS
0140	720-45090	INLET, UA	4.00	EACH
0141	720-45095	INLET, WA	5.00	EACH
0142	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	1139.00	SFT
0143	722-51842	BRIDGE DECK OVERLAY	3617.00	SYS
0144	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	49.00	CYS
0145	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1698.00	SFT
0146	722-51874	OVERLAY DAM	131.00	SFT
0147	722-60824	SURFACE MILLING	3617.00	SYS

0148	724-03276	STRUCTURAL EXPANSION JOINT SEALING SYS	56.00	LFT
0149	724-11063	STRUCTURAL EXPANSION JOINT, SS, REPLACE	180.00	LFT
0150	724-12103	PRE-COMPRESSED FOAM JOINT	198.00	LFT
0151	724-51925	STRUCTURAL EXPANSION JOINT, SS	181.00	LFT
0152	726-92406	BEARING ASSEMBLY ELASTOMERIC	2.00	EACH
0153	729-11819	STRAIGHTEN STEEL MEMBER	1.00	LS
0154	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	4833.00	SYS
0155	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0156	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	2.00	EACH
0157	801-02595	CONTROLLER RESET TIMING	2.00	EACH
0158	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0159	801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.00	EACH
0160	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	15318.00	LFT
0161	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	80635.00	LFT
0162	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00	LS
0163	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	30.00	LFT
0164	801-06625	DETOUR ROUTE MARKER ASSEMBLY	20.00	EACH
0165	801-06640	CONSTRUCTION SIGN, A	440.00	EACH
0166	801-06645	CONSTRUCTION SIGN, B	49.00	EACH
0167	801-06710	FLASHING ARROW SIGN	1283.00	DAY
0168	801-06775	MAINTAINING TRAFFIC	1.00	LS
0169	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	EACH
0170	801-07118	BARRICADE, III-A	180.00	LFT
0171	801-07119	BARRICADE, III-B	84.00	LFT
0172	801-07612	TEMPORARY PAVEMENT MARKING, 24 IN.	22.00	LFT
0173	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	5252.00	LFT
0174	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	4207.00	LFT
0175	801-92448	CONSTRUCTION SIGNS MOBILE	10.00	DAY
0176	801-94295	SIGNAL HEAD RELOCATE	2.00	EACH
0177	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	73.00	LFT
0178	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	6.00	SFT
0179	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	63.00	SFT
0180	804-11920	DELINEATOR POST FLEXIBLE, TYPE I	4.00	EACH
0181	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1083.00	LFT
0182	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	7.60	SYS
0183	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1866.00	LFT
0184	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3614.00	LFT
0185	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	41.00	LFT
0186	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	128.00	LFT
0187	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2486.00	LFT
0188	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1649.00	LFT
0189	808-06716	LINE, REMOVE	29308.25	LFT
0190	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	6192.00	LFT

0191	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	7464.00	LFT
0192	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	9163.00	LFT
0193	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	1467.00	LFT
0194	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	70.00	LFT
0195	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	4.00	EACH
0196	808-10101	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 8 IN.	140.00	LFT
0197	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	195.00	LFT
0198	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2054.00	LFT
0199	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	181.00	EACH
0200	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	133.00	EACH
0201	808-95933	CURB, PAINTING, YELLOW	1055.00	LFT

Call: 701

Contract: B -36679-A

Section No.: 2 BRIDGE REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0202	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0203	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0204	709-51821	SURFACE SEAL	1.00	LS
0205	801-06710	FLASHING ARROW SIGN	2.00	DAY
0206	801-06775	MAINTAINING TRAFFIC	1.00	LS
0207	801-92448	CONSTRUCTION SIGNS MOBILE	2.00	DAY
0208	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	41.00	LFT
0209	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	326.00	LFT
0210	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	3.00	EACH

Call: 711

Contract: B -36701-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02272	PAVED SIDE DITCH, REMOVE	49.00	LFT

0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0014	203-02000	EXCAVATION, COMMON	465.00	CYS
0015	205-12108	STORM WATER MANAGEMENT BUDGET	6617.75	DOL
0016	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0017	207-09935	SUBGRADE TREATMENT, TYPE IC	746.00	SYS
0018	211-09265	STRUCTURE BACKFILL, TYPE 2	753.00	CYS
0019	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	1332.00	SYS
0020	301-12232	COMPACTED AGGREGATE NO 5	211.00	CYS
0021	301-12234	COMPACTED AGGREGATE NO 53	106.00	CYS
0022	303-01180	COMPACTED AGGREGATE NO. 53	242.00	TON
0023	304-07493	WIDENING WITH HMA, TYPE B	82.50	TON
0024	306-08034	MILLING, ASPHALT, 1 1/2 IN.	786.00	SYS
0025	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	113.00	TON
0026	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	47.60	TON
0027	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	58.20	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	390.00	LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	685.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	390.00	LFT
0031	406-05521	ASPHALT FOR TACK COAT	2001.00	SYS
0032	601-02241	GUARDRAIL, REMOVE	382.00	LFT
0033	601-06854	GUARDRAIL, W-BEAM, NESTED	2.00	EACH
0034	601-91147	GUARDRAIL END TREATMENT, RESET	4.00	EACH
0035	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	131.20	LFT
0036	615-06505	MONUMENT, B	2.00	EACH
0037	616-05688	RIPRAP, CLASS 1	90.00	TON
0038	616-06405	RIPRAP, REVETMENT	208.00	TON
0039	616-06451	RIPRAP, UNIFORM	40.00	TON
0040	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	551.00	SYS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0042	621-02770	EROSION CONTROL BLANKET	853.00	SYS
0043	621-06559	MULCHED SEEDING R	853.00	SYS
0044	621-06567	WATER	0.20	kGAL
0045	621-06574	SODDING	45.00	SYS
0046	628-09402	FIELD OFFICE, B	12.00	MOS
0047	628-11729	CELLULAR TELEPHONE, TYPE A	3.00	EACH
0048	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0049	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0050	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	36.00	MOS
0051	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0052	714-11146	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 14 FT X 9 FT	58.00	LFT
0053	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	77.00	LFT
0054	715-05051	PIPE, TYPE 4, CIRCULAR, 10 IN.	46.00	LFT
0055	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	66.00	LFT

0056	715-09064	VIDEO INSPECTION FOR PIPE	201.00	LFT
0057	719-05442	PIPE, DRAIN. TILE TERMINAL SECTION, 10 IN.	20.00	LFT
0058	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0059	801-06625	DETOUR ROUTE MARKER ASSEMBLY	60.00	EACH
0060	801-06640	CONSTRUCTION SIGN, A	24.00	EACH
0061	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0062	801-06775	MAINTAINING TRAFFIC	1.00	LS
0063	801-07118	BARRICADE, III-A	72.00	LFT
0064	801-07119	BARRICADE, III-B	48.00	LFT
0065	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	12.50	LFT
0066	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	6.20	SFT
0067	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	100.00	LFT
0068	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	780.00	LFT
0069	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	390.00	LFT
0070	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6.00	EACH
0071	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	6.00	EACH

Call: 721

Contract: B -36920-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	128.00	SYS
0012	202-02278	CURB, CONCRETE, REMOVE	806.00	LFT
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0014	202-91385	INLET, REMOVE	8.00	EACH
0015	202-95027	IMPACT ATTENUATOR, REMOVE	2.00	EACH
0016	202-96133	PIPE, REMOVE	176.00	LFT
0017	203-02000	EXCAVATION, COMMON	3616.00	CYS
0018	205-12108	STORM WATER MANAGEMENT BUDGET	8800.00	DOL
0019	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0020	206-93520	TEMPORARY SHEET PILING	1755.00	SFT
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	2251.00	SYS

0022	211-02050	B BORROW	927.00	CYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	121.00	CYS
0024	211-09266	STRUCTURE BACKFILL, TYPE 3	1160.00	CYS
0025	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	4.00	CYS
0026	301-12234	COMPACTED AGGREGATE NO 53	92.00	CYS
0027	302-07455	DENSE GRADED SUBBASE	30.00	CYS
0028	303-01180	COMPACTED AGGREGATE NO. 53	132.00	TON
0029	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	165.00	TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	334.00	TON
0031	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	400.00	TON
0032	401-10258	JOINT ADHESIVE, SURFACE	1300.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	1300.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	1300.00	LFT
0035	406-05521	ASPHALT FOR TACK COAT	4034.00	SYS
0036	503-05240	D-1 CONTRACTION JOINT	30.00	LFT
0037	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	4.00	EACH
0038	601-02241	GUARDRAIL, REMOVE	616.00	LFT
0039	601-06035	GUARDRAIL, RESET	138.00	LFT
0040	601-06233	IMPACT ATTENUATOR, ED-W1, TL-3	2.00	EACH
0041	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	88.00	LFT
0042	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	2.00	EACH
0043	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	2.00	EACH
0044	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0045	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	175.00	LFT
0046	602-06729	BARRIER, DELINEATOR	10.00	EACH
0047	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	178.00	SYS
0048	615-06505	MONUMENT, B	2.00	EACH
0049	616-06405	RIPRAP, REVETMENT	256.00	TON
0050	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	467.00	SYS
0051	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0052	621-06559	MULCHED SEEDING R	2940.00	SYS
0053	621-06567	WATER	0.60	KGAL
0054	621-06574	SODDING	165.00	SYS
0055	628-09402	FIELD OFFICE, B	12.00	MOS
0056	701-06011	DYNAMIC PILE LOAD TEST	3.00	EACH
0057	701-09557	TEST PILE, DYNAMIC, PRODUCTION	230.00	LFT
0058	701-09559	TEST PILE, DYNAMIC, RESTRIKE	3.00	EACH
0059	701-09663	PILE, STEEL PIPE, 0.312 IN., 14 IN.	1520.00	LFT
0060	701-09679	CONICAL PILE TIP, 14 IN.	30.00	EACH
0061	702-51015	CONCRETE, B, FOOTINGS	42.00	CYS
0062	702-92857	CONCRETE, C, SUBSTRUCTURE	56.00	CYS
0063	703-06028	REINFORCING BARS	23650.00	LBS
0064	703-06029	REINFORCING BARS, EPOXY COATED	95169.00	LBS

0065	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	42.00	EACH
0066	704-51002	CONCRETE, C, SUPERSTRUCTURE	217.30	CYS
0067	706-08500	REINFORCED CONCRETE MOMENT SLAB, 14 IN.	64.00	SYS
0068	706-11600	RAILING, CONCRETE FC	38.20	CYS
0069	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0070	707-05984	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 45 IN. X 16 IN.	748.00	LFT
0071	709-51821	SURFACE SEAL	1.00	LS
0072	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	188.00	LFT
0073	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	88.00	LFT
0074	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	100.00	LFT
0075	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	146.00	SYS
0076	718-52610	AGGREGATE FOR UNDERDRAINS	16.00	CYS
0077	720-45075	INLET, R13	4.00	EACH
0078	731-93945	FACE PANELS, CONCRETE	4286.00	SFT
0079	731-93946	WALL ERECTION	4286.00	SFT
0080	731-93947	LEVELING PAD, CONCRETE	258.00	LFT
0081	801-03290	CONSTRUCTION SIGN, C	1.00	EACH
0082	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0083	801-06625	DETOUR ROUTE MARKER ASSEMBLY	19.00	EACH
0084	801-06640	CONSTRUCTION SIGN, A	28.00	EACH
0085	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0086	801-06775	MAINTAINING TRAFFIC	1.00	LS
0087	801-07118	BARRICADE, III-A	48.00	LFT
0088	801-07119	BARRICADE, III-B	96.00	LFT
0089	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1040.00	LFT
0090	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	115.00	LFT
0091	802-07060	SIGN, SHEET, RELOCATE	15.00	EACH
0092	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1277.00	LFT
0093	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1278.00	LFT

Call: 731

Contract: B -37824-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	105-12018	UTILITY PROTECTION	1.00	LS
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL

0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	162.00	SYS
0014	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0015	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0016	203-02000	EXCAVATION, COMMON	329.00	CYS
0017	203-02070	BORROW	54.00	CYS
0018	203-51223	EXCAVATION, WATERWAY	359.00	CYS
0019	205-12108	STORM WATER MANAGEMENT BUDGET	17100.00	DOL
0020	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0021	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	44.00	CYS
0022	206-51235	COFFERDAM	1.00	LS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	731.00	SYS
0024	211-09265	STRUCTURE BACKFILL, TYPE 2	160.00	CYS
0025	211-09268	STRUCTURE BACKFILL, TYPE 5	58.00	CYS
0026	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	18.00	CYS
0027	301-12232	COMPACTED AGGREGATE NO 5	26.00	CYS
0028	301-12234	COMPACTED AGGREGATE NO 53	9.00	CYS
0029	302-07455	DENSE GRADED SUBBASE	45.00	CYS
0030	303-01180	COMPACTED AGGREGATE NO. 53	364.00	TON
0031	306-08034	MILLING, ASPHALT, 1 1/2 IN.	270.00	SYS
0032	306-08043	MILLING, TRANSITION	1053.00	SYS
0033	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	155.00	TON
0034	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	116.00	TON
0035	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	272.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	1339.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	944.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	1339.00	LFT
0039	406-05521	ASPHALT FOR TACK COAT	3183.00	SYS
0040	601-01128	GUARDRAIL, TRANSITION, TYPE WGB	4.00	EACH
0041	601-01700	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 1	1.00	EACH
0042	601-02241	GUARDRAIL, REMOVE	496.00	LFT
0043	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0044	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	269.00	LFT
0045	602-06729	BARRIER, DELINEATOR	8.00	EACH
0046	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	271.00	SYS
0047	615-06490	RIGHT-OF-WAY MARKER	4.00	EACH
0048	615-06505	MONUMENT, B	4.00	EACH
0049	616-05688	RIPRAP, CLASS 1	561.00	TON
0050	616-05689	RIPRAP, CLASS 2	119.00	TON
0051	616-06405	RIPRAP, REVETMENT	109.00	TON

0052	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	837.00	SYS
0053	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0054	621-02770	EROSION CONTROL BLANKET	81.00	SYS
0055	621-03787	SEED MIXTURE D	3.00	LBS
0056	621-06559	MULCHED SEEDING R	1597.00	SYS
0057	621-06567	WATER	1.00	kGAL
0058	621-06574	SODDING	115.00	SYS
0059	622-52436	SIGN, DO NOT MOW OR SPRAY	4.00	EACH
0060	628-09402	FIELD OFFICE, B	14.00	MOS
0061	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0062	701-09558	TEST PILE, INDICATOR, PRODUCTION	368.00	LFT
0063	701-09560	TEST PILE, INDICATOR, RESTRIKE	4.00	EACH
0064	701-09739	PILE SHOE, HP 12 X 53	28.00	EACH
0065	701-51195	PILE, STEEL H HP 12 X 53	1797.00	LFT
0066	701-97874	PILE, STEEL H, REINFORCED CONCRETE ENCASED, HP, 12 X 53	196.00	LFT
0067	702-51046	CONCRETE, FOUNDATION SEAL	6.00	CYS
0068	703-01540	THREADED TIE BAR ASSEMBLY	42.00	EACH
0069	703-06029	REINFORCING BARS, EPOXY COATED	113232.00	LBS
0070	704-51002	CONCRETE, C, SUPERSTRUCTURE	355.00	CYS
0071	706-11622	CONCRETE BRIDGE RAILING TRANSITION, WFC	4.00	EACH
0072	706-51020	RAILING, CONCRETE C	19.60	CYS
0073	709-51821	SURFACE SEAL	1.00	LS
0074	714-11175	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 5 FT.	66.00	LFT
0075	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00	EACH
0076	801-06625	DETOUR ROUTE MARKER ASSEMBLY	30.00	EACH
0077	801-06640	CONSTRUCTION SIGN, A	30.00	EACH
0078	801-06645	CONSTRUCTION SIGN, B	1.00	EACH
0079	801-06775	MAINTAINING TRAFFIC	1.00	LS
0080	801-07118	BARRICADE, III-A	120.00	LFT
0081	801-07119	BARRICADE, III-B	96.00	LFT
0082	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	56.00	LFT
0083	802-07060	SIGN, SHEET, RELOCATE	4.00	EACH
0084	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	6.25	SFT
0085	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	73.00	LFT
0086	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1440.00	LFT
0087	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2620.00	LFT
0088	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	15.00	EACH
0089	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	15.00	EACH

Call: 741

Contract: B -38575-A

Section No.: 1 REPLACE SUPERSTRUCTURE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	5.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-01066	HYDRO DEMOLITION	2760.00	SYS
0014	202-02240	PAVEMENT REMOVAL	290.00	SYS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0018	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0019	202-51822	BRIDGE DECK OVERLAY, REMOVE	2760.00	SYS
0020	202-93741	GUARDRAIL, END TREATMENT, REMOVE	4.00	EACH
0021	203-02000	EXCAVATION, COMMON	337.00	CYS
0022	203-02070	BORROW	412.00	CYS
0023	203-51223	EXCAVATION, WATERWAY	247.00	CYS
0024	205-11626	PUMP AROUND	2.00	EACH
0025	205-12108	STORM WATER MANAGEMENT BUDGET	25774.00	DOL
0026	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0027	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	18.00	CYS
0028	206-51235	COFFERDAM	1.00	LS
0029	207-09935	SUBGRADE TREATMENT, TYPE IC	667.00	SYS
0030	211-02050	B BORROW	252.00	CYS
0031	211-06467	AGGREGATE FOR END BENT BACKFILL	8.00	CYS
0032	211-09266	STRUCTURE BACKFILL, TYPE 3	180.00	CYS
0033	213-09270	FLOWABLE BACKFILL, REMOVABLE	18.00	CYS
0034	302-07455	DENSE GRADED SUBBASE	76.00	CYS
0035	303-01180	COMPACTED AGGREGATE NO. 53	403.00	TON
0036	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	421.00	TON
0037	306-08034	MILLING, ASPHALT, 1 1/2 IN.	596.00	SYS
0038	306-08043	MILLING, TRANSITION	1445.00	SYS
0039	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	125.00	TON
0040	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	99.00	TON
0041	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	104.00	TON
0042	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	71.00	TON

0043	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	49.00	TON
0044	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	170.00	TON
0045	401-10258	JOINT ADHESIVE, SURFACE	2386.00	LFT
0046	401-10259	JOINT ADHESIVE, INTERMEDIATE	1470.00	LFT
0047	401-11785	LIQUID ASPHALT SEALANT	2386.00	LFT
0048	404-05514	SEAL COAT, 5	210.00	SYS
0049	406-05521	ASPHALT FOR TACK COAT	3441.00	SYS
0050	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.20	TON
0051	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	4.00	EACH
0052	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	1.00	EACH
0053	601-02241	GUARDRAIL, REMOVE	2085.00	LFT
0054	601-02800	GUARDRAIL, TRANSITION, TGT	4.00	EACH
0055	601-05585	GUARDRAIL, TERMINAL SYSTEM, W- BEAM, CURVED, 8	1.00	EACH
0056	601-06053	GUARDRAIL	4.00	EACH
0057	601-11624	GUARDRAIL, TRANSITION, TGR	8.00	EACH
0058	601-94689	GUARDRAIL, END TREATMENT, OS	14.00	EACH
0059	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	1163.00	LFT
0060	602-06729	BARRIER, DELINEATOR	48.00	EACH
0061	605-06095	CURB, INTEGRAL B CONCRETE	56.00	LFT
0062	605-08636	CURB AND GUTTER, TURNOUT COMBINED	10.00	LFT
0063	606-07484	MILLED HMA CORRUGATIONS	1131.00	LFT
0064	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	152.00	SYS
0065	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	305.00	SYS
0066	615-06490	RIGHT-OF-WAY MARKER	16.00	EACH
0067	615-06505	MONUMENT, B	6.00	EACH
0068	615-06530	BENCH MARK POST	1.00	EACH
0069	616-05688	RIPRAP, CLASS 1	298.00	TON
0070	616-05689	RIPRAP, CLASS 2	1237.00	TON
0071	616-06405	RIPRAP, REVETMENT	707.00	TON
0072	616-07210	FIBER ROLL	1305.00	LFT
0073	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1697.00	SYS
0074	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	53.00	SYS
0075	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	865.00	SYS
0076	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0077	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0078	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0079	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0080	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0081	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0082	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00	EACH
0083	621-02770	EROSION CONTROL BLANKET	500.00	SYS
0084	621-04978	SEED MIXTURE	850.00	SYS
0085	621-06559	MULCHED SEEDING R	1930.00	SYS

0086	621-06574	SODDING	107.00	SYS
0087	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN.	41.00	EACH
0088	628-09402	FIELD OFFICE, B	18.00	MOS
0089	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0090	702-51005	CONCRETE, A, SUBSTRUCTURE	19.20	CYS
0091	702-51863	FIELD DRILLED HOLE IN CONCRETE	1364.00	EACH
0092	702-92857	CONCRETE, C, SUBSTRUCTURE	3.20	CYS
0093	703-01540	THREADED TIE BAR ASSEMBLY	32.00	EACH
0094	703-06028	REINFORCING BARS	2663.00	LBS
0095	703-06029	REINFORCING BARS, EPOXY COATED	61221.00	LBS
0096	703-08247	EMBEDDED GALVANIC ANODE	100.00	EACH
0097	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	175.00	EACH
0098	704-51002	CONCRETE, C, SUPERSTRUCTURE	166.90	CYS
0099	706-08188	RAILING, STEEL TR	1408.00	LFT
0100	706-08352	RAILING, CF-1	537.00	LFT
0101	706-11600	RAILING, CONCRETE FC	15.00	CYS
0102	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0103	709-51821	SURFACE SEAL	1.00	LS
0104	709-51821	SURFACE SEAL	1.00	LS
0105	709-51821	SURFACE SEAL	1.00	LS
0106	709-51821	SURFACE SEAL	1.00	LS
0107	710-09158	PATCHING CONCRETE STRUCTURES	511.00	SFT
0108	711-51035	STRUCTURAL STEEL	88193.00	LBS
0109	711-51035	STRUCTURAL STEEL	2011.00	LBS
0110	711-51035	STRUCTURAL STEEL	1646.00	LBS
0111	711-51864	DRILLED HOLE	42.00	EACH
0112	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS
0113	711-95291	JACKING AND SUPPORTING, STEEL BEAMS	1.00	LS
0114	711-95291	JACKING AND SUPPORTING, STEEL BEAMS	1.00	LS
0115	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	115.00	LFT
0116	715-05407	PIPE, END BENT DRAIN, 6 IN.	75.00	LFT
0117	715-06802	CONCRETE ANCHOR, MIN. AREA 18.1 SFT	1.00	EACH
0118	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	52.00	SYS
0119	718-12309	GEOTEXTILE FOR UNDERDRAIN, TYPE 3	73.00	SYS
0120	718-52610	AGGREGATE FOR UNDERDRAINS	8.00	CYS
0121	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	1764.00	SFT
0122	722-51842	BRIDGE DECK OVERLAY	805.00	SYS
0123	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	56.00	CYS
0124	722-51874	OVERLAY DAM	84.00	SFT
0125	722-60824	SURFACE MILLING	2760.00	SYS
0126	724-12103	PRE-COMPRESSED FOAM JOINT	84.00	LFT
0127	724-51925	STRUCTURAL EXPANSION JOINT, SS	72.00	LFT
0128	725-11868	PIPE LINER, CURED-IN-PLACE, MIN AREA 18.1 SFT	116.50	LFT

0129	726-11773	BEARING ASSEMBLY RESET	11.00	EACH
0130	731-93945	FACE PANELS, CONCRETE	1212.00	SFT
0131	731-93946	WALL ERECTION	1212.00	SFT
0132	731-93947	LEVELING PAD, CONCRETE	96.00	LFT
0133	732-11770	AGGREGATE FOR DRAINAGE FILL	259.00	CYS
0134	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0135	801-03290	CONSTRUCTION SIGN, C	5.00	EACH
0136	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0137	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	13130.00	LFT
0138	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	46.00	LFT
0139	801-06625	DETOUR ROUTE MARKER ASSEMBLY	102.00	EACH
0140	801-06640	CONSTRUCTION SIGN, A	71.00	EACH
0141	801-06645	CONSTRUCTION SIGN, B	15.00	EACH
0142	801-06775	MAINTAINING TRAFFIC	1.00	LS
0143	801-07118	BARRICADE, III-A	104.00	LFT
0144	801-07119	BARRICADE, III-B	120.00	LFT
0145	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	490.00	LFT
0146	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1370.00	LFT
0147	801-12081	PORTABLE SIGNAL	1.00	LS
0148	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	4654.00	LFT
0149	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	4974.00	LFT
0150	808-06716	LINE, REMOVE	5675.00	LFT
0151	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	231.00	LFT
0152	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	231.00	LFT
0153	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	61.00	EACH
0154	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	60.00	EACH

Call: 741

Contract: B -38575-A

Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0155	722-51842	BRIDGE DECK OVERLAY	1310.00	SYS
0156	722-51842	BRIDGE DECK OVERLAY	831.00	SYS

Call: 741

Contract: B -38575-A

Section No.: 3 MICROSILICA CONCRETE OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0157	736-01061	BRIDGE DECK OVERLAY MICROSILICA	1310.00	SYS
0158	736-01061	BRIDGE DECK OVERLAY MICROSILICA	831.00	SYS

Call: 751

Contract: B -38608-A

Section No.: 1 SUBSTRUCTURE REPAIR AND REHABILITATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	202-51368	SLOPEWALL, REMOVE	55.00	SYS
0009	205-12108	STORM WATER MANAGEMENT BUDGET	200.00	DOL
0010	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0011	211-02050	B BORROW	22.00	CYS
0012	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	50.00	CYS
0013	507-08271	JOINTS IN PCCP, FILLED	110.00	LFT
0014	616-06405	RIPRAP, REVETMENT	8.00	TON
0015	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	25.00	SYS
0016	616-51367	SLOPEWALL, CONCRETE, 4 IN.	55.00	SYS
0017	616-93772	INSPECTION HOLE	10.00	EACH
0018	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	20.00	LFT
0019	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0020	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00	EACH
0021	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	20.00	SFT
0022	801-06625	DETOUR ROUTE MARKER ASSEMBLY	23.00	EACH
0023	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0024	801-06645	CONSTRUCTION SIGN, B	3.00	EACH
0025	801-06775	MAINTAINING TRAFFIC	1.00	LS
0026	801-07118	BARRICADE, III-A	176.00	LFT
0027	801-07119	BARRICADE, III-B	44.00	LFT

Call: 761

Contract: B -38613-B

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL

0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0014	202-01066	HYDRO DEMOLITION	10162.00	SYS
0015	202-02240	PAVEMENT REMOVAL	11576.00	SYS
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0018	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0019	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0020	202-51368	SLOPEWALL, REMOVE	48.00	SYS
0021	202-94954	BARRIER WALL, CONCRETE, REMOVE	1312.00	LFT
0022	203-04523	DEWATERING	1.00	LS
0023	205-11626	PUMP AROUND	2.00	EACH
0024	205-12108	STORM WATER MANAGEMENT BUDGET	31206.00	DOL
0025	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0026	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	277.00	CYS
0027	206-51235	COFFERDAM	1.00	LS
0028	207-09935	SUBGRADE TREATMENT, TYPE IC	8373.00	SYS
0029	211-09267	STRUCTURE BACKFILL, TYPE 4	11.00	CYS
0030	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	40.00	CYS
0031	213-09270	FLOWABLE BACKFILL, REMOVABLE	115.00	CYS
0032	302-06464	SUBBASE FOR PCCP	1623.00	CYS
0033	302-07455	DENSE GRADED SUBBASE	504.00	CYS
0034	306-08043	MILLING, TRANSITION	734.00	SYS
0035	306-08159	MILLING, ASPHALT	294.00	SYS
0036	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	86.00	TON
0037	401-10258	JOINT ADHESIVE, SURFACE	630.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	630.00	LFT
0039	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0040	502-06329	PCCP, 12 IN.	8284.00	SYS
0041	503-03489	RETROFITTED TIE BARS	714.00	EACH
0042	503-05240	D-1 CONTRACTION JOINT	4679.00	LFT
0043	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	725.00	LFT
0044	601-02241	GUARDRAIL, REMOVE	544.00	LFT
0045	601-06035	GUARDRAIL, RESET	1304.00	LFT
0046	601-06303	IMPACT ATTENUATOR, RESET, R2-W2, TL-2	3.00	EACH
0047	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	50.00	LFT
0048	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	5.00	EACH
0049	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	7.00	EACH
0050	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	2.00	EACH

0051	602-01064	CONCRETE BARRIER	1024.00	LFT
0052	602-06729	BARRIER, DELINEATOR	158.00	EACH
0053	603-06060	FENCE, FARM FIELD, RESET	100.00	LFT
0054	604-02007	SIDEWALK, CONCRETE, RECONSTRUCT	11.00	SYS
0055	606-11064	MILLED PCCP CORRUGATIONS	2940.00	LFT
0056	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	3140.00	SYS
0057	616-05688	RIPRAP, CLASS 1	31.00	TON
0058	616-06405	RIPRAP, REVETMENT	936.00	TON
0059	616-06406	RIPRAP, REVETMENT	46.00	SYS
0060	616-06451	RIPRAP, UNIFORM	8.00	TON
0061	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	639.00	SYS
0062	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	154.00	SYS
0063	616-51367	SLOPEWALL, CONCRETE, 4 IN.	48.00	SYS
0064	616-93772	INSPECTION HOLE	48.00	EACH
0065	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0066	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0067	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0068	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0069	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	13.00	EACH
0070	621-06560	MULCHED SEEDING U	2968.00	SYS
0071	621-06567	WATER	3.00	KGAL
0072	621-06574	SODDING	957.00	SYS
0073	628-09403	FIELD OFFICE, C	15.00	MOS
0074	628-11729	CELLULAR TELEPHONE, TYPE A	2.00	EACH
0075	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0076	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0077	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	30.00	MOS
0078	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	EACH
0079	628-11977	COMPUTER SYSTEM	2.00	EACH
0080	701-93790	CLEAN AND EPOXY COAT EXISTING PILES	1.00	LS
0081	702-51005	CONCRETE, A, SUBSTRUCTURE	11.00	CYS
0082	702-51015	CONCRETE, B, FOOTINGS	3.00	CYS
0083	702-51863	FIELD DRILLED HOLE IN CONCRETE	513.00	EACH
0084	703-06029	REINFORCING BARS, EPOXY COATED	213534.00	LBS
0085	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	1221.00	EACH
0086	704-51002	CONCRETE, C, SUPERSTRUCTURE	202.80	CYS
0087	706-11600	RAILING, CONCRETE FC	11.80	CYS
0088	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00	EACH
0089	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0090	709-51821	SURFACE SEAL	1.00	LS
0091	709-51821	SURFACE SEAL	1.00	LS
0092	709-51821	SURFACE SEAL	1.00	LS
0093	709-51821	SURFACE SEAL	1.00	LS

0094	709-51821	SURFACE SEAL	1.00	LS
0095	709-51821	SURFACE SEAL	1.00	LS
0096	709-51821	SURFACE SEAL	1.00	LS
0097	709-51821	SURFACE SEAL	1.00	LS
0098	709-51821	SURFACE SEAL	1.00	LS
0099	710-09158	PATCHING CONCRETE STRUCTURES	2276.00	SFT
0100	711-51038	STRUCTURAL STEEL	1.00	LS
0101	711-51038	STRUCTURAL STEEL	1.00	LS
0102	711-51038	STRUCTURAL STEEL	1.00	LS
0103	711-51038	STRUCTURAL STEEL	1.00	LS
0104	711-51864	DRILLED HOLE	144.00	EACH
0105	713-04331	TEMPORARY CAUSEWAY	1.00	LS
0106	715-01354	CLEAN EXISTING PIPE	600.00	LFT
0107	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	2730.00	LFT
0108	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	35.00	EACH
0109	715-92037	PIPE PVC 4 IN	359.00	LFT
0110	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	1820.00	SYS
0111	718-52610	AGGREGATE FOR UNDERDRAINS	228.00	CYS
0112	720-01355	INLET, CLEAN EXISTING	13.00	EACH
0113	720-44000	CASTING, ADJUST TO GRADE	8.00	EACH
0114	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	3795.00	SFT
0115	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	95.80	CYS
0116	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1463.00	SFT
0117	722-51874	OVERLAY DAM	684.00	SFT
0118	722-60824	SURFACE MILLING	10162.00	SYS
0119	724-51925	STRUCTURAL EXPANSION JOINT, SS	384.00	LFT
0120	725-11300	PIPE LINER, CURED-IN-PLACE, MIN AREA 8.9 SFT	157.00	LFT
0121	727-90308	EPOXY INJECTION, CRACK PREPARATION	100.00	LFT
0122	727-90309	EPOXY INJECTION, EPOXY MATERIAL	2.00	GAL
0123	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0124	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	1433.00	SYS
0125	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	7.00	EACH
0126	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0127	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	66850.00	LFT
0128	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	4634.00	LFT
0129	801-06625	DETOUR ROUTE MARKER ASSEMBLY	43.00	EACH
0130	801-06640	CONSTRUCTION SIGN, A	173.00	EACH
0131	801-06645	CONSTRUCTION SIGN, B	59.00	EACH
0132	801-06710	FLASHING ARROW SIGN	600.00	DAY
0133	801-06775	MAINTAINING TRAFFIC	1.00	LS
0134	801-07118	BARRICADE, III-A	192.00	LFT
0135	801-07119	BARRICADE, III-B	108.00	LFT
0136	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	3296.00	LFT

0137	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	2026.00	LFT
0138	805-04973	CONDUIT	20.00	LFT
0139	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	593.00	LFT
0140	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	88.50	LFT
0141	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	18457.00	LFT
0142	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	13461.00	LFT
0143	808-06716	LINE, REMOVE	38392.00	LFT
0144	808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	5022.00	LFT
0145	808-75008	LINE, PAINT, SOLID, WHITE, 8 IN.	2670.00	LFT
0146	808-75072	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE 24 IN.	375.00	LFT
0147	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	358.00	EACH
0148	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	345.00	EACH

Call: 761

Contract: B -38613-B

Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0149	722-51842	BRIDGE DECK OVERLAY	10407.00	SYS

Call: 761

Contract: B -38613-B

Section No.: 3 MICROSILICA CONCRETE OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0150	736-01061	BRIDGE DECK OVERLAY MICROSILICA	10407.00	SYS

Call: 771

Contract: B -38645-A

Section No.: 1 BRIDGE PAINTING

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0010	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0011	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0012	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS

0013	709-51821	SURFACE SEAL	1.00	LS
0014	709-51821	SURFACE SEAL	1.00	LS
0015	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0016	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	25832.00	LFT
0017	801-06640	CONSTRUCTION SIGN, A	52.00	EACH
0018	801-06710	FLASHING ARROW SIGN	360.00	DAY
0019	801-06775	MAINTAINING TRAFFIC	1.00	LS
0020	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0021	808-06716	LINE, REMOVE	12916.00	LFT
0022	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0023	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	5740.00	LFT
0024	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	5740.00	LFT
0025	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	1436.00	LFT
0026	808-12032	GROOVING FOR PAVEMENT MARKINGS	12916.00	LFT
0027	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	72.00	EACH
0028	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	72.00	EACH

Call: 775

Contract: B -38681-B

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-01066	HYDRO DEMOLITION	5964.00	SYS
0013	202-51822	BRIDGE DECK OVERLAY, REMOVE	4272.00	SYS
0014	203-02000	EXCAVATION, COMMON	93.00	CYS
0015	205-12108	STORM WATER MANAGEMENT BUDGET	9600.00	DOL
0016	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0017	207-08268	SUBGRADE TREATMENT, TYPE IV	215.00	SYS
0018	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1200.00	SYS
0019	306-08036	MILLING, ASPHALT, 2 IN.	14628.00	SYS
0020	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	1731.00	TON
0021	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	10.40	TON

0022	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	29.60	TON
0023	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	118.50	TON
0024	401-10258	JOINT ADHESIVE, SURFACE	1264.00	LFT
0025	401-11785	LIQUID ASPHALT SEALANT	1264.00	LFT
0026	406-05521	ASPHALT FOR TACK COAT	16306.60	SYS
0027	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	432.00	LFT
0028	601-06035	GUARDRAIL, RESET	2063.00	LFT
0029	616-02281	GROUT FOR RIPRAP	30.00	CYS
0030	616-05688	RIPRAP, CLASS 1	1095.00	TON
0031	616-06405	RIPRAP, REVETMENT	37.00	TON
0032	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1269.00	SYS
0033	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0034	621-01660	MULCHED SEEDING LEGUME, 2	882.00	SYS
0035	621-03787	SEED MIXTURE D	1.50	LBS
0036	621-06567	WATER	0.10	kGAL
0037	621-06574	SODDING	25.00	SYS
0038	628-09402	FIELD OFFICE, B	12.00	MOS
0039	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0040	709-51821	SURFACE SEAL	1.00	LS
0041	709-51821	SURFACE SEAL	1.00	LS
0042	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	2704.00	SFT
0043	722-51842	BRIDGE DECK OVERLAY	6028.00	SYS
0044	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	64.20	CYS
0045	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	5430.00	SFT
0046	722-51874	OVERLAY DAM	1334.00	SFT
0047	722-60824	SURFACE MILLING	6028.00	SYS
0048	724-12103	PRE-COMPRESSED FOAM JOINT	666.00	LFT
0049	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	24.00	EACH
0050	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9936.00	LFT
0051	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	271728.00	LFT
0052	801-06640	CONSTRUCTION SIGN, A	144.00	EACH
0053	801-06710	FLASHING ARROW SIGN	192.00	DAY
0054	801-06775	MAINTAINING TRAFFIC	1.00	LS
0055	801-07118	BARRICADE, III-A	72.00	LFT
0056	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	6362.00	LFT
0057	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	12.00	EACH
0058	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1322.00	LFT
0059	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1322.00	LFT
0060	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	662.00	LFT
0061	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	76.00	EACH

Call: 781

Contract: B -39086-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-01066	HYDRO DEMOLITION	6748.00	SYS
0011	202-02240	PAVEMENT REMOVAL	2487.00	SYS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	202-51822	BRIDGE DECK OVERLAY, REMOVE	5903.00	SYS
0018	203-02000	EXCAVATION, COMMON	11.00	CYS
0019	203-08607	LINEAR GRADING	500.00	LFT
0020	302-07455	DENSE GRADED SUBBASE	423.00	CYS
0021	303-01180	COMPACTED AGGREGATE NO. 53	23.00	TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1924.00	SYS
0023	306-08043	MILLING, TRANSITION	573.00	SYS
0024	306-08599	MILLING, ASPHALT, 1/2 IN.	266.00	SYS
0025	401-10258	JOINT ADHESIVE, SURFACE	2220.00	LFT
0026	401-11785	LIQUID ASPHALT SEALANT	2220.00	LFT
0027	406-05521	ASPHALT FOR TACK COAT	2763.00	SYS
0028	410-09530	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm - SMA	228.30	TON
0029	601-02241	GUARDRAIL, REMOVE	1231.00	LFT
0030	601-06238	IMPACT ATTENUATOR, R1-W1, TL-3	1.00	EACH
0031	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	175.00	LFT
0032	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	10.00	EACH
0033	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	14.00	EACH
0034	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	2.00	EACH
0035	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0036	602-91266	CONCRETE MEDIAN BARRIER MODIFIED	222.00	LFT
0037	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	2486.00	SYS
0038	628-09402	FIELD OFFICE, B	12.00	MOS
0039	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0040	702-51863	FIELD DRILLED HOLE IN CONCRETE	780.00	EACH

0041	703-06029	REINFORCING BARS, EPOXY COATED	164097.00	LBS
0042	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	521.00	EACH
0043	706-11600	RAILING, CONCRETE FC	14.00	CYS
0044	706-11601	RAILING, CONCRETE FT	4.00	CYS
0045	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	7.00	EACH
0046	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	9.00	EACH
0047	709-51821	SURFACE SEAL	1.00	LS
0048	709-51821	SURFACE SEAL	1.00	LS
0049	709-51821	SURFACE SEAL	1.00	LS
0050	709-51821	SURFACE SEAL	1.00	LS
0051	709-51821	SURFACE SEAL	1.00	LS
0052	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	1142.00	SFT
0053	722-51874	OVERLAY DAM	825.00	SFT
0054	722-60824	SURFACE MILLING	8215.00	SYS
0055	724-12157	PREFORMED SILICONE JOINT	825.00	LFT
0056	801-04308	ROAD CLOSURE SIGN ASSEMBLY	18.00	EACH
0057	801-06201	TEMPORARY PANEL SIGNS	2901.00	SFT
0058	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	16746.00	LFT
0059	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	10.00	EACH
0060	801-06625	DETOUR ROUTE MARKER ASSEMBLY	31.00	EACH
0061	801-06640	CONSTRUCTION SIGN, A	138.00	EACH
0062	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0063	801-06710	FLASHING ARROW SIGN	330.00	DAY
0064	801-06775	MAINTAINING TRAFFIC	1.00	LS
0065	801-07118	BARRICADE, III-A	744.00	LFT
0066	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1200.00	LFT
0067	801-11598	ARIES FIELD PROCESSOR FOR PCMS	9.00	EACH
0068	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	9.00	EACH
0069	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2590.00	LFT
0070	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2590.00	LFT
0071	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	820.00	LFT
0072	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	134.00	LFT
0073	808-12032	GROOVING FOR PAVEMENT MARKINGS	1050.00	LFT
0074	808-75994	PRISMATIC REFLECTOR	51.00	EACH
0075	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	50.00	EACH
0076	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	54.00	EACH

Call: 781

Contract: B -39086-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED

Line				
Item No	Item Code	Description	Quantity	Unit
0077	722-51842	BRIDGE DECK OVERLAY	6748.00	SYS

0078 722-51846 BRIDGE DECK OVERLAY, ADDITIONAL

54.00 CYS

Call: 781

Contract: B -39086-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0079	722-51842	BRIDGE DECK OVERLAY	6748.00	SYS
0080	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	54.00	CYS

Call: 791

Contract: B -39255-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	10.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-01066	HYDRO DEMOLITION	241.00	SYS
0014	202-02240	PAVEMENT REMOVAL	331.00	SYS
0015	202-02278	CURB, CONCRETE, REMOVE	21.00	LFT
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0018	202-62420	BRIDGE RAILING, REMOVE	91.00	LFT
0019	202-96133	PIPE, REMOVE	21.00	LFT
0020	203-02000	EXCAVATION, COMMON	450.00	CYS
0021	203-02070	BORROW	20.00	CYS
0022	203-51223	EXCAVATION, WATERWAY	20.00	CYS
0023	205-12108	STORM WATER MANAGEMENT BUDGET	3300.00	DOL
0024	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0025	207-09935	SUBGRADE TREATMENT, TYPE IC	1254.00	SYS
0026	211-09265	STRUCTURE BACKFILL, TYPE 2	51.00	CYS
0027	302-07455	DENSE GRADED SUBBASE	53.00	CYS
0028	303-01180	COMPACTED AGGREGATE NO. 53	176.00	TON
0029	306-08043	MILLING, TRANSITION	1577.00	SYS

0030	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	14.00	TON
0031	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	216.00	TON
0032	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	24.00	TON
0033	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	142.00	TON
0034	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	79.00	TON
0035	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	289.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	1740.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	120.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	1740.00	LFT
0039	402-10086	HMA FOR TEMPORARY PAVEMENT, C	25.00	TON
0040	406-05521	ASPHALT FOR TACK COAT	3979.00	SYS
0041	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	2.00	EACH
0042	601-01626	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 2	2.00	EACH
0043	601-02241	GUARDRAIL, REMOVE	380.00	LFT
0044	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	12.50	LFT
0045	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00	EACH
0046	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0047	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0048	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0049	601-99132	GUARDRAIL, TRANSITION, VH, 6 FT 3 IN. SPACING	1.00	EACH
0050	602-06729	BARRIER, DELINEATOR	4.00	EACH
0051	605-06120	CURB, CONCRETE	15.00	LFT
0052	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	305.00	SYS
0053	610-07487	HMA FOR APPROACHES, TYPE B	4.00	TON
0054	616-06405	RIPRAP, REVETMENT	375.00	TON
0055	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	598.00	SYS
0056	621-06574	SODDING	13.00	SYS
0057	621-06575	SODDING, NURSERY	90.00	SYS
0058	628-09401	FIELD OFFICE, A	4.00	MOS
0059	703-06029	REINFORCING BARS, EPOXY COATED	24833.00	LBS
0060	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	94.00	EACH
0061	704-51002	CONCRETE, C, SUPERSTRUCTURE	11.10	CYS
0062	706-09960	RAILING, CONCRETE FC	60.00	LFT
0063	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0064	709-51821	SURFACE SEAL	1.00	LS
0065	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	54.00	LFT
0066	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	854.00	LFT
0067	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	8.00	LFT
0068	715-05208	PIPE, TYPE 4, CIRCULAR, 15 IN.	58.00	LFT
0069	715-05218	PIPE, TYPE 5, CIRCULAR, 15 IN.	5.00	LFT
0070	715-08283	PCCP FOR STRUCTURE INSTALLATION	5.00	SYS
0071	718-06526	HMA FOR UNDERDRAINS	28.00	TON
0072	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	404.00	SYS

0073	718-52610	AGGREGATE FOR UNDERDRAINS	44.00	CYS
0074	720-44015	CASTING, 2, FURNISH AND ADJUST TO GRADE	1.00	EACH
0075	720-45085	INLET, T14	2.00	EACH
0076	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	50.00	SFT
0077	722-51842	BRIDGE DECK OVERLAY	255.00	SYS
0078	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	3.00	CYS
0079	722-60824	SURFACE MILLING	255.00	SYS
0080	801-03290	CONSTRUCTION SIGN, C	6.00	EACH
0081	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0082	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4539.00	LFT
0083	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	24.00	LFT
0084	801-06625	DETOUR ROUTE MARKER ASSEMBLY	107.00	EACH
0085	801-06640	CONSTRUCTION SIGN, A	34.00	EACH
0086	801-06645	CONSTRUCTION SIGN, B	16.00	EACH
0087	801-06775	MAINTAINING TRAFFIC	1.00	LS
0088	801-07118	BARRICADE, III-A	228.00	LFT
0089	801-07119	BARRICADE, III-B	120.00	LFT
0090	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	50.00	LFT
0091	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	367.00	LFT
0092	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0093	802-04893	REFERENCE POST	1.00	EACH
0094	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	63.00	LFT
0095	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1517.00	LFT
0096	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	80.00	LFT
0097	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	80.00	LFT
0098	808-06716	LINE, REMOVE	1540.00	LFT
0099	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	220.00	LFT
0100	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	194.00	LFT
0101	808-12032	GROOVING FOR PAVEMENT MARKINGS	2924.00	LFT
0102	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	107.00	LFT
0103	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1325.00	LFT
0104	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	120.00	LFT
0105	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	25.00	EACH
0106	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	24.00	EACH

Call: 801

Contract: B -40352-A

Section No.: 1 BRIDGE REHABILITATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL

0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	202-91840	FENCE, CHAIN. LINK, REMOVE	212.00	LFT
0011	205-12108	STORM WATER MANAGEMENT BUDGET	8688.00	DOL
0012	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0013	206-51235	COFFERDAM	1.00	LS
0014	603-06045	FENCE, CHAIN LINK, 48 IN.	212.00	LFT
0015	616-06405	RIPRAP, REVETMENT	1720.00	TON
0016	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	2216.00	SYS
0017	619-04981	CLEAN AND PAINT	1.00	LS
0018	619-04981	CLEAN AND PAINT	1.00	LS
0019	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0020	621-06559	MULCHED SEEDING R	1000.00	SYS
0021	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0022	702-51005	CONCRETE, A, SUBSTRUCTURE	117.20	CYS
0023	703-06028	REINFORCING BARS	25090.00	LBS
0024	709-51821	SURFACE SEAL	1.00	LS
0025	709-51821	SURFACE SEAL	1.00	LS
0026	713-04331	TEMPORARY CAUSEWAY	1.00	LS
0027	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1104.00	SFT
0028	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	6124.00	SYS
0029	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	12640.00	LFT
0030	801-06640	CONSTRUCTION SIGN, A	62.00	EACH
0031	801-06645	CONSTRUCTION SIGN, B	28.00	EACH
0032	801-06710	FLASHING ARROW SIGN	240.00	DAY
0033	801-06775	MAINTAINING TRAFFIC	1.00	LS
0034	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	2380.00	LFT
0035	801-12042	TRUCK MOUNTED ATTENUATOR	120.00	DAY
0036	808-06716	LINE, REMOVE	5970.00	LFT
0037	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2810.00	LFT
0038	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2060.00	LFT
0039	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	1080.00	LFT
0040	808-12032	GROOVING FOR PAVEMENT MARKINGS	5950.00	LFT
0041	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	54.00	EACH
0042	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	54.00	EACH

Call: 811

Contract: B -40354-A

Section No.: 1 BRIDGE DECK OVERLAY

Line Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-01066	HYDRO DEMOLITION	1858.00	SYS
0014	202-02240	PAVEMENT REMOVAL	1232.00	SYS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	202-51822	BRIDGE DECK OVERLAY, REMOVE	1190.00	SYS
0018	203-02000	EXCAVATION, COMMON	280.00	CYS
0019	205-12108	STORM WATER MANAGEMENT BUDGET	34376.00	DOL
0020	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0021	206-51220	EXCAVATION, WET	130.00	CYS
0022	206-51235	COFFERDAM	1.00	LS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	719.00	SYS
0024	302-06464	SUBBASE FOR PCCP	14.00	CYS
0025	302-07455	DENSE GRADED SUBBASE	182.40	CYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	134.00	TON
0027	306-08042	MILLING, SCARIFICATION	1856.00	SYS
0028	306-08043	MILLING, TRANSITION	1855.00	SYS
0029	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	306.00	TON
0030	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	80.00	TON
0031	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	99.00	TON
0032	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	274.00	TON
0033	401-10258	JOINT ADHESIVE, SURFACE	5621.00	LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	2891.00	LFT
0035	401-11785	LIQUID ASPHALT SEALANT	4541.00	LFT
0036	406-05521	ASPHALT FOR TACK COAT	5135.00	SYS
0037	502-06329	PCCP, 12 IN.	106.00	SYS
0038	503-05240	D-1 CONTRACTION JOINT	96.00	LFT
0039	503-05310	TERMINAL JOINT	96.00	LFT
0040	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	8.00	EACH
0041	601-02241	GUARDRAIL, REMOVE	910.00	LFT

0042	601-94689	GUARDRAIL, END TREATMENT, OS	8.00	EACH
0043	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	100.00	LFT
0044	602-06729	BARRIER, DELINEATOR	14.00	EACH
0045	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	1092.00	SYS
0046	611-08232	MAILBOX ASSEMBLY, SINGLE RESET	2.00	EACH
0047	616-06405	RIPRAP, REVETMENT	1356.00	TON
0048	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1844.00	SYS
0049	619-04981	CLEAN AND PAINT	1.00	LS
0050	619-04981	CLEAN AND PAINT	1.00	LS
0051	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0052	621-06559	MULCHED SEEDING R	1508.00	SYS
0053	621-06567	WATER	2.40	kGAL
0054	621-06574	SODDING	12.00	SYS
0055	621-06575	SODDING, NURSERY	553.00	SYS
0056	628-09402	FIELD OFFICE, B	8.00	MOS
0057	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0058	702-51005	CONCRETE, A, SUBSTRUCTURE	26.20	CYS
0059	702-51863	FIELD DRILLED HOLE IN CONCRETE	184.00	EACH
0060	703-01540	THREADED TIE BAR ASSEMBLY	280.00	EACH
0061	703-06028	REINFORCING BARS	2802.00	LBS
0062	703-06029	REINFORCING BARS, EPOXY COATED	85265.00	LBS
0063	703-08247	EMBEDDED GALVANIC ANODE	150.00	EACH
0064	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	164.00	EACH
0065	704-51002	CONCRETE, C, SUPERSTRUCTURE	44.60	CYS
0066	706-11600	RAILING, CONCRETE FC	17.90	CYS
0067	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00	EACH
0068	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0069	709-51821	SURFACE SEAL	1.00	LS
0070	709-51821	SURFACE SEAL	1.00	LS
0071	709-51821	SURFACE SEAL	1.00	LS
0072	709-51821	SURFACE SEAL	1.00	LS
0073	710-09158	PATCHING CONCRETE STRUCTURES	1770.00	SFT
0074	715-06566	PIPE EXTENSION, CIRCULAR, 6 IN.	18.00	LFT
0075	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	620.00	SFT
0076	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	13.80	CYS
0077	722-51874	OVERLAY DAM	586.00	SFT
0078	722-60824	SURFACE MILLING	1858.00	SYS
0079	724-12103	PRE-COMPRESSED FOAM JOINT	420.00	LFT
0080	727-90308	EPOXY INJECTION, CRACK PREPARATION	470.00	LFT
0081	727-90309	EPOXY INJECTION, EPOXY MATERIAL	26.00	GAL
0082	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0083	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0084	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH

0085	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0086	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	15638.00	LFT
0087	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	24.00	LFT
0088	801-06640	CONSTRUCTION SIGN, A	56.00	EACH
0089	801-06645	CONSTRUCTION SIGN, B	18.00	EACH
0090	801-06710	FLASHING ARROW SIGN	240.00	DAY
0091	801-06775	MAINTAINING TRAFFIC	1.00	LS
0092	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	5.00	EACH
0093	801-07118	BARRICADE, III-A	30.00	LFT
0094	801-07119	BARRICADE, III-B	152.00	LFT
0095	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	200.00	LFT
0096	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1425.00	LFT
0097	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0098	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	700.00	LFT
0099	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1960.00	LFT
0100	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1495.00	LFT
0101	808-06716	LINE, REMOVE	6965.00	LFT
0102	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	2400.00	LFT
0103	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1600.00	LFT
0104	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1170.00	LFT
0105	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	17.00	EACH
0106	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	11.00	EACH

Call: 811

Contract: B -40354-A

Section No.: 2 LATEX MODIFIED PORTLAND CEMENT CONCRETE OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0107	722-51842	BRIDGE DECK OVERLAY	1907.00	SYS

Call: 811

Contract: B -40354-A

Section No.: 3 SILCA FUME MODIFIED STRUCTURAL CONCRETE OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0108	736-01061	BRIDGE DECK OVERLAY MICROSILICA	1907.00	SYS

Call: 831

Contract: B -40830-A

Section No.: 1 BRIDGE PAINTING

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL

0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0008	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0009	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0010	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0011	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0012	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0013	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0014	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0015	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0016	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0017	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0018	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0019	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0020	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0021	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0022	801-06640	CONSTRUCTION SIGN, A	205.00	EACH
0023	801-06710	FLASHING ARROW SIGN	90.00	DAY
0024	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 851

Contract: M -40390-A

Section No.: 1 ROADSIDE MAINTENANCE, HERBICIDE TREATMENT

Line			Quantity Unit	
Item No	Item Code	Description		
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	624-92647	HERBICIDE TREATMENT	4597.20	ACRE
0004	628-09409	MOBILE INTERNET SERVICE	3.00	MOS
0005	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0006	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0007	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	3.00	MOS

Call: 861

Contract: M -40391-A

Section No.: 1 WEDGE AND LEVEL

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL

0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	303-07449	COMPACTED AGGREGATE NO. 73	718.00	TON
0010	306-08043	MILLING, TRANSITION	8960.00	SYS
0011	306-08432	MILLING, APPROACH	1923.00	SYS
0012	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	4110.00	TON
0013	401-10258	JOINT ADHESIVE, SURFACE	16324.00	LFT
0014	401-11785	LIQUID ASPHALT SEALANT	16324.00	LFT
0015	406-05520	ASPHALT FOR TACK COAT	13.00	TON
0016	610-07487	HMA FOR APPROACHES, TYPE B	159.00	TON
0017	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0018	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0019	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	2.00	MOS
0020	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1449.00	LFT
0021	801-06640	CONSTRUCTION SIGN, A	32.00	EACH
0022	801-06775	MAINTAINING TRAFFIC	1.00	LS
0023	801-92448	CONSTRUCTION SIGNS MOBILE	360.00	DAY
0024	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	3330.00	LFT
0025	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	28984.00	LFT
0026	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	8117.00	LFT

Call: 871

Contract: M -40392-A

Section No.: 1 WEDGE AND LEVEL

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	207-08264	SUBGRADE TREATMENT, TYPE II	322.00	SYS
0012	303-07449	COMPACTED AGGREGATE NO. 73	903.00	TON
0013	304-07491	HMA PATCHING, TYPE C	297.00	TON
0014	306-08034	MILLING, ASPHALT, 1 1/2 IN.	39966.00	SYS

0015	306-08043	MILLING, TRANSITION	7680.00	SYS
0016	306-08432	MILLING, APPROACH	7352.00	SYS
0017	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	5761.00	TON
0018	401-10258	JOINT ADHESIVE, SURFACE	28613.00	LFT
0019	401-11785	LIQUID ASPHALT SEALANT	28613.00	LFT
0020	406-05520	ASPHALT FOR TACK COAT	21.00	TON
0021	610-07488	HMA FOR APPROACHES, TYPE C	709.00	TON
0022	615-06520	MONUMENT, RE-ESTABLISH	1.00	EACH
0023	720-44000	CASTING, ADJUST TO GRADE	2.00	EACH
0024	720-44080	CASTING, 15, FURNISH AND ADJUST TO GRADE	1.00	EACH
0025	720-45605	STRUCTURE, MANHOLE, RECONSTRUCTED	10.00	LFT
0026	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	2.00	EACH
0027	801-01506	TEMPORARY PAVEMENT MESSAGE MARKING, (RXR)	2.00	EACH
0028	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	3015.00	LFT
0029	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3015.00	LFT
0030	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	2.00	EACH
0031	801-06213	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (RXR)	2.00	EACH
0032	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	30.00	LFT
0033	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	30.00	LFT
0034	801-06640	CONSTRUCTION SIGN, A	67.00	EACH
0035	801-06775	MAINTAINING TRAFFIC	1.00	LS
0036	801-92448	CONSTRUCTION SIGNS MOBILE	360.00	DAY
0037	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	1.00	EACH
0038	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	4210.00	LFT
0039	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	46874.00	LFT
0040	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	24327.00	LFT
0041	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0042	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	30.00	LFT
0043	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	829.00	LFT
0044	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	2.00	EACH
0045	808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC R X R	2.00	EACH
0046	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	220.00	EACH
0047	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	220.00	EACH

Call: 881

Contract: M -40397-B

Section No.: 1 GUARDRAIL MAINTENANCE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL

0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0006	202-93741	GUARDRAIL, END TREATMENT, REMOVE	12.00	EACH
0007	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	2.00	EACH
0008	601-01625	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 1	17.00	EACH
0009	601-01626	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 2	17.00	EACH
0010	601-02241	GUARDRAIL, REMOVE	500.00	LFT
0011	601-03456	GUARDRAIL POST, WOOD TYPE W5	9.00	EACH
0012	601-03457	GUARDRAIL W THRIE BEAM RAIL SECTION, 12FT-6 IN	11.00	EACH
0013	601-03464	GUARDRAIL, STEEL CURVED TERMINAL END SECTION	5.00	EACH
0014	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	13.00	EACH
0015	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	17.00	EACH
0016	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	15.00	EACH
0017	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	15.00	EACH
0018	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	17.00	EACH
0019	601-03492	GUARDRAIL MISCELLANEOUS MATERIAL AND LABOR FOR REPAIR	1.00	LS
0020	601-05856	CAT	10.00	EACH
0021	601-05856	CAT	10.00	EACH
0022	601-05856	CAT	12.00	EACH
0023	601-05856	CAT	10.00	EACH
0024	601-05857	GUARDRAIL, BLOCKOUT, WOOD, 4 IN. X 6 IN.	17.00	EACH
0025	601-06037	GUARDRAIL, END TREATMENT, I	5.00	EACH
0026	601-06246	IMPACT ATTENUATOR, R2-W1, TL-3	3.00	EACH
0027	601-06273	GUARDRAIL, END TREATMENT, SKT-350	14.00	EACH
0028	601-06273	GUARDRAIL, END TREATMENT, SKT-350	18.00	EACH
0029	601-06273	GUARDRAIL, END TREATMENT, SKT-350	31.00	EACH
0030	601-06273	GUARDRAIL, END TREATMENT, SKT-350	32.00	EACH
0031	601-06273	GUARDRAIL, END TREATMENT, SKT-350	36.00	EACH
0032	601-06798	TIMBER BLOCK	700.00	EACH
0033	601-06854	GUARDRAIL, W-BEAM, NESTED	2.00	EACH
0034	601-07179	ET_2000 OS UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES, ABOVE GROUND COMPONENTS ONLY	32.00	EACH
0035	601-07607	IMPACT ATTENUATOR	6.00	EACH
0036	601-07607	IMPACT ATTENUATOR	15.00	EACH
0037	601-07607	IMPACT ATTENUATOR	14.00	EACH
0038	601-07607	IMPACT ATTENUATOR	4.00	EACH
0039	601-07607	IMPACT ATTENUATOR	6.00	EACH
0040	601-07607	IMPACT ATTENUATOR	6.00	EACH
0041	601-07607	IMPACT ATTENUATOR	6.00	EACH
0042	601-07607	IMPACT ATTENUATOR	4.00	EACH
0043	601-07607	IMPACT ATTENUATOR	4.00	EACH
0044	601-08132	GUARDRAIL, THRIE BEAM, BLOCKOUT, STEEL	6.00	EACH
0045	601-09238	HAND DIG GUARDRAIL POST HOLES	38.00	EACH
0046	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	125.00	LFT
0047	601-12282	GUARDRAIL, MGS W-BEAM, 3 FT 1.5 IN SPACING	125.00	LFT

0048	601-12283	GUARDRAIL, MGS W-BEAM, 1 FT 6.75 IN SPACING	125.00	LFT
0049	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	100.00	LFT
0050	601-12286	GUARDRAIL, MGS W-BEAM, SHOP CURVED, 6 FT 3 IN SPACING	100.00	LFT
0051	601-12287	GUARDRAIL, MGS, LONG SPAN, TYPE 1	8.00	EACH
0052	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	8.00	EACH
0053	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	8.00	EACH
0054	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	5.00	EACH
0055	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	6.00	EACH
0056	601-12293	GUARDRAIL, MGS, STRUCTURE, TOP-MOUNTED POST	10.00	EACH
0057	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	7.00	EACH
0058	601-52501	GUARDRAIL POST	15.00	EACH
0059	601-52501	GUARDRAIL POST	70.00	EACH
0060	601-52501	GUARDRAIL POST	25.00	EACH
0061	601-52501	GUARDRAIL POST	45.00	EACH
0062	601-52501	GUARDRAIL POST	40.00	EACH
0063	601-52540	GUARDRAIL TERMINAL SECTION, W BEAM	4.00	EACH
0064	601-61340	GUARDRAIL POST, 15.5 LBS PER FT., GALVANIZED, 6 FT. 3 IN. LONG	62.00	EACH
0065	601-62070	GUARDRAIL, STEEL BEAM, GALVANIZED	15700.00	LFT
0066	601-62080	GUARDRAIL, STEEL BEAM, CURVED SECTION, GALVANIZED	720.00	LFT
0067	601-62150	GUARDRAIL POST, 15.5 LBS PER LFT, GALVANIZED, 7 FT 0 IN. LONG	80.00	EACH
0068	601-62540	GUARDRAIL POST, PLUMB	650.00	EACH
0069	601-62555	GUARDRAIL, TUBING, ELLIPTICAL, ALUMINUM, LABOR ONLY	250.00	LFT
0070	601-91511	GUARDRAIL POST, W4, 8 IN. X 8 IN.	10.00	EACH
0071	601-91542	GUARDRAIL BLOCK, 6 IN. X 8 IN., B1	17.00	EACH
0072	601-91575	GUARDRAIL BLOCK, 6 IN. X 8 IN., B2	13.00	EACH
0073	601-91576	GUARDRAIL BLOCK, 6 IN. X 8 IN., B3	30.00	EACH
0074	601-91649	GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	6.00	EACH
0075	601-94689	GUARDRAIL, END TREATMENT, OS	8.00	EACH
0076	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0077	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0078	601-94690	GUARDRAIL, END TREATMENT, MS	4.00	EACH
0079	601-94690	GUARDRAIL, END TREATMENT, MS	3.00	EACH
0080	601-94690	GUARDRAIL, END TREATMENT, MS	3.00	EACH
0081	601-95342	GUARDRAIL SPLICE PLATE, C, GALVANIZED	3.00	EACH
0082	601-95972	GUARDRAIL POST (CRT), 8 IN X 6 IN TREATED LUMBER, 6 FT. 0 IN. LONG	28.00	EACH
0083	601-98636	GUARDRAIL CHANNEL, 10 kg PER m, GALVANIZED, 125 mm	250.00	LFT
0084	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	125.00	LFT
0085	801-06640	CONSTRUCTION SIGN, A	14.00	EACH
0086	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 891

Contract: M -40398-A

Section No.: 1 ROADSIDE MAINTENANCE, HERBICIDE TREATMENT

Line Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	624-92647	HERBICIDE TREATMENT	3688.10	ACRE
0006	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0007	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 931

Contract: M -40820-A

Section No.: 1 ROADSIDE MAINTENANCE, MOWING

Line Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	623-04884	MOWING, CYCLE NO. 1	1.00	CYCL
0004	623-04885	MOWING, CYCLE NO. 2	1.00	CYCL
0005	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0006	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0007	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	6.00	MOS

Call: 961

Contract: T -38188-A

Section No.: 1 IT COMMUNICATIONS SYSTEMS

Line Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	25.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	100.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-06587	CLEARING AND GRUBBING	1.00	ACRE
0013	202-07083	REMOVAL	1.00	LS
0014	202-07083	REMOVAL	1.00	LS
0015	205-12108	STORM WATER MANAGEMENT BUDGET	60000.00	DOL
0016	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS

0017	302-07455	DENSE GRADED SUBBASE	9.00	CYS
0018	603-01932	FENCE, CHAIN LINK, 96 IN.	82.00	LFT
0019	603-04847	FENCE GATE	1.00	EACH
0020	610-08446	PCCP FOR APPROACHES, 6 IN.	54.00	SYS
0021	621-09867	MULCHED SEEDING	809.00	SYS
0022	628-09402	FIELD OFFICE, B	24.00	MOS
0023	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0024	715-04985	VAULT	58.00	EACH
0025	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0026	801-03290	CONSTRUCTION SIGN, C	5.00	EACH
0027	801-06640	CONSTRUCTION SIGN, A	46.00	EACH
0028	801-06645	CONSTRUCTION SIGN, B	19.00	EACH
0029	801-06710	FLASHING ARROW SIGN	600.00	DAY
0030	801-06775	MAINTAINING TRAFFIC	1.00	LS
0031	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0032	802-03126	SIGN OVERHEAD RELOCATE	4.00	EACH
0033	805-04973	CONDUIT	640.00	LFT
0034	805-04973	CONDUIT	760.00	LFT
0035	805-04973	CONDUIT	2260.00	LFT
0036	805-04973	CONDUIT	630.00	LFT
0037	805-04973	CONDUIT	215.00	LFT
0038	805-04973	CONDUIT	7190.00	LFT
0039	805-04973	CONDUIT	131035.00	LFT
0040	805-04973	CONDUIT	345.00	LFT
0041	805-04973	CONDUIT	6075.00	LFT
0042	805-04973	CONDUIT	20685.00	LFT
0043	805-04973	CONDUIT	205.00	LFT
0044	805-04973	CONDUIT	5205.00	LFT
0045	805-04973	CONDUIT	1415.00	LFT
0046	805-04973	CONDUIT	4041.00	LFT
0047	805-04973	CONDUIT	15371.00	LFT
0048	805-04973	CONDUIT	50.00	LFT
0049	805-04973	CONDUIT	195.00	LFT
0050	805-04973	CONDUIT	2530.00	LFT
0051	807-04651	WIRE	500.00	LFT
0052	807-04651	WIRE	500.00	LFT
0053	807-78590	HANDHOLE	210.00	EACH
0054	807-86955	CABLE-DUCT MARKER	989.00	EACH
0055	807-86955	CABLE-DUCT MARKER	1707.00	EACH
0056	809-04652	SERVICE POINT	1.00	EACH
0057	809-04970	FIBER OPTIC	24.00	EACH
0058	809-04970	FIBER OPTIC	5124.00	EACH
0059	809-04970	FIBER OPTIC	2.00	EACH

0060	809-04970	FIBER OPTIC	15.00	EACH
0061	809-04970	FIBER OPTIC	16.00	EACH
0062	809-04970	FIBER OPTIC	7.00	EACH
0063	809-04970	FIBER OPTIC	5.00	EACH
0064	809-04970	FIBER OPTIC	1.00	EACH
0065	809-04970	FIBER OPTIC	43.00	EACH
0066	809-04970	FIBER OPTIC	104.00	EACH
0067	809-04970	FIBER OPTIC	74.00	EACH
0068	809-04970	FIBER OPTIC	38.00	EACH
0069	809-04970	FIBER OPTIC	15.00	EACH
0070	809-04970	FIBER OPTIC	81.00	EACH
0071	809-04970	FIBER OPTIC	110.00	EACH
0072	809-04970	FIBER OPTIC	50.00	EACH
0073	809-04970	FIBER OPTIC	7.00	EACH
0074	809-04970	FIBER OPTIC	30.00	EACH
0075	809-09343	ITS	29.00	EACH
0076	809-09343	ITS	1.00	EACH
0077	809-09343	ITS	7.00	EACH
0078	809-09343	ITS	1.00	EACH
0079	809-09343	ITS	7.00	EACH
0080	809-09343	ITS	16.00	EACH
0081	809-09343	ITS	16.00	EACH
0082	809-09343	ITS	176505.00	EACH
0083	809-94971	FIBER OPTIC CABLE	31645.00	LFT
0084	809-94971	FIBER OPTIC CABLE	186926.00	LFT
0085	809-94971	FIBER OPTIC CABLE	2725.00	LFT

Call: 971

Contract: T -38189-A

Section No.: 1 ITS TRAVELER INFORMATION SYSTEMS

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	15.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	30.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-06587	CLEARING AND GRUBBING	1.00	ACRE

0012	202-94954	BARRIER WALL, CONCRETE, REMOVE	85.50	LFT
0013	203-08607	LINEAR GRADING	743.00	LFT
0014	205-12108	STORM WATER MANAGEMENT BUDGET	35000.00	DOL
0015	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0016	207-08264	SUBGRADE TREATMENT, TYPE II	147.00	SYS
0017	303-01180	COMPACTED AGGREGATE NO. 53	316.00	TON
0018	304-07493	WIDENING WITH HMA, TYPE B	85.00	TON
0019	601-01128	GUARDRAIL, TRANSITION, TYPE WGB	1.00	EACH
0020	601-02241	GUARDRAIL, REMOVE	6.25	LFT
0021	601-05999	CURVED TERMINAL END	3.00	EACH
0022	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	606.00	LFT
0023	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00	EACH
0024	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	1.00	EACH
0025	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0026	602-01064	CONCRETE BARRIER	80.00	LFT
0027	602-06729	BARRIER, DELINEATOR	4.00	EACH
0028	603-04847	FENCE GATE	1.00	EACH
0029	603-06065	FENCE, CHAIN LINK, RESET	4.00	LFT
0030	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	18.00	EACH
0031	621-06560	MULCHED SEEDING U	1025.00	SYS
0032	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	1.00	EACH
0033	715-01354	CLEAN EXISTING PIPE	1750.00	LFT
0034	715-04985	VAULT	1.00	EACH
0035	715-04985	VAULT	15.00	EACH
0036	718-08308	UNDERDRAIN PATCHING	30.00	LFT
0037	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0038	801-06640	CONSTRUCTION SIGN, A	257.00	EACH
0039	801-06645	CONSTRUCTION SIGN, B	30.00	EACH
0040	801-06710	FLASHING ARROW SIGN	720.00	DAY
0041	801-06775	MAINTAINING TRAFFIC	1.00	LS
0042	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00	EACH
0043	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	300.00	LFT
0044	801-08507	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 1	300.00	LFT
0045	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0046	802-02475	SIGN, PANEL, RELOCATE	1.00	EACH
0047	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	12.00	LFT
0048	802-07057	SIGN, PANEL, WITH LEGEND	3120.00	SFT
0049	802-07060	SIGN, SHEET, RELOCATE	2.00	EACH
0050	802-09576	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE D	9.00	EACH
0051	802-09581	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 36 IN.	2.00	EACH
0052	802-09581	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 36 IN.	8.00	EACH
0053	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	229.50	SFT
0054	802-09861	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE I	1.00	EACH

0055	802-11818	OVERHEAD SIGN STRUCTURE, BUTTERFLY CANTILEVER	2.00	EACH
0056	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	2.00	EACH
0057	802-12224	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, C	2.00	EACH
0058	802-12350	OVERHEAD BUTTERFLY CANTILEVER SIGN STRUCTURE FOUNDATION, DRILLED SHAFT 33 INCH	1.00	EACH
0059	802-12351	OVERHEAD BUTTERFLY CANTILEVER SIGN STRUCTURE FOUNDATION, DRILLED SHAFT 45 INCH	1.00	EACH
0060	802-76095	STRUCTURAL STEEL, BREAKAWAY	1945.00	LBS
0061	802-93388	BARRIER WALL SIGN BRACKET ASSEMBLY MEDIAN	2.00	EACH
0062	805-04973	CONDUIT	360.00	LFT
0063	805-04973	CONDUIT	530.00	LFT
0064	805-04973	CONDUIT	2400.00	LFT
0065	805-04973	CONDUIT	3805.00	LFT
0066	805-04973	CONDUIT	840.00	LFT
0067	805-04973	CONDUIT	3095.00	LFT
0068	805-04973	CONDUIT	7899.00	LFT
0069	805-04973	CONDUIT	5710.00	LFT
0070	805-04973	CONDUIT	5935.00	LFT
0071	805-04973	CONDUIT	430.00	LFT
0072	805-04973	CONDUIT	3330.00	LFT
0073	805-04973	CONDUIT	9235.00	LFT
0074	805-04973	CONDUIT	735.00	LFT
0075	807-02603	LIGHT STANDARD RELOCATE	1.00	EACH
0076	807-02934	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. X 36 IN. X 96 IN.	1.00	EACH
0077	807-04651	WIRE	3955.00	LFT
0078	807-04651	WIRE	3955.00	LFT
0079	807-05073	JUNCTION BOX	5.00	EACH
0080	807-78590	HANDHOLE	79.00	EACH
0081	807-86955	CABLE-DUCT MARKER	79.00	EACH
0082	807-86955	CABLE-DUCT MARKER	55.00	EACH
0083	809-04652	SERVICE POINT	6.00	EACH
0084	809-04652	SERVICE POINT	4.00	EACH
0085	809-04652	SERVICE POINT	1.00	EACH
0086	809-04652	SERVICE POINT	5.00	EACH
0087	809-04970	FIBER OPTIC	1.00	EACH
0088	809-04970	FIBER OPTIC	598.00	EACH
0089	809-04970	FIBER OPTIC	2.00	EACH
0090	809-04970	FIBER OPTIC	5.00	EACH
0091	809-04970	FIBER OPTIC	5.00	EACH
0092	809-04970	FIBER OPTIC	2.00	EACH
0093	809-04970	FIBER OPTIC	4.00	EACH
0094	809-04970	FIBER OPTIC	1.00	EACH
0095	809-04970	FIBER OPTIC	9.00	EACH
0096	809-04970	FIBER OPTIC	32.00	EACH
0097	809-04970	FIBER OPTIC	3.00	EACH

0098	809-04970	FIBER OPTIC	31.00	EACH
0099	809-04970	FIBER OPTIC	3.00	EACH
0100	809-04970	FIBER OPTIC	21.00	EACH
0101	809-04970	FIBER OPTIC	2.00	EACH
0102	809-04970	FIBER OPTIC	31.00	EACH
0103	809-04970	FIBER OPTIC	35.00	EACH
0104	809-04970	FIBER OPTIC	11.00	EACH
0105	809-04970	FIBER OPTIC	5.00	EACH
0106	809-04970	FIBER OPTIC	19.00	EACH
0107	809-08398	ITS CONTROLLER CABINET	12.00	EACH
0108	809-08399	ITS CONTROLLER CABINET FOUNDATION	12.00	EACH
0109	809-08571	AFP	17.00	EACH
0110	809-09343	ITS	2.00	EACH
0111	809-09343	ITS	4.00	EACH
0112	809-09343	ITS	6.00	EACH
0113	809-09343	ITS	4.00	EACH
0114	809-09343	ITS	25.00	EACH
0115	809-09343	ITS	1.00	EACH
0116	809-09343	ITS	350.00	EACH
0117	809-09343	ITS	39.00	EACH
0118	809-09343	ITS	26.00	EACH
0119	809-09343	ITS	20144.00	EACH
0120	809-09343	ITS	13.00	EACH
0121	809-94971	FIBER OPTIC CABLE	28753.00	LFT

Call: 981

Contract: T -39945-A

Section No.: 1 TRAFFIC SIGNALS MODERNIZATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0008	801-06775	MAINTAINING TRAFFIC	1.00	LS
0009	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	30.00	LFT
0010	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	100.00	SFT
0011	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	63.00	SFT
0012	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0013	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	1.00	EACH

0014	805-01842	HANDHOLE SIGNAL TYPE 1	4.00	EACH
0015	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	15.00	LFT
0016	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0017	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0018	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	70.00	LFT
0019	805-09539	LOOP DETECTOR DELAY COUNTING AMPLIFIER 2 CHANNEL	8.00	EACH
0020	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	2200.00	LFT
0021	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	8.00	EACH
0022	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	4.00	EACH
0023	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	4.00	EACH
0024	805-78415	SPAN, CATENARY, AND TETHER	4.00	EACH
0025	805-78420	DISCONNECT HANGER	4.00	EACH
0026	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	50.00	LFT
0027	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	3120.00	LFT
0028	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	950.00	LFT
0029	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	450.00	LFT
0030	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	1390.00	LFT
0031	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	5360.00	LFT
0032	805-78785	SIGNAL DETECTOR HOUSING	11.00	EACH
0033	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1090.00	LFT
0034	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0035	805-79020	TRAFFIC SIGNAL INSTALLATION	1.00	LS
0036	808-06368	TRANSVERSE MARKING, REMOVE	76.00	LFT
0037	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	650.00	LFT
0038	808-12148	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 36 IN.	36.00	LFT
0039	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	290.00	LFT
0040	808-75274	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 8 IN.	32.00	LFT
0041	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	160.00	LFT
0042	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	8.00	EACH
0043	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	55.00	LFT