

Call: 120

Contract: R -29585-A

Section No.: 1

BIKE AND PEDESTRIAN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	202-02272	PAVED SIDE DITCH, REMOVE	38.00	LFT
0011	202-02278	CURB, CONCRETE, REMOVE	183.00	LFT
0012	202-52710	SIDEWALK CONCRETE, REMOVE	31.40	SYS
0013	202-94810	CURB TURNOUT, REMOVE	3.00	EACH
0014	202-96531	FENCE RIGHT-OF-WAY, REMOVE	1365.00	LFT
0015	203-02000	EXCAVATION, COMMON	2648.00	CYS
0016	203-02070	BORROW	1952.00	CYS
0017	205-12108	STORM WATER MANAGEMENT BUDGET	29000.00	DOL
0018	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	2909.00	SYS
0020	207-08266	SUBGRADE TREATMENT, TYPE III	4519.00	SYS
0021	211-02050	B BORROW	1035.00	CYS
0022	211-09264	STRUCTURE BACKFILL, TYPE 1	156.00	CYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	9.00	CYS
0024	211-09268	STRUCTURE BACKFILL, TYPE 5	17.00	CYS
0025	214-11796	GEOGRID, TYPE IB	534.00	SYS
0026	301-12234	COMPACTED AGGREGATE NO 53	456.00	CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	2002.00	TON
0028	406-05521	ASPHALT FOR TACK COAT	5344.00	SYS
0029	603-05744	FENCE GATE, CHAIN LINK, 72 IN. X 10 FT	1.00	EACH
0030	603-06065	FENCE, CHAIN LINK, RESET	320.00	LFT
0031	603-11002	FENCE GATE, CHAIN LINK, 72 IN. X 24 FT	1.00	EACH

0032	603-92636	FENCE, CHAIN LINK, 72 IN.	1033.00	LFT
0033	604-05528	HMA FOR SIDEWALK	989.00	TON
0034	604-06070	SIDEWALK, CONCRETE	39.10	SYS
0035	604-08086	CURB RAMP, CONCRETE	84.00	SYS
0036	604-12083	DETECTABLE WARNING SURFACES	15.00	SYS
0037	604-95344	HAND RAIL, PEDESTRIAN	100.00	LFT
0038	605-06120	CURB, CONCRETE	202.00	LFT
0039	607-06335	PAVED SIDE DITCH, A	50.00	LFT
0040	610-09108	PCCP FOR APPROACHES, 9 IN.	82.00	SYS
0041	616-05688	RIPRAP, CLASS 1	29.00	TON
0042	616-06405	RIPRAP, REVETMENT	28.00	TON
0043	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	65.00	SYS
0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0045	621-06545	FERTILIZER	1.00	TON
0046	621-06554	SEED MIXTURE U	311.00	LBS
0047	621-06565	MULCHING MATERIAL	3.00	TON
0048	621-06574	SODDING	277.00	SYS
0049	621-08161	PERMANENT TURF REINFORCEMENT MAT	342.00	SYS
0050	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN.	195.00	EACH
0051	706-04683	RAILING	460.00	LFT
0052	712-09730	BOARDWALK	170.00	LFT
0053	714-11197	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 3 FT. X 2 FT.	39.00	LFT
0054	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	45.00	LFT
0055	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	8.00	LFT
0056	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	96.00	LFT
0057	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	156.00	LFT
0058	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	30.00	LFT
0059	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	20.00	LFT
0060	715-05842	CONCRETE ANCHOR, 42 IN.	1.00	EACH
0061	715-07679	CONCRETE ANCHOR, 36 IN.	1.00	EACH
0062	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00	EACH
0063	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0064	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH
0065	720-44000	CASTING, ADJUST TO GRADE	2.00	EACH
0066	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	1.00	EACH
0067	720-45010	INLET, A3	1.00	EACH
0068	720-45035	INLET, F7	2.00	EACH

0069	720-92025	MANHOLE, D2	1.00	EACH
0070	720-94612	MANHOLE, K4	1.00	EACH
0071	801-06640	CONSTRUCTION SIGN, A	18.00	EACH
0072	801-06775	MAINTAINING TRAFFIC	1.00	LS
0073	801-07118	BARRICADE, III-A	72.00	LFT
0074	802-03896	BOLLARD	5.00	EACH
0075	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	26.00	LFT
0076	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	30.00	LFT
0077	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	29.80	SFT
0078	808-06609	PAVEMENT MESSAGE MARKING	4.00	EACH
0079	808-06609	PAVEMENT MESSAGE MARKING	4.00	EACH
0080	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	280.00	LFT
0081	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	27.00	LFT
0082	808-11960	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 24 IN.	290.00	LFT

Call: 160

Contract: R -35296-A

Section No.: 1

ROAD RECONSTRUCTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	70.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	20.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0008	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0009	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0013	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0014	202-99187	FENCE, FARM FIELD, REMOVE	3251.00	LFT
0015	203-02000	EXCAVATION, COMMON	24072.00	CYS
0016	203-02070	BORROW	9118.00	CYS
0017	205-11626	PUMP AROUND	2.00	EACH
0018	205-12108	STORM WATER MANAGEMENT BUDGET	63973.00	DOL
0019	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	4102.00	SYS
0021	207-08266	SUBGRADE TREATMENT, TYPE III	11414.00	SYS
0022	207-09934	SUBGRADE TREATMENT, TYPE IB	62142.00	SYS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	9987.00	SYS
0024	211-02050	B BORROW	1723.00	CYS
0025	211-09265	STRUCTURE BACKFILL, TYPE 2	7853.00	CYS
0026	211-09268	STRUCTURE BACKFILL, TYPE 5	118.00	CYS
0027	301-12234	COMPACTED AGGREGATE NO 53	10556.00	CYS
0028	303-01180	COMPACTED AGGREGATE NO. 53	68.00	TON
0029	304-07491	HMA PATCHING, TYPE C	41.00	TON
0030	306-08033	MILLING, ASPHALT, 1 IN.	6157.00	SYS
0031	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2610.00	TON

0032	401-07352	QC/QA-HMA, 3, 76, SURFACE, 12.5 mm	1645.00	TON
0033	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	4349.00	TON
0034	401-07403	QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	2057.00	TON
0035	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	14436.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	22687.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	22687.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	22687.00	LFT
0039	402-10086	HMA FOR TEMPORARY PAVEMENT, C	1125.00	TON
0040	406-05520	ASPHALT FOR TACK COAT	35.00	TON
0041	502-11564	PCCP, 7 IN.	717.00	SYS
0042	503-05240	D-1 CONTRACTION JOINT	540.00	LFT
0043	604-05528	HMA FOR SIDEWALK	1659.00	TON
0044	604-06070	SIDEWALK, CONCRETE	4711.00	SYS
0045	604-08086	CURB RAMP, CONCRETE	913.00	SYS
0046	604-12083	DETECTABLE WARNING SURFACES	124.00	SYS
0047	605-06120	CURB, CONCRETE	323.00	LFT
0048	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	18057.00	LFT
0049	605-06160	CURB AND GUTTER, B, CONCRETE, MODIFIED	645.00	LFT
0050	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	2.00	LFT
0051	610-07487	HMA FOR APPROACHES, TYPE B	584.00	TON
0052	610-08446	PCCP FOR APPROACHES, 6 IN.	1051.00	SYS
0053	610-09108	PCCP FOR APPROACHES, 9 IN.	3078.00	SYS
0054	611-06497	MAILBOX ASSEMBLY, SINGLE	14.00	EACH
0055	615-06505	MONUMENT, B	13.00	EACH
0056	615-06527	MONUMENT, SECTION CORNER	3.00	EACH
0057	616-05688	RIPRAP, CLASS 1	128.00	TON
0058	616-06405	RIPRAP, REVETMENT	395.00	TON
0059	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	535.00	SYS
0060	621-06545	FERTILIZER	1.00	TON
0061	621-06554	SEED MIXTURE U	269.00	LBS
0062	621-06565	MULCHING MATERIAL	3.00	TON
0063	621-06567	WATER	18.00	kGAL
0064	621-06575	SODDING, NURSERY	10607.00	SYS
0065	628-09402	FIELD OFFICE, B	24.00	MOS
0066	714-11173	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 3 FT.	233.00	LFT
0067	715-03475	SAFETY METAL END SECTION, 4:1, DIA 15 IN.	4.00	EACH
0068	715-04522	PIPE END SECTION, DIA 42 IN.	2.00	EACH

0069	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	1151.00	LFT
0070	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	17378.00	LFT
0071	715-05127	PIPE, TYPE 1, CIRCULAR, 42 IN.	105.00	LFT
0072	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	5239.00	LFT
0073	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	1083.00	LFT
0074	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	802.00	LFT
0075	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	855.00	LFT
0076	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	522.00	LFT
0077	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	505.00	LFT
0078	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	1299.00	LFT
0079	715-05162	PIPE, TYPE 2, CIRCULAR, 54 IN.	3766.00	LFT
0080	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	100.00	LFT
0081	715-08048	STORMWATER TREATMENT SYSTEM	5.00	EACH
0082	715-09064	VIDEO INSPECTION FOR PIPE	15222.00	LFT
0083	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0084	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0085	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	EACH
0086	715-46040	PIPE END SECTION, DIAMETER 36 IN.	1.00	EACH
0087	715-96881	PIPE END SECTION, DIAMETER 54 IN.	1.00	EACH
0088	716-07726	PIPE INSTALLATION, TRENCHLESS, 54 IN.	200.00	LFT
0089	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	17378.00	LFT
0090	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	14482.00	SYS
0091	718-52610	AGGREGATE FOR UNDERDRAINS	1564.00	CYS
0092	720-03481	MANHOLE, H4 MODIFIED	7.00	EACH
0093	720-45030	INLET, E7	16.00	EACH
0094	720-45035	INLET, F7	4.00	EACH
0095	720-45075	INLET, R13	2.00	EACH
0096	720-45410	MANHOLE, C4	1.00	EACH
0097	720-91973	MANHOLE, H4	14.00	EACH
0098	720-92884	MANHOLE, K4 MODIFIED	2.00	EACH
0099	720-93501	MANHOLE, L4	19.00	EACH
0100	720-94612	MANHOLE, K4	6.00	EACH
0101	720-95335	MANHOLE, M4	6.00	EACH
0102	720-98174	INLET, B15	70.00	EACH
0103	720-98555	INLET, C15	77.00	EACH
0104	720-98869	MANHOLE, L4 MODIFIED	6.00	EACH
0105	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH

0106	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	17425.00	LFT
0107	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	233.00	LFT
0108	801-06625	DETOUR ROUTE MARKER ASSEMBLY	54.00	EACH
0109	801-06640	CONSTRUCTION SIGN, A	29.00	EACH
0110	801-06775	MAINTAINING TRAFFIC	1.00	LS
0111	801-07118	BARRICADE, III-A	192.00	LFT
0112	801-07119	BARRICADE, III-B	96.00	LFT
0113	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	718.00	LFT
0114	802-05705	SIGN POST, SQUARE TYPE 2 UNREINFORCED ANCHOR BASE	328.00	LFT
0115	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	801.00	SFT
0116	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	176.00	SFT
0117	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	2.00	EACH
0118	805-01842	HANDHOLE SIGNAL TYPE 1	3.00	EACH
0119	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	364.00	LFT
0120	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	16.00	EACH
0121	805-06742	SOLAR POWERED FLASHING BEACON ASSEMBLY	16.00	EACH
0122	805-78069	CONTROLLER AND CABINET, SECONDARY MENU DRIVEN, 4 PHASE	1.00	EACH
0123	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	4.00	EACH
0124	805-78415	SPAN, CATENARY, AND TETHER	1.00	EACH
0125	805-78420	DISCONNECT HANGER	1.00	EACH
0126	805-78445	SIGNAL SERVICE	1.00	EACH
0127	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	140.00	LFT
0128	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	1001.00	LFT
0129	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	124.00	LFT
0130	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	128.00	LFT
0131	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	507.00	LFT
0132	805-78785	SIGNAL DETECTOR HOUSING	3.00	EACH
0133	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	344.00	LFT
0134	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0135	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	2.00	EACH
0136	807-01414	SERVICE POINT RISER AND WEATHERHEAD, INSTALL	2.00	EACH
0137	807-03950	LUMINAIRE ORNAMENTAL	34.00	EACH
0138	807-03951	LIGHT POLE ORNAMENTAL	34.00	EACH
0139	807-04428	CABLE DUCT	5048.00	LFT
0140	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	853.00	LFT
0141	807-11981	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. DIA X 96 IN.	34.00	EACH
0142	807-95888	WIRE, NO 8 COPPER, 1/C	1334.00	LFT

0143	807-95889	WIRE, NO. 10 COPPER, 1/C	24452.00	LFT
0144	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	5.00	EACH
0145	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	3693.00	LFT
0146	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1049.00	LFT
0147	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	400.00	LFT
0148	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	400.00	LFT
0149	808-09506	PAVEMENT MESSAGE MARKINGS THERMOPLASTIC WORD YIELD	12.00	EACH
0150	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	13.00	LFT
0151	808-11698	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 27 IN.	226.00	LFT
0152	808-11953	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 18 IN.	356.00	LFT
0153	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1967.00	LFT
0154	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	15711.00	LFT
0155	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	184.00	LFT
0156	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	6.00	EACH



Call: 734

Contract: B -40258-C

Section No.: 1

BRIDGE REHABILITATION OR REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-02240	PAVEMENT REMOVAL	222.00	SYS
0011	202-02273	CENTER CURB, CONCRETE, REMOVE	316.00	SYS
0012	202-02278	CURB, CONCRETE, REMOVE	30.00	LFT
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	202-52710	SIDEWALK CONCRETE, REMOVE	70.00	SYS
0015	202-94954	BARRIER WALL, CONCRETE, REMOVE	561.00	LFT
0016	203-02000	EXCAVATION, COMMON	330.00	CYS
0017	205-12108	STORM WATER MANAGEMENT BUDGET	30000.00	DOL
0018	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	102.00	SYS
0020	211-06467	AGGREGATE FOR END BENT BACKFILL	144.00	CYS
0021	302-07455	DENSE GRADED SUBBASE	36.00	CYS
0022	402-10086	HMA FOR TEMPORARY PAVEMENT, C	322.00	TON
0023	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0024	602-01064	CONCRETE BARRIER	486.00	LFT
0025	602-06729	BARRIER, DELINEATOR	27.00	EACH
0026	602-11938	CONCRETE BARRIER, MODIFIED SECTION	8.00	CYS
0027	604-06070	SIDEWALK, CONCRETE	70.00	SYS
0028	605-06090	CURB, INTEGRAL CONCRETE	30.00	LFT
0029	605-06210	CENTER CURB, C CONCRETE	714.00	LFT
0030	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	220.00	SYS
0031	610-07488	HMA FOR APPROACHES, TYPE C	16.00	TON

0032	628-09401	FIELD OFFICE, A	12.00	MOS
0033	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0034	628-11977	COMPUTER SYSTEM	1.00	EACH
0035	702-51005	CONCRETE, A, SUBSTRUCTURE	17.00	CYS
0036	702-51863	FIELD DRILLED HOLE IN CONCRETE	5770.00	EACH
0037	702-93722	CONCRETE, C,	17.20	CYS
0038	703-06029	REINFORCING BARS, EPOXY COATED	49933.00	LBS
0039	703-08247	EMBEDDED GALVANIC ANODE	50.00	EACH
0040	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	48.00	EACH
0041	704-51002	CONCRETE, C, SUPERSTRUCTURE	441.70	CYS
0042	706-09959	RAILING, CONCRETE FT	12.00	LFT
0043	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	2.00	EACH
0044	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0045	709-51821	SURFACE SEAL	1.00	LS
0046	710-09158	PATCHING CONCRETE STRUCTURES	2700.00	SFT
0047	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS
0048	715-05407	PIPE, END BENT DRAIN, 6 IN.	140.00	LFT
0049	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	160.00	SYS
0050	722-60824	SURFACE MILLING	1510.00	SYS
0051	724-09626	STRUCTURAL EXPANSION JOINT SEAL, SS, REPLACE	98.00	LFT
0052	724-51925	STRUCTURAL EXPANSION JOINT, SS	16.00	LFT
0053	726-92406	BEARING ASSEMBLY ELASTOMERIC	60.00	EACH
0054	726-95870	BEARING ASSEMBLY, PTFE	120.00	EACH
0055	727-90308	EPOXY INJECTION, CRACK PREPARATION	1520.00	LFT
0056	727-90309	EPOXY INJECTION, EPOXY MATERIAL	30.00	GAL
0057	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0058	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	8948.00	SYS
0059	801-03291	CONSTRUCTION SIGN, D	15.00	EACH
0060	801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.00	EACH
0061	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	60684.00	LFT
0062	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	30.00	LFT
0063	801-06625	DETOUR ROUTE MARKER ASSEMBLY	64.00	EACH
0064	801-06640	CONSTRUCTION SIGN, A	97.00	EACH
0065	801-06645	CONSTRUCTION SIGN, B	80.00	EACH
0066	801-06710	FLASHING ARROW SIGN	600.00	DAY
0067	801-06775	MAINTAINING TRAFFIC	1.00	LS
0068	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	1.00	EACH

0069	801-07118	BARRICADE, III-A	288.00	LFT
0070	801-07119	BARRICADE, III-B	72.00	LFT
0071	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2700.00	LFT
0072	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	2800.00	LFT
0073	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	1.00	EACH
0074	801-97643	TEMPORARY BUZZ STRIPS	300.00	LFT
0075	807-02370	LIGHT STRUCTURE, REMOVE AND RESET	1.00	EACH
0076	808-06716	LINE, REMOVE	15710.00	LFT
0077	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0078	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	4900.00	LFT
0079	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	6400.00	LFT
0080	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	8300.00	LFT
0081	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	850.00	LFT
0082	808-10043	LINE, MULTI-COMPONENT, SOLID, WHITE, 24 IN.	60.00	LFT
0083	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	105.00	LFT
0084	808-12032	GROOVING FOR PAVEMENT MARKINGS	12775.00	LFT
0085	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	143.00	EACH
0086	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	143.00	EACH

Call: 830

Contract: T -39217-A

Section No.: 1 TRAFFIC SIGNALS MODERNIZATION

**Line**

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	12.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	628-09401	FIELD OFFICE, A	8.00	MOS
0009	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0010	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0011	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0012	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	8.00	MOS
0013	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0014	628-11977	COMPUTER SYSTEM	1.00	EACH
0015	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0016	801-06645	CONSTRUCTION SIGN, B	16.00	EACH
0017	801-06775	MAINTAINING TRAFFIC	1.00	LS
0018	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	160.00	LFT
0019	802-07060	SIGN, SHEET, RELOCATE	8.00	EACH

0020	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	120.00	SFT
0021	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	67.50	SFT
0022	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	5.00	EACH
0023	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	11.00	EACH
0024	805-01842	HANDHOLE SIGNAL TYPE 1	2.00	EACH
0025	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0026	805-06483	CONTROLLER	2.00	EACH
0027	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	275.00	LFT
0028	805-09845	CONTACT CLOSURE CARD	2.00	EACH
0029	805-09846	RECEIVER PROCESSOR	4.00	EACH
0030	805-10107	WIRELESS MAGNETOMETER DETECTOR	80.00	EACH
0031	805-10108	WIRELESS REPEATER	12.00	EACH
0032	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	32.00	EACH
0033	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	4.00	EACH
0034	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	8.00	EACH
0035	805-78415	SPAN, CATENARY, AND TETHER	16.00	EACH
0036	805-78420	DISCONNECT HANGER	14.00	EACH
0037	805-78445	SIGNAL SERVICE	4.00	EACH
0038	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	375.00	LFT
0039	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	1896.00	LFT
0040	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	7015.00	LFT
0041	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	1325.00	LFT
0042	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	785.00	LFT
0043	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0044	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	11.00	EACH
0045	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	51.70	SYS
0046	808-06368	TRANSVERSE MARKING, REMOVE	386.00	LFT
0047	808-06716	LINE, REMOVE	4500.00	LFT
0048	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2900.00	LFT
0049	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1600.00	LFT
0050	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	386.00	LFT
0051	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	28.00	EACH

Call: 840

Contract: T -39219-A

Section No.: 1                      TRAFFIC SIGNAL VISIBILITY IMPROVEMENTS

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL

0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	628-09401	FIELD OFFICE, A	8.00	MOS
0008	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0009	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0010	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0011	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	8.00	MOS
0012	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0013	628-11977	COMPUTER SYSTEM	1.00	EACH
0014	801-06775	MAINTAINING TRAFFIC	1.00	LS
0015	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	487.07	SFT
0016	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	417.00	SFT
0017	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	109.50	SFT
0018	805-06483	CONTROLLER	24.00	EACH
0019	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	251.00	EACH
0020	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	59.00	EACH
0021	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	28.00	EACH
0022	805-78420	DISCONNECT HANGER	72.00	EACH
0023	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	3150.00	LFT
0024	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	3000.00	LFT
0025	808-06716	LINE, REMOVE	750.00	LFT
0026	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	750.00	LFT