

Call: 170

Contract: R -36178-A

Section No.: 1 SLIDE CORRECTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	104-05404	DESIGN/BUILD	1.00	LS
0002	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	203-02000	EXCAVATION, COMMON	6040.00	CYS
0013	205-11626	PUMP AROUND	3.00	EACH
0014	205-12108	STORM WATER MANAGEMENT BUDGET	23553.70	DOL
0015	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0016	207-08264	SUBGRADE TREATMENT, TYPE II	280.00	SYS
0017	207-09934	SUBGRADE TREATMENT, TYPE IB	6400.00	SYS
0018	211-09265	STRUCTURE BACKFILL, TYPE 2	274.40	CYS
0019	303-01180	COMPACTED AGGREGATE NO. 53	383.00	TON
0020	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	444.00	TON
0021	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	744.00	TON
0022	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	1810.00	TON
0023	401-10258	JOINT ADHESIVE, SURFACE	1550.00	LFT
0024	401-10259	JOINT ADHESIVE, INTERMEDIATE	1550.00	LFT
0025	401-11785	LIQUID ASPHALT SEALANT	1550.00	LFT
0026	406-05520	ASPHALT FOR TACK COAT	4.00	TON
0027	601-01839	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 6	1.00	EACH
0028	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0029	601-01848	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 5	2.00	EACH
0030	601-05585	GUARDRAIL, TERMINAL SYSTEM, W- BEAM, CURVED, 8	1.00	EACH
0031	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1337.50	LFT

0032	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	8.00	EACH
0033	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0034	601-99106	GUARDRAIL, W-BEAM, 3 FT 1.5 IN. SPACING	3.20	LFT
0035	605-06120	CURB, CONCRETE	1292.00	LFT
0036	605-06121	CURB, CONCRETE B	203.00	LFT
0037	605-09137	CURB, TURNOUT	56.00	LFT
0038	607-06175	GUTTER, CONCRETE, A	1252.00	LFT
0039	610-07487	HMA FOR APPROACHES, TYPE B	62.00	TON
0040	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00	EACH
0041	615-06490	RIGHT-OF-WAY MARKER	4.00	EACH
0042	615-06505	MONUMENT, B	3.00	EACH
0043	616-05689	RIPRAP, CLASS 2	329.40	TON
0044	616-06405	RIPRAP, REVETMENT	154.00	TON
0045	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	309.00	SYS
0046	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	676.00	SYS
0047	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0048	621-06559	MULCHED SEEDING R	4113.00	SYS
0049	621-06567	WATER	9.00	KGAL
0050	621-06575	SODDING, NURSERY	2220.00	SYS
0051	628-09402	FIELD OFFICE, B	21.00	MOS
0052	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0053	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	47.00	LFT
0054	715-05128	PIPE, TYPE 1, CIRCULAR, 48 IN.	48.00	LFT
0055	715-05136	PIPE, TYPE 1, CIRCULAR, 72 IN.	51.00	LFT
0056	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	42.00	LFT
0057	715-06004	CONCRETE ANCHOR, 48 IN.	1.00	EACH
0058	715-06357	CONCRETE ANCHOR, 72 IN.	1.00	EACH
0059	715-09064	VIDEO INSPECTION FOR PIPE	89.00	LFT
0060	715-46040	PIPE END SECTION, DIAMETER 36 IN.	1.00	EACH
0061	720-45030	INLET, E7	1.00	EACH
0062	801-03291	CONSTRUCTION SIGN, D	2.00	EACH
0063	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	EACH
0064	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00	EACH
0065	801-06640	CONSTRUCTION SIGN, A	10.00	EACH
0066	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0067	801-06775	MAINTAINING TRAFFIC	1.00	LS
0068	801-07119	BARRICADE, III-B	96.00	LFT

0069	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0070	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	24.00	LFT
0071	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	2.00	EACH
0072	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	16.00	SFT
0073	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3100.00	LFT
0074	808-12032	GROOVING FOR PAVEMENT MARKINGS	6200.00	LFT
0075	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3100.00	LFT
0076	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	30.00	EACH