

Schedule of Pay Items Letting Date November 15, 2018 Letting ID 181115

Call: 131

Contract: R -36695-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0011	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0012	202-96133	PIPE, REMOVE	127.00	LFT
0013	202-99187	FENCE, FARM FIELD, REMOVE	354.00	LFT
0014	203-02000	EXCAVATION, COMMON	3792.00	CYS
0015	203-02020	EXCAVATION, UNCLASSIFIED	32.00	CYS
0016	203-02070	BORROW	1006.00	CYS
0017	203-08607	LINEAR GRADING	170.00	LFT
0018	205-11626	PUMP AROUND	17.00	EACH
0019	205-12108	STORM WATER MANAGEMENT BUDGET	26311.50	DOL
0020	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	89.00	SYS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	1888.00	SYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	825.30	CYS
0024	211-09266	STRUCTURE BACKFILL, TYPE 3	119.00	CYS
0025	211-09268	STRUCTURE BACKFILL, TYPE 5	402.00	CYS
0026	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	129.00	SYS
0027	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	340.00	SYS
0028	301-12232	COMPACTED AGGREGATE NO 5	98.00	CYS
0029	303-01180	COMPACTED AGGREGATE NO. 53	691.00	TON
0030	303-07449	COMPACTED AGGREGATE NO. 73	3.00	TON
0031	306-08034	MILLING, ASPHALT, 1 1/2 IN.	229.00	SYS

0032	306-08043	MILLING, TRANSITION	496.00	SYS
0033	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	256.00	TON
0034	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	215.00	TON
0035	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	539.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	3140.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	2246.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	5366.00	LFT
0039	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0040	406-05521	ASPHALT FOR TACK COAT	5197.00	SYS
0041	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	826.00	LFT
0042	601-12286	GUARDRAIL, MGS W-BEAM, SHOP CURVED, 6 FT 3 IN SPACING	43.00	LFT
0043	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	2.00	EACH
0044	601-12293	GUARDRAIL, MGS, STRUCTURE, TOP-MOUNTED POST	8.00	EACH
0045	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	1.00	EACH
0046	601-94689	GUARDRAIL, END TREATMENT, OS	7.00	EACH
0047	603-06040	FENCE, FARM FIELD, 47 IN.	354.00	LFT
0048	603-97461	TEMPORARY FENCE	425.00	LFT
0049	610-07487	HMA FOR APPROACHES, TYPE B	24.00	TON
0050	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0051	615-01469	MONUMENT SECTION CORNER INSTALL	1.00	EACH
0052	615-06490	RIGHT-OF-WAY MARKER	23.00	EACH
0053	615-06490	RIGHT-OF-WAY MARKER	8.00	EACH
0054	615-06505	MONUMENT, B	14.00	EACH
0055	616-05688	RIPRAP, CLASS 1	530.00	TON
0056	616-05689	RIPRAP, CLASS 2	40.00	TON
0057	616-06405	RIPRAP, REVETMENT	348.00	TON
0058	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1419.00	SYS
0059	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	9.00	EACH
0060	621-02770	EROSION CONTROL BLANKET	106.00	SYS
0061	621-03909	SEED MIXTURE, NATIVE	11.00	LBS
0062	621-06545	FERTILIZER	1.00	TON
0063	621-06559	MULCHED SEEDING R	3958.00	SYS
0064	621-06567	WATER	6.00	kGAL
0065	621-06570	TOPSOIL	83.00	CYS
0066	621-06626	MULCHED SEEDING D	170.00	SYS
0067	622-10003	LIVE PLANT STAKING	774.00	EACH
0068	622-52436	SIGN, DO NOT MOW OR SPRAY	3.00	EACH

0069	628-09401	FIELD OFFICE, A	42.00	MOS
0070	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0071	629-12029	PLANT GROWTH LAYER	1562.00	SYS
0072	702-44240	CONCRETE, A, STRUCTURES	18.00	CYS
0073	702-51015	CONCRETE, B, FOOTINGS	42.00	CYS
0074	703-06029	REINFORCING BARS, EPOXY COATED	7427.00	LBS
0075	714-10249	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 20 FT. X 8 FT.	60.00	LFT
0076	714-11114	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 14 FT. X 7 FT.	54.00	LFT
0077	714-11191	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 5 FT. X 4 FT.	42.00	LFT
0078	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	78.00	LFT
0079	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	37.00	LFT
0080	715-05248	PIPE, TYPE 1, DEFORMED, MIN. AREA 16.6 SFT	44.00	LFT
0081	715-05596	PIPE EXTENSION, CIRCULAR, 18 IN.	5.50	LFT
0082	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0083	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH
0084	716-07633	PIPE INSTALLATION, TRENCHLESS, 24 IN.	41.00	LFT
0085	725-11021	LINER PIPE, THERMOPLASTIC, DEFORMED, 13.5-16.0 SFT	82.00	LFT
0086	801-03290	CONSTRUCTION SIGN, C	7.00	EACH
0087	801-04308	ROAD CLOSURE SIGN ASSEMBLY	22.00	EACH
0088	801-06625	DETOUR ROUTE MARKER ASSEMBLY	136.00	EACH
0089	801-06640	CONSTRUCTION SIGN, A	69.00	EACH
0090	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0091	801-06775	MAINTAINING TRAFFIC	1.00	LS
0092	801-07118	BARRICADE, III-A	204.00	LFT
0093	801-07119	BARRICADE, III-B	204.00	LFT
0094	802-04893	REFERENCE POST	2.00	EACH
0095	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	58.00	LFT
0096	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	460.00	LFT
0097	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2210.00	LFT
0098	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1056.00	LFT
0099	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	150.00	LFT
0100	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	15.00	EACH
0101	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	16.00	EACH

Call: 141

Contract: R -37142-A

Section No.: 1 ROAD RECONSTRUCTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02278	CURB, CONCRETE, REMOVE	27.00	LFT
0013	202-02279	CURB AND GUTTER, REMOVE	1060.00	LFT
0014	202-06542	RELOCATE	1.00	EACH
0015	202-52710	SIDEWALK CONCRETE, REMOVE	309.00	SYS
0016	202-74035	SIGN, REMOVE	10.00	EACH
0017	202-91385	INLET, REMOVE	1.00	EACH
0018	202-96133	PIPE, REMOVE	640.00	LFT
0019	203-02000	EXCAVATION, COMMON	11930.00	CYS
0020	203-02070	BORROW	360.00	CYS
0021	205-12108	STORM WATER MANAGEMENT BUDGET	46878.06	DOL
0022	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0023	207-08264	SUBGRADE TREATMENT, TYPE II	1719.00	SYS
0024	207-09934	SUBGRADE TREATMENT, TYPE IB	15554.00	SYS
0025	207-09934	SUBGRADE TREATMENT, TYPE IB	10688.00	SYS
0026	211-09265	STRUCTURE BACKFILL, TYPE 2	325.00	CYS
0027	211-09268	STRUCTURE BACKFILL, TYPE 5	183.00	CYS
0028	301-12234	COMPACTED AGGREGATE NO 53	2563.00	CYS
0029	303-01180	COMPACTED AGGREGATE NO. 53	2880.00	TON
0030	304-07493	WIDENING WITH HMA, TYPE B	478.00	TON
0031	306-08034	MILLING, ASPHALT, 1 1/2 IN.	3035.69	SYS

0032	307-12254	FULL DEPTH RECLAMATION	16288.00	SYS
0033	401-06264	PROFILOGRAPH, HMA	1.00	LS
0034	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	3417.00	TON
0035	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	4214.00	TON
0036	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	5244.00	TON
0037	401-10258	JOINT ADHESIVE, SURFACE	21095.00	LFT
0038	401-10259	JOINT ADHESIVE, INTERMEDIATE	21095.00	LFT
0039	401-11785	LIQUID ASPHALT SEALANT	21095.00	LFT
0040	402-07451	HMA WEDGE AND LEVEL, TYPE B	5.00	TON
0041	406-05520	ASPHALT FOR TACK COAT	18.00	TON
0042	601-02241	GUARDRAIL, REMOVE	28.00	LFT
0043	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	200.00	LFT
0044	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	2.00	EACH
0045	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0046	604-05528	HMA FOR SIDEWALK	35.00	TON
0047	604-08086	CURB RAMP, CONCRETE	89.00	SYS
0048	604-12083	DETECTABLE WARNING SURFACES	22.00	SYS
0049	605-06120	CURB, CONCRETE	11475.00	LFT
0050	605-06140	CURB AND GUTTER, CONCRETE	409.00	LFT
0051	605-06255	CENTER CURB, D CONCRETE	33.00	SYS
0052	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	7.00	LFT
0053	605-97937	CURB AND GUTTER, ROLL CURB	360.00	LFT
0054	610-07487	HMA FOR APPROACHES, TYPE B	458.00	TON
0055	610-08446	PCCP FOR APPROACHES, 6 IN.	479.00	SYS
0056	611-06497	MAILBOX ASSEMBLY, SINGLE	10.00	EACH
0057	611-06498	MAILBOX ASSEMBLY, DOUBLE	1.00	EACH
0058	615-06490	RIGHT-OF-WAY MARKER	56.00	EACH
0059	615-06505	MONUMENT, B	9.00	EACH
0060	615-06510	MONUMENT, C	21.00	EACH
0061	615-06520	MONUMENT, RE-ESTABLISH	19.00	EACH
0062	616-06405	RIPRAP, REVETMENT	95.00	TON
0063	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	184.00	SYS
0064	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0065	621-06545	FERTILIZER	3.00	TON
0066	621-06554	SEED MIXTURE U	1135.00	LBS
0067	621-06565	MULCHING MATERIAL	12.00	TON
0068	621-06567	WATER	23.00	kGAL

0069	621-06575	SODDING, NURSERY	5728.00	SYS
0070	628-09402	FIELD OFFICE, B	18.00	MOS
0071	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0072	628-11977	COMPUTER SYSTEM	2.00	EACH
0073	714-11398	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS 18 FT. X 6 FT.	65.00	LFT
0074	715-04555	PIPE END SECTION, MIN. AREA 5.1 SFT	9.00	EACH
0075	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	47.00	LFT
0076	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	67.00	LFT
0077	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	59.00	LFT
0078	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	3.00	LFT
0079	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	256.00	LFT
0080	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	198.00	LFT
0081	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	301.00	LFT
0082	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	29.00	LFT
0083	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	89.00	LFT
0084	715-05335	PIPE, TYPE 2, DEFORMED, MIN. AREA 5.1 SFT	20.00	LFT
0085	715-05363	PIPE, TYPE 3, DEFORMED, MIN. AREA 1.8 SFT	82.00	LFT
0086	715-09769	PIPE, TYPE 3, DEFORMED, MIN. AREA 5.1 SFT	101.00	LFT
0087	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0088	715-46005	PIPE END SECTION, DIAMETER 15 IN.	18.00	EACH
0089	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0090	715-46020	PIPE END SECTION, DIAMETER 24 IN.	8.00	EACH
0091	715-46040	PIPE END SECTION, DIAMETER 36 IN.	1.00	EACH
0092	715-46055	PIPE END SECTION, MIN. AREA 1.8 SFT	2.00	EACH
0093	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0094	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	4.00	EACH
0095	720-45069	INLET, P12	2.00	EACH
0096	720-45410	MANHOLE, C4	3.00	EACH
0097	720-45615	STRUCTURE, INLET, RECONSTRUCTED	3.00	LFT
0098	720-95422	MANHOLE, J4	1.00	EACH
0099	720-98174	INLET, B15	1.00	EACH
0100	801-03291	CONSTRUCTION SIGN, D	4.00	EACH
0101	801-04308	ROAD CLOSURE SIGN ASSEMBLY	22.00	EACH
0102	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	32719.00	LFT
0103	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2070.00	LFT
0104	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	188.00	LFT
0105	801-06625	DETOUR ROUTE MARKER ASSEMBLY	26.00	EACH

0106	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0107	801-06645	CONSTRUCTION SIGN, B	18.00	EACH
0108	801-06775	MAINTAINING TRAFFIC	1.00	LS
0109	801-07118	BARRICADE, III-A	684.00	LFT
0110	801-07119	BARRICADE, III-B	156.00	LFT
0111	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	292.00	LFT
0112	802-07060	SIGN, SHEET, RELOCATE	11.00	EACH
0113	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	197.00	SFT
0114	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	1.00	EACH
0115	805-10107	WIRELESS MAGNETOMETER DETECTOR	1.00	EACH
0116	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	494.00	LFT
0117	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	23.00	LFT
0118	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	18721.00	LFT
0119	808-06716	LINE, REMOVE	179.00	LFT
0120	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0121	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	35.00	LFT
0122	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	17526.00	LFT
0123	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	150.00	LFT
0124	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	23.00	EACH
0125	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	326.00	EACH
0126	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	56.00	EACH
0127	808-95933	CURB, PAINTING, YELLOW	55.00	LFT

Call: 151

Contract: R -37568-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-96133	PIPE, REMOVE	126.00	LFT
0013	203-02000	EXCAVATION, COMMON	936.00	CYS
0014	203-02070	BORROW	26.00	CYS
0015	205-12108	STORM WATER MANAGEMENT BUDGET	6485.00	DOL
0016	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0017	207-08266	SUBGRADE TREATMENT, TYPE III	41.00	SYS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	3415.00	SYS
0019	211-09265	STRUCTURE BACKFILL, TYPE 2	63.00	CYS
0020	301-12234	COMPACTED AGGREGATE NO 53	337.00	CYS
0021	306-08036	MILLING, ASPHALT, 2 IN.	202.00	SYS
0022	401-07352	QC/QA-HMA, 3, 76, SURFACE, 12.5 mm	266.00	TON
0023	401-07403	QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	305.00	TON
0024	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	427.00	TON
0025	401-11787	QC/QA-HMA, 3, 76, INTERMEDIATE, OG 19.0 mm	333.00	TON
0026	406-05521	ASPHALT FOR TACK COAT	6881.00	SYS
0027	415-11527	BASE SEAL	6.00	TON
0028	502-11564	PCCP, 7 IN.	335.00	SYS
0029	503-05240	D-1 CONTRACTION JOINT	187.00	LFT
0030	604-06070	SIDEWALK, CONCRETE	551.00	SYS
0031	604-08086	CURB RAMP, CONCRETE	95.00	SYS

0032	604-12083	DETECTABLE WARNING SURFACES	9.00	SYS
0033	605-06120	CURB, CONCRETE	94.00	LFT
0034	605-06140	CURB AND GUTTER, CONCRETE	1083.00	LFT
0035	605-06255	CENTER CURB, D CONCRETE	57.00	SYS
0036	605-97937	CURB AND GUTTER, ROLL CURB	513.00	LFT
0037	610-07487	HMA FOR APPROACHES, TYPE B	7.00	TON
0038	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00	EACH
0039	615-06490	RIGHT-OF-WAY MARKER	16.00	EACH
0040	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0041	616-06405	RIPRAP, REVETMENT	9.00	TON
0042	621-06560	MULCHED SEEDING U	1375.00	SYS
0043	621-06567	WATER	3.00	kGAL
0044	621-06575	SODDING, NURSERY	694.00	SYS
0045	628-09402	FIELD OFFICE, B	6.00	MOS
0046	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0047	628-11977	COMPUTER SYSTEM	1.00	EACH
0048	715-03475	SAFETY METAL END SECTION, 4:1, DIA 15 IN.	1.00	EACH
0049	715-03584	SAFETY METAL END SECTION, 4:1, DIA 18 IN.	1.00	EACH
0050	715-04611	SAFETY METAL END SECTION, 4:1, DIA 12 IN.	1.00	EACH
0051	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	1017.00	LFT
0052	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	179.00	LFT
0053	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	260.00	LFT
0054	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	208.00	LFT
0055	715-09064	VIDEO INSPECTION FOR PIPE	647.00	LFT
0056	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	839.00	SYS
0057	718-52610	AGGREGATE FOR UNDERDRAINS	85.00	CYS
0058	720-08241	MANHOLE, K15 MODIFIED	3.00	EACH
0059	720-44000	CASTING, ADJUST TO GRADE	2.00	EACH
0060	720-45035	INLET, F7	1.00	EACH
0061	720-45410	MANHOLE, C4	1.00	EACH
0062	720-94432	MANHOLE, C7	2.00	EACH
0063	720-98174	INLET, B15	1.00	EACH
0064	720-98555	INLET, C15	2.00	EACH
0065	801-04308	ROAD CLOSURE SIGN ASSEMBLY	24.00	EACH
0066	801-06625	DETOUR ROUTE MARKER ASSEMBLY	68.00	EACH
0067	801-06640	CONSTRUCTION SIGN, A	20.00	EACH
0068	801-06645	CONSTRUCTION SIGN, B	6.00	EACH

0069	801-06775	MAINTAINING TRAFFIC	1.00	LS
0070	801-07119	BARRICADE, III-B	530.00	LFT
0071	802-04089	SIGN, SHEET, REMOVE	5.00	EACH
0072	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	260.00	LFT
0073	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	68.00	LFT
0074	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	124.00	SFT
0075	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	83.00	SFT
0076	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	22.00	SFT
0077	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	190.00	LFT
0078	807-02426	WIRE, THW, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	190.00	LFT
0079	807-02934	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. X 36 IN. X 96 IN.	4.00	EACH
0080	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	480.00	LFT
0081	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	4.00	EACH
0082	807-83752	LIGHT POLE, 40 FT. E.M.H. 10 FT. MAST ARM, ANCHOR BASE	4.00	EACH
0083	807-86805	SERVICE POINT, I	1.00	EACH
0084	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	480.00	LFT
0085	807-86910	CONNECTOR KIT, UNFUSED	4.00	EACH
0086	807-86915	CONNECTOR KIT, FUSED	4.00	EACH
0087	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	9.00	EACH
0088	807-86930	INSULATION LINK, NON-WATERPROOFED	8.00	EACH
0089	807-86950	SIGN, UNDERPASS AND ROADWAY LIGHTING LOCATION IDENTIFICATION	4.00	EACH
0090	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	162.00	LFT
0091	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	313.00	LFT
0092	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	40.00	LFT
0093	808-11698	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 27 IN.	65.00	LFT
0094	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	776.00	LFT

Call: 161

Contract: R -37713-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	202-02278	CURB, CONCRETE, REMOVE	1765.00	LFT
0011	202-52710	SIDEWALK CONCRETE, REMOVE	1960.00	SYS
0012	202-91385	INLET, REMOVE	3.00	EACH
0013	202-93615	CONCRETE, REMOVE	615.00	SYS
0014	205-12108	STORM WATER MANAGEMENT BUDGET	7000.00	DOL
0015	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0016	207-08264	SUBGRADE TREATMENT, TYPE II	3186.00	SYS
0017	214-07202	GEOGRID, TYPE IA	1770.00	SYS
0018	502-05402	CEMENT CONCRETE PAVEMENT FOR DRIVEWAYS	760.00	SYS
0019	506-06333	PCCP PATCHING, FULL DEPTH	75.00	SYS
0020	604-01268	HAND RAIL ALUMINUM	38.00	LFT
0021	604-06070	SIDEWALK, CONCRETE	1684.00	SYS
0022	604-08086	CURB RAMP, CONCRETE	792.00	SYS
0023	604-12083	DETECTABLE WARNING SURFACES	347.00	SYS
0024	605-06120	CURB, CONCRETE	2047.00	LFT
0025	618-03812	BENCH	2.00	EACH
0026	621-06574	SODDING	1900.00	SYS
0027	628-09401	FIELD OFFICE, A	9.00	MOS
0028	715-05052	PIPE, TYPE 4, CIRCULAR, 12 IN.	244.00	LFT
0029	715-05209	PIPE, TYPE 4, CIRCULAR, 18 IN.	10.00	LFT
0030	715-05212	PIPE, TYPE 4, CIRCULAR, 24 IN.	82.00	LFT
0031	715-05422	PIPE, SLOTTED DRAIN, 12 IN.	381.00	LFT

0032	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	EACH
0033	715-91739	WATER SERVICE LINE, 0.75 IN	31.00	LFT
0034	715-91742	WATER METER RELOCATE	1.00	EACH
0035	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0036	720-45045	INLET, J10	1.00	EACH
0037	720-45075	INLET, R13	2.00	EACH
0038	720-90984	MANHOLE, C2	2.00	EACH
0039	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	12.00	EACH
0040	801-06640	CONSTRUCTION SIGN, A	46.00	EACH
0041	801-06645	CONSTRUCTION SIGN, B	41.00	EACH
0042	801-06775	MAINTAINING TRAFFIC	1.00	LS
0043	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	8.00	EACH
0044	808-06716	LINE, REMOVE	1364.00	LFT
0045	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	1934.00	LFT
0046	808-75215	LINE, THERMOPLASTIC, SOLID, WHITE, 12 IN.	540.00	LFT
0047	808-97222	PAVEMENT MESSAGE MARKING, PAINT, HANDICAP SYMBOL	1.00	EACH

Call: 171

Contract: R -37730-A

Section No.: 1 SMALL STRUCTURE MAINTENANCE AND REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0012	202-96133	PIPE, REMOVE	15.00	LFT
0013	203-02000	EXCAVATION, COMMON	20.00	CYS
0014	205-12108	STORM WATER MANAGEMENT BUDGET	2955.50	DOL
0015	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0016	207-09935	SUBGRADE TREATMENT, TYPE IC	160.00	SYS
0017	211-09265	STRUCTURE BACKFILL, TYPE 2	115.00	CYS
0018	301-12232	COMPACTED AGGREGATE NO 5	10.00	CYS
0019	301-12234	COMPACTED AGGREGATE NO 53	10.00	CYS
0020	303-07449	COMPACTED AGGREGATE NO. 73	75.00	TON
0021	306-08034	MILLING, ASPHALT, 1 1/2 IN.	630.00	SYS
0022	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	65.00	TON
0023	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	22.00	TON
0024	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	52.00	TON
0025	401-10258	JOINT ADHESIVE, SURFACE	250.00	LFT
0026	401-10259	JOINT ADHESIVE, INTERMEDIATE	100.00	LFT
0027	401-11785	LIQUID ASPHALT SEALANT	250.00	LFT
0028	406-05521	ASPHALT FOR TACK COAT	1090.00	SYS
0029	616-06405	RIPRAP, REVETMENT	42.00	TON
0030	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	180.00	SYS
0031	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH

0032	621-02770	EROSION CONTROL BLANKET	230.00	SYS
0033	621-03787	SEED MIXTURE D	1.00	LBS
0034	621-03909	SEED MIXTURE, NATIVE	4.00	LBS
0035	628-09402	FIELD OFFICE, B	4.00	MOS
0036	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0037	714-11309	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 9 FT. X 5 FT.	38.00	LFT
0038	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	15.00	LFT
0039	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0040	801-06625	DETOUR ROUTE MARKER ASSEMBLY	40.00	EACH
0041	801-06640	CONSTRUCTION SIGN, A	17.00	EACH
0042	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0043	801-06775	MAINTAINING TRAFFIC	1.00	LS
0044	801-07118	BARRICADE, III-A	48.00	LFT
0045	801-07119	BARRICADE, III-B	32.00	LFT
0046	802-91122	SIGN GROUND MOUNTED RESET	4.00	EACH
0047	804-11920	DELINEATOR POST FLEXIBLE, TYPE I	2.00	EACH
0048	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	60.00	LFT
0049	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	500.00	LFT
0050	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	175.00	LFT
0051	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6.00	EACH

Call: 191

Contract: R -38310-A

Section No.: 1 INTERSECTION IMPROVEMENTS

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0003	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0004	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0005	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0008	202-02278	CURB, CONCRETE, REMOVE	182.00	LFT
0009	202-52710	SIDEWALK CONCRETE, REMOVE	108.00	SYS
0010	202-74035	SIGN, REMOVE	2.00	EACH
0011	205-12108	STORM WATER MANAGEMENT BUDGET	5000.00	DOL
0012	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0013	207-08262	SUBGRADE TREATMENT, TYPE I	10.00	SYS
0014	302-06464	SUBBASE FOR PCCP	2.00	CYS
0015	604-06070	SIDEWALK, CONCRETE	127.00	SYS
0016	604-08086	CURB RAMP, CONCRETE	42.00	SYS
0017	604-12083	DETECTABLE WARNING SURFACES	12.00	SYS
0018	605-06090	CURB, INTEGRAL CONCRETE	150.00	LFT
0019	610-08516	PCCP FOR APPROACHES, 12 IN.	10.00	SYS
0020	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0021	621-06560	MULCHED SEEDING U	320.00	SYS
0022	628-09402	FIELD OFFICE, B	6.00	MOS
0023	801-06640	CONSTRUCTION SIGN, A	8.00	EACH
0024	801-06775	MAINTAINING TRAFFIC	1.00	LS
0025	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	38.00	SFT
0026	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	7.00	SFT
0027	802-09841	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.125 IN. THICKNESS	21.00	SFT
0028	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	28.00	SFT
0029	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00	EACH
0030	805-01842	HANDHOLE SIGNAL TYPE 1	6.00	EACH
0031	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	578.00	LFT

0032	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	8.00	EACH
0033	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0034	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	8.00	EACH
0035	805-03978	EMERGENCY VEHICLE PREEMPTION DETECTOR, SINGLE CHANNEL, ONE DIRECTION	4.00	EACH
0036	805-03980	EMERGENCY VEHICLE CONFIRMATION LIGHT KIT	4.00	EACH
0037	805-09451	SIGNAL POLE, PEDESTAL, 15 FT	2.00	EACH
0038	805-09845	CONTACT CLOSURE CARD	2.00	EACH
0039	805-09846	RECEIVER PROCESSOR	2.00	EACH
0040	805-10107	WIRELESS MAGNETOMETER DETECTOR	40.00	EACH
0041	805-10108	WIRELESS REPEATER	2.00	EACH
0042	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	270.00	LFT
0043	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00	EACH
0044	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	9.00	EACH
0045	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	1.00	EACH
0046	805-78415	SPAN, CATENARY, AND TETHER	4.00	EACH
0047	805-78420	DISCONNECT HANGER	4.00	EACH
0048	805-78445	SIGNAL SERVICE	1.00	EACH
0049	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	88.00	LFT
0050	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	2959.00	LFT
0051	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	53.00	LFT
0052	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	739.00	LFT
0053	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0054	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	4.00	EACH
0055	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	8.00	EACH
0056	807-02191	HANDHOLE LIGHTING	4.00	EACH
0057	807-02579	MAST ARM, 15FT	4.00	EACH
0058	807-03950	LUMINAIRE ORNAMENTAL	4.00	EACH
0059	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	825.00	LFT
0060	807-86810	SERVICE POINT, II	1.00	EACH
0061	807-86910	CONNECTOR KIT, UNFUSED	4.00	EACH
0062	807-86915	CONNECTOR KIT, FUSED	4.00	EACH
0063	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.00	EACH
0064	807-86935	INSULATION LINK, WATERPROOFED	20.00	EACH
0065	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	500.00	LFT
0066	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1200.00	LFT
0067	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	154.00	LFT
0068	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	734.00	LFT

0069	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	11.00	EACH
0070	809-03983	PHASE SELECTORS	1.00	EACH

Call: 201

Contract: R -39234-A

Section No.: 1 SMALL STRUCTURE MAINTENANCE AND REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0010	202-91840	FENCE, CHAIN. LINK, REMOVE	1024.00	LFT
0011	205-11583	MANUFACTURED SURFACE PROTECTION PRODUCT TYPE	124.00	SYS
0012	205-11626	PUMP AROUND	1.00	EACH
0013	205-12108	STORM WATER MANAGEMENT BUDGET	53260.00	DOL
0014	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0015	211-09265	STRUCTURE BACKFILL, TYPE 2	4207.00	CYS
0016	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	4550.00	SYS
0017	301-12233	COMPACTED AGGREGATE NO 8	675.00	CYS
0018	603-06045	FENCE, CHAIN LINK, 48 IN.	1024.00	LFT
0019	616-05688	RIPRAP, CLASS 1	235.00	TON
0020	616-05689	RIPRAP, CLASS 2	411.00	TON
0021	616-06405	RIPRAP, REVETMENT	401.00	TON
0022	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	1434.00	SYS
0023	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0024	621-02770	EROSION CONTROL BLANKET	134.00	SYS
0025	621-03909	SEED MIXTURE, NATIVE	43.00	LBS
0026	621-03909	SEED MIXTURE, NATIVE	8.00	LBS
0027	621-06545	FERTILIZER	1.00	TON
0028	621-06553	SEED MIXTURE R	118.00	LBS
0029	621-06565	MULCHING MATERIAL	5.00	TON
0030	621-06737	SEED MIXTURE, EMERGENT WETLAND	1.00	LBS
0031	622-05640	PLANT, DECIDUOUS SHRUB, 24 TO 36 IN.	245.00	EACH

0032	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	319.00	EACH
0033	622-98200	SIGN, DO NOT DISTURB	12.00	EACH
0034	628-09403	FIELD OFFICE, C	35.00	MOS
0035	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0036	628-11977	COMPUTER SYSTEM	1.00	EACH
0037	701-12304	VIBRATION MONITORING	1.00	LS
0038	714-11077	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 12 FT X 12 FT	910.00	LFT
0039	715-05756	PIPE EXTENSION, CIRCULAR, 12 IN.	10.00	LFT
0040	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0041	801-06775	MAINTAINING TRAFFIC	1.00	LS
0042	804-06770	DELINEATOR POST	12.00	EACH

Call: 211

Contract: R -39382-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	205-11626	PUMP AROUND	4.00	EACH
0010	205-12108	STORM WATER MANAGEMENT BUDGET	57460.00	DOL
0011	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0012	211-09268	STRUCTURE BACKFILL, TYPE 5	316.00	CYS
0013	601-06035	GUARDRAIL, RESET	100.00	LFT
0014	603-06040	FENCE, FARM FIELD, 47 IN.	400.00	LFT
0015	603-97461	TEMPORARY FENCE	200.00	LFT
0016	616-05688	RIPRAP, CLASS 1	86.00	TON
0017	616-05689	RIPRAP, CLASS 2	449.00	TON
0018	616-06405	RIPRAP, REVETMENT	34.00	TON
0019	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	369.00	SYS
0020	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	168.00	SYS
0021	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0022	621-06559	MULCHED SEEDING R	1620.00	SYS
0023	628-09402	FIELD OFFICE, B	8.00	MOS
0024	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0025	702-90915	CONCRETE, CLASS, A	143.00	CYS
0026	715-95325	INVERT, CONCRETE PAVED	172.00	LFT
0027	725-10245	PERPETUATION, EXISTING PIPE	3.00	EACH
0028	725-11022	LINER PIPE, THERMOPLASTIC, DEFORMED, 22.4-23.8 SFT	229.00	LFT
0029	725-11039	LINER PIPE, THERMOPLASTIC, CIRCULAR, 19.6-19.7 SFT	554.00	LFT
0030	725-11042	LINER PIPE, THERMOPLASTIC, CIRCULAR, 27.7-28.3 SFT	246.00	LFT
0031	801-06640	CONSTRUCTION SIGN, A	80.00	EACH

0032	801-06775	MAINTAINING TRAFFIC	1.00	LS
------	-----------	---------------------	------	----

Call: 221

Contract: R -39790-A

Section No.: 1 SIDEWALK MODERNIZATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	12.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	15.50	SYS
0013	202-02278	CURB, CONCRETE, REMOVE	826.00	LFT
0014	202-02279	CURB AND GUTTER, REMOVE	539.50	LFT
0015	202-52710	SIDEWALK CONCRETE, REMOVE	951.20	SYS
0016	203-02000	EXCAVATION, COMMON	7.40	CYS
0017	205-12108	STORM WATER MANAGEMENT BUDGET	1900.00	DOL
0018	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	905.00	SYS
0020	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	905.00	SYS
0021	304-07491	HMA PATCHING, TYPE C	292.40	TON
0022	305-12395	PCC BASE 10.5 IN	17.60	SYS
0023	502-06329	PCCP, 12 IN.	15.50	SYS
0024	502-06457	PCCP, 9 IN.	10.00	SYS
0025	604-06070	SIDEWALK, CONCRETE	463.10	SYS
0026	604-08086	CURB RAMP, CONCRETE	458.60	SYS
0027	604-12083	DETECTABLE WARNING SURFACES	61.40	SYS
0028	605-06125	CURB, CONCRETE, MODIFIED	729.00	LFT
0029	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	531.50	LFT
0030	621-06567	WATER	1.60	kGAL
0031	621-06570	TOPSOIL	8.70	CYS

0032	621-06575	SODDING, NURSERY	244.90	SYS
0033	628-09402	FIELD OFFICE, B	12.00	MOS
0034	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0035	720-44000	CASTING, ADJUST TO GRADE	8.00	EACH
0036	720-44000	CASTING, ADJUST TO GRADE	2.00	EACH
0037	801-06775	MAINTAINING TRAFFIC	1.00	LS
0038	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	77.00	LFT
0039	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	11.00	EACH
0040	802-07060	SIGN, SHEET, RELOCATE	16.00	EACH
0041	802-90623	SIGN BRACKET FOR STREET NAME	2.00	EACH
0042	802-97428	SIGN POST, TUBULAR	27.00	LFT
0043	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0044	805-01842	HANDHOLE SIGNAL TYPE 1	1.00	EACH
0045	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	114.00	LFT
0046	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0047	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	4.00	EACH
0048	805-05405	SIGNAL POLE, PEDESTAL, 4FT	4.00	EACH
0049	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00	EACH
0050	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	214.00	LFT
0051	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	212.00	LFT
0052	805-92951	SIGNAL DETECTOR HOUSING ADJUST TO GRADE	1.00	EACH
0053	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	11.00	LFT
0054	808-06716	LINE, REMOVE	960.00	LFT
0055	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	940.50	LFT
0056	808-75035	LINE, PAINT, SOLID, WHITE, 24 IN.	75.00	LFT

Call: 231

Contract: R -40747-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	222.00	SYS
0013	202-02271	HEADWALL, REMOVE	1.00	EACH
0014	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0015	203-02020	EXCAVATION, UNCLASSIFIED	490.00	CYS
0016	205-11626	PUMP AROUND	2.00	EACH
0017	205-12108	STORM WATER MANAGEMENT BUDGET	9712.00	DOL
0018	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0019	206-51215	EXCAVATION, X	32.00	CYS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	756.00	SYS
0021	211-09265	STRUCTURE BACKFILL, TYPE 2	36.00	CYS
0022	211-09268	STRUCTURE BACKFILL, TYPE 5	292.00	CYS
0023	214-12236	GEOTEXTILE FOR PAVEMENT TYPE 1A	450.00	SYS
0024	301-12232	COMPACTED AGGREGATE NO 5	69.00	CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	366.00	TON
0026	306-08034	MILLING, ASPHALT, 1 1/2 IN.	533.33	SYS
0027	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	98.30	TON
0028	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	95.20	TON
0029	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	330.70	TON
0030	401-10258	JOINT ADHESIVE, SURFACE	1250.00	LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	1050.00	LFT

0032	401-11785	LIQUID ASPHALT SEALANT	1250.00	LFT
0033	406-05521	ASPHALT FOR TACK COAT	1874.00	SYS
0034	601-01704	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, MODIFIED	1.00	EACH
0035	601-02241	GUARDRAIL, REMOVE	387.50	LFT
0036	601-06854	GUARDRAIL, W-BEAM, NESTED	1.00	EACH
0037	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	156.25	LFT
0038	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	1.00	EACH
0039	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00	EACH
0040	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0041	606-07484	MILLED HMA CORRUGATIONS	686.00	LFT
0042	615-06490	RIGHT-OF-WAY MARKER	17.00	EACH
0043	615-06505	MONUMENT, B	4.00	EACH
0044	616-05689	RIPRAP, CLASS 2	44.00	TON
0045	616-06405	RIPRAP, REVETMENT	199.00	TON
0046	616-06451	RIPRAP, UNIFORM	162.00	TON
0047	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	486.00	SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0049	621-06559	MULCHED SEEDING R	657.00	SYS
0050	621-06574	SODDING	77.00	SYS
0051	628-09402	FIELD OFFICE, B	12.00	MOS
0052	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0053	702-04325	TEMPORARY SHORING	1.00	LS
0054	702-51005	CONCRETE, A, SUBSTRUCTURE	15.00	CYS
0055	703-06029	REINFORCING BARS, EPOXY COATED	1968.00	LBS
0056	723-12198	STRUCTURE, COATED REINFORCED CONCRETE, THREE-SIDED SECTIONS, 168 IN.X 108 IN.	51.50	LFT
0057	725-10224	LINER PIPE, THERMOPLASTIC, CIRCULAR, 8.4-8.8 SFT	82.70	LFT
0058	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0059	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2251.00	LFT
0060	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	24.00	LFT
0061	801-06640	CONSTRUCTION SIGN, A	28.00	EACH
0062	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0063	801-06775	MAINTAINING TRAFFIC	1.00	LS
0064	801-07118	BARRICADE, III-A	24.00	LFT
0065	801-07119	BARRICADE, III-B	24.00	LFT
0066	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	150.00	LFT
0067	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0068	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	60.00	LFT

0069	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	28.50	SFT
0070	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0071	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1000.00	LFT
0072	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1300.00	LFT
0073	808-06716	LINE, REMOVE	1500.00	LFT
0074	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	3.00	EACH
0075	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	3.00	EACH

Call: 241

Contract: R -40783-A

Section No.: 1 SMALL STRUCTURE, PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02272	PAVED SIDE DITCH, REMOVE	15.00	LFT
0013	203-02000	EXCAVATION, COMMON	285.00	CYS
0014	203-02010	EXCAVATION, ROCK	16.00	CYS
0015	205-11626	PUMP AROUND	9.00	EACH
0016	205-12108	STORM WATER MANAGEMENT BUDGET	22914.25	DOL
0017	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0018	207-08266	SUBGRADE TREATMENT, TYPE III	1297.333	SYS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	412.889	SYS
0020	211-09265	STRUCTURE BACKFILL, TYPE 2	4853.00	CYS
0021	301-12234	COMPACTED AGGREGATE NO 53	168.00	CYS
0022	303-01180	COMPACTED AGGREGATE NO. 53	348.00	TON
0023	303-07449	COMPACTED AGGREGATE NO. 73	205.00	TON
0024	306-08034	MILLING, ASPHALT, 1 1/2 IN.	252.00	SYS
0025	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	52.00	TON
0026	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	51.00	TON
0027	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	120.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	245.00	LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	145.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	245.00	LFT
0031	406-05520	ASPHALT FOR TACK COAT	2.00	TON

0032	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0033	601-02241	GUARDRAIL, REMOVE	1151.00	LFT
0034	601-06035	GUARDRAIL, RESET	50.00	LFT
0035	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1250.00	LFT
0036	601-94689	GUARDRAIL, END TREATMENT, OS	7.00	EACH
0037	615-06490	RIGHT-OF-WAY MARKER	27.00	EACH
0038	615-06505	MONUMENT, B	4.00	EACH
0039	615-06530	BENCH MARK POST	2.00	EACH
0040	616-05688	RIPRAP, CLASS 1	158.00	TON
0041	616-05689	RIPRAP, CLASS 2	362.00	TON
0042	616-06405	RIPRAP, REVETMENT	2576.00	TON
0043	616-06451	RIPRAP, UNIFORM	152.00	TON
0044	616-11928	RIPRAP, GROUTED, 24 IN.	30.00	SYS
0045	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	4165.00	SYS
0046	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	565.00	SYS
0047	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.00	EACH
0048	621-06559	MULCHED SEEDING R	1781.00	SYS
0049	621-06626	MULCHED SEEDING D	197.00	SYS
0050	628-09403	FIELD OFFICE, C	9.00	MOS
0051	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0052	702-51015	CONCRETE, B, FOOTINGS	11.222	CYS
0053	702-90915	CONCRETE, CLASS, A	15.259	CYS
0054	714-11188	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 12 FT. X 8 FT.	94.00	LFT
0055	715-05133	PIPE, TYPE 1, CIRCULAR, 60 IN.	73.00	LFT
0056	715-11643	PIPE END SECTION, ENERGY DISSIPATOR	1.00	EACH
0057	725-10203	PIPE LINER, CURED-IN-PLACE, 72 IN	202.00	LFT
0058	801-04308	ROAD CLOSURE SIGN ASSEMBLY	17.00	EACH
0059	801-06625	DETOUR ROUTE MARKER ASSEMBLY	70.00	EACH
0060	801-06640	CONSTRUCTION SIGN, A	43.00	EACH
0061	801-06775	MAINTAINING TRAFFIC	1.00	LS
0062	801-07118	BARRICADE, III-A	96.00	LFT
0063	801-07119	BARRICADE, III-B	264.00	LFT
0064	802-04089	SIGN, SHEET, REMOVE	1.00	EACH
0065	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	9.00	LFT
0066	802-07060	SIGN, SHEET, RELOCATE	2.00	EACH
0067	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	37.00	LFT
0068	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	490.00	LFT

0069 808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.

345.00 LFT

Call: 251

Contract: R -41354-A

Section No.: 1 ROADSIDE MAINTENANCE, TREE REMOVAL AND TRIMMING

Line

Item No	Item Code	Description	Quantity Unit	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	201-01015	CLEARING AND GRUBBING	1.00	LS
0008	201-02245	TREE 6 IN., REMOVE	94.00	EACH
0009	201-02250	TREE 10 IN., REMOVE	55.00	EACH
0010	201-02250	TREE 10 IN., REMOVE	1.00	EACH
0011	201-02255	TREE 18 IN., REMOVE	16.00	EACH
0012	201-02255	TREE 18 IN., REMOVE	3.00	EACH
0013	201-02260	TREE 30 IN., REMOVE	22.00	EACH
0014	201-02260	TREE 30 IN., REMOVE	20.00	EACH
0015	201-02265	TREE 48 IN., REMOVE	11.00	EACH
0016	201-02265	TREE 48 IN., REMOVE	2.00	EACH
0017	201-02270	TREE 60 IN., REMOVE	2.00	EACH
0018	201-02270	TREE 60 IN., REMOVE	2.00	EACH
0019	801-06640	CONSTRUCTION SIGN, A	8.00	EACH
0020	801-06710	FLASHING ARROW SIGN	20.00	DAY
0021	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 301

Contract: RS-39375-A

Section No.: 1 PCCP CLEANING AND SEALING JOINTS

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02278	CURB, CONCRETE, REMOVE	822.00	LFT
0014	202-02279	CURB AND GUTTER, REMOVE	746.00	LFT
0015	202-52710	SIDEWALK CONCRETE, REMOVE	634.00	SYS
0016	203-02000	EXCAVATION, COMMON	335.00	CYS
0017	203-02070	BORROW	1.00	CYS
0018	205-12108	STORM WATER MANAGEMENT BUDGET	1800.00	DOL
0019	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	5956.00	SYS
0021	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	960.00	SYS
0022	301-12234	COMPACTED AGGREGATE NO 53	107.00	CYS
0023	302-06464	SUBBASE FOR PCCP	899.00	CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	181.00	TON
0025	304-07491	HMA PATCHING, TYPE C	1156.00	TON
0026	306-08034	MILLING, ASPHALT, 1 1/2 IN.	165091.00	SYS
0027	306-08432	MILLING, APPROACH	18754.00	SYS
0028	306-08599	MILLING, ASPHALT, 1/2 IN.	4883.00	SYS
0029	306-11680	MILLING, ASPHALT, 5.5 IN.	4883.00	SYS
0030	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2905.00	TON
0031	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	11196.00	TON

0032	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1366.00	TON
0033	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	317.00	TON
0034	401-10258	JOINT ADHESIVE, SURFACE	93486.00	LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	115.00	LFT
0036	401-11785	LIQUID ASPHALT SEALANT	93486.00	LFT
0037	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	144.00	TON
0038	406-05520	ASPHALT FOR TACK COAT	38.00	TON
0039	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	3.00	TON
0040	503-03489	RETROFITTED TIE BARS	844.00	EACH
0041	503-05240	D-1 CONTRACTION JOINT	1142.00	LFT
0042	506-06333	PCCP PATCHING, FULL DEPTH	3596.00	SYS
0043	507-07482	CRACKS IN PCCP, ROUT AND SEAL	1714.00	LFT
0044	507-08272	JOINTS IN PCCP, SAW AND SEAL	610215.00	LFT
0045	507-12191	JOINT REPAIR, PARTIAL DEPTH	2268.00	SFT
0046	604-06070	SIDEWALK, CONCRETE	272.00	SYS
0047	604-08086	CURB RAMP, CONCRETE	313.00	SYS
0048	604-12083	DETECTABLE WARNING SURFACES	57.00	SYS
0049	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	4.00	SYS
0050	605-06120	CURB, CONCRETE	824.00	LFT
0051	605-06145	CURB AND GUTTER, B, CONCRETE	720.00	LFT
0052	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	131.00	LFT
0053	610-07488	HMA FOR APPROACHES, TYPE C	1547.00	TON
0054	615-06520	MONUMENT, RE-ESTABLISH	20.00	EACH
0055	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0056	621-06560	MULCHED SEEDING U	37.00	SYS
0057	621-06567	WATER	0.30	kgAL
0058	621-06570	TOPSOIL	16.00	CYS
0059	621-06575	SODDING, NURSERY	84.00	SYS
0060	628-09402	FIELD OFFICE, B	22.00	MOS
0061	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0062	628-11977	COMPUTER SYSTEM	1.00	EACH
0063	702-51005	CONCRETE, A, SUBSTRUCTURE	5.00	CYS
0064	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	720.00	LFT
0065	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	20.00	LFT
0066	718-06528	OUTLET PROTECTOR, 1	1.00	EACH
0067	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	536.00	SYS
0068	718-52610	AGGREGATE FOR UNDERDRAINS	80.00	CYS

0069	720-44000	CASTING, ADJUST TO GRADE	5.00	EACH
0070	720-44000	CASTING, ADJUST TO GRADE	3.00	EACH
0071	720-44000	CASTING, ADJUST TO GRADE	46.00	EACH
0072	720-44000	CASTING, ADJUST TO GRADE	28.00	EACH
0073	720-44000	CASTING, ADJUST TO GRADE	29.00	EACH
0074	720-44070	CASTING, 13, FURNISH AND ADJUST TO GRADE	1.00	EACH
0075	801-06640	CONSTRUCTION SIGN, A	105.00	EACH
0076	801-06710	FLASHING ARROW SIGN	2640.00	DAY
0077	801-06775	MAINTAINING TRAFFIC	1.00	LS
0078	801-12042	TRUCK MOUNTED ATTENUATOR	2640.00	DAY
0079	801-12324	LAW ENFORCEMENT OFFICER	1000.00	HRS
0080	805-01744	LOOP RESEAL	410.00	EACH
0081	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	66.00	LFT
0082	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	2.00	EACH
0083	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	4.00	EACH
0084	805-05405	SIGNAL POLE, PEDESTAL, 4FT	2.00	EACH
0085	805-11817	PEDESTRIAN PUSH BUTTON, APS	4.00	EACH
0086	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	1011.00	LFT
0087	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	479.00	LFT
0088	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	2.00	EACH
0089	808-03442	PAVEMENT MESSAGE MARKING, PAINT, BIKE SYMBOL	5.00	EACH
0090	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	10416.00	LFT
0091	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	1895.00	LFT
0092	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	182380.00	LFT
0093	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	136993.00	LFT
0094	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	224.00	EACH
0095	808-06724	PAVEMENT MESSAGE MARKING, PAINT, ONLY	70.00	EACH
0096	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	2912.00	LFT
0097	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0098	808-11960	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 24 IN.	30.00	LFT
0099	808-12032	GROOVING FOR PAVEMENT MARKINGS	47614.00	LFT
0100	808-12046	LINE, PAINT, DOTTED, WHITE, 4 IN.	345.00	LFT
0101	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	1860.00	LFT
0102	808-75056	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE, 8 IN.	50.00	LFT
0103	808-75059	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	47614.00	LFT
0104	808-75060	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE 12 IN.	1756.00	LFT
0105	808-75074	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, YELLOW, 8 IN.	1627.00	LFT

0106	808-75078	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, YELLOW, 12 IN.	120.00	LFT
0107	808-75100	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 6 IN.	3598.00	LFT
0108	808-75140	PAVEMENT MESSAGE MARKING, PAINT, R X R	8.00	EACH
0109	808-75350	PAVEMENT MESSAGE MARKING, THERMOPLASTIC SCHOOL	1.00	EACH
0110	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	3490.00	EACH
0111	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	3490.00	EACH

Call: 305

Contract: RS-39782-B

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-52710	SIDEWALK CONCRETE, REMOVE	13.80	SYS
0012	202-90277	DETECTOR HOUSING, REMOVE	2.00	EACH
0013	207-09935	SUBGRADE TREATMENT, TYPE IC	66.00	SYS
0014	303-01180	COMPACTED AGGREGATE NO. 53	1347.00	TON
0015	304-07490	HMA PATCHING, TYPE B	1589.00	TON
0016	306-08036	MILLING, ASPHALT, 2 IN.	86384.00	SYS
0017	306-08043	MILLING, TRANSITION	5715.00	SYS
0018	306-08432	MILLING, APPROACH	5243.00	SYS
0019	401-06264	PROFILOGRAPH, HMA	1.00	LS
0020	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	10126.00	TON
0021	401-11785	LIQUID ASPHALT SEALANT	44462.00	LFT
0022	401-11785	LIQUID ASPHALT SEALANT	44462.00	LFT
0023	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	20.00	TON
0024	604-08086	CURB RAMP, CONCRETE	13.80	SYS
0025	604-12083	DETECTABLE WARNING SURFACES	2.20	SYS
0026	605-06120	CURB, CONCRETE	29.50	LFT
0027	610-07487	HMA FOR APPROACHES, TYPE B	577.00	TON
0028	628-09402	FIELD OFFICE, B	6.00	MOS
0029	720-44000	CASTING, ADJUST TO GRADE	5.00	EACH
0030	720-44000	CASTING, ADJUST TO GRADE	7.00	EACH
0031	720-44000	CASTING, ADJUST TO GRADE	4.00	EACH

0032	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2519.00	LFT
0033	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	693.00	LFT
0034	801-06640	CONSTRUCTION SIGN, A	55.00	EACH
0035	801-06775	MAINTAINING TRAFFIC	1.00	LS
0036	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	3563.00	LFT
0037	805-78785	SIGNAL DETECTOR HOUSING	2.00	EACH
0038	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1158.00	LFT
0039	805-92951	SIGNAL DETECTOR HOUSING ADJUST TO GRADE	1.00	EACH
0040	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1949.25	LFT
0041	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	44652.00	LFT
0042	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0043	808-12032	GROOVING FOR PAVEMENT MARKINGS	87474.00	LFT
0044	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1439.50	LFT
0045	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	39433.00	LFT
0046	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	693.00	LFT
0047	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	32.00	EACH
0048	808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC R X R	4.00	EACH
0049	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	315.00	EACH
0050	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	315.00	EACH

Call: 311

Contract: RS-40520-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	42.00	SYS
0013	202-02279	CURB AND GUTTER, REMOVE	707.00	LFT
0014	202-52710	SIDEWALK CONCRETE, REMOVE	354.00	SYS
0015	205-12108	STORM WATER MANAGEMENT BUDGET	1900.00	DOL
0016	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0017	207-08264	SUBGRADE TREATMENT, TYPE II	42.00	SYS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	1497.00	SYS
0019	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	24.00	EACH
0020	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	84.00	CYS
0021	301-12231	COMPACTED AGGREGATE NO 2	36.00	CYS
0022	303-01180	COMPACTED AGGREGATE NO. 53	10.00	TON
0023	303-07449	COMPACTED AGGREGATE NO. 73	2495.00	TON
0024	304-07490	HMA PATCHING, TYPE B	3009.00	TON
0025	306-08034	MILLING, ASPHALT, 1 1/2 IN.	236730.00	SYS
0026	306-08036	MILLING, ASPHALT, 2 IN.	132.00	SYS
0027	306-08038	MILLING, ASPHALT, 4 IN.	71.00	SYS
0028	306-08432	MILLING, APPROACH	12820.00	SYS
0029	401-06264	PROFILOGRAPH, HMA	1.00	LS
0030	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	19530.00	TON
0031	401-10258	JOINT ADHESIVE, SURFACE	123300.00	LFT

0032	401-11785	LIQUID ASPHALT SEALANT	180700.00	LFT
0033	406-05520	ASPHALT FOR TACK COAT	62.00	TON
0034	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	35.00	TON
0035	604-06070	SIDEWALK, CONCRETE	102.00	SYS
0036	604-08086	CURB RAMP, CONCRETE	300.00	SYS
0037	604-12083	DETECTABLE WARNING SURFACES	54.00	SYS
0038	605-06140	CURB AND GUTTER, CONCRETE	707.00	LFT
0039	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	131402.00	LFT
0040	610-07487	HMA FOR APPROACHES, TYPE B	1060.00	TON
0041	610-09108	PCCP FOR APPROACHES, 9 IN.	42.00	SYS
0042	615-06525	CASTING ADJUST TO GRADE, MONUMENT	28.00	EACH
0043	615-06527	MONUMENT, SECTION CORNER	2.00	EACH
0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0045	621-06567	WATER	1.00	kGAL
0046	621-06575	SODDING, NURSERY	124.00	SYS
0047	628-09402	FIELD OFFICE, B	12.00	MOS
0048	628-11729	CELLULAR TELEPHONE, TYPE A	2.00	EACH
0049	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0050	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0051	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	24.00	MOS
0052	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0053	709-51821	SURFACE SEAL	1.00	LS
0054	709-51821	SURFACE SEAL	1.00	LS
0055	709-51821	SURFACE SEAL	1.00	LS
0056	709-51821	SURFACE SEAL	1.00	LS
0057	710-09158	PATCHING CONCRETE STRUCTURES	20.00	SFT
0058	720-44000	CASTING, ADJUST TO GRADE	8.00	EACH
0059	720-44000	CASTING, ADJUST TO GRADE	14.00	EACH
0060	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	10.00	EACH
0061	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	242.00	SFT
0062	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	665.00	SFT
0063	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	6010.00	SYS
0064	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.00	EACH
0065	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0066	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00	EACH
0067	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	17692.00	LFT
0068	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	150.00	LFT

0069	801-06625	DETOUR ROUTE MARKER ASSEMBLY	64.00	EACH
0070	801-06640	CONSTRUCTION SIGN, A	159.00	EACH
0071	801-06645	CONSTRUCTION SIGN, B	44.00	EACH
0072	801-06710	FLASHING ARROW SIGN	60.00	DAY
0073	801-06775	MAINTAINING TRAFFIC	1.00	LS
0074	801-07118	BARRICADE, III-A	440.00	LFT
0075	801-07119	BARRICADE, III-B	144.00	LFT
0076	801-12042	TRUCK MOUNTED ATTENUATOR	75.00	DAY
0077	802-04314	SIGN	5.00	EACH
0078	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	100.00	LFT
0079	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	8600.00	LFT
0080	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	111030.00	LFT
0081	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	63031.00	LFT
0082	808-06716	LINE, REMOVE	5806.00	LFT
0083	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	5.00	EACH
0084	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0085	808-74815	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 12 IN.	80.00	LFT
0086	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	700.00	LFT
0087	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	150.00	LFT
0088	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	700.00	LFT
0089	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1215.00	EACH

Call: 401

Contract: B -37707-A

Section No.: 1 BRIDGE PAINTING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	202-06541	REMOVE	4.00	EACH
0008	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0009	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0010	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0011	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0012	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0013	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0014	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0015	628-11977	COMPUTER SYSTEM	1.00	EACH
0016	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9617.00	LFT
0017	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	6492.00	LFT
0018	801-06640	CONSTRUCTION SIGN, A	55.00	EACH
0019	801-06710	FLASHING ARROW SIGN	45.00	DAY
0020	801-06775	MAINTAINING TRAFFIC	1.00	LS
0021	801-07118	BARRICADE, III-A	32.00	LFT
0022	801-12042	TRUCK MOUNTED ATTENUATOR	45.00	DAY
0023	801-12348	TEMPORARY WORKSITE SPEED DISPLAY ASSEMBLY	4.00	EACH
0024	801-12388	TEMPORARY PAVEMENT MARKING, REMOVABLE, 9 IN	3708.00	LFT
0025	801-12389	TEMPORARY PAVEMENT MARKING, REMOVABLE, 25 IN	300.00	LFT

Call: 411

Contract: B -37736-A

Section No.: 1 BRIDGE DECK REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	5216.00	SYS
0014	202-02278	CURB, CONCRETE, REMOVE	1621.00	LFT
0015	202-07553	REGULATED MATERIALS, REMOVE, TYPE Y	100.00	CYS
0016	202-07554	REGULATED MATERIALS, TRANSPORT, TYPE Y	100.00	CYS
0017	202-07555	REGULATED MATERIALS, DISPOSE, TYPE Y	100.00	CYS
0018	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0019	202-52710	SIDEWALK CONCRETE, REMOVE	960.00	SYS
0020	202-62420	BRIDGE RAILING, REMOVE	168.00	LFT
0021	203-02000	EXCAVATION, COMMON	1057.00	CYS
0022	205-12108	STORM WATER MANAGEMENT BUDGET	7650.00	DOL
0023	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0024	207-12151	SUBGRADE TREATMENT, TYPE IVA	5230.00	SYS
0025	302-07455	DENSE GRADED SUBBASE	40.00	CYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	874.00	TON
0027	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	1084.00	TON
0028	502-06328	PCCP, 11 IN.	4973.00	SYS
0029	503-05240	D-1 CONTRACTION JOINT	2992.00	LFT
0030	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	104.00	LFT
0031	604-06070	SIDEWALK, CONCRETE	960.00	SYS

0032	605-06090	CURB, INTEGRAL CONCRETE	82.00	LFT
0033	605-06100	CURB, INTEGRAL C CONCRETE	1621.00	LFT
0034	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	243.00	SYS
0035	621-06567	WATER	1.00	kGAL
0036	621-06570	TOPSOIL	10.00	CYS
0037	621-06574	SODDING	91.00	SYS
0038	628-09402	FIELD OFFICE, B	12.00	MOS
0039	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0040	628-11977	COMPUTER SYSTEM	1.00	EACH
0041	702-51863	FIELD DRILLED HOLE IN CONCRETE	54.00	EACH
0042	703-06029	REINFORCING BARS, EPOXY COATED	13346.00	LBS
0043	704-51002	CONCRETE, C, SUPERSTRUCTURE	9.20	CYS
0044	709-51821	SURFACE SEAL	1.00	LS
0045	711-96866	GRID FLOOR, STEEL	4189.00	SFT
0046	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	123.00	LFT
0047	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	1675.00	LFT
0048	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	85.00	SYS
0049	718-52610	AGGREGATE FOR UNDERDRAINS	5.00	CYS
0050	720-44000	CASTING, ADJUST TO GRADE	18.00	EACH
0051	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	450.00	SFT
0052	724-09626	STRUCTURAL EXPANSION JOINT SEAL, SS, REPLACE	136.00	LFT
0053	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	1016.00	SYS
0054	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0055	801-06625	DETOUR ROUTE MARKER ASSEMBLY	29.00	EACH
0056	801-06640	CONSTRUCTION SIGN, A	14.00	EACH
0057	801-06645	CONSTRUCTION SIGN, B	56.00	EACH
0058	801-06775	MAINTAINING TRAFFIC	1.00	LS
0059	801-07118	BARRICADE, III-A	104.00	LFT
0060	801-07119	BARRICADE, III-B	156.00	LFT
0061	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	578.00	LFT
0062	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	46.00	LFT
0063	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2309.00	LFT
0064	808-12032	GROOVING FOR PAVEMENT MARKINGS	2887.00	LFT

Call: 421

Contract: B -37742-A

Section No.: 1 BRIDGE REHABILITATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-01066	HYDRO DEMOLITION	1791.00	SYS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	202-51368	SLOPEWALL, REMOVE	1089.00	SYS
0015	202-51822	BRIDGE DECK OVERLAY, REMOVE	1233.00	SYS
0016	203-02000	EXCAVATION, COMMON	361.00	CYS
0017	205-12108	STORM WATER MANAGEMENT BUDGET	6230.00	DOL
0018	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	644.00	SYS
0020	211-09264	STRUCTURE BACKFILL, TYPE 1	2.00	CYS
0021	303-01180	COMPACTED AGGREGATE NO. 53	180.00	TON
0022	304-07490	HMA PATCHING, TYPE B	47.00	TON
0023	306-08038	MILLING, ASPHALT, 4 IN.	2595.00	SYS
0024	306-08041	MILLING, PCCP	558.00	SYS
0025	306-08043	MILLING, TRANSITION	2454.00	SYS
0026	306-08159	MILLING, ASPHALT	558.00	SYS
0027	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	461.00	TON
0028	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	445.00	TON
0029	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	164.00	TON
0030	401-10258	JOINT ADHESIVE, SURFACE	3680.00	LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	1350.00	LFT

0032	401-11785	LIQUID ASPHALT SEALANT	3680.00	LFT
0033	406-05521	ASPHALT FOR TACK COAT	6440.00	SYS
0034	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	368.00	LFT
0035	601-06035	GUARDRAIL, RESET	236.00	LFT
0036	601-94690	GUARDRAIL, END TREATMENT, MS	1.00	EACH
0037	602-06729	BARRIER, DELINEATOR	48.00	EACH
0038	616-06405	RIPRAP, REVETMENT	110.00	TON
0039	628-09402	FIELD OFFICE, B	12.00	MOS
0040	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0041	703-08247	EMBEDDED GALVANIC ANODE	248.00	EACH
0042	709-51821	SURFACE SEAL	1.00	LS
0043	709-51821	SURFACE SEAL	1.00	LS
0044	710-09158	PATCHING CONCRETE STRUCTURES	261.00	SFT
0045	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	650.00	LFT
0046	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	38.00	LFT
0047	718-06526	HMA FOR UNDERDRAINS	19.00	TON
0048	718-06528	OUTLET PROTECTOR, 1	2.00	EACH
0049	718-52610	AGGREGATE FOR UNDERDRAINS	28.00	CYS
0050	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	584.00	SFT
0051	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1791.00	SYS
0052	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	12.50	CYS
0053	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	322.00	SFT
0054	722-51874	OVERLAY DAM	1052.00	SFT
0055	722-60824	SURFACE MILLING	1233.00	SYS
0056	724-03276	STRUCTURAL EXPANSION JOINT SEALING SYS	222.00	LFT
0057	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	4714.00	SYS
0058	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	5.00	EACH
0059	801-03290	CONSTRUCTION SIGN, C	3.00	EACH
0060	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0061	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	31978.00	LFT
0062	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	5944.00	LFT
0063	801-06625	DETOUR ROUTE MARKER ASSEMBLY	15.00	EACH
0064	801-06640	CONSTRUCTION SIGN, A	134.00	EACH
0065	801-06645	CONSTRUCTION SIGN, B	26.00	EACH
0066	801-06710	FLASHING ARROW SIGN	150.00	DAY
0067	801-06775	MAINTAINING TRAFFIC	1.00	LS
0068	801-07118	BARRICADE, III-A	192.00	LFT

0069	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	460.00	LFT
0070	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1410.00	LFT
0071	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0072	801-12042	TRUCK MOUNTED ATTENUATOR	30.00	DAY
0073	802-04893	REFERENCE POST	2.00	EACH
0074	808-06716	LINE, REMOVE	8526.00	LFT
0075	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1450.00	LFT
0076	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	4886.00	LFT
0077	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	3669.00	LFT
0078	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	1562.00	LFT
0079	808-12032	GROOVING FOR PAVEMENT MARKINGS	3740.00	LFT
0080	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	64.00	EACH
0081	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	41.00	EACH

Call: 431

Contract: B -37766-A

Section No.: 1 REPLACE SUPERSTRUCTURE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	2.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	203-02000	EXCAVATION, COMMON	285.00	CYS
0015	203-02070	BORROW	631.00	CYS
0016	205-11626	PUMP AROUND	1.00	EACH
0017	205-12108	STORM WATER MANAGEMENT BUDGET	7231.00	DOL
0018	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0019	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	32.00	CYS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	587.00	SYS
0021	211-06467	AGGREGATE FOR END BENT BACKFILL	32.00	CYS
0022	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	141.00	SYS
0023	301-12234	COMPACTED AGGREGATE NO 53	78.00	CYS
0024	302-06464	SUBBASE FOR PCCP	50.00	CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	154.00	TON
0026	304-07494	WIDENING WITH HMA, TYPE C	106.00	TON
0027	306-08043	MILLING, TRANSITION	1099.00	SYS
0028	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	138.00	TON
0029	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	233.00	TON
0030	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	104.00	TON
0031	401-10258	JOINT ADHESIVE, SURFACE	1383.00	LFT

0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	180.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	1569.00	LFT
0034	406-05521	ASPHALT FOR TACK COAT	1663.00	SYS
0035	503-05310	TERMINAL JOINT	67.00	LFT
0036	601-02241	GUARDRAIL, REMOVE	230.00	LFT
0037	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	144.00	LFT
0038	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0039	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0040	602-06729	BARRIER, DELINEATOR	2.00	EACH
0041	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	176.00	SYS
0042	615-06490	RIGHT-OF-WAY MARKER	8.00	EACH
0043	615-06505	MONUMENT, B	2.00	EACH
0044	616-05688	RIPRAP, CLASS 1	122.00	TON
0045	616-06405	RIPRAP, REVETMENT	51.00	TON
0046	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	251.00	SYS
0047	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0048	621-02770	EROSION CONTROL BLANKET	800.00	SYS
0049	621-06559	MULCHED SEEDING R	800.00	SYS
0050	621-06567	WATER	1.00	KGAL
0051	621-06574	SODDING	29.00	SYS
0052	622-52436	SIGN, DO NOT MOW OR SPRAY	2.00	EACH
0053	628-09403	FIELD OFFICE, C	12.00	MOS
0054	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0055	702-04325	TEMPORARY SHORING	1.00	LS
0056	702-51005	CONCRETE, A, SUBSTRUCTURE	32.80	CYS
0057	702-51863	FIELD DRILLED HOLE IN CONCRETE	364.00	EACH
0058	703-01540	THREADED TIE BAR ASSEMBLY	16.00	EACH
0059	703-06028	REINFORCING BARS	3616.00	LBS
0060	703-06029	REINFORCING BARS, EPOXY COATED	34428.00	LBS
0061	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	206.00	EACH
0062	704-51002	CONCRETE, C, SUPERSTRUCTURE	98.40	CYS
0063	706-11600	RAILING, CONCRETE FC	6.80	CYS
0064	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0065	709-51821	SURFACE SEAL	1.00	LS
0066	715-05407	PIPE, END BENT DRAIN, 6 IN.	100.00	LFT
0067	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	98.00	SYS
0068	724-12103	PRE-COMPRESSED FOAM JOINT	67.00	LFT

0069	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	1792.00	LFT
0070	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	800.00	LFT
0071	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	48.00	LFT
0072	801-06640	CONSTRUCTION SIGN, A	24.00	EACH
0073	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0074	801-06775	MAINTAINING TRAFFIC	1.00	LS
0075	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	168.00	LFT
0076	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	280.00	LFT
0077	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0078	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	138.00	LFT
0079	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1100.00	LFT
0080	808-06716	LINE, REMOVE	648.00	LFT
0081	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	7.00	EACH
0082	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	7.00	EACH

Call: 441

Contract: B -37782-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-01066	HYDRO DEMOLITION	1536.00	SYS
0013	202-02240	PAVEMENT REMOVAL	1300.80	SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0017	202-51368	SLOPEWALL, REMOVE	28.60	SYS
0018	202-51822	BRIDGE DECK OVERLAY, REMOVE	1536.00	SYS
0019	202-93741	GUARDRAIL, END TREATMENT, REMOVE	3.00	EACH
0020	202-96133	PIPE, REMOVE	140.00	LFT
0021	203-02000	EXCAVATION, COMMON	785.00	CYS
0022	203-02070	BORROW	895.00	CYS
0023	203-08607	LINEAR GRADING	264.00	LFT
0024	203-51223	EXCAVATION, WATERWAY	705.00	CYS
0025	205-12108	STORM WATER MANAGEMENT BUDGET	60889.50	DOL
0026	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0027	206-51220	EXCAVATION, WET	214.00	CYS
0028	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	247.00	CYS
0029	206-51235	COFFERDAM	1.00	LS
0030	206-51235	COFFERDAM	1.00	LS
0031	207-08264	SUBGRADE TREATMENT, TYPE II	142.00	SYS

0032	207-09935	SUBGRADE TREATMENT, TYPE IC	3424.00	SYS
0033	211-06467	AGGREGATE FOR END BENT BACKFILL	121.40	CYS
0034	211-09264	STRUCTURE BACKFILL, TYPE 1	8.00	CYS
0035	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	4.00	CYS
0036	213-09270	FLOWABLE BACKFILL, REMOVABLE	10.00	CYS
0037	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	953.00	SYS
0038	301-12232	COMPACTED AGGREGATE NO 5	105.00	CYS
0039	301-12234	COMPACTED AGGREGATE NO 53	77.00	CYS
0040	302-07455	DENSE GRADED SUBBASE	111.00	CYS
0041	303-01180	COMPACTED AGGREGATE NO. 53	293.00	TON
0042	303-07449	COMPACTED AGGREGATE NO. 73	20.00	TON
0043	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1090.00	SYS
0044	306-08043	MILLING, TRANSITION	525.00	SYS
0045	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	30.00	TON
0046	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	310.00	TON
0047	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	435.00	TON
0048	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1092.00	TON
0049	401-10258	JOINT ADHESIVE, SURFACE	2790.00	LFT
0050	401-10259	JOINT ADHESIVE, INTERMEDIATE	2509.00	LFT
0051	401-11785	LIQUID ASPHALT SEALANT	2790.00	LFT
0052	402-10086	HMA FOR TEMPORARY PAVEMENT, C	192.00	TON
0053	406-05521	ASPHALT FOR TACK COAT	3712.30	SYS
0054	503-05310	TERMINAL JOINT	55.00	LFT
0055	601-01701	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 2	1.00	EACH
0056	601-02241	GUARDRAIL, REMOVE	600.00	LFT
0057	601-06035	GUARDRAIL, RESET	395.00	LFT
0058	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	337.50	LFT
0059	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	2.00	EACH
0060	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0061	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0062	602-06729	BARRIER, DELINEATOR	45.00	EACH
0063	606-07484	MILLED HMA CORRUGATIONS	1403.00	LFT
0064	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	540.40	SYS
0065	610-07487	HMA FOR APPROACHES, TYPE B	42.00	TON
0066	611-06497	MAILBOX ASSEMBLY, SINGLE	3.00	EACH
0067	615-06490	RIGHT-OF-WAY MARKER	8.00	EACH
0068	615-06505	MONUMENT, B	3.00	EACH

0069	615-06530	BENCH MARK POST	1.00	EACH
0070	616-05689	RIPRAP, CLASS 2	1015.00	TON
0071	616-06405	RIPRAP, REVETMENT	525.00	TON
0072	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1681.00	SYS
0073	616-51367	SLOPEWALL, CONCRETE, 4 IN.	28.60	SYS
0074	619-11049	CLEAN STEEL BRIDGE, PARTIAL, QP-1 BRIDGE NO.	1.00	LS
0075	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0076	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0077	621-02770	EROSION CONTROL BLANKET	672.00	SYS
0078	621-06545	FERTILIZER	0.20	TON
0079	621-06553	SEED MIXTURE R	29.00	LBS
0080	621-06553	SEED MIXTURE R	7.00	LBS
0081	621-06559	MULCHED SEEDING R	15.00	SYS
0082	621-06565	MULCHING MATERIAL	1.00	TON
0083	621-06567	WATER	21.00	KGAL
0084	621-06574	SODDING	381.00	SYS
0085	621-06575	SODDING, NURSERY	1500.00	SYS
0086	621-06626	MULCHED SEEDING D	270.00	SYS
0087	628-09402	FIELD OFFICE, B	24.00	MOS
0088	628-11729	CELLULAR TELEPHONE, TYPE A	2.00	EACH
0089	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0090	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0091	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	48.00	MOS
0092	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0093	701-02936	PILE, STEEL H, HP 14 X 89	732.00	LFT
0094	701-09558	TEST PILE, INDICATOR, PRODUCTION	322.00	LFT
0095	701-09560	TEST PILE, INDICATOR, RESTRIKE	4.00	EACH
0096	701-09684	PILE SHOE, HP 14 X 89	14.00	EACH
0097	701-09891	PILE SHOE, HP 12 X 84	12.00	EACH
0098	701-95782	PILE, STEEL H, HP, 12 X 84	800.00	LFT
0099	702-04325	TEMPORARY SHORING	1.00	LS
0100	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	4.00	EACH
0101	702-51005	CONCRETE, A, SUBSTRUCTURE	186.60	CYS
0102	702-51015	CONCRETE, B, FOOTINGS	12.20	CYS
0103	702-51863	FIELD DRILLED HOLE IN CONCRETE	250.00	EACH
0104	702-90915	CONCRETE, CLASS, A	3.00	CYS
0105	702-92857	CONCRETE, C, SUBSTRUCTURE	53.20	CYS

0106	703-01540	THREADED TIE BAR ASSEMBLY	128.00	EACH
0107	703-06028	REINFORCING BARS	18934.00	LBS
0108	703-06029	REINFORCING BARS, EPOXY COATED	121958.00	LBS
0109	703-08247	EMBEDDED GALVANIC ANODE	215.00	EACH
0110	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	801.00	EACH
0111	704-51002	CONCRETE, C, SUPERSTRUCTURE	268.70	CYS
0112	706-09960	RAILING, CONCRETE FC	283.00	LFT
0113	706-09960	RAILING, CONCRETE FC	60.00	LFT
0114	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00	EACH
0115	709-51821	SURFACE SEAL	1.00	LS
0116	709-51821	SURFACE SEAL	1.00	LS
0117	710-51870	REPOINTING MASONRY IN. STRUCTURES	1052.00	SFT
0118	711-51038	STRUCTURAL STEEL	1.00	LS
0119	711-51864	DRILLED HOLE	54.00	EACH
0120	711-95291	JACKING AND SUPPORTING, STEEL BEAMS	1.00	LS
0121	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	1100.00	LFT
0122	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	96.00	LFT
0123	715-05407	PIPE, END BENT DRAIN, 6 IN.	310.00	LFT
0124	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	4.00	EACH
0125	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0126	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	99.00	SYS
0127	718-12309	GEOTEXTILE FOR UNDERDRAIN, TYPE 3	775.00	SYS
0128	718-52610	AGGREGATE FOR UNDERDRAINS	90.00	CYS
0129	720-45075	INLET, R13	2.00	EACH
0130	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	230.00	SFT
0131	722-51874	OVERLAY DAM	64.00	SFT
0132	722-60824	SURFACE MILLING	1536.00	SYS
0133	726-92406	BEARING ASSEMBLY ELASTOMERIC	18.00	EACH
0134	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0135	801-04308	ROAD CLOSURE SIGN ASSEMBLY	17.00	EACH
0136	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	10133.00	LFT
0137	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	26.00	LFT
0138	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00	LS
0139	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0140	801-06625	DETOUR ROUTE MARKER ASSEMBLY	29.00	EACH
0141	801-06640	CONSTRUCTION SIGN, A	70.00	EACH
0142	801-06645	CONSTRUCTION SIGN, B	32.00	EACH

0143	801-06775	MAINTAINING TRAFFIC	1.00	LS
0144	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	EACH
0145	801-07118	BARRICADE, III-A	84.00	LFT
0146	801-07119	BARRICADE, III-B	110.00	LFT
0147	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1460.00	LFT
0148	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0149	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0150	801-97643	TEMPORARY BUZZ STRIPS	864.00	LFT
0151	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1750.00	LFT
0152	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1970.00	LFT
0153	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1970.00	LFT
0154	808-06716	LINE, REMOVE	5499.00	LFT
0155	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	550.00	LFT
0156	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	604.00	LFT
0157	808-12032	GROOVING FOR PAVEMENT MARKINGS	3446.00	LFT
0158	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1696.00	LFT
0159	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	34.00	EACH
0160	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	39.00	EACH

Call: 441

Contract: B -37782-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0161	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1678.00	SYS
0162	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	14.60	CYS

Call: 441

Contract: B -37782-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME

Line

Item No	Item Code	Description	Quantity	Unit
0163	722-96912	BRIDGE DECK OVERLAY, ADDITIONAL, SILICA FUME MODIFIED	14.60	CYS
0164	736-01061	BRIDGE DECK OVERLAY MICROSILICA	1678.00	SYS

Call: 451

Contract: B -37789-A

Section No.: 1 BRIDGE DECK REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-01066	HYDRO DEMOLITION	1275.00	SYS
0013	202-02240	PAVEMENT REMOVAL	266.00	SYS
0014	202-04435	DELINEATOR POST, REMOVE	4.00	EACH
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	202-51822	BRIDGE DECK OVERLAY, REMOVE	1275.00	SYS
0018	203-02000	EXCAVATION, COMMON	101.00	CYS
0019	203-02070	BORROW	47.00	CYS
0020	203-08607	LINEAR GRADING	410.00	LFT
0021	205-12108	STORM WATER MANAGEMENT BUDGET	36880.00	DOL
0022	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	74.00	SYS
0024	211-06467	AGGREGATE FOR END BENT BACKFILL	12.00	CYS
0025	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	80.00	SYS
0026	301-12234	COMPACTED AGGREGATE NO 53	64.00	CYS
0027	302-07455	DENSE GRADED SUBBASE	48.00	CYS
0028	304-07490	HMA PATCHING, TYPE B	22.00	TON
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	68.00	SYS
0030	306-08043	MILLING, TRANSITION	139.00	SYS
0031	306-11872	MILLING, PROFILE	568.00	SYS

0032	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	12.00	TON
0033	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	61.00	TON
0034	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	6.00	TON
0035	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	16.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	383.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	40.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	383.00	LFT
0039	406-05521	ASPHALT FOR TACK COAT	928.00	SYS
0040	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	3.00	EACH
0041	601-01625	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 1	1.00	EACH
0042	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	1.00	EACH
0043	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0044	601-02241	GUARDRAIL, REMOVE	504.00	LFT
0045	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	119.25	LFT
0046	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	2.00	EACH
0047	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	5.00	EACH
0048	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0049	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	44.00	LFT
0050	602-06729	BARRIER, DELINEATOR	10.00	EACH
0051	605-06120	CURB, CONCRETE	7.00	LFT
0052	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	302.00	SYS
0053	616-06405	RIPRAP, REVETMENT	260.00	TON
0054	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	408.00	SYS
0055	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0056	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0057	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0058	621-02770	EROSION CONTROL BLANKET	488.00	SYS
0059	621-06545	FERTILIZER	1.00	TON
0060	621-06553	SEED MIXTURE R	24.00	LBS
0061	621-06559	MULCHED SEEDING R	353.00	SYS
0062	621-06565	MULCHING MATERIAL	0.40	TON
0063	621-06567	WATER	4.00	kGAL
0064	621-06574	SODDING	52.00	SYS
0065	628-09402	FIELD OFFICE, B	14.00	MOS
0066	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0067	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0068	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL

0069	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0070	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	28.00	MOS
0071	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0072	628-11977	COMPUTER SYSTEM	1.00	EACH
0073	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	18.00	EACH
0074	702-51863	FIELD DRILLED HOLE IN CONCRETE	1052.00	EACH
0075	702-92857	CONCRETE, C, SUBSTRUCTURE	26.50	CYS
0076	703-06029	REINFORCING BARS, EPOXY COATED	87059.00	LBS
0077	703-08247	EMBEDDED GALVANIC ANODE	214.00	EACH
0078	704-51002	CONCRETE, C, SUPERSTRUCTURE	140.00	CYS
0079	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	3.00	EACH
0080	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	5.00	EACH
0081	706-09962	RAILING, CONCRETE PF-1	718.00	LFT
0082	706-09962	RAILING, CONCRETE PF-1	257.00	LFT
0083	706-11404	RAILING, STEEL PF-1	1010.20	LFT
0084	707-11715	STRUCTURAL MEMBERS	144.00	LFT
0085	709-12077	FIBER WRAP CONCRETE CASING SYSTEM	796.00	SFT
0086	709-51821	SURFACE SEAL	1.00	LS
0087	709-51821	SURFACE SEAL	1.00	LS
0088	710-09158	PATCHING CONCRETE STRUCTURES	312.00	SFT
0089	711-05728	REPAIR	4.00	EACH
0090	711-05728	REPAIR	16.00	EACH
0091	711-05728	REPAIR	2.00	EACH
0092	711-05728	REPAIR	2.00	EACH
0093	711-05728	REPAIR	33.00	EACH
0094	711-05728	REPAIR	7.00	EACH
0095	711-05728	REPAIR	2.00	EACH
0096	711-05728	REPAIR	12.00	EACH
0097	711-05728	REPAIR	18.00	EACH
0098	711-05728	REPAIR	16.00	EACH
0099	711-51035	STRUCTURAL STEEL	33734.00	LBS
0100	711-51864	DRILLED HOLE	1356.00	EACH
0101	711-51866	RIVET, REMOVE	3735.00	EACH
0102	711-96800	STUD SHEAR CONNECTORS	2016.00	EACH
0103	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	22.00	EACH
0104	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0105	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	345.00	SFT

0106	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	10.40	CYS
0107	722-51874	OVERLAY DAM	212.00	SFT
0108	722-60824	SURFACE MILLING	1275.00	SYS
0109	724-12157	PREFORMED SILICONE JOINT	206.00	LFT
0110	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00	EACH
0111	801-06625	DETOUR ROUTE MARKER ASSEMBLY	56.00	EACH
0112	801-06640	CONSTRUCTION SIGN, A	41.00	EACH
0113	801-06645	CONSTRUCTION SIGN, B	7.00	EACH
0114	801-06775	MAINTAINING TRAFFIC	1.00	LS
0115	801-07118	BARRICADE, III-A	140.00	LFT
0116	801-07119	BARRICADE, III-B	250.00	LFT
0117	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	90.00	LFT
0118	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	39.00	SFT
0119	804-76350	DELINEATOR WITH POST, D3	22.00	EACH
0120	805-02383	CONDUIT, STEEL, GALVANIZED, 2.5 IN.	1642.00	LFT
0121	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	350.00	LFT
0122	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1576.00	LFT
0123	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	876.00	LFT

Call: 451

Contract: B -37789-A

Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0124	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1406.00	SYS

Call: 451

Contract: B -37789-A

Section No.: 3 MICROSILICA CONCRETE OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0125	736-01061	BRIDGE DECK OVERLAY MICROSILICA	1406.00	SYS

Call: 461

Contract: B -37791-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-01066	HYDRO DEMOLITION	18160.00	SYS
0014	202-02240	PAVEMENT REMOVAL	600.00	SYS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	203-02000	EXCAVATION, COMMON	570.00	CYS
0018	203-02070	BORROW	4950.00	CYS
0019	203-08607	LINEAR GRADING	375.00	LFT
0020	205-12108	STORM WATER MANAGEMENT BUDGET	35000.00	DOL
0021	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0022	206-51235	COFFERDAM	1.00	LS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	7135.00	SYS
0024	214-12236	GEOTEXTILE FOR PAVEMENT TYPE 1A	180.00	SYS
0025	301-12232	COMPACTED AGGREGATE NO 5	60.00	CYS
0026	301-12234	COMPACTED AGGREGATE NO 53	570.00	CYS
0027	302-07455	DENSE GRADED SUBBASE	104.00	CYS
0028	303-01180	COMPACTED AGGREGATE NO. 53	295.00	TON
0029	306-08033	MILLING, ASPHALT, 1 IN.	130.00	SYS
0030	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	145.00	TON
0031	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	208.00	TON

0032	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	436.00	TON
0033	401-10258	JOINT ADHESIVE, SURFACE	3350.00	LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	3190.00	LFT
0035	401-11785	LIQUID ASPHALT SEALANT	3350.00	LFT
0036	402-10087	HMA FOR TEMPORARY PAVEMENT, D	2680.00	TON
0037	406-05521	ASPHALT FOR TACK COAT	4640.00	SYS
0038	501-06323	QC/QA-PCCP, 12 IN.	215.00	SYS
0039	503-05240	D-1 CONTRACTION JOINT	144.00	LFT
0040	503-05310	TERMINAL JOINT	72.00	LFT
0041	601-02205	TEMPORARY GUARDRAIL TRANSITION, TGB	2.00	EACH
0042	601-02241	GUARDRAIL, REMOVE	325.00	LFT
0043	601-06035	GUARDRAIL, RESET	307.00	LFT
0044	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	275.00	LFT
0045	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	1.00	EACH
0046	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0047	601-97080	TEMPORARY GUARDRAIL END TREATMENT, OS	2.00	EACH
0048	602-06729	BARRIER, DELINEATOR	216.00	EACH
0049	606-07484	MILLED HMA CORRUGATIONS	3320.00	LFT
0050	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	386.00	SYS
0051	616-05688	RIPRAP, CLASS 1	1635.00	TON
0052	616-06405	RIPRAP, REVETMENT	155.00	TON
0053	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	1615.00	SYS
0054	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0055	621-06559	MULCHED SEEDING R	6800.00	SYS
0056	628-09402	FIELD OFFICE, B	15.00	MOS
0057	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0058	702-51863	FIELD DRILLED HOLE IN CONCRETE	228.00	EACH
0059	703-06029	REINFORCING BARS, EPOXY COATED	30272.00	LBS
0060	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	8.00	EACH
0061	709-51821	SURFACE SEAL	1.00	LS
0062	709-51821	SURFACE SEAL	1.00	LS
0063	710-09158	PATCHING CONCRETE STRUCTURES	40.00	SFT
0064	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	3280.00	SFT
0065	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	18355.00	SYS
0066	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	102.00	CYS
0067	722-60824	SURFACE MILLING	36300.00	SYS
0068	724-09626	STRUCTURAL EXPANSION JOINT SEAL, SS, REPLACE	170.00	LFT

0069	724-09627	STRUCTURAL EXPANSION JOINT SEAL, M, REPLACE	170.00	LFT
0070	801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.00	EACH
0071	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	16980.00	LFT
0072	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	2016.00	LFT
0073	801-06586	TEMPORARY PAVEMENT MARKING, 8 IN.	3132.00	LFT
0074	801-06640	CONSTRUCTION SIGN, A	55.00	EACH
0075	801-06645	CONSTRUCTION SIGN, B	3.00	EACH
0076	801-06710	FLASHING ARROW SIGN	360.00	DAY
0077	801-06775	MAINTAINING TRAFFIC	1.00	LS
0078	801-07118	BARRICADE, III-A	72.00	LFT
0079	801-07119	BARRICADE, III-B	72.00	LFT
0080	801-07606	TEMPORARY CROSSOVER DRAINAGE PIPE	1050.00	LFT
0081	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0082	801-52817	TEMPORARY CROSSOVER, B	2.00	EACH
0083	808-06716	LINE, REMOVE	2227.00	LFT
0084	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1755.00	LFT
0085	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	4400.00	LFT
0086	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	5972.00	LFT
0087	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	60.00	EACH
0088	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	60.00	EACH

Call: 471

Contract: B -38039-A

Section No.: 1 BRIDGE REHABILITATION OR REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	534.00	SYS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0013	203-02000	EXCAVATION, COMMON	147.00	CYS
0014	205-12108	STORM WATER MANAGEMENT BUDGET	1.00	DOL
0015	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0016	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	173.00	CYS
0017	207-09935	SUBGRADE TREATMENT, TYPE IC	367.00	SYS
0018	211-06467	AGGREGATE FOR END BENT BACKFILL	131.00	CYS
0019	302-07455	DENSE GRADED SUBBASE	101.00	CYS
0020	303-01180	COMPACTED AGGREGATE NO. 53	145.00	TON
0021	304-07493	WIDENING WITH HMA, TYPE B	141.00	TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1713.00	SYS
0023	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	140.00	TON
0024	401-10258	JOINT ADHESIVE, SURFACE	1118.00	LFT
0025	401-11785	LIQUID ASPHALT SEALANT	1118.00	LFT
0026	406-05521	ASPHALT FOR TACK COAT	2209.00	SYS
0027	503-03489	RETROFITTED TIE BARS	72.00	EACH
0028	503-05310	TERMINAL JOINT	80.00	LFT
0029	506-06333	PCCP PATCHING, FULL DEPTH	52.00	SYS
0030	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	4.00	EACH
0031	601-01839	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 6	1.00	EACH

0032	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0033	601-02241	GUARDRAIL, REMOVE	769.00	LFT
0034	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0035	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	1594.00	LFT
0036	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	578.00	SYS
0037	616-06405	RIPRAP, REVETMENT	444.00	TON
0038	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	592.00	SYS
0039	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0040	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0042	621-06560	MULCHED SEEDING U	1180.00	SYS
0043	628-09402	FIELD OFFICE, B	12.00	MOS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0045	628-11977	COMPUTER SYSTEM	1.00	EACH
0046	702-04325	TEMPORARY SHORING	1.00	LS
0047	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	14.00	EACH
0048	702-51005	CONCRETE, A, SUBSTRUCTURE	166.20	CYS
0049	702-51863	FIELD DRILLED HOLE IN CONCRETE	1376.00	EACH
0050	702-92857	CONCRETE, C, SUBSTRUCTURE	32.50	CYS
0051	703-06028	REINFORCING BARS	45199.00	LBS
0052	703-06029	REINFORCING BARS, EPOXY COATED	253004.00	LBS
0053	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	182.00	EACH
0054	704-51002	CONCRETE, C, SUPERSTRUCTURE	895.00	CYS
0055	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TPS-1	4.00	EACH
0056	706-11418	RAILING, STEEL PS-1	710.00	LFT
0057	706-11455	BRIDGE RAILING PEDESTRIAN FENCE	692.00	LFT
0058	706-11604	RAILING, CONCRETE PS-1	61.40	CYS
0059	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0060	709-51821	SURFACE SEAL	1.00	LS
0061	710-09158	PATCHING CONCRETE STRUCTURES	59.00	SFT
0062	711-51035	STRUCTURAL STEEL	18590.00	LBS
0063	711-51864	DRILLED HOLE	600.00	EACH
0064	711-51866	RIVET, REMOVE	150.00	EACH
0065	711-95291	JACKING AND SUPPORTING, STEEL BEAMS	1.00	LS
0066	711-96479	BOLT, REMOVE	50.00	EACH
0067	711-96800	STUD SHEAR CONNECTORS	8235.00	EACH
0068	715-05407	PIPE, END BENT DRAIN, 6 IN.	306.00	LFT

0069	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0070	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	305.00	SYS
0071	726-92406	BEARING ASSEMBLY ELASTOMERIC	90.00	EACH
0072	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0073	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	19612.00	LFT
0074	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	2.00	EACH
0075	801-06640	CONSTRUCTION SIGN, A	20.00	EACH
0076	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0077	801-06710	FLASHING ARROW SIGN	360.00	DAY
0078	801-06775	MAINTAINING TRAFFIC	1.00	LS
0079	801-07119	BARRICADE, III-B	48.00	LFT
0080	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	966.00	LFT
0081	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	438.00	LFT
0082	808-06716	LINE, REMOVE	7936.00	LFT
0083	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1383.00	LFT
0084	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	3835.00	LFT
0085	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	6414.00	LFT

Call: 481

Contract: B -38381-A

Section No.: 1 BRIDGE MAINTENANCE AND REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	202-93741	GUARDRAIL, END TREATMENT, REMOVE	3.00	EACH
0008	601-02241	GUARDRAIL, REMOVE	250.00	LFT
0009	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00	EACH
0010	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0011	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0012	628-09403	FIELD OFFICE, C	5.00	MOS
0013	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0014	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0015	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0016	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	250.00	LFT
0017	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00	EACH
0018	801-06640	CONSTRUCTION SIGN, A	8.00	EACH
0019	801-06775	MAINTAINING TRAFFIC	1.00	LS
0020	801-07118	BARRICADE, III-A	72.00	LFT
0021	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	1.00	EACH

Call: 491

Contract: B -38569-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-01066	HYDRO DEMOLITION	1182.00	SYS
0012	202-02240	PAVEMENT REMOVAL	493.00	SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-51822	BRIDGE DECK OVERLAY, REMOVE	1182.00	SYS
0016	203-02000	EXCAVATION, COMMON	2083.00	CYS
0017	206-51225	EXCAVATION, DRY	36.00	CYS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	3152.00	SYS
0019	211-02050	B BORROW	1360.00	CYS
0020	211-06467	AGGREGATE FOR END BENT BACKFILL	36.00	CYS
0021	302-07455	DENSE GRADED SUBBASE	121.00	CYS
0022	303-01180	COMPACTED AGGREGATE NO. 53	574.00	TON
0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	320.00	SYS
0024	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	271.00	TON
0025	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	407.00	TON
0026	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	1365.00	TON
0027	401-10258	JOINT ADHESIVE, SURFACE	2642.00	LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	2642.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	5284.00	LFT
0030	406-05521	ASPHALT FOR TACK COAT	6058.00	SYS
0031	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	6.00	EACH

0032	601-02241	GUARDRAIL, REMOVE	150.00	LFT
0033	602-06729	BARRIER, DELINEATOR	20.00	EACH
0034	606-07484	MILLED HMA CORRUGATIONS	2582.00	LFT
0035	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	726.00	SYS
0036	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0037	621-06559	MULCHED SEEDING R	574.00	SYS
0038	628-09403	FIELD OFFICE, C	12.00	MOS
0039	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0040	702-51863	FIELD DRILLED HOLE IN CONCRETE	1600.00	EACH
0041	702-92857	CONCRETE, C, SUBSTRUCTURE	30.80	CYS
0042	703-06029	REINFORCING BARS, EPOXY COATED	82714.00	LBS
0043	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	452.00	EACH
0044	704-51002	CONCRETE, C, SUPERSTRUCTURE	41.20	CYS
0045	706-11601	RAILING, CONCRETE FT	79.60	CYS
0046	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	8.00	EACH
0047	709-51821	SURFACE SEAL	1.00	LS
0048	709-51821	SURFACE SEAL	1.00	LS
0049	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	2582.00	LFT
0050	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	272.00	LFT
0051	715-05146	PIPE, TYPE 2, CIRCULAR, 6 IN.	80.00	LFT
0052	718-06526	HMA FOR UNDERDRAINS	129.00	TON
0053	718-06528	OUTLET PROTECTOR, 1	8.00	EACH
0054	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	1913.00	SYS
0055	718-52610	AGGREGATE FOR UNDERDRAINS	236.00	CYS
0056	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	798.00	SFT
0057	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	19.00	CYS
0058	722-60824	SURFACE MILLING	1182.00	SYS
0059	724-51925	STRUCTURAL EXPANSION JOINT, SS	236.00	LFT
0060	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	15860.00	LFT
0061	801-06640	CONSTRUCTION SIGN, A	54.00	EACH
0062	801-06645	CONSTRUCTION SIGN, B	18.00	EACH
0063	801-06710	FLASHING ARROW SIGN	180.00	DAY
0064	801-06775	MAINTAINING TRAFFIC	1.00	LS
0065	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	3420.00	LFT
0066	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	580.00	LFT
0067	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	1.00	EACH
0068	801-12417	PORTABLE TRAFFIC SENSOR	4.00	EACH

0069	808-06716	LINE, REMOVE	2000.00	LFT
0070	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	3062.00	LFT
0071	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	480.00	LFT
0072	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	2000.00	LFT
0073	808-12032	GROOVING FOR PAVEMENT MARKINGS	4502.00	LFT

Call: 491
Contract: B -38569-A
Section No.: 2
BRIDGE DECK OVERLAY LATEX MODIFIED

Line			Quantity Unit	
Item No	Item Code	Description		
0074	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1182.00	SYS

Call: 491
Contract: B -38569-A
Section No.: 3
BRIDGE DECK OVERLAY MICROSILICA

Line			Quantity Unit	
Item No	Item Code	Description		
0075	736-01061	BRIDGE DECK OVERLAY MICROSILICA	1182.00	SYS

Call: 501

Contract: B -38702-C

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	202-01066	HYDRO DEMOLITION	1528.00	SYS
0011	202-02240	PAVEMENT REMOVAL	2553.00	SYS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	203-02000	EXCAVATION, COMMON	1150.00	CYS
0015	203-08607	LINEAR GRADING	100.00	LFT
0016	205-12108	STORM WATER MANAGEMENT BUDGET	13704.00	DOL
0017	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	2853.00	SYS
0019	211-06467	AGGREGATE FOR END BENT BACKFILL	60.00	CYS
0020	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	8.00	CYS
0021	302-06464	SUBBASE FOR PCCP	714.00	CYS
0022	302-07455	DENSE GRADED SUBBASE	80.00	CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	170.00	TON
0024	502-06331	PCCP, 14 IN.	2639.00	SYS
0025	503-03489	RETROFITTED TIE BARS	144.00	EACH
0026	503-05240	D-1 CONTRACTION JOINT	1385.00	LFT
0027	503-05310	TERMINAL JOINT	204.00	LFT
0028	601-02241	GUARDRAIL, REMOVE	204.00	LFT
0029	601-06035	GUARDRAIL, RESET	616.00	LFT
0030	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	6.00	EACH
0031	602-06729	BARRIER, DELINEATOR	24.00	EACH

0032	603-06060	FENCE, FARM FIELD, RESET	64.00	LFT
0033	606-11064	MILLED PCCP CORRUGATIONS	960.00	LFT
0034	609-06262	REINFORCED CONCRETE BRIDGE APPROACH, 14 IN.	480.00	SYS
0035	616-06451	RIPRAP, UNIFORM	8.00	TON
0036	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	220.00	SYS
0037	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0038	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0039	621-02770	EROSION CONTROL BLANKET	124.00	SYS
0040	621-06559	MULCHED SEEDING R	1570.00	SYS
0041	628-09402	FIELD OFFICE, B	9.00	MOS
0042	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0043	628-11977	COMPUTER SYSTEM	1.00	EACH
0044	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	8.00	EACH
0045	703-06029	REINFORCING BARS, EPOXY COATED	53400.00	LBS
0046	703-08247	EMBEDDED GALVANIC ANODE	112.00	EACH
0047	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	396.00	EACH
0048	704-51002	CONCRETE, C, SUPERSTRUCTURE	80.00	CYS
0049	706-11601	RAILING, CONCRETE FT	7.20	CYS
0050	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	8.00	EACH
0051	709-51821	SURFACE SEAL	1.00	LS
0052	709-51821	SURFACE SEAL	1.00	LS
0053	709-51821	SURFACE SEAL	1.00	LS
0054	710-09158	PATCHING CONCRETE STRUCTURES	150.00	SFT
0055	711-11599	REPAIR WELD	40.00	IN
0056	711-51038	STRUCTURAL STEEL	1.00	LS
0057	711-51864	DRILLED HOLE	280.00	EACH
0058	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS
0059	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS
0060	715-05217	PIPE, TYPE 5, CIRCULAR, 12 IN.	224.00	LFT
0061	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0062	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0063	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	4.00	EACH
0064	715-46000	PIPE END SECTION, DIAMETER 12 IN.	4.00	EACH
0065	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	100.00	SFT
0066	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	12.80	CYS
0067	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1147.00	SFT
0068	722-60824	SURFACE MILLING	1528.00	SYS

0069	724-12103	PRE-COMPRESSED FOAM JOINT	83.00	LFT
0070	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0071	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	EACH
0072	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	13805.00	LFT
0073	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00	EACH
0074	801-06640	CONSTRUCTION SIGN, A	95.00	EACH
0075	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0076	801-06710	FLASHING ARROW SIGN	200.00	DAY
0077	801-06775	MAINTAINING TRAFFIC	1.00	LS
0078	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00	EACH
0079	801-07118	BARRICADE, III-A	72.00	LFT
0080	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1040.00	LFT
0081	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1300.00	LFT
0082	801-12042	TRUCK MOUNTED ATTENUATOR	20.00	DAY
0083	805-02383	CONDUIT, STEEL, GALVANIZED, 2.5 IN.	96.00	LFT
0084	808-06716	LINE, REMOVE	1143.00	LFT
0085	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1180.00	LFT
0086	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	874.00	LFT
0087	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	669.00	LFT
0088	808-10038	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE WHITE 24 IN.	15.00	LFT
0089	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	218.00	LFT
0090	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	526.00	LFT
0091	808-12032	GROOVING FOR PAVEMENT MARKINGS	2517.00	LFT
0092	808-75994	PRISMATIC REFLECTOR	31.00	EACH
0093	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	20.00	EACH
0094	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	16.00	EACH

Call: 501

Contract: B -38702-C

Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0095	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1680.00	SYS

Call: 501
Contract: B -38702-C
Section No.: 3 MICROSILICA CONCRETE OVERLAY

Line			Quantity Unit	
Item No	Item Code	Description		
0096	736-01061	BRIDGE DECK OVERLAY MICROSILICA	1680.00	SYS

Call: 511

Contract: B -39237-A

Section No.: 1 BRIDGE PAINTING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0009	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0010	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0011	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0012	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0013	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0014	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0015	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0016	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0017	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0018	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0019	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0020	628-09403	FIELD OFFICE, C	12.00	MOS
0021	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0022	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	90.00	EACH
0023	801-06640	CONSTRUCTION SIGN, A	52.00	EACH
0024	801-06710	FLASHING ARROW SIGN	240.00	DAY
0025	801-06775	MAINTAINING TRAFFIC	1.00	LS
0026	801-12042	TRUCK MOUNTED ATTENUATOR	180.00	DAY

Call: 521

Contract: B -39247-A

Section No.: 1

SUBSTRUCTURE REPAIR AND REHABILITATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	205-11626	PUMP AROUND	2.00	EACH
0008	205-12108	STORM WATER MANAGEMENT BUDGET	6300.00	DOL
0009	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0010	206-51220	EXCAVATION, WET	16.00	CYS
0011	206-51235	COFFERDAM	1.00	LS
0012	701-93790	CLEAN AND EPOXY COAT EXISTING PILES	1.00	LS
0013	801-06640	CONSTRUCTION SIGN, A	8.00	EACH
0014	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 531

Contract: B -39317-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	202-01066	HYDRO DEMOLITION	1638.00	SYS
0012	202-02240	PAVEMENT REMOVAL	305.00	SYS
0013	202-02272	PAVED SIDE DITCH, REMOVE	60.00	LFT
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-51822	BRIDGE DECK OVERLAY, REMOVE	1638.00	SYS
0016	202-93741	GUARDRAIL, END TREATMENT, REMOVE	3.00	EACH
0017	205-12108	STORM WATER MANAGEMENT BUDGET	6000.00	DOL
0018	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0019	302-06464	SUBBASE FOR PCCP	32.00	CYS
0020	302-07455	DENSE GRADED SUBBASE	30.00	CYS
0021	304-07490	HMA PATCHING, TYPE B	10.00	TON
0022	306-08043	MILLING, TRANSITION	480.00	SYS
0023	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	40.00	TON
0024	401-10258	JOINT ADHESIVE, SURFACE	360.00	LFT
0025	401-11785	LIQUID ASPHALT SEALANT	360.00	LFT
0026	406-05521	ASPHALT FOR TACK COAT	480.00	SYS
0027	501-06322	QC/QA-PCCP, 11 IN.	125.00	SYS
0028	503-05310	TERMINAL JOINT	56.00	LFT
0029	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0030	601-02241	GUARDRAIL, REMOVE	1049.00	LFT
0031	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	851.00	LFT

0032	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0033	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0034	602-06729	BARRIER, DELINEATOR	24.00	EACH
0035	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	178.00	SYS
0036	616-06405	RIPRAP, REVETMENT	840.00	TON
0037	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	970.00	SYS
0038	628-09402	FIELD OFFICE, B	9.00	MOS
0039	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0040	703-06029	REINFORCING BARS, EPOXY COATED	61583.00	LBS
0041	704-51002	CONCRETE, C, SUPERSTRUCTURE	121.10	CYS
0042	706-09960	RAILING, CONCRETE FC	869.00	LFT
0043	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0044	709-51821	SURFACE SEAL	1.00	LS
0045	710-09158	PATCHING CONCRETE STRUCTURES	87.00	SFT
0046	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0047	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	782.00	SFT
0048	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1761.00	SYS
0049	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	20.00	CYS
0050	724-51925	STRUCTURAL EXPANSION JOINT, SS	80.00	LFT
0051	801-03290	CONSTRUCTION SIGN, C	3.00	EACH
0052	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0053	801-06625	DETOUR ROUTE MARKER ASSEMBLY	26.00	EACH
0054	801-06640	CONSTRUCTION SIGN, A	15.00	EACH
0055	801-06645	CONSTRUCTION SIGN, B	11.00	EACH
0056	801-06775	MAINTAINING TRAFFIC	1.00	LS
0057	801-07118	BARRICADE, III-A	96.00	LFT
0058	801-07119	BARRICADE, III-B	48.00	LFT
0059	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2000.00	LFT
0060	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2000.00	LFT

Call: 541

Contract: B -39379-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	202-02240	PAVEMENT REMOVAL	546.00	SYS
0010	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0011	203-02000	EXCAVATION, COMMON	434.00	CYS
0012	205-12108	STORM WATER MANAGEMENT BUDGET	8200.00	DOL
0013	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0014	207-09935	SUBGRADE TREATMENT, TYPE IC	677.00	SYS
0015	302-07455	DENSE GRADED SUBBASE	92.00	CYS
0016	306-08034	MILLING, ASPHALT, 1 1/2 IN.	401.00	SYS
0017	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	89.00	TON
0018	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	94.00	TON
0019	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	224.00	TON
0020	401-10258	JOINT ADHESIVE, SURFACE	910.00	LFT
0021	401-10259	JOINT ADHESIVE, INTERMEDIATE	690.00	LFT
0022	401-11785	LIQUID ASPHALT SEALANT	910.00	LFT
0023	406-05521	ASPHALT FOR TACK COAT	2607.00	SYS
0024	601-06035	GUARDRAIL, RESET	100.00	LFT
0025	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	546.00	SYS
0026	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0027	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0028	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0029	621-02770	EROSION CONTROL BLANKET	1000.00	SYS
0030	621-06559	MULCHED SEEDING R	1200.00	SYS
0031	628-09402	FIELD OFFICE, B	14.00	MOS

0032	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0033	702-51863	FIELD DRILLED HOLE IN CONCRETE	40.00	EACH
0034	703-06029	REINFORCING BARS, EPOXY COATED	32704.00	LBS
0035	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	312.00	EACH
0036	704-51002	CONCRETE, C, SUPERSTRUCTURE	11.60	CYS
0037	706-11600	RAILING, CONCRETE FC	1.60	CYS
0038	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	2.00	EACH
0039	709-51821	SURFACE SEAL	1.00	LS
0040	709-51821	SURFACE SEAL	1.00	LS
0041	711-95291	JACKING AND SUPPORTING, STEEL BEAMS	1.00	LS
0042	715-01354	CLEAN EXISTING PIPE	60.00	LFT
0043	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	100.00	SFT
0044	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	255.00	SFT
0045	726-92406	BEARING ASSEMBLY ELASTOMERIC	12.00	EACH
0046	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	1309.00	SYS
0047	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9095.00	LFT
0048	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	58.00	LFT
0049	801-06640	CONSTRUCTION SIGN, A	42.00	EACH
0050	801-06645	CONSTRUCTION SIGN, B	15.00	EACH
0051	801-06775	MAINTAINING TRAFFIC	1.00	LS
0052	801-07118	BARRICADE, III-A	28.00	LFT
0053	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1250.00	LFT
0054	801-12081	PORTABLE SIGNAL	1.00	LS
0055	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0056	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	86.00	LFT
0057	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1784.00	LFT
0058	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1915.00	LFT
0059	808-06716	LINE, REMOVE	2850.00	LFT
0060	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	9.00	EACH

Call: 551

Contract: B -40862-B

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0013	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0014	202-01066	HYDRO DEMOLITION	2140.00	SYS
0015	202-02240	PAVEMENT REMOVAL	328.00	SYS
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0018	202-51822	BRIDGE DECK OVERLAY, REMOVE	2140.00	SYS
0019	203-08607	LINEAR GRADING	80.00	LFT
0020	205-12108	STORM WATER MANAGEMENT BUDGET	20000.00	DOL
0021	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0022	206-51235	COFFERDAM	1.00	LS
0023	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	8.00	CYS
0024	302-06464	SUBBASE FOR PCCP	40.00	CYS
0025	302-07455	DENSE GRADED SUBBASE	60.00	CYS
0026	306-08043	MILLING, TRANSITION	2708.00	SYS
0027	306-08159	MILLING, ASPHALT	266.00	SYS
0028	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	247.00	TON
0029	401-10258	JOINT ADHESIVE, SURFACE	1806.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	1806.00	LFT
0031	406-05521	ASPHALT FOR TACK COAT	2973.00	SYS

0032	503-03489	RETROFITTED TIE BARS	148.00	EACH
0033	503-05310	TERMINAL JOINT	132.00	LFT
0034	506-06333	PCCP PATCHING, FULL DEPTH	148.00	SYS
0035	601-06035	GUARDRAIL, RESET	125.00	LFT
0036	606-07484	MILLED HMA CORRUGATIONS	3449.00	LFT
0037	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	340.00	SYS
0038	616-05688	RIPRAP, CLASS 1	374.00	TON
0039	616-06405	RIPRAP, REVETMENT	105.00	TON
0040	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	352.00	SYS
0041	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	137.00	SYS
0042	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0043	621-06559	MULCHED SEEDING R	778.00	SYS
0044	628-09402	FIELD OFFICE, B	13.00	MOS
0045	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0046	702-51863	FIELD DRILLED HOLE IN CONCRETE	144.00	EACH
0047	703-06029	REINFORCING BARS, EPOXY COATED	25760.00	LBS
0048	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	168.00	EACH
0049	704-51002	CONCRETE, C, SUPERSTRUCTURE	5.60	CYS
0050	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00	EACH
0051	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0052	709-51821	SURFACE SEAL	1.00	LS
0053	709-51821	SURFACE SEAL	1.00	LS
0054	710-09158	PATCHING CONCRETE STRUCTURES	185.00	SFT
0055	713-04331	TEMPORARY CAUSEWAY	1.00	LS
0056	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	24.00	EACH
0057	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	964.00	SFT
0058	722-51846	BRIDGE DECK OVERLAY, ADDITIONAL	16.40	CYS
0059	722-60824	SURFACE MILLING	2140.00	SYS
0060	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0061	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0062	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	18960.00	LFT
0063	801-06640	CONSTRUCTION SIGN, A	34.00	EACH
0064	801-06645	CONSTRUCTION SIGN, B	1.00	EACH
0065	801-06710	FLASHING ARROW SIGN	150.00	DAY
0066	801-06775	MAINTAINING TRAFFIC	1.00	LS
0067	801-07118	BARRICADE, III-A	360.00	LFT
0068	801-07119	BARRICADE, III-B	40.00	LFT

0069	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1920.00	LFT
0070	808-06716	LINE, REMOVE	15220.00	LFT
0071	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1621.00	LFT
0072	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	6467.00	LFT
0073	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	6213.00	LFT
0074	808-12032	GROOVING FOR PAVEMENT MARKINGS	12817.00	LFT
0075	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	79.00	EACH
0076	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	75.00	EACH

Call: 551

Contract: B -40862-B

Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0077	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	2140.00	SYS

Call: 551

Contract: B -40862-B

Section No.: 3 MICROSILICA CONCRETE OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0078	736-01061	BRIDGE DECK OVERLAY MICROSILICA	2140.00	SYS

Call: 561

Contract: B -40921-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	127.00	SYS
0013	203-02000	EXCAVATION, COMMON	740.00	CYS
0014	203-02070	BORROW	10.00	CYS
0015	205-11626	PUMP AROUND	1.00	EACH
0016	205-12108	STORM WATER MANAGEMENT BUDGET	21810.00	DOL
0017	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0018	206-51220	EXCAVATION, WET	20.00	CYS
0019	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	3.00	CYS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	2419.00	SYS
0021	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	4.90	CYS
0022	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	243.00	SYS
0023	301-12232	COMPACTED AGGREGATE NO 5	41.00	CYS
0024	302-07455	DENSE GRADED SUBBASE	22.00	CYS
0025	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	200.00	TON
0026	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	334.00	TON
0027	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	799.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	2176.00	LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	2176.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	2176.00	LFT
0031	406-05520	ASPHALT FOR TACK COAT	0.70	TON

0032	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	96.00	LFT
0033	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	1.00	EACH
0034	601-01839	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 6	1.00	EACH
0035	601-02241	GUARDRAIL, REMOVE	2363.00	LFT
0036	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1984.00	LFT
0037	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	4.00	EACH
0038	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0039	602-06729	BARRIER, DELINEATOR	32.00	EACH
0040	605-05523	CURB, HMA	2176.00	LFT
0041	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	127.00	SYS
0042	616-05688	RIPRAP, CLASS 1	38.00	TON
0043	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	40.00	SYS
0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0045	621-06559	MULCHED SEEDING R	3371.00	SYS
0046	628-09402	FIELD OFFICE, B	12.00	MOS
0047	628-11730	CELLULAR TELEPHONE, TYPE B	2.00	EACH
0048	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0049	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	24.00	MOS
0050	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0051	702-51005	CONCRETE, A, SUBSTRUCTURE	6.70	CYS
0052	703-06029	REINFORCING BARS, EPOXY COATED	8996.00	LBS
0053	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	52.00	EACH
0054	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	1.00	EACH
0055	706-51020	RAILING, CONCRETE C	3.30	CYS
0056	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0057	709-51821	SURFACE SEAL	1.00	LS
0058	709-51821	SURFACE SEAL	1.00	LS
0059	710-09158	PATCHING CONCRETE STRUCTURES	950.00	SFT
0060	711-95291	JACKING AND SUPPORTING, STEEL BEAMS	1.00	LS
0061	715-91361	PIPE PVC 6 IN	20.00	LFT
0062	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	508.00	SFT
0063	724-12103	PRE-COMPRESSED FOAM JOINT	82.00	LFT
0064	725-11421	PIPE LINER, CURED-IN-PLACE, 51 IN	70.00	LFT
0065	726-11773	BEARING ASSEMBLY RESET	1.00	EACH
0066	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	2542.00	SYS
0067	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0068	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	13186.00	LFT

0069	801-06625	DETOUR ROUTE MARKER ASSEMBLY	29.00	EACH
0070	801-06640	CONSTRUCTION SIGN, A	63.00	EACH
0071	801-06645	CONSTRUCTION SIGN, B	24.00	EACH
0072	801-06710	FLASHING ARROW SIGN	240.00	DAY
0073	801-06775	MAINTAINING TRAFFIC	1.00	LS
0074	801-07118	BARRICADE, III-A	72.00	LFT
0075	801-07119	BARRICADE, III-B	72.00	LFT
0076	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1160.00	LFT
0077	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	440.00	LFT
0078	801-12042	TRUCK MOUNTED ATTENUATOR	120.00	DAY
0079	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	1310.00	LFT
0080	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	3814.00	LFT
0081	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	4106.00	LFT
0082	808-06716	LINE, REMOVE	7411.00	LFT
0083	808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	230.00	LFT
0084	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	72.00	EACH
0085	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	6.00	EACH

Call: 581

Contract: M -41676-A

Section No.: 1 GUARDRAIL MAINTENANCE OR REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	601-01128	GUARDRAIL, TRANSITION, TYPE WGB	1.00	EACH
0008	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH
0009	601-01700	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 1	2.00	EACH
0010	601-01867	GUARDRAIL, TRANSITION, TGB RETROFIT	1.00	EACH
0011	601-02211	GUARDRAIL POST, 8.5 LBS PER LFT, 7 FT LONG, GALVANIZED	350.00	EACH
0012	601-02800	GUARDRAIL, TRANSITION, TGT	1.00	EACH
0013	601-03452	EXCAVATION OF DAMAGED STEEL BEAM GUARDRAIL BURIED END SECTION LABOR ONLY	6.00	EACH
0014	601-03453	GUARDRAIL, CLAMP BAR, 7.125 IN., ALUMINUM	30.00	EACH
0015	601-03456	GUARDRAIL POST, WOOD TYPE W5	8.00	EACH
0016	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	8.00	EACH
0017	601-03599	GUARDRAIL, THRIE BEAM, RAIL SECTION, 12 FT. 6 IN	2.00	EACH
0018	601-06035	GUARDRAIL, RESET	50.00	LFT
0019	601-06774	COMBINATION ATTENUATING TERMINAL	1.00	EACH
0020	601-06798	TIMBER BLOCK	200.00	EACH
0021	601-06854	GUARDRAIL, W-BEAM, NESTED	1.00	EACH
0022	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	1.00	EACH
0023	601-08433	GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS PACKAGE, STAGE 1	10.00	EACH
0024	601-08435	GUARDRAIL END TREATMENT, TYPE MS, SPARE PARTS PACKAGE, STAGE 1	10.00	EACH
0025	601-09238	HAND DIG GUARDRAIL POST HOLES	50.00	EACH
0026	601-61320	CURVED SECTION, STEEL BEAM GUARDRAIL GALVANIZED, 12 GA.	1000.00	LFT
0027	601-61340	GUARDRAIL POST, 15.5 LBS PER FT., GALVANIZED, 6 FT. 3 IN. LONG	40.00	EACH
0028	601-61350	GUARDRAIL POST BRACKET, 15.5 LBS PER LFT., GALVANIZED, 1 FT. 2.25 IN.	80.00	EACH
0029	601-61370	GUARDRAIL POST BRACKET, 8.5 LBS PER LFT., GALVANIZED 1 FT. 2.25 IN.	125.00	EACH
0030	601-61380	GUARDRAIL TERMINAL SECTION, FLAT END, GALVANIZED	1.00	EACH
0031	601-61390	GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE, GALVANIZED	10.00	EACH

0032	601-61400	GUARDRAIL BURIED END, GALVANIZED, SINGLE FACE	1.00	EACH
0033	601-61550	GUARDRAIL TERMINAL END SECTION, ALUMINUM	5.00	EACH
0034	601-62070	GUARDRAIL, STEEL BEAM, GALVANIZED	25500.00	LFT
0035	601-62090	GUARDRAIL, STEEL BEAM, INSTALL	15.00	LFT
0036	601-62100	GUARDRAIL POST, STEEL, INSTALL	5.00	EACH
0037	601-62110	GUARDRAIL, CHANNEL, 6.7 LBS PER LFT., INSTALL	50.00	LFT
0038	601-62120	GUARDRAIL POST BRACKET, INSTALL	3.00	EACH
0039	601-62150	GUARDRAIL POST, 15.5 LBS PER LFT, GALVANIZED, 7 FT 0 IN. LONG	2.00	EACH
0040	601-62297	GUARDRAIL STANDARD TERMINAL CONNECTOR, MICHIGAN END SHOE	1.00	EACH
0041	601-62530	GUARDRAIL PIER CONNECTION, ES	1.00	EACH
0042	601-62540	GUARDRAIL POST, PLUMB	900.00	EACH
0043	601-62550	GUARDRAIL, TUBING, ELLIPTICAL, ALUMINUM	250.00	LFT
0044	601-62580	GUARDRAIL SPLICE BAR, ALUMINUM	25.00	EACH
0045	601-62630	GUARDRAIL POST, ALUMINUM, 6 FT. 3 IN.	1.00	EACH
0046	601-62640	GUARDRAIL POST, ALUMINUM, 5 FT. 3 IN.	5.00	EACH
0047	601-62680	GUARDRAIL TERMINAL SECTION, SINGLE FACE, BURIED END, ALUMINUM	1.00	EACH
0048	601-90382	GUARDRAIL POST, ALUMINUM, 7 FT.	1.00	EACH
0049	601-90389	GUARDRAIL TERMINAL SECTION, GALVANIZED, 11 IN.	1.00	EACH
0050	601-90677	DRILLED BRACKET INSTALL	1.00	EACH
0051	601-91198	GUARDRAIL POST, MODIFIED	4.00	EACH
0052	601-91504	GUARDRAIL POST, W1, 10 IN X 10 IN	1.00	EACH
0053	601-91505	GUARDRAIL POST, W2, 8 IN. X 8 IN.	5.00	EACH
0054	601-91510	GUARDRAIL POST, W3, 8 IN. X 8 IN.	5.00	EACH
0055	601-91511	GUARDRAIL POST, W4, 8 IN. X 8 IN.	5.00	EACH
0056	601-91542	GUARDRAIL BLOCK, 6 IN. X 8 IN., B1	5.00	EACH
0057	601-91575	GUARDRAIL BLOCK, 6 IN. X 8 IN., B2	5.00	EACH
0058	601-91576	GUARDRAIL BLOCK, 6 IN. X 8 IN., B3	5.00	EACH
0059	601-91649	GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	8.00	EACH
0060	601-91653	GUARDRAIL THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	2.00	EACH
0061	601-93346	GUARDRAIL CONNECTOR, AS	5.00	EACH
0062	601-94689	GUARDRAIL, END TREATMENT, OS	30.00	EACH
0063	601-95342	GUARDRAIL SPLICE PLATE, C, GALVANIZED	4.00	EACH
0064	601-95972	GUARDRAIL POST (CRT), 8 IN X 6 IN TREATED LUMBER, 6 FT. 0 IN. LONG	15.00	EACH
0065	601-98636	GUARDRAIL CHANNEL, 10 kg PER m, GALVANIZED, 125 mm	100.00	LFT
0066	601-98637	GUARDRAIL BURIED END, TERMINAL CONNECTOR, GALVANIZED	1.00	EACH
0067	601-98638	GUARDRAIL SPLICE PLATE, ALUMINUM	1.00	EACH
0068	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	1500.00	LFT

0069	601-99108	GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN. SPACING	150.00	LFT
0070	601-99123	GUARDRAIL, TRANSITION, GP	1.00	EACH
0071	627-09327	CABLE BARRIER SYSTEM, TYPE TL-4	100.00	LFT
0072	627-09910	CABLE LINE POST LESS SOCKET, REPAIR	500.00	EACH
0073	627-09911	TERMINAL POST LESS SOCKET, REPAIR	16.00	EACH
0074	627-09912	CABLE RELEASE POST LESS SOCKET, REPAIR	1.00	EACH
0075	627-09913	CABLE SOCKET WITH CONCRETE, REPAIR	1.00	EACH
0076	627-09914	ANCHOR TERMINAL FITTING, REPAIR	8.00	EACH
0077	627-09915	CABLE SPLICE, REPAIR	1.00	EACH
0078	627-09916	RETENTION CABLE, REPAIR	4.00	EACH
0079	627-11647	CABLE BARRIER SYSTEM, TYPE TL-4 RESET	1000.00	LFT
0080	706-01515	BRIDGE BRACKET A, ALUMINUM	1.00	EACH
0081	706-05587	BRIDGE BARRIER RAIL BRACKET, CONCRETE, INSTALL	1.00	EACH
0082	706-06347	RAILING, STEEL CF-1	50.00	LFT
0083	706-62380	BRIDGE RAILING POST, 5A	3.00	EACH
0084	706-62390	BRIDGE RAILING POST, 6	1.00	EACH
0085	706-62400	BRIDGE RAILING POST, 7	1.00	EACH
0086	706-90672	BRIDGE RAILING POST, ALUMINUM, 5	5.00	EACH
0087	706-94133	RAILING, TUBE, GALVANIZED STEEL	1.00	LFT
0088	706-95431	BARRIER X CONCRETE BRIDGE RAILING BRACKET TYPE A	1.00	EACH
0089	706-95432	BARRIER X CONCRETE BRIDGE RAILING BRACKET TYPE B	1.00	EACH
0090	706-95433	BARRIER X CONCRETE BRIDGE RAILING BRACKET TYPE C	1.00	EACH
0091	706-98639	BRIDGE RAILING SPLICE BAR, ALUMINUM	1.00	EACH
0092	711-51823	EXPANSION ANCHOR 0.75 IN	1.00	EACH
0093	801-03290	CONSTRUCTION SIGN, C	4.00	EACH
0094	801-06775	MAINTAINING TRAFFIC	1.00	LS
0095	801-12042	TRUCK MOUNTED ATTENUATOR	72.00	DAY
0096	802-97573	ANGLE POST	1.00	EACH
0097	803-61430	BRIDGE BRACKET A GALVANIZED	1.00	EACH
0098	803-61440	BRIDGE BRACKET B GALVANIZED	1.00	EACH

Call: 601

Contract: T -39038-A

Section No.: 1 TRAFFIC SIGNAL MODERNIZATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	203-02020	EXCAVATION, UNCLASSIFIED	28.50	CYS
0008	604-06070	SIDEWALK, CONCRETE	25.00	SYS
0009	604-07092	BED COURSE MATERIAL	10.10	TON
0010	604-08086	CURB RAMP, CONCRETE	8.00	SYS
0011	604-12083	DETECTABLE WARNING SURFACES	6.00	SYS
0012	801-06640	CONSTRUCTION SIGN, A	469.00	EACH
0013	801-06775	MAINTAINING TRAFFIC	1.00	LS
0014	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	12.00	EACH
0015	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0016	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0017	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0018	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0019	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0020	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0021	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0022	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0023	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0024	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	150.00	LFT
0025	805-02445	CONTROLLER AND CABINET, P1	12.00	EACH
0026	805-03980	EMERGENCY VEHICLE CONFIRMATION LIGHT KIT	313.00	EACH
0027	805-07842	VEHICLE DETECTION SYSTEM	212.00	EACH
0028	805-78445	SIGNAL SERVICE	1.00	EACH
0029	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	50.00	LFT
0030	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	34992.00	LFT
0031	805-78925	CONTROLLER CABINET FOUNDATION, P1	12.00	EACH

Call: 611

Contract: T -40045-A

Section No.: 1 RAISED PAVEMENT MARKINGS, REFURBISHED

Line			Quantity Unit	
Item No	Item Code	Description		
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0006	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0007	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0008	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	6.00	MOS
0009	801-06710	FLASHING ARROW SIGN	180.00	DAY
0010	801-06775	MAINTAINING TRAFFIC	1.00	LS
0011	801-92448	CONSTRUCTION SIGNS MOBILE	1800.00	DAY
0012	808-75994	PRISMATIC REFLECTOR	45886.00	EACH
0013	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6883.00	EACH
0014	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	6883.00	EACH

Call: 621

Contract: T -40843-A

Section No.: 1 TRAFFIC SIGNAL MODERNIZATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0003	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0004	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0005	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	205-12108	STORM WATER MANAGEMENT BUDGET	2000.00	DOL
0008	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0009	206-51215	EXCAVATION, X	9.00	CYS
0010	211-02050	B BORROW	18.70	CYS
0011	604-06070	SIDEWALK, CONCRETE	46.00	SYS
0012	604-08086	CURB RAMP, CONCRETE	52.60	SYS
0013	604-12083	DETECTABLE WARNING SURFACES	12.50	SYS
0014	605-06120	CURB, CONCRETE	200.00	LFT
0015	628-09402	FIELD OFFICE, B	9.00	MOS
0016	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0017	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0018	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2756.00	LFT
0019	801-06625	DETOUR ROUTE MARKER ASSEMBLY	21.00	EACH
0020	801-06640	CONSTRUCTION SIGN, A	13.00	EACH
0021	801-06645	CONSTRUCTION SIGN, B	23.50	EACH
0022	801-06710	FLASHING ARROW SIGN	56.00	DAY
0023	801-06775	MAINTAINING TRAFFIC	1.00	LS
0024	801-07118	BARRICADE, III-A	48.00	LFT
0025	801-07119	BARRICADE, III-B	48.00	LFT
0026	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	228.10	SFT
0027	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	112.60	SFT
0028	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.00	EACH
0029	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0030	805-01828	TRAFFIC SIGNAL HEAD REALIGN	13.00	EACH
0031	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1498.00	LFT

0032	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	32.00	EACH
0033	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	22.00	EACH
0034	805-08464	RADIO INTERCONNECT	1.00	EACH
0035	805-08493	RADIO INTERCONNECTION SYSTEM TESTING	1.00	LS
0036	805-09089	RADIO YAGI ANTENNA	3.00	EACH
0037	805-11374	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 20 FT	2.00	EACH
0038	805-11376	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 30 FT.	2.00	EACH
0039	805-11377	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 35 FT.	1.00	EACH
0040	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, A	5.00	EACH
0041	805-11386	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, F	3.00	EACH
0042	805-11392	SIGNAL CANTILEVER STRUCTURE, DUAL ARM 30 FT	1.00	EACH
0043	805-11394	SIGNAL CANTILEVER STRUCTURE, DUAL ARM 40 FT	1.00	EACH
0044	805-11396	SIGNAL CANTILEVER STRUCTURE, DUAL ARM 45 FT	1.00	EACH
0045	805-11570	RADIO ANTENNA	1.00	EACH
0046	805-11744	HANDHOLE SIGNAL TYPE 2	14.00	EACH
0047	805-11817	PEDESTRIAN PUSH BUTTON, APS	32.00	EACH
0048	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	20.00	EACH
0049	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	3600.00	LFT
0050	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	1054.00	LFT
0051	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	3673.00	LFT
0052	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	1157.00	LFT
0053	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	887.00	LFT
0054	805-78785	SIGNAL DETECTOR HOUSING	8.00	EACH
0055	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1136.00	LFT
0056	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	22.00	EACH
0057	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	80.00	LFT
0058	807-12214	LUMINAIRE ROADWAY LED 157 WATT	2.00	EACH
0059	807-12214	LUMINAIRE ROADWAY LED 157 WATT	2.00	EACH
0060	807-12214	LUMINAIRE ROADWAY LED 157 WATT	2.00	EACH
0061	807-12214	LUMINAIRE ROADWAY LED 157 WATT	2.00	EACH
0062	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	576.00	LFT
0063	807-86910	CONNECTOR KIT, UNFUSED	8.00	EACH
0064	807-86915	CONNECTOR KIT, FUSED	8.00	EACH
0065	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	9.00	EACH
0066	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	16.00	EACH
0067	807-86930	INSULATION LINK, NON-WATERPROOFED	16.00	EACH
0068	807-86935	INSULATION LINK, WATERPROOFED	32.00	EACH

0069	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	120.00	LFT
0070	808-06716	LINE, REMOVE	2480.00	LFT
0071	809-04982	CABLE	180.00	LFT
0072	809-04982	CABLE	300.00	LFT