

Schedule of Pay Items Letting Date April 3, 2019 Letting ID 190403

Call: 121

Contract: R -29423-A

Section No.: 1 ROAD REHABILITATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-02250	TREE 10 IN., REMOVE	3.00	EACH
0011	201-02255	TREE 18 IN., REMOVE	4.00	EACH
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02278	CURB, CONCRETE, REMOVE	200.00	LFT
0014	202-52710	SIDEWALK CONCRETE, REMOVE	1400.00	SYS
0015	202-96133	PIPE, REMOVE	1000.00	LFT
0016	203-02000	EXCAVATION, COMMON	5100.00	CYS
0017	205-12108	STORM WATER MANAGEMENT BUDGET	15500.00	DOL
0018	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	1100.00	SYS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	5300.00	SYS
0021	214-12144	GEOTEXTILE FOR SUBBASE	7200.00	SYS
0022	301-12231	COMPACTED AGGREGATE NO 2	2900.00	CYS
0023	301-12233	COMPACTED AGGREGATE NO 8	300.00	CYS
0024	301-12234	COMPACTED AGGREGATE NO 53	1700.00	CYS
0025	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	250.00	TON
0026	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	500.00	TON
0027	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	1400.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	2400.00	LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	2400.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	3300.00	LFT
0031	406-05521	ASPHALT FOR TACK COAT	5500.00	SYS

0032	604-06070	SIDEWALK, CONCRETE	2900.00	SYS
0033	604-08086	CURB RAMP, CONCRETE	70.00	SYS
0034	604-10013	PERMEABLE UNIT PAVERS	9900.00	SFT
0035	605-06125	CURB, CONCRETE, MODIFIED	4800.00	LFT
0036	605-06140	CURB AND GUTTER, CONCRETE	200.00	LFT
0037	610-08446	PCCP FOR APPROACHES, 6 IN.	1100.00	SYS
0038	615-06505	MONUMENT, B	4.00	EACH
0039	621-06575	SODDING, NURSERY	2750.00	SYS
0040	628-09403	FIELD OFFICE, C	18.00	MOS
0041	715-11896	WATER SERVICE CONNECTION	2.00	EACH
0042	715-91742	WATER METER RELOCATE	2.00	EACH
0043	718-04986	CLEANOUT	38.00	EACH
0044	720-44000	CASTING, ADJUST TO GRADE	20.00	EACH
0045	720-97008	FIRE HYDRANT ASSEMBLY RELOCATE	2.00	EACH
0046	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0047	801-06625	DETOUR ROUTE MARKER ASSEMBLY	18.00	EACH
0048	801-06645	CONSTRUCTION SIGN, B	27.00	EACH
0049	801-06775	MAINTAINING TRAFFIC	1.00	LS
0050	801-07119	BARRICADE, III-B	92.00	LFT
0051	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	50.00	LFT
0052	802-07060	SIGN, SHEET, RELOCATE	13.00	EACH
0053	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	25.00	SFT
0054	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	25.00	SFT
0055	807-91361	PIPE PVC 6 IN	1000.00	LFT
0056	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	900.00	LFT
0057	808-06706	LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	260.00	LFT
0058	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	300.00	LFT
0059	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	2500.00	LFT
0060	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	40.00	LFT

Call: 141

Contract: R -33953-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	140.00	SYS
0014	202-04435	DELINEATOR POST, REMOVE	2.00	EACH
0015	202-91840	FENCE, CHAIN. LINK, REMOVE	560.00	LFT
0016	203-02000	EXCAVATION, COMMON	98.00	CYS
0017	203-02070	BORROW	165.00	CYS
0018	205-12108	STORM WATER MANAGEMENT BUDGET	28982.00	DOL
0019	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	3572.00	SYS
0021	211-09264	STRUCTURE BACKFILL, TYPE 1	576.00	CYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	920.00	CYS
0023	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	270.00	CYS
0024	301-12232	COMPACTED AGGREGATE NO 5	65.00	CYS
0025	301-12234	COMPACTED AGGREGATE NO 53	138.00	CYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	710.00	TON
0027	304-07783	HMA PATCHING, TYPE D	30.00	TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1740.00	SYS
0029	306-08041	MILLING, PCCP	12.00	SYS
0030	306-08043	MILLING, TRANSITION	610.00	SYS
0031	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	51.00	TON

0032	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	165.00	TON
0033	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	231.00	TON
0034	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	392.00	TON
0035	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	1593.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	1822.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	220.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	1720.00	LFT
0039	406-05521	ASPHALT FOR TACK COAT	11262.00	SYS
0040	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.00	TON
0041	507-07482	CRACKS IN PCCP, ROUT AND SEAL	160.00	LFT
0042	507-08269	CRACKS IN PCCP, FILLED	120.00	LFT
0043	507-08272	JOINTS IN PCCP, SAW AND SEAL	330.00	LFT
0044	601-08433	GUARDRAIL END TREATMENT, TYPE OS, SPARE PARTS PACKAGE, STAGE 1	1.00	EACH
0045	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	500.00	LFT
0046	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	2.00	EACH
0047	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0048	602-06729	BARRIER, DELINEATOR	28.00	EACH
0049	603-06060	FENCE, FARM FIELD, RESET	450.00	LFT
0050	615-06490	RIGHT-OF-WAY MARKER	4.00	EACH
0051	615-06510	MONUMENT, C	2.00	EACH
0052	616-05688	RIPRAP, CLASS 1	88.00	TON
0053	616-05689	RIPRAP, CLASS 2	122.00	TON
0054	616-06405	RIPRAP, REVETMENT	202.00	TON
0055	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	569.00	SYS
0056	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	335.00	SYS
0057	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	13.00	EACH
0058	621-02356	SEEDING WETLAND	5.00	LBS
0059	621-02770	EROSION CONTROL BLANKET	2090.00	SYS
0060	621-03787	SEED MIXTURE D	10.00	LBS
0061	621-03909	SEED MIXTURE, NATIVE	30.00	LBS
0062	628-09402	FIELD OFFICE, B	12.00	MOS
0063	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0064	706-11455	BRIDGE RAILING PEDESTRIAN FENCE	560.00	LFT
0065	708-51813	PNEUMATICALLY PLACED MORTAR	35.00	SFT
0066	708-51814	WELDED STEEL WIRE FABRIC	35.00	SFT
0067	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0068	709-51821	SURFACE SEAL	1.00	LS

0069	709-51821	SURFACE SEAL	1.00	LS
0070	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	64.00	LFT
0071	715-05136	PIPE, TYPE 1, CIRCULAR, 72 IN.	182.00	LFT
0072	715-06357	CONCRETE ANCHOR, 72 IN.	2.00	EACH
0073	715-07625	PIPE, TYPE 1, CIRCULAR, 66 IN.	250.00	LFT
0074	715-08307	HMA FOR STRUCTURE INSTALLATION, TYPE D	105.00	TON
0075	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	70.00	SYS
0076	718-52610	AGGREGATE FOR UNDERDRAINS	10.00	CYS
0077	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	497.00	SFT
0078	724-12103	PRE-COMPRESSED FOAM JOINT	184.00	LFT
0079	725-11288	PIPE LINER, CURED-IN-PLACE, 60"	100.00	LFT
0080	725-11300	PIPE LINER, CURED-IN-PLACE, MIN AREA 8.9 SFT	420.00	LFT
0081	725-11908	LINER PIPE, THERMOPLASTIC, CIRCULAR, 5.5-5.6 SFT	88.00	LFT
0082	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	1708.00	SYS
0083	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.00	EACH
0084	801-03290	CONSTRUCTION SIGN, C	8.00	EACH
0085	801-04308	ROAD CLOSURE SIGN ASSEMBLY	30.00	EACH
0086	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	25943.00	LFT
0087	801-06625	DETOUR ROUTE MARKER ASSEMBLY	166.00	EACH
0088	801-06640	CONSTRUCTION SIGN, A	211.00	EACH
0089	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0090	801-06710	FLASHING ARROW SIGN	114.00	DAY
0091	801-06775	MAINTAINING TRAFFIC	1.00	LS
0092	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00	EACH
0093	801-07118	BARRICADE, III-A	320.00	LFT
0094	801-07119	BARRICADE, III-B	256.00	LFT
0095	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	3600.00	LFT
0096	802-11843	SIGN SHEET WITH SPEED DISPLAY	4.00	EACH
0097	804-11920	DELINEATOR POST FLEXIBLE, TYPE I	12.00	EACH
0098	808-06716	LINE, REMOVE	12875.00	LFT
0099	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1810.00	LFT
0100	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	7179.00	LFT
0101	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	7230.00	LFT
0102	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	9.00	EACH

Call: 161

Contract: R -37803-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0013	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0014	202-02240	PAVEMENT REMOVAL	2890.00	SYS
0015	202-02278	CURB, CONCRETE, REMOVE	4931.00	LFT
0016	202-52710	SIDEWALK CONCRETE, REMOVE	550.00	SYS
0017	202-90277	DETECTOR HOUSING, REMOVE	44.00	EACH
0018	203-02000	EXCAVATION, COMMON	1300.00	CYS
0019	205-12108	STORM WATER MANAGEMENT BUDGET	13200.00	DOL
0020	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	4160.00	SYS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	5945.00	SYS
0023	302-07455	DENSE GRADED SUBBASE	154.00	CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	60.00	TON
0025	304-07783	HMA PATCHING, TYPE D	471.00	TON
0026	304-07783	HMA PATCHING, TYPE D	478.00	TON
0027	306-08036	MILLING, ASPHALT, 2 IN.	138035.00	SYS
0028	306-08432	MILLING, APPROACH	11249.00	SYS
0029	401-07353	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm	16296.00	TON
0030	401-11785	LIQUID ASPHALT SEALANT	91335.00	LFT
0031	406-05520	ASPHALT FOR TACK COAT	42.00	TON

0032	502-11543	PCCP, 4 IN.	210.00	SYS
0033	503-03489	RETROFITTED TIE BARS	4121.00	EACH
0034	503-05240	D-1 CONTRACTION JOINT	1028.00	LFT
0035	506-06333	PCCP PATCHING, FULL DEPTH	3957.00	SYS
0036	604-06070	SIDEWALK, CONCRETE	3618.00	SYS
0037	604-08086	CURB RAMP, CONCRETE	637.00	SYS
0038	604-12083	DETECTABLE WARNING SURFACES	158.00	SYS
0039	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	3.00	SYS
0040	605-06120	CURB, CONCRETE	1120.00	LFT
0041	605-06140	CURB AND GUTTER, CONCRETE	4800.00	LFT
0042	610-07788	HMA FOR APPROACHES, TYPE D	1238.00	TON
0043	610-08446	PCCP FOR APPROACHES, 6 IN.	232.00	SYS
0044	610-09108	PCCP FOR APPROACHES, 9 IN.	3928.00	SYS
0045	611-08232	MAILBOX ASSEMBLY, SINGLE RESET	30.00	EACH
0046	621-06570	TOPSOIL	380.00	CYS
0047	621-06574	SODDING	2247.00	SYS
0048	628-09402	FIELD OFFICE, B	15.00	MOS
0049	628-11729	CELLULAR TELEPHONE, TYPE A	2.00	EACH
0050	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0051	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0052	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	30.00	MOS
0053	628-11977	COMPUTER SYSTEM	1.00	EACH
0054	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	5.00	EACH
0055	720-44000	CASTING, ADJUST TO GRADE	3.00	EACH
0056	720-44000	CASTING, ADJUST TO GRADE	39.00	EACH
0057	720-44000	CASTING, ADJUST TO GRADE	4.00	EACH
0058	720-44000	CASTING, ADJUST TO GRADE	47.00	EACH
0059	720-44045	CASTING, 8, FURNISH AND ADJUST TO GRADE	3.00	EACH
0060	720-44080	CASTING, 15, FURNISH AND ADJUST TO GRADE	2.00	EACH
0061	720-45615	STRUCTURE, INLET, RECONSTRUCTED	15.00	LFT
0062	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	7.00	EACH
0063	720-96995	CLEAN INLET	19.00	EACH
0064	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	83.00	EACH
0065	801-03291	CONSTRUCTION SIGN, D	2.00	EACH
0066	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	8914.00	LFT
0067	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8914.00	LFT
0068	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	83.00	EACH

0069	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	487.00	LFT
0070	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	487.00	LFT
0071	801-06640	CONSTRUCTION SIGN, A	118.00	EACH
0072	801-06645	CONSTRUCTION SIGN, B	68.00	EACH
0073	801-06710	FLASHING ARROW SIGN	780.00	DAY
0074	801-06775	MAINTAINING TRAFFIC	1.00	LS
0075	801-07118	BARRICADE, III-A	152.00	LFT
0076	801-07119	BARRICADE, III-B	84.00	LFT
0077	801-92448	CONSTRUCTION SIGNS MOBILE	2520.00	DAY
0078	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	99.00	SFT
0079	802-91122	SIGN GROUND MOUNTED RESET	5.00	EACH
0080	804-11921	DELINEATOR POST FLEXIBLE, TYPE II	36.00	EACH
0081	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	585.00	LFT
0082	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	20.00	EACH
0083	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	16.00	EACH
0084	805-06600	CONDUIT, PVC, 3 IN.	17278.00	LFT
0085	805-11799	RECTANGULAR RAPID FLASHING BEACON	12.00	EACH
0086	805-11817	PEDESTRIAN PUSH BUTTON, APS	20.00	EACH
0087	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	23242.00	LFT
0088	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	2697.00	LFT
0089	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	3012.00	LFT
0090	805-78785	SIGNAL DETECTOR HOUSING	44.00	EACH
0091	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	8863.00	LFT
0092	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	4.00	EACH
0093	805-90267	CONDUIT, STEEL, GALVANIZED, 3 IN.	242.00	LFT
0094	807-98469	PULL BOX	22.00	EACH
0095	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	8900.00	LFT
0096	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	13944.00	LFT
0097	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0098	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	34.00	LFT
0099	808-11493	LINE, THERMOPLASTIC, DOTTED, YELLOW, 4 IN.	30.00	LFT
0100	808-12032	GROOVING FOR PAVEMENT MARKINGS	72778.00	LFT
0101	808-74815	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 12 IN.	363.00	LFT
0102	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	7270.00	LFT
0103	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	41478.00	LFT
0104	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	57.00	LFT
0105	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	260.00	LFT

0106	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	487.00	LFT
0107	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	4120.00	LFT
0108	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	83.00	EACH
0109	808-75330	PAVEMENT MESSAGE MARKING, THERMOPLASTIC PED XING	2.00	EACH
0110	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	1122.00	LFT
0111	808-97323	LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN.	397.00	LFT

Call: 171

Contract: R -37841-A

Section No.: 1 AUXILIARY LANES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	203-02000	EXCAVATION, COMMON	3938.00	CYS
0014	203-02070	BORROW	6646.00	CYS
0015	205-11626	PUMP AROUND	1.00	EACH
0016	205-12108	STORM WATER MANAGEMENT BUDGET	178612.00	DOL
0017	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0018	207-08264	SUBGRADE TREATMENT, TYPE II	6929.00	SYS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	30904.00	SYS
0020	211-09265	STRUCTURE BACKFILL, TYPE 2	35.10	CYS
0021	211-09268	STRUCTURE BACKFILL, TYPE 5	79.80	CYS
0022	214-12236	GEOTEXTILE FOR PAVEMENT TYPE 1A	5620.00	SYS
0023	301-12232	COMPACTED AGGREGATE NO 5	1703.00	CYS
0024	301-12234	COMPACTED AGGREGATE NO 53	738.00	CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	537.00	TON
0026	304-07783	HMA PATCHING, TYPE D	1571.00	TON
0027	304-07789	WIDENING WITH HMA, TYPE D	7791.00	TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	15697.00	SYS
0029	306-08039	MILLING, ASPHALT REMOVAL	35540.00	SYS
0030	306-08432	MILLING, APPROACH	803.00	SYS
0031	306-11872	MILLING, PROFILE	21147.00	SYS

0032	401-06264	PROFILOGRAPH, HMA	1.00	LS
0033	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	7808.00	TON
0034	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	8231.00	TON
0035	401-08364	QC/QA-HMA, 4, 64, BASE, 19.0 mm	10455.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	30032.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	19503.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	30032.00	LFT
0039	401-12139	QC/QA-HMA, 4, 76, BASE, OG, 19.0 mm	262.00	TON
0040	406-05520	ASPHALT FOR TACK COAT	62.00	TON
0041	503-03489	RETROFITTED TIE BARS	255.00	EACH
0042	503-05240	D-1 CONTRACTION JOINT	96.00	LFT
0043	506-06333	PCCP PATCHING, FULL DEPTH	1730.00	SYS
0044	507-08269	CRACKS IN PCCP, FILLED	1000.00	LFT
0045	601-01626	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 2	1.00	EACH
0046	601-01700	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 1	2.00	EACH
0047	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	2.00	EACH
0048	601-02241	GUARDRAIL, REMOVE	2216.00	LFT
0049	601-06038	GUARDRAIL, END TREATMENT, II	1.00	EACH
0050	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1613.00	LFT
0051	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	5.00	EACH
0052	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	2.00	EACH
0053	601-94689	GUARDRAIL, END TREATMENT, OS	5.00	EACH
0054	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	14835.00	LFT
0055	610-07487	HMA FOR APPROACHES, TYPE B	1917.00	TON
0056	611-06497	MAILBOX ASSEMBLY, SINGLE	12.00	EACH
0057	611-06498	MAILBOX ASSEMBLY, DOUBLE	4.00	EACH
0058	615-06490	RIGHT-OF-WAY MARKER	8.00	EACH
0059	615-06500	MONUMENT, A	19.00	EACH
0060	615-06527	MONUMENT, SECTION CORNER	4.00	EACH
0061	616-05689	RIPRAP, CLASS 2	52.00	TON
0062	616-06405	RIPRAP, REVETMENT	10.00	TON
0063	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	196.00	SYS
0064	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.00	EACH
0065	621-02770	EROSION CONTROL BLANKET	10266.00	SYS
0066	621-06545	FERTILIZER	5.00	TON
0067	621-06553	SEED MIXTURE R	1824.00	LBS
0068	621-06565	MULCHING MATERIAL	19.00	TON

0069	621-06574	SODDING	581.00	SYS
0070	628-09402	FIELD OFFICE, B	24.00	MOS
0071	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0072	714-12438	STRUCTURE COATED RC BOX SECTIONS 4 FT X 4 FT	60.00	LFT
0073	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	680.00	LFT
0074	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	78.00	LFT
0075	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	52.00	LFT
0076	715-09064	VIDEO INSPECTION FOR PIPE	52.00	LFT
0077	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0078	718-06528	OUTLET PROTECTOR, 1	1.00	EACH
0079	718-11685	UNDERDRAIN CLEANOUT PORT	1.00	EACH
0080	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	491.00	SYS
0081	718-52610	AGGREGATE FOR UNDERDRAINS	48.00	CYS
0082	801-06625	DETOUR ROUTE MARKER ASSEMBLY	70.00	EACH
0083	801-06640	CONSTRUCTION SIGN, A	61.00	EACH
0084	801-06775	MAINTAINING TRAFFIC	1.00	LS
0085	801-07119	BARRICADE, III-B	712.00	LFT
0086	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	7.00	EACH
0087	802-04893	REFERENCE POST	3.00	EACH
0088	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	773.00	LFT
0089	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	226.00	LFT
0090	802-07060	SIGN, SHEET, RELOCATE	4.00	EACH
0091	802-09837	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	9.00	SFT
0092	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	294.00	SFT
0093	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	6.00	SFT
0094	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	100.00	SFT
0095	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	19.00	SFT
0096	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	1900.00	LFT
0097	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	315.00	LFT
0098	808-06694	LINE, PAINT, SOLID, YELLOW, 8 IN.	380.00	LFT
0099	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1370.00	LFT
0100	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	48001.00	LFT
0101	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	1178.00	LFT
0102	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0103	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	60.00	LFT
0104	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	242.00	LFT
0105	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	242.00	LFT

0106	808-12032	GROOVING FOR PAVEMENT MARKINGS	76153.00	LFT
0107	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1650.00	LFT
0108	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	39571.00	LFT
0109	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	394.00	LFT
0110	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	20.00	EACH
0111	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	514.00	EACH
0112	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	644.00	EACH

Call: 181

Contract: R -38722-A

Section No.: 1 ADDED TRAVEL LANES, TURN LANES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	126.00	SYS
0012	202-02273	CENTER CURB, CONCRETE, REMOVE	108.00	SYS
0013	202-91385	INLET, REMOVE	1.00	EACH
0014	202-93047	MANHOLE, REMOVE	2.00	EACH
0015	202-93615	CONCRETE, REMOVE	35.00	SYS
0016	202-93995	SIGNAL POLE FOUNDATION, REMOVE	1.00	EACH
0017	202-93999	SIGNAL POLE, REMOVE	1.00	EACH
0018	203-02000	EXCAVATION, COMMON	390.00	CYS
0019	205-12108	STORM WATER MANAGEMENT BUDGET	4756.00	DOL
0020	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	21.00	SYS
0022	207-12151	SUBGRADE TREATMENT, TYPE IVA	765.00	SYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	55.00	CYS
0024	302-06464	SUBBASE FOR PCCP	189.00	CYS
0025	502-08204	PCCP, 12.5 IN.	323.00	SYS
0026	503-05240	D-1 CONTRACTION JOINT	222.00	LFT
0027	506-06333	PCCP PATCHING, FULL DEPTH	368.00	SYS
0028	605-06090	CURB, INTEGRAL CONCRETE	264.00	LFT
0029	605-06255	CENTER CURB, D CONCRETE	170.00	SYS
0030	610-09108	PCCP FOR APPROACHES, 9 IN.	21.00	SYS
0031	621-06575	SODDING, NURSERY	226.00	SYS

0032	628-09402	FIELD OFFICE, B	4.00	MOS
0033	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0034	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	65.00	LFT
0035	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	132.00	LFT
0036	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	58.00	SYS
0037	718-52610	AGGREGATE FOR UNDERDRAINS	6.00	CYS
0038	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0039	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	1.00	EACH
0040	720-44070	CASTING, 13, FURNISH AND ADJUST TO GRADE	4.00	EACH
0041	720-45030	INLET, E7	1.00	EACH
0042	720-45055	INLET, M10	1.00	EACH
0043	720-94208	MANHOLE, C10	1.00	EACH
0044	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	13.00	EACH
0045	801-01505	TEMPORARY PAVEMENT MESSAGE MARKING, (ONLY)	8.00	EACH
0046	801-02595	CONTROLLER RESET TIMING	3.00	EACH
0047	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4654.00	LFT
0048	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00	LS
0049	801-06640	CONSTRUCTION SIGN, A	14.00	EACH
0050	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
0051	801-06775	MAINTAINING TRAFFIC	1.00	LS
0052	801-07118	BARRICADE, III-A	24.00	LFT
0053	801-94295	SIGNAL HEAD RELOCATE	11.00	EACH
0054	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	47.00	LFT
0055	802-07060	SIGN, SHEET, RELOCATE	17.00	EACH
0056	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	60.00	SFT
0057	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	30.00	SFT
0058	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.00	EACH
0059	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	1.00	EACH
0060	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0061	805-08464	RADIO INTERCONNECT	1.00	EACH
0062	805-08493	RADIO INTERCONNECTION SYSTEM TESTING	1.00	LS
0063	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL	6.00	EACH
0064	805-09540	LOOP DETECTOR RACK	1.00	EACH
0065	805-11570	RADIO ANTENNA	1.00	EACH
0066	805-11744	HANDHOLE SIGNAL TYPE 2	1.00	EACH
0067	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	1322.00	LFT
0068	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	1.00	EACH

0069	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	2.00	EACH
0070	805-78415	SPAN, CATENARY, AND TETHER	4.00	EACH
0071	805-78420	DISCONNECT HANGER	2.00	EACH
0072	805-78445	SIGNAL SERVICE	1.00	EACH
0073	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	25.00	LFT
0074	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	2880.00	LFT
0075	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	341.00	LFT
0076	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	165.00	LFT
0077	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	313.00	LFT
0078	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	5688.00	LFT
0079	805-78785	SIGNAL DETECTOR HOUSING	7.00	EACH
0080	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	920.00	LFT
0081	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	1.00	EACH
0082	807-02370	LIGHT STRUCTURE, REMOVE AND RESET	1.00	EACH
0083	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	25.00	LFT
0084	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	250.00	LFT
0085	807-86955	CABLE-DUCT MARKER	1.00	EACH
0086	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	9.00	SYS
0087	808-06716	LINE, REMOVE	9291.00	LFT
0088	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	530.00	LFT
0089	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2423.00	LFT
0090	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1314.00	LFT
0091	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	793.00	LFT
0092	808-10042	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW 12 IN.	243.00	LFT
0093	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	143.00	LFT
0094	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	6.00	EACH
0095	808-10058	LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN.	995.00	LFT
0096	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	8.00	EACH
0097	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	225.00	LFT
0098	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	166.00	LFT
0099	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	235.00	LFT
0100	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	1.00	EACH
0101	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	1.00	EACH
0102	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	460.00	LFT

Call: 191

Contract: R -39629-A

Section No.: 1 SAFETY IMPROVEMENTS

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	11.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	306-08034	MILLING, ASPHALT, 1 1/2 IN.	13691.00	SYS
0013	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1130.00	TON
0014	401-10258	JOINT ADHESIVE, SURFACE	6741.30	LFT
0015	401-11785	LIQUID ASPHALT SEALANT	6741.30	LFT
0016	406-05520	ASPHALT FOR TACK COAT	3.40	TON
0017	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	163.00	LFT
0018	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0019	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	5095.00	LFT
0020	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0021	621-06560	MULCHED SEEDING U	1290.00	SYS
0022	716-09360	PIPE INSTALLATION, TRENCHLESS, 3 IN.	186.00	LFT
0023	716-09396	PIPE INSTALLATION, TRENCHLESS, 2 IN.	254.00	LFT
0024	801-06640	CONSTRUCTION SIGN, A	20.00	EACH
0025	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0026	801-06775	MAINTAINING TRAFFIC	1.00	LS
0027	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	16.00	LFT
0028	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	85.00	SFT
0029	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	254.00	LFT
0030	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0031	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	5.00	EACH

0032	805-02658	CABLE COAXIAL	4448.00	LFT
0033	805-04980	FLASHING BEACON	5.00	EACH
0034	805-06595	CONDUIT, PVC, 2 IN.	2136.00	LFT
0035	805-11887	THERMAL DETECTION CAMERA	7.00	EACH
0036	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	3577.00	LFT
0037	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0038	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	5.00	EACH
0039	805-90267	CONDUIT, STEEL, GALVANIZED, 3 IN.	186.00	LFT
0040	805-95568	CONDUIT, PVC, 4 IN.	225.00	LFT
0041	807-02191	HANDHOLE LIGHTING	18.00	EACH
0042	807-02194	SERVICE POINT II MODIFIED	1.00	EACH
0043	807-04651	WIRE	718.00	LFT
0044	807-04962	LIGHT	16.00	EACH
0045	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	3665.00	LFT
0046	807-11712	WIRE, NO. 6 COPPER, 1/C	51.00	LFT
0047	807-11980	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 30 IN. DIA X 96 IN.	16.00	EACH
0048	807-12344	WIRE XHHW, NO 8 COPPER, 1/C	16.00	LFT
0049	807-95889	WIRE, NO. 10 COPPER, 1/C	1152.00	LFT
0050	807-99338	WIRE, NO. 6 COPPER, GROUND, 1/C	318.00	LFT
0051	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0052	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	10027.00	LFT
0053	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	10190.00	LFT
0054	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	14.00	LFT
0055	808-12032	GROOVING FOR PAVEMENT MARKINGS	10027.00	LFT

Call: 201

Contract: R -39865-A

Section No.: 1 NOISE ABATEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	202-99187	FENCE, FARM FIELD, REMOVE	142.00	LFT
0010	205-12108	STORM WATER MANAGEMENT BUDGET	11155.00	DOL
0011	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0012	603-06040	FENCE, FARM FIELD, 47 IN.	165.00	LFT
0013	620-01754	SOUND BARRIER PANELS GROUND MOUNTED TYPE	15455.00	SFT
0014	620-01756	SOUND BARRIER ERECTION GROUND MOUNTED TYPE	15455.00	SFT
0015	620-08426	SOUND BARRIER DESIGN AND LAYOUT	1.00	LS
0016	628-09402	FIELD OFFICE, B	12.00	MOS
0017	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0018	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	30.00	LFT
0019	801-06640	CONSTRUCTION SIGN, A	10.00	EACH
0020	801-06775	MAINTAINING TRAFFIC	1.00	LS
0021	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	1.00	EACH

Call: 221

Contract: R -40447-A

Section No.: 1 SMALL STRUCTURES AND DRAINS CONSTRUCTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	202-02271	HEADWALL, REMOVE	7.00	EACH
0010	202-91385	INLET, REMOVE	15.00	EACH
0011	202-96133	PIPE, REMOVE	187.00	LFT
0012	205-12108	STORM WATER MANAGEMENT BUDGET	8870.00	DOL
0013	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0014	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	38.00	CYS
0015	601-06035	GUARDRAIL, RESET	20.00	LFT
0016	603-06060	FENCE, FARM FIELD, RESET	30.00	LFT
0017	616-06405	RIPRAP, REVETMENT	74.00	TON
0018	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	159.00	SYS
0019	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	40.00	LFT
0020	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	118.00	LFT
0021	715-08307	HMA FOR STRUCTURE INSTALLATION, TYPE D	5.00	TON
0022	715-09064	VIDEO INSPECTION FOR PIPE	961.00	LFT
0023	715-46000	PIPE END SECTION, DIAMETER 12 IN.	9.00	EACH
0024	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0025	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0026	716-07630	PIPE INSTALLATION, TRENCHLESS, 12 IN.	580.00	LFT
0027	716-07631	PIPE INSTALLATION, TRENCHLESS, 15 IN.	93.00	LFT
0028	716-07632	PIPE INSTALLATION, TRENCHLESS, 18 IN.	170.00	LFT
0029	718-06528	OUTLET PROTECTOR, 1	1.00	EACH
0030	720-45035	INLET, F7	1.00	EACH
0031	720-45045	INLET, J10	3.00	EACH

0032	720-45055	INLET, M10	1.00	EACH
0033	720-45070	INLET, P12A	4.00	EACH
0034	720-45075	INLET, R13	1.00	EACH
0035	720-45130	INLET, E7 MODIFIED	1.00	EACH
0036	720-45135	INLET, F7 MODIFIED	2.00	EACH
0037	801-06640	CONSTRUCTION SIGN, A	28.00	EACH
0038	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0039	801-06775	MAINTAINING TRAFFIC	1.00	LS
0040	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	8.00	EACH
0041	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2500.00	LFT
0042	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	400.00	LFT

Call: 231

Contract: R -40730-A

Section No.: 1 INTERSECTION IMPROVEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	648.00	SYS
0013	202-74045	SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	6.00	EACH
0014	202-91385	INLET, REMOVE	1.00	EACH
0015	202-93615	CONCRETE, REMOVE	103.248	SYS
0016	202-96133	PIPE, REMOVE	6.00	LFT
0017	203-02000	EXCAVATION, COMMON	525.00	CYS
0018	205-12108	STORM WATER MANAGEMENT BUDGET	3000.00	DOL
0019	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	1000.00	SYS
0021	211-09264	STRUCTURE BACKFILL, TYPE 1	54.00	CYS
0022	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	100.00	SYS
0023	302-07455	DENSE GRADED SUBBASE	80.00	CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	53.00	TON
0025	306-08038	MILLING, ASPHALT, 4 IN.	275.00	SYS
0026	306-08041	MILLING, PCCP	73.00	SYS
0027	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	87.00	TON
0028	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	141.00	TON
0029	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	237.00	TON
0030	401-10258	JOINT ADHESIVE, SURFACE	405.00	LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	405.00	LFT

0032	401-11785	LIQUID ASPHALT SEALANT	358.00	LFT
0033	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0034	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	0.50	TON
0035	502-06329	PCCP, 12 IN.	126.00	SYS
0036	503-03489	RETROFITTED TIE BARS	395.00	EACH
0037	503-05240	D-1 CONTRACTION JOINT	54.00	LFT
0038	605-06205	CENTER CURB, B CONCRETE	105.50	LFT
0039	605-06240	CENTER CURB, A CONCRETE	373.00	SYS
0040	616-06451	RIPRAP, UNIFORM	79.00	TON
0041	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	144.00	SYS
0042	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0043	621-02770	EROSION CONTROL BLANKET	473.333	SYS
0044	621-06545	FERTILIZER	1.00	TON
0045	621-06553	SEED MIXTURE R	15.00	LBS
0046	621-06567	WATER	1.00	kGAL
0047	621-06574	SODDING	135.00	SYS
0048	628-09401	FIELD OFFICE, A	8.00	MOS
0049	715-04611	SAFETY METAL END SECTION, 4:1, DIA 12 IN.	1.00	EACH
0050	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	239.00	LFT
0051	715-09064	VIDEO INSPECTION FOR PIPE	239.00	LFT
0052	720-45005	INLET, A2	2.00	EACH
0053	720-45069	INLET, P12	1.00	EACH
0054	720-45410	MANHOLE, C4	1.00	EACH
0055	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0056	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3151.78	LFT
0057	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	6.00	EACH
0058	801-06212	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (ONLY)	3.00	EACH
0059	801-06625	DETOUR ROUTE MARKER ASSEMBLY	12.00	EACH
0060	801-06640	CONSTRUCTION SIGN, A	18.00	EACH
0061	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0062	801-06710	FLASHING ARROW SIGN	60.00	DAY
0063	801-06775	MAINTAINING TRAFFIC	1.00	LS
0064	801-07118	BARRICADE, III-A	84.00	LFT
0065	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	88.00	LFT
0066	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	35.00	SFT
0067	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	12.00	SFT
0068	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	21.00	SFT

0069	808-06716	LINE, REMOVE	120.00	LFT
0070	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	61.00	LFT
0071	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	612.04	LFT
0072	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	712.80	LFT
0073	808-10042	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW 12 IN.	89.00	LFT
0074	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	232.50	LFT
0075	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	24.00	LFT
0076	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	3.00	EACH
0077	808-10058	LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN.	103.40	LFT
0078	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	3.00	EACH
0079	808-11776	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 24 IN.	21.10	LFT
0080	808-12032	GROOVING FOR PAVEMENT MARKINGS	1529.24	LFT

Call: 235

Contract: R -40733-A

Section No.: 1 ROAD RECONSTRUCTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	33700.00	SYS
0013	202-02271	HEADWALL, REMOVE	2.00	EACH
0014	202-02278	CURB, CONCRETE, REMOVE	4592.00	LFT
0015	202-02279	CURB AND GUTTER, REMOVE	513.00	LFT
0016	202-91385	INLET, REMOVE	14.00	EACH
0017	202-93741	GUARDRAIL, END TREATMENT, REMOVE	4.00	EACH
0018	202-96133	PIPE, REMOVE	713.00	LFT
0019	203-02000	EXCAVATION, COMMON	9820.00	CYS
0020	205-12108	STORM WATER MANAGEMENT BUDGET	21200.00	DOL
0021	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0022	207-08264	SUBGRADE TREATMENT, TYPE II	1316.00	SYS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	29739.00	SYS
0024	207-09935	SUBGRADE TREATMENT, TYPE IC	7428.00	SYS
0025	211-09264	STRUCTURE BACKFILL, TYPE 1	257.00	CYS
0026	303-07449	COMPACTED AGGREGATE NO. 73	2659.00	TON
0027	304-07491	HMA PATCHING, TYPE C	5.00	TON
0028	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	2668.00	TON
0029	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	4481.00	TON
0030	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	13074.00	TON
0031	401-10258	JOINT ADHESIVE, SURFACE	20173.00	LFT

0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	20173.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	20173.00	LFT
0034	402-10086	HMA FOR TEMPORARY PAVEMENT, C	98.00	TON
0035	406-05520	ASPHALT FOR TACK COAT	25.00	TON
0036	506-06333	PCCP PATCHING, FULL DEPTH	19.00	SYS
0037	601-02241	GUARDRAIL, REMOVE	1247.00	LFT
0038	601-05999	CURVED TERMINAL END	3.00	EACH
0039	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1238.00	LFT
0040	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	1.00	EACH
0041	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0042	605-06140	CURB AND GUTTER, CONCRETE	750.00	LFT
0043	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	4907.00	LFT
0044	610-09108	PCCP FOR APPROACHES, 9 IN.	1062.00	SYS
0045	615-06505	MONUMENT, B	13.00	EACH
0046	616-06405	RIPRAP, REVETMENT	19.00	TON
0047	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	45.00	SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0049	621-06545	FERTILIZER	2.00	TON
0050	621-06554	SEED MIXTURE U	598.00	LBS
0051	621-06565	MULCHING MATERIAL	6.00	TON
0052	628-09402	FIELD OFFICE, B	12.00	MOS
0053	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0054	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	169.00	LFT
0055	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	671.00	LFT
0056	715-09064	VIDEO INSPECTION FOR PIPE	840.00	LFT
0057	715-46000	PIPE END SECTION, DIAMETER 12 IN.	6.00	EACH
0058	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	EACH
0059	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00	EACH
0060	720-03757	MANHOLE, C15	3.00	EACH
0061	720-45235	CATCH BASIN, E7	6.00	EACH
0062	720-94432	MANHOLE, C7	1.00	EACH
0063	720-98174	INLET, B15	1.00	EACH
0064	801-03290	CONSTRUCTION SIGN, C	3.00	EACH
0065	801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.00	EACH
0066	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	41492.00	LFT
0067	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	8.00	EACH
0068	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	11.00	LFT

0069	801-06625	DETOUR ROUTE MARKER ASSEMBLY	7.00	EACH
0070	801-06640	CONSTRUCTION SIGN, A	46.00	EACH
0071	801-06645	CONSTRUCTION SIGN, B	17.00	EACH
0072	801-06710	FLASHING ARROW SIGN	570.00	DAY
0073	801-06775	MAINTAINING TRAFFIC	1.00	LS
0074	801-07118	BARRICADE, III-A	264.00	LFT
0075	802-04089	SIGN, SHEET, REMOVE	4.00	EACH
0076	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	140.00	LFT
0077	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	45.00	LFT
0078	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	7.00	EACH
0079	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	71.00	SFT
0080	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	18.00	SFT
0081	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	3220.00	LFT
0082	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	10112.00	LFT
0083	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	137.00	LFT
0084	808-06716	LINE, REMOVE	15087.00	LFT
0085	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0086	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	225.00	LFT
0087	808-12032	GROOVING FOR PAVEMENT MARKINGS	20229.00	LFT
0088	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1029.00	LFT
0089	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5506.00	LFT
0090	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	22.00	LFT
0091	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	44.00	LFT
0092	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	14.00	EACH
0093	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	2.00	EACH

Call: 241

Contract: R -40983-A

Section No.: 1 CONSTRUCT ADA APPROVED SIDEWALK RAMPS

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	202-02278	CURB, CONCRETE, REMOVE	1390.00	LFT
0010	202-02279	CURB AND GUTTER, REMOVE	304.00	LFT
0011	202-02772	CASTING, REMOVE	1.00	EACH
0012	202-52710	SIDEWALK CONCRETE, REMOVE	1005.00	SYS
0013	205-12108	STORM WATER MANAGEMENT BUDGET	2400.00	DOL
0014	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0015	304-07490	HMA PATCHING, TYPE B	75.00	TON
0016	306-08159	MILLING, ASPHALT	137.00	SYS
0017	604-06070	SIDEWALK, CONCRETE	378.00	SYS
0018	604-08086	CURB RAMP, CONCRETE	694.00	SYS
0019	604-11975	SIDEWALK, CONCRETE, RE-LAY	25.00	SYS
0020	604-12083	DETECTABLE WARNING SURFACES	110.00	SYS
0021	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	3.00	SYS
0022	605-06120	CURB, CONCRETE	1923.00	LFT
0023	605-06140	CURB AND GUTTER, CONCRETE	300.00	LFT
0024	621-06575	SODDING, NURSERY	1048.00	SYS
0025	628-09402	FIELD OFFICE, B	8.00	MOS
0026	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0027	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0028	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	8.00	MOS
0029	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0030	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	70.00	LFT
0031	715-05422	PIPE, SLOTTED DRAIN, 12 IN.	33.00	LFT

0032	720-44015	CASTING, 2, FURNISH AND ADJUST TO GRADE	1.00	EACH
0033	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0034	801-06645	CONSTRUCTION SIGN, B	9.00	EACH
0035	801-06775	MAINTAINING TRAFFIC	1.00	LS
0036	802-91122	SIGN GROUND MOUNTED RESET	8.00	EACH
0037	808-05929	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 8 IN.	394.00	LFT
0038	808-06368	TRANSVERSE MARKING, REMOVE	394.00	LFT
0039	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	96.00	LFT

Call: 261

Contract: R -41662-A

Section No.: 1 INSTALL NEW GUARDRAIL

Line

Item No	Item Code	Description	Quantity Unit	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	5.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	5.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0010	202-93741	GUARDRAIL, END TREATMENT, REMOVE	1.00	EACH
0011	601-02241	GUARDRAIL, REMOVE	40.00	LFT
0012	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	4172.00	LFT
0013	601-12282	GUARDRAIL, MGS W-BEAM, 3 FT 1.5 IN SPACING	25.00	LFT
0014	601-12283	GUARDRAIL, MGS W-BEAM, 1 FT 6.75 IN SPACING	12.50	LFT
0015	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	5.00	EACH
0016	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	1.00	EACH
0017	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	4.00	EACH
0018	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 271

Contract: R -41673-A

Section No.: 1 CURVE CORRECTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	3.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	202-96133	PIPE, REMOVE	73.00	LFT
0012	203-02000	EXCAVATION, COMMON	163.89	CYS
0013	205-11626	PUMP AROUND	1.00	EACH
0014	205-12108	STORM WATER MANAGEMENT BUDGET	15000.00	DOL
0015	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0016	207-09935	SUBGRADE TREATMENT, TYPE IC	315.00	SYS
0017	211-02050	B BORROW	78.00	CYS
0018	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	34.62	CYS
0019	306-08034	MILLING, ASPHALT, 1 1/2 IN.	215.83	SYS
0020	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	41.88	TON
0021	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	166.79	TON
0022	401-10258	JOINT ADHESIVE, SURFACE	345.00	LFT

0023	401-10259	JOINT ADHESIVE, INTERMEDIATE	420.50	LFT
0024	401-11785	LIQUID ASPHALT SEALANT	345.00	LFT
0025	406-05521	ASPHALT FOR TACK COAT	504.63	SYS
0026	616-06451	RIPRAP, UNIFORM	15.26	TON
0027	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	20.40	SYS
0028	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0029	621-06545	FERTILIZER	0.03	TON
0030	621-06553	SEED MIXTURE R	10.92	LBS
0031	621-06565	MULCHING MATERIAL	0.13	TON
0032	621-06574	SODDING	108.00	SYS
0033	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	122.00	LFT
0034	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0035	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0036	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	EACH
0037	801-06640	CONSTRUCTION SIGN, A	15.00	EACH
0038	801-06645	CONSTRUCTION SIGN, B	1.00	EACH
0039	801-06775	MAINTAINING TRAFFIC	1.00	LS
0040	801-07118	BARRICADE, III-A	32.00	LFT
0041	801-07119	BARRICADE, III-B	64.00	LFT
0042	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	25.50	LFT
0043	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	3.00	EACH
0044	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	246.00	LFT
0045	808-06716	LINE, REMOVE	84.30	LFT
0046	808-12032	GROOVING FOR PAVEMENT MARKINGS	246.00	LFT
0047	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	17.00	LFT

Call: 281

Contract: R -41679-A

Section No.: 1 PAVEMENT REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL

0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	17698.00	SYS
0013	203-02000	EXCAVATION, COMMON	1944.00	CYS
0014	203-02020	EXCAVATION, UNCLASSIFIED	1541.00	CYS
0015	205-12108	STORM WATER MANAGEMENT BUDGET	44200.00	DOL
0016	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0017	207-09934	SUBGRADE TREATMENT, TYPE IB	22235.00	SYS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	10649.00	SYS
0019	211-06467	AGGREGATE FOR END BENT BACKFILL	1068.00	CYS
0020	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	2161.00	SYS
0021	302-06464	SUBBASE FOR PCCP	5620.00	CYS
0022	302-06464	SUBBASE FOR PCCP	279.00	CYS

0023	302-07455	DENSE GRADED SUBBASE	132.00	CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	5378.00	TON
0025	306-08034	MILLING, ASPHALT, 1 1/2 IN.	17996.00	SYS
0026	306-08036	MILLING, ASPHALT, 2 IN.	1136.00	SYS
0027	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1703.00	TON
0028	401-07356	QC/QA-HMA, 2, 64, INTERMEDIATE, 9.5 mm	257.00	TON
0029	401-10258	JOINT ADHESIVE, SURFACE	32455.00	LFT
0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	4055.00	LFT
0031	401-11785	LIQUID ASPHALT SEALANT	32455.00	LFT
0032	402-10084	HMA FOR TEMPORARY PAVEMENT, B	2233.00	TON
0033	406-05520	ASPHALT FOR TACK COAT	7.00	TON
0034	501-06266	PROFILOGRAPH PCCP	1.00	LS
0035	501-06322	QC/QA-PCCP, 11 IN.	22448.00	SYS
0036	501-06727	CORING, PCCP	1.00	LS
0037	503-03489	RETROFITTED TIE BARS	128.00	EACH
0038	503-05240	D-1 CONTRACTION JOINT	14046.00	LFT
0039	506-06333	PCCP PATCHING, FULL DEPTH	526.00	SYS
0040	506-06334	PCCP PATCHING, PARTIAL DEPTH	73.00	SYS
0041	507-08272	JOINTS IN PCCP, SAW AND SEAL	27195.00	LFT
0042	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	2.00	EACH
0043	601-01700	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 1	4.00	EACH
0044	601-02241	GUARDRAIL, REMOVE	894.60	LFT
0045	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1113.00	LFT
0046	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00	EACH
0047	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0048	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0049	605-06255	CENTER CURB, D CONCRETE	2017.00	SYS
0050	606-11064	MILLED PCCP CORRUGATIONS, CONVENTIONAL	6006.00	LFT
0051	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	25033.00	LFT
0052	609-06258	REINFORCED CONCRETE BRIDGE APPROACH, 11 IN.	789.00	SYS
0053	616-04312	GEOTEXTILE FOR PAVEMENT STABILIZATION	22892.00	SYS
0054	616-05689	RIPRAP, CLASS 2	238.00	TON
0055	616-06405	RIPRAP, REVETMENT	138.00	TON
0056	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	178.00	SYS
0057	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	331.00	SYS
0058	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0059	621-06554	SEED MIXTURE U	289.00	LBS

0060	628-09403	FIELD OFFICE, C	12.00	MOS
0061	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0062	702-51001	CONCRETE, A, SUPERSTRUCTURE	62.00	CYS
0063	702-51863	FIELD DRILLED HOLE IN CONCRETE	182.00	EACH
0064	703-06029	REINFORCING BARS, EPOXY COATED	43140.00	LBS
0065	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	450.00	EACH
0066	704-51002	CONCRETE, C, SUPERSTRUCTURE	399.00	CYS
0067	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0068	709-51821	SURFACE SEAL	1.00	LS
0069	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	8498.00	LFT
0070	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	860.00	LFT
0071	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0072	718-06528	OUTLET PROTECTOR, 1	22.00	EACH
0073	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	8498.00	LFT
0074	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	6761.00	SYS
0075	718-52610	AGGREGATE FOR UNDERDRAINS	1059.00	CYS
0076	720-44000	CASTING, ADJUST TO GRADE	2.00	EACH
0077	724-12103	PRE-COMPRESSED FOAM JOINT	250.00	LFT
0078	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0079	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0080	801-06196	DETOUR ROUTE MARKER ASSEMBLY, MULTIPLE ROUTES	28.00	EACH
0081	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	85997.00	LFT
0082	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	5600.00	LFT
0083	801-06625	DETOUR ROUTE MARKER ASSEMBLY	21.00	EACH
0084	801-06640	CONSTRUCTION SIGN, A	49.00	EACH
0085	801-06645	CONSTRUCTION SIGN, B	11.00	EACH
0086	801-06710	FLASHING ARROW SIGN	250.00	DAY
0087	801-06775	MAINTAINING TRAFFIC	1.00	LS
0088	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	3.00	EACH
0089	801-07119	BARRICADE, III-B	240.00	LFT
0090	801-07606	TEMPORARY CROSSEVER DRAINAGE PIPE	205.00	LFT
0091	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2340.00	LFT
0092	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0093	801-52817	TEMPORARY CROSSEVER, B	1.00	EACH
0094	804-11920	DELINEATOR POST FLEXIBLE, TYPE I	120.00	EACH
0095	805-11744	HANDHOLE SIGNAL TYPE 2	1.00	EACH
0096	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	281.00	LFT

0097	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	642.00	LFT
0098	805-78785	SIGNAL DETECTOR HOUSING	3.00	EACH
0099	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	281.00	LFT
0100	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	378.00	LFT
0101	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1710.00	LFT
0102	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7055.00	LFT
0103	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0104	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	4664.00	LFT
0105	808-10032	LINE, MULTI-COMPONENT, DOTTED, WHITE, 8 IN.	1259.00	LFT
0106	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	18646.00	LFT
0107	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	17607.00	LFT
0108	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	1730.00	LFT
0109	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	72.00	LFT
0110	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	6.00	EACH
0111	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	9.00	EACH
0112	808-12032	GROOVING FOR PAVEMENT MARKINGS	58760.00	LFT
0113	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7055.00	LFT
0114	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	352.00	EACH
0115	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	352.00	EACH

Call: 321

Contract: R -41815-A

Section No.: 1 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02928	CATCH BASIN, REMOVE	1.00	EACH

0013	202-96133	PIPE, REMOVE	63.00	LFT
0014	203-02000	EXCAVATION, COMMON	4708.00	CYS
0015	203-02070	BORROW	1392.00	CYS
0016	205-12108	STORM WATER MANAGEMENT BUDGET	1.00	DOL
0017	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	5517.00	SYS
0019	211-09264	STRUCTURE BACKFILL, TYPE 1	185.00	CYS
0020	303-01180	COMPACTED AGGREGATE NO. 53	667.00	TON
0021	304-07493	WIDENING WITH HMA, TYPE B	2.00	TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	11390.00	SYS

0023	401-06264	PROFILOGRAPH, HMA	1.00	LS
0024	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	1420.00	TON
0025	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	793.00	TON
0026	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	994.00	TON
0027	401-10258	JOINT ADHESIVE, SURFACE	9064.00	LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	2238.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	9064.00	LFT
0030	406-05521	ASPHALT FOR TACK COAT	26603.00	SYS
0031	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0032	604-06070	SIDEWALK, CONCRETE	65.00	SYS
0033	605-02493	CURB, ISLAND CONCRETE	80.00	SYS
0034	605-06140	CURB AND GUTTER, CONCRETE	672.00	LFT
0035	605-06145	CURB AND GUTTER, B, CONCRETE	127.00	LFT
0036	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	14.00	LFT
0037	615-06490	RIGHT-OF-WAY MARKER	16.00	EACH
0038	615-06505	MONUMENT, B	2.00	EACH
0039	616-06405	RIPRAP, REVETMENT	227.00	TON
0040	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	296.00	SYS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0042	621-06574	SODDING	133.00	SYS
0043	628-09402	FIELD OFFICE, B	15.00	MOS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0045	628-11977	COMPUTER SYSTEM	2.00	EACH
0046	715-05118	PIPE, TYPE 1, CIRCULAR, 12 IN.	39.00	LFT
0047	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	130.00	LFT
0048	715-05148	PIPE, TYPE 2, CIRCULAR, 10 IN.	17.00	LFT
0049	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	32.00	LFT
0050	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	149.00	LFT
0051	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0052	715-46020	PIPE END SECTION, DIAMETER 24 IN.	4.00	EACH
0053	715-90325	PIPE END SECTION, DIAMETER 10 IN.	1.00	EACH
0054	720-44000	CASTING, ADJUST TO GRADE	8.00	EACH
0055	720-98174	INLET, B15	2.00	EACH
0056	720-98555	INLET, C15	2.00	EACH
0057	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	5283.00	LFT
0058	801-06640	CONSTRUCTION SIGN, A	15.00	EACH
0059	801-06645	CONSTRUCTION SIGN, B	2.00	EACH

0060	801-06710	FLASHING ARROW SIGN	360.00	DAY
0061	801-06775	MAINTAINING TRAFFIC	1.00	LS
0062	801-07118	BARRICADE, III-A	33.00	LFT
0063	802-04089	SIGN, SHEET, REMOVE	2.00	EACH
0064	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	41.00	LFT
0065	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	105.00	SFT
0066	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	64.00	SFT
0067	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0068	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00	EACH
0069	805-01842	HANDHOLE SIGNAL TYPE 1	7.00	EACH
0070	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1870.00	LFT
0071	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0072	805-08244	CELLULAR MODEM KIT	1.00	EACH
0073	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	10.00	EACH
0074	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	2.00	EACH
0075	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	1.00	EACH
0076	805-78415	SPAN, CATENARY, AND TETHER	4.00	EACH
0077	805-78420	DISCONNECT HANGER	4.00	EACH
0078	805-78445	SIGNAL SERVICE	1.00	EACH
0079	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	70.00	LFT
0080	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	5440.00	LFT
0081	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	160.00	LFT
0082	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	70.00	LFT
0083	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	920.00	LFT
0084	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	3990.00	LFT
0085	805-78785	SIGNAL DETECTOR HOUSING	15.00	EACH
0086	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1670.00	LFT
0087	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0088	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	4.00	EACH
0089	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	9.00	EACH
0090	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	3.00	SYS
0091	808-06368	TRANSVERSE MARKING, REMOVE	34.00	LFT
0092	808-06716	LINE, REMOVE	927.00	LFT
0093	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0094	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1040.00	LFT
0095	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	8341.00	LFT
0096	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	6041.00	LFT

0097	808-12032	GROOVING FOR PAVEMENT MARKINGS	15837.00	LFT
0098	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	80.00	LFT
0099	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	22.00	LFT
0100	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	54.00	LFT
0101	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	259.00	LFT
0102	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	15.00	EACH
0103	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	199.00	EACH
0104	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	214.00	EACH

Call: 401

Contract: RS-37727-A

Section No.: 1 ASPHALT RESURFACE

Line

Item No	Item Code	Description	Quantity Unit	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	10360.00	SYS
0013	202-90277	DETECTOR HOUSING, REMOVE	21.00	EACH
0014	203-02000	EXCAVATION, COMMON	782.00	CYS
0015	203-02070	BORROW	500.00	CYS
0016	205-06937	TEMPORARY SILT FENCE	200.00	LFT
0017	205-11584	TEMPORARY CHECK DAM, TRAVERSABLE	10.00	LFT
0018	205-12108	STORM WATER MANAGEMENT BUDGET	1.00	DOL
0019	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	12914.00	SYS
0021	211-09194	B BORROW	10.00	TON
0022	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	11395.00	SYS

0023	302-07455	DENSE GRADED SUBBASE	170.00	CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	2794.00	TON
0025	303-01180	COMPACTED AGGREGATE NO. 53	1073.00	TON
0026	304-07491	HMA PATCHING, TYPE C	319.00	TON
0027	304-07493	WIDENING WITH HMA, TYPE B	50.00	TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	3452.00	SYS
0029	306-08038	MILLING, ASPHALT, 4 IN.	2830.00	SYS
0030	306-08042	MILLING, SCARIFICATION	368371.00	SYS
0031	306-08043	MILLING, TRANSITION	400.00	SYS
0032	306-08432	MILLING, APPROACH	11879.00	SYS
0033	401-06264	PROFILOGRAPH, HMA	1.00	LS
0034	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	890.00	TON
0035	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2447.00	TON
0036	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1009.00	TON
0037	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	4079.00	TON
0038	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	4900.00	TON
0039	401-10258	JOINT ADHESIVE, SURFACE	15270.00	LFT
0040	401-10259	JOINT ADHESIVE, INTERMEDIATE	15270.00	LFT
0041	401-11785	LIQUID ASPHALT SEALANT	15270.00	LFT
0042	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	155.00	TON
0043	406-05520	ASPHALT FOR TACK COAT	35.00	TON
0044	414-11468	ULTRATHIN BONDED WEARING COURSE 9.5 mm	345584.00	SYS
0045	503-03489	RETROFITTED TIE BARS	150.00	EACH
0046	503-05240	D-1 CONTRACTION JOINT	100.00	LFT
0047	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	380.00	LFT
0048	506-06333	PCCP PATCHING, FULL DEPTH	1435.00	SYS
0049	506-06334	PCCP PATCHING, PARTIAL DEPTH	162.00	SYS
0050	507-08269	CRACKS IN PCCP, FILLED	1000.00	LFT
0051	507-08271	JOINTS IN PCCP, FILLED	13470.00	LFT
0052	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	83325.00	LFT
0053	610-07487	HMA FOR APPROACHES, TYPE B	1453.00	TON
0054	615-06525	CASTING ADJUST TO GRADE, MONUMENT	6.00	EACH
0055	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0056	621-06559	MULCHED SEEDING R	1200.00	SYS
0057	628-09403	FIELD OFFICE, C	12.00	MOS
0058	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0059	702-90915	CONCRETE, CLASS, A	5.00	CYS

0060	703-06029	REINFORCING BARS, EPOXY COATED	38.00	LBS
0061	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	20.00	LFT
0062	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0063	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0064	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	17810.00	LFT
0065	801-06204	TEMPORARY PAVEMENT MARKING, 5 IN.	8445.00	LFT
0066	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8510.00	LFT
0067	801-06640	CONSTRUCTION SIGN, A	44.00	EACH
0068	801-06710	FLASHING ARROW SIGN	90.00	DAY
0069	801-06775	MAINTAINING TRAFFIC	1.00	LS
0070	801-07119	BARRICADE, III-B	150.00	LFT
0071	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	3800.00	LFT
0072	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	144.00	LFT
0073	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	12.00	EACH
0074	801-12324	LAW ENFORCEMENT OFFICER	2400.00	HRS
0075	801-12348	TEMPORARY WORKSITE SPEED DISPLAY ASSEMBLY	4.00	EACH
0076	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0077	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	9750.00	LFT
0078	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	975.00	LFT
0079	805-78785	SIGNAL DETECTOR HOUSING	21.00	EACH
0080	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	3120.00	LFT
0081	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	550.00	LFT
0082	808-06702	LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	20832.00	LFT
0083	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	97627.00	LFT
0084	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	2360.00	LFT
0085	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	41.00	LFT
0086	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	8693.00	LFT
0087	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	8693.00	LFT
0088	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	30.00	LFT
0089	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0090	808-12032	GROOVING FOR PAVEMENT MARKINGS	206509.00	LFT
0091	808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	548.00	LFT
0092	808-75008	LINE, PAINT, SOLID, WHITE, 8 IN.	340.00	LFT
0093	808-75072	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE 24 IN.	51.00	LFT
0094	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	85140.00	LFT
0095	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	354.00	LFT
0096	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	530.00	LFT

0097	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	42.00	EACH
0098	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1054.00	EACH
0099	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1054.00	EACH

Call: 411

Contract: RS-38590-A

Section No.: 1 AUXILIARY LANES

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02278	CURB, CONCRETE, REMOVE	1996.00	LFT
0014	202-02279	CURB AND GUTTER, REMOVE	318.00	LFT
0015	202-03875	CONCRETE STEPS, REMOVE	6.00	EACH
0016	202-06580	CONTAMINATED SOIL, REMOVE	16.00	CYS
0017	202-07553	REGULATED MATERIALS, REMOVE, TYPE Y	16.00	CYS
0018	202-07554	REGULATED MATERIALS, TRANSPORT, TYPE Y	16.00	CYS
0019	202-07555	REGULATED MATERIALS, DISPOSE, TYPE Y	16.00	CYS
0020	202-52710	SIDEWALK CONCRETE, REMOVE	1415.00	SYS
0021	202-90747	RETAINING WALL, REMOVE	93.00	LFT
0022	202-91385	INLET, REMOVE	19.00	EACH

0023	202-96133	PIPE, REMOVE	98.00	LFT
0024	202-96328	FOUNDATION, STREET LIGHT, REMOVE	1.00	EACH
0025	203-02000	EXCAVATION, COMMON	1064.00	CYS
0026	203-02010	EXCAVATION, ROCK	10.00	CYS
0027	205-12108	STORM WATER MANAGEMENT BUDGET	39633.00	DOL
0028	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0029	207-08264	SUBGRADE TREATMENT, TYPE II	406.00	SYS
0030	207-09935	SUBGRADE TREATMENT, TYPE IC	7795.00	SYS
0031	211-09265	STRUCTURE BACKFILL, TYPE 2	270.00	CYS
0032	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	200.00	SYS
0033	301-12232	COMPACTED AGGREGATE NO 5	57.00	CYS
0034	301-12234	COMPACTED AGGREGATE NO 53	153.00	CYS
0035	303-01180	COMPACTED AGGREGATE NO. 53	466.00	TON
0036	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	100.00	TON
0037	304-07491	HMA PATCHING, TYPE C	2885.00	TON
0038	305-07468	PCC BASE PATCHING, 12 IN.	5.00	SYS
0039	306-08034	MILLING, ASPHALT, 1 1/2 IN.	26710.00	SYS
0040	306-08038	MILLING, ASPHALT, 4 IN.	40890.00	SYS
0041	306-08043	MILLING, TRANSITION	934.00	SYS
0042	306-08432	MILLING, APPROACH	32.00	SYS
0043	306-11872	MILLING, PROFILE	2394.00	SYS
0044	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	6065.00	TON
0045	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	6057.00	TON
0046	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	602.00	TON
0047	401-10258	JOINT ADHESIVE, SURFACE	46683.00	LFT
0048	401-10259	JOINT ADHESIVE, INTERMEDIATE	27595.00	LFT
0049	401-11785	LIQUID ASPHALT SEALANT	46683.00	LFT
0050	406-05520	ASPHALT FOR TACK COAT	30.40	TON
0051	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	4.30	TON
0052	604-06070	SIDEWALK, CONCRETE	488.00	SYS
0053	604-06070	SIDEWALK, CONCRETE	230.00	SYS
0054	604-08086	CURB RAMP, CONCRETE	291.00	SYS
0055	604-08086	CURB RAMP, CONCRETE	563.00	SYS
0056	604-12083	DETECTABLE WARNING SURFACES	124.00	SYS
0057	604-44251	STEPS, CONCRETE	2.00	CYS
0058	604-92237	HAND RAIL, STEEL	32.00	LFT
0059	605-06120	CURB, CONCRETE	2203.00	LFT

0060	605-06140	CURB AND GUTTER, CONCRETE	253.00	LFT
0061	607-06175	GUTTER, CONCRETE, A	180.00	LFT
0062	610-07487	HMA FOR APPROACHES, TYPE B	204.00	TON
0063	610-08446	PCCP FOR APPROACHES, 6 IN.	144.00	SYS
0064	610-09108	PCCP FOR APPROACHES, 9 IN.	133.00	SYS
0065	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00	EACH
0066	611-06498	MAILBOX ASSEMBLY, DOUBLE	1.00	EACH
0067	615-06490	RIGHT-OF-WAY MARKER	7.00	EACH
0068	615-06505	MONUMENT, B	6.00	EACH
0069	615-06510	MONUMENT, C	1.00	EACH
0070	616-06451	RIPRAP, UNIFORM	6.00	TON
0071	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	13.00	SYS
0072	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0073	621-06567	WATER	6.00	kGAL
0074	621-06575	SODDING, NURSERY	2212.00	SYS
0075	628-09402	FIELD OFFICE, B	20.00	MOS
0076	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	EACH
0077	702-44240	CONCRETE, A, STRUCTURES	2.00	CYS
0078	702-90915	CONCRETE, CLASS, A	15.00	CYS
0079	703-06028	REINFORCING BARS	9700.00	LBS
0080	703-06029	REINFORCING BARS, EPOXY COATED	1302.00	LBS
0081	708-01112	GROUT, NON-SHRINK	0.50	CYS
0082	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	87.00	LFT
0083	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	14.00	LFT
0084	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	32.00	LFT
0085	715-94530	ADJUST WATER VALVE TO GRADE	38.00	EACH
0086	720-44000	CASTING, ADJUST TO GRADE	61.00	EACH
0087	720-44000	CASTING, ADJUST TO GRADE	84.00	EACH
0088	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0089	720-45045	INLET, J10	18.00	EACH
0090	720-45055	INLET, M10	1.00	EACH
0091	720-45410	MANHOLE, C4	1.00	EACH
0092	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	EACH
0093	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	3992.00	LFT
0094	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	68257.00	LFT
0095	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	2.00	EACH
0096	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	152.00	LFT

0097	801-06625	DETOUR ROUTE MARKER ASSEMBLY	15.00	EACH
0098	801-06640	CONSTRUCTION SIGN, A	68.00	EACH
0099	801-06645	CONSTRUCTION SIGN, B	43.00	EACH
0100	801-06710	FLASHING ARROW SIGN	180.00	DAY
0101	801-06775	MAINTAINING TRAFFIC	1.00	LS
0102	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	5.00	EACH
0103	801-07118	BARRICADE, III-A	84.00	LFT
0104	801-07119	BARRICADE, III-B	292.00	LFT
0105	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	810.00	LFT
0106	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH
0107	802-04893	REFERENCE POST	1.00	EACH
0108	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	52.00	LFT
0109	802-07060	SIGN, SHEET, RELOCATE	52.00	EACH
0110	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	190.30	SFT
0111	802-76055	SIGN POST, A	306.00	LFT
0112	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.00	EACH
0113	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	12.00	EACH
0114	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	940.00	LFT
0115	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0116	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	16.00	EACH
0117	805-02437	CONTROLLER, RELOCATE AND REWIRE	3.00	EACH
0118	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	12.00	EACH
0119	805-05405	SIGNAL POLE, PEDESTAL, 4FT	12.00	EACH
0120	805-06595	CONDUIT, PVC, 2 IN.	1410.00	LFT
0121	805-09540	LOOP DETECTOR RACK	3.00	EACH
0122	805-11817	PEDESTRIAN PUSH BUTTON, APS	16.00	EACH
0123	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	19.00	EACH
0124	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	6.00	EACH
0125	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	1.00	EACH
0126	805-78415	SPAN, CATENARY, AND TETHER	12.00	EACH
0127	805-78420	DISCONNECT HANGER	12.00	EACH
0128	805-78445	SIGNAL SERVICE	3.00	EACH
0129	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	300.00	LFT
0130	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	6812.00	LFT
0131	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	1710.00	LFT
0132	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	1100.00	LFT
0133	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	1855.00	LFT

0134	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	1680.00	LFT
0135	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	3490.00	LFT
0136	805-78785	SIGNAL DETECTOR HOUSING	21.00	EACH
0137	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2776.00	LFT
0138	805-78925	CONTROLLER CABINET FOUNDATION, P1	3.00	EACH
0139	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	12.00	EACH
0140	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	19.00	EACH
0141	805-93067	CONTROLLER CABINET, P	3.00	EACH
0142	807-78590	HANDHOLE	26.00	EACH
0143	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	270.00	SYS
0144	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	395.00	LFT
0145	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1631.00	LFT
0146	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1953.00	LFT
0147	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	894.00	LFT
0148	808-06716	LINE, REMOVE	24198.00	LFT
0149	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0150	808-12032	GROOVING FOR PAVEMENT MARKINGS	38002.00	LFT
0151	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	3247.00	LFT
0152	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	4676.00	LFT
0153	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	28053.00	LFT
0154	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	153.00	LFT
0155	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	698.00	LFT
0156	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	90.00	EACH
0157	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	32.00	EACH

Call: 421

Contract: RS-38672-A

Section No.: 1 BRIDGE REHABILITATION

Line

Item No	Item Code	Description	Quantity Unit	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL

0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	116.00	SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-93741	GUARDRAIL, END TREATMENT, REMOVE	6.00	EACH
0016	203-02000	EXCAVATION, COMMON	1620.00	CYS
0017	203-02070	BORROW	2734.00	CYS
0018	205-12108	STORM WATER MANAGEMENT BUDGET	11218.00	DOL
0019	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0020	206-98327	SHEET PILING STEEL S=30.2	17458.00	SFT
0021	207-08264	SUBGRADE TREATMENT, TYPE II	163.00	SYS
0022	207-09934	SUBGRADE TREATMENT, TYPE IB	5174.00	SYS

0023	207-09935	SUBGRADE TREATMENT, TYPE IC	71.00	SYS
0024	211-09266	STRUCTURE BACKFILL, TYPE 3	185.00	CYS
0025	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	2.00	CYS
0026	301-12234	COMPACTED AGGREGATE NO 53	409.00	CYS
0027	302-06464	SUBBASE FOR PCCP	18.00	CYS
0028	302-07455	DENSE GRADED SUBBASE	42.00	CYS
0029	303-01180	COMPACTED AGGREGATE NO. 53	867.00	TON
0030	304-07490	HMA PATCHING, TYPE B	1502.00	TON
0031	304-07783	HMA PATCHING, TYPE D	525.00	TON
0032	306-08034	MILLING, ASPHALT, 1 1/2 IN.	264760.00	SYS
0033	306-08037	MILLING, ASPHALT, 3 IN.	7800.00	SYS
0034	306-08043	MILLING, TRANSITION	489.00	SYS
0035	306-08432	MILLING, APPROACH	2616.00	SYS
0036	306-08432	MILLING, APPROACH	1757.00	SYS
0037	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	7771.00	TON
0038	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	21499.00	TON
0039	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	663.00	TON
0040	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	804.00	TON
0041	401-10258	JOINT ADHESIVE, SURFACE	186772.00	LFT
0042	401-10259	JOINT ADHESIVE, INTERMEDIATE	3210.00	LFT
0043	401-11785	LIQUID ASPHALT SEALANT	186772.00	LFT
0044	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0045	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0046	406-12347	ASPHALT EMULSION FOR TACK COAT	197.00	TON
0047	414-11468	ULTRATHIN BONDED WEARING COURSE 9.5 mm	13030.00	SYS
0048	503-03489	RETROFITTED TIE BARS	13.00	EACH
0049	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	499.00	LFT
0050	506-06333	PCCP PATCHING, FULL DEPTH	71.00	SYS
0051	506-06334	PCCP PATCHING, PARTIAL DEPTH	1953.00	SYS
0052	507-08271	JOINTS IN PCCP, FILLED	3263.00	LFT
0053	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	1.00	EACH
0054	601-02241	GUARDRAIL, REMOVE	1978.00	LFT
0055	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1687.50	LFT
0056	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00	EACH
0057	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0058	601-94689	GUARDRAIL, END TREATMENT, OS	5.00	EACH
0059	602-06729	BARRIER, DELINEATOR	14.00	EACH

0060	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	144230.00	LFT
0061	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	248.00	SYS
0062	610-07487	HMA FOR APPROACHES, TYPE B	46.00	TON
0063	610-07788	HMA FOR APPROACHES, TYPE D	353.00	TON
0064	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00	EACH
0065	615-06505	MONUMENT, B	5.00	EACH
0066	616-51367	SLOPEWALL, CONCRETE, 4 IN.	8.00	SYS
0067	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0068	621-02770	EROSION CONTROL BLANKET	908.00	SYS
0069	621-06545	FERTILIZER	1.00	TON
0070	621-06553	SEED MIXTURE R	39.00	LBS
0071	621-06565	MULCHING MATERIAL	1.00	TON
0072	628-09402	FIELD OFFICE, B	18.00	MOS
0073	628-11977	COMPUTER SYSTEM	1.00	EACH
0074	702-51005	CONCRETE, A, SUBSTRUCTURE	4.00	CYS
0075	702-51863	FIELD DRILLED HOLE IN CONCRETE	272.00	EACH
0076	702-92857	CONCRETE, C, SUBSTRUCTURE	39.90	CYS
0077	703-06028	REINFORCING BARS	489.00	LBS
0078	703-06029	REINFORCING BARS, EPOXY COATED	109552.00	LBS
0079	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	50.00	EACH
0080	704-51002	CONCRETE, C, SUPERSTRUCTURE	255.70	CYS
0081	706-11600	RAILING, CONCRETE FC	10.30	CYS
0082	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0083	709-51821	SURFACE SEAL	1.00	LS
0084	711-51038	STRUCTURAL STEEL	1.00	LS
0085	711-51864	DRILLED HOLE	248.00	EACH
0086	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	556.00	SYS
0087	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	120.00	SYS
0088	732-11770	AGGREGATE FOR DRAINAGE FILL	299.00	CYS
0089	801-04308	ROAD CLOSURE SIGN ASSEMBLY	14.00	EACH
0090	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	13732.00	LFT
0091	801-06625	DETOUR ROUTE MARKER ASSEMBLY	89.00	EACH
0092	801-06640	CONSTRUCTION SIGN, A	28.00	EACH
0093	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
0094	801-06775	MAINTAINING TRAFFIC	1.00	LS
0095	801-07118	BARRICADE, III-A	320.00	LFT
0096	801-07119	BARRICADE, III-B	96.00	LFT

0097	802-04089	SIGN, SHEET, REMOVE	3.00	EACH
0098	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	12.00	LFT
0099	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0100	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	8.00	SFT
0101	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	13732.00	LFT
0102	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	67082.00	LFT
0103	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	6138.00	LFT
0104	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2600.00	LFT
0105	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2600.00	LFT
0106	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0107	808-12032	GROOVING FOR PAVEMENT MARKINGS	190917.00	LFT
0108	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	65219.00	LFT
0109	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	1750.00	LFT
0110	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	362.00	LFT
0111	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	850.00	EACH
0112	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	782.00	EACH

Call: 431

Contract: RS-39090-A

Section No.: 1 PATCH AND REHAB PAVEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	3217.00	SYS
0012	202-02274	CURB, CONCRETE INTEGRAL, REMOVE	450.00	LFT
0013	203-02000	EXCAVATION, COMMON	5600.00	CYS
0014	203-02070	BORROW	90.00	CYS
0015	205-12108	STORM WATER MANAGEMENT BUDGET	15859.00	DOL

0016	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0017	207-08268	SUBGRADE TREATMENT, TYPE IV	3468.00	SYS
0018	207-09934	SUBGRADE TREATMENT, TYPE IB	3864.00	SYS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	3153.00	SYS
0020	214-11796	GEOGRID, TYPE IB	3864.00	SYS
0021	302-06464	SUBBASE FOR PCCP	769.00	CYS
0022	303-01180	COMPACTED AGGREGATE NO. 53	1492.00	TON

0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	6502.00	SYS
0024	306-08038	MILLING, ASPHALT, 4 IN.	55782.00	SYS
0025	306-08043	MILLING, TRANSITION	50061.00	SYS
0026	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	7.00	TON
0027	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	346.00	TON
0028	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	17648.00	TON
0029	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	81.00	TON
0030	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	522.00	TON
0031	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	15150.00	TON
0032	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	29.00	TON
0033	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	726.00	TON
0034	401-08364	QC/QA-HMA, 4, 64, BASE, 19.0 mm	1974.00	TON
0035	401-10258	JOINT ADHESIVE, SURFACE	38908.00	LFT
0036	401-10259	JOINT ADHESIVE, INTERMEDIATE	13704.00	LFT
0037	401-11785	LIQUID ASPHALT SEALANT	38908.00	LFT
0038	402-10087	HMA FOR TEMPORARY PAVEMENT, D	533.00	TON
0039	406-05520	ASPHALT FOR TACK COAT	46.00	TON
0040	503-03489	RETROFITTED TIE BARS	293.00	EACH
0041	503-05240	D-1 CONTRACTION JOINT	403.00	LFT
0042	506-06333	PCCP PATCHING, FULL DEPTH	3073.00	SYS
0043	601-06035	GUARDRAIL, RESET	32424.00	LFT
0044	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	357.00	LFT
0045	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	1.00	EACH
0046	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0047	605-05523	CURB, HMA	452.00	LFT
0048	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	3680.00	LFT
0049	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	1515.00	LFT
0050	621-02770	EROSION CONTROL BLANKET	1138.00	SYS
0051	621-06559	MULCHED SEEDING R	1138.00	SYS
0052	628-09402	FIELD OFFICE, B	20.00	MOS
0053	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0054	713-04509	TEMPORARY PIPE	1.00	LS
0055	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	3387.00	LFT
0056	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	514.00	LFT
0057	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	99.00	LFT
0058	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	2153.00	SYS
0059	718-52610	AGGREGATE FOR UNDERDRAINS	506.00	CYS

0060	720-04499	INLET RECONSTRUCT	1.00	EACH
0061	720-45410	MANHOLE, C4	1.00	EACH
0062	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.00	EACH
0063	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0064	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	371932.00	LFT
0065	801-06640	CONSTRUCTION SIGN, A	128.00	EACH
0066	801-06645	CONSTRUCTION SIGN, B	26.00	EACH
0067	801-06710	FLASHING ARROW SIGN	280.00	DAY
0068	801-06775	MAINTAINING TRAFFIC	1.00	LS
0069	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	1.00	EACH
0070	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	1.00	EACH
0071	801-07118	BARRICADE, III-A	32.00	LFT
0072	801-07119	BARRICADE, III-B	24.00	LFT
0073	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	3157.00	LFT
0074	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0075	801-12042	TRUCK MOUNTED ATTENUATOR	280.00	DAY
0076	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	230511.00	LFT
0077	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	233785.00	LFT
0078	808-06716	LINE, REMOVE	475901.00	LFT
0079	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	6.00	EACH
0080	808-06724	PAVEMENT MESSAGE MARKING, PAINT, ONLY	3.00	EACH
0081	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	40.00	LFT
0082	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0083	808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	48843.00	LFT
0084	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	759.00	LFT
0085	808-75008	LINE, PAINT, SOLID, WHITE, 8 IN.	1059.00	LFT
0086	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	6002.00	LFT
0087	808-75090	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, YELLOW, 24 IN.	643.00	LFT
0088	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	684.00	EACH
0089	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	684.00	EACH

Call: 441

Contract: RS-39251-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS

0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0013	202-96133	PIPE, REMOVE	61.00	LFT
0014	203-02000	EXCAVATION, COMMON	229.00	CYS
0015	203-02070	BORROW	311.00	CYS
0016	205-11626	PUMP AROUND	1.00	EACH
0017	205-12108	STORM WATER MANAGEMENT BUDGET	6864.00	DOL
0018	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0019	207-08268	SUBGRADE TREATMENT, TYPE IV	108.00	SYS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	14398.00	SYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	167.00	SYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	28.00	CYS

0023	211-09268	STRUCTURE BACKFILL, TYPE 5	185.00	CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	1159.00	TON
0025	304-07490	HMA PATCHING, TYPE B	10822.00	TON
0026	306-08036	MILLING, ASPHALT, 2 IN.	149442.00	SYS
0027	306-08037	MILLING, ASPHALT, 3 IN.	130214.00	SYS
0028	306-08043	MILLING, TRANSITION	2502.00	SYS
0029	306-08432	MILLING, APPROACH	11286.00	SYS
0030	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	19084.00	TON
0031	401-07339	QC/QA-HMA, 2, 64, SURFACE, 12.5 mm	8057.00	TON
0032	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	18851.00	TON
0033	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	49.00	TON
0034	401-10258	JOINT ADHESIVE, SURFACE	199389.00	LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	47650.00	LFT
0036	401-11785	LIQUID ASPHALT SEALANT	199389.00	LFT
0037	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0038	406-05520	ASPHALT FOR TACK COAT	109.00	TON
0039	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	17.00	TON
0040	412-09355	FOG SEAL	108736.00	SYS
0041	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	179184.00	LFT
0042	610-07487	HMA FOR APPROACHES, TYPE B	1340.00	TON
0043	615-06490	RIGHT-OF-WAY MARKER	6.00	EACH
0044	615-06520	MONUMENT, RE-ESTABLISH	17.00	EACH
0045	616-06405	RIPRAP, REVETMENT	128.00	TON
0046	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	199.00	SYS
0047	616-93019	RIPRAP, GROUTED, 18 IN.	29.00	SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0049	621-06559	MULCHED SEEDING R	1104.00	SYS
0050	621-06574	SODDING	189.00	SYS
0051	628-09403	FIELD OFFICE, C	18.00	MOS
0052	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0053	714-11184	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 10 FT. X 7 FT.	98.00	LFT
0054	715-05052	PIPE, TYPE 4, CIRCULAR, 12 IN.	20.00	LFT
0055	715-05212	PIPE, TYPE 4, CIRCULAR, 24 IN.	6.00	LFT
0056	720-45410	MANHOLE, C4	2.00	EACH
0057	801-04308	ROAD CLOSURE SIGN ASSEMBLY	34.00	EACH
0058	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	39245.00	LFT
0059	801-06625	DETOUR ROUTE MARKER ASSEMBLY	31.00	EACH

0060	801-06640	CONSTRUCTION SIGN, A	64.00	EACH
0061	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0062	801-06775	MAINTAINING TRAFFIC	1.00	LS
0063	801-07118	BARRICADE, III-A	96.00	LFT
0064	801-07119	BARRICADE, III-B	96.00	LFT
0065	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0066	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	10.00	SYS
0067	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	22450.00	LFT
0068	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	198409.00	LFT
0069	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	37787.00	LFT
0070	808-06716	LINE, REMOVE	258052.00	LFT
0071	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	3.00	EACH
0072	808-06724	PAVEMENT MESSAGE MARKING, PAINT, ONLY	2.00	EACH
0073	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	226.00	LFT
0074	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1272.00	EACH
0075	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1276.00	EACH

Call: 451

Contract: RS-39271-A

Section No.: 1 ASPHALT RESURFACE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	4655.00	SYS
0012	203-08607	LINEAR GRADING	13535.00	LFT
0013	205-12108	STORM WATER MANAGEMENT BUDGET	83090.00	DOL
0014	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0015	207-09935	SUBGRADE TREATMENT, TYPE IC	4833.00	SYS

0016	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	58.00	CYS
0017	301-12234	COMPACTED AGGREGATE NO 53	336.00	CYS
0018	303-07449	COMPACTED AGGREGATE NO. 73	6835.00	TON
0019	304-07783	HMA PATCHING, TYPE D	458.00	TON
0020	304-07783	HMA PATCHING, TYPE D	657.00	TON
0021	304-07783	HMA PATCHING, TYPE D	4171.00	TON
0022	304-07783	HMA PATCHING, TYPE D	130.00	TON

0023	306-08033	MILLING, ASPHALT, 1 IN.	111715.00	SYS
0024	306-08034	MILLING, ASPHALT, 1 1/2 IN.	20836.00	SYS
0025	306-08036	MILLING, ASPHALT, 2 IN.	530217.00	SYS
0026	306-08043	MILLING, TRANSITION	6196.00	SYS
0027	306-08432	MILLING, APPROACH	5656.00	SYS
0028	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	9342.00	TON
0029	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	2079.00	TON
0030	401-07348	QC/QA-HMA, 4, 70, SURFACE, 12.5 mm	8807.00	TON
0031	401-07379	QC/QA-HMA, 3, 70, INTERMEDIATE, 12.5 mm	2079.00	TON
0032	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	1537.00	TON
0033	401-10258	JOINT ADHESIVE, SURFACE	318581.00	LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	4626.00	LFT
0035	401-11785	LIQUID ASPHALT SEALANT	367971.00	LFT
0036	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0037	406-05520	ASPHALT FOR TACK COAT	180.00	TON
0038	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	19.00	TON
0039	410-11777	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm - SMA	48712.00	TON
0040	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	265339.00	LFT
0041	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	73890.00	LFT
0042	610-07487	HMA FOR APPROACHES, TYPE B	126.00	TON
0043	610-07788	HMA FOR APPROACHES, TYPE D	380.00	TON
0044	615-01469	MONUMENT SECTION CORNER INSTALL	3.00	EACH
0045	615-06525	CASTING ADJUST TO GRADE, MONUMENT	2.00	EACH
0046	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0047	621-02770	EROSION CONTROL BLANKET	7994.00	SYS
0048	621-06545	FERTILIZER	1.00	TON
0049	621-06559	MULCHED SEEDING R	9031.00	SYS
0050	621-06626	MULCHED SEEDING D	363.00	SYS
0051	628-09402	FIELD OFFICE, B	9.00	MOS
0052	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0053	628-11730	CELLULAR TELEPHONE, TYPE B	2.00	EACH
0054	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0055	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0056	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	27.00	MOS
0057	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0058	628-11977	COMPUTER SYSTEM	3.00	EACH
0059	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	1677.00	LFT

0060	718-04986	CLEANOUT	21.00	EACH
0061	718-06529	OUTLET PROTECTOR, 2	103.00	EACH
0062	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	15774.00	LFT
0063	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	30.00	EACH
0064	801-03290	CONSTRUCTION SIGN, C	25.00	EACH
0065	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0066	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	281619.00	LFT
0067	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	277655.00	LFT
0068	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	110.00	LFT
0069	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	110.00	LFT
0070	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	56.00	LFT
0071	801-06640	CONSTRUCTION SIGN, A	139.00	EACH
0072	801-06710	FLASHING ARROW SIGN	300.00	DAY
0073	801-06775	MAINTAINING TRAFFIC	1.00	LS
0074	801-07118	BARRICADE, III-A	28.00	LFT
0075	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1012.00	LFT
0076	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	7.00	EACH
0077	801-12042	TRUCK MOUNTED ATTENUATOR	266.00	DAY
0078	801-12348	TEMPORARY WORKSITE SPEED DISPLAY ASSEMBLY	2.00	EACH
0079	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	5530.00	LFT
0080	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	50010.00	LFT
0081	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	17194.00	LFT
0082	808-06716	LINE, REMOVE	136931.00	LFT
0083	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	110.00	LFT
0084	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0085	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	144329.00	LFT
0086	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	137378.00	LFT
0087	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	6625.00	LFT
0088	808-10043	LINE, MULTI-COMPONENT, SOLID, WHITE, 24 IN.	734.00	LFT
0089	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	56.00	LFT
0090	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	33258.00	LFT
0091	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	1146.00	LFT
0092	808-12032	GROOVING FOR PAVEMENT MARKINGS	322736.00	LFT
0093	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2442.00	EACH
0094	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1950.00	EACH
0095	809-05905	ATR STATION- 4 LANE	1.00	EACH

Call: 461

Contract: RS-39375-B

Section No.: 1 PCCP CLEANING AND SEALING JOINTS

Line

Item No	Item Code	Description	Quantity Unit	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02278	CURB, CONCRETE, REMOVE	662.00	LFT
0013	202-02279	CURB AND GUTTER, REMOVE	676.00	LFT
0014	202-52710	SIDEWALK CONCRETE, REMOVE	433.00	SYS
0015	203-02000	EXCAVATION, COMMON	335.00	CYS
0016	203-02070	BORROW	1.00	CYS
0017	205-12108	STORM WATER MANAGEMENT BUDGET	700.00	DOL
0018	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	4386.00	SYS
0020	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	960.00	SYS
0021	301-12234	COMPACTED AGGREGATE NO 53	107.00	CYS
0022	302-06464	SUBBASE FOR PCCP	781.00	CYS

0023	303-01180	COMPACTED AGGREGATE NO. 53	164.00	TON
0024	304-07491	HMA PATCHING, TYPE C	123.00	TON
0025	306-08034	MILLING, ASPHALT, 1 1/2 IN.	29376.00	SYS
0026	306-08432	MILLING, APPROACH	6066.00	SYS
0027	306-08599	MILLING, ASPHALT, 1/2 IN.	4883.00	SYS
0028	306-11680	MILLING, ASPHALT, 5.5 IN.	4883.00	SYS
0029	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2905.00	TON
0030	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1366.00	TON
0031	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	317.00	TON
0032	401-10258	JOINT ADHESIVE, SURFACE	4404.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	115.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	4404.00	LFT
0035	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	144.00	TON
0036	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0037	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0038	503-03489	RETROFITTED TIE BARS	726.00	EACH
0039	503-05240	D-1 CONTRACTION JOINT	1120.00	LFT
0040	506-06333	PCCP PATCHING, FULL DEPTH	3126.00	SYS
0041	507-07482	CRACKS IN PCCP, ROUT AND SEAL	1714.00	LFT
0042	507-08272	JOINTS IN PCCP, SAW AND SEAL	607057.00	LFT
0043	507-12191	JOINT REPAIR, PARTIAL DEPTH	2268.00	SFT
0044	604-06070	SIDEWALK, CONCRETE	187.00	SYS
0045	604-08086	CURB RAMP, CONCRETE	218.00	SYS
0046	604-12083	DETECTABLE WARNING SURFACES	39.00	SYS
0047	605-06120	CURB, CONCRETE	663.00	LFT
0048	605-06145	CURB AND GUTTER, B, CONCRETE	720.00	LFT
0049	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	61.00	LFT
0050	610-07488	HMA FOR APPROACHES, TYPE C	500.00	TON
0051	615-06520	MONUMENT, RE-ESTABLISH	10.00	EACH
0052	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0053	621-06560	MULCHED SEEDING U	37.00	SYS
0054	621-06567	WATER	0.17	kGAL
0055	621-06570	TOPSOIL	9.00	CYS
0056	621-06575	SODDING, NURSERY	49.00	SYS
0057	628-09402	FIELD OFFICE, B	13.00	MOS
0058	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0059	628-11977	COMPUTER SYSTEM	1.00	EACH

0060	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	720.00	LFT
0061	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	20.00	LFT
0062	718-06528	OUTLET PROTECTOR, 1	1.00	EACH
0063	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	536.00	SYS
0064	718-52610	AGGREGATE FOR UNDERDRAINS	80.00	CYS
0065	720-44000	CASTING, ADJUST TO GRADE	2.00	EACH
0066	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0067	801-06640	CONSTRUCTION SIGN, A	55.00	EACH
0068	801-06710	FLASHING ARROW SIGN	1320.00	DAY
0069	801-06775	MAINTAINING TRAFFIC	1.00	LS
0070	801-12042	TRUCK MOUNTED ATTENUATOR	1320.00	DAY
0071	801-12324	LAW ENFORCEMENT OFFICER	500.00	HRS
0072	805-01744	LOOP RESEAL	317.00	EACH
0073	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	66.00	LFT
0074	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	2.00	EACH
0075	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	4.00	EACH
0076	805-05405	SIGNAL POLE, PEDESTAL, 4FT	2.00	EACH
0077	805-11817	PEDESTRIAN PUSH BUTTON, APS	4.00	EACH
0078	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	1011.00	LFT
0079	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	479.00	LFT
0080	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	2.00	EACH
0081	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	134298.00	LFT
0082	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	96288.00	LFT
0083	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	143.00	EACH
0084	808-06724	PAVEMENT MESSAGE MARKING, PAINT, ONLY	50.00	EACH
0085	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	1772.00	LFT
0086	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0087	808-12032	GROOVING FOR PAVEMENT MARKINGS	47614.00	LFT
0088	808-75059	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	47614.00	LFT
0089	808-75060	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE 12 IN.	1756.00	LFT
0090	808-75078	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, YELLOW, 12 IN.	120.00	LFT
0091	808-75100	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 6 IN.	1960.00	LFT
0092	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2774.00	EACH
0093	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2774.00	EACH

Call: 481

Contract: RS-39470-A

Section No.: 1 ASPHALT RESURFACE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-02240	PAVEMENT REMOVAL	403.00	SYS
0011	207-09935	SUBGRADE TREATMENT, TYPE IC	568.00	SYS
0012	302-07455	DENSE GRADED SUBBASE	68.00	CYS
0013	303-01180	COMPACTED AGGREGATE NO. 53	269.00	TON
0014	303-07449	COMPACTED AGGREGATE NO. 73	577.00	TON
0015	304-07490	HMA PATCHING, TYPE B	653.00	TON
0016	306-08034	MILLING, ASPHALT, 1 1/2 IN.	121063.00	SYS
0017	306-08432	MILLING, APPROACH	6320.00	SYS
0018	401-06264	PROFILOGRAPH, HMA	1.00	LS
0019	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	9988.00	TON
0020	401-10258	JOINT ADHESIVE, SURFACE	112888.00	LFT
0021	401-11785	LIQUID ASPHALT SEALANT	145140.00	LFT
0022	406-05520	ASPHALT FOR TACK COAT	33.00	TON

0023	506-06333	PCCP PATCHING, FULL DEPTH	403.00	SYS
0024	601-92948	GUARDRAIL, ADJUST HEIGHT	36208.00	LFT
0025	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	32490.00	LFT
0026	610-07487	HMA FOR APPROACHES, TYPE B	523.00	TON
0027	611-08232	MAILBOX ASSEMBLY, SINGLE RESET	3.00	EACH
0028	628-09402	FIELD OFFICE, B	5.00	MOS
0029	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0030	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	EACH
0031	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3581.00	LFT
0032	801-06625	DETOUR ROUTE MARKER ASSEMBLY	39.00	EACH
0033	801-06640	CONSTRUCTION SIGN, A	55.00	EACH
0034	801-06775	MAINTAINING TRAFFIC	1.00	LS
0035	801-07118	BARRICADE, III-A	72.00	LFT
0036	801-07119	BARRICADE, III-B	120.00	LFT
0037	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	8870.00	LFT
0038	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	71628.00	LFT
0039	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	4818.00	LFT
0040	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	24.00	LFT
0041	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS

Call: 491

Contract: RS-40618-B

Section No.: 1 ASPHALT RESURFACE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	304-07783	HMA PATCHING, TYPE D	37.00	TON
0011	306-08034	MILLING, ASPHALT, 1 1/2 IN.	394307.00	SYS
0012	306-08038	MILLING, ASPHALT, 4 IN.	2483.00	SYS

0013	401-06264	PROFILOGRAPH, HMA	1.00	LS
0014	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	8609.00	TON
0015	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	510.00	TON
0016	401-10258	JOINT ADHESIVE, SURFACE	345857.00	LFT
0017	401-10259	JOINT ADHESIVE, INTERMEDIATE	1736.00	LFT
0018	401-11785	LIQUID ASPHALT SEALANT	345857.00	LFT
0019	406-05520	ASPHALT FOR TACK COAT	100.00	TON
0020	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	12.00	TON
0021	410-09530	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm - SMA	23875.00	TON
0022	412-09355	FOG SEAL	135690.00	SYS

0023	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	108519.00	LFT
0024	628-09402	FIELD OFFICE, B	14.00	MOS
0025	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0026	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0027	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	21704.00	LFT
0028	801-06640	CONSTRUCTION SIGN, A	24.00	EACH
0029	801-06710	FLASHING ARROW SIGN	200.00	DAY
0030	801-06775	MAINTAINING TRAFFIC	1.00	LS
0031	801-12042	TRUCK MOUNTED ATTENUATOR	40.00	DAY
0032	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	6002.00	LFT
0033	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0034	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	635.00	LFT
0035	808-12032	GROOVING FOR PAVEMENT MARKINGS	259928.00	LFT
0036	808-12134	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 4 IN.	929.00	LFT
0037	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	120807.00	LFT
0038	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	120641.00	LFT
0039	808-75061	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	11549.00	LFT
0040	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	744.00	LFT
0041	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	52.00	LFT
0042	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1357.00	EACH
0043	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1630.00	EACH
0044	809-05905	ATR STATION- 4 LANE	1.00	EACH
0045	809-09871	ATR STATION, REMOVE	1.00	EACH

Call: 501

Contract: RS-40675-A

Section No.: 1 ASPHALT RESURFACE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL

0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	207-09935	SUBGRADE TREATMENT, TYPE IC	260.00	SYS
0011	303-01180	COMPACTED AGGREGATE NO. 53	800.00	TON
0012	304-07490	HMA PATCHING, TYPE B	360.00	TON
0013	306-08036	MILLING, ASPHALT, 2 IN.	30197.00	SYS
0014	306-08043	MILLING, TRANSITION	2000.00	SYS
0015	306-08432	MILLING, APPROACH	1721.00	SYS
0016	401-06264	PROFILOGRAPH, HMA	1.00	LS
0017	401-07340	QC/QA-HMA, 3, 64, SURFACE, 12.5 mm	3322.00	TON
0018	401-10258	JOINT ADHESIVE, SURFACE	10152.00	LFT
0019	401-11785	LIQUID ASPHALT SEALANT	10152.00	LFT
0020	402-07451	HMA WEDGE AND LEVEL, TYPE B	100.00	TON
0021	406-05520	ASPHALT FOR TACK COAT	9.00	TON
0022	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	5.00	TON

0023	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	10152.00	LFT
0024	610-07487	HMA FOR APPROACHES, TYPE B	189.00	TON
0025	615-06525	CASTING ADJUST TO GRADE, MONUMENT	1.00	EACH
0026	628-09403	FIELD OFFICE, C	6.00	MOS
0027	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0028	702-90915	CONCRETE, CLASS, A	2.00	CYS
0029	703-06029	REINFORCING BARS, EPOXY COATED	15.00	LBS
0030	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0031	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	5222.00	LFT
0032	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5222.00	LFT
0033	801-06640	CONSTRUCTION SIGN, A	22.00	EACH
0034	801-06775	MAINTAINING TRAFFIC	1.00	LS
0035	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	21528.00	LFT
0036	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0037	808-12032	GROOVING FOR PAVEMENT MARKINGS	37469.00	LFT
0038	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1406.00	LFT
0039	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	14535.00	LFT
0040	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	1.00	EACH
0041	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	292.00	EACH
0042	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	292.00	EACH

Call: 511

Contract: RS-40676-A

Section No.: 1 ASPHALT RESURFACE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	202-52710	SIDEWALK CONCRETE, REMOVE	713.00	SYS

0012	202-90277	DETECTOR HOUSING, REMOVE	13.00	EACH
0013	207-09935	SUBGRADE TREATMENT, TYPE IC	111.00	SYS
0014	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	11.00	CYS
0015	304-07491	HMA PATCHING, TYPE C	368.00	TON
0016	306-08034	MILLING, ASPHALT, 1 1/2 IN.	33072.00	SYS
0017	306-08043	MILLING, TRANSITION	55.00	SYS
0018	306-08432	MILLING, APPROACH	3637.00	SYS
0019	401-06264	PROFILOGRAPH, HMA	1.00	LS
0020	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2729.00	TON
0021	401-10258	JOINT ADHESIVE, SURFACE	20215.00	LFT
0022	401-11785	LIQUID ASPHALT SEALANT	20215.00	LFT

0023	402-07452	HMA WEDGE AND LEVEL, TYPE C	5.00	TON
0024	406-05520	ASPHALT FOR TACK COAT	10.00	TON
0025	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	10.00	TON
0026	503-03489	RETROFITTED TIE BARS	9.00	EACH
0027	503-05240	D-1 CONTRACTION JOINT	24.00	LFT
0028	506-06333	PCCP PATCHING, FULL DEPTH	74.00	SYS
0029	506-06334	PCCP PATCHING, PARTIAL DEPTH	25.00	SYS
0030	507-07480	PROFILING, PCCP	1600.00	SYS
0031	507-08269	CRACKS IN PCCP, FILLED	50.00	LFT
0032	507-08271	JOINTS IN PCCP, FILLED	1484.00	LFT
0033	604-06070	SIDEWALK, CONCRETE	312.00	SYS
0034	604-07092	BED COURSE MATERIAL	19.00	TON
0035	604-08086	CURB RAMP, CONCRETE	420.00	SYS
0036	604-12083	DETECTABLE WARNING SURFACES	46.00	SYS
0037	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	5.00	SYS
0038	605-01870	CURB, CONCRETE A	194.00	LFT
0039	605-02278	CURB, REMOVE	115.00	LFT
0040	610-07488	HMA FOR APPROACHES, TYPE C	326.00	TON
0041	621-06565	MULCHING MATERIAL	2.00	TON
0042	621-06567	WATER	5.00	kGAL
0043	621-06574	SODDING	31.00	SYS
0044	628-09403	FIELD OFFICE, C	12.00	MOS
0045	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0046	628-11977	COMPUTER SYSTEM	1.00	EACH
0047	702-51863	FIELD DRILLED HOLE IN CONCRETE	18.00	EACH
0048	702-90915	CONCRETE, CLASS, A	24.00	CYS
0049	703-06029	REINFORCING BARS, EPOXY COATED	1740.00	LBS
0050	720-44000	CASTING, ADJUST TO GRADE	6.00	EACH
0051	720-44000	CASTING, ADJUST TO GRADE	18.00	EACH
0052	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	4.00	EACH
0053	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	2286.00	LFT
0054	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2286.00	LFT
0055	801-06640	CONSTRUCTION SIGN, A	49.00	EACH
0056	801-06775	MAINTAINING TRAFFIC	1.00	LS
0057	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	9.00	EACH
0058	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	120.00	LFT
0059	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	8.00	EACH

0060	805-05405	SIGNAL POLE, PEDESTAL, 4FT	6.00	EACH
0061	805-11817	PEDESTRIAN PUSH BUTTON, APS	24.00	EACH
0062	805-11817	PEDESTRIAN PUSH BUTTON, APS	6.00	EACH
0063	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	6500.00	LFT
0064	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	1249.00	LFT
0065	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	650.00	LFT
0066	805-78785	SIGNAL DETECTOR HOUSING	13.00	EACH
0067	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2080.00	LFT
0068	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	300.00	LFT
0069	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7767.00	LFT
0070	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	68.00	LFT
0071	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1302.00	LFT
0072	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	813.00	LFT
0073	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0074	808-12032	GROOVING FOR PAVEMENT MARKINGS	19404.00	LFT
0075	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE 4 IN.	2062.00	LFT
0076	808-12274	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, BLUE 4 IN.	96.00	LFT
0077	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	924.00	LFT
0078	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	8859.00	LFT
0079	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	283.00	LFT
0080	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	1205.00	LFT
0081	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	21.00	EACH
0082	808-97664	PAVEMENT MESSAGE MARKING, THERMOPLASTIC HANDICAP SYMBOL	4.00	EACH

Call: 521

Contract: RS-40982-A

Section No.: 1 ASPHALT RESURFACE

Line

Item No	Item Code	Description	Quantity Unit	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS

0009	301-12234	COMPACTED AGGREGATE NO 53	2.00	CYS
0010	303-07449	COMPACTED AGGREGATE NO. 73	28.00	TON
0011	304-07490	HMA PATCHING, TYPE B	5.00	TON
0012	304-07490	HMA PATCHING, TYPE B	296.00	TON
0013	306-08034	MILLING, ASPHALT, 1 1/2 IN.	13414.00	SYS
0014	306-08432	MILLING, APPROACH	1231.00	SYS
0015	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1107.00	TON
0016	401-10258	JOINT ADHESIVE, SURFACE	7825.00	LFT
0017	401-11785	LIQUID ASPHALT SEALANT	7825.00	LFT
0018	406-05520	ASPHALT FOR TACK COAT	5.00	TON
0019	605-06120	CURB, CONCRETE	20.00	LFT
0020	610-07487	HMA FOR APPROACHES, TYPE B	102.00	TON
0021	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	3.00	EACH
0022	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	393.00	LFT

0023	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	393.00	LFT
0024	801-06640	CONSTRUCTION SIGN, A	28.00	EACH
0025	801-06775	MAINTAINING TRAFFIC	1.00	LS
0026	801-92448	CONSTRUCTION SIGNS MOBILE	600.00	DAY
0027	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	630.00	LFT
0028	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	5362.00	LFT
0029	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	3225.00	LFT
0030	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE 4 IN.	300.00	LFT
0031	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	72.00	LFT
0032	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	19.00	EACH
0033	808-97664	PAVEMENT MESSAGE MARKING, THERMOPLASTIC HANDICAP SYMBOL	1.00	EACH

Call: 531

Contract: RS-41833-A

Section No.: 1 ASPHALT RESURFACE

Line

Item No	Item Code	Description	Quantity Unit	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02278	CURB, CONCRETE, REMOVE	160.00	LFT
0013	202-02279	CURB AND GUTTER, REMOVE	70.00	LFT
0014	202-52710	SIDEWALK CONCRETE, REMOVE	201.00	SYS
0015	205-12108	STORM WATER MANAGEMENT BUDGET	1100.00	DOL
0016	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0017	207-09935	SUBGRADE TREATMENT, TYPE IC	1570.00	SYS
0018	302-06464	SUBBASE FOR PCCP	118.00	CYS
0019	303-01180	COMPACTED AGGREGATE NO. 53	17.00	TON
0020	304-07491	HMA PATCHING, TYPE C	1033.00	TON

0021	306-08034	MILLING, ASPHALT, 1 1/2 IN.	135715.00	SYS
0022	306-08432	MILLING, APPROACH	12688.00	SYS

0023	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	11196.00	TON
0024	401-10258	JOINT ADHESIVE, SURFACE	89082.00	LFT
0025	401-11785	LIQUID ASPHALT SEALANT	89082.00	LFT
0026	406-05520	ASPHALT FOR TACK COAT	37.00	TON
0027	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.00	TON
0028	503-03489	RETROFITTED TIE BARS	118.00	EACH
0029	503-05240	D-1 CONTRACTION JOINT	22.00	LFT
0030	506-06333	PCCP PATCHING, FULL DEPTH	470.00	SYS
0031	507-08272	JOINTS IN PCCP, SAW AND SEAL	3158.00	LFT
0032	604-06070	SIDEWALK, CONCRETE	85.00	SYS
0033	604-08086	CURB RAMP, CONCRETE	95.00	SYS
0034	604-12083	DETECTABLE WARNING SURFACES	18.00	SYS
0035	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	4.00	SYS
0036	605-06120	CURB, CONCRETE	161.00	LFT
0037	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	70.00	LFT
0038	610-07488	HMA FOR APPROACHES, TYPE C	1047.00	TON
0039	615-06520	MONUMENT, RE-ESTABLISH	10.00	EACH
0040	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0041	621-06567	WATER	0.13	kGAL
0042	621-06570	TOPSOIL	7.00	CYS
0043	621-06575	SODDING, NURSERY	35.00	SYS
0044	628-09402	FIELD OFFICE, B	7.00	MOS
0045	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0046	628-11977	COMPUTER SYSTEM	1.00	EACH
0047	702-51005	CONCRETE, A, SUBSTRUCTURE	5.00	CYS
0048	720-44000	CASTING, ADJUST TO GRADE	3.00	EACH
0049	720-44000	CASTING, ADJUST TO GRADE	3.00	EACH
0050	720-44000	CASTING, ADJUST TO GRADE	45.00	EACH
0051	720-44000	CASTING, ADJUST TO GRADE	28.00	EACH
0052	720-44000	CASTING, ADJUST TO GRADE	29.00	EACH
0053	720-44070	CASTING, 13, FURNISH AND ADJUST TO GRADE	1.00	EACH
0054	801-06640	CONSTRUCTION SIGN, A	50.00	EACH
0055	801-06710	FLASHING ARROW SIGN	1320.00	DAY
0056	801-06775	MAINTAINING TRAFFIC	1.00	LS
0057	801-12042	TRUCK MOUNTED ATTENUATOR	1320.00	DAY
0058	801-12324	LAW ENFORCEMENT OFFICER	500.00	HRS
0059	805-01744	LOOP RESEAL	93.00	EACH

0060	808-03442	PAVEMENT MESSAGE MARKING, PAINT, BIKE SYMBOL	5.00	EACH
0061	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	10416.00	LFT
0062	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	1895.00	LFT
0063	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	48082.00	LFT
0064	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	40705.00	LFT
0065	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	81.00	EACH
0066	808-06724	PAVEMENT MESSAGE MARKING, PAINT, ONLY	20.00	EACH
0067	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	1140.00	LFT
0068	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0069	808-11960	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 24 IN.	30.00	LFT
0070	808-12046	LINE, PAINT, DOTTED, WHITE, 4 IN.	345.00	LFT
0071	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	1860.00	LFT
0072	808-75056	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE, 8 IN.	50.00	LFT
0073	808-75074	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, YELLOW, 8 IN.	1627.00	LFT
0074	808-75100	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 6 IN.	1638.00	LFT
0075	808-75140	PAVEMENT MESSAGE MARKING, PAINT, R X R	8.00	EACH
0076	808-75350	PAVEMENT MESSAGE MARKING, THERMOPLASTIC SCHOOL	1.00	EACH
0077	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	716.00	EACH
0078	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	716.00	EACH

Call: 541

Contract: RS-41855-A

Section No.: 1 ASPHALT RESURFACE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-93741	GUARDRAIL, END TREATMENT, REMOVE	13.00	EACH
0011	203-08607	LINEAR GRADING	30116.00	LFT
0012	205-12108	STORM WATER MANAGEMENT BUDGET	7415.00	DOL

0013	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0014	207-08266	SUBGRADE TREATMENT, TYPE III	16.00	SYS
0015	301-12234	COMPACTED AGGREGATE NO 53	2.00	CYS
0016	303-01180	COMPACTED AGGREGATE NO. 53	911.00	TON
0017	304-07783	HMA PATCHING, TYPE D	1249.00	TON
0018	306-08034	MILLING, ASPHALT, 1 1/2 IN.	280029.00	SYS
0019	306-11872	MILLING, PROFILE	125776.00	SYS
0020	401-06264	PROFILOGRAPH, HMA	1.00	LS
0021	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	9289.00	TON
0022	401-07368	QC/QA-HMA, 4, 76, INTERMEDIATE, 9.5 mm	7623.00	TON

0023	401-10258	JOINT ADHESIVE, SURFACE	186832.00	LFT
0024	401-11785	LIQUID ASPHALT SEALANT	364723.00	LFT
0025	406-05520	ASPHALT FOR TACK COAT	31.50	TON
0026	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	7.00	TON
0027	410-09530	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm - SMA	24191.00	TON
0028	601-02241	GUARDRAIL, REMOVE	9108.00	LFT
0029	601-05999	CURVED TERMINAL END	7.00	EACH
0030	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	7870.00	LFT
0031	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	1238.00	LFT
0032	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	14.00	EACH
0033	601-94689	GUARDRAIL, END TREATMENT, OS	9.00	EACH
0034	601-94690	GUARDRAIL, END TREATMENT, MS	4.00	EACH
0035	604-05528	HMA FOR SIDEWALK	2.00	TON
0036	604-08086	CURB RAMP, CONCRETE	20.00	SYS
0037	604-12083	DETECTABLE WARNING SURFACES	3.00	SYS
0038	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	19.00	SYS
0039	606-07484	MILLED HMA CORRUGATIONS	175162.00	LFT
0040	628-09402	FIELD OFFICE, B	8.00	MOS
0041	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0042	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0043	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	27579.00	LFT
0044	801-06640	CONSTRUCTION SIGN, A	40.00	EACH
0045	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0046	801-06710	FLASHING ARROW SIGN	200.00	DAY
0047	801-06775	MAINTAINING TRAFFIC	1.00	LS
0048	801-07119	BARRICADE, III-B	20.00	LFT
0049	801-12042	TRUCK MOUNTED ATTENUATOR	180.00	DAY
0050	801-92448	CONSTRUCTION SIGNS MOBILE	1200.00	DAY
0051	804-06770	DELINEATOR POST	80.00	EACH
0052	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	93711.00	LFT
0053	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	93193.00	LFT
0054	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	5909.00	LFT
0055	808-10038	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE WHITE 24 IN.	857.00	LFT
0056	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	15.00	EACH
0057	808-10097	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 27 IN.	74.00	LFT
0058	808-10099	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 24 IN.	219.00	LFT
0059	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	1397.00	LFT

0060	808-11831	LINE, EXTENDED WARRANTY, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	22340.00	LFT
0061	808-12032	GROOVING FOR PAVEMENT MARKINGS	217407.00	LFT
0062	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1458.00	EACH
0063	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1458.00	EACH

Call: 615

Contract: B -39245-B

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	164.00	LFT
0009	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	420.00	SFT
0010	724-12103	PRE-COMPRESSED FOAM JOINT	164.00	LFT
0011	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	2320.00	SYS
0012	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0013	801-06640	CONSTRUCTION SIGN, A	24.00	EACH
0014	801-06710	FLASHING ARROW SIGN	60.00	DAY
0015	801-06775	MAINTAINING TRAFFIC	1.00	LS
0016	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	6.00	EACH
0017	801-12042	TRUCK MOUNTED ATTENUATOR	14.00	DAY
0018	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	522.00	LFT
0019	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	522.00	LFT
0020	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	132.00	LFT
0021	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	8.00	EACH

Call: 621

Contract: B -39412-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	12.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	1025.00	SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0018	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0019	202-74035	SIGN, REMOVE	4.00	EACH
0020	202-96133	PIPE, REMOVE	31.00	LFT
0021	203-02000	EXCAVATION, COMMON	799.00	CYS
0022	203-08607	LINEAR GRADING	732.00	LFT

0023	205-11626	PUMP AROUND	2.00	EACH
0024	205-12108	STORM WATER MANAGEMENT BUDGET	36907.00	DOL
0025	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0026	206-51220	EXCAVATION, WET	18.00	CYS
0027	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	125.00	CYS
0028	207-09935	SUBGRADE TREATMENT, TYPE IC	2097.00	SYS
0029	207-09935	SUBGRADE TREATMENT, TYPE IC	86.00	SYS
0030	211-06467	AGGREGATE FOR END BENT BACKFILL	109.00	CYS
0031	211-09264	STRUCTURE BACKFILL, TYPE 1	9.00	CYS
0032	211-09265	STRUCTURE BACKFILL, TYPE 2	30.00	CYS
0033	211-09268	STRUCTURE BACKFILL, TYPE 5	117.00	CYS
0034	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	165.00	SYS
0035	301-12232	COMPACTED AGGREGATE NO 5	13.00	CYS
0036	301-12234	COMPACTED AGGREGATE NO 53	221.00	CYS
0037	302-06464	SUBBASE FOR PCCP	14.00	CYS
0038	302-07455	DENSE GRADED SUBBASE	199.00	CYS
0039	303-01180	COMPACTED AGGREGATE NO. 53	378.00	TON
0040	304-07490	HMA PATCHING, TYPE B	120.00	TON
0041	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1075.00	SYS
0042	306-08043	MILLING, TRANSITION	1333.00	SYS
0043	306-08432	MILLING, APPROACH	68.00	SYS
0044	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	358.00	TON
0045	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	239.00	TON
0046	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	311.00	TON
0047	401-10258	JOINT ADHESIVE, SURFACE	2557.00	LFT
0048	401-10259	JOINT ADHESIVE, INTERMEDIATE	1924.00	LFT
0049	401-11785	LIQUID ASPHALT SEALANT	2407.00	LFT
0050	406-05521	ASPHALT FOR TACK COAT	6096.00	SYS
0051	501-06323	QC/QA-PCCP, 12 IN.	107.00	SYS
0052	502-06330	PCCP, 13 IN.	46.00	SYS
0053	503-03489	RETROFITTED TIE BARS	52.00	EACH
0054	503-05310	TERMINAL JOINT	88.00	LFT
0055	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	104.00	LFT
0056	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	5.00	EACH
0057	601-01626	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 2	1.00	EACH
0058	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	1.00	EACH
0059	601-02103	GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN. SPACING	38.00	LFT

0060	601-02241	GUARDRAIL, REMOVE	1957.00	LFT
0061	601-02800	GUARDRAIL, TRANSITION, TGT	1.00	EACH
0062	601-06035	GUARDRAIL, RESET	20.00	LFT
0063	601-06238	IMPACT ATTENUATOR, R1-W1, TL-3	1.00	EACH
0064	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	713.00	LFT
0065	601-12287	GUARDRAIL, MGS, LONG SPAN, TYPE 1	2.00	EACH
0066	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	6.00	EACH
0067	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	3.00	EACH
0068	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	7.00	EACH
0069	601-94689	GUARDRAIL, END TREATMENT, OS	9.00	EACH
0070	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	19.00	LFT
0071	602-06729	BARRIER, DELINEATOR	61.00	EACH
0072	603-03829	FENCE	448.00	LFT
0073	605-02278	CURB, REMOVE	38.00	LFT
0074	605-06145	CURB AND GUTTER, B, CONCRETE	38.00	LFT
0075	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	453.00	SYS
0076	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	422.00	SYS
0077	609-06260	REINFORCED CONCRETE BRIDGE APPROACH, 13 IN.	226.00	SYS
0078	611-08232	MAILBOX ASSEMBLY, SINGLE RESET	1.00	EACH
0079	615-06505	MONUMENT, B	2.00	EACH
0080	615-06515	MONUMENT, D	4.00	EACH
0081	616-05688	RIPRAP, CLASS 1	711.00	TON
0082	616-06405	RIPRAP, REVETMENT	145.00	TON
0083	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	895.00	SYS
0084	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	72.00	SYS
0085	616-93019	RIPRAP, GROUTED, 18 IN.	396.00	SYS
0086	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0087	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0088	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0089	621-02770	EROSION CONTROL BLANKET	403.00	SYS
0090	621-06559	MULCHED SEEDING R	2960.00	SYS
0091	621-06567	WATER	1.00	kGAL
0092	621-06574	SODDING	169.00	SYS
0093	621-08161	PERMANENT TURF REINFORCEMENT MAT	23.00	SYS
0094	622-98200	SIGN, DO NOT DISTURB	6.00	EACH
0095	701-09558	TEST PILE, INDICATOR, PRODUCTION	72.00	LFT
0096	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00	EACH

0097	701-09739	PILE SHOE, HP 12 X 53	14.00	EACH
0098	701-51195	PILE, STEEL H HP 12 X 53	312.00	LFT
0099	701-93790	CLEAN AND EPOXY COAT EXISTING PILES	1.00	LS
0100	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	8.00	EACH
0101	702-51005	CONCRETE, A, SUBSTRUCTURE	109.60	CYS
0102	702-51863	FIELD DRILLED HOLE IN CONCRETE	734.00	EACH
0103	702-92857	CONCRETE, C, SUBSTRUCTURE	44.80	CYS
0104	703-01540	THREADED TIE BAR ASSEMBLY	432.00	EACH
0105	703-06028	REINFORCING BARS	11804.00	LBS
0106	703-06029	REINFORCING BARS, EPOXY COATED	301705.00	LBS
0107	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	84.00	EACH
0108	704-51002	CONCRETE, C, SUPERSTRUCTURE	539.20	CYS
0109	706-11601	RAILING, CONCRETE FT	200.00	CYS
0110	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	16.00	EACH
0111	707-11426	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 61 IN.	475.00	LFT
0112	708-51813	PNEUMATICALLY PLACED MORTAR	150.00	SFT
0113	709-51821	SURFACE SEAL	1.00	LS
0114	709-51821	SURFACE SEAL	1.00	LS
0115	709-51821	SURFACE SEAL	1.00	LS
0116	709-51821	SURFACE SEAL	1.00	LS
0117	710-09158	PATCHING CONCRETE STRUCTURES	210.00	SFT
0118	711-51038	STRUCTURAL STEEL	1.00	LS
0119	714-11089	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 11 FT. X 4 FT.	44.00	LFT
0120	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	41.00	LFT
0121	715-05407	PIPE, END BENT DRAIN, 6 IN.	232.00	LFT
0122	715-05596	PIPE EXTENSION, CIRCULAR, 18 IN.	8.00	LFT
0123	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0124	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH
0125	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	80.00	SYS
0126	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	102.00	SYS
0127	722-01066	HYDRODEMOLITION	2258.00	SYS
0128	722-12380	BRIDGE DECK OVERLAY, BUDGET	46805.00	DOL
0129	722-12382	TRANSVERSE GROOVING	2926.00	SYS
0130	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	405.00	SFT
0131	722-60824	SURFACE MILLING	2200.00	SYS
0132	801-04308	ROAD CLOSURE SIGN ASSEMBLY	15.00	EACH
0133	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	12001.00	LFT

0134	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	48.00	LFT
0135	801-06625	DETOUR ROUTE MARKER ASSEMBLY	55.00	EACH
0136	801-06640	CONSTRUCTION SIGN, A	78.00	EACH
0137	801-06645	CONSTRUCTION SIGN, B	16.00	EACH
0138	801-06775	MAINTAINING TRAFFIC	1.00	LS
0139	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	1.00	EACH
0140	801-07118	BARRICADE, III-A	259.00	LFT
0141	801-07119	BARRICADE, III-B	168.00	LFT
0142	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2931.00	LFT
0143	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	709.00	LFT
0144	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0145	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0146	802-04893	REFERENCE POST	2.00	EACH
0147	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	13.00	LFT
0148	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0149	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	600.00	LFT
0150	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	296.00	LFT
0151	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	3872.00	LFT
0152	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2011.00	LFT
0153	808-06716	LINE, REMOVE	3050.00	LFT
0154	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	634.00	LFT
0155	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	634.00	LFT
0156	808-12032	GROOVING FOR PAVEMENT MARKINGS	736.00	LFT
0157	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	76.00	LFT
0158	808-75994	PRISMATIC REFLECTOR	11.00	EACH
0159	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	36.00	EACH
0160	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	49.00	EACH

Call: 621

Contract: B -39412-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0161	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	2926.00	SYS

Call: 621

Contract: B -39412-A

Section No.: 3 BRIDGE DECK OVERLAY SILICA FUME CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0162	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	2926.00	SYS

Call: 631

Contract: B -40458-A

Section No.: 1 DEBRIS REMOVAL FROM CHANNEL

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0010	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0011	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0012	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0013	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0014	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0015	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0016	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0017	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
0018	203-51223	EXCAVATION, WATERWAY	951.00	CYS
0019	206-51235	COFFERDAM	1.00	LS
0020	621-06559	MULCHED SEEDING R	69.00	SYS
0021	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0022	801-06640	CONSTRUCTION SIGN, A	112.00	EACH

0023	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0024	801-06710	FLASHING ARROW SIGN	2.00	DAY
0025	801-06775	MAINTAINING TRAFFIC	1.00	LS
0026	801-07118	BARRICADE, III-A	16.00	LFT

Call: 661

Contract: B -40619-A

Section No.: 1 BRIDGE DECK OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	1584.00	SYS
0012	202-91840	FENCE, CHAIN. LINK, REMOVE	300.00	LFT
0013	202-93741	GUARDRAIL, END TREATMENT, REMOVE	6.00	EACH
0014	203-02000	EXCAVATION, COMMON	383.00	CYS
0015	207-09935	SUBGRADE TREATMENT, TYPE IC	36.00	SYS
0016	302-07455	DENSE GRADED SUBBASE	247.00	CYS
0017	306-08034	MILLING, ASPHALT, 1 1/2 IN.	2090.00	SYS
0018	306-08041	MILLING, PCCP	7251.00	SYS
0019	306-08041	MILLING, PCCP	2139.00	SYS
0020	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	333.00	TON
0021	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	322.00	TON
0022	401-08364	QC/QA-HMA, 4, 64, BASE, 19.0 mm	375.00	TON

0023	401-10258	JOINT ADHESIVE, SURFACE	2200.00	LFT
0024	401-10259	JOINT ADHESIVE, INTERMEDIATE	1800.00	LFT
0025	401-11785	LIQUID ASPHALT SEALANT	2200.00	LFT
0026	406-05520	ASPHALT FOR TACK COAT	4.00	TON
0027	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	0.20	TON
0028	501-06323	QC/QA-PCCP, 12 IN.	94.00	SYS
0029	503-05240	D-1 CONTRACTION JOINT	28.00	LFT
0030	503-05310	TERMINAL JOINT	28.00	LFT
0031	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	1060.00	LFT
0032	506-06333	PCCP PATCHING, FULL DEPTH	214.00	SYS
0033	601-02241	GUARDRAIL, REMOVE	3220.00	LFT
0034	601-06035	GUARDRAIL, RESET	250.00	LFT
0035	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	618.75	LFT
0036	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	487.50	LFT
0037	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	10.00	EACH
0038	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	5.00	EACH
0039	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	28.00	EACH
0040	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	10.00	EACH
0041	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0042	601-94690	GUARDRAIL, END TREATMENT, MS	1.00	EACH
0043	601-94690	GUARDRAIL, END TREATMENT, MS	4.00	EACH
0044	603-01159	FENCE, CHAIN LINK, PVC COATED, 42 IN.	180.00	LFT
0045	603-01159	FENCE, CHAIN LINK, PVC COATED, 42 IN.	120.00	LFT
0046	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	96.60	SYS
0047	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	911.40	SYS
0048	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	388.00	SYS
0049	616-06405	RIPRAP, REVETMENT	12.00	TON
0050	616-06451	RIPRAP, UNIFORM	24.00	TON
0051	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	50.00	SYS
0052	619-98427	CLEAN DRAINS	12.00	EACH
0053	628-09402	FIELD OFFICE, B	24.00	MOS
0054	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0055	702-51863	FIELD DRILLED HOLE IN CONCRETE	64.00	EACH
0056	702-93722	CONCRETE, C,	1.00	CYS
0057	703-01540	THREADED TIE BAR ASSEMBLY	509.00	EACH
0058	703-06029	REINFORCING BARS, EPOXY COATED	93143.00	LBS
0059	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	27.00	EACH

0060	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0061	709-51821	SURFACE SEAL	1.00	LS
0062	709-51821	SURFACE SEAL	1.00	LS
0063	709-51821	SURFACE SEAL	1.00	LS
0064	709-51821	SURFACE SEAL	1.00	LS
0065	709-51821	SURFACE SEAL	1.00	LS
0066	709-51821	SURFACE SEAL	1.00	LS
0067	709-51821	SURFACE SEAL	1.00	LS
0068	709-51821	SURFACE SEAL	1.00	LS
0069	709-51821	SURFACE SEAL	1.00	LS
0070	709-51821	SURFACE SEAL	1.00	LS
0071	709-51821	SURFACE SEAL	1.00	LS
0072	709-51821	SURFACE SEAL	1.00	LS
0073	709-51821	SURFACE SEAL	1.00	LS
0074	709-51821	SURFACE SEAL	1.00	LS
0075	709-51821	SURFACE SEAL	1.00	LS
0076	709-51821	SURFACE SEAL	1.00	LS
0077	709-51821	SURFACE SEAL	1.00	LS
0078	709-51821	SURFACE SEAL	1.00	LS
0079	709-51821	SURFACE SEAL	1.00	LS
0080	709-51821	SURFACE SEAL	1.00	LS
0081	709-51821	SURFACE SEAL	1.00	LS
0082	709-51821	SURFACE SEAL	1.00	LS
0083	709-51821	SURFACE SEAL	1.00	LS
0084	709-51821	SURFACE SEAL	1.00	LS
0085	709-51821	SURFACE SEAL	1.00	LS
0086	709-51821	SURFACE SEAL	1.00	LS
0087	709-51821	SURFACE SEAL	1.00	LS
0088	709-51821	SURFACE SEAL	1.00	LS
0089	710-09158	PATCHING CONCRETE STRUCTURES	1.00	SFT
0090	718-06531	OUTLET PROTECTOR, 3	5.00	EACH
0091	722-12381	BRIDGE DECK OVERLAY, LMC-VE	7251.00	SYS
0092	722-12381	BRIDGE DECK OVERLAY, LMC-VE	2139.00	SYS
0093	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	5574.00	SFT
0094	724-04163	STRUCTURAL EXPANSION JOINT SEAL, REPLACE	772.00	LFT
0095	724-04163	STRUCTURAL EXPANSION JOINT SEAL, REPLACE	350.00	LFT
0096	724-04163	STRUCTURAL EXPANSION JOINT SEAL, REPLACE	86.00	LFT

0097	724-12103	PRE-COMPRESSED FOAM JOINT	2346.00	LFT
0098	727-90308	EPOXY INJECTION, CRACK PREPARATION	142.00	LFT
0099	731-93947	LEVELING PAD, CONCRETE	12.00	LFT
0100	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	29881.00	SYS
0101	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	90.00	EACH
0102	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	EACH
0103	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	191787.00	LFT
0104	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	435.00	LFT
0105	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	44.00	LFT
0106	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00	EACH
0107	801-06640	CONSTRUCTION SIGN, A	413.00	EACH
0108	801-06710	FLASHING ARROW SIGN	396.00	DAY
0109	801-06775	MAINTAINING TRAFFIC	1.00	LS
0110	801-07118	BARRICADE, III-A	444.00	LFT
0111	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	5960.00	LFT
0112	801-12042	TRUCK MOUNTED ATTENUATOR	354.00	DAY
0113	804-06770	DELINEATOR POST	7.00	EACH
0114	808-06702	LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	1675.00	LFT
0115	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	6700.00	LFT
0116	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	12032.00	LFT
0117	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	13077.00	LFT
0118	808-06716	LINE, REMOVE	56059.00	LFT
0119	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	60420.00	LFT
0120	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	60420.00	LFT
0121	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	15108.00	LFT
0122	808-11959	LINE, PAINT, DOTTED, WHITE, 8 IN.	400.00	LFT
0123	808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	1539.00	LFT
0124	808-75008	LINE, PAINT, SOLID, WHITE, 8 IN.	1365.00	LFT
0125	808-75035	LINE, PAINT, SOLID, WHITE, 24 IN.	368.00	LFT
0126	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	6700.00	LFT
0127	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	901.00	EACH
0128	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	901.00	EACH

Call: 701

Contract: M -41268-A

Section No.: 1 GUARDRAIL, MAINTENANCE OR REPAIR

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	202-93741	GUARDRAIL, END TREATMENT, REMOVE	8.00	EACH
0006	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	5.00	EACH
0007	601-01625	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 1	2.00	EACH
0008	601-01626	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 2	1.00	EACH
0009	601-02211	GUARDRAIL POST, 8.5 LBS PER LFT, 7 FT LONG, GALVANIZED	25.00	EACH
0010	601-02241	GUARDRAIL, REMOVE	100.00	LFT
0011	601-02241	GUARDRAIL, REMOVE	100.00	LFT
0012	601-03452	EXCAVATION OF DAMAGED STEEL BEAM GUARDRAIL BURIED END SECTION LABOR ONLY	2.00	EACH
0013	601-03456	GUARDRAIL POST, WOOD TYPE W5	10.00	EACH
0014	601-03463	GUARDRAIL, STEEL CURVED TERMINAL END SECTION, LABOR ONLY	2.00	EACH
0015	601-03467	ALUMINUM TO STEEL SPLICE CONNECTOR, TYPE A S	1.00	EACH
0016	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	5.00	EACH
0017	601-03683	COMBINATION ATTENUATING TERMINAL, REPAIR, LABOR ONLY	60.00	HRS
0018	601-05856	CAT	2.00	EACH
0019	601-05856	CAT	3.00	EACH
0020	601-05856	CAT	2.00	EACH
0021	601-05856	CAT	3.00	EACH
0022	601-05856	CAT	5.00	EACH

0023	601-05856	CAT	2.00	EACH
0024	601-05856	CAT	5.00	EACH
0025	601-06035	GUARDRAIL, RESET	1000.00	LFT
0026	601-06037	GUARDRAIL, END TREATMENT, I	3.00	EACH
0027	601-06053	GUARDRAIL	10.00	EACH
0028	601-06273	GUARDRAIL, END TREATMENT, SKT-350	20.00	EACH
0029	601-06273	GUARDRAIL, END TREATMENT, SKT-350	5.00	EACH
0030	601-06273	GUARDRAIL, END TREATMENT, SKT-350	10.00	EACH
0031	601-06273	GUARDRAIL, END TREATMENT, SKT-350	5.00	EACH
0032	601-06273	GUARDRAIL, END TREATMENT, SKT-350	5.00	EACH
0033	601-06273	GUARDRAIL, END TREATMENT, SKT-350	20.00	EACH
0034	601-06728	GUARDRAIL, WR-BEAM	100.00	LFT
0035	601-06777	GRAVEL BARREL ARRAY	10.00	EACH
0036	601-06854	GUARDRAIL, W-BEAM, NESTED	10.00	EACH
0037	601-07607	IMPACT ATTENUATOR	1.00	EACH
0038	601-07607	IMPACT ATTENUATOR	1.00	EACH
0039	601-07607	IMPACT ATTENUATOR	1.00	EACH
0040	601-07607	IMPACT ATTENUATOR	1.00	EACH
0041	601-07607	IMPACT ATTENUATOR	1.00	EACH
0042	601-07607	IMPACT ATTENUATOR	1.00	EACH
0043	601-07607	IMPACT ATTENUATOR	1.00	EACH
0044	601-07607	IMPACT ATTENUATOR	1.00	EACH
0045	601-07607	IMPACT ATTENUATOR	1.00	EACH
0046	601-07607	IMPACT ATTENUATOR	1.00	EACH
0047	601-07607	IMPACT ATTENUATOR	1.00	EACH
0048	601-07607	IMPACT ATTENUATOR	1.00	EACH
0049	601-07607	IMPACT ATTENUATOR	1.00	EACH
0050	601-07607	IMPACT ATTENUATOR	1.00	EACH
0051	601-07607	IMPACT ATTENUATOR	1.00	EACH
0052	601-07607	IMPACT ATTENUATOR	1.00	EACH
0053	601-07607	IMPACT ATTENUATOR	1.00	EACH
0054	601-07607	IMPACT ATTENUATOR	1.00	EACH
0055	601-07607	IMPACT ATTENUATOR	1.00	EACH
0056	601-07607	IMPACT ATTENUATOR	1.00	EACH
0057	601-07607	IMPACT ATTENUATOR	1.00	EACH
0058	601-07607	IMPACT ATTENUATOR	1.00	EACH
0059	601-07607	IMPACT ATTENUATOR	1.00	EACH

0060	601-07607	IMPACT ATTENUATOR	1.00	EACH
0061	601-07607	IMPACT ATTENUATOR	1.00	EACH
0062	601-09238	HAND DIG GUARDRAIL POST HOLES	1.00	EACH
0063	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	375.00	LFT
0064	601-12287	GUARDRAIL, MGS, LONG SPAN, TYPE 1	1.00	EACH
0065	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	1.00	EACH
0066	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00	EACH
0067	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	1.00	EACH
0068	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	1.00	EACH
0069	601-12293	GUARDRAIL, MGS, STRUCTURE, TOP-MOUNTED POST	1.00	EACH
0070	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	1.00	EACH
0071	601-12404	MODIFIED MGS W-BEAM POST	1.00	EACH
0072	601-52540	GUARDRAIL TERMINAL SECTION, W BEAM	5.00	EACH
0073	601-61320	CURVED SECTION, STEEL BEAM GUARDRAIL GALVANIZED, 12 GA.	400.00	LFT
0074	601-61340	GUARDRAIL POST, 15.5 LBS PER FT., GALVANIZED, 6 FT. 3 IN. LONG	45.00	EACH
0075	601-61350	GUARDRAIL POST BRACKET, 15.5 LBS PER LFT., GALVANIZED, 1 FT. 2.25 IN.	200.00	EACH
0076	601-61360	GUARDRAIL POST, 8.5 LBS PER LFT., GALVANIZED, 5 FT. 9 IN. LONG	10.00	EACH
0077	601-61390	GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE, GALVANIZED	10.00	EACH
0078	601-62070	GUARDRAIL, STEEL BEAM, GALVANIZED	15000.00	LFT
0079	601-62090	GUARDRAIL, STEEL BEAM, INSTALL	400.00	LFT
0080	601-62100	GUARDRAIL POST, STEEL, INSTALL	10.00	EACH
0081	601-62110	GUARDRAIL, CHANNEL, 6.7 LBS PER LFT., INSTALL	1500.00	LFT
0082	601-62150	GUARDRAIL POST, 15.5 LBS PER LFT, GALVANIZED, 7 FT 0 IN. LONG	5.00	EACH
0083	601-62260	GUARDRAIL FLAT TERMINAL END SECTION, GALVANIZED	5.00	EACH
0084	601-62460	GUARDRAIL ANCHOR CABLE ASSEMBLY, 0.75 IN.	5.00	EACH
0085	601-62510	GUARDRAIL BREAKAWAY CABLE TERMINAL, MICHIGAN END SHOE	10.00	EACH
0086	601-62540	GUARDRAIL POST, PLUMB	1000.00	EACH
0087	601-62554	GUARDRAIL, TUBING, ELLIPTICAL, ALUMINUM, INSTALL	150.00	LFT
0088	601-90745	GUARDRAIL POST ALUMINUM	10.00	EACH
0089	601-90745	GUARDRAIL POST ALUMINUM	10.00	EACH
0090	601-91426	GUARDRAIL TERMINAL END SECTION, A	5.00	EACH
0091	601-91468	GUARDRAIL POST, 8.5 LBS PER LFT., GALVANIZED, 6 FT. 0 IN. LONG	50.00	EACH
0092	601-91502	GUARDRAIL TERMINAL SECTION, WOOD BREAKAWAY POST	5.00	EACH
0093	601-91504	GUARDRAIL POST, W1, 10 IN X 10 IN	2.00	EACH
0094	601-91505	GUARDRAIL POST, W2, 8 IN. X 8 IN.	5.00	EACH
0095	601-91510	GUARDRAIL POST, W3, 8 IN. X 8 IN.	5.00	EACH
0096	601-91511	GUARDRAIL POST, W4, 8 IN. X 8 IN.	5.00	EACH

0097	601-91542	GUARDRAIL BLOCK, 6 IN. X 8 IN., B1	10.00	EACH
0098	601-91575	GUARDRAIL BLOCK, 6 IN. X 8 IN., B2	10.00	EACH
0099	601-91576	GUARDRAIL BLOCK, 6 IN. X 8 IN., B3	10.00	EACH
0100	601-91578	GUARDRAIL TERMINAL SECTION, ANCHOR PLATE	5.00	EACH
0101	601-91640	GUARDRAIL TERMINAL SECTION, SOIL PLATE	2.00	EACH
0102	601-91642	GUARDRAIL TERMINAL SECTION, BEARING PLATE	5.00	EACH
0103	601-91643	GUARDRAIL ANCHOR CABLE, 0.75 IN. DIA. X 9 FT.	5.00	EACH
0104	601-91649	GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	5.00	EACH
0105	601-91650	GUARDRAIL THRIE BEAM EXPANSION RAIL, GALVANIZED	75.00	LFT
0106	601-91653	GUARDRAIL THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	2.00	EACH
0107	601-91654	GUARDRAIL ROUND NOSE SUPPORT ATTACHMENT, GALVANIZED	1.00	EACH
0108	601-91656	GUARDRAIL SQUARE NOSE SUPPORT ATTACHMENT, GALVANIZED	1.00	EACH
0109	601-94689	GUARDRAIL, END TREATMENT, OS	13.00	EACH
0110	601-94690	GUARDRAIL, END TREATMENT, MS	1.00	EACH
0111	601-95916	GUARDRAIL POST 5 FT 3 IN. LONG, ALUMINUM, INSTALL	10.00	EACH
0112	601-95927	GUARDRAIL TERMINAL SECTION, SINGLEFACE, BURIED END, ALUMINUM, INSTALL	5.00	EACH
0113	601-95928	GUARDRAIL TERMINAL SECTION, DOUBLEFACE, BURIED END, ALUMINUM, INSTALL	2.00	EACH
0114	601-97948	GUARDRAIL POST, PADDLE, 15.5 LBS PER LFT, GALVANIZED, 6 FT. 3 IN. LONG	2.00	EACH
0115	601-97950	GUARDRAIL POST BRACKET, TREATED TIMBER, 6 IN. X 6 IN.	300.00	EACH
0116	601-98076	GUARDRAIL POST BRACKET, MODIFIED	10.00	EACH
0117	602-01064	CONCRETE BARRIER	100.00	LFT
0118	627-09327	CABLE BARRIER SYSTEM, TYPE TL-4	3000.00	LFT
0119	627-09331	SAFETY TERMINAL TYPE, TL-4	1.00	EACH
0120	627-09331	SAFETY TERMINAL TYPE, TL-4	1.00	EACH
0121	627-09331	SAFETY TERMINAL TYPE, TL-4	1.00	EACH
0122	627-09331	SAFETY TERMINAL TYPE, TL-4	1.00	EACH
0123	627-09331	SAFETY TERMINAL TYPE, TL-4	1.00	EACH
0124	627-09331	SAFETY TERMINAL TYPE, TL-4	1.00	EACH
0125	627-09912	CABLE RELEASE POST LESS SOCKET, REPAIR	3.00	EACH
0126	627-09913	CABLE SOCKET WITH CONCRETE, REPAIR	3.00	EACH
0127	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0128	801-06775	MAINTAINING TRAFFIC	1.00	LS
0129	801-92448	CONSTRUCTION SIGNS MOBILE	1000.00	DAY

Call: 711

Contract: M -41539-A

Section No.: 1 WEDGE AND LEVEL

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL

0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	303-07449	COMPACTED AGGREGATE NO. 73	820.00	TON
0011	304-07490	HMA PATCHING, TYPE B	950.00	TON
0012	304-07491	HMA PATCHING, TYPE C	362.00	TON
0013	306-08034	MILLING, ASPHALT, 1 1/2 IN.	4180.00	SYS
0014	306-08043	MILLING, TRANSITION	5750.00	SYS
0015	306-08432	MILLING, APPROACH	439.00	SYS
0016	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	3409.00	TON
0017	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	346.00	TON
0018	401-10258	JOINT ADHESIVE, SURFACE	27101.00	LFT
0019	401-11785	LIQUID ASPHALT SEALANT	27101.00	LFT
0020	406-05520	ASPHALT FOR TACK COAT	15.00	TON
0021	610-07487	HMA FOR APPROACHES, TYPE B	37.00	TON
0022	611-08232	MAILBOX ASSEMBLY, SINGLE RESET	1.00	EACH

0023	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	1419.00	LFT
0024	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1419.00	LFT
0025	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	44.00	LFT
0026	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	44.00	LFT
0027	801-06640	CONSTRUCTION SIGN, A	166.00	EACH
0028	801-06710	FLASHING ARROW SIGN	120.00	DAY
0029	801-06775	MAINTAINING TRAFFIC	1.00	LS
0030	801-92448	CONSTRUCTION SIGNS MOBILE	360.00	DAY
0031	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	540.00	LFT
0032	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	1950.00	LFT
0033	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	23383.00	LFT
0034	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	11262.00	LFT
0035	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	44.00	LFT
0036	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	246.00	EACH
0037	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	246.00	EACH

Call: 721

Contract: M -41814-A

Section No.: 1 ROADSIDE MAINTENANCE, TREE REMOVAL AND TRIMMING

Line

Item No	Item Code	Description	Quantity Unit	
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0006	201-02250	TREE 10 IN., REMOVE	5.00	EACH

0007	201-02255	TREE 18 IN., REMOVE	35.00	EACH
0008	201-02260	TREE 30 IN., REMOVE	36.00	EACH
0009	201-02265	TREE 48 IN., REMOVE	22.00	EACH
0010	201-02270	TREE 60 IN., REMOVE	2.00	EACH
0011	801-06640	CONSTRUCTION SIGN, A	6.00	EACH
0012	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 801

Contract: T -40022-A

Section No.: 1 TRAFFIC SIGNALS MODERNIZATION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	12.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	62.10	SYS
0012	202-02279	CURB AND GUTTER, REMOVE	390.00	LFT
0013	202-52710	SIDEWALK CONCRETE, REMOVE	75.60	SYS
0014	202-96022	CONCRETE FOUNDATION, REMOVE	3.00	EACH
0015	205-12108	STORM WATER MANAGEMENT BUDGET	10000.00	DOL
0016	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0017	207-09935	SUBGRADE TREATMENT, TYPE IC	105.60	SYS
0018	301-12234	COMPACTED AGGREGATE NO 53	45.70	CYS
0019	304-07491	HMA PATCHING, TYPE C	82.00	TON
0020	604-06070	SIDEWALK, CONCRETE	40.60	SYS
0021	604-08086	CURB RAMP, CONCRETE	55.60	SYS
0022	604-12083	DETECTABLE WARNING SURFACES	24.10	SYS
0023	605-06120	CURB, CONCRETE	180.00	LFT
0024	605-06140	CURB AND GUTTER, CONCRETE	475.00	LFT
0025	621-06570	TOPSOIL	62.10	CYS

0026	621-98038	MULCH HARDWOOD SHREDDED BARK	15.50	CYS
0027	628-09401	FIELD OFFICE, A	6.00	MOS
0028	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0029	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0030	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0031	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	6.00	MOS
0032	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0033	628-11977	COMPUTER SYSTEM	1.00	EACH
0034	720-44000	CASTING, ADJUST TO GRADE	4.00	EACH
0035	801-06640	CONSTRUCTION SIGN, A	28.00	EACH
0036	801-06645	CONSTRUCTION SIGN, B	12.00	EACH
0037	801-06775	MAINTAINING TRAFFIC	1.00	LS
0038	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	242.00	LFT
0039	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	57.00	LFT
0040	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	2.00	EACH
0041	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	144.00	SFT
0042	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	133.00	SFT
0043	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	43.00	SFT
0044	802-91122	SIGN GROUND MOUNTED RESET	2.00	EACH
0045	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.00	EACH
0046	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0047	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	16.00	EACH
0048	805-01842	HANDHOLE SIGNAL TYPE 1	5.00	EACH
0049	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	240.00	LFT

0050	805-02056	SPAN AND CATENARY FOR FLASHER	12.00	EACH
0051	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	8.00	EACH
0052	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0053	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	2.00	EACH
0054	805-07190	TRAFFIC SIGNAL HEAD, 1 SECTION, 12 IN.	24.00	EACH
0055	805-08244	CELLULAR MODEM KIT	1.00	EACH
0056	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL	7.00	EACH
0057	805-09845	CONTACT CLOSURE CARD	1.00	EACH
0058	805-09846	RECEIVER PROCESSOR	4.00	EACH
0059	805-10107	WIRELESS MAGNETOMETER DETECTOR	33.00	EACH
0060	805-11689	SIGNAL POLE, PEDESTAL, 20 FT	2.00	EACH
0061	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00	EACH
0062	805-78010	CONTROLLER AND CABINET, FLASHER SOLID STATE	3.00	EACH
0063	805-78109	CONTROLLER AND CABINET, SECONDARY MENU DRIVEN, 8 PHASE	1.00	EACH
0064	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	8.00	EACH
0065	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	7.00	EACH
0066	805-78415	SPAN, CATENARY, AND TETHER	8.00	EACH
0067	805-78420	DISCONNECT HANGER	19.00	EACH
0068	805-78445	SIGNAL SERVICE	5.00	EACH
0069	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	710.00	LFT
0070	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	1000.00	LFT
0071	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	2835.00	LFT
0072	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	3205.00	LFT
0073	805-78925	CONTROLLER CABINET FOUNDATION, P1	2.00	EACH
0074	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	16.00	EACH
0075	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	1.00	EACH
0076	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	400.00	LFT
0077	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	16.00	SYS
0078	808-06368	TRANSVERSE MARKING, REMOVE	481.00	LFT
0079	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	265.00	LFT
0080	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	103.00	LFT
0081	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	1.00	EACH
0082	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	411.00	LFT
0083	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	405.00	LFT

Call: 811

Contract: T -40176-A

Section No.: 1 TRAFFIC SIGNALS, NEW OR MODERNIZED

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	628-09409	MOBILE INTERNET SERVICE	9.00	MOS
0010	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0011	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0012	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0013	801-06775	MAINTAINING TRAFFIC	1.00	LS
0014	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	44.00	LFT
0015	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	62.90	SFT
0016	805-01842	HANDHOLE SIGNAL TYPE 1	2.00	EACH
0017	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	122.00	LFT
0018	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	2.00	EACH
0019	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0020	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	5.00	EACH
0021	805-06742	SOLAR POWERED FLASHING BEACON ASSEMBLY	3.00	EACH
0022	805-11377	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 35 FT.	1.00	EACH
0023	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, A	1.00	EACH
0024	805-11496	PEDESTRIAN HYBRID BEACON	4.00	EACH
0025	805-11771	SIGNAL POLE, PEDESTAL, 16 FT	3.00	EACH
0026	805-11817	PEDESTRIAN PUSH BUTTON, APS	2.00	EACH
0027	805-78412	SIGNAL POLE, PEDESTAL, 9FT	2.00	EACH
0028	805-78445	SIGNAL SERVICE	1.00	EACH
0029	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	67.00	LFT
0030	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	149.00	LFT
0031	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	324.00	LFT
0032	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0033	805-97042	SIGNAL POLE, WOOD, 5, 35 FT	1.00	EACH
0034	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	32.00	LFT

0035808-75300TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.64.00LFT

Call: 821

Contract: T -41218-A

Section No.: 1TRAFFIC MANAGEMENT SYSTEM PROJECT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS

0009	202-94954	BARRIER WALL, CONCRETE, REMOVE	357.50	LFT
0010	205-12108	STORM WATER MANAGEMENT BUDGET	10000.00	DOL
0011	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0012	601-02241	GUARDRAIL, REMOVE	76.00	LFT
0013	601-06035	GUARDRAIL, RESET	325.00	LFT
0014	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1585.00	LFT
0015	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	375.00	LFT
0016	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	6.00	EACH
0017	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	3.00	EACH
0018	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	20.00	EACH
0019	601-94689	GUARDRAIL, END TREATMENT, OS	7.00	EACH
0020	601-94690	GUARDRAIL, END TREATMENT, MS	4.00	EACH
0021	602-11938	CONCRETE BARRIER, MODIFIED SECTION	76.60	CYS
0022	628-09402	FIELD OFFICE, B	8.00	MOS
0023	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0024	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	40.00	EACH
0025	801-06640	CONSTRUCTION SIGN, A	60.00	EACH
0026	801-06645	CONSTRUCTION SIGN, B	60.00	EACH
0027	801-06710	FLASHING ARROW SIGN	36.00	DAY
0028	801-06775	MAINTAINING TRAFFIC	1.00	LS
0029	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1800.00	LFT
0030	802-06402	DYNAMIC MESSAGE SIGN	6.00	EACH
0031	802-07061	OVERHEAD SIGN STRUCTURE, DMS BOX TRUSS	6.00	EACH
0032	802-09535	BOX TRUSS SIGN STRUCTURE FOUNDATION, 33 IN. CONCRETE BARRIER WALL	2.00	EACH
0033	802-09536	BOX TRUSS SIGN STRUCTURE FOUNDATION, 45 IN. CONCRETE BARRIER WALL	3.00	EACH
0034	802-09898	BOX TRUSS SIGN STRUCTURE FOUNDATION, DMS 36 IN. HEIGHT	7.00	EACH
0035	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	1.00	EACH
0036	805-04973	CONDUIT	521.00	LFT
0037	805-04973	CONDUIT	3326.00	LFT
0038	805-04973	CONDUIT	10220.00	LFT
0039	805-09845	CONTACT CLOSURE CARD	31.00	EACH
0040	805-09846	RECEIVER PROCESSOR	31.00	EACH
0041	805-10107	WIRELESS MAGNETOMETER DETECTOR	288.00	EACH
0042	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	1.00	EACH
0043	807-04651	WIRE	3293.00	LFT
0044	807-04651	WIRE	11503.00	LFT
0045	807-04651	WIRE	14796.00	LFT

0046	807-78590	HANDHOLE	89.00	EACH
0047	809-04652	SERVICE POINT	33.00	EACH
0048	809-04652	SERVICE POINT	17.00	EACH
0049	809-04982	CABLE	8891.00	LFT

0050	809-06101	FOUNDATION	30.00	EACH
0051	809-06128	CCTV ASSEMBLY	37.00	EACH
0052	809-08398	ITS CONTROLLER CABINET	22.00	EACH
0053	809-08398	ITS CONTROLLER CABINET	8.00	EACH
0054	809-08399	ITS CONTROLLER CABINET FOUNDATION	22.00	EACH
0055	809-08571	AFP	37.00	EACH
0056	809-09343	ITS	37.00	EACH
0057	809-09343	ITS	6.00	EACH
0058	809-09343	ITS	1.00	EACH
0059	809-09343	ITS	5.00	EACH
0060	809-09343	ITS	24.00	EACH
0061	809-11707	ITS FIELD SWITCH	37.00	EACH

Call: 831

Contract: T -41219-A

Section No.: 1 ITS COMMUNICATIONS SYSTEMS

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	205-12108	STORM WATER MANAGEMENT BUDGET	3000.00	DOL
0009	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0010	628-09401	FIELD OFFICE, A	12.00	MOS
0011	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0012	715-04985	VAULT	3.00	EACH
0013	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0014	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0015	801-06710	FLASHING ARROW SIGN	12.00	DAY
0016	801-06775	MAINTAINING TRAFFIC	1.00	LS
0017	805-04973	CONDUIT	125.00	LFT
0018	805-04973	CONDUIT	235.00	LFT
0019	805-04973	CONDUIT	21985.00	LFT

0020	805-04973	CONDUIT	495.00	LFT
0021	805-04973	CONDUIT	170.00	LFT
0022	805-04973	CONDUIT	1170.00	LFT
0023	805-04973	CONDUIT	1170.00	LFT
0024	805-04973	CONDUIT	23365.00	LFT
0025	807-78590	HANDHOLE	38.00	EACH
0026	807-86955	CABLE-DUCT MARKER	23.00	EACH
0027	807-86955	CABLE-DUCT MARKER	39.00	EACH
0028	809-04970	FIBER OPTIC	978.00	EACH
0029	809-04970	FIBER OPTIC	2.00	EACH
0030	809-04970	FIBER OPTIC	2.00	EACH
0031	809-04970	FIBER OPTIC	8.00	EACH
0032	809-04970	FIBER OPTIC	12.00	EACH
0033	809-04970	FIBER OPTIC	3.00	EACH
0034	809-04970	FIBER OPTIC	4.00	EACH
0035	809-04970	FIBER OPTIC	10.00	EACH
0036	809-04970	FIBER OPTIC	3.00	EACH
0037	809-04970	FIBER OPTIC	3.00	EACH
0038	809-09343	ITS	1.00	EACH
0039	809-09343	ITS	5.00	EACH
0040	809-09343	ITS	3.00	EACH
0041	809-94971	FIBER OPTIC CABLE	25195.00	LFT

Call: 841

Contract: T -41220-A

Section No.: 1 ITS TRAFFIC MANAGEMENT SYSTEMS

Line

Item No	Item Code	Description	Quantity Unit	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL

0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	628-11729	CELLULAR TELEPHONE, TYPE A	5.00	EACH
0008	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0009	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0010	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	60.00	MOS
0011	628-11976	COMPUTER SYSTEM EQUIPMENT	5.00	EACH
0012	801-06640	CONSTRUCTION SIGN, A	34.00	EACH
0013	801-06645	CONSTRUCTION SIGN, B	12.00	EACH
0014	801-06710	FLASHING ARROW SIGN	120.00	DAY
0015	801-06775	MAINTAINING TRAFFIC	1.00	LS
0016	802-06402	DYNAMIC MESSAGE SIGN	1.00	EACH
0017	802-06402	DYNAMIC MESSAGE SIGN	14.00	EACH
0018	802-06402	DYNAMIC MESSAGE SIGN	28.00	EACH
0019	802-06402	DYNAMIC MESSAGE SIGN	3.00	EACH
0020	802-06402	DYNAMIC MESSAGE SIGN	52.00	EACH
0021	802-06402	DYNAMIC MESSAGE SIGN	104.00	EACH
0022	802-06402	DYNAMIC MESSAGE SIGN	20.00	EACH
0023	802-06402	DYNAMIC MESSAGE SIGN	8.00	EACH
0024	802-06402	DYNAMIC MESSAGE SIGN	41.00	EACH
0025	802-06402	DYNAMIC MESSAGE SIGN	22.00	EACH
0026	802-06402	DYNAMIC MESSAGE SIGN	9.00	EACH
0027	802-06402	DYNAMIC MESSAGE SIGN	37.00	EACH

Call: 851

Contract: T -41223-A

Section No.: 1 ITS DEVICES AND SIGNAL MAINTENANCE

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0006	202-86946	HANDHOLE, REMOVE	4.00	EACH

0007	202-90277	DETECTOR HOUSING, REMOVE	4.00	EACH
0008	202-95579	SERVICE POINT, REMOVE	1.00	EACH
0009	301-12231	COMPACTED AGGREGATE NO 2	20.00	CYS
0010	702-90915	CONCRETE, CLASS, A	10.00	CYS
0011	715-04985	VAULT	3.00	EACH
0012	801-06775	MAINTAINING TRAFFIC	1.00	LS
0013	802-03821	SIGN, SHEET, WITH LEGEND,	10.00	EACH
0014	805-01439	MICROWAVE DETECTOR	2.00	EACH
0015	805-01479	CONTROLLER CABINET FOUNDATION, P1 MODIFIED	1.00	EACH
0016	805-01842	HANDHOLE SIGNAL TYPE 1	4.00	EACH

0017	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	4.00	EACH
0018	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1000.00	LFT
0019	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0020	805-02202	SIGNAL DETECTOR HOUSING DOUBLE	2.00	EACH
0021	805-02658	CABLE COAXIAL	200.00	LFT
0022	805-04973	CONDUIT	200.00	LFT
0023	805-04973	CONDUIT	200.00	LFT
0024	805-06997	CAMERA	1.00	EACH
0025	805-07212	SPLICE KIT	4.00	EACH
0026	805-09089	RADIO YAGI ANTENNA	3.00	EACH
0027	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL	5.00	EACH
0028	805-09540	LOOP DETECTOR RACK	1.00	EACH
0029	805-09845	CONTACT CLOSURE CARD	4.00	EACH
0030	805-09846	RECEIVER PROCESSOR	6.00	EACH
0031	805-10107	WIRELESS MAGNETOMETER DETECTOR	85.00	EACH
0032	805-10108	WIRELESS REPEATER	2.00	EACH
0033	805-11539	AUXILIARY BIU PANEL	1.00	EACH
0034	805-11540	MICROLOOP DETECTOR PROBE	1.00	EACH
0035	805-11569	RADIO SPLITTER	1.00	EACH
0036	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	200.00	LFT
0037	805-11817	PEDESTRIAN PUSH BUTTON, APS	1.00	EACH
0038	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	14000.00	LFT
0039	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	4500.00	LFT
0040	805-78785	SIGNAL DETECTOR HOUSING	10.00	EACH
0041	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	4300.00	LFT
0042	805-91706	ANCHOR BOLT REPAIR	1.00	EACH
0043	805-92951	SIGNAL DETECTOR HOUSING ADJUST TO GRADE	6.00	EACH
0044	805-93067	CONTROLLER CABINET, P	1.00	EACH
0045	807-01617	HANDHOLE COVER AND RING	3.00	EACH
0046	807-04651	WIRE	200.00	LFT
0047	807-78590	HANDHOLE	5.00	EACH
0048	807-87085	ELECTRICIAN	1.00	HRS
0049	809-04956	PANEL FOR FIBER OPTICS	1.00	EACH

0050	809-04970	FIBER OPTIC	20.00	EACH
0051	809-04970	FIBER OPTIC	12.00	EACH
0052	809-04970	FIBER OPTIC	2.00	EACH
0053	809-04970	FIBER OPTIC	8.00	EACH
0054	809-04982	CABLE	500.00	LFT
0055	809-04982	CABLE	800.00	LFT
0056	809-06114	ANTENNA	1.00	EACH
0057	809-06128	CCTV ASSEMBLY	1.00	EACH
0058	809-08398	ITS CONTROLLER CABINET	2.00	EACH
0059	809-08399	ITS CONTROLLER CABINET FOUNDATION	1.00	EACH
0060	809-09343	ITS	4.00	EACH
0061	809-09343	ITS	4.00	EACH
0062	809-09343	ITS	4.00	EACH
0063	809-94971	FIBER OPTIC CABLE	2000.00	LFT

Call: 861

Contract: T -41224-A

Section No.: 1 ITS DEVICES AND SIGNAL MAINTENANCE

Line

Item No	Item Code	Description	Quantity Unit	
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0006	202-86946	HANDHOLE, REMOVE	6.00	EACH
0007	202-90277	DETECTOR HOUSING, REMOVE	5.00	EACH
0008	202-95579	SERVICE POINT, REMOVE	1.00	EACH
0009	301-12231	COMPACTED AGGREGATE NO 2	20.00	CYS
0010	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0011	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0012	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0013	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	12.00	MOS
0014	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0015	702-90915	CONCRETE, CLASS, A	10.00	CYS
0016	715-04985	VAULT	1.00	EACH
0017	801-06775	MAINTAINING TRAFFIC	1.00	LS

0018	802-03821	SIGN, SHEET, WITH LEGEND,	10.00	EACH
0019	805-01439	MICROWAVE DETECTOR	1.00	EACH
0020	805-01479	CONTROLLER CABINET FOUNDATION, P1 MODIFIED	1.00	EACH
0021	805-01842	HANDHOLE SIGNAL TYPE 1	4.00	EACH
0022	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	4.00	EACH
0023	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	2000.00	LFT
0024	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0025	805-02202	SIGNAL DETECTOR HOUSING DOUBLE	2.00	EACH
0026	805-02658	CABLE COAXIAL	1200.00	LFT
0027	805-04973	CONDUIT	200.00	LFT
0028	805-04973	CONDUIT	200.00	LFT
0029	805-06997	CAMERA	1.00	EACH
0030	805-07212	SPLICE KIT	4.00	EACH
0031	805-09089	RADIO YAGI ANTENNA	6.00	EACH
0032	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL	2.00	EACH
0033	805-09540	LOOP DETECTOR RACK	2.00	EACH
0034	805-09845	CONTACT CLOSURE CARD	2.00	EACH
0035	805-09846	RECEIVER PROCESSOR	2.00	EACH
0036	805-10107	WIRELESS MAGNETOMETER DETECTOR	60.00	EACH
0037	805-10108	WIRELESS REPEATER	2.00	EACH
0038	805-11539	AUXILIARY BIU PANEL	1.00	EACH
0039	805-11540	MICROLOOP DETECTOR PROBE	2.00	EACH
0040	805-11569	RADIO SPLITTER	2.00	EACH
0041	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	250.00	LFT
0042	805-11817	PEDESTRIAN PUSH BUTTON, APS	34.00	EACH
0043	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	15000.00	LFT
0044	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	4800.00	LFT
0045	805-78785	SIGNAL DETECTOR HOUSING	6.00	EACH
0046	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	4600.00	LFT
0047	805-91706	ANCHOR BOLT REPAIR	1.00	EACH
0048	805-92951	SIGNAL DETECTOR HOUSING ADJUST TO GRADE	8.00	EACH
0049	805-93067	CONTROLLER CABINET, P	1.00	EACH

0050	807-01617	HANDHOLE COVER AND RING	8.00	EACH
0051	807-04651	WIRE	200.00	LFT
0052	807-78590	HANDHOLE	5.00	EACH
0053	807-87085	ELECTRICIAN	20.00	HRS
0054	809-04956	PANEL FOR FIBER OPTICS	2.00	EACH
0055	809-04970	FIBER OPTIC	3.00	EACH
0056	809-04970	FIBER OPTIC	20.00	EACH
0057	809-04970	FIBER OPTIC	18.00	EACH
0058	809-04970	FIBER OPTIC	18.00	EACH
0059	809-04970	FIBER OPTIC	8.00	EACH
0060	809-04982	CABLE	200.00	LFT
0061	809-04982	CABLE	200.00	LFT
0062	809-06114	ANTENNA	2.00	EACH
0063	809-06128	CCTV ASSEMBLY	1.00	EACH
0064	809-08398	ITS CONTROLLER CABINET	1.00	EACH
0065	809-08399	ITS CONTROLLER CABINET FOUNDATION	1.00	EACH
0066	809-09343	ITS	1.00	EACH
0067	809-09343	ITS	2.00	EACH
0068	809-09343	ITS	1.00	EACH
0069	809-94971	FIBER OPTIC CABLE	1000.00	LFT

Call: 871

Contract: T -41225-A

Section No.: 1 ITS DEVICES AND SIGNAL MAINTENANCE

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0006	202-86946	HANDHOLE, REMOVE	4.00	EACH
0007	202-90277	DETECTOR HOUSING, REMOVE	4.00	EACH
0008	202-95579	SERVICE POINT, REMOVE	1.00	EACH
0009	301-12231	COMPACTED AGGREGATE NO 2	20.00	CYS
0010	702-90915	CONCRETE, CLASS, A	8.00	CYS
0011	715-04985	VAULT	1.00	EACH

0012	801-06775	MAINTAINING TRAFFIC	1.00	LS
0013	802-03821	SIGN, SHEET, WITH LEGEND,	10.00	EACH
0014	805-01439	MICROWAVE DETECTOR	1.00	EACH
0015	805-01479	CONTROLLER CABINET FOUNDATION, P1 MODIFIED	1.00	EACH
0016	805-01842	HANDHOLE SIGNAL TYPE 1	2.00	EACH
0017	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	4.00	EACH
0018	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	500.00	LFT
0019	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00	LS
0020	805-02202	SIGNAL DETECTOR HOUSING DOUBLE	2.00	EACH
0021	805-02658	CABLE COAXIAL	300.00	LFT
0022	805-04973	CONDUIT	200.00	LFT
0023	805-04973	CONDUIT	200.00	LFT
0024	805-06997	CAMERA	1.00	EACH
0025	805-07212	SPLICE KIT	4.00	EACH
0026	805-09089	RADIO YAGI ANTENNA	3.00	EACH
0027	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL	2.00	EACH
0028	805-09540	LOOP DETECTOR RACK	1.00	EACH
0029	805-09845	CONTACT CLOSURE CARD	2.00	EACH
0030	805-09846	RECEIVER PROCESSOR	2.00	EACH
0031	805-10107	WIRELESS MAGNETOMETER DETECTOR	25.00	EACH
0032	805-10108	WIRELESS REPEATER	1.00	EACH
0033	805-11539	AUXILIARY BIU PANEL	1.00	EACH
0034	805-11540	MICROLOOP DETECTOR PROBE	2.00	EACH
0035	805-11569	RADIO SPLITTER	2.00	EACH
0036	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	200.00	LFT
0037	805-11817	PEDESTRIAN PUSH BUTTON, APS	9.00	EACH
0038	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	7500.00	LFT
0039	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	3800.00	LFT
0040	805-78785	SIGNAL DETECTOR HOUSING	2.00	EACH
0041	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	3600.00	LFT
0042	805-91706	ANCHOR BOLT REPAIR	1.00	EACH
0043	805-92951	SIGNAL DETECTOR HOUSING ADJUST TO GRADE	4.00	EACH
0044	807-01617	HANDHOLE COVER AND RING	2.00	EACH
0045	807-04651	WIRE	200.00	LFT
0046	807-78590	HANDHOLE	2.00	EACH
0047	807-87085	ELECTRICIAN	10.00	HRS
0048	809-04956	PANEL FOR FIBER OPTICS	1.00	EACH

0049	809-04970	FIBER OPTIC	2.00	EACH
------	-----------	-------------	------	------

0050	809-04970	FIBER OPTIC	10.00	EACH
0051	809-04970	FIBER OPTIC	6.00	EACH
0052	809-04970	FIBER OPTIC	6.00	EACH
0053	809-04970	FIBER OPTIC	8.00	EACH
0054	809-04982	CABLE	1000.00	LFT
0055	809-04982	CABLE	800.00	LFT
0056	809-06114	ANTENNA	6.00	EACH
0057	809-09343	ITS	1.00	EACH
0058	809-09343	ITS	1.00	EACH
0059	809-09343	ITS	1.00	EACH
0060	809-94971	FIBER OPTIC CABLE	500.00	LFT

Call: 881

Contract: T -41661-A

Section No.: 1 SIGNAL MODERNIZATION

Line

Item No	Item Code	Description	Quantity Unit	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	801-06775	MAINTAINING TRAFFIC	1.00	LS
0008	805-12016	UNINTERRUPTIBLE POWER SUPPLY	17.00	EACH

Call: 891

Contract: T -41793-A

Section No.: 1 TRAFFIC SIGNAL VISIBILITY IMPROVEMENTS

Line

Item No	Item Code	Description	Quantity Unit	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS

0007	628-09402	FIELD OFFICE, B	9.00	MOS
0008	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0009	801-06775	MAINTAINING TRAFFIC	1.00	LS
0010	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	32.00	LFT
0011	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	143.00	SFT
0012	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	20.00	SFT
0013	805-03372	TETHER FOR SIGNAL	89.00	EACH
0014	805-06483	CONTROLLER	1.00	EACH
0015	805-08487	BACKPLATE, SIGNAL	24.00	EACH
0016	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	266.00	EACH
0017	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	16.00	EACH
0018	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	13.00	EACH
0019	805-78245	TRAFFIC SIGNAL HEAD, OPTICALLY PROGRAMMED, 3 SECTION, 12 IN.	4.00	EACH
0020	805-78415	SPAN, CATENARY, AND TETHER	6.00	EACH
0021	805-78420	DISCONNECT HANGER	87.00	EACH
0022	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	698.00	LFT
0023	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	4022.00	LFT
0024	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	2706.00	LFT

Call: 901

Contract: TM-41267-A

Section No.: 1 LIGHTING MAINTENANCE

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS

0006	202-52710	SIDEWALK CONCRETE, REMOVE	10.00	SYS
0007	202-90277	DETECTOR HOUSING, REMOVE	1.00	EACH
0008	202-93763	LIGHT STANDARD AND FOUNDATION, REMOVE	2.00	EACH
0009	604-06070	SIDEWALK, CONCRETE	10.00	SYS
0010	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0011	702-90915	CONCRETE, CLASS, A	5.00	CYS
0012	801-06775	MAINTAINING TRAFFIC	1.00	LS
0013	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	2.00	EACH
0014	805-01816	SIGNAL SUPPORT FOUNDATION, 36 IN. X 36 IN. X 96 IN.	1.00	EACH
0015	805-01842	HANDHOLE SIGNAL TYPE 1	1.00	EACH
0016	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	100.00	LFT
0017	805-09845	CONTACT CLOSURE CARD	1.00	EACH
0018	805-09846	RECEIVER PROCESSOR	1.00	EACH
0019	805-10107	WIRELESS MAGNETOMETER DETECTOR	1.00	EACH

0020	805-10108	WIRELESS REPEATER	1.00	EACH
0021	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	100.00	LFT
0022	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	2500.00	LFT
0023	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	200.00	LFT
0024	805-78785	SIGNAL DETECTOR HOUSING	5.00	EACH
0025	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	800.00	LFT
0026	805-86898	CONDUIT, STEEL, GALVANIZED, 0.75 IN.	20.00	LFT
0027	805-87715	GROUND ROD WITH CONNECTOR	1.00	EACH
0028	805-87780	CIRCUIT BREAKER	5.00	EACH
0029	805-91706	ANCHOR BOLT REPAIR	3.00	EACH
0030	805-95518	CONDUIT, FLEXIBLE, 2 IN.	15.00	LFT
0031	805-95519	CONDUIT, FLEXIBLE, 0.75 IN.	5.00	LFT
0032	805-95520	EXPANSION FITTING 2.0 IN.	1.00	EACH
0033	805-95521	EXPANSION FITTING 0.75 IN.	2.00	EACH
0034	805-97042	SIGNAL POLE, WOOD, 5, 35 FT	1.00	EACH
0035	807-01425	SHAFT FOR ANY EMH, ANY MAST ARM, INSTALL	15.00	EACH
0036	807-01562	POWER DISCONNECT PLUG FOR HIGH MAST TOWER	1.00	EACH
0037	807-01617	HANDHOLE COVER AND RING	1.00	EACH
0038	807-02105	ROUTINE MAINTENANCE LUMINAIRE HIGH PRESSURE SODIUM 150 WATT	72.00	MOS
0039	807-02191	HANDHOLE LIGHTING	2.00	EACH
0040	807-02782	LUMINAIRE MAST ARM 12 FT	1.00	EACH
0041	807-02783	LUMINAIRE MAST ARM 15 FT	1.00	EACH
0042	807-04428	CABLE DUCT	2500.00	LFT
0043	807-04654	LIGHT POLE	1.00	EACH
0044	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	100.00	LFT
0045	807-11365	LUMINAIRE, ROADWAY, LED, 250 WATT	43.00	EACH
0046	807-12266	ROUTINE MAINTENANCE LUMINAIRE LED 250 WATT	516.00	MOS
0047	807-78590	HANDHOLE	1.00	EACH
0048	807-78590	HANDHOLE	1.00	EACH
0049	807-78590	HANDHOLE	1.00	EACH

0050	807-86615	LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 250 WATT	20.00	EACH
0051	807-86620	LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 400 WATT	20.00	EACH
0052	807-86665	LUMINAIRE, HIGH MAST HIGH PRESSURE SODIUM, 1000 WATT	2.00	EACH
0053	807-86805	SERVICE POINT, I	1.00	EACH
0054	807-86810	SERVICE POINT, II	3.00	EACH
0055	807-86843	WIRE, NO. 4 COPPER, 1/C	3000.00	LFT
0056	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	1800.00	LFT
0057	807-86910	CONNECTOR KIT, UNFUSED	15.00	EACH
0058	807-86915	CONNECTOR KIT, FUSED	20.00	EACH
0059	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	45.00	EACH
0060	807-86930	INSULATION LINK, NON-WATERPROOFED	20.00	EACH
0061	807-86950	SIGN, UNDERPASS AND ROADWAY LIGHTING LOCATION IDENTIFICATION	5.00	EACH
0062	807-86955	CABLE-DUCT MARKER	1.00	EACH
0063	807-87022	ROUTINE MAINTENANCE LUMINAIRE HIGH PRESSURE SODIUM 400 WATT	10788.00	MOS
0064	807-87028	ROUTINE MAINTENANCE LUMINAIRE HIGH PRESSURE SODIUM 1000 WATT	8496.00	MOS
0065	807-87042	ROUTINE MAINTENANCE LUMINAIRE HIGH PRESSURE SODIUM UNDERPASS 150 WATT	1692.00	MOS
0066	807-87055	ROUTINE MAINTENANCE LUMINAIRE MERCURY VAPOR 400W	84.00	MOS
0067	807-87085	ELECTRICIAN	20.00	HRS
0068	807-87098	CALLOUT REPAIR	1.00	EACH
0069	807-87635	MAST ARM INSTALL	5.00	EACH
0070	807-87640	BREAKAWAY COUPLING	2.00	SET
0071	807-91704	LIGHT POLE HANDHOLE COVER	1.00	EACH
0072	807-91705	CONDUIT POLYETHYLENE REPAIR	2.00	EACH
0073	807-92523	SKIRTING, EXPANDED ALUMINUM	1.00	EACH
0074	807-93650	FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR ROADWAY LIGHT	1.00	SET
0075	807-93746	TOWER RING LIFT CABLE, 0.375	150.00	LFT
0076	807-95078	TRANSFORMER BASE	9.00	EACH
0077	807-95488	NEMA 4/5 UNDERPASS OR SIGN CIRCUIT BREAKER, ENCLOSURE	1.00	EACH
0078	807-95492	SERVICE POINT, II, BREAKER ENCLOSURE	1.00	EACH
0079	807-95508	VANDAL SHIELD, LEXAN	1.00	EACH
0080	807-95509	GLARE SHIELD	1.00	EACH
0081	807-95513	SERVICE POINT MAIN BREAKER	2.00	EACH
0082	807-95514	SERVICE POINT RISER	1.00	EACH
0083	807-95515	SERVICE POINT WEATHERHEAD	1.00	EACH
0084	807-95516	RELAY SWITCH	9.00	EACH
0085	807-95522	PIPE STRAP	1.00	EACH
0086	807-95523	WATERPROOFING OF ELECTRICAL CONNECTOR	23.00	EACH

0087	807-95525	LIGHTING SUPPORT	1.00	EACH
0088	807-95709	PHOTOCELLS	10.00	EACH
0089	807-96194	ROUTINE MAINTENANCE LUMINAIRE HIGH PRESSURE SODIUM 250 WATT	4788.00	MOS
0090	807-96203	LIGHT POLE, HIGH MAST, TOWER SUSPENSION CABLE	1.00	EACH
0091	807-96204	LOWERING AND RAISING OF TOWER	2.00	EACH
0092	807-96236	LIGHT POLE, HIGH MAST, TOWER POWER CABLE	1.00	EACH
0093	807-96868	LUMINAIRE INSTALL	1.00	EACH
0094	807-98716	KELLUM GRIP STAINLESS STEEL	1.00	EACH