

Schedule of Pav Items Letting Date April 17, 2019 Letting ID 190417

Call: 143

Contract: R -35457-A

Section No.: 1 BRIDGE DECK REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	19120.00	SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-94954	BARRIER WALL, CONCRETE, REMOVE	695.00	LFT
0017	203-02000	EXCAVATION, COMMON	1895.50	CYS
0018	205-12108	STORM WATER MANAGEMENT BUDGET	63966.00	DOL
0019	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	6414.00	SYS
0021	211-06467	AGGREGATE FOR END BENT BACKFILL	127.80	CYS
0022	214-12236	GEOTEXTILE FOR PAVEMENT TYPE 1A	30288.00	SYS
0023	215-12446	CEMENT STABILIZED SUBGRADE SOILS	30288.00	SYS
0024	215-12447	CEMENT STABILIZATION OF FOUNDATION SOIL	30288.00	SYS
0025	301-12234	COMPACTED AGGREGATE NO 53	5048.00	CYS
0026	302-06464	SUBBASE FOR PCCP	107.00	CYS
0027	302-07455	DENSE GRADED SUBBASE	300.10	CYS
0028	303-01180	COMPACTED AGGREGATE NO. 53	1923.00	TON
0029	303-07449	COMPACTED AGGREGATE NO. 73	3463.00	TON
0030	304-07490	HMA PATCHING, TYPE B	36.00	TON
0031	304-07783	HMA PATCHING, TYPE D	464.00	TON
0032	304-07783	HMA PATCHING, TYPE D	156.00	TON
0033	306-08036	MILLING, ASPHALT, 2 IN.	475243.00	SYS
0034	306-08038	MILLING, ASPHALT, 4 IN.	25583.00	SYS
0035	306-08043	MILLING, TRANSITION	1860.00	SYS

0036	306-08432	MILLING, APPROACH	620.00	SYS
0037	306-10113	MILLING, ASPHALT, 4 1/2 IN.	16924.00	SYS
0038	401-06264	PROFILOGRAPH, HMA	1.00	LS
0039	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	9967.00	TON
0040	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	4222.00	TON
0041	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	2327.00	TON
0042	401-10258	JOINT ADHESIVE, SURFACE	200313.00	LFT
0043	401-10259	JOINT ADHESIVE, INTERMEDIATE	10186.00	LFT
0044	401-11785	LIQUID ASPHALT SEALANT	267130.00	LFT
0045	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	4544.00	TON
0046	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0047	401-12439	VOID REDUCING ASPHALT MEMBRANE	122400.00	LFT
0048	402-10087	HMA FOR TEMPORARY PAVEMENT, D	3617.00	TON
0049	406-05520	ASPHALT FOR TACK COAT	142.00	TON
0050	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	22.00	TON
0051	410-11777	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm - SMA	46489.00	TON
0052	501-06266	PROFILOGRAPH PCCP	1.00	LS
0053	501-06323	QC/QA-PCCP, 12 IN.	27403.00	SYS
0054	503-05240	D-1 CONTRACTION JOINT	16720.00	LFT
0055	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	320.00	LFT
0056	506-06333	PCCP PATCHING, FULL DEPTH	437.00	SYS
0057	601-02205	TEMPORARY GUARDRAIL TRANSITION, TGB	3.00	EACH
0058	601-02206	TEMPORARY GUARDRAIL, W BEAM, 6FT-3 IN SPACING	432.00	LFT
0059	601-02241	GUARDRAIL, REMOVE	8168.00	LFT
0060	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	3607.00	LFT
0061	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	1163.00	LFT
0062	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	1.00	EACH
0063	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	19.00	EACH
0064	601-52540	GUARDRAIL TERMINAL SECTION, W BEAM	1.00	EACH
0065	601-94689	GUARDRAIL, END TREATMENT, OS	12.00	EACH
0066	601-94690	GUARDRAIL, END TREATMENT, MS	8.00	EACH
0067	601-97080	TEMPORARY GUARDRAIL END TREATMENT, OS	3.00	EACH
0068	602-01064	CONCRETE BARRIER	695.00	LFT
0069	602-06729	BARRIER, DELINEATOR	36.00	EACH
0070	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	133633.00	LFT
0071	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	845.70	SYS
0072	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	990.00	SYS
0073	610-07788	HMA FOR APPROACHES, TYPE D	69.00	TON
0074	615-06520	MONUMENT, RE-ESTABLISH	25.00	EACH
0075	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	248.70	SYS
0076	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0077	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0078	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS

0079	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0080	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0081	621-06545	FERTILIZER	4.20	TON
0082	621-06553	SEED MIXTURE R	1630.60	LBS
0083	621-06565	MULCHING MATERIAL	15.50	TON
0084	621-06567	WATER	9.68	KGAL
0085	621-06574	SODDING	8400.00	SYS
0086	627-09327	CABLE BARRIER SYSTEM, TYPE TL-4	800.00	LFT
0087	627-09331	SAFETY TERMINAL TYPE, TL-4	2.00	EACH
0088	628-09402	FIELD OFFICE, B	12.00	MOS
0089	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0090	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	16.00	EACH
0091	702-51005	CONCRETE, A, SUBSTRUCTURE	3.00	CYS
0092	702-51863	FIELD DRILLED HOLE IN CONCRETE	493.00	EACH
0093	703-06029	REINFORCING BARS, EPOXY COATED	476193.00	LBS
0094	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	207.00	EACH
0095	704-51002	CONCRETE, C, SUPERSTRUCTURE	818.40	CYS
0096	706-11600	RAILING, CONCRETE FC	56.60	CYS
0097	706-11601	RAILING, CONCRETE FT	72.90	CYS
0098	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	20.00	EACH
0099	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	4.00	EACH
0100	709-51821	SURFACE SEAL	1.00	LS
0101	709-51821	SURFACE SEAL	1.00	LS
0102	709-51821	SURFACE SEAL	1.00	LS
0103	709-51821	SURFACE SEAL	1.00	LS
0104	709-51821	SURFACE SEAL	1.00	LS
0105	709-51821	SURFACE SEAL	1.00	LS
0106	709-51821	SURFACE SEAL	1.00	LS
0107	710-09158	PATCHING CONCRETE STRUCTURES	350.00	SFT
0108	711-51864	DRILLED HOLE	120.00	EACH
0109	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00	LS
0110	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00	LS
0111	711-96800	STUD SHEAR CONNECTORS	7140.00	EACH
0112	715-01662	PIPE CLEANING, 12 IN. TO 48 IN. DIA.	1337.00	LFT
0113	715-04985	VAULT	7.00	EACH
0114	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	12724.00	LFT
0115	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	1653.00	LFT
0116	715-05407	PIPE, END BENT DRAIN, 6 IN.	218.00	LFT
0117	718-06529	OUTLET PROTECTOR, 2	16.00	EACH
0118	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00	LFT
0119	718-11685	UNDERDRAIN CLEANOUT PORT	10.00	EACH
0120	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	12095.00	SYS
0121	718-52610	AGGREGATE FOR UNDERDRAINS	1730.00	CYS

0122	720-01355	INLET, CLEAN EXISTING	11.00	EACH
0123	720-44000	CASTING, ADJUST TO GRADE	8.00	EACH
0124	722-01066	HYDRODEMOLITION	1856.00	SYS
0125	722-12380	BRIDGE DECK OVERLAY, BUDGET	40600.00	DOL
0126	722-12382	TRANSVERSE GROOVING	3432.00	SYS
0127	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	1162.00	SFT
0128	722-51822	BRIDGE DECK OVERLAY, REMOVE EXISTING	1856.00	SYS
0129	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	4261.00	SFT
0130	722-51874	OVERLAY DAM	384.00	SFT
0131	722-60824	SURFACE MILLING	1856.00	SYS
0132	726-92406	BEARING ASSEMBLY ELASTOMERIC	33.00	EACH
0133	801-03290	CONSTRUCTION SIGN, C	14.00	EACH
0134	801-04308	ROAD CLOSURE SIGN ASSEMBLY	22.00	EACH
0135	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	173848.00	LFT
0136	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	4672.00	LFT
0137	801-06640	CONSTRUCTION SIGN, A	124.00	EACH
0138	801-06645	CONSTRUCTION SIGN, B	26.00	EACH
0139	801-06710	FLASHING ARROW SIGN	210.00	DAY
0140	801-06775	MAINTAINING TRAFFIC	1.00	LS
0141	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	3.00	EACH
0142	801-07118	BARRICADE, III-A	372.00	LFT
0143	801-07119	BARRICADE, III-B	120.00	LFT
0144	801-07606	TEMPORARY CROSSOVER DRAINAGE PIPE	526.00	LFT
0145	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	20095.00	LFT
0146	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2500.00	LFT
0147	801-08507	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 1	1941.00	LFT
0148	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	20.00	EACH
0149	801-52817	TEMPORARY CROSSOVER, B	2.00	EACH
0150	805-04973	CONDUIT	3615.00	LFT
0151	805-04973	CONDUIT	1392.00	LFT
0152	805-04973	CONDUIT	100.00	LFT
0153	805-06595	CONDUIT, PVC, 2 IN.	667.00	LFT
0154	807-04651	WIRE	5010.00	LFT
0155	807-78590	HANDHOLE	6.00	EACH
0156	807-86955	CABLE-DUCT MARKER	9.00	EACH
0157	807-86955	CABLE-DUCT MARKER	7.00	EACH
0158	808-06702	LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	11555.00	LFT
0159	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	49355.00	LFT
0160	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	5078.00	LFT
0161	808-06706	LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	1295.00	LFT
0162	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0163	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	82491.00	LFT
0164	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	82491.00	LFT

0165	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	6796.00	LFT
0166	808-10038	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE WHITE 24 IN.	1020.00	LFT
0167	808-10043	LINE, MULTI-COMPONENT, SOLID, WHITE, 24 IN.	73.00	LFT
0168	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	85.00	LFT
0169	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	19446.00	LFT
0170	808-10094	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 12 IN.	520.00	LFT
0171	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	474.00	LFT
0172	808-12032	GROOVING FOR PAVEMENT MARKINGS	296019.00	LFT
0173	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	48555.00	LFT
0174	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1889.00	EACH
0175	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1870.00	EACH
0176	809-04970	FIBER OPTIC	384.00	EACH
0177	809-94971	FIBER OPTIC CABLE	5620.00	LFT
0178	809-94971	FIBER OPTIC CABLE	450.00	LFT

Call: 143

Contract: R -35457-A

Section No.: 2 BRIDGE DECK OVERLAY LATEX MODIFIED OPTION

Line

Item No	Item Code	Description	Quantity	Unit
0179	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1856.00	SYS

Call: 143

Contract: R -35457-A

Section No.: 3 BRIDGE DECK OVERLAY SILICA FUME MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0180	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	1856.00	SYS

Call: 223

Contract: R -40522-A

Section No.: 1 BRIDGE DECK OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL

0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	4775.00	SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-94954	BARRIER WALL, CONCRETE, REMOVE	1155.00	LFT
0017	203-02000	EXCAVATION, COMMON	341.00	CYS
0018	205-12108	STORM WATER MANAGEMENT BUDGET	6486.00	DOL
0019	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	2270.00	SYS
0021	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	5100.00	SYS
0022	301-12233	COMPACTED AGGREGATE NO 8	210.00	CYS
0023	301-12234	COMPACTED AGGREGATE NO 53	464.00	CYS
0024	302-06464	SUBBASE FOR PCCP	442.00	CYS
0025	302-07455	DENSE GRADED SUBBASE	670.00	CYS
0026	304-07783	HMA PATCHING, TYPE D	2188.00	TON
0027	306-08036	MILLING, ASPHALT, 2 IN.	146447.00	SYS
0028	306-10113	MILLING, ASPHALT, 4 1/2 IN.	191243.00	SYS
0029	401-06264	PROFILOGRAPH, HMA	1.00	LS
0030	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	15016.00	TON
0031	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	26297.00	TON
0032	401-10258	JOINT ADHESIVE, SURFACE	190756.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	89690.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	190756.00	LFT
0035	402-10087	HMA FOR TEMPORARY PAVEMENT, D	248.00	TON
0036	406-05520	ASPHALT FOR TACK COAT	134.00	TON
0037	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	8.00	TON
0038	410-11777	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm - SMA	22132.00	TON
0039	501-06325	QC/QA-PCCP, 14 IN.	2520.00	SYS
0040	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
0041	503-03489	RETROFITTED TIE BARS	565.00	EACH
0042	503-05240	D-1 CONTRACTION JOINT	2108.00	LFT
0043	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	236.00	LFT
0044	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	693.00	LFT
0045	506-06333	PCCP PATCHING, FULL DEPTH	2270.00	SYS
0046	506-06334	PCCP PATCHING, PARTIAL DEPTH	1.00	SYS
0047	507-07505	RETROFIT LOAD TRANSFER	1031.00	EACH
0048	507-08271	JOINTS IN PCCP, FILLED	149174.00	LFT
0049	507-12191	JOINT REPAIR, PARTIAL DEPTH	17804.00	SFT
0050	507-12192	JOINT REPAIR, BOTTOM-HALF	102.00	SFT
0051	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH
0052	601-02241	GUARDRAIL, REMOVE	30.00	LFT
0053	601-06035	GUARDRAIL, RESET	80.00	LFT

0054	602-01064	CONCRETE BARRIER	1155.00	LFT
0055	602-06729	BARRIER, DELINEATOR	112.00	EACH
0056	605-06095	CURB, INTEGRAL B CONCRETE	105.00	LFT
0057	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	1527.00	SYS
0058	609-06262	REINFORCED CONCRETE BRIDGE APPROACH, 14 IN.	728.00	SYS
0059	702-51005	CONCRETE, A, SUBSTRUCTURE	17.20	CYS
0060	702-51863	FIELD DRILLED HOLE IN CONCRETE	778.00	EACH
0061	703-06029	REINFORCING BARS, EPOXY COATED	143116.00	LBS
0062	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	276.00	EACH
0063	704-51002	CONCRETE, C, SUPERSTRUCTURE	33.30	CYS
0064	706-09959	RAILING, CONCRETE FT	164.00	LFT
0065	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	1.00	EACH
0066	709-51821	SURFACE SEAL	1.00	LS
0067	710-09158	PATCHING CONCRETE STRUCTURES	90.00	SFT
0068	720-44000	CASTING, ADJUST TO GRADE	8.00	EACH
0069	722-01066	HYDRODEMOLITION	12324.00	SYS
0070	722-12380	BRIDGE DECK OVERLAY, BUDGET	194337.00	DOL
0071	722-12382	TRANSVERSE GROOVING	11886.00	SYS
0072	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	1071.00	SFT
0073	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	11886.00	SYS
0074	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	5512.00	SFT
0075	722-60824	SURFACE MILLING	11886.00	SYS
0076	724-51927	STRUCTURAL EXPANSION JOINT, M	236.00	LFT
0077	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	9.00	EACH
0078	801-03290	CONSTRUCTION SIGN, C	3.00	EACH
0079	801-04308	ROAD CLOSURE SIGN ASSEMBLY	15.00	EACH
0080	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	185082.00	LFT
0081	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	21487.00	LFT
0082	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	49345.00	LFT
0083	801-06640	CONSTRUCTION SIGN, A	70.00	EACH
0084	801-06645	CONSTRUCTION SIGN, B	12.00	EACH
0085	801-06710	FLASHING ARROW SIGN	256.00	DAY
0086	801-06775	MAINTAINING TRAFFIC	1.00	LS
0087	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	1.00	EACH
0088	801-07118	BARRICADE, III-A	320.00	LFT
0089	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	21233.00	LFT
0090	801-11598	ARIES FIELD PROCESSOR FOR PCMS	9.00	EACH
0091	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	9.00	EACH
0092	801-12042	TRUCK MOUNTED ATTENUATOR	90.00	DAY
0093	805-10107	WIRELESS MAGNETOMETER DETECTOR	12.00	EACH
0094	805-10108	WIRELESS REPEATER	2.00	EACH
0095	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	3900.00	LFT
0096	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1320.00	LFT

0097	808-06716	LINE, REMOVE	65531.00	LFT
0098	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0099	808-12032	GROOVING FOR PAVEMENT MARKINGS	202698.00	LFT
0100	808-12134	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 4 IN.	2687.00	LFT
0101	808-12454	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 8 IN.	797.00	LFT
0102	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	91814.00	LFT
0103	808-75053	LINE, PREFORMED PLASTIC, SOLID, WHITE, 8 IN.	9614.00	LFT
0104	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	78027.00	LFT
0105	808-75059	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	70.00	LFT
0106	808-75061	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	35876.00	LFT
0107	808-75067	TRANSVERSE MARKING, PREFORMED PLASTIC, STOP LINE, WHITE, 24 IN.	97.00	LFT
0108	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	12.00	EACH
0109	808-75073	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, ONLY	12.00	EACH
0110	808-75510	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	1723.00	LFT
0111	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1544.00	EACH
0112	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1725.00	EACH
0113	809-05904	ATR STATION- 6 LANE	2.00	EACH
0114	809-09871	ATR STATION, REMOVE	2.00	EACH

Call: 483

Contract: RS-40584-A

Section No.: 1 CONCRETE PAVEMENT RESTORATION

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	203-02000	EXCAVATION, COMMON	155.00	CYS
	0012	207-09935	SUBGRADE TREATMENT, TYPE IC	17516.00	SYS
	0013	211-09266	STRUCTURE BACKFILL, TYPE 3	1029.00	CYS
	0014	214-12236	GEOTEXTILE FOR PAVEMENT TYPE 1A	2906.00	SYS
	0015	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	362.00	SYS
	0016	301-12234	COMPACTED AGGREGATE NO 53	93.00	CYS
	0017	302-06464	SUBBASE FOR PCCP	3570.00	CYS
	0018	304-07783	HMA PATCHING, TYPE D	5631.00	TON
	0019	306-08034	MILLING, ASPHALT, 1 1/2 IN.	95776.00	SYS

0020	306-08036	MILLING, ASPHALT, 2 IN.	683369.00	SYS
0021	306-08038	MILLING, ASPHALT, 4 IN.	16257.00	SYS
0022	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	15277.00	TON
0023	401-07353	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm	22813.00	TON
0024	401-07368	QC/QA-HMA, 4, 76, INTERMEDIATE, 9.5 mm	1789.00	TON
0025	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	39.00	TON
0026	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	39.00	TON
0027	401-10258	JOINT ADHESIVE, SURFACE	528665.00	LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	13715.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	528665.00	LFT
0030	401-11787	QC/QA-HMA, 3, 76, INTERMEDIATE, OG 19.0 mm	42.00	TON
0031	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0032	406-05520	ASPHALT FOR TACK COAT	191.00	TON
0033	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	15.00	TON
0034	410-09530	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm - SMA	46785.00	TON
0035	503-03489	RETROFITTED TIE BARS	1696.00	EACH
0036	503-05240	D-1 CONTRACTION JOINT	2333.00	LFT
0037	503-09261	PCCP STITCHING	16.00	EACH
0038	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	4275.00	LFT
0039	506-06333	PCCP PATCHING, FULL DEPTH	14498.00	SYS
0040	506-06334	PCCP PATCHING, PARTIAL DEPTH	1078.00	SYS
0041	507-07482	CRACKS IN PCCP, ROUT AND SEAL	18500.00	LFT
0042	507-07505	RETROFIT LOAD TRANSFER	120.00	EACH
0043	507-08272	JOINTS IN PCCP, SAW AND SEAL	425368.00	LFT
0044	507-12099	PCCP GROOVING	227245.00	SYS
0045	507-12191	JOINT REPAIR, PARTIAL DEPTH	40544.00	SFT
0046	602-06729	BARRIER, DELINEATOR	128.00	EACH
0047	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	78670.00	LFT
0048	628-09403	FIELD OFFICE, C	12.00	MOS
0049	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0050	702-51863	FIELD DRILLED HOLE IN CONCRETE	86.00	EACH
0051	703-06029	REINFORCING BARS, EPOXY COATED	180.00	LBS
0052	709-51821	SURFACE SEAL	1.00	LS
0053	709-51821	SURFACE SEAL	1.00	LS
0054	709-51821	SURFACE SEAL	1.00	LS
0055	709-51821	SURFACE SEAL	1.00	LS
0056	709-51821	SURFACE SEAL	1.00	LS
0057	709-51821	SURFACE SEAL	1.00	LS
0058	709-51821	SURFACE SEAL	1.00	LS
0059	709-51821	SURFACE SEAL	1.00	LS
0060	710-09158	PATCHING CONCRETE STRUCTURES	320.00	SFT
0061	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	2309.00	SFT
0062	724-03276	STRUCTURAL EXPANSION JOINT SEALING SYS	86.00	LFT

0063	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	21134.00	SYS
0064	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	56.00	EACH
0065	801-03290	CONSTRUCTION SIGN, C	32.00	EACH
0066	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00	EACH
0067	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	129196.00	LFT
0068	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	13705.00	LFT
0069	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	41430.00	LFT
0070	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	685.00	LFT
0071	801-06640	CONSTRUCTION SIGN, A	426.00	EACH
0072	801-06645	CONSTRUCTION SIGN, B	55.00	EACH
0073	801-06710	FLASHING ARROW SIGN	1944.00	DAY
0074	801-06775	MAINTAINING TRAFFIC	1.00	LS
0075	801-07118	BARRICADE, III-A	1639.00	LFT
0076	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	4480.00	LFT
0077	801-08403	TEMPORARY TRAFFIC BARRIER TYPE 4	21120.00	LFT
0078	801-09087	TEMPORARY PAVEMENT MARKING, REMOVABLE, 12 IN.	4074.00	LFT
0079	801-11598	ARIES FIELD PROCESSOR FOR PCMS	2.00	EACH
0080	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	51.00	EACH
0081	801-12042	TRUCK MOUNTED ATTENUATOR	1890.00	DAY
0082	805-10107	WIRELESS MAGNETOMETER DETECTOR	50.00	EACH
0083	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	3730.00	LFT
0084	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1390.00	LFT
0085	808-06609	PAVEMENT MESSAGE MARKING	12.00	EACH
0086	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	42153.00	LFT
0087	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	11152.00	LFT
0088	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	3434.00	LFT
0089	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	4612.00	LFT
0090	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	4612.00	LFT
0091	808-06716	LINE, REMOVE	3895.00	LFT
0092	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0093	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	2535.00	LFT
0094	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	5990.00	LFT
0095	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	5186.00	LFT
0096	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	1300.00	LFT
0097	808-10043	LINE, MULTI-COMPONENT, SOLID, WHITE, 24 IN.	240.00	LFT
0098	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	2023.00	LFT
0099	808-11650	LINE, THERMOPLASTIC, DOTTED, WHITE, 6 IN.	2600.00	LFT
0100	808-12032	GROOVING FOR PAVEMENT MARKINGS	332775.00	LFT
0101	808-12134	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 4 IN.	503.00	LFT
0102	808-12454	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 8 IN.	8368.00	LFT
0103	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	64303.00	LFT
0104	808-75053	LINE, PREFORMED PLASTIC, SOLID, WHITE, 8 IN.	26996.00	LFT
0105	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	71074.00	LFT

0106	808-75061	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	62198.00	LFT
0107	808-75067	TRANSVERSE MARKING, PREFORMED PLASTIC, STOP LINE, WHITE, 24 IN.	145.00	LFT
0108	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	10.00	EACH
0109	808-75073	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, ONLY	1.00	EACH
0110	808-75215	LINE, THERMOPLASTIC, SOLID, WHITE, 12 IN.	3636.00	LFT
0111	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	38016.00	LFT
0112	808-75510	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	4531.00	LFT
0113	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	5009.00	EACH
0114	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	4919.00	EACH
0115	808-91662	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSHATCH LINE, WHITE 12 IN.	219.00	LFT
0116	809-04970	FIBER OPTIC	10.00	EACH
0117	809-04970	FIBER OPTIC	10.00	EACH
0118	809-04970	FIBER OPTIC	10.00	EACH
0119	809-05904	ATR STATION- 6 LANE	4.00	EACH
0120	809-05905	ATR STATION- 4 LANE	1.00	EACH
0121	809-09871	ATR STATION, REMOVE	5.00	EACH