

Schedule of Pay Items Letting Date January 16, 2019 Letting ID 190116

Call: 335

Contract: R -40778-B

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line	Item Code	Description	Quantity	Unit
	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	202-96133	PIPE, REMOVE	21.00	LFT
0010	202-99187	FENCE, FARM FIELD, REMOVE	640.00	LFT
0011	203-02070	BORROW	35.00	CYS
0012	205-12108	STORM WATER MANAGEMENT BUDGET	34767.00	DOL
0013	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0014	211-09265	STRUCTURE BACKFILL, TYPE 2	5.00	CYS
0015	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	17.00	SYS
0016	603-06040	FENCE, FARM FIELD, 47 IN.	640.00	LFT
0017	616-05688	RIPRAP, CLASS 1	123.00	TON
0018	616-05689	RIPRAP, CLASS 2	448.00	TON
0019	616-06405	RIPRAP, REVETMENT	132.00	TON
0020	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	809.00	SYS
0021	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0022	621-02770	EROSION CONTROL BLANKET	628.00	SYS
0023	621-06559	MULCHED SEEDING R	8584.00	SYS
0024	628-09402	FIELD OFFICE, B	10.00	MOS
0025	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0026	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0027	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0028	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0029	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	20.00	MOS
0030	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0031	628-11977	COMPUTER SYSTEM	1.00	EACH
0032	702-04325	TEMPORARY SHORING	1.00	LS
0033	702-51005	CONCRETE, A, SUBSTRUCTURE	18.00	CYS
0034	703-06029	REINFORCING BARS, EPOXY COATED	1195.00	LBS
0035	715-05128	PIPE, TYPE 1, CIRCULAR, 48 IN.	10.00	LFT
0036	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	28.00	LFT
0037	715-05244	PIPE, TYPE 1, DEFORMED, MIN. AREA 11.6 SFT	74.00	LFT
0038	715-05246	PIPE, TYPE 1, DEFORMED, MIN. AREA 14.7 SFT	20.00	LFT
0039	715-05840	CONCRETE ANCHOR, MIN. AREA 14.7SF	4.00	EACH
0040	715-05842	CONCRETE ANCHOR, 42 IN.	2.00	EACH
0041	715-06004	CONCRETE ANCHOR, 48 IN.	2.00	EACH
0042	715-07090	CONCRETE ANCHOR, MIN. AREA 11.6 SFT	4.00	EACH
0043	715-09992	PIPE, TYPE 1, DEFORMED, MIN. AREA 29.5 SFT	10.00	LFT
0044	715-10167	CONCRETE ANCHOR, MIN. AREA 37.0 SFT	2.00	EACH
0045	715-12056	CONCRETE ANCHOR, MIN. AREA 30.1 SFT	1.00	EACH
0046	716-07635	PIPE INSTALLATION, TRENCHLESS, 36 IN.	330.00	LFT
0047	716-07636	PIPE INSTALLATION, TRENCHLESS, 42 IN.	282.00	LFT
0048	725-10224	LINER PIPE, THERMOPLASTIC, CIRCULAR, 8.4-8.8 SFT	330.00	LFT
0049	725-11709	PIPE LINER, CURED-IN-PLACE, MIN AREA 12.5 SFT	432.00	LFT
0050	725-11861	PIPE LINER, CURED-IN-PLACE, MIN AREA 11.4 SFT	413.00	LFT
0051	725-11986	LINER PIPE, THERMOPLASTIC, CIRCULAR, 76.9-78.6 SFT	282.00	LFT
0052	725-12054	PIPE LINER, CURED-IN-PLACE, MIN AREA 30.1 SFT	218.00	LFT
0053	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	20.00	EACH
0054	801-06640	CONSTRUCTION SIGN, A	109.00	EACH
0055	801-06775	MAINTAINING TRAFFIC	1.00	LS
0056	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2893.00	LFT
0057				