

Schedule of Pay Items Letting Date March 6, 2019 Letting ID 190306

Call: 271

Contract: R -37842-A

Section No.: 1 SLIDE CORRECTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	25.00	SYS
0013	202-96133	PIPE, REMOVE	48.00	LFT
0014	203-02020	EXCAVATION, UNCLASSIFIED	5438.00	CYS
0015	203-02070	BORROW	100.00	CYS
0016	205-11626	PUMP AROUND	1.00	EACH
0017	205-12108	STORM WATER MANAGEMENT BUDGET	45766.00	DOL
0018	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	1109.00	SYS
0020	211-09264	STRUCTURE BACKFILL, TYPE 1	122.00	CYS
0021	301-12231	COMPACTED AGGREGATE NO 2	360.00	CYS
0022	303-01180	COMPACTED AGGREGATE NO. 53	733.00	TON
0023	304-07490	HMA PATCHING, TYPE B	21.00	TON
0024	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	64.00	TON
0025	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	108.00	TON
0026	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	91.00	TON
0027	401-10258	JOINT ADHESIVE, SURFACE	1125.00	LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	1125.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	1125.00	LFT
0030	406-05521	ASPHALT FOR TACK COAT	1323.00	SYS
0031	601-02241	GUARDRAIL, REMOVE	1947.00	LFT

0032	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1757.00	LFT
0033	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	4.00	EACH
0034	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0035	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	200.00	LFT
0036	607-06175	GUTTER, CONCRETE, A	1125.00	LFT
0037	615-06490	RIGHT-OF-WAY MARKER	20.00	EACH
0038	616-05688	RIPRAP, CLASS 1	149.00	TON
0039	616-06405	RIPRAP, REVETMENT	152.00	TON
0040	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	359.00	SYS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	9.00	EACH
0042	621-02770	EROSION CONTROL BLANKET	1739.00	SYS
0043	621-06545	FERTILIZER	0.20	TON
0044	621-06553	SEED MIXTURE R	74.00	LBS
0045	621-06565	MULCHING MATERIAL	1.00	TON
0046	628-09402	FIELD OFFICE, B	16.00	MOS
0047	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0048	715-03487	SAFETY METAL END SECTION, 4:1, DIA 30 IN.	1.00	EACH
0049	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	41.00	LFT
0050	715-09064	VIDEO INSPECTION FOR PIPE	41.00	LFT
0051	715-46030	PIPE END SECTION, DIAMETER 30 IN.	1.00	EACH
0052	720-45415	MANHOLE, D4	1.00	EACH
0053	731-06223	SOIL NAILED WALL	1370.00	SYS
0054	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00	EACH
0055	801-06625	DETOUR ROUTE MARKER ASSEMBLY	58.00	EACH
0056	801-06640	CONSTRUCTION SIGN, A	4.00	EACH
0057	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0058	801-06775	MAINTAINING TRAFFIC	1.00	LS
0059	801-07118	BARRICADE, III-A	144.00	LFT
0060	801-07119	BARRICADE, III-B	120.00	LFT
0061	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2180.00	LFT
0062	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	4160.00	LFT
0063	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	56.00	EACH
0064	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	56.00	EACH