

Schedule of Pay Items Letting Date March 6, 2019 Letting ID 190306

Call: 393

Contract: R -41677-B

Section No.: 1 IDIQ. PATCH AND REHAB PAVEMENT

Line

Item No	Item Code	Description	Quantity Unit	
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	110-07025	MOBILIZATION AND DEMOBILIZATION	4.00	EACH
0008	201-02245	TREE 6 IN., REMOVE	3.00	EACH
0009	201-02250	TREE 10 IN., REMOVE	3.00	EACH
0010	201-02255	TREE 18 IN., REMOVE	3.00	EACH
0011	201-02260	TREE 30 IN., REMOVE	3.00	EACH
0012	201-02265	TREE 48 IN., REMOVE	3.00	EACH
0013	201-02270	TREE 60 IN., REMOVE	3.00	EACH
0014	202-02240	PAVEMENT REMOVAL	800.00	SYS
0015	202-52710	SIDEWALK CONCRETE, REMOVE	100.00	SYS
0016	203-02000	EXCAVATION, COMMON	50.00	CYS
0017	207-08268	SUBGRADE TREATMENT, TYPE IV	100.00	SYS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	200.00	SYS
0019	303-01180	COMPACTED AGGREGATE NO. 53	100.00	TON
0020	303-07449	COMPACTED AGGREGATE NO. 73	100.00	TON
0021	304-07490	HMA PATCHING, TYPE B	200.00	TON
0022	304-07491	HMA PATCHING, TYPE C	400.00	TON
0023	304-07783	HMA PATCHING, TYPE D	400.00	TON
0024	306-08034	MILLING, ASPHALT, 1 1/2 IN.	10000.00	SYS
0025	306-08159	MILLING, ASPHALT	15000.00	SYS
0026	401-10258	JOINT ADHESIVE, SURFACE	26000.00	LFT
0027	401-11785	LIQUID ASPHALT SEALANT	26000.00	LFT
0028	402-07451	HMA WEDGE AND LEVEL, TYPE B	200.00	TON
0029	402-07452	HMA WEDGE AND LEVEL, TYPE C	400.00	TON
0030	402-07787	HMA WEDGE AND LEVEL, TYPE D	200.00	TON

0031	406-05520	ASPHALT FOR TACK COAT	4.00	TON
0032	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	5.00	TON
0033	503-05240	D-1 CONTRACTION JOINT	144.00	LFT
0034	506-06333	PCCP PATCHING, FULL DEPTH	500.00	SYS
0035	506-06334	PCCP PATCHING, PARTIAL DEPTH	400.00	SYS
0036	507-07505	RETROFIT LOAD TRANSFER	50.00	EACH
0037	507-08269	CRACKS IN PCCP, FILLED	25000.00	LFT
0038	507-08272	JOINTS IN PCCP, SAW AND SEAL	25000.00	LFT
0039	604-06070	SIDEWALK, CONCRETE	1.00	SYS
0040	604-08086	CURB RAMP, CONCRETE	75.00	SYS
0041	605-01870	CURB, CONCRETE A	100.00	LFT
0042	801-06640	CONSTRUCTION SIGN, A	10.00	EACH
0043	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0044	801-06710	FLASHING ARROW SIGN	5.00	DAY
0045	801-12440	MAINTAINING TRAFFIC, IDIQ	1.00	DOL
0046	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	5280.00	LFT
0047	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	5280.00	LFT
0048	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	5280.00	LFT
0049	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	5280.00	LFT
0050	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	5280.00	LFT
0051	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	5280.00	LFT
0052	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	5280.00	LFT

0053 808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN. 5280.00 LFT

Call: 395

Contract: R -41682-B

Section No.: 1 IDIQ, PATCH AND REHAB PAVEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	110-07025	MOBILIZATION AND DEMOBILIZATION	2.00	EACH
0008	201-02245	TREE 6 IN., REMOVE	3.00	EACH
0009	201-02250	TREE 10 IN., REMOVE	3.00	EACH
0010	201-02255	TREE 18 IN., REMOVE	3.00	EACH
0011	201-02260	TREE 30 IN., REMOVE	3.00	EACH
0012	201-02265	TREE 48 IN., REMOVE	3.00	EACH
0013	201-02270	TREE 60 IN., REMOVE	3.00	EACH
0014	202-02240	PAVEMENT REMOVAL	400.00	SYS
0015	202-52710	SIDEWALK CONCRETE, REMOVE	28.00	SYS
0016	203-02000	EXCAVATION, COMMON	6.00	CYS
0017	303-01180	COMPACTED AGGREGATE NO. 53	25.00	TON
0018	303-07449	COMPACTED AGGREGATE NO. 73	25.00	TON
0019	304-07491	HMA PATCHING, TYPE C	100.00	TON
0020	304-07783	HMA PATCHING, TYPE D	120.00	TON
0021	306-08159	MILLING, ASPHALT	12500.00	SYS
0022	401-10258	JOINT ADHESIVE, SURFACE	12500.00	LFT
0023	401-11785	LIQUID ASPHALT SEALANT	12500.00	LFT
0024	402-07452	HMA WEDGE AND LEVEL, TYPE C	100.00	TON
0025	402-07787	HMA WEDGE AND LEVEL, TYPE D	100.00	TON
0026	406-05521	ASPHALT FOR TACK COAT	12500.00	SYS
0027	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	3.00	TON
0028	503-05240	D-1 CONTRACTION JOINT	144.00	LFT
0029	506-06333	PCCP PATCHING, FULL DEPTH	180.00	SYS
0030	506-06334	PCCP PATCHING, PARTIAL DEPTH	180.00	SYS

0031	507-07505	RETROFIT LOAD TRANSFER	50.00	EACH
0032	507-08269	CRACKS IN PCCP, FILLED	12500.00	LFT
0033	507-08272	JOINTS IN PCCP, SAW AND SEAL	12500.00	LFT
0034	604-06070	SIDEWALK, CONCRETE	3.00	SYS
0035	604-08086	CURB RAMP, CONCRETE	25.00	SYS
0036	604-12083	DETECTABLE WARNING SURFACES	9.00	SYS
0037	605-01870	CURB, CONCRETE A	100.00	LFT
0038	801-06640	CONSTRUCTION SIGN, A	10.00	EACH
0039	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0040	801-06710	FLASHING ARROW SIGN	5.00	DAY
0041	801-12440	MAINTAINING TRAFFIC, IDIQ	1.00	DOL
0042	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	5280.00	LFT
0043	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	5280.00	LFT
0044	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	5280.00	LFT
0045	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	5280.00	LFT
0046	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	5280.00	LFT
0047	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	5280.00	LFT
0048	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	5280.00	LFT

0049 808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN. 5280.00 LFT

Call: 397

Contract: R -41684-B

Section No.: 1 IDIQ, PATCH AND REHAB PAVEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-07025	MOBILIZATION AND DEMOBILIZATION	8.00	EACH
0009	201-02245	TREE 6 IN., REMOVE	9.00	EACH
0010	201-02250	TREE 10 IN., REMOVE	9.00	EACH
0011	201-02255	TREE 18 IN., REMOVE	9.00	EACH
0012	201-02260	TREE 30 IN., REMOVE	9.00	EACH
0013	201-02265	TREE 48 IN., REMOVE	9.00	EACH
0014	201-02270	TREE 60 IN., REMOVE	9.00	EACH
0015	202-02240	PAVEMENT REMOVAL	1285.00	SYS
0016	202-52710	SIDEWALK CONCRETE, REMOVE	240.00	SYS
0017	203-02000	EXCAVATION, COMMON	25.00	CYS
0018	303-01180	COMPACTED AGGREGATE NO. 53	50.00	TON
0019	303-07449	COMPACTED AGGREGATE NO. 73	50.00	TON
0020	304-07491	HMA PATCHING, TYPE C	355.00	TON
0021	304-07783	HMA PATCHING, TYPE D	640.00	TON
0022	306-08159	MILLING, ASPHALT	33000.00	SYS
0023	401-10258	JOINT ADHESIVE, SURFACE	26000.00	LFT
0024	401-11785	LIQUID ASPHALT SEALANT	39000.00	LFT
0025	402-07452	HMA WEDGE AND LEVEL, TYPE C	650.00	TON
0026	402-07787	HMA WEDGE AND LEVEL, TYPE D	450.00	TON
0027	406-05521	ASPHALT FOR TACK COAT	36500.00	SYS
0028	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	9.00	TON
0029	503-05240	D-1 CONTRACTION JOINT	200.00	LFT
0030	506-06333	PCCP PATCHING, FULL DEPTH	675.00	SYS

0031	506-06334	PCCP PATCHING, PARTIAL DEPTH	875.00	SYS
0032	507-07505	RETROFIT LOAD TRANSFER	75.00	EACH
0033	507-08269	CRACKS IN PCCP, FILLED	75000.00	LFT
0034	507-08272	JOINTS IN PCCP, SAW AND SEAL	75000.00	LFT
0035	604-06070	SIDEWALK, CONCRETE	15.00	SYS
0036	604-08086	CURB RAMP, CONCRETE	225.00	SYS
0037	605-01870	CURB, CONCRETE A	300.00	LFT
0038	801-06640	CONSTRUCTION SIGN, A	30.00	EACH
0039	801-06645	CONSTRUCTION SIGN, B	30.00	EACH
0040	801-06710	FLASHING ARROW SIGN	15.00	DAY
0041	801-12440	MAINTAINING TRAFFIC, IDIQ	1.00	DOL
0042	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	5280.00	LFT
0043	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	5280.00	LFT
0044	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	5280.00	LFT
0045	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	5280.00	LFT
0046	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	5280.00	LFT
0047	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	5280.00	LFT
0048	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	5280.00	LFT

0049 808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN. 5280.00 LFT

Call: 398

Contract: R -41687-B

Section No.: 1 IDIQ, PATCH AND REHAB PAVEMENT

Line

Item No	Item Code	Description	Quantity Unit	
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	110-07025	MOBILIZATION AND DEMOBILIZATION	4.00	EACH
0009	201-02245	TREE 6 IN., REMOVE	3.00	EACH
0010	201-02250	TREE 10 IN., REMOVE	3.00	EACH
0011	201-02255	TREE 18 IN., REMOVE	3.00	EACH
0012	201-02260	TREE 30 IN., REMOVE	3.00	EACH
0013	201-02265	TREE 48 IN., REMOVE	3.00	EACH
0014	201-02270	TREE 60 IN., REMOVE	3.00	EACH
0015	202-02240	PAVEMENT REMOVAL	800.00	SYS
0016	202-52710	SIDEWALK CONCRETE, REMOVE	76.00	SYS
0017	203-02000	EXCAVATION, COMMON	50.00	CYS
0018	303-01180	COMPACTED AGGREGATE NO. 53	100.00	TON
0019	303-07449	COMPACTED AGGREGATE NO. 73	100.00	TON
0020	304-07490	HMA PATCHING, TYPE B	200.00	TON
0021	304-07491	HMA PATCHING, TYPE C	400.00	TON
0022	304-07783	HMA PATCHING, TYPE D	400.00	TON
0023	306-08159	MILLING, ASPHALT	25000.00	SYS
0024	401-11785	LIQUID ASPHALT SEALANT	26000.00	LFT
0025	402-07452	HMA WEDGE AND LEVEL, TYPE C	400.00	TON
0026	402-07787	HMA WEDGE AND LEVEL, TYPE D	400.00	TON
0027	406-05520	ASPHALT FOR TACK COAT	4.00	TON
0028	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	5.00	TON
0029	503-05240	D-1 CONTRACTION JOINT	144.00	LFT
0030	506-06333	PCCP PATCHING, FULL DEPTH	500.00	SYS

0031	506-06334	PCCP PATCHING, PARTIAL DEPTH	400.00	SYS
0032	507-07505	RETROFIT LOAD TRANSFER	50.00	EACH
0033	507-08269	CRACKS IN PCCP, FILLED	25000.00	LFT
0034	507-08272	JOINTS IN PCCP, SAW AND SEAL	25000.00	LFT
0035	604-06070	SIDEWALK, CONCRETE	1.00	SYS
0036	604-08086	CURB RAMP, CONCRETE	75.00	SYS
0037	605-01870	CURB, CONCRETE A	100.00	LFT
0038	801-06640	CONSTRUCTION SIGN, A	10.00	EACH
0039	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0040	801-06710	FLASHING ARROW SIGN	5.00	DAY
0041	801-12440	MAINTAINING TRAFFIC, IDIQ	1.00	DOL
0042	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	5280.00	LFT
0043	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	5280.00	LFT
0044	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	5280.00	LFT
0045	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	5280.00	LFT
0046	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	5280.00	LFT
0047	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	5280.00	LFT
0048	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	5280.00	LFT

0049 808-10036 LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN. 5280.00 LFT

Call: 399

Contract: R -41692-B

Section No.: 1 IDIQ, PATCH AND REHAB PAVEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	110-07025	MOBILIZATION AND DEMOBILIZATION	4.00	EACH
0008	201-02245	TREE 6 IN., REMOVE	3.00	EACH
0009	201-02250	TREE 10 IN., REMOVE	3.00	EACH
0010	201-02255	TREE 18 IN., REMOVE	3.00	EACH
0011	201-02260	TREE 30 IN., REMOVE	3.00	EACH
0012	201-02265	TREE 48 IN., REMOVE	3.00	EACH
0013	201-02270	TREE 60 IN., REMOVE	3.00	EACH
0014	202-02278	CURB, CONCRETE, REMOVE	100.00	LFT
0015	202-02279	CURB AND GUTTER, REMOVE	100.00	LFT
0016	202-52710	SIDEWALK CONCRETE, REMOVE	100.00	SYS
0017	203-02000	EXCAVATION, COMMON	50.00	CYS
0018	203-08607	LINEAR GRADING	1000.00	LFT
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	600.00	SYS
0020	211-09264	STRUCTURE BACKFILL, TYPE 1	20.00	CYS
0021	302-06464	SUBBASE FOR PCCP	100.00	CYS
0022	302-07455	DENSE GRADED SUBBASE	100.00	CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	100.00	TON
0024	303-07449	COMPACTED AGGREGATE NO. 73	100.00	TON
0025	304-07491	HMA PATCHING, TYPE C	400.00	TON
0026	304-07783	HMA PATCHING, TYPE D	400.00	TON
0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	3300.00	SYS
0028	306-08036	MILLING, ASPHALT, 2 IN.	3300.00	SYS
0029	306-08042	MILLING, SCARIFICATION	1300.00	SYS
0030	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	275.00	TON

0031	401-07340	QC/QA-HMA, 3, 64, SURFACE, 12.5 mm	370.00	TON
0032	401-10258	JOINT ADHESIVE, SURFACE	10000.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	10000.00	LFT
0034	406-05520	ASPHALT FOR TACK COAT	5.00	TON
0035	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	5.00	TON
0036	503-03489	RETROFITTED TIE BARS	100.00	EACH
0037	503-05240	D-1 CONTRACTION JOINT	144.00	LFT
0038	506-06333	PCCP PATCHING, FULL DEPTH	500.00	SYS
0039	506-06334	PCCP PATCHING, PARTIAL DEPTH	400.00	SYS
0040	507-07480	PROFILING, PCCP	700.00	SYS
0041	507-07505	RETROFIT LOAD TRANSFER	60.00	EACH
0042	507-08269	CRACKS IN PCCP, FILLED	2000.00	LFT
0043	507-08271	JOINTS IN PCCP, FILLED	3000.00	LFT
0044	507-08272	JOINTS IN PCCP, SAW AND SEAL	500.00	LFT
0045	604-06070	SIDEWALK, CONCRETE	25.00	SYS
0046	604-08086	CURB RAMP, CONCRETE	75.00	SYS
0047	605-01870	CURB, CONCRETE A	100.00	LFT
0048	605-06140	CURB AND GUTTER, CONCRETE	100.00	LFT
0049	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	3000.00	LFT
0050	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	400.00	LFT
0051	718-06526	HMA FOR UNDERDRAINS	215.00	TON
0052	718-06529	OUTLET PROTECTOR, 2	10.00	EACH
0053	718-06531	OUTLET PROTECTOR, 3	10.00	EACH
0054	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00	LFT
0055	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	2350.00	SYS
0056	718-52610	AGGREGATE FOR UNDERDRAINS	175.00	CYS
0057	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0058	801-06640	CONSTRUCTION SIGN, A	10.00	EACH
0059	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0060	801-06710	FLASHING ARROW SIGN	50.00	DAY
0061	801-07118	BARRICADE, III-A	60.00	LFT
0062	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0063	801-12440	MAINTAINING TRAFFIC, IDIQ	1.00	DOL
0064	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	1250.00	LFT
0065	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	1250.00	LFT
0066	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	5000.00	LFT
0067	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	5000.00	LFT

0068	808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	1250.00	LFT
0069	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	100.00	EACH