

Schedule of Pay Items Letting Date May 9, 2019 Letting ID 190509

Call: 140

Contract: R -39726-A

Section No.: 1 NEW ROAD CONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	203-02000	EXCAVATION, COMMON	53777.00 CYS
0013	204-08415	STAKE, SETTLEMENT	7.00 EACH
0014	205-11626	PUMP AROUND	3.00 EACH
0015	205-12108	STORM WATER MANAGEMENT BUDGET	69154.00 DOL
0016	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00 LS
0017	207-08264	SUBGRADE TREATMENT, TYPE II	597.00 SYS
0018	207-09934	SUBGRADE TREATMENT, TYPE IB	49520.00 SYS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	2227.00 SYS
0020	211-02050	B BORROW	3856.00 CYS
0021	211-09264	STRUCTURE BACKFILL, TYPE 1	25.00 CYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	825.00 CYS
0023	211-09268	STRUCTURE BACKFILL, TYPE 5	126.00 CYS
0024	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	11273.00 SYS
0025	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	2062.00 SYS
0026	217-11917	DRYING SOILS FOR EMBANKMENT	1177.00 TON
0027	301-12232	COMPACTED AGGREGATE NO 5	1033.00 CYS
0028	301-12233	COMPACTED AGGREGATE NO 8	626.00 CYS
0029	301-12234	COMPACTED AGGREGATE NO 53	7530.00 CYS
0030	303-01180	COMPACTED AGGREGATE NO. 53	6363.00 TON
0031	304-07490	HMA PATCHING, TYPE B	377.00 TON

0032	304-07493	WIDENING WITH HMA, TYPE B	123.00 TON
0033	306-08034	MILLING, ASPHALT, 1 1/2 IN.	6802.00 SYS
0034	306-08036	MILLING, ASPHALT, 2 IN.	586.00 SYS
0035	401-06264	PROFILOGRAPH, HMA	1.00 LS
0036	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	3644.00 TON
0037	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	685.00 TON
0038	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	5224.00 TON
0039	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	896.00 TON
0040	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	8384.00 TON
0041	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	908.00 TON
0042	401-10258	JOINT ADHESIVE, SURFACE	16616.00 LFT
0043	401-10259	JOINT ADHESIVE, INTERMEDIATE	13273.00 LFT
0044	401-11785	LIQUID ASPHALT SEALANT	16616.00 LFT
0045	402-10084	HMA FOR TEMPORARY PAVEMENT, B	229.00 TON
0046	406-05521	ASPHALT FOR TACK COAT	95010.00 SYS
0047	502-11564	PCCP, 7 IN.	337.00 SYS
0048	601-01625	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 1	1.00 EACH
0049	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	12.50 LFT
0050	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	2.00 EACH
0051	601-94689	GUARDRAIL, END TREATMENT, OS	2.00 EACH
0052	605-06120	CURB, CONCRETE	351.00 LFT
0053	605-06145	CURB AND GUTTER, B, CONCRETE	550.00 LFT
0054	605-06245	CENTER CURB, B CONCRETE	133.00 SYS
0055	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	7.00 LFT
0056	605-52807	CURB AND GUTTER, COMBINED	248.00 LFT
0057	605-97937	CURB AND GUTTER, ROLL CURB	1248.00 LFT
0058	610-07487	HMA FOR APPROACHES, TYPE B	123.00 TON
0059	610-08446	PCCP FOR APPROACHES, 6 IN.	245.00 SYS
0060	611-06497	MAILBOX ASSEMBLY, SINGLE	5.00 EACH
0061	611-06498	MAILBOX ASSEMBLY, DOUBLE	1.00 EACH
0062	615-06490	RIGHT-OF-WAY MARKER	92.00 EACH
0063	615-06505	MONUMENT, B	29.00 EACH
0064	615-06510	MONUMENT, C	2.00 EACH
0065	615-06527	MONUMENT, SECTION CORNER	5.00 EACH
0066	616-05688	RIPRAP, CLASS 1	268.00 TON
0067	616-06405	RIPRAP, REVETMENT	1780.00 TON
0068	616-06450	RIPRAP, PRECAST CONCRETE	183.00 SYS

0069	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	2924.00	SYS
0070	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.00	EACH
0071	621-03909	SEED MIXTURE, NATIVE	190.00	LBS
0072	621-06545	FERTILIZER	7.00	TON
0073	621-06553	SEED MIXTURE R	2272.00	LBS
0074	621-06565	MULCHING MATERIAL	31.00	TON
0075	621-06567	WATER	23.00	kGAL
0076	621-06570	TOPSOIL	275.00	CYS
0077	621-06574	SODDING	3855.00	SYS
0078	621-06575	SODDING, NURSERY	1653.00	SYS
0079	628-09402	FIELD OFFICE, B	14.00	MOS
0080	714-11303	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 10 FT. X 4 FT.	68.00	LFT
0081	714-11304	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 7 FT. X 4 FT.	200.00	LFT
0082	714-11309	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 9 FT. X 5 FT.	60.00	LFT
0083	715-03475	SAFETY METAL END SECTION, 4:1, DIA 15 IN.	16.00	EACH
0084	715-03476	SAFETY METAL END SECTION, 4:1, DIA 24 IN.	2.00	EACH
0085	715-03584	SAFETY METAL END SECTION, 4:1, DIA 18 IN.	2.00	EACH
0086	715-04611	SAFETY METAL END SECTION, 4:1, DIA 12 IN.	2.00	EACH
0087	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	2838.00	LFT
0088	715-05052	PIPE, TYPE 4, CIRCULAR, 12 IN.	300.00	LFT
0089	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	489.00	LFT
0090	715-05115	PIPE, TYPE 1, CIRCULAR, 6 IN.	10.00	LFT
0091	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	602.00	LFT
0092	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	186.00	LFT
0093	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	127.00	LFT
0094	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	193.00	LFT
0095	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	178.00	LFT
0096	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	258.00	LFT
0097	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	60.00	LFT
0098	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	362.00	LFT
0099	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	57.00	LFT
0100	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	190.00	LFT
0101	715-09936	PIPE, TYPE 1, CIRCULAR, 10 IN.	200.00	LFT
0102	715-46005	PIPE END SECTION, DIAMETER 15 IN.	11.00	EACH
0103	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0104	715-46020	PIPE END SECTION, DIAMETER 24 IN.	6.00	EACH
0105	716-07633	PIPE INSTALLATION, TRENCHLESS, 24 IN.	95.00	LFT

0106	718-06529	OUTLET PROTECTOR, 2	4.00 EACH
0107	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	2272.00 SYS
0108	718-52610	AGGREGATE FOR UNDERDRAINS	238.00 CYS
0109	720-45030	INLET, E7	2.00 EACH
0110	720-45035	INLET, F7	1.00 EACH
0111	720-45410	MANHOLE, C4	8.00 EACH
0112	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00 EACH
0113	801-03290	CONSTRUCTION SIGN, C	2.00 EACH
0114	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00 EACH
0115	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9963.00 LFT
0116	801-06625	DETOUR ROUTE MARKER ASSEMBLY	51.00 EACH
0117	801-06640	CONSTRUCTION SIGN, A	16.00 EACH
0118	801-06645	CONSTRUCTION SIGN, B	4.00 EACH
0119	801-06775	MAINTAINING TRAFFIC	1.00 LS
0120	801-07118	BARRICADE, III-A	144.00 LFT
0121	801-07119	BARRICADE, III-B	144.00 LFT
0122	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	413.00 LFT
0123	802-07057	SIGN, PANEL, WITH LEGEND	180.00 SFT
0124	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	114.00 SFT
0125	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	146.00 SFT
0126	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	25.00 SFT
0127	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	4.00 EACH
0128	802-76095	STRUCTURAL STEEL, BREAKAWAY	870.00 LBS
0129	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	221.00 LFT
0130	807-02191	HANDHOLE LIGHTING	6.00 EACH
0131	807-02428	LIGHTING FOUNDATION, CONCRETE WITH GROUND 30 IN. X 30 IN. X 96 IN.	6.00 EACH
0132	807-09637	WIRE, NO. 6 COPPER, IN PLASTIC DUCT, 4 1/C	311.00 LFT
0133	807-09638	WIRE, NO. 6 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	860.00 LFT
0134	807-11365	LUMINAIRE, ROADWAY, LED, 250 WATT	6.00 EACH
0135	807-85752	LIGHT POLE, 40 FT. E.M.H. 10.0 FT. MAST ARM, BREAKAWAY BASE	6.00 EACH
0136	807-86805	SERVICE POINT, I	1.00 EACH
0137	807-86910	CONNECTOR KIT, UNFUSED	6.00 EACH
0138	807-86915	CONNECTOR KIT, FUSED	6.00 EACH
0139	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.00 EACH
0140	807-86935	INSULATION LINK, WATERPROOFED	12.00 EACH
0141	807-87556	WIRE, TW/THW, NO. 10 COPPER, STRANDED	1200.00 LFT
0142	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	2.00 EACH

0143	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4418.00	LFT
0144	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	18639.00	LFT
0145	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	355.00	LFT
0146	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2063.00	LFT
0147	808-06716	LINE, REMOVE	2418.00	LFT
0148	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	210.00	LFT
0149	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	210.00	LFT
0150	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	135.00	LFT
0151	808-11698	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 27 IN.	67.00	LFT
0152	808-12032	GROOVING FOR PAVEMENT MARKINGS	53270.00	LFT
0153	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	27982.00	LFT
0154	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	254.00	LFT
0155	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	356.00	EACH
0156	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	2096.00	LFT

Call: 170

Contract: R -39915-A

Section No.: 1 CONSTRUCT ADA APPROVED SIDEWALK RAMPS

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0009	202-05545	REGULATED MATERIALS, DISPOSE, TYPE C	16.00 CYS
0010	202-05550	REGULATED MATERIALS, REMOVE, TYPE C	16.00 CYS
0011	202-05555	REGULATED MATERIALS, TRANSPORT, TYPE C	16.00 CYS
0012	202-07603	TESTING FOR WASTES, TYPE C	5.00 EACH
0013	304-07491	HMA PATCHING, TYPE C	16.00 TON
0014	406-05521	ASPHALT FOR TACK COAT	97.00 SYS
0015	604-08086	CURB RAMP, CONCRETE	208.00 SYS
0016	604-12083	DETECTABLE WARNING SURFACES	34.00 SYS
0017	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	4.00 SYS
0018	621-06567	WATER	1.00 kGAL
0019	621-06575	SODDING, NURSERY	124.00 SYS
0020	801-06640	CONSTRUCTION SIGN, A	44.00 EACH
0021	801-06775	MAINTAINING TRAFFIC	1.00 LS
0022	808-06368	TRANSVERSE MARKING, REMOVE	15.00 LFT
0023	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	11.00 LFT

Call: 173

Contract: R -40447-B

Section No.: 1 SMALL STRUCTURES AND DRAINS CONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0009	202-02271	HEADWALL, REMOVE	6.00 EACH
0010	202-91385	INLET, REMOVE	14.00 EACH
0011	202-96133	PIPE, REMOVE	146.00 LFT
0012	205-12108	STORM WATER MANAGEMENT BUDGET	8370.00 DOL
0013	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00 LS
0014	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	38.00 CYS
0015	601-06035	GUARDRAIL, RESET	20.00 LFT
0016	603-06060	FENCE, FARM FIELD, RESET	30.00 LFT
0017	616-06405	RIPRAP, REVETMENT	68.00 TON
0018	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	146.00 SYS
0019	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	40.00 LFT
0020	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	77.00 LFT
0021	715-08307	HMA FOR STRUCTURE INSTALLATION, TYPE D	5.00 TON
0022	715-09064	VIDEO INSPECTION FOR PIPE	920.00 LFT
0023	715-46000	PIPE END SECTION, DIAMETER 12 IN.	8.00 EACH
0024	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00 EACH
0025	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00 EACH
0026	716-07630	PIPE INSTALLATION, TRENCHLESS, 12 IN.	580.00 LFT
0027	716-07631	PIPE INSTALLATION, TRENCHLESS, 15 IN.	93.00 LFT
0028	716-07632	PIPE INSTALLATION, TRENCHLESS, 18 IN.	170.00 LFT
0029	718-06528	OUTLET PROTECTOR, 1	1.00 EACH
0030	720-45035	INLET, F7	1.00 EACH
0031	720-45045	INLET, J10	2.00 EACH

0032	720-45055	INLET, M10	1.00 EACH
0033	720-45070	INLET, P12A	4.00 EACH
0034	720-45075	INLET, R13	1.00 EACH
0035	720-45130	INLET, E7 MODIFIED	1.00 EACH
0036	720-45135	INLET, F7 MODIFIED	2.00 EACH
0037	801-06640	CONSTRUCTION SIGN, A	28.00 EACH
0038	801-06645	CONSTRUCTION SIGN, B	4.00 EACH
0039	801-06775	MAINTAINING TRAFFIC	1.00 LS
0040	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	8.00 EACH
0041	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2500.00 LFT
0042	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	400.00 LFT

Call: 230

Contract: R -41265-A

Section No.: 1 INTERCHANGE MODIFICATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	7372.00	SYS
0014	202-02272	PAVED SIDE DITCH, REMOVE	450.00	LFT
0015	202-02278	CURB, CONCRETE, REMOVE	55.00	LFT
0016	202-02279	CURB AND GUTTER, REMOVE	387.00	LFT
0017	202-02637	PIPE ABANDON AND GROUT FILL	656.00	LFT
0018	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00	LS
0019	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0020	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0021	202-93741	GUARDRAIL, END TREATMENT, REMOVE	8.00	EACH
0022	202-96531	FENCE RIGHT-OF-WAY, REMOVE	1154.00	LFT
0023	203-02000	EXCAVATION, COMMON	76697.00	CYS
0024	203-02070	BORROW	34628.00	CYS
0025	205-12108	STORM WATER MANAGEMENT BUDGET	149119.75	DOL
0026	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0027	206-93520	TEMPORARY SHEET PILING	8400.00	SFT
0028	207-08264	SUBGRADE TREATMENT, TYPE II	1524.00	SYS
0029	207-08266	SUBGRADE TREATMENT, TYPE III	16791.00	SYS
0030	207-09934	SUBGRADE TREATMENT, TYPE IB	52296.00	SYS
0031	207-09935	SUBGRADE TREATMENT, TYPE IC	442.00	SYS

0032	211-02050	B BORROW	3740.00	CYS
0033	211-09264	STRUCTURE BACKFILL, TYPE 1	2391.00	CYS
0034	211-09266	STRUCTURE BACKFILL, TYPE 3	7534.00	CYS
0035	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	47172.00	SYS
0036	301-12233	COMPACTED AGGREGATE NO 8	148.00	CYS
0037	302-07455	DENSE GRADED SUBBASE	90.00	CYS
0038	303-07449	COMPACTED AGGREGATE NO. 73	186.00	TON
0039	306-08034	MILLING, ASPHALT, 1 1/2 IN.	3068.00	SYS
0040	402-10087	HMA FOR TEMPORARY PAVEMENT, D	6369.00	TON
0041	601-02241	GUARDRAIL, REMOVE	1565.00	LFT
0042	601-06247	IMPACT ATTENUATOR, R2-W2, TL-3	2.00	EACH
0043	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	163.00	LFT
0044	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	1.00	EACH
0045	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0046	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	3.00	EACH
0047	601-94689	GUARDRAIL, END TREATMENT, OS	5.00	EACH
0048	602-06729	BARRIER, DELINEATOR	367.00	EACH
0049	603-06040	FENCE, FARM FIELD, 47 IN.	1511.00	LFT
0050	603-06045	FENCE, CHAIN LINK, 48 IN.	102.00	LFT
0051	604-05528	HMA FOR SIDEWALK	312.00	TON
0052	604-06070	SIDEWALK, CONCRETE	21.00	SYS
0053	604-08086	CURB RAMP, CONCRETE	198.00	SYS
0054	604-12083	DETECTABLE WARNING SURFACES	28.00	SYS
0055	605-06120	CURB, CONCRETE	55.00	LFT
0056	605-06140	CURB AND GUTTER, CONCRETE	4731.00	LFT
0057	605-06255	CENTER CURB, D CONCRETE	9.00	SYS
0058	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	513.20	SYS
0059	610-07487	HMA FOR APPROACHES, TYPE B	131.00	TON
0060	615-06490	RIGHT-OF-WAY MARKER	22.00	EACH
0061	615-06515	MONUMENT, D	2.00	EACH
0062	616-05688	RIPRAP, CLASS 1	59.00	TON
0063	616-06405	RIPRAP, REVETMENT	1958.00	TON
0064	616-06451	RIPRAP, UNIFORM	411.00	TON
0065	616-09997	DITCH DETENTION CHECK	5.00	EACH
0066	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	2909.00	SYS
0067	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	324.00	SYS
0068	616-51367	SLOPEWALL, CONCRETE, 4 IN.	54.00	SYS

0069	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.00 EACH
0070	621-06545	FERTILIZER	7.00 TON
0071	621-06554	SEED MIXTURE U	3704.00 LBS
0072	621-06565	MULCHING MATERIAL	37.00 TON
0073	621-06567	WATER	48.00 kGAL
0074	621-06574	SODDING	6523.00 SYS
0075	621-06575	SODDING, NURSERY	5579.00 SYS
0076	627-11647	CABLE BARRIER SYSTEM, TYPE TL-4 RESET	5480.00 LFT
0077	628-09403	FIELD OFFICE, C	36.00 MOS
0078	628-11729	CELLULAR TELEPHONE, TYPE A	3.00 EACH
0079	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0080	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0081	628-11976	COMPUTER SYSTEM EQUIPMENT	5.00 EACH
0082	628-11977	COMPUTER SYSTEM	3.00 EACH
0083	701-06011	DYNAMIC PILE LOAD TEST	6.00 EACH
0084	701-08253	PILE, SLEEVES	28.00 EACH
0085	701-09557	TEST PILE, DYNAMIC, PRODUCTION	326.00 LFT
0086	701-09559	TEST PILE, DYNAMIC, RESTRIKE	6.00 EACH
0087	702-51005	CONCRETE, A, SUBSTRUCTURE	270.40 CYS
0088	702-92857	CONCRETE, C, SUBSTRUCTURE	76.70 CYS
0089	703-06029	REINFORCING BARS, EPOXY COATED	267406.00 LBS
0090	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	82.00 EACH
0091	704-51002	CONCRETE, C, SUPERSTRUCTURE	689.90 CYS
0092	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TPS-1	2.00 EACH
0093	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	123.00 SYS
0094	706-09961	RAILING, CONCRETE PS-1	331.00 LFT
0095	706-11418	RAILING, STEEL PS-1	528.00 LFT
0096	706-11600	RAILING, CONCRETE FC	66.50 CYS
0097	706-11604	RAILING, CONCRETE PS-1	16.00 CYS
0098	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	5.00 EACH
0099	707-09634	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 48 IN. X 49 IN.	1751.00 LFT
0100	709-07733	ANTI-GRAFFITI COAT	1.00 LS
0101	709-51821	SURFACE SEAL	1.00 LS
0102	709-51821	SURFACE SEAL	1.00 LS
0103	711-51035	STRUCTURAL STEEL	8465.00 LBS
0104	711-51035	STRUCTURAL STEEL	2253.00 LBS
0105	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	112.00 LFT

0106	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	32163.00	LFT
0107	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	1792.00	LFT
0108	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	113.00	LFT
0109	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	189.00	LFT
0110	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	1496.00	LFT
0111	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	536.00	LFT
0112	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	125.00	LFT
0113	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	47.00	LFT
0114	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	59.00	LFT
0115	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	88.00	LFT
0116	715-06471	PIPE END SECTION, MIN. AREA 3.3 SFT	1.00	EACH
0117	715-08243	PIPE, TYPE 3, DEFORMED, MIN. AREA 3.3 SFT	80.00	LFT
0118	715-46005	PIPE END SECTION, DIAMETER 15 IN.	10.00	EACH
0119	715-46010	PIPE END SECTION, DIAMETER 18 IN.	7.00	EACH
0120	715-46020	PIPE END SECTION, DIAMETER 24 IN.	3.00	EACH
0121	715-46030	PIPE END SECTION, DIAMETER 30 IN.	2.00	EACH
0122	715-46040	PIPE END SECTION, DIAMETER 36 IN.	4.00	EACH
0123	716-07632	PIPE INSTALLATION, TRENCHLESS, 18 IN.	79.00	LFT
0124	716-07634	PIPE INSTALLATION, TRENCHLESS, 30 IN.	330.00	LFT
0125	716-07635	PIPE INSTALLATION, TRENCHLESS, 36 IN.	150.00	LFT
0126	718-06528	OUTLET PROTECTOR, 1	18.00	EACH
0127	718-06529	OUTLET PROTECTOR, 2	8.00	EACH
0128	718-06531	OUTLET PROTECTOR, 3	9.00	EACH
0129	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	13613.00	SYS
0130	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	777.00	SYS
0131	718-52610	AGGREGATE FOR UNDERDRAINS	1594.00	CYS
0132	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0133	720-45015	INLET, A8	15.00	EACH
0134	720-45030	INLET, E7	2.00	EACH
0135	720-45035	INLET, F7	3.00	EACH
0136	720-45040	INLET, G7	5.00	EACH
0137	720-45315	CATCH BASIN, A8 MODIFIED	19.00	EACH
0138	720-45400	MANHOLE, A4	1.00	EACH
0139	726-92406	BEARING ASSEMBLY ELASTOMERIC	18.00	EACH
0140	731-93945	FACE PANELS, CONCRETE	10521.00	SFT
0141	731-93946	WALL ERECTION	10521.00	SFT
0142	731-93947	LEVELING PAD, CONCRETE	785.00	LFT

0143	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.00 EACH
0144	801-03290	CONSTRUCTION SIGN, C	4.00 EACH
0145	801-03291	CONSTRUCTION SIGN, D	6.00 EACH
0146	801-03621	TEMPORARY ILLUMINATION	1.00 LS
0147	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00 EACH
0148	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	29447.00 LFT
0149	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	29766.00 LFT
0150	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	96.00 LFT
0151	801-06625	DETOUR ROUTE MARKER ASSEMBLY	35.00 EACH
0152	801-06640	CONSTRUCTION SIGN, A	127.00 EACH
0153	801-06645	CONSTRUCTION SIGN, B	28.00 EACH
0154	801-06710	FLASHING ARROW SIGN	350.00 DAY
0155	801-06775	MAINTAINING TRAFFIC	1.00 LS
0156	801-07118	BARRICADE, III-A	424.00 LFT
0157	801-07119	BARRICADE, III-B	48.00 LFT
0158	801-07612	TEMPORARY PAVEMENT MARKING, 24 IN.	449.00 LFT
0159	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	9670.00 LFT
0160	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	3690.00 LFT
0161	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	8.00 EACH
0162	801-12082	FIXED TEMPORARY SIGNAL	1.00 LS
0163	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	580.00 LFT
0164	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	240.00 LFT
0165	802-07057	SIGN, PANEL, WITH LEGEND	622.00 SFT
0166	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	36.00 EACH
0167	802-09578	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	2.00 EACH
0168	802-09581	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 36 IN.	2.00 EACH
0169	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	370.00 SFT
0170	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	205.00 SFT
0171	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	36.00 SFT
0172	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	6.00 EACH
0173	802-12223	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, B	2.00 EACH
0174	802-74040	SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	4.00 EACH
0175	802-74080	OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	2.00 EACH
0176	802-76095	STRUCTURAL STEEL, BREAKAWAY	2270.00 LBS
0177	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	3.00 EACH
0178	805-01842	HANDHOLE SIGNAL TYPE 1	22.00 EACH
0179	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00 LS

0180	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	10.00 EACH
0181	805-02445	CONTROLLER AND CABINET, P1	1.00 EACH
0182	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	14.00 EACH
0183	805-04973	CONDUIT	533.00 LFT
0184	805-04973	CONDUIT	216.00 LFT
0185	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	1972.00 LFT
0186	805-09845	CONTACT CLOSURE CARD	1.00 EACH
0187	805-09846	RECEIVER PROCESSOR	4.00 EACH
0188	805-10107	WIRELESS MAGNETOMETER DETECTOR	120.00 EACH
0189	805-10108	WIRELESS REPEATER	4.00 EACH
0190	805-11375	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 25 FT.	2.00 EACH
0191	805-11376	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 30 FT.	2.00 EACH
0192	805-11377	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 35 FT.	1.00 EACH
0193	805-11378	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 40 FT.	3.00 EACH
0194	805-11689	SIGNAL POLE, PEDESTAL, 20 FT	4.00 EACH
0195	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	542.00 LFT
0196	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	868.00 LFT
0197	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	21.00 EACH
0198	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	2.00 EACH
0199	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	1.00 EACH
0200	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	10.00 EACH
0201	805-78445	SIGNAL SERVICE	1.00 EACH
0202	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	120.00 LFT
0203	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	3155.00 LFT
0204	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	4448.00 LFT
0205	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	3658.00 LFT
0206	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	416.00 LFT
0207	805-78790	LOOP DETECTOR DELAY AMPLIFIER, 4 CHANNEL	21.00 EACH
0208	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00 EACH
0209	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	10.00 EACH
0210	807-01653	WIRE, NO. 4 COPPER, IN CONDUIT, BRIDGE 1/C	2176.00 LFT
0211	807-02191	HANDHOLE LIGHTING	12.00 EACH
0212	807-02603	LIGHT STANDARD RELOCATE	1.00 EACH
0213	807-02934	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. X 36 IN. X 96 IN.	1.00 EACH
0214	807-04651	WIRE	949.00 LFT
0215	807-04651	WIRE	949.00 LFT
0216	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	802.00 LFT

0217	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	10230.00	LFT
0218	807-12201	LUMINAIRE, HIGH MAST	12.00	EACH
0219	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	14.00	EACH
0220	807-12424	LIGHT POLE, HIGH MAST, 170 FT E.M.H.	2.00	EACH
0221	807-12425	LIGHT FOUNDATION CONCRETE WITH GROUND 54 IN. DIA X 240 IN.	2.00	EACH
0222	807-78590	HANDHOLE	4.00	EACH
0223	807-86810	SERVICE POINT, II	1.00	EACH
0224	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	2520.00	LFT
0225	807-86910	CONNECTOR KIT, UNFUSED	14.00	EACH
0226	807-86915	CONNECTOR KIT, FUSED	14.00	EACH
0227	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	11.00	EACH
0228	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	11.00	EACH
0229	807-86930	INSULATION LINK, NON-WATERPROOFED	32.00	EACH
0230	807-86935	INSULATION LINK, WATERPROOFED	48.00	EACH
0231	807-86955	CABLE-DUCT MARKER	7.00	EACH
0232	807-91082	LUMINAIRE, REMOVE AND RELOCATE	12.00	EACH
0233	808-06368	TRANSVERSE MARKING, REMOVE	215.00	LFT
0234	808-06716	LINE, REMOVE	14371.00	LFT
0235	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0236	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1012.00	LFT
0237	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	506.00	LFT
0238	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	6.00	EACH
0239	808-12032	GROOVING FOR PAVEMENT MARKINGS	34031.00	LFT
0240	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	54.00	EACH
0241	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	402.00	EACH
0242	809-04652	SERVICE POINT	1.00	EACH

Call: 230

Contract: R -41265-A

Section No.: 2 INTERCHANGE MODIFICATION, HMA

Line			
Item No	Item Code	Description	Quantity Unit
0243	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0244	301-12234	COMPACTED AGGREGATE NO 53	10987.00 CYS
0245	303-01180	COMPACTED AGGREGATE NO. 53	16960.00 TON
0246	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	331.00 TON
0247	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	3814.00 TON
0248	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	552.00 TON
0249	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	5934.00 TON
0250	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	1324.00 TON
0251	401-08364	QC/QA-HMA, 4, 64, BASE, 19.0 mm	14242.00 TON
0252	401-10258	JOINT ADHESIVE, SURFACE	35679.00 LFT
0253	401-10259	JOINT ADHESIVE, INTERMEDIATE	32888.00 LFT
0254	401-11785	LIQUID ASPHALT SEALANT	35679.00 LFT
0255	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	8326.00 TON
0256	406-05520	ASPHALT FOR TACK COAT	59.00 TON
0257	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1085.00 LFT
0258	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	17744.00 LFT
0259	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	16.00 LFT
0260	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	411.00 LFT
0261	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	321.00 LFT
0262	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	14469.00 LFT
0263	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	401.00 LFT
0264	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	585.00 LFT
0265	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	60.00 EACH
0266	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	8.00 EACH

Call: 230

Contract: R -41265-A

Section No.: 3 INTERCHANGE MODIFICATION, PCCP

Line				
Item No	Item Code	Description	Quantity	Unit
0267	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0268	301-12234	COMPACTED AGGREGATE NO 53	3043.00	CYS
0269	302-06464	SUBBASE FOR PCCP	13074.00	CYS
0270	303-01180	COMPACTED AGGREGATE NO. 53	16830.00	TON
0271	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	253.00	TON
0272	401-10258	JOINT ADHESIVE, SURFACE	3209.00	LFT
0273	401-10259	JOINT ADHESIVE, INTERMEDIATE	419.00	LFT
0274	401-11785	LIQUID ASPHALT SEALANT	3209.00	LFT
0275	406-05520	ASPHALT FOR TACK COAT	12.00	TON
0276	501-06321	QC/QA-PCCP, 10 IN.	47960.00	SYS
0277	503-05240	D-1 CONTRACTION JOINT	27197.00	LFT
0278	503-05310	TERMINAL JOINT	153.00	LFT
0279	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1085.00	LFT
0280	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	17744.00	LFT
0281	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	14469.00	LFT
0282	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	321.00	LFT
0283	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	401.00	LFT
0284	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	8.00	EACH
0285	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	585.00	LFT
0286	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	60.00	EACH
0287	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	411.00	LFT
0288	808-11776	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 24 IN.	16.00	LFT

Call: 230
Contract: R -41265-A
Section No.: 4 BRIDGE REPLACEMENT, FOUNDATION OPTION 1

Line			Quantity	Unit
Item No	Item Code	Description		
0289	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	374.00	CYS
0290	211-02050	B BORROW	374.00	CYS
0291	701-09891	PILE SHOE, HP 12 X 84	58.00	EACH
0292	701-95782	PILE, STEEL H, HP, 12 X 84	2358.00	LFT
0293	702-51015	CONCRETE, B, FOOTINGS	152.70	CYS
0294	703-06028	REINFORCING BARS	38859.00	LBS

Call: 230
Contract: R -41265-A
Section No.: 5 BRIDGE REPLACEMENT, FOUNDATION OPTION 2

Line			Quantity	Unit
Item No	Item Code	Description		
0295	204-02290	SETTLEMENT PLATE	16.00	EACH
0296	204-08396	STANDPIPE PIEZOMETER	4.00	EACH
0297	204-08415	STAKE, SETTLEMENT	4.00	EACH
0298	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	489.00	CYS
0299	211-02050	B BORROW	489.00	CYS
0300	701-09739	PILE SHOE, HP 12 X 53	73.00	EACH
0301	701-51195	PILE, STEEL H HP 12 X 53	2823.00	LFT
0302	702-51015	CONCRETE, B, FOOTINGS	229.20	CYS
0303	703-06028	REINFORCING BARS	41378.00	LBS

Call: 254

Contract: R -41815-B

Section No.: 1 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-02928	CATCH BASIN, REMOVE	1.00 EACH
0013	202-96133	PIPE, REMOVE	63.00 LFT
0014	203-02000	EXCAVATION, COMMON	4708.00 CYS
0015	203-02070	BORROW	1392.00 CYS
0016	205-12108	STORM WATER MANAGEMENT BUDGET	1.00 DOL
0017	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00 LS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	5517.00 SYS
0019	211-09264	STRUCTURE BACKFILL, TYPE 1	185.00 CYS
0020	303-01180	COMPACTED AGGREGATE NO. 53	667.00 TON
0021	304-07493	WIDENING WITH HMA, TYPE B	2.00 TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	11390.00 SYS
0023	401-06264	PROFILOGRAPH, HMA	1.00 LS
0024	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	1420.00 TON
0025	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	793.00 TON
0026	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	994.00 TON
0027	401-10258	JOINT ADHESIVE, SURFACE	9064.00 LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	2238.00 LFT
0029	401-11785	LIQUID ASPHALT SEALANT	9064.00 LFT
0030	406-05521	ASPHALT FOR TACK COAT	26603.00 SYS
0031	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00 TON

0032	604-06070	SIDEWALK, CONCRETE	65.00	SYS
0033	605-02493	CURB, ISLAND CONCRETE	80.00	SYS
0034	605-06140	CURB AND GUTTER, CONCRETE	672.00	LFT
0035	605-06145	CURB AND GUTTER, B, CONCRETE	127.00	LFT
0036	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	14.00	LFT
0037	615-06490	RIGHT-OF-WAY MARKER	16.00	EACH
0038	615-06505	MONUMENT, B	2.00	EACH
0039	616-06405	RIPRAP, REVETMENT	227.00	TON
0040	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	296.00	SYS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0042	621-06574	SODDING	133.00	SYS
0043	628-09402	FIELD OFFICE, B	15.00	MOS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0045	628-11977	COMPUTER SYSTEM	2.00	EACH
0046	715-05118	PIPE, TYPE 1, CIRCULAR, 12 IN.	39.00	LFT
0047	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	130.00	LFT
0048	715-05148	PIPE, TYPE 2, CIRCULAR, 10 IN.	17.00	LFT
0049	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	32.00	LFT
0050	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	149.00	LFT
0051	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0052	715-46020	PIPE END SECTION, DIAMETER 24 IN.	4.00	EACH
0053	715-90325	PIPE END SECTION, DIAMETER 10 IN.	1.00	EACH
0054	720-44000	CASTING, ADJUST TO GRADE	8.00	EACH
0055	720-98174	INLET, B15	2.00	EACH
0056	720-98555	INLET, C15	2.00	EACH
0057	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	5283.00	LFT
0058	801-06640	CONSTRUCTION SIGN, A	15.00	EACH
0059	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0060	801-06710	FLASHING ARROW SIGN	360.00	DAY
0061	801-06775	MAINTAINING TRAFFIC	1.00	LS
0062	801-07118	BARRICADE, III-A	33.00	LFT
0063	802-04089	SIGN, SHEET, REMOVE	2.00	EACH
0064	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	41.00	LFT
0065	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	105.00	SFT
0066	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	64.00	SFT
0067	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0068	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00	EACH

0069	805-01842	HANDHOLE SIGNAL TYPE 1	7.00 EACH
0070	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1870.00 LFT
0071	805-02445	CONTROLLER AND CABINET, P1	1.00 EACH
0072	805-08244	CELLULAR MODEM KIT	1.00 EACH
0073	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	10.00 EACH
0074	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	2.00 EACH
0075	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	1.00 EACH
0076	805-78415	SPAN, CATENARY, AND TETHER	4.00 EACH
0077	805-78420	DISCONNECT HANGER	4.00 EACH
0078	805-78445	SIGNAL SERVICE	1.00 EACH
0079	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	70.00 LFT
0080	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	5440.00 LFT
0081	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	160.00 LFT
0082	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	70.00 LFT
0083	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	920.00 LFT
0084	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	3990.00 LFT
0085	805-78785	SIGNAL DETECTOR HOUSING	15.00 EACH
0086	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1670.00 LFT
0087	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00 EACH
0088	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	4.00 EACH
0089	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	9.00 EACH
0090	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	3.00 SYS
0091	808-06368	TRANSVERSE MARKING, REMOVE	34.00 LFT
0092	808-06716	LINE, REMOVE	927.00 LFT
0093	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0094	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1040.00 LFT
0095	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	8341.00 LFT
0096	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	6041.00 LFT
0097	808-12032	GROOVING FOR PAVEMENT MARKINGS	15837.00 LFT
0098	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	80.00 LFT
0099	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	22.00 LFT
0100	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	54.00 LFT
0101	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	259.00 LFT
0102	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	15.00 EACH
0103	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	199.00 EACH
0104	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	214.00 EACH

Call: 314

Contract: RS-40676-B

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	202-52710	SIDEWALK CONCRETE, REMOVE	713.00	SYS
0012	202-90277	DETECTOR HOUSING, REMOVE	13.00	EACH
0013	207-09935	SUBGRADE TREATMENT, TYPE IC	111.00	SYS
0014	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	11.00	CYS
0015	304-07491	HMA PATCHING, TYPE C	368.00	TON
0016	306-08034	MILLING, ASPHALT, 1 1/2 IN.	33072.00	SYS
0017	306-08043	MILLING, TRANSITION	55.00	SYS
0018	306-08432	MILLING, APPROACH	3637.00	SYS
0019	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2729.00	TON
0020	401-10258	JOINT ADHESIVE, SURFACE	20215.00	LFT
0021	401-11785	LIQUID ASPHALT SEALANT	20215.00	LFT
0022	402-07452	HMA WEDGE AND LEVEL, TYPE C	5.00	TON
0023	406-05520	ASPHALT FOR TACK COAT	10.00	TON
0024	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	10.00	TON
0025	503-03489	RETROFITTED TIE BARS	9.00	EACH
0026	503-05240	D-1 CONTRACTION JOINT	24.00	LFT
0027	506-06333	PCCP PATCHING, FULL DEPTH	74.00	SYS
0028	506-06334	PCCP PATCHING, PARTIAL DEPTH	25.00	SYS
0029	507-07480	PROFILING, PCCP	1600.00	SYS
0030	507-08269	CRACKS IN PCCP, FILLED	50.00	LFT
0031	507-08271	JOINTS IN PCCP, FILLED	1484.00	LFT

0032	604-06070	SIDEWALK, CONCRETE	312.00	SYS
0033	604-07092	BED COURSE MATERIAL	19.00	TON
0034	604-08086	CURB RAMP, CONCRETE	420.00	SYS
0035	604-12083	DETECTABLE WARNING SURFACES	46.00	SYS
0036	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	5.00	SYS
0037	605-01870	CURB, CONCRETE A	194.00	LFT
0038	605-02278	CURB, REMOVE	115.00	LFT
0039	610-07488	HMA FOR APPROACHES, TYPE C	326.00	TON
0040	621-06565	MULCHING MATERIAL	2.00	TON
0041	621-06567	WATER	5.00	KGAL
0042	621-06574	SODDING	31.00	SYS
0043	628-09403	FIELD OFFICE, C	12.00	MOS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0045	628-11977	COMPUTER SYSTEM	1.00	EACH
0046	702-51863	FIELD DRILLED HOLE IN CONCRETE	18.00	EACH
0047	702-90915	CONCRETE, CLASS, A	24.00	CYS
0048	703-06029	REINFORCING BARS, EPOXY COATED	1740.00	LBS
0049	720-44000	CASTING, ADJUST TO GRADE	6.00	EACH
0050	720-44000	CASTING, ADJUST TO GRADE	18.00	EACH
0051	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	4.00	EACH
0052	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	2286.00	LFT
0053	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2286.00	LFT
0054	801-06640	CONSTRUCTION SIGN, A	49.00	EACH
0055	801-06645	CONSTRUCTION SIGN, B	20.00	EACH
0056	801-06775	MAINTAINING TRAFFIC	1.00	LS
0057	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	9.00	EACH
0058	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	120.00	LFT
0059	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	8.00	EACH
0060	805-05405	SIGNAL POLE, PEDESTAL, 4FT	6.00	EACH
0061	805-11817	PEDESTRIAN PUSH BUTTON, APS	24.00	EACH
0062	805-11817	PEDESTRIAN PUSH BUTTON, APS	6.00	EACH
0063	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	6500.00	LFT
0064	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	1249.00	LFT
0065	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	650.00	LFT
0066	805-78785	SIGNAL DETECTOR HOUSING	13.00	EACH
0067	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2080.00	LFT
0068	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	300.00	LFT

0069	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7767.00	LFT
0070	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	68.00	LFT
0071	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1302.00	LFT
0072	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	813.00	LFT
0073	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0074	808-12032	GROOVING FOR PAVEMENT MARKINGS	17550.00	LFT
0075	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE 4 IN.	2062.00	LFT
0076	808-12274	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, BLUE 4 IN.	96.00	LFT
0077	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	924.00	LFT
0078	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	8859.00	LFT
0079	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	283.00	LFT
0080	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	1205.00	LFT
0081	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	21.00	EACH
0082	808-97664	PAVEMENT MESSAGE MARKING, THERMOPLASTIC HANDICAP SYMBOL	4.00	EACH

Call: 390

Contract: RS-41964-A

Section No.: 1 ASPHALT PATCHING

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	304-07783	HMA PATCHING, TYPE D	9422.00	TON
0010	406-05520	ASPHALT FOR TACK COAT	22.00	TON
0011	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0012	801-06775	MAINTAINING TRAFFIC	1.00	LS
0013	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	446.00	LFT
0014	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	160.00	LFT
0015	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	930.00	LFT
0016	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	5430.00	LFT
0017	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	59520.00	LFT
0018	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	36500.00	LFT

Call: 642

Contract: B -41681-B

Section No.: 1 IDIQ, BRIDGE REHABILITATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0002	109-08360	CONTRACT LIENS	1.00 DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0007	110-07025	MOBILIZATION AND DEMOBILIZATION	5.00 EACH
0008	202-02240	PAVEMENT REMOVAL	50.00 SYS
0009	202-51368	SLOPEWALL, REMOVE	450.00 SYS
0010	203-02000	EXCAVATION, COMMON	75.00 CYS
0011	211-09268	STRUCTURE BACKFILL, TYPE 5	150.00 CYS
0012	213-09270	FLOWABLE BACKFILL, REMOVABLE	200.00 CYS
0013	302-07455	DENSE GRADED SUBBASE	250.00 CYS
0014	303-01180	COMPACTED AGGREGATE NO. 53	25.00 TON
0015	402-07452	HMA WEDGE AND LEVEL, TYPE C	10.00 TON
0016	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	288.00 LFT
0017	507-07482	CRACKS IN PCCP, ROUT AND SEAL	160.00 LFT
0018	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	700.00 SYS
0019	616-06405	RIPRAP, REVETMENT	70.00 TON
0020	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	100.00 SYS
0021	616-51366	SLOPEWALL, CONCRETE, 5 IN.	450.00 SYS
0022	703-06029	REINFORCING BARS, EPOXY COATED	500.00 LBS
0023	709-12077	FIBER WRAP CONCRETE CASING SYSTEM	1000.00 SFT
0024	710-09158	PATCHING CONCRETE STRUCTURES	150.00 SFT
0025	711-11599	REPAIR WELD	90.00 IN
0026	711-51035	STRUCTURAL STEEL	4000.00 LBS
0027	711-51864	DRILLED HOLE	40.00 EACH
0028	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00 LS
0029	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	50.00 SFT
0030	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	2000.00 SFT
0031	722-60824	SURFACE MILLING	1000.00 SYS

0032	724-12103	PRE-COMPRESSED FOAM JOINT	288.00	LFT
0033	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	1200.00	SYS
0034	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	500.00	LFT
0035	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0036	801-06710	FLASHING ARROW SIGN	10.00	DAY
0037	801-07118	BARRICADE, III-A	72.00	LFT
0038	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0039	801-12042	TRUCK MOUNTED ATTENUATOR	12.00	DAY
0040	801-12324	LAW ENFORCEMENT OFFICER	20.00	HRS
0041	801-12440	MAINTAINING TRAFFIC, IDIQ	1.00	DOL

Call: 716

Contract: T -41220-B

Section No.: 1 ITS TRAFFIC MANAGEMENT SYSTEMS

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0007	628-11729	CELLULAR TELEPHONE, TYPE A	5.00 EACH
0008	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0009	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0010	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	60.00 MOS
0011	628-11976	COMPUTER SYSTEM EQUIPMENT	5.00 EACH
0012	801-06640	CONSTRUCTION SIGN, A	34.00 EACH
0013	801-06645	CONSTRUCTION SIGN, B	12.00 EACH
0014	801-06710	FLASHING ARROW SIGN	120.00 DAY
0015	801-06775	MAINTAINING TRAFFIC	1.00 LS
0016	802-06402	DYNAMIC MESSAGE SIGN	1.00 EACH
0017	802-06402	DYNAMIC MESSAGE SIGN	14.00 EACH
0018	802-06402	DYNAMIC MESSAGE SIGN	28.00 EACH
0019	802-06402	DYNAMIC MESSAGE SIGN	3.00 EACH
0020	802-06402	DYNAMIC MESSAGE SIGN	52.00 EACH
0021	802-06402	DYNAMIC MESSAGE SIGN	104.00 EACH
0022	802-06402	DYNAMIC MESSAGE SIGN	20.00 EACH
0023	802-06402	DYNAMIC MESSAGE SIGN	8.00 EACH
0024	802-06402	DYNAMIC MESSAGE SIGN	41.00 EACH
0025	802-06402	DYNAMIC MESSAGE SIGN	22.00 EACH
0026	802-06402	DYNAMIC MESSAGE SIGN	9.00 EACH
0027	802-06402	DYNAMIC MESSAGE SIGN	37.00 EACH