

Schedule of Pay Items Letting Date September 11, 2019 Letting ID 190911

Call: 131

Contract: R -31319-B

Section No.: 1 ROAD REHABILITATION

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	98.00	EACH
0003	109-04299	FORCE ACCOUNT WORK	100000.00	DOL
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0010	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0011	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0012	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0014	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0015	202-02240	PAVEMENT REMOVAL	9733.00	SYS
0016	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00	LS
0017	202-03729	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	20.00	LFT
0018	202-05545	REGULATED MATERIALS, DISPOSE, TYPE C	23.00	CYS
0019	202-05550	REGULATED MATERIALS, REMOVE, TYPE C	23.00	CYS
0020	202-05555	REGULATED MATERIALS, TRANSPORT, TYPE C	23.00	CYS
0021	202-05571	TESTING FOR WASTES	2.00	EACH
0022	203-02000	EXCAVATION, COMMON	12100.00	CYS
0023	203-02070	BORROW	4400.00	CYS
0024	205-12108	STORM WATER MANAGEMENT BUDGET	88378.00	DOL
0025	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0026	207-08264	SUBGRADE TREATMENT, TYPE II	7092.00	SYS
0027	207-08268	SUBGRADE TREATMENT, TYPE IV	23254.00	SYS
0028	207-09935	SUBGRADE TREATMENT, TYPE IC	8215.00	SYS
0029	207-09935	SUBGRADE TREATMENT, TYPE IC	4848.00	SYS
0030	211-02050	B BORROW	1300.00	CYS
0031	211-09264	STRUCTURE BACKFILL, TYPE 1	5584.00	CYS
0032	211-09266	STRUCTURE BACKFILL, TYPE 3	1325.00	CYS
0033	301-12231	COMPACTED AGGREGATE NO 2	1.00	CYS

0034	301-12234	COMPACTED AGGREGATE NO 53	866.00	CYS
0035	304-07491	HMA PATCHING, TYPE C	2667.00	TON
0036	304-07494	WIDENING WITH HMA, TYPE C	5474.00	TON
0037	306-08034	MILLING, ASPHALT, 1 1/2 IN.	8357.00	SYS
0038	306-11872	MILLING, PROFILE	54648.00	SYS
0039	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	6300.00	TON
0040	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1924.00	TON
0041	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	1760.00	TON
0042	401-10258	JOINT ADHESIVE, SURFACE	35030.00	LFT
0043	401-10259	JOINT ADHESIVE, INTERMEDIATE	4750.00	LFT
0044	401-11785	LIQUID ASPHALT SEALANT	35030.00	LFT
0045	402-10086	HMA FOR TEMPORARY PAVEMENT, C	352.00	TON
0046	406-05520	ASPHALT FOR TACK COAT	28.00	TON
0047	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0048	503-05240	D-1 CONTRACTION JOINT	315.00	LFT
0049	601-01128	GUARDRAIL, TRANSITION, TYPE WGB	1.00	EACH
0050	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	2.00	EACH
0051	601-01701	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 2	2.00	EACH
0052	601-05999	CURVED TERMINAL END	3.00	EACH
0053	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	639.00	LFT
0054	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0055	603-06045	FENCE, CHAIN LINK, 48 IN.	16.00	LFT
0056	603-06065	FENCE, CHAIN LINK, RESET	36.00	LFT
0057	603-97461	TEMPORARY FENCE	700.00	LFT
0058	604-06070	SIDEWALK, CONCRETE	9405.00	SYS
0059	604-08086	CURB RAMP, CONCRETE	692.00	SYS
0060	604-12083	DETECTABLE WARNING SURFACES	142.00	SYS
0061	604-44251	STEPS, CONCRETE	1.00	CYS
0062	604-95344	HAND RAIL, PEDESTRIAN	379.00	LFT
0063	605-06120	CURB, CONCRETE	727.00	LFT
0064	605-06125	CURB, CONCRETE, MODIFIED	169.00	LFT
0065	605-06145	CURB AND GUTTER, B, CONCRETE	805.00	LFT
0066	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	1255.00	LFT
0067	605-06255	CENTER CURB, D CONCRETE	220.00	SYS
0068	605-09137	CURB, TURNOUT	56.00	LFT
0069	605-52807	CURB AND GUTTER, COMBINED	26645.00	LFT
0070	605-97937	CURB AND GUTTER, ROLL CURB	96.00	LFT
0071	610-08446	PCCP FOR APPROACHES, 6 IN.	1875.00	SYS
0072	610-09108	PCCP FOR APPROACHES, 9 IN.	5217.00	SYS
0073	611-06497	MAILBOX ASSEMBLY, SINGLE	12.00	EACH
0074	611-08232	MAILBOX ASSEMBLY, SINGLE RESET	1.00	EACH
0075	615-06505	MONUMENT, B	42.00	EACH

0076	615-06510	MONUMENT, C	2.00 EACH
0077	615-06527	MONUMENT, SECTION CORNER	3.00 EACH
0078	616-06405	RIPRAP, REVETMENT	77.00 TON
0079	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	199.00 SYS
0080	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00 EACH
0081	621-06545	FERTILIZER	2.15 TON
0082	621-06554	SEED MIXTURE U	757.00 LBS
0083	621-06565	MULCHING MATERIAL	7.90 TON
0084	621-06575	SODDING, NURSERY	9992.00 SYS
0085	628-09403	FIELD OFFICE, C	55.00 MOS
0086	628-11730	CELLULAR TELEPHONE, TYPE B	3.00 EACH
0087	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0088	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	165.00 MOS
0089	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0090	703-06029	REINFORCING BARS, EPOXY COATED	7915.00 LBS
0091	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	547.00 SYS
0092	706-09964	RAILING, CONCRETE PS-2	547.00 LFT
0093	706-11419	RAILING, STEEL PS-2	547.00 LFT
0094	709-51821	SURFACE SEAL	1.00 LS
0095	715-04555	PIPE END SECTION, MIN. AREA 5.1 SFT	1.00 EACH
0096	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	2598.00 LFT
0097	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	550.00 LFT
0098	715-05147	PIPE, TYPE 2, CIRCULAR, 8 IN.	8.00 LFT
0099	715-05148	PIPE, TYPE 2, CIRCULAR, 10 IN.	170.00 LFT
0100	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	4849.00 LFT
0101	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	1441.00 LFT
0102	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	1967.00 LFT
0103	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	1511.00 LFT
0104	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	598.00 LFT
0105	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	64.00 LFT
0106	715-05327	PIPE, TYPE 2, DEFORMED, MIN. AREA 1.83 SFT	4.00 LFT
0107	715-05335	PIPE, TYPE 2, DEFORMED, MIN. AREA 5.1 SFT	49.00 LFT
0108	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	868.00 TON
0109	715-09064	VIDEO INSPECTION FOR PIPE	10483.00 LFT
0110	715-46000	PIPE END SECTION, DIAMETER 12 IN.	7.00 EACH
0111	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00 EACH
0112	715-46010	PIPE END SECTION, DIAMETER 18 IN.	6.00 EACH
0113	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00 EACH
0114	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3547.00 LFT
0115	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	2834.00 SYS
0116	718-52610	AGGREGATE FOR UNDERDRAINS	285.00 CYS
0117	720-01092	MANHOLE, J15 MODIFIED	29.00 EACH

0118	720-44000	CASTING, ADJUST TO GRADE	2.00 EACH
0119	720-44015	CASTING, 2, FURNISH AND ADJUST TO GRADE	3.00 EACH
0120	720-44020	CASTING, 3, FURNISH AND ADJUST TO GRADE	1.00 EACH
0121	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	34.00 EACH
0122	720-45030	INLET, E7	10.00 EACH
0123	720-45045	INLET, J10	4.00 EACH
0124	720-45075	INLET, R13	16.00 EACH
0125	720-45235	CATCH BASIN, E7	1.00 EACH
0126	720-45410	MANHOLE, C4	24.00 EACH
0127	720-45605	STRUCTURE, MANHOLE, RECONSTRUCTED	4.00 LFT
0128	720-90984	MANHOLE, C2	7.00 EACH
0129	720-93501	MANHOLE, L4	1.00 EACH
0130	720-94612	MANHOLE, K4	1.00 EACH
0131	720-95422	MANHOLE, J4	6.00 EACH
0132	720-98174	INLET, B15	70.00 EACH
0133	720-98555	INLET, C15	44.00 EACH
0134	720-99416	CATCH BASIN, B15	1.00 EACH
0135	720-99417	CATCH BASIN, C15	4.00 EACH
0136	731-93945	FACE PANELS, CONCRETE	4034.00 SFT
0137	731-93946	WALL ERECTION	4034.00 SFT
0138	731-93947	LEVELING PAD, CONCRETE	547.00 LFT
0139	732-11770	AGGREGATE FOR DRAINAGE FILL	18.00 CYS
0140	732-11811	MODULAR BLOCK WALL ERECTION	482.00 SFT
0141	732-11812	MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	482.00 SFT
0142	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	22.00 EACH
0143	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00 EACH
0144	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	98937.00 LFT
0145	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	464.00 LFT
0146	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	142.00 LFT
0147	801-06625	DETOUR ROUTE MARKER ASSEMBLY	68.00 EACH
0148	801-06640	CONSTRUCTION SIGN, A	84.00 EACH
0149	801-06645	CONSTRUCTION SIGN, B	32.00 EACH
0150	801-06710	FLASHING ARROW SIGN	270.00 DAY
0151	801-06775	MAINTAINING TRAFFIC	1.00 LS
0152	801-07118	BARRICADE, III-A	168.00 LFT
0153	801-07119	BARRICADE, III-B	96.00 LFT
0154	801-94295	SIGNAL HEAD RELOCATE	28.00 EACH
0155	802-04893	REFERENCE POST	2.00 EACH
0156	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	840.00 LFT
0157	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	104.00 LFT
0158	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	62.00 EACH
0159	802-07060	SIGN, SHEET, RELOCATE	57.00 EACH

0160	802-07135	CABLE SPAN SIGN STRUCTURE FOUNDATION, IV	2.00 EACH
0161	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	722.00 SFT
0162	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	457.00 SFT
0163	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	375.00 SFT
0164	802-74050	SIGN, OVERHEAD, REMOVE	16.00 EACH
0165	802-74070	OVERHEAD SIGN STRUCTURE, CABLE SPAN, REMOVE	3.00 EACH
0166	802-76125	OVERHEAD SIGN STRUCTURE, CABLESPAN	1.00 EACH
0167	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	7.00 EACH
0168	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	27.00 EACH
0169	805-01842	HANDHOLE SIGNAL TYPE 1	21.00 EACH
0170	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	35.00 EACH
0171	805-02445	CONTROLLER AND CABINET, P1	7.00 EACH
0172	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	23.00 EACH
0173	805-04133	SIGNAL POLE, PEDESTAL, 12FT	18.00 EACH
0174	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	596.00 LFT
0175	805-08244	CELLULAR MODEM KIT	7.00 EACH
0176	805-09845	CONTACT CLOSURE CARD	11.00 EACH
0177	805-09846	RECEIVER PROCESSOR	18.00 EACH
0178	805-10107	WIRELESS MAGNETOMETER DETECTOR	251.00 EACH
0179	805-10108	WIRELESS REPEATER	5.00 EACH
0180	805-11689	SIGNAL POLE, PEDESTAL, 20 FT	5.00 EACH
0181	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	1145.00 LFT
0182	805-11817	PEDESTRIAN PUSH BUTTON, APS	35.00 EACH
0183	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	43.00 EACH
0184	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	16.00 EACH
0185	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	9.00 EACH
0186	805-78415	SPAN, CATENARY, AND TETHER	27.00 EACH
0187	805-78420	DISCONNECT HANGER	27.00 EACH
0188	805-78445	SIGNAL SERVICE	7.00 EACH
0189	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	700.00 LFT
0190	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	6648.00 LFT
0191	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	10390.00 LFT
0192	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	2760.00 LFT
0193	805-78925	CONTROLLER CABINET FOUNDATION, P1	7.00 EACH
0194	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	16.00 EACH
0195	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	11.00 EACH
0196	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	648.00 LFT
0197	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1780.00 LFT
0198	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7880.00 LFT
0199	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	833.00 LFT
0200	808-06716	LINE, REMOVE	40040.00 LFT
0201	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS

0202	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	96.00	LFT
0203	808-11478	LINE, THERMOPLASTIC, DOTTED, WHITE, 8 IN.	117.00	LFT
0204	808-12032	GROOVING FOR PAVEMENT MARKINGS	47193.00	LFT
0205	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	394.00	LFT
0206	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	394.00	LFT
0207	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	740.00	LFT
0208	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	35055.00	LFT
0209	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	112.00	LFT
0210	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	1022.00	LFT
0211	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	2860.00	LFT
0212	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	64.00	EACH
0213	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	125.00	EACH

Call: 141

Contract: R -35191-B

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0010	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0012	203-02000	EXCAVATION, COMMON	890.00	CYS
	0013	203-51223	EXCAVATION, WATERWAY	635.00	CYS
	0014	205-12108	STORM WATER MANAGEMENT BUDGET	7300.00	DOL
	0015	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
	0016	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	100.00	CYS
	0017	207-08266	SUBGRADE TREATMENT, TYPE III	39.00	SYS
	0018	207-09895	SUBGRADE TREATMENT, TYPE V	2525.00	SYS
	0019	207-09935	SUBGRADE TREATMENT, TYPE IC	1262.00	SYS
	0020	211-06467	AGGREGATE FOR END BENT BACKFILL	30.00	CYS
	0021	301-12234	COMPACTED AGGREGATE NO 53	1949.00	CYS
	0022	406-05520	ASPHALT FOR TACK COAT	1.00	TON
	0023	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
	0024	502-06627	PCCP, 6 IN.	39.00	SYS

0025	601-03667	RAILING ORNAMENTAL	568.00	LFT
0026	603-06040	FENCE, FARM FIELD, 47 IN.	1708.00	LFT
0027	604-05528	HMA FOR SIDEWALK	332.00	TON
0028	604-08086	CURB RAMP, CONCRETE	14.00	SYS
0029	604-12083	DETECTABLE WARNING SURFACES	3.00	SYS
0030	616-06405	RIPRAP, REVETMENT	260.00	TON
0031	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	355.00	SYS
0032	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0033	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0034	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0035	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0036	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0037	621-02770	EROSION CONTROL BLANKET	163.00	SYS
0038	621-06545	FERTILIZER	0.30	TON
0039	621-06553	SEED MIXTURE R	29.00	LBS
0040	621-06565	MULCHING MATERIAL	0.50	TON
0041	628-09402	FIELD OFFICE, B	18.00	MOS
0042	628-09409	MOBILE INTERNET SERVICE	18.00	MOS
0043	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0044	628-11977	COMPUTER SYSTEM	1.00	EACH
0045	701-09558	TEST PILE, INDICATOR, PRODUCTION	85.00	LFT
0046	701-09560	TEST PILE, INDICATOR, RESTRIKE	1.00	EACH
0047	701-09679	CONICAL PILE TIP, 14 IN.	5.00	EACH
0048	701-09826	PILE, STEEL PIPE, 0.5 IN., 14 IN.	300.00	LFT
0049	702-51005	CONCRETE, A, SUBSTRUCTURE	53.60	CYS
0050	702-51863	FIELD DRILLED HOLE IN CONCRETE	138.00	EACH
0051	703-06029	REINFORCING BARS, EPOXY COATED	15440.00	LBS
0052	704-51002	CONCRETE, C, SUPERSTRUCTURE	76.00	CYS
0053	708-05394	REPAIR	1.00	LS
0054	708-05394	REPAIR	1.00	LS
0055	709-51821	SURFACE SEAL	1.00	LS
0056	709-51821	SURFACE SEAL	1.00	LS
0057	710-51870	REPOINTING MASONRY IN. STRUCTURES	880.00	SFT
0058	711-51038	STRUCTURAL STEEL	1.00	LS
0059	711-51038	STRUCTURAL STEEL	1.00	LS
0060	711-51823	EXPANSION ANCHOR 0.75 IN	44.00	EACH
0061	713-04331	TEMPORARY CAUSEWAY	1.00	LS
0062	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	490.00	LFT
0063	715-05407	PIPE, END BENT DRAIN, 6 IN.	60.00	LFT
0064	724-03855	EXPANSION JOINT SLIDING PLATE	30.00	LFT
0065	726-92406	BEARING ASSEMBLY ELASTOMERIC	4.00	EACH
0066	726-95870	BEARING ASSEMBLY, PTFE	4.00	EACH

0067	801-03290	CONSTRUCTION SIGN, C	4.00 EACH
0068	801-03291	CONSTRUCTION SIGN, D	6.00 EACH
0069	801-06640	CONSTRUCTION SIGN, A	4.00 EACH
0070	801-06645	CONSTRUCTION SIGN, B	2.00 EACH
0071	801-06775	MAINTAINING TRAFFIC	1.00 LS
0072	801-06775	MAINTAINING TRAFFIC	1.00 LS
0073	802-03896	BOLLARD	1.00 EACH
0074	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	14.00 LFT
0075	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	14.00 SFT
0076	802-11364	POST	34.00 LFT

Call: 151

Contract: R -36260-A

Section No.: 1 NEW ROAD CONSTRUCTION

Line			Quantity Unit
Item No	Item Code	Description	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-01261	TESTING FOR ASBESTOS	3.00 EACH
0014	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0015	202-91840	FENCE, CHAIN. LINK, REMOVE	1247.00 LFT
0016	203-02000	EXCAVATION, COMMON	133560.00 CYS
0017	203-02010	EXCAVATION, ROCK	36250.00 CYS
0018	203-02020	EXCAVATION, UNCLASSIFIED	42731.00 CYS
0019	203-02070	BORROW	13485.00 CYS
0020	204-08415	STAKE, SETTLEMENT	30.00 EACH
0021	205-12108	STORM WATER MANAGEMENT BUDGET	122400.00 DOL
0022	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00 LS
0023	206-51215	EXCAVATION, X	613.00 CYS
0024	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	591.00 CYS
0025	207-08264	SUBGRADE TREATMENT, TYPE II	3911.00 SYS
0026	207-09934	SUBGRADE TREATMENT, TYPE IB	40653.00 SYS

0027	207-09935	SUBGRADE TREATMENT, TYPE IC	7905.00	SYS
0028	211-06467	AGGREGATE FOR END BENT BACKFILL	161.00	CYS
0029	211-09264	STRUCTURE BACKFILL, TYPE 1	1607.00	CYS
0030	211-09268	STRUCTURE BACKFILL, TYPE 5	279.00	CYS
0031	214-12236	GEOTEXTILE FOR PAVEMENT TYPE 1A	41451.00	SYS
0032	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	4500.00	SYS
0033	215-11477	CHEMICAL STABILIZATION	4274.00	TON
0034	301-12232	COMPACTED AGGREGATE NO 5	202.00	CYS
0035	302-07455	DENSE GRADED SUBBASE	79.80	CYS
0036	401-06264	PROFILOGRAPH, HMA	1.00	LS
0037	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	1675.00	TON
0038	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	2877.00	TON
0039	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	3357.00	TON
0040	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	1010.00	TON
0041	401-10258	JOINT ADHESIVE, SURFACE	4056.00	LFT
0042	401-10259	JOINT ADHESIVE, INTERMEDIATE	4056.00	LFT
0043	401-11785	LIQUID ASPHALT SEALANT	4056.00	LFT
0044	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
0045	503-05310	TERMINAL JOINT	48.00	LFT
0046	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	4.00	EACH
0047	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	6075.00	LFT
0048	601-61390	GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE, GALVANIZED	1.00	EACH
0049	601-94689	GUARDRAIL, END TREATMENT, OS	5.00	EACH
0050	602-06729	BARRIER, DELINEATOR	30.00	EACH
0051	603-01932	FENCE, CHAIN LINK, 96 IN.	918.00	LFT
0052	603-02009	FENCE GATE, CHAIN LINK, 96 IN. X 20 FT	1.00	EACH
0053	605-06140	CURB AND GUTTER, CONCRETE	900.00	LFT
0054	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	1546.00	LFT
0055	605-06160	CURB AND GUTTER, B, CONCRETE, MODIFIED	69.00	LFT
0056	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	478.00	SYS
0057	610-08446	PCCP FOR APPROACHES, 6 IN.	406.00	SYS
0058	610-09108	PCCP FOR APPROACHES, 9 IN.	502.00	SYS
0059	611-06497	MAILBOX ASSEMBLY, SINGLE	11.00	EACH
0060	615-06490	RIGHT-OF-WAY MARKER	78.00	EACH
0061	615-06510	MONUMENT, C	4.00	EACH
0062	616-05688	RIPRAP, CLASS 1	2400.00	TON
0063	616-06405	RIPRAP, REVETMENT	2767.00	TON
0064	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	8723.00	SYS
0065	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0066	621-02770	EROSION CONTROL BLANKET	49846.00	SYS
0067	621-04258	SEED MIXTURE	16.00	LBS
0068	621-04258	SEED MIXTURE	12.00	LBS

0069	621-06545	FERTILIZER	9.00 TON
0070	621-06553	SEED MIXTURE R	4156.00 LBS
0071	621-06565	MULCHING MATERIAL	42.00 TON
0072	621-06567	WATER	402.00 kGAL
0073	621-06574	SODDING	2825.00 SYS
0074	622-52436	SIGN, DO NOT MOW OR SPRAY	8.00 EACH
0075	622-91786	SEEDLING	141.00 EACH
0076	622-98200	SIGN, DO NOT DISTURB	14.00 EACH
0077	624-92647	HERBICIDE TREATMENT	1.00 ACRE
0078	628-09403	FIELD OFFICE, C	30.00 MOS
0079	628-11976	COMPUTER SYSTEM EQUIPMENT	5.00 EACH
0080	628-11977	COMPUTER SYSTEM	2.00 EACH
0081	701-08253	PILE, SLEEVES	32.00 EACH
0082	701-09683	PILE SHOE, HP 12 X 74	32.00 EACH
0083	701-11645	CORED HOLE IN ROCK, 30 IN	224.00 LFT
0084	701-95780	PILE, STEEL H, HP 12 X 74	752.00 LFT
0085	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	5.00 EACH
0086	702-51005	CONCRETE, A, SUBSTRUCTURE	566.90 CYS
0087	702-51015	CONCRETE, B, FOOTINGS	383.80 CYS
0088	702-92857	CONCRETE, C, SUBSTRUCTURE	134.70 CYS
0089	703-06028	REINFORCING BARS	156474.00 LBS
0090	703-06029	REINFORCING BARS, EPOXY COATED	377996.00 LBS
0091	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	48.00 EACH
0092	704-51002	CONCRETE, C, SUPERSTRUCTURE	1061.70 CYS
0093	706-11601	RAILING, CONCRETE FT	118.80 CYS
0094	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	4.00 EACH
0095	707-06404	STRUCTURAL MEMBER, CONCRETE BULB-T BEAM,	2415.00 LFT
0096	709-51821	SURFACE SEAL	1.00 LS
0097	714-11173	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 3 FT.	54.00 LFT
0098	714-11186	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 12 FT. X 4 FT.	264.00 LFT
0099	714-11198	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 5 FT. X 3 FT.	71.00 LFT
0100	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	177.00 LFT
0101	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	13286.00 LFT
0102	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	191.00 LFT
0103	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	247.00 LFT
0104	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	585.00 LFT
0105	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	15.00 LFT
0106	715-05157	PIPE, TYPE 2, CIRCULAR, 33 IN.	150.00 LFT
0107	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	40.00 LFT
0108	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	121.00 LFT
0109	715-05407	PIPE, END BENT DRAIN, 6 IN.	200.00 LFT
0110	715-08048	STORMWATER TREATMENT SYSTEM	1.00 EACH

0111	715-08083	CONCRETE ANCHOR, MIN. AREA 58 SFT	2.00	EACH
0112	715-08657	PIPE, TYPE 1, DEFORMED, MIN. AREA 56.5 SFT	185.00	LFT
0113	715-09064	VIDEO INSPECTION FOR PIPE	1711.00	LFT
0114	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0115	715-46010	PIPE END SECTION, DIAMETER 18 IN.	9.00	EACH
0116	715-46040	PIPE END SECTION, DIAMETER 36 IN.	4.00	EACH
0117	718-06528	OUTLET PROTECTOR, 1	25.00	EACH
0118	718-06528	OUTLET PROTECTOR, 1	1.00	EACH
0119	718-06529	OUTLET PROTECTOR, 2	9.00	EACH
0120	718-06531	OUTLET PROTECTOR, 3	8.00	EACH
0121	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00	LFT
0122	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	247.00	SYS
0123	720-08239	MANHOLE, J7 MODIFIED	1.00	EACH
0124	720-45410	MANHOLE, C4	4.00	EACH
0125	720-98174	INLET, B15	2.00	EACH
0126	720-98555	INLET, C15	1.00	EACH
0127	720-99417	CATCH BASIN, C15	2.00	EACH
0128	801-04308	ROAD CLOSURE SIGN ASSEMBLY	13.00	EACH
0129	801-06625	DETOUR ROUTE MARKER ASSEMBLY	70.00	EACH
0130	801-06640	CONSTRUCTION SIGN, A	4.00	EACH
0131	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0132	801-06775	MAINTAINING TRAFFIC	1.00	LS
0133	801-07118	BARRICADE, III-A	216.00	LFT
0134	801-07119	BARRICADE, III-B	24.00	LFT
0135	801-07120	BARRICADE, III, PERMANENT	48.00	LFT
0136	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	487.00	LFT
0137	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	130.00	LFT
0138	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	128.00	SFT
0139	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	136.00	SFT
0140	804-06770	DELINEATOR POST	41.00	EACH
0141	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	232.00	EACH

Call: 151

Contract: R -36260-A

Section No.: 2 NEW ROAD CONSTRUCTION - HMA

Line	Item No	Item Code	Description	Quantity	Unit
	0142	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0143	301-12234	COMPACTED AGGREGATE NO 53	9431.00	CYS
	0144	303-01180	COMPACTED AGGREGATE NO. 53	9598.00	TON
	0145	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	1721.00	TON
	0146	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	2905.00	TON

0147	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	9601.00	TON
0148	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	3826.00	TON
0149	401-12439	VOID REDUCING ASPHALT MEMBRANE	43108.00	LFT
0150	406-05520	ASPHALT FOR TACK COAT	35.00	TON
0151	610-07487	HMA FOR APPROACHES, TYPE B	3086.00	TON
0152	615-06505	MONUMENT, B	38.00	EACH
0153	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	1126.00	LFT
0154	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	9594.00	SYS
0155	718-52610	AGGREGATE FOR UNDERDRAINS	1202.00	CYS
0156	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	16483.00	LFT
0157	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1152.00	LFT
0158	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1152.00	LFT
0159	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	16980.00	LFT
0160	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	79.00	LFT

Call: 151

Contract: R -36260-A

Section No.: 3 NEW ROAD CONSTRUCTION - PCCP

Line

Item No	Item Code	Description	Quantity	Unit
0161	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0162	301-12234	COMPACTED AGGREGATE NO 53	5929.00	CYS
0163	302-06464	SUBBASE FOR PCCP	5858.00	CYS
0164	303-01180	COMPACTED AGGREGATE NO. 53	9221.00	TON
0165	406-05520	ASPHALT FOR TACK COAT	11.00	TON
0166	501-08193	QC/QA-PCCP, 10.5 IN.	20756.00	SYS
0167	502-09531	PCCP	2677.00	SYS
0168	503-05240	D-1 CONTRACTION JOINT	11700.00	LFT
0169	610-07487	HMA FOR APPROACHES, TYPE B	858.00	TON
0170	615-06505	MONUMENT, B	18.00	EACH
0171	615-06515	MONUMENT, D	20.00	EACH
0172	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	1194.00	LFT
0173	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	9113.00	SYS
0174	718-52610	AGGREGATE FOR UNDERDRAINS	1082.00	CYS
0175	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2132.00	LFT
0176	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	15863.00	LFT
0177	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	15400.00	LFT
0178	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	60.00	LFT
0179	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2732.00	LFT
0180	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	19.00	LFT

Call: 161

Contract: R -37028-A

Section No.: 1

BIKE AND PEDESTRIAN FACILITIES

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0013	203-02000	EXCAVATION, COMMON	7670.00	CYS
	0014	203-02070	BORROW	2207.00	CYS
	0015	205-11626	PUMP AROUND	2.00	EACH
	0016	205-12108	STORM WATER MANAGEMENT BUDGET	63874.00	DOL
	0017	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
	0018	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	50.00	CYS
	0019	207-08264	SUBGRADE TREATMENT, TYPE II	693.00	SYS
	0020	207-08266	SUBGRADE TREATMENT, TYPE III	7090.00	SYS
	0021	207-09895	SUBGRADE TREATMENT, TYPE V	9410.00	SYS
	0022	211-06467	AGGREGATE FOR END BENT BACKFILL	64.00	CYS
	0023	211-09264	STRUCTURE BACKFILL, TYPE 1	78.00	CYS
	0024	301-12234	COMPACTED AGGREGATE NO 53	4542.00	CYS
	0025	302-07455	DENSE GRADED SUBBASE	27.00	CYS
	0026	303-01180	COMPACTED AGGREGATE NO. 53	1463.00	TON
	0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	3775.00	SYS
	0028	402-07451	HMA WEDGE AND LEVEL, TYPE B	73.00	TON
	0029	406-05520	ASPHALT FOR TACK COAT	7.00	TON
	0030	603-91714	FENCE, RAIL WOOD	472.00	LFT
	0031	603-92636	FENCE, CHAIN LINK, 72 IN.	752.00	LFT
	0032	604-01268	HAND RAIL ALUMINUM	236.00	LFT
	0033	604-05528	HMA FOR SIDEWALK	2477.00	TON
	0034	604-06070	SIDEWALK, CONCRETE	118.00	SYS
	0035	604-08086	CURB RAMP, CONCRETE	125.00	SYS
	0036	604-12083	DETECTABLE WARNING SURFACES	16.00	SYS
	0037	604-95344	HAND RAIL, PEDESTRIAN	1051.00	LFT
	0038	605-06120	CURB, CONCRETE	70.00	LFT

0039	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	52.00	SYS
0040	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	52.00	SYS
0041	610-07487	HMA FOR APPROACHES, TYPE B	191.00	TON
0042	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0043	616-05688	RIPRAP, CLASS 1	241.00	TON
0044	616-05689	RIPRAP, CLASS 2	252.00	TON
0045	616-06405	RIPRAP, REVETMENT	105.00	TON
0046	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	767.00	SYS
0047	618-03812	BENCH	24.00	EACH
0048	618-97672	TRASH RECEPTACLE	3.00	EACH
0049	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0050	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0051	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0052	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0053	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0054	621-06545	FERTILIZER	2.00	TON
0055	621-06554	SEED MIXTURE U	806.00	LBS
0056	621-06565	MULCHING MATERIAL	8.00	TON
0057	621-06567	WATER	7.00	KGAL
0058	621-06570	TOPSOIL	554.00	CYS
0059	621-06574	SODDING	1923.00	SYS
0060	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN.	1250.00	EACH
0061	628-09402	FIELD OFFICE, B	12.00	MOS
0062	628-09409	MOBILE INTERNET SERVICE	12.00	MOS
0063	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0064	628-11977	COMPUTER SYSTEM	1.00	EACH
0065	702-51863	FIELD DRILLED HOLE IN CONCRETE	104.00	EACH
0066	703-06029	REINFORCING BARS, EPOXY COATED	16017.00	LBS
0067	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	48.00	EACH
0068	704-51002	CONCRETE, C, SUPERSTRUCTURE	74.40	CYS
0069	708-51813	PNEUMATICALLY PLACED MORTAR	880.00	SFT
0070	708-51814	WELDED STEEL WIRE FABRIC	440.00	SFT
0071	709-07733	ANTI-GRAFFITI COAT	1.00	LS
0072	709-07733	ANTI-GRAFFITI COAT	1.00	LS
0073	709-51821	SURFACE SEAL	1.00	LS
0074	709-51821	SURFACE SEAL	1.00	LS
0075	711-51035	STRUCTURAL STEEL	1411.00	LBS
0076	711-51864	DRILLED HOLE	32.00	EACH
0077	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS
0078	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS
0079	711-95290	FIELD WELDING	16.00	LFT
0080	715-05032	PIPE, TYPE 2, CIRCULAR, 15 IN.	308.00	LFT

0081	715-05165	PIPE, TYPE 2, CIRCULAR, 72 IN.	92.00	LFT
0082	715-05407	PIPE, END BENT DRAIN, 6 IN.	164.00	LFT
0083	715-09064	VIDEO INSPECTION FOR PIPE	423.00	LFT
0084	715-46005	PIPE END SECTION, DIAMETER 15 IN.	3.00	EACH
0085	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	53.00	SYS
0086	720-45030	INLET, E7	1.00	EACH
0087	726-92406	BEARING ASSEMBLY ELASTOMERIC	8.00	EACH
0088	727-90308	EPOXY INJECTION, CRACK PREPARATION	236.00	LFT
0089	727-90309	EPOXY INJECTION, EPOXY MATERIAL	28.00	GAL
0090	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0091	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0092	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.00	EACH
0093	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	1.00	EACH
0094	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3063.00	LFT
0095	801-06640	CONSTRUCTION SIGN, A	11.00	EACH
0096	801-06775	MAINTAINING TRAFFIC	1.00	LS
0097	801-07118	BARRICADE, III-A	24.00	LFT
0098	802-04314	SIGN	127.00	EACH
0099	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	331.00	LFT
0100	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	60.00	LFT
0101	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	38.00	SFT
0102	805-06742	SOLAR POWERED FLASHING BEACON ASSEMBLY	6.00	EACH
0103	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	360.00	LFT
0104	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	356.00	LFT
0105	808-06716	LINE, REMOVE	838.00	LFT
0106	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2153.00	LFT

Call: 171

Contract: R -37497-A

Section No.: 1 ROAD RECONSTRUCTION

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	20.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS

0011	202-02240	PAVEMENT REMOVAL	34652.00	SYS
0012	202-02273	CENTER CURB, CONCRETE, REMOVE	316.00	SYS
0013	202-74035	SIGN, REMOVE	18.00	EACH
0014	202-74080	OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	3.00	EACH
0015	202-93763	LIGHT STANDARD AND FOUNDATION, REMOVE	2.00	EACH
0016	202-96022	CONCRETE FOUNDATION, REMOVE	5.00	EACH
0017	203-02000	EXCAVATION, COMMON	7317.00	CYS
0018	203-04523	DEWATERING	1.00	LS
0019	205-12108	STORM WATER MANAGEMENT BUDGET	44000.00	DOL
0020	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	963.00	SYS
0022	207-09934	SUBGRADE TREATMENT, TYPE IB	30153.00	SYS
0023	211-02050	B BORROW	3910.00	CYS
0024	211-09264	STRUCTURE BACKFILL, TYPE 1	330.00	CYS
0025	302-07455	DENSE GRADED SUBBASE	4696.00	CYS
0026	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	986.00	TON
0027	501-09749	QC/QA-PCCP, 9.5 IN.	24320.00	SYS
0028	503-05240	D-1 CONTRACTION JOINT	15922.00	LFT
0029	601-01128	GUARDRAIL, TRANSITION, TYPE WGB	1.00	EACH
0030	601-02241	GUARDRAIL, REMOVE	142.00	LFT
0031	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0032	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	100.00	LFT
0033	604-06070	SIDEWALK, CONCRETE	4357.00	SYS
0034	604-08086	CURB RAMP, CONCRETE	237.00	SYS
0035	604-12083	DETECTABLE WARNING SURFACES	27.00	SYS
0036	605-02278	CURB, REMOVE	11236.00	LFT
0037	605-06090	CURB, INTEGRAL CONCRETE	10198.00	LFT
0038	605-06250	CENTER CURB, C CONCRETE	321.00	SYS
0039	610-09108	PCCP FOR APPROACHES, 9 IN.	981.00	SYS
0040	610-09253	PCCP FOR APPROACHES, 9.5 IN.	2333.00	SYS
0041	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0042	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0043	621-06545	FERTILIZER	6.00	TON
0044	621-06554	SEED MIXTURE U	570.00	LBS
0045	621-06565	MULCHING MATERIAL	2.00	TON
0046	621-06570	TOPSOIL	1531.00	CYS
0047	621-98038	MULCH HARDWOOD SHREDDED BARK	53.00	CYS
0048	622-05646	PLANT, DECIDUOUS TREE, MULTI-STEM, 96 TO 120 IN.	19.00	EACH
0049	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN.	118.00	EACH
0050	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	7.00	EACH
0051	628-09401	FIELD OFFICE, A	15.00	MOS
0052	702-51010	CONCRETE, B, ABOVE FOOTINGS	6.00	CYS

0053	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1253.00	LFT
0054	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	8.00	LFT
0055	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	135.00	LFT
0056	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	83.00	LFT
0057	715-08250	PIPE DUCTILE IRON 12 IN.	97.00	LFT
0058	715-94530	ADJUST WATER VALVE TO GRADE	8.00	EACH
0059	720-01092	MANHOLE, J15 MODIFIED	36.00	EACH
0060	720-08241	MANHOLE, K15 MODIFIED	1.00	EACH
0061	720-44000	CASTING, ADJUST TO GRADE	4.00	EACH
0062	720-44015	CASTING, 2, FURNISH AND ADJUST TO GRADE	9.00	EACH
0063	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	10.00	EACH
0064	720-44080	CASTING, 15, FURNISH AND ADJUST TO GRADE	13.00	EACH
0065	720-90129	MANHOLE, J2	2.00	EACH
0066	720-98136	FIRE HYDRANT, RESET	1.00	EACH
0067	720-98174	INLET, B15	1.00	EACH
0068	720-98555	INLET, C15	5.00	EACH
0069	801-03290	CONSTRUCTION SIGN, C	1.00	EACH
0070	801-03291	CONSTRUCTION SIGN, D	2.00	EACH
0071	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0072	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	9826.00	LFT
0073	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	16798.00	LFT
0074	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	2.00	EACH
0075	801-06212	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (ONLY)	2.00	EACH
0076	801-06625	DETOUR ROUTE MARKER ASSEMBLY	34.00	EACH
0077	801-06640	CONSTRUCTION SIGN, A	62.00	EACH
0078	801-06645	CONSTRUCTION SIGN, B	27.00	EACH
0079	801-06710	FLASHING ARROW SIGN	540.00	DAY
0080	801-06775	MAINTAINING TRAFFIC	1.00	LS
0081	801-07119	BARRICADE, III-B	168.00	LFT
0082	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0083	801-94295	SIGNAL HEAD RELOCATE	2.00	EACH
0084	802-05705	SIGN POST, SQUARE TYPE 2 UNREINFORCED ANCHOR BASE	330.50	LFT
0085	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0086	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	219.00	SFT
0087	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.00	EACH
0088	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0089	805-01842	HANDHOLE SIGNAL TYPE 1	5.00	EACH
0090	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	4.00	EACH
0091	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	3.00	EACH
0092	805-04133	SIGNAL POLE, PEDESTAL, 12FT	3.00	EACH
0093	805-06595	CONDUIT, PVC, 2 IN.	965.00	LFT
0094	805-11378	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 40 FT.	1.00	EACH

0095	805-11384	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, B	1.00 EACH
0096	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	1.00 EACH
0097	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	3.00 EACH
0098	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	4.00 EACH
0099	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	5038.00 LFT
0100	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	780.00 LFT
0101	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	876.00 LFT
0102	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	656.00 LFT
0103	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	1172.00 LFT
0104	805-78785	SIGNAL DETECTOR HOUSING	10.00 EACH
0105	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1639.00 LFT
0106	807-02370	LIGHT STRUCTURE, REMOVE AND RESET	2.00 EACH
0107	807-11981	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. DIA X 96 IN.	2.00 EACH
0108	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	32.00 SYS
0109	808-06716	LINE, REMOVE	272.00 LFT
0110	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	111.00 LFT
0111	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	12568.00 LFT
0112	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	9348.00 LFT
0113	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	1503.00 LFT
0114	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	170.00 LFT
0115	808-10039	LINE, MULTI-COMPONENT, SOLID, WHITE, 12 IN.	69.00 LFT
0116	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	673.00 LFT
0117	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	495.00 LFT
0118	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	15.00 EACH
0119	808-10058	LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN.	2456.00 LFT
0120	808-10059	LINE, MULTI-COMPONENT, SOLID, YELLOW, 12 IN.	1251.00 LFT
0121	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	41.00 EACH
0122	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	158.00 EACH

Call: 181

Contract: R -37562-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL

0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0014	202-74035	SIGN, REMOVE	10.00	EACH
0015	202-99187	FENCE, FARM FIELD, REMOVE	413.00	LFT
0016	203-02000	EXCAVATION, COMMON	2441.00	CYS
0017	203-02070	BORROW	3807.00	CYS
0018	205-11626	PUMP AROUND	1.00	EACH
0019	205-12108	STORM WATER MANAGEMENT BUDGET	38886.50	DOL
0020	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	180.00	SYS
0022	207-09934	SUBGRADE TREATMENT, TYPE IB	5331.00	SYS
0023	211-09264	STRUCTURE BACKFILL, TYPE 1	285.00	CYS
0024	211-09265	STRUCTURE BACKFILL, TYPE 2	575.00	CYS
0025	211-09268	STRUCTURE BACKFILL, TYPE 5	880.00	CYS
0026	301-12234	COMPACTED AGGREGATE NO 53	1715.00	CYS
0027	302-07455	DENSE GRADED SUBBASE	2.80	CYS
0028	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	8.00	TON
0029	304-07493	WIDENING WITH HMA, TYPE B	204.00	TON
0030	306-08036	MILLING, ASPHALT, 2 IN.	714.00	SYS
0031	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	491.00	TON
0032	401-07397	QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	458.00	TON
0033	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	1279.00	TON
0034	401-10258	JOINT ADHESIVE, SURFACE	900.00	LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	1600.00	LFT
0036	401-11785	LIQUID ASPHALT SEALANT	1600.00	LFT
0037	406-05520	ASPHALT FOR TACK COAT	4.00	TON
0038	502-11564	PCCP, 7 IN.	266.00	SYS
0039	503-05240	D-1 CONTRACTION JOINT	110.00	LFT
0040	604-06070	SIDEWALK, CONCRETE	719.00	SYS
0041	604-08086	CURB RAMP, CONCRETE	154.00	SYS
0042	604-12083	DETECTABLE WARNING SURFACES	36.00	SYS
0043	604-95344	HAND RAIL, PEDESTRIAN	86.00	LFT
0044	605-01870	CURB, CONCRETE A	436.00	LFT
0045	605-06090	CURB, INTEGRAL CONCRETE	151.00	LFT
0046	605-06140	CURB AND GUTTER, CONCRETE	1667.00	LFT
0047	605-06145	CURB AND GUTTER, B, CONCRETE	201.00	LFT
0048	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	15.00	LFT
0049	610-08446	PCCP FOR APPROACHES, 6 IN.	180.00	SYS
0050	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH

0051	615-06490	RIGHT-OF-WAY MARKER	12.00 EACH
0052	615-06505	MONUMENT, B	4.00 EACH
0053	615-06520	MONUMENT, RE-ESTABLISH	1.00 EACH
0054	616-05688	RIPRAP, CLASS 1	762.00 TON
0055	616-06405	RIPRAP, REVETMENT	48.00 TON
0056	616-06451	RIPRAP, UNIFORM	77.00 TON
0057	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	833.00 SYS
0058	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	638.00 SYS
0059	621-06575	SODDING, NURSERY	4129.00 SYS
0060	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	4.00 EACH
0061	628-09402	FIELD OFFICE, B	12.00 MOS
0062	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0063	628-11977	COMPUTER SYSTEM	1.00 EACH
0064	702-90915	CONCRETE, CLASS, A	11.00 CYS
0065	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	85.00 LFT
0066	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	434.00 LFT
0067	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	68.00 LFT
0068	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	57.00 LFT
0069	715-05153	PIPE, TYPE 2, CIRCULAR, 21 IN.	166.00 LFT
0070	715-05408	PIPE, SANITARY SEWER, 8 IN.	93.00 LFT
0071	715-08283	PCCP FOR STRUCTURE INSTALLATION	17.00 SYS
0072	715-09064	VIDEO INSPECTION FOR PIPE	810.00 LFT
0073	715-09475	STORMWATER QUALITY STRUCTURE	2.00 EACH
0074	715-11879	SEWER, SANITARY LATERAL, CONNECTIONS	12.00 LFT
0075	715-46000	PIPE END SECTION, DIAMETER 12 IN.	5.00 EACH
0076	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00 EACH
0077	715-46015	PIPE END SECTION, DIAMETER 21 IN.	1.00 EACH
0078	715-46040	PIPE END SECTION, DIAMETER 36 IN.	2.00 EACH
0079	720-03194	MANHOLE	2.00 EACH
0080	720-03194	MANHOLE	1.00 EACH
0081	720-45030	INLET, E7	1.00 EACH
0082	720-45035	INLET, F7	1.00 EACH
0083	720-45042	INLET, HA5	1.00 EACH
0084	720-45410	MANHOLE, C4	3.00 EACH
0085	720-93409	INLET, B15 MODIFIED	4.00 EACH
0086	720-93411	INLET, C15 MODIFIED	4.00 EACH
0087	720-98174	INLET, B15	1.00 EACH
0088	720-98555	INLET, C15	4.00 EACH
0089	723-12332	STRUCTURE COATED REINFORCED CONCRETE 3-SIDED SECTION 216 IN. X 72 IN.	181.00 LFT
0090	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00 EACH
0091	801-06625	DETOUR ROUTE MARKER ASSEMBLY	71.00 EACH
0092	801-06640	CONSTRUCTION SIGN, A	14.00 EACH

0093	801-07118	BARRICADE, III-A	96.00	LFT
0094	801-07119	BARRICADE, III-B	108.00	LFT
0095	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	323.00	LFT
0096	802-05706	SIGN POST, SQUARE TYPE 3 UNREINFORCED ANCHOR BASE	64.00	LFT
0097	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	131.00	SFT
0098	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	96.00	SFT
0099	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	42.00	SFT
0100	807-90714	PIPE PVC 4 IN	245.00	LFT
0101	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	320.00	LFT
0102	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	52.00	LFT
0103	808-11698	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 27 IN.	41.00	LFT
0104	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	326.00	LFT
0105	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2151.00	LFT
0106	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	67.00	EACH

Call: 201

Contract: R -38048-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	203-02000	EXCAVATION, COMMON	5302.00	CYS
0013	203-02070	BORROW	2719.00	CYS
0014	205-12108	STORM WATER MANAGEMENT BUDGET	41516.00	DOL
0015	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0016	207-08264	SUBGRADE TREATMENT, TYPE II	206.00	SYS
0017	207-09934	SUBGRADE TREATMENT, TYPE IB	10626.00	SYS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	518.00	SYS
0019	211-09264	STRUCTURE BACKFILL, TYPE 1	6.00	CYS
0020	211-09265	STRUCTURE BACKFILL, TYPE 2	252.00	CYS
0021	301-12234	COMPACTED AGGREGATE NO 53	1412.00	CYS
0022	304-07493	WIDENING WITH HMA, TYPE B	80.00	TON

0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	661.00	SYS
0024	306-08036	MILLING, ASPHALT, 2 IN.	2970.00	SYS
0025	306-08432	MILLING, APPROACH	178.00	SYS
0026	401-07345	QC/QA-HMA, 2, 70, SURFACE, 12.5 mm	472.00	TON
0027	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	761.00	TON
0028	401-07397	QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	522.00	TON
0029	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	508.00	TON
0030	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	712.00	TON
0031	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	731.00	TON
0032	401-10258	JOINT ADHESIVE, SURFACE	4151.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	2701.00	LFT
0034	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	1013.00	TON
0035	406-05521	ASPHALT FOR TACK COAT	26045.00	SYS
0036	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
0037	502-06999	PCCP, 8 IN.	383.00	SYS
0038	502-11564	PCCP, 7 IN.	264.00	SYS
0039	604-06070	SIDEWALK, CONCRETE	540.00	SYS
0040	604-08086	CURB RAMP, CONCRETE	254.00	SYS
0041	604-12083	DETECTABLE WARNING SURFACES	65.00	SYS
0042	605-06120	CURB, CONCRETE	337.00	LFT
0043	605-06140	CURB AND GUTTER, CONCRETE	2371.00	LFT
0044	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	1061.00	LFT
0045	605-06255	CENTER CURB, D CONCRETE	458.00	SYS
0046	605-52807	CURB AND GUTTER, COMBINED	2008.00	LFT
0047	610-07487	HMA FOR APPROACHES, TYPE B	28.00	TON
0048	610-08446	PCCP FOR APPROACHES, 6 IN.	191.00	SYS
0049	611-06497	MAILBOX ASSEMBLY, SINGLE	8.00	EACH
0050	615-06490	RIGHT-OF-WAY MARKER	32.00	EACH
0051	615-06505	MONUMENT, B	8.00	EACH
0052	615-06527	MONUMENT, SECTION CORNER	2.00	EACH
0053	616-06405	RIPRAP, REVETMENT	352.00	TON
0054	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	708.00	SYS
0055	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0056	621-06560	MULCHED SEEDING U	6786.00	SYS
0057	621-06575	SODDING, NURSERY	803.00	SYS
0058	628-09402	FIELD OFFICE, B	12.00	MOS
0059	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0060	628-11977	COMPUTER SYSTEM	1.00	EACH
0061	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	1192.00	LFT
0062	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	109.00	LFT
0063	715-05118	PIPE, TYPE 1, CIRCULAR, 12 IN.	105.00	LFT
0064	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	243.00	LFT

0065	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	361.00	LFT
0066	715-46000	PIPE END SECTION, DIAMETER 12 IN.	10.00	EACH
0067	715-46010	PIPE END SECTION, DIAMETER 18 IN.	3.00	EACH
0068	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	1005.00	SYS
0069	718-52610	AGGREGATE FOR UNDERDRAINS	104.00	CYS
0070	720-08239	MANHOLE, J7 MODIFIED	1.00	EACH
0071	720-95422	MANHOLE, J4	2.00	EACH
0072	720-98174	INLET, B15	2.00	EACH
0073	720-98555	INLET, C15	1.00	EACH
0074	801-04308	ROAD CLOSURE SIGN ASSEMBLY	18.00	EACH
0075	801-06625	DETOUR ROUTE MARKER ASSEMBLY	85.00	EACH
0076	801-06640	CONSTRUCTION SIGN, A	45.00	EACH
0077	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0078	801-06775	MAINTAINING TRAFFIC	1.00	LS
0079	801-07118	BARRICADE, III-A	192.00	LFT
0080	801-07119	BARRICADE, III-B	240.00	LFT
0081	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	507.00	LFT
0082	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	136.00	LFT
0083	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	223.00	SFT
0084	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	169.00	SFT
0085	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	34.00	SFT
0086	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	525.00	LFT
0087	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	626.00	LFT
0088	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1752.00	LFT
0089	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	81.00	LFT
0090	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	103.00	LFT
0091	808-11698	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 27 IN.	130.00	LFT
0092	808-12032	GROOVING FOR PAVEMENT MARKINGS	5369.00	LFT
0093	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	1.00	EACH
0094	808-75073	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, ONLY	1.00	EACH
0095	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5136.00	LFT
0096	808-75256	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 8 IN.	179.00	LFT
0097	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	73.00	EACH

Call: 211

Contract: R -38146-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL

0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-02245	TREE 6 IN., REMOVE	61.00	EACH
0009	201-02250	TREE 10 IN., REMOVE	60.00	EACH
0010	201-02255	TREE 18 IN., REMOVE	77.00	EACH
0011	201-02260	TREE 30 IN., REMOVE	17.00	EACH
0012	201-02265	TREE 48 IN., REMOVE	3.00	EACH
0013	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0014	202-02278	CURB, CONCRETE, REMOVE	87.00	LFT
0015	202-52710	SIDEWALK CONCRETE, REMOVE	1322.00	SYS
0016	202-96133	PIPE, REMOVE	276.00	LFT
0017	203-02000	EXCAVATION, COMMON	1322.00	CYS
0018	205-12108	STORM WATER MANAGEMENT BUDGET	25300.00	DOL
0019	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	277.00	SYS
0021	207-08266	SUBGRADE TREATMENT, TYPE III	5836.00	SYS
0022	211-09264	STRUCTURE BACKFILL, TYPE 1	117.00	CYS
0023	211-09267	STRUCTURE BACKFILL, TYPE 4	4.00	CYS
0024	301-12234	COMPACTED AGGREGATE NO 53	1862.00	CYS
0025	304-07490	HMA PATCHING, TYPE B	55.00	TON
0026	306-08034	MILLING, ASPHALT, 1 1/2 IN.	303.00	SYS
0027	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0028	604-05528	HMA FOR SIDEWALK	1087.00	TON
0029	604-06070	SIDEWALK, CONCRETE	2.00	SYS
0030	604-08086	CURB RAMP, CONCRETE	202.00	SYS
0031	604-12083	DETECTABLE WARNING SURFACES	43.00	SYS
0032	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	681.00	LFT
0033	610-07487	HMA FOR APPROACHES, TYPE B	609.00	TON
0034	610-08446	PCCP FOR APPROACHES, 6 IN.	358.00	SYS
0035	611-06497	MAILBOX ASSEMBLY, SINGLE	4.00	EACH
0036	616-06405	RIPRAP, REVETMENT	5.00	TON
0037	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	17.00	SYS
0038	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0039	621-06560	MULCHED SEEDING U	2291.00	SYS
0040	621-06567	WATER	10.00	kGAL
0041	621-06575	SODDING, NURSERY	2320.00	SYS
0042	622-05651	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	210.00	EACH
0043	628-09402	FIELD OFFICE, B	6.00	MOS
0044	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1180.00	LFT
0045	715-46000	PIPE END SECTION, DIAMETER 12 IN.	5.00	EACH

0046	715-91742	WATER METER RELOCATE	1.00 EACH
0047	720-45030	INLET, E7	2.00 EACH
0048	720-45035	INLET, F7	6.00 EACH
0049	720-45045	INLET, J10	2.00 EACH
0050	720-45055	INLET, M10	1.00 EACH
0051	720-45410	MANHOLE, C4	3.00 EACH
0052	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00 EACH
0053	801-06640	CONSTRUCTION SIGN, A	19.00 EACH
0054	801-06645	CONSTRUCTION SIGN, B	2.00 EACH
0055	801-06775	MAINTAINING TRAFFIC	1.00 LS
0056	801-07119	BARRICADE, III-B	48.00 LFT
0057	802-03896	BOLLARD	1.00 EACH
0058	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	174.00 LFT
0059	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	19.00 LFT
0060	802-07060	SIGN, SHEET, RELOCATE	5.00 EACH
0061	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	81.00 SFT

Call: 221

Contract: R -38604-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0012	202-02240	PAVEMENT REMOVAL	444.00	SYS
	0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0014	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0015	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0016	202-93741	GUARDRAIL, END TREATMENT, REMOVE	1.00	EACH
	0017	203-02000	EXCAVATION, COMMON	379.00	CYS
	0018	203-02070	BORROW	197.00	CYS
	0019	205-11626	PUMP AROUND	3.00	EACH
	0020	205-12108	STORM WATER MANAGEMENT BUDGET	10871.00	DOL

0021	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	903.00	SYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	1476.00	CYS
0024	211-09268	STRUCTURE BACKFILL, TYPE 5	197.00	CYS
0025	301-12234	COMPACTED AGGREGATE NO 53	10.00	CYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	135.00	TON
0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	746.00	SYS
0028	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	7.00	TON
0029	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	138.00	TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	12.00	TON
0031	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	105.00	TON
0032	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	341.00	TON
0033	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	14.00	TON
0034	401-10258	JOINT ADHESIVE, SURFACE	1230.00	LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	630.00	LFT
0036	401-11785	LIQUID ASPHALT SEALANT	1230.00	LFT
0037	406-05521	ASPHALT FOR TACK COAT	2292.00	SYS
0038	601-02241	GUARDRAIL, REMOVE	575.00	LFT
0039	601-06035	GUARDRAIL, RESET	200.00	LFT
0040	601-06854	GUARDRAIL, W-BEAM, NESTED	4.00	EACH
0041	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	37.50	LFT
0042	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00	EACH
0043	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0044	615-06490	RIGHT-OF-WAY MARKER	9.00	EACH
0045	615-06505	MONUMENT, B	5.00	EACH
0046	615-06530	BENCH MARK POST	1.00	EACH
0047	616-05688	RIPRAP, CLASS 1	61.00	TON
0048	616-06405	RIPRAP, REVETMENT	725.00	TON
0049	616-06451	RIPRAP, UNIFORM	13.00	TON
0050	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1328.00	SYS
0051	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0052	621-06559	MULCHED SEEDING R	540.00	SYS
0053	621-06567	WATER	3.00	KGAL
0054	621-06575	SODDING, NURSERY	626.00	SYS
0055	628-09402	FIELD OFFICE, B	8.00	MOS
0056	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0057	714-11116	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 13 FT. X 8 FT.	70.00	LFT
0058	714-11445	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 16 FT. X 10 FT.	44.00	LFT
0059	715-05049	PIPE, TYPE 4, CIRCULAR, 8 IN.	20.00	LFT
0060	715-05052	PIPE, TYPE 4, CIRCULAR, 12 IN.	20.00	LFT
0061	715-06939	CONCRETE ANCHOR, MIN. AREA 29.5 SFT	2.00	EACH
0062	715-09992	PIPE, TYPE 1, DEFORMED, MIN. AREA 29.5 SFT	195.00	LFT

0063	801-04308	ROAD CLOSURE SIGN ASSEMBLY	20.00 EACH
0064	801-06625	DETOUR ROUTE MARKER ASSEMBLY	71.00 EACH
0065	801-06640	CONSTRUCTION SIGN, A	71.00 EACH
0066	801-06775	MAINTAINING TRAFFIC	1.00 LS
0067	801-07118	BARRICADE, III-A	300.00 LFT
0068	801-07119	BARRICADE, III-B	180.00 LFT
0069	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	11.00 LFT
0070	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	6.25 SFT
0071	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	862.00 LFT
0072	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	670.00 LFT
0073	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	20.00 LFT
0074	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	10.00 EACH
0075	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	10.00 EACH

Call: 241

Contract: R -39970-A

Section No.: 1 ENVIRONMENTAL MITIGATION

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	201-01015	CLEARING AND GRUBBING	1.00	LS
	0009	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00	LS
	0010	203-02000	EXCAVATION, COMMON	5481.00	CYS
	0011	204-12510	MONITORING WELL	3.00	EACH
	0012	205-12108	STORM WATER MANAGEMENT BUDGET	31885.00	DOL
	0013	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
	0014	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	2.60	CYS
	0015	616-05689	RIPRAP, CLASS 2	8913.00	TON
	0016	616-06396	RIPRAP	6275.00	TON
	0017	616-06405	RIPRAP, REVETMENT	345.00	TON
	0018	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	540.00	SYS
	0019	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
	0020	621-02770	EROSION CONTROL BLANKET	17625.00	SYS
	0021	621-04258	SEED MIXTURE	646.10	LBS
	0022	621-04258	SEED MIXTURE	69.50	LBS
	0023	621-04258	SEED MIXTURE	219.00	LBS

0024	621-04258	SEED MIXTURE	4483.20	LBS
0025	621-04258	SEED MIXTURE	256.50	LBS
0026	621-06545	FERTILIZER	1.20	TON
0027	621-06565	MULCHING MATERIAL	40.00	TON
0028	621-06737	SEED MIXTURE, EMERGENT WETLAND	200.00	LBS
0029	621-08161	PERMANENT TURF REINFORCEMENT MAT	312.00	SYS
0030	621-09508	INVASIVE SPECIES CONTROL	1.00	LS
0031	622-05641	PLANT, DECIDUOUS SHRUB, 36 TO 48 IN.	852.00	EACH
0032	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	6392.00	EACH
0033	622-05654	PLANT, PERENNIAL	1100.00	EACH
0034	622-10003	LIVE PLANT STAKING	2905.00	EACH
0035	622-10003	LIVE PLANT STAKING	2820.00	EACH
0036	622-10003	LIVE PLANT STAKING	5355.00	EACH
0037	622-91786	SEEDLING	44064.00	EACH
0038	622-98200	SIGN, DO NOT DISTURB	44.00	EACH
0039	624-92647	HERBICIDE TREATMENT	124.20	ACRE
0040	628-09402	FIELD OFFICE, B	24.00	MOS
0041	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0042	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0043	628-11783	CELLULAR TELEPHONE SERVICE, 2000 MIN.	24.00	MOS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0045	628-11977	COMPUTER SYSTEM	1.00	EACH
0046	712-04784	STRUCTURE	2.00	EACH
0047	712-99107	LOG DEFLECTOR	25.00	EACH
0048	713-04643	TEMPORARY ACCESS LANE	1.00	LS
0049	715-05147	PIPE, TYPE 2, CIRCULAR, 8 IN.	26.00	LFT
0050	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	72.00	LFT
0051	719-09505	TILE INTERCEPT TRENCH EXCAVATION AND LOCATION	4500.00	LFT
0052	801-06640	CONSTRUCTION SIGN, A	2.00	EACH
0053	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	6.00	SFT
0054	802-11648	SIGN POST	2.00	EACH
0055	804-06770	DELINEATOR POST	138.00	EACH

Call: 261

Contract: R -41934-A

Section No.: 1 DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-04299	FORCE ACCOUNT WORK	139000.00	DOL
	0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0004	109-08360	CONTRACT LIENS	1.00	DOL

0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	202-04890	WELL	21.00	EACH
0009	202-05823	UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE, UNDER 3000 GALLONS CAPACITY	12.00	EACH
0010	202-06541	REMOVE	1.00	EACH
0011	202-06541	REMOVE	21.00	EACH
0012	202-08192	UNDERGROUND STORAGE TANK, LIQUID WASTE DISPOSAL, C	3600.00	GAL
0013	202-12410	HOUSES AND BUILDINGS SMALL REMOVE	10.00	EACH
0014	202-12411	HOUSES AND BUILDINGS MEDIUM REMOVE	5.00	EACH
0015	202-12412	HOUSES AND BUILDINGS LARGE REMOVE	7.00	EACH
0016	202-12414	OUTBUILDING SMALL REMOVE	36.00	EACH
0017	202-12415	OUTBUILDING MEDIUM REMOVE	11.00	EACH
0018	202-12416	OUTBUILDING LARGE REMOVE	6.00	EACH
0019	205-12108	STORM WATER MANAGEMENT BUDGET	93340.00	DOL
0020	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS

Call: 271

Contract: R -41935-A

Section No.: 1 DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-04299	FORCE ACCOUNT WORK	21375.00	DOL
	0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0004	109-08360	CONTRACT LIENS	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0008	202-04890	WELL	3.00	EACH
	0009	202-05825	UNDERGROUND STORAGE TANK, REMOVE AND DISPOSE, 6,000-10,000 GALLONS CAPACITY	3.00	EACH
	0010	202-06541	REMOVE	5.00	EACH
	0011	202-06580	CONTAMINATED SOIL, REMOVE	550.00	CYS
	0012	202-08192	UNDERGROUND STORAGE TANK, LIQUID WASTE DISPOSAL, C	24000.00	GAL
	0013	202-12413	COMMERCIAL BUILDING REMOVE PARCEL NO	1.00	LS
	0014	202-12413	COMMERCIAL BUILDING REMOVE PARCEL NO	1.00	LS
	0015	202-12413	COMMERCIAL BUILDING REMOVE PARCEL NO	1.00	LS
	0016	202-12413	COMMERCIAL BUILDING REMOVE PARCEL NO	1.00	LS
	0017	202-12413	COMMERCIAL BUILDING REMOVE PARCEL NO	1.00	LS
	0018	205-12108	STORM WATER MANAGEMENT BUDGET	38455.00	DOL
	0019	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
	0020	801-06640	CONSTRUCTION SIGN, A	10.00	EACH

0021 801-07118 BARRICADE, III-A

564.00 LFT

Call: 281

Contract: R -41970-A

Section No.: 1 ROADSIDE MAINTENANCE, TREE REMOVAL/TRIMMING

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	201-01015	CLEARING AND GRUBBING	1.00	LS
0008	201-02245	TREE 6 IN., REMOVE	17.00	EACH
0009	201-02250	TREE 10 IN., REMOVE	11.00	EACH
0010	201-02255	TREE 18 IN., REMOVE	20.00	EACH
0011	201-02260	TREE 30 IN., REMOVE	1.00	EACH
0012	201-02265	TREE 48 IN., REMOVE	2.00	EACH
0013	201-06587	CLEARING AND GRUBBING	2.20	ACRE
0014	801-06640	CONSTRUCTION SIGN, A	6.00	EACH
0015	801-06710	FLASHING ARROW SIGN	31.00	DAY
0016	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 285

Contract: R -42024-B

Section No.: 1 PATCH AND REHAB PAVEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	207-09935	SUBGRADE TREATMENT, TYPE IC	2071.00	SYS
0010	302-07455	DENSE GRADED SUBBASE	420.00	CYS
0011	304-07491	HMA PATCHING, TYPE C	1485.00	TON
0012	406-05520	ASPHALT FOR TACK COAT	4.00	TON
0013	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	6.00	TON
0014	503-03489	RETROFITTED TIE BARS	315.00	EACH

0015	503-05240	D-1 CONTRACTION JOINT	1068.00	LFT
0016	506-06333	PCCP PATCHING, FULL DEPTH	1680.00	SYS
0017	507-12191	JOINT REPAIR, PARTIAL DEPTH	100.00	SFT
0018	801-06640	CONSTRUCTION SIGN, A	57.00	EACH
0019	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0020	801-06710	FLASHING ARROW SIGN	208.00	DAY
0021	801-06775	MAINTAINING TRAFFIC	1.00	LS
0022	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	9127.00	LFT
0023	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	5130.00	LFT
0024	808-06702	LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	411.00	LFT
0025	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4491.00	LFT
0026	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	998.00	LFT
0027	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	200.00	LFT
0028	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	50.00	LFT
0029	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	315.00	LFT
0030	808-12032	GROOVING FOR PAVEMENT MARKINGS	9962.00	LFT
0031	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3497.00	LFT
0032	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	60.00	EACH
0033	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	60.00	EACH

Call: 291

Contract: RS-39151-B

Section No.: 1 ASPHALT RESURFACE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	207-09935	SUBGRADE TREATMENT, TYPE IC	794.00	SYS
	0011	303-01180	COMPACTED AGGREGATE NO. 53	1100.00	TON
	0012	304-07491	HMA PATCHING, TYPE C	750.00	TON
	0013	306-08034	MILLING, ASPHALT, 1 1/2 IN.	52967.00	SYS
	0014	306-08043	MILLING, TRANSITION	500.00	SYS
	0015	306-08432	MILLING, APPROACH	5335.00	SYS
	0016	401-06264	PROFILOGRAPH, HMA	1.00	LS
	0017	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	4730.00	TON

0018	401-10258	JOINT ADHESIVE, SURFACE	15637.00	LFT
0019	401-11785	LIQUID ASPHALT SEALANT	15637.00	LFT
0020	402-07452	HMA WEDGE AND LEVEL, TYPE C	50.00	TON
0021	406-05520	ASPHALT FOR TACK COAT	16.00	TON
0022	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	5.00	TON
0023	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	15637.00	LFT
0024	610-07488	HMA FOR APPROACHES, TYPE C	532.00	TON
0025	628-09403	FIELD OFFICE, C	6.00	MOS
0026	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0027	702-90915	CONCRETE, CLASS, A	5.00	CYS
0028	703-06029	REINFORCING BARS, EPOXY COATED	38.00	LBS
0029	720-44000	CASTING, ADJUST TO GRADE	5.00	EACH
0030	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0031	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	3909.00	LFT
0032	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3909.00	LFT
0033	801-06640	CONSTRUCTION SIGN, A	36.00	EACH
0034	801-06775	MAINTAINING TRAFFIC	1.00	LS
0035	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0036	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	32793.00	LFT
0037	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	450.00	LFT
0038	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0039	808-12032	GROOVING FOR PAVEMENT MARKINGS	64242.00	LFT
0040	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	4395.00	LFT
0041	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	15450.00	LFT
0042	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	177.00	LFT
0043	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	291.00	LFT
0044	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	58.00	LFT
0045	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	11.00	EACH
0046	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	427.00	EACH
0047	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	427.00	EACH
0048	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	1026.00	LFT

Call: 301

Contract: RS-40585-A

Section No.: 1 ASPHALT RESURFACE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL

0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	303-01180	COMPACTED AGGREGATE NO. 53	884.00	TON
0011	304-07783	HMA PATCHING, TYPE D	462.00	TON
0012	306-08034	MILLING, ASPHALT, 1 1/2 IN.	74182.00	SYS
0013	306-08432	MILLING, APPROACH	2001.00	SYS
0014	401-06264	PROFILOGRAPH, HMA	1.00	LS
0015	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	6121.00	TON
0016	401-10258	JOINT ADHESIVE, SURFACE	19818.00	LFT
0017	401-10259	JOINT ADHESIVE, INTERMEDIATE	4921.00	LFT
0018	401-11785	LIQUID ASPHALT SEALANT	19818.00	LFT
0019	406-05520	ASPHALT FOR TACK COAT	19.00	TON
0020	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	4.00	TON
0021	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	49300.00	LFT
0022	610-07788	HMA FOR APPROACHES, TYPE D	158.00	TON
0023	628-09402	FIELD OFFICE, B	6.00	MOS
0024	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0025	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	6409.00	LFT
0026	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6409.00	LFT
0027	801-06640	CONSTRUCTION SIGN, A	22.00	EACH
0028	801-06710	FLASHING ARROW SIGN	90.00	DAY
0029	801-06775	MAINTAINING TRAFFIC	1.00	LS
0030	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	2049.00	LFT
0031	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	40361.00	LFT
0032	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0033	808-12032	GROOVING FOR PAVEMENT MARKINGS	67324.00	LFT
0034	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	2220.00	LFT
0035	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	22694.00	LFT
0036	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	18.00	LFT
0037	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	573.00	EACH
0038	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	573.00	EACH

Call: 311

Contract: RS-41823-A

Section No.: 1 ASPHALT RESURFACE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL

0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	202-90277	DETECTOR HOUSING, REMOVE	4.00	EACH
0011	207-08264	SUBGRADE TREATMENT, TYPE II	272.00	SYS
0012	211-09268	STRUCTURE BACKFILL, TYPE 5	113.00	CYS
0013	301-12234	COMPACTED AGGREGATE NO 53	18.00	CYS
0014	303-07449	COMPACTED AGGREGATE NO. 73	723.00	TON
0015	304-07491	HMA PATCHING, TYPE C	85.00	TON
0016	304-07491	HMA PATCHING, TYPE C	666.00	TON
0017	304-07491	HMA PATCHING, TYPE C	444.00	TON
0018	304-07783	HMA PATCHING, TYPE D	30.00	TON
0019	306-08034	MILLING, ASPHALT, 1 1/2 IN.	103493.00	SYS
0020	306-08036	MILLING, ASPHALT, 2 IN.	164218.00	SYS
0021	306-08432	MILLING, APPROACH	10056.00	SYS
0022	401-06264	PROFILOGRAPH, HMA	1.00	LS
0023	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	26221.00	TON
0024	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	384.00	TON
0025	401-10258	JOINT ADHESIVE, SURFACE	102858.00	LFT
0026	401-11785	LIQUID ASPHALT SEALANT	296256.00	LFT
0027	406-05520	ASPHALT FOR TACK COAT	72.00	TON
0028	604-06070	SIDEWALK, CONCRETE	3.00	SYS
0029	604-08086	CURB RAMP, CONCRETE	5.00	SYS
0030	604-12083	DETECTABLE WARNING SURFACES	3.00	SYS
0031	605-06120	CURB, CONCRETE	22.00	LFT
0032	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	220982.00	LFT
0033	610-07487	HMA FOR APPROACHES, TYPE B	799.00	TON
0034	610-07488	HMA FOR APPROACHES, TYPE C	315.00	TON
0035	611-08232	MAILBOX ASSEMBLY, SINGLE RESET	19.00	EACH
0036	615-06505	MONUMENT, B	5.00	EACH
0037	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0038	616-06405	RIPRAP, REVETMENT	9.00	TON
0039	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	15.00	SYS
0040	628-09402	FIELD OFFICE, B	12.00	MOS
0041	715-03475	SAFETY METAL END SECTION, 4:1, DIA 15 IN.	6.00	EACH
0042	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	165.00	LFT
0043	715-46005	PIPE END SECTION, DIAMETER 15 IN.	6.00	EACH
0044	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	9624.00	LFT
0045	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9624.00	LFT

0046	801-06640	CONSTRUCTION SIGN, A	88.00	EACH
0047	801-06775	MAINTAINING TRAFFIC	1.00	LS
0048	801-92448	CONSTRUCTION SIGNS MOBILE	100.00	DAY
0049	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	1244.00	LFT
0050	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	300.00	LFT
0051	805-78785	SIGNAL DETECTOR HOUSING	4.00	EACH
0052	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	414.00	LFT
0053	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	50.00	LFT
0054	808-06694	LINE, PAINT, SOLID, YELLOW, 8 IN.	200.00	LFT
0055	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	720.00	LFT
0056	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	17920.00	LFT
0057	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	157418.00	LFT
0058	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	26112.00	LFT
0059	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0060	808-75008	LINE, PAINT, SOLID, WHITE, 8 IN.	240.00	LFT
0061	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	100.00	LFT
0062	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	72.00	LFT
0063	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	162.00	LFT
0064	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	98.00	LFT
0065	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	9.00	EACH
0066	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1340.00	EACH

Call: 315

Contract: RS-41992-B

Section No.: 1 ASPHALT RESURFACE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	207-08264	SUBGRADE TREATMENT, TYPE II	701.00	SYS
0011	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	100.00	CYS
0012	304-07783	HMA PATCHING, TYPE D	111.00	TON
0013	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0014	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	5.00	TON
0015	506-06333	PCCP PATCHING, FULL DEPTH	701.00	SYS

0016	628-09403	FIELD OFFICE, C	6.00	MOS
0017	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0018	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0019	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	17000.00	LFT
0020	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	8500.00	LFT
0021	801-06640	CONSTRUCTION SIGN, A	48.00	EACH
0022	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0023	801-06710	FLASHING ARROW SIGN	60.00	DAY
0024	801-06775	MAINTAINING TRAFFIC	1.00	LS
0025	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	5500.00	LFT
0026	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	9.00	EACH
0027	801-12042	TRUCK MOUNTED ATTENUATOR	160.00	DAY
0028	801-12324	LAW ENFORCEMENT OFFICER	500.00	HRS
0029	801-92448	CONSTRUCTION SIGNS MOBILE	100.00	DAY
0030	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1000.00	LFT
0031	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1500.00	LFT
0032	808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	400.00	LFT
0033	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	50.00	EACH
0034	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	50.00	EACH

Call: 321

Contract: RS-41998-A

Section No.: 1 INSTITUTION AND PARK ROAD MAINTENANCE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	207-09935	SUBGRADE TREATMENT, TYPE IC	151.00	SYS
	0010	303-01180	COMPACTED AGGREGATE NO. 53	42.00	TON
	0011	304-07490	HMA PATCHING, TYPE B	50.00	TON
	0012	306-08034	MILLING, ASPHALT, 1 1/2 IN.	692.00	SYS
	0013	306-08042	MILLING, SCARIFICATION	30226.00	SYS
	0014	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2551.00	TON
	0015	401-10258	JOINT ADHESIVE, SURFACE	18215.00	LFT
	0016	404-10137	SEAL COAT, 2P	42741.00	SYS
	0017	406-05520	ASPHALT FOR TACK COAT	8.00	TON

0018	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.00	TON
0019	412-09355	FOG SEAL	42741.00	SYS
0020	615-11537	PARKING BARRIER, CONCRETE	15.00	EACH
0021	615-97768	PARKING BARRIER, RESET	284.00	EACH
0022	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0023	801-06640	CONSTRUCTION SIGN, A	3.00	EACH
0024	801-06775	MAINTAINING TRAFFIC	1.00	LS
0025	802-03821	SIGN, SHEET, WITH LEGEND,	9.00	EACH
0026	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	63.00	LFT
0027	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	812.00	LFT
0028	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	972.00	LFT
0029	808-12274	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, BLUE 4 IN.	605.00	LFT
0030	808-97664	PAVEMENT MESSAGE MARKING, THERMOPLASTIC HANDICAP SYMBOL	9.00	EACH

Call: 331

Contract: RS-42146-A

Section No.: 1 PATCHING AND REHAB PAVEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	207-09935	SUBGRADE TREATMENT, TYPE IC	1197.00	SYS
	0010	207-12151	SUBGRADE TREATMENT, TYPE IVA	475.00	SYS
	0011	304-07491	HMA PATCHING, TYPE C	5658.00	TON
	0012	306-08036	MILLING, ASPHALT, 2 IN.	2533.00	SYS
	0013	306-08041	MILLING, PCCP	13089.00	SYS
	0014	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	1718.00	TON
	0015	401-10258	JOINT ADHESIVE, SURFACE	3700.00	LFT
	0016	401-11785	LIQUID ASPHALT SEALANT	3700.00	LFT
	0017	406-05520	ASPHALT FOR TACK COAT	15.00	TON
	0018	628-09402	FIELD OFFICE, B	10.00	MOS
	0019	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
	0020	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	44.00	EACH
	0021	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9270.00	LFT
	0022	801-06640	CONSTRUCTION SIGN, A	188.00	EACH
	0023	801-06710	FLASHING ARROW SIGN	60.00	DAY

0024	801-06775	MAINTAINING TRAFFIC	1.00	LS
0025	801-12042	TRUCK MOUNTED ATTENUATOR	140.00	DAY
0026	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	500.00	LFT
0027	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	200.00	LFT
0028	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	2100.00	LFT
0029	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	30775.00	LFT
0030	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	11555.00	LFT
0031	808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	1000.00	LFT
0032	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	72.00	LFT
0033	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	3.00	EACH
0034	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	1.00	EACH
0035	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	208.00	EACH
0036	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	218.00	EACH

Call: 341

Contract: RS-42162-A

Section No.: 1 ASPHALT RESURFACE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	203-02000	EXCAVATION, COMMON	75.00	CYS
	0010	207-08264	SUBGRADE TREATMENT, TYPE II	1100.00	SYS
	0011	207-08266	SUBGRADE TREATMENT, TYPE III	1800.00	SYS
	0012	303-01180	COMPACTED AGGREGATE NO. 53	50.00	TON
	0013	304-07490	HMA PATCHING, TYPE B	160.00	TON
	0014	306-08033	MILLING, ASPHALT, 1 IN.	10100.00	SYS
	0015	306-08034	MILLING, ASPHALT, 1 1/2 IN.	17000.00	SYS
	0016	306-11553	MILLING, ASPHALT, 3/4 IN.	1800.00	SYS
	0017	401-07339	QC/QA-HMA, 2, 64, SURFACE, 12.5 mm	3223.00	TON
	0018	401-10258	JOINT ADHESIVE, SURFACE	3000.00	LFT
	0019	401-11785	LIQUID ASPHALT SEALANT	3000.00	LFT
	0020	406-05520	ASPHALT FOR TACK COAT	10.00	TON
	0021	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
	0022	605-01870	CURB, CONCRETE A	40.00	LFT
	0023	605-02278	CURB, REMOVE	40.00	LFT

0024	615-11537	PARKING BARRIER, CONCRETE	10.00 EACH
0025	615-97768	PARKING BARRIER, RESET	175.00 EACH
0026	628-09403	FIELD OFFICE, C	6.00 MOS
0027	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0028	801-06640	CONSTRUCTION SIGN, A	4.00 EACH
0029	801-06775	MAINTAINING TRAFFIC	1.00 LS
0030	802-91122	SIGN GROUND MOUNTED RESET	2.00 EACH
0031	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	15.00 EACH
0032	808-09314	LINE, PAINT, SOLID, BLUE, 4 IN.	350.00 LFT
0033	808-12316	TRANSVERSE MARKING, PAINT, PARKING LINE, WHITE 4"	6500.00 LFT
0034	808-97222	PAVEMENT MESSAGE MARKING, PAINT, HANDICAP SYMBOL	8.00 EACH

Call: 421

Contract: B -37638-B

Section No.: 1 BRIDGE REHABILITATION OR REPAIR

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0009	202-11501	SHORING	1.00	LS
	0010	205-12108	STORM WATER MANAGEMENT BUDGET	16500.00	DOL
	0011	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
	0012	615-08351	PLAQUE	1.00	EACH
	0013	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
	0014	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
	0015	628-09401	FIELD OFFICE, A	12.00	MOS
	0016	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
	0017	628-11977	COMPUTER SYSTEM	1.00	EACH
	0018	708-05394	REPAIR	1.00	LS
	0019	708-05394	REPAIR	1.00	LS
	0020	708-05394	REPAIR	1.00	LS
	0021	708-05394	REPAIR	1.00	LS
	0022	708-05394	REPAIR	1.00	LS
	0023	708-05394	REPAIR	1.00	LS
	0024	708-05394	REPAIR	1.00	LS
	0025	708-05394	REPAIR	1.00	LS

0026	711-01772	RETROFIT	2.00 EACH
0027	711-05396	REPLACE	1.00 LS
0028	711-05396	REPLACE	1.00 LS
0029	712-11616	STONE ABUTMENT REPAIR	1.00 LS
0030	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00 EACH
0031	801-06625	DETOUR ROUTE MARKER ASSEMBLY	49.00 EACH
0032	801-06640	CONSTRUCTION SIGN, A	8.00 EACH
0033	801-06775	MAINTAINING TRAFFIC	1.00 LS
0034	801-07118	BARRICADE, III-A	48.00 LFT
0035	802-04314	SIGN	2.00 EACH

Call: 431

Contract: B -38041-A

Section No.: 1 BRIDGE REHABILITATION

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0012	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
	0013	202-02278	CURB, CONCRETE, REMOVE	1003.00	LFT
	0014	202-02279	CURB AND GUTTER, REMOVE	29.00	LFT
	0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0016	202-52710	SIDEWALK CONCRETE, REMOVE	775.00	SYS
	0017	203-02000	EXCAVATION, COMMON	259.00	CYS
	0018	205-06933	TEMPORARY INLET PROTECTION	4.00	EACH
	0019	205-12108	STORM WATER MANAGEMENT BUDGET	25000.00	DOL
	0020	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
	0021	206-51225	EXCAVATION, DRY	3763.00	CYS
	0022	206-51235	COFFERDAM	1.00	LS
	0023	207-09935	SUBGRADE TREATMENT, TYPE IC	621.00	SYS
	0024	211-09264	STRUCTURE BACKFILL, TYPE 1	9.00	CYS
	0025	211-09266	STRUCTURE BACKFILL, TYPE 3	3336.00	CYS
	0026	302-07455	DENSE GRADED SUBBASE	66.00	CYS

0027	303-01180	COMPACTED AGGREGATE NO. 53	242.00 TON
0028	306-08043	MILLING, TRANSITION	193.00 SYS
0029	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	63.00 TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	78.00 TON
0031	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	156.00 TON
0032	401-10258	JOINT ADHESIVE, SURFACE	506.00 LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	423.00 LFT
0034	401-11785	LIQUID ASPHALT SEALANT	506.00 LFT
0035	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0036	502-06457	PCCP, 9 IN.	101.00 SYS
0037	502-06627	PCCP, 6 IN.	60.00 SYS
0038	604-06070	SIDEWALK, CONCRETE	556.00 SYS
0039	605-06090	CURB, INTEGRAL CONCRETE	689.00 LFT
0040	605-06120	CURB, CONCRETE	324.00 LFT
0041	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	393.00 SYS
0042	616-05688	RIPRAP, CLASS 1	1437.00 TON
0043	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	1018.00 SYS
0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0045	621-06560	MULCHED SEEDING U	1000.00 SYS
0046	628-09402	FIELD OFFICE, B	12.00 MOS
0047	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0048	628-11977	COMPUTER SYSTEM	1.00 EACH
0049	702-02925	WATERPROOFING MEMBRANE SYSTEM	17323.00 SFT
0050	702-51005	CONCRETE, A, SUBSTRUCTURE	63.80 CYS
0051	702-51863	FIELD DRILLED HOLE IN CONCRETE	1608.00 EACH
0052	703-06029	REINFORCING BARS, EPOXY COATED	156385.00 LBS
0053	703-08247	EMBEDDED GALVANIC ANODE	4924.00 EACH
0054	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	44.00 EACH
0055	704-51002	CONCRETE, C, SUPERSTRUCTURE	373.10 CYS
0056	708-51813	PNEUMATICALLY PLACED MORTAR	21450.00 SFT
0057	708-51814	WELDED STEEL WIRE FABRIC	13000.00 SFT
0058	709-51821	SURFACE SEAL	1.00 LS
0059	710-09158	PATCHING CONCRETE STRUCTURES	1500.00 SFT
0060	713-04331	TEMPORARY CAUSEWAY	1.00 LS
0061	715-01354	CLEAN EXISTING PIPE	120.00 LFT
0062	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	59.00 LFT
0063	720-45042	INLET, HA5	2.00 EACH
0064	720-45410	MANHOLE, C4	1.00 EACH
0065	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00 EACH
0066	801-06625	DETOUR ROUTE MARKER ASSEMBLY	21.00 EACH
0067	801-06640	CONSTRUCTION SIGN, A	8.00 EACH
0068	801-06645	CONSTRUCTION SIGN, B	2.00 EACH

0069	801-06775	MAINTAINING TRAFFIC	1.00	LS
0070	801-07118	BARRICADE, III-A	144.00	LFT
0071	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	33.00	LFT
0072	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	27.00	SFT
0073	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	264.00	LFT
0074	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1056.00	LFT

Call: 441

Contract: B -38352-C

Section No.: 1 BRIDGE REHABILITATION

Line

Item No	Item Code	Description	Quantity	Unit
1	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
10	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
11	202-02240	PAVEMENT REMOVAL	219.00	SYS
12	202-02279	CURB AND GUTTER, REMOVE	20.00	LFT
13	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
14	202-52710	SIDEWALK CONCRETE, REMOVE	15.00	SYS
15	202-95027	IMPACT ATTENUATOR, REMOVE	1.00	EACH
16	203-02000	EXCAVATION, COMMON	178.00	CYS
17	205-12108	STORM WATER MANAGEMENT BUDGET	5706.00	DOL
18	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
19	211-06467	AGGREGATE FOR END BENT BACKFILL	88.00	CYS
2	109-08359	LIQUIDATED DAMAGES	1.00	DOL
20	302-07455	DENSE GRADED SUBBASE	37.00	CYS
21	304-07783	HMA PATCHING, TYPE D	30.00	TON
22	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	5.00	TON
23	601-06035	GUARDRAIL, RESET	75.00	LFT
24	601-06238	IMPACT ATTENUATOR, R1-W1, TL-3	1.00	EACH
25	604-02007	SIDEWALK, CONCRETE, RECONSTRUCT	42.00	SYS
26	605-06140	CURB AND GUTTER, CONCRETE	20.00	LFT
27	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	219.00	SYS
28	616-06405	RIPRAP, REVETMENT	20.00	TON
29	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	17.00	SYS
3	109-08360	CONTRACT LIENS	1.00	DOL
30	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	17.00	SYS
31	621-06574	SODDING	17.00	SYS
32	628-09403	FIELD OFFICE, C	12.00	MOS
33	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
34	703-06029	REINFORCING BARS, EPOXY COATED	28850.00	LBS
35	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	308.00	EACH
36	704-51002	CONCRETE, C, SUPERSTRUCTURE	111.00	CYS

37	709-51821	SURFACE SEAL	1.00	LS
38	709-51821	SURFACE SEAL	1.00	LS
39	715-05407	PIPE, END BENT DRAIN, 6 IN.	102.00	LFT
4	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
40	715-06566	PIPE EXTENSION, CIRCULAR, 6 IN.	30.00	LFT
41	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	52.00	SYS
42	722-01066	HYDRODEMOLITION	1378.00	SYS
43	722-12380	BRIDGE DECK OVERLAY, BUDGET	21050.00	DOL
44	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	1357.00	SYS
45	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	1221.00	SFT
46	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1357.00	SYS
47	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	209.00	SFT
48	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	2857.00	SYS
49	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
5	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
50	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	11053.00	LFT
51	801-06625	DETOUR ROUTE MARKER ASSEMBLY	29.00	EACH
52	801-06640	CONSTRUCTION SIGN, A	55.00	EACH
53	801-06645	CONSTRUCTION SIGN, B	31.00	EACH
54	801-06710	FLASHING ARROW SIGN	208.00	DAY
55	801-06775	MAINTAINING TRAFFIC	1.00	LS
56	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	EACH
57	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	800.00	LFT
58	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
59	801-12042	TRUCK MOUNTED ATTENUATOR	28.00	DAY
6	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
60	805-01744	LOOP RESEAL	1.00	EACH
61	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	50.00	LFT
62	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	50.00	LFT
63	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1460.00	LFT
64	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2000.00	LFT
65	808-06716	LINE, REMOVE	5320.00	LFT
66	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	2.00	EACH
67	808-06724	PAVEMENT MESSAGE MARKING, PAINT, ONLY	1.00	EACH
68	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	244.00	LFT
69	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1856.00	LFT
7	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
70	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	976.00	LFT
71	808-12032	GROOVING FOR PAVEMENT MARKINGS	1060.00	LFT
72	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	26.00	EACH
73	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	26.00	EACH
74	808-95933	CURB, PAINTING, YELLOW	976.00	LFT

8	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
9	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL

Call: 451

Contract: B -38678-A

Section No.: 1 BRIDGE DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	202-02240	PAVEMENT REMOVAL	160.00	SYS
	0012	203-02000	EXCAVATION, COMMON	85.00	CYS
	0013	205-12108	STORM WATER MANAGEMENT BUDGET	10000.00	DOL
	0014	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
	0015	207-09935	SUBGRADE TREATMENT, TYPE IC	382.00	SYS
	0016	302-07455	DENSE GRADED SUBBASE	28.00	CYS
	0017	303-01180	COMPACTED AGGREGATE NO. 53	65.00	TON
	0018	306-08043	MILLING, TRANSITION	2484.00	SYS
	0019	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	256.00	TON
	0020	401-10258	JOINT ADHESIVE, SURFACE	2306.00	LFT
	0021	401-11785	LIQUID ASPHALT SEALANT	2306.00	LFT
	0022	402-10086	HMA FOR TEMPORARY PAVEMENT, C	288.00	TON
	0023	406-05521	ASPHALT FOR TACK COAT	3479.00	SYS
	0024	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
	0025	502-08203	PCCP, 11.5 IN.	160.00	SYS
	0026	503-03489	RETROFITTED TIE BARS	140.00	EACH
	0027	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	144.00	LFT
	0028	616-06405	RIPRAP, REVETMENT	108.00	TON
	0029	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	197.00	SYS
	0030	628-09403	FIELD OFFICE, C	12.00	MOS
	0031	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
	0032	709-51821	SURFACE SEAL	1.00	LS
	0033	722-01066	HYDRODEMOLITION	3775.00	SYS
	0034	722-12380	BRIDGE DECK OVERLAY, BUDGET	73920.00	DOL

0035	722-12382	TRANSVERSE GROOVING	3775.00	SYS
0036	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	3775.00	SYS
0037	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	100.00	SFT
0038	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6924.00	LFT
0039	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	62.00	LFT
0040	801-06640	CONSTRUCTION SIGN, A	42.00	EACH
0041	801-06645	CONSTRUCTION SIGN, B	20.00	EACH
0042	801-06710	FLASHING ARROW SIGN	240.00	DAY
0043	801-06775	MAINTAINING TRAFFIC	1.00	LS
0044	801-07118	BARRICADE, III-A	48.00	LFT
0045	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1213.00	LFT
0046	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	2153.00	LFT
0047	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1643.00	LFT
0048	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1564.00	LFT
0049	808-06716	LINE, REMOVE	962.00	LFT
0050	808-12032	GROOVING FOR PAVEMENT MARKINGS	1610.00	LFT
0051	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	31.00	EACH
0052	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	31.00	EACH

Call: 451

Contract: B -38678-A

Section No.: 2 LATEX CONCRETE MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0053	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	3775.00	SYS

Call: 451

Contract: B -38678-A

Section No.: 3 SILICA FUME CONCRETE MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0054	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	3775.00	SYS

Call: 461

Contract: B -39805-A

Section No.: 1 BRIDGE REPLACEMENT, PAINTING AND PIPE LINING

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL

0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	356.00	SYS
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0014	203-02000	EXCAVATION, COMMON	649.00	CYS
0015	205-12108	STORM WATER MANAGEMENT BUDGET	19379.00	DOL
0016	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0017	206-51235	COFFERDAM	1.00	LS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	1839.00	SYS
0019	207-12151	SUBGRADE TREATMENT, TYPE IVA	217.00	SYS
0020	211-02050	B BORROW	74.00	CYS
0021	211-09265	STRUCTURE BACKFILL, TYPE 2	1051.00	CYS
0022	301-12233	COMPACTED AGGREGATE NO 8	1.00	CYS
0023	301-12234	COMPACTED AGGREGATE NO 53	49.00	CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	56.00	TON
0025	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	76.00	TON
0026	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	127.00	TON
0027	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	405.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	1491.00	LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	1491.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	1491.00	LFT
0031	402-10086	HMA FOR TEMPORARY PAVEMENT, C	289.00	TON
0032	406-05521	ASPHALT FOR TACK COAT	4955.00	SYS
0033	601-02241	GUARDRAIL, REMOVE	125.00	LFT
0034	601-06854	GUARDRAIL, W-BEAM, NESTED	1.00	EACH
0035	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	25.00	LFT
0036	615-06505	MONUMENT, B	2.00	EACH
0037	616-05688	RIPRAP, CLASS 1	108.00	TON
0038	616-06405	RIPRAP, REVETMENT	504.00	TON
0039	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	70.00	SYS
0040	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	125.00	SYS
0041	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	450.00	SYS
0042	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0043	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0045	621-02356	SEEDING WETLAND	7.00	LBS
0046	621-02770	EROSION CONTROL BLANKET	418.00	SYS
0047	621-03909	SEED MIXTURE, NATIVE	18.00	LBS

0048	621-06553	SEED MIXTURE R	1.50	LBS
0049	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0050	702-04325	TEMPORARY SHORING	1.00	LS
0051	702-51046	CONCRETE, FOUNDATION SEAL	18.50	CYS
0052	723-11346	STRUCTURE, REINFORCED CONCRETE, THREE-SIDED SECTIONS, 336 IN. X 120 IN.	96.00	LFT
0053	725-10245	PERPETUATION, EXISTING PIPE	1.00	EACH
0054	725-11294	PIPE LINER, CURED-IN-PLACE, MIN AREA 6.5 SFT	306.00	LFT
0055	725-11861	PIPE LINER, CURED-IN-PLACE, MIN AREA 11.4 SFT	150.00	LFT
0056	725-12063	PIPE LINER, CURED-IN-PLACE, MIN AREA 14.7 SFT	51.00	LFT
0057	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0058	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0059	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5922.00	LFT
0060	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVEABLE, 24 IN.	24.00	LFT
0061	801-06625	DETOUR ROUTE MARKER ASSEMBLY	30.00	EACH
0062	801-06640	CONSTRUCTION SIGN, A	68.00	EACH
0063	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0064	801-06775	MAINTAINING TRAFFIC	1.00	LS
0065	801-07118	BARRICADE, III-A	72.00	LFT
0066	801-07119	BARRICADE, III-B	48.00	LFT
0067	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	249.00	LFT
0068	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0069	804-11920	DELINEATOR POST FLEXIBLE, TYPE I	6.00	EACH
0070	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	275.00	LFT
0071	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1794.00	LFT
0072	808-06716	LINE, REMOVE	2069.00	LFT
0073	808-75994	PRISMATIC REFLECTOR	14.00	EACH
0074	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2.00	EACH

Call: 471

Contract: B -39892-A

Section No.: 1 REPLACE SUPERSTRUCTURE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
	0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL

0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	1725.00	SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-90277	DETECTOR HOUSING, REMOVE	1.00	EACH
0017	203-02000	EXCAVATION, COMMON	670.00	CYS
0018	205-12108	STORM WATER MANAGEMENT BUDGET	7000.00	DOL
0019	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0020	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	70.00	CYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	3620.00	SYS
0022	211-06467	AGGREGATE FOR END BENT BACKFILL	64.00	CYS
0023	302-06464	SUBBASE FOR PCCP	448.00	CYS
0024	302-07455	DENSE GRADED SUBBASE	252.00	CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	204.00	TON
0026	304-07494	WIDENING WITH HMA, TYPE C	85.00	TON
0027	306-08043	MILLING, TRANSITION	669.00	SYS
0028	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	53.00	TON
0029	401-10258	JOINT ADHESIVE, SURFACE	644.00	LFT
0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	344.00	LFT
0031	401-11785	LIQUID ASPHALT SEALANT	644.00	LFT
0032	406-05521	ASPHALT FOR TACK COAT	777.00	SYS
0033	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
0034	502-06329	PCCP, 12 IN.	760.00	SYS
0035	503-03489	RETROFITTED TIE BARS	174.00	EACH
0036	503-05240	D-1 CONTRACTION JOINT	580.00	LFT
0037	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	628.20	SYS
0038	503-12478	TERMINAL JOINT, TYPE PCCP	136.00	SYS
0039	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	144.00	LFT
0040	506-06333	PCCP PATCHING, FULL DEPTH	1512.00	SYS
0041	507-12191	JOINT REPAIR, PARTIAL DEPTH	10828.00	SFT
0042	507-12192	JOINT REPAIR, BOTTOM-HALF	300.00	SFT
0043	601-02241	GUARDRAIL, REMOVE	575.00	LFT
0044	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	87.50	LFT
0045	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	200.00	LFT
0046	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	2.00	EACH
0047	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	5.00	EACH
0048	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0049	601-94690	GUARDRAIL, END TREATMENT, MS	2.00	EACH
0050	602-06729	BARRIER, DELINEATOR	24.00	EACH
0051	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	451.40	SYS

0052	616-06405	RIPRAP, REVETMENT	162.00 TON
0053	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	300.00 SYS
0054	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00 EACH
0055	621-06560	MULCHED SEEDING U	1700.00 SYS
0056	621-06567	WATER	0.60 KGAL
0057	621-06574	SODDING	106.00 SYS
0058	628-09403	FIELD OFFICE, C	16.00 MOS
0059	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0060	702-51005	CONCRETE, A, SUBSTRUCTURE	105.00 CYS
0061	702-92857	CONCRETE, C, SUBSTRUCTURE	103.60 CYS
0062	703-06028	REINFORCING BARS	8694.00 LBS
0063	703-06029	REINFORCING BARS, EPOXY COATED	207284.00 LBS
0064	703-08247	EMBEDDED GALVANIC ANODE	300.00 EACH
0065	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	1860.00 EACH
0066	704-51002	CONCRETE, C, SUPERSTRUCTURE	366.20 CYS
0067	706-09960	RAILING, CONCRETE FC	704.00 LFT
0068	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00 EACH
0069	707-11443	STRUCTURAL MEMBER, CONCRETE, BOX BEAM, 17 IN. X 36 IN.	2042.00 LFT
0070	709-51821	SURFACE SEAL	1.00 LS
0071	709-51821	SURFACE SEAL	1.00 LS
0072	710-09158	PATCHING CONCRETE STRUCTURES	950.00 SFT
0073	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	310.00 LFT
0074	715-05407	PIPE, END BENT DRAIN, 6 IN.	252.00 LFT
0075	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	432.00 SYS
0076	718-52610	AGGREGATE FOR UNDERDRAINS	22.00 CYS
0077	727-90308	EPOXY INJECTION, CRACK PREPARATION	180.00 LFT
0078	727-90309	EPOXY INJECTION, EPOXY MATERIAL	18.00 GAL
0079	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00 LS
0080	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00 LS
0081	801-02595	CONTROLLER RESET TIMING	4.00 EACH
0082	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	16732.00 LFT
0083	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	4.00 EACH
0084	801-06640	CONSTRUCTION SIGN, A	49.00 EACH
0085	801-06645	CONSTRUCTION SIGN, B	19.00 EACH
0086	801-06710	FLASHING ARROW SIGN	150.00 DAY
0087	801-06775	MAINTAINING TRAFFIC	1.00 LS
0088	801-07118	BARRICADE, III-A	132.00 LFT
0089	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	460.00 LFT
0090	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	860.00 LFT
0091	801-94295	SIGNAL HEAD RELOCATE	4.00 EACH
0092	802-04089	SIGN, SHEET, REMOVE	17.00 EACH
0093	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	8.00 SFT

0094	802-91122	SIGN GROUND MOUNTED RESET	17.00 EACH
0095	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.00 EACH
0096	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	86.00 LFT
0097	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	3.00 EACH
0098	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	2776.00 LFT
0099	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	155.00 LFT
0100	805-78785	SIGNAL DETECTOR HOUSING	2.00 EACH
0101	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	694.00 LFT
0102	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	850.00 LFT
0103	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4310.00 LFT
0104	808-06716	LINE, REMOVE	3550.00 LFT
0105	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	25.00 EACH
0106	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	245.00 LFT
0107	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0108	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	880.00 LFT
0109	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	7100.00 LFT
0110	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	4900.00 LFT
0111	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	192.00 LFT
0112	808-12032	GROOVING FOR PAVEMENT MARKINGS	23595.00 LFT
0113	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5310.00 LFT
0114	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	100.00 EACH

Call: 481

Contract: B -40057-A

Section No.: 1 BRIDGE PAINTING

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	619-11051	CLEAN STEEL BRIDGE, QP-1, BRIDGE NO.	1.00	LS
0009	619-11051	CLEAN STEEL BRIDGE, QP-1, BRIDGE NO.	1.00	LS
0010	619-11051	CLEAN STEEL BRIDGE, QP-1, BRIDGE NO.	1.00	LS
0011	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0012	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0013	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0014	628-09403	FIELD OFFICE, C	6.00	MOS
0015	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH

0016	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00 EACH
0017	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	20002.00 LFT
0018	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	7535.00 LFT
0019	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	4.00 EACH
0020	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	1491.00 LFT
0021	801-06640	CONSTRUCTION SIGN, A	44.00 EACH
0022	801-06645	CONSTRUCTION SIGN, B	14.00 EACH
0023	801-06775	MAINTAINING TRAFFIC	1.00 LS
0024	801-08403	TEMPORARY TRAFFIC BARRIER TYPE 4	157.00 LFT
0025	801-09087	TEMPORARY PAVEMENT MARKING, REMOVABLE, 12 IN.	250.00 LFT
0026	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	6.00 EACH
0027	801-12081	PORTABLE SIGNAL	1.00 LS

Call: 491

Contract: B -40080-A

Section No.: 1 BRIDGE DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0011	202-02240	PAVEMENT REMOVAL	5150.00	SYS
	0012	202-02928	CATCH BASIN, REMOVE	2.00	EACH
	0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0017	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0018	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0019	202-94954	BARRIER WALL, CONCRETE, REMOVE	1440.00	LFT
	0020	203-02000	EXCAVATION, COMMON	540.00	CYS
	0021	203-08607	LINEAR GRADING	50.00	LFT
	0022	205-11626	PUMP AROUND	2.00	EACH
	0023	205-12108	STORM WATER MANAGEMENT BUDGET	31000.00	DOL
	0024	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS

0025	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	650.00	CYS
0026	206-51235	COFFERDAM	1.00	LS
0027	207-09935	SUBGRADE TREATMENT, TYPE IC	3697.00	SYS
0028	211-06467	AGGREGATE FOR END BENT BACKFILL	436.00	CYS
0029	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	1.00	EACH
0030	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	15.00	CYS
0031	301-12233	COMPACTED AGGREGATE NO 8	40.00	CYS
0032	301-12234	COMPACTED AGGREGATE NO 53	31.00	CYS
0033	302-06464	SUBBASE FOR PCCP	675.00	CYS
0034	302-07455	DENSE GRADED SUBBASE	249.00	CYS
0035	303-01180	COMPACTED AGGREGATE NO. 53	240.00	TON
0036	402-10086	HMA FOR TEMPORARY PAVEMENT, C	176.00	TON
0037	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
0038	502-06329	PCCP, 12 IN.	3571.00	SYS
0039	503-05240	D-1 CONTRACTION JOINT	392.00	LFT
0040	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	642.00	LFT
0041	601-02241	GUARDRAIL, REMOVE	160.00	LFT
0042	601-06035	GUARDRAIL, RESET	175.00	LFT
0043	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	2.00	EACH
0044	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0045	602-01064	CONCRETE BARRIER	1500.00	LFT
0046	602-06729	BARRIER, DELINEATOR	76.00	EACH
0047	602-91266	CONCRETE MEDIAN BARRIER MODIFIED	100.00	LFT
0048	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	1655.00	SYS
0049	616-05688	RIPRAP, CLASS 1	567.00	TON
0050	616-06405	RIPRAP, REVETMENT	77.00	TON
0051	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	294.00	SYS
0052	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	372.00	SYS
0053	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	640.00	SYS
0054	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0055	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0056	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0057	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0058	628-09403	FIELD OFFICE, C	20.00	MOS
0059	628-11729	CELLULAR TELEPHONE, TYPE A	2.00	EACH
0060	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0061	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0062	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	20.00	MOS
0063	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	EACH
0064	628-11977	COMPUTER SYSTEM	2.00	EACH
0065	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	6.00	EACH
0066	702-51005	CONCRETE, A, SUBSTRUCTURE	98.00	CYS

0067	702-51863	FIELD DRILLED HOLE IN CONCRETE	452.00	EACH
0068	702-92857	CONCRETE, C, SUBSTRUCTURE	162.00	CYS
0069	703-01540	THREADED TIE BAR ASSEMBLY	779.00	EACH
0070	703-06028	REINFORCING BARS	8984.00	LBS
0071	703-06029	REINFORCING BARS, EPOXY COATED	317332.00	LBS
0072	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	100.00	EACH
0073	704-51002	CONCRETE, C, SUPERSTRUCTURE	761.00	CYS
0074	706-09960	RAILING, CONCRETE FC	692.00	LFT
0075	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	12.00	EACH
0076	706-51020	RAILING, CONCRETE C	9.20	CYS
0077	707-05983	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 36 IN. X 12 IN.	2372.00	LFT
0078	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0079	709-51821	SURFACE SEAL	1.00	LS
0080	709-51821	SURFACE SEAL	1.00	LS
0081	709-51821	SURFACE SEAL	1.00	LS
0082	709-51821	SURFACE SEAL	1.00	LS
0083	709-51821	SURFACE SEAL	1.00	LS
0084	709-51821	SURFACE SEAL	1.00	LS
0085	710-09158	PATCHING CONCRETE STRUCTURES	20.00	SFT
0086	711-51038	STRUCTURAL STEEL	1.00	LS
0087	711-51038	STRUCTURAL STEEL	1.00	LS
0088	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	600.00	LFT
0089	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	28.00	LFT
0090	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	76.00	LFT
0091	715-05407	PIPE, END BENT DRAIN, 6 IN.	200.00	LFT
0092	715-05422	PIPE, SLOTTED DRAIN, 12 IN.	10.00	LFT
0093	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0094	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	3.00	EACH
0095	718-06531	OUTLET PROTECTOR, 3	4.00	EACH
0096	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	460.00	SYS
0097	718-52610	AGGREGATE FOR UNDERDRAINS	60.00	CYS
0098	720-45042	INLET, HA5	2.00	EACH
0099	720-45260	PIPE CATCH BASIN, 12 IN.	2.00	EACH
0100	722-01066	HYDRODEMOLITION	4010.00	SYS
0101	722-12380	BRIDGE DECK OVERLAY, BUDGET	64775.00	DOL
0102	722-12382	TRANSVERSE GROOVING	5400.00	SYS
0103	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	975.00	SYS
0104	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	775.00	SYS
0105	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	1130.00	SYS
0106	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	1130.00	SYS
0107	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	100.00	SFT
0108	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	374.00	SFT

0109	724-12103	PRE-COMPRESSED FOAM JOINT	94.00	LFT
0110	727-90308	EPOXY INJECTION, CRACK PREPARATION	20.00	LFT
0111	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	1799.00	SYS
0112	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	13.00	EACH
0113	801-01295	BARRELS FOR CROSSOVER	450.00	EACH
0114	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0115	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	2860.00	LFT
0116	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	37510.00	LFT
0117	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	4500.00	LFT
0118	801-06625	DETOUR ROUTE MARKER ASSEMBLY	17.00	EACH
0119	801-06640	CONSTRUCTION SIGN, A	89.00	EACH
0120	801-06645	CONSTRUCTION SIGN, B	13.00	EACH
0121	801-06710	FLASHING ARROW SIGN	610.00	DAY
0122	801-06775	MAINTAINING TRAFFIC	1.00	LS
0123	801-07118	BARRICADE, III-A	82.00	LFT
0124	801-07119	BARRICADE, III-B	60.00	LFT
0125	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	3400.00	LFT
0126	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2132.00	LFT
0127	801-12042	TRUCK MOUNTED ATTENUATOR	10.00	DAY
0128	802-11843	SIGN SHEET WITH SPEED DISPLAY	4.00	EACH
0129	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	560.00	LFT
0130	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	550.00	LFT
0131	808-06716	LINE, REMOVE	20945.00	LFT
0132	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1550.00	LFT
0133	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	10735.00	LFT
0134	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	8620.00	LFT
0135	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	1000.00	LFT
0136	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	53.00	EACH
0137	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	13.00	EACH

Call: 491

Contract: B -40080-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0138	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	4225.00	SYS

Call: 491

Contract: B -40080-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0139	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	4225.00	SYS

Call: 501

Contract: B -40093-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	4.00	CYS
0011	306-08034	MILLING, ASPHALT, 1 1/2 IN.	404.00	SYS
0012	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	22.00	TON
0013	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	7.00	TON
0014	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	8.00	TON
0015	401-10258	JOINT ADHESIVE, SURFACE	870.00	LFT
0016	401-11785	LIQUID ASPHALT SEALANT	870.00	LFT
0017	406-05521	ASPHALT FOR TACK COAT	405.00	SYS
0018	507-08271	JOINTS IN PCCP, FILLED	873.00	LFT
0019	616-93772	INSPECTION HOLE	10.00	EACH
0020	628-09402	FIELD OFFICE, B	11.00	MOS
0021	709-51821	SURFACE SEAL	1.00	LS
0022	709-51821	SURFACE SEAL	1.00	LS
0023	710-09158	PATCHING CONCRETE STRUCTURES	546.00	SFT
0024	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	3.00	SFT
0025	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	2439.00	SFT
0026	724-12103	PRE-COMPRESSED FOAM JOINT	273.00	LFT
0027	724-12420	BRIDGE JOINT NOSING	481.00	SFT
0028	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	4592.00	SYS
0029	801-06640	CONSTRUCTION SIGN, A	123.00	EACH
0030	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0031	801-06710	FLASHING ARROW SIGN	28.00	DAY
0032	801-06775	MAINTAINING TRAFFIC	1.00	LS
0033	801-12042	TRUCK MOUNTED ATTENUATOR	374.00	DAY
0034	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	301.00	LFT
0035	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	3044.00	LFT
0036	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1214.00	LFT

0037 808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE

29.00 EACH

Call: 511

Contract: B -40532-A

Section No.: 1 BRIDGE DECK OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	202-51368	SLOPEWALL, REMOVE	406.00	SYS
0008	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	5.00	CYS
0009	616-06405	RIPRAP, REVETMENT	80.00	TON
0010	628-09401	FIELD OFFICE, A	3.00	MOS
0011	709-51821	SURFACE SEAL	1.00	LS
0012	710-09158	PATCHING CONCRETE STRUCTURES	84.00	SFT
0013	715-05146	PIPE, TYPE 2, CIRCULAR, 6 IN.	140.00	LFT
0014	722-01066	HYDRODEMOLITION	740.00	SYS
0015	722-12380	BRIDGE DECK OVERLAY, BUDGET	16800.00	DOL
0016	722-12381	BRIDGE DECK OVERLAY, LMC-VE	740.00	SYS
0017	722-12382	TRANSVERSE GROOVING	740.00	SYS
0018	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	740.00	SYS
0019	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	333.00	SFT
0020	724-12103	PRE-COMPRESSED FOAM JOINT	59.00	LFT
0021	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0022	801-06625	DETOUR ROUTE MARKER ASSEMBLY	24.00	EACH
0023	801-06640	CONSTRUCTION SIGN, A	30.00	EACH
0024	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0025	801-06710	FLASHING ARROW SIGN	13.00	DAY
0026	801-06775	MAINTAINING TRAFFIC	1.00	LS
0027	801-07118	BARRICADE, III-A	64.00	LFT
0028	801-07119	BARRICADE, III-B	64.00	LFT
0029	801-12042	TRUCK MOUNTED ATTENUATOR	10.00	DAY
0030	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	504.00	LFT

Call: 521

Contract: B -40864-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
----------------	------------------	--------------------	-----------------	-------------

0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	202-52710	SIDEWALK CONCRETE, REMOVE	85.00	SYS
0008	604-06070	SIDEWALK, CONCRETE	85.00	SYS
0009	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	315.00	SFT
0010	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	350.00	SYS
0011	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0012	801-06625	DETOUR ROUTE MARKER ASSEMBLY	26.00	EACH
0013	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0014	801-06775	MAINTAINING TRAFFIC	1.00	LS
0015	801-07118	BARRICADE, III-A	128.00	LFT
0016	801-07119	BARRICADE, III-B	96.00	LFT
0017	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	180.00	LFT
0018	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	45.00	LFT
0019	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	2.00	EACH
0020	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	2.00	EACH
0021	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	8.00	EACH

Call: 531

Contract: B -40930-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	602-06729	BARRIER, DELINEATOR	6.00	EACH
0008	628-09403	FIELD OFFICE, C	11.00	MOS
0009	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0010	709-51821	SURFACE SEAL	1.00	LS
0011	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	140.00	SFT
0012	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	310.00	SYS
0013	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	EACH
0014	801-06625	DETOUR ROUTE MARKER ASSEMBLY	34.00	EACH
0015	801-06640	CONSTRUCTION SIGN, A	11.00	EACH

0016	801-07118	BARRICADE, III-A	48.00	LFT
0017	801-07119	BARRICADE, III-B	48.00	LFT
0018	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	166.00	LFT
0019	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	332.00	LFT
0020	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	166.00	LFT

Call: 541

Contract: B -40934-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	507-07482	CRACKS IN PCCP, ROUT AND SEAL	475.00	LFT
0008	507-08272	JOINTS IN PCCP, SAW AND SEAL	175.00	LFT
0009	602-06729	BARRIER, DELINEATOR	22.00	EACH
0010	628-09403	FIELD OFFICE, C	8.00	MOS
0011	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0012	709-51821	SURFACE SEAL	1.00	LS
0013	709-51821	SURFACE SEAL	1.00	LS
0014	709-51821	SURFACE SEAL	1.00	LS
0015	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	93.00	SFT
0016	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	1069.00	SYS
0017	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0018	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00	EACH
0019	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1300.00	LFT
0020	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	300.00	LFT
0021	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	600.00	LFT
0022	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	48.00	LFT
0023	801-06625	DETOUR ROUTE MARKER ASSEMBLY	53.00	EACH
0024	801-06640	CONSTRUCTION SIGN, A	53.00	EACH
0025	801-06775	MAINTAINING TRAFFIC	1.00	LS
0026	801-07118	BARRICADE, III-A	192.00	LFT
0027	801-07119	BARRICADE, III-B	264.00	LFT
0028	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	6.00	EACH
0029	801-12081	PORTABLE SIGNAL	1.00	LS
0030	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	500.00	LFT
0031	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1000.00	LFT

0032 808-06714 LINE, PAINT, SOLID, YELLOW, 4 IN.

400.00 LFT

Call: 551

Contract: B -40935-A

Section No.: 1 SMALL STRUCTURE MAINTENANCE AND REPAIR

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0009	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0010	203-02000	EXCAVATION, COMMON	8.00	CYS
0011	303-01180	COMPACTED AGGREGATE NO. 53	16.00	TON
0012	601-02241	GUARDRAIL, REMOVE	377.00	LFT
0013	601-06854	GUARDRAIL, W-BEAM, NESTED	2.00	EACH
0014	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	2.00	EACH
0015	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0016	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0017	621-06559	MULCHED SEEDING R	10.00	SYS
0018	702-51863	FIELD DRILLED HOLE IN CONCRETE	109.00	EACH
0019	703-06029	REINFORCING BARS, EPOXY COATED	1125.00	LBS
0020	704-51002	CONCRETE, C, SUPERSTRUCTURE	6.00	CYS
0021	710-09158	PATCHING CONCRETE STRUCTURES	20.00	SFT
0022	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1200.00	LFT
0023	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	48.00	LFT
0024	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0025	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
0026	801-06775	MAINTAINING TRAFFIC	1.00	LS
0027	801-07119	BARRICADE, III-B	24.00	LFT
0028	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	600.00	LFT
0029	801-12081	PORTABLE SIGNAL	1.00	LS

Call: 561

Contract: B -41694-B

Section No.: 1 IDIQ, BRIDGE MAINTENANCE

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL

0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	110-07025	MOBILIZATION AND DEMOBILIZATION	2.00	EACH
0007	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0008	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0009	213-09270	FLOWABLE BACKFILL, REMOVABLE	20.00	CYS
0010	602-91266	CONCRETE MEDIAN BARRIER MODIFIED	260.00	LFT
0011	702-92857	CONCRETE, C, SUBSTRUCTURE	100.00	CYS
0012	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1000.00	LFT
0013	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1480.00	LFT
0014	801-12440	MAINTAINING TRAFFIC, IDIQ	1.00	DOL

Call: 571

Contract: B -41824-A

Section No.: 1 BRIDGE REPLACEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	664.00	SYS
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0014	203-02000	EXCAVATION, COMMON	1036.00	CYS
0015	203-02070	BORROW	789.00	CYS
0016	205-12108	STORM WATER MANAGEMENT BUDGET	6329.00	DOL
0017	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0018	206-51215	EXCAVATION, X	220.00	CYS
0019	206-51220	EXCAVATION, WET	284.00	CYS
0020	206-51235	COFFERDAM	1.00	LS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	362.00	SYS
0022	211-06467	AGGREGATE FOR END BENT BACKFILL	30.00	CYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	27.00	CYS

0024	302-07455	DENSE GRADED SUBBASE	85.00	CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	153.00	TON
0026	306-08043	MILLING, TRANSITION	1420.00	SYS
0027	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	80.00	TON
0028	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	74.00	TON
0029	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	37.00	TON
0030	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	122.00	TON
0031	401-10258	JOINT ADHESIVE, SURFACE	881.00	LFT
0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	233.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	881.00	LFT
0034	406-05521	ASPHALT FOR TACK COAT	1865.00	SYS
0035	502-06329	PCCP, 12 IN.	90.00	SYS
0036	503-05310	TERMINAL JOINT	80.00	LFT
0037	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	2.00	EACH
0038	601-01700	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 1	1.00	EACH
0039	601-01701	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 2	1.00	EACH
0040	601-06035	GUARDRAIL, RESET	200.00	LFT
0041	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	119.00	LFT
0042	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0043	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0044	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	12.50	LFT
0045	605-06095	CURB, INTEGRAL B CONCRETE	20.00	LFT
0046	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	619.00	SYS
0047	615-06505	MONUMENT, B	2.00	EACH
0048	616-06405	RIPRAP, REVETMENT	300.00	TON
0049	616-06451	RIPRAP, UNIFORM	4.00	TON
0050	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	12.00	SYS
0051	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	400.00	SYS
0052	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0053	621-06559	MULCHED SEEDING R	1111.00	SYS
0054	621-06567	WATER	1.00	KGAL
0055	621-06574	SODDING	9.00	SYS
0056	628-09402	FIELD OFFICE, B	12.00	MOS
0057	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0058	701-02938	CORED HOLE IN ROCK, 24 IN	55.00	LFT
0059	701-09558	TEST PILE, INDICATOR, PRODUCTION	40.00	LFT
0060	701-51195	PILE, STEEL H HP 12 X 53	160.00	LFT
0061	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	6.00	EACH
0062	702-51005	CONCRETE, A, SUBSTRUCTURE	132.80	CYS
0063	702-51015	CONCRETE, B, FOOTINGS	61.40	CYS
0064	702-51863	FIELD DRILLED HOLE IN CONCRETE	262.00	EACH
0065	703-06028	REINFORCING BARS	31876.00	LBS

0066	703-06029	REINFORCING BARS, EPOXY COATED	86656.00	LBS
0067	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	38.00	EACH
0068	704-51002	CONCRETE, C, SUPERSTRUCTURE	223.80	CYS
0069	706-11600	RAILING, CONCRETE FC	21.30	CYS
0070	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0071	707-05982	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 28 IN. X 12 IN.	607.50	LFT
0072	709-51821	SURFACE SEAL	1.00	LS
0073	709-51821	SURFACE SEAL	1.00	LS
0074	709-51821	SURFACE SEAL	1.00	LS
0075	710-09158	PATCHING CONCRETE STRUCTURES	160.00	SFT
0076	715-03584	SAFETY METAL END SECTION, 4:1, DIA 18 IN.	2.00	EACH
0077	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	88.00	LFT
0078	715-05407	PIPE, END BENT DRAIN, 6 IN.	110.00	LFT
0079	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	6.00	EACH
0080	718-12309	GEOTEXTILE FOR UNDERDRAIN, TYPE 3	74.00	SYS
0081	722-01066	HYDRODEMOLITION	358.00	SYS
0082	722-12380	BRIDGE DECK OVERLAY, BUDGET	5890.00	DOL
0083	722-12382	TRANSVERSE GROOVING	589.00	SYS
0084	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	358.00	SYS
0085	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	50.00	SFT
0086	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	210.00	SFT
0087	727-90308	EPOXY INJECTION, CRACK PREPARATION	80.00	LFT
0088	727-90309	EPOXY INJECTION, EPOXY MATERIAL	5.00	GAL
0089	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0090	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	233.00	SYS
0091	801-04308	ROAD CLOSURE SIGN ASSEMBLY	15.00	EACH
0092	801-06625	DETOUR ROUTE MARKER ASSEMBLY	60.00	EACH
0093	801-06640	CONSTRUCTION SIGN, A	52.00	EACH
0094	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0095	801-06775	MAINTAINING TRAFFIC	1.00	LS
0096	801-07118	BARRICADE, III-A	240.00	LFT
0097	801-07119	BARRICADE, III-B	228.00	LFT
0098	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	228.00	LFT
0099	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1806.00	LFT
0100	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	13.00	EACH
0101	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	6.00	EACH

Call: 571

Contract: B -41824-A

Section No.: 2 BRIDGE DECK OVERLAY, SILICA FUME

Line

Item No Item Code Description

Quantity Unit

0102 722-01061 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

358.00 SYS

Call: 571

Contract: B -41824-A

Section No.: 3 BRIDGE DECK OVERLAY, LATEX MODIFIED

Line

Item No Item Code Description

Quantity Unit

0103 722-51842 BRIDGE DECK OVERLAY, LATEX MODIFIED

358.00 SYS

Call: 581

Contract: M -40397-C

Section No.: 1 GUARDRAIL, MAINTENANCE

Line

Item No Item Code Description

Quantity Unit

0001 109-08359 LIQUIDATED DAMAGES

1.00 DOL

0002 109-08360 CONTRACT LIENS

1.00 DOL

0003 109-08443 QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES

1.00 DOL

0004 109-08444 QUALITY ADJUSTMENTS, FAILED MATERIALS

1.00 DOL

0005 110-01001 MOBILIZATION AND DEMOBILIZATION

1.00 LS

0006 601-01522 GUARDRAIL, TRANSITION, TYPE TGB

2.00 EACH

0007 601-01625 GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 1

1.00 EACH

0008 601-01626 GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 2

1.00 EACH

0009 601-03456 GUARDRAIL POST, WOOD TYPE W5

9.00 EACH

0010 601-03457 GUARDRAIL W THRIE BEAM RAIL SECTION, 12FT-6 IN

8.00 EACH

0011 601-03464 GUARDRAIL, STEEL CURVED TERMINAL END SECTION

5.00 EACH

0012 601-03471 CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY

8.00 EACH

0013 601-03471 CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY

8.00 EACH

0014 601-03471 CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY

7.00 EACH

0015 601-03471 CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY

7.00 EACH

0016 601-03471 CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY

8.00 EACH

0017 601-06273 GUARDRAIL, END TREATMENT, SKT-350

14.00 EACH

0018 601-06273 GUARDRAIL, END TREATMENT, SKT-350

8.00 EACH

0019 601-06273 GUARDRAIL, END TREATMENT, SKT-350

31.00 EACH

0020 601-06273 GUARDRAIL, END TREATMENT, SKT-350

32.00 EACH

0021 601-06273 GUARDRAIL, END TREATMENT, SKT-350

36.00 EACH

0022 601-06798 TIMBER BLOCK

125.00 EACH

0023 601-07179 ET_2000 OS UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES, ABOVE GROUND COMPONENTS ONLY

3.00 EACH

0024 601-07607 IMPACT ATTENUATOR

2.00 EACH

0025 601-08132 GUARDRAIL, THRIE BEAM, BLOCKOUT, STEEL

40.00 EACH

0026 601-09238 HAND DIG GUARDRAIL POST HOLES

32.00 EACH

0027 601-12281 GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING

150.00 LFT

0028 601-12284 GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING

75.00 LFT

0029 601-52501 GUARDRAIL POST

125.00 EACH

0030	601-52501	GUARDRAIL POST	20.00 EACH
0031	601-52501	GUARDRAIL POST	100.00 EACH
0032	601-52501	GUARDRAIL POST	1.00 EACH
0033	601-52501	GUARDRAIL POST	20.00 EACH
0034	601-61340	GUARDRAIL POST, 15.5 LBS PER FT., GALVANIZED, 6 FT. 3 IN. LONG	470.00 EACH
0035	601-62070	GUARDRAIL, STEEL BEAM, GALVANIZED	7500.00 LFT
0036	601-62080	GUARDRAIL, STEEL BEAM, CURVED SECTION, GALVANIZED	720.00 LFT
0037	601-62150	GUARDRAIL POST, 15.5 LBS PER LFT, GALVANIZED, 7 FT 0 IN. LONG	5.00 EACH
0038	601-62540	GUARDRAIL POST, PLUMB	3200.00 EACH
0039	601-91511	GUARDRAIL POST, W4, 8 IN. X 8 IN.	10.00 EACH
0040	601-91542	GUARDRAIL BLOCK, 6 IN. X 8 IN., B1	17.00 EACH
0041	601-91575	GUARDRAIL BLOCK, 6 IN. X 8 IN., B2	13.00 EACH
0042	601-91576	GUARDRAIL BLOCK, 6 IN. X 8 IN., B3	30.00 EACH
0043	601-91649	GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	6.00 EACH
0044	601-95342	GUARDRAIL SPLICE PLATE, C, GALVANIZED	8.00 EACH
0045	801-06640	CONSTRUCTION SIGN, A	14.00 EACH
0046	801-06775	MAINTAINING TRAFFIC	1.00 LS

Call: 591

Contract: M -42220-A

Section No.: 1 SLAB JACKING

Line

Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	612-12497	HIGH DENSITY POLYURETHANE	1530.00 GAL

Call: 601

Contract: M -42224-A

Section No.: 1 GUARDRAIL, MAINTENANCE

Line

Item No	Item Code	Description	Quantity Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0002	109-08360	CONTRACT LIENS	1.00 DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0006	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	2.00 EACH
0007	601-01625	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 1	1.00 EACH
0008	601-01626	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 2	1.00 EACH
0009	601-03456	GUARDRAIL POST, WOOD TYPE W5	9.00 EACH
0010	601-03457	GUARDRAIL W THRIE BEAM RAIL SECTION, 12FT-6 IN	8.00 EACH

0011	601-03464	GUARDRAIL, STEEL CURVED TERMINAL END SECTION	5.00 EACH
0012	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	8.00 EACH
0013	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	8.00 EACH
0014	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	7.00 EACH
0015	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	7.00 EACH
0016	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	8.00 EACH
0017	601-06273	GUARDRAIL, END TREATMENT, SKT-350	14.00 EACH
0018	601-06273	GUARDRAIL, END TREATMENT, SKT-350	8.00 EACH
0019	601-06273	GUARDRAIL, END TREATMENT, SKT-350	31.00 EACH
0020	601-06273	GUARDRAIL, END TREATMENT, SKT-350	32.00 EACH
0021	601-06273	GUARDRAIL, END TREATMENT, SKT-350	36.00 EACH
0022	601-06798	TIMBER BLOCK	125.00 EACH
0023	601-07179	ET_2000 OS UNIT, COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES, ABOVE GROUND COMPONENTS ONLY	3.00 EACH
0024	601-07607	IMPACT ATTENUATOR	2.00 EACH
0025	601-08132	GUARDRAIL, THRIE BEAM, BLOCKOUT, STEEL	40.00 EACH
0026	601-09238	HAND DIG GUARDRAIL POST HOLES	32.00 EACH
0027	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	150.00 LFT
0028	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	75.00 LFT
0029	601-52501	GUARDRAIL POST	125.00 EACH
0030	601-52501	GUARDRAIL POST	20.00 EACH
0031	601-52501	GUARDRAIL POST	100.00 EACH
0032	601-52501	GUARDRAIL POST	1.00 EACH
0033	601-52501	GUARDRAIL POST	20.00 EACH
0034	601-61340	GUARDRAIL POST, 15.5 LBS PER FT., GALVANIZED, 6 FT. 3 IN. LONG	470.00 EACH
0035	601-62070	GUARDRAIL, STEEL BEAM, GALVANIZED	7500.00 LFT
0036	601-62080	GUARDRAIL, STEEL BEAM, CURVED SECTION, GALVANIZED	720.00 LFT
0037	601-62150	GUARDRAIL POST, 15.5 LBS PER LFT, GALVANIZED, 7 FT 0 IN. LONG	5.00 EACH
0038	601-62540	GUARDRAIL POST, PLUMB	3200.00 EACH
0039	601-91511	GUARDRAIL POST, W4, 8 IN. X 8 IN.	10.00 EACH
0040	601-91542	GUARDRAIL BLOCK, 6 IN. X 8 IN., B1	17.00 EACH
0041	601-91575	GUARDRAIL BLOCK, 6 IN. X 8 IN., B2	13.00 EACH
0042	601-91576	GUARDRAIL BLOCK, 6 IN. X 8 IN., B3	30.00 EACH
0043	601-91649	GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	6.00 EACH
0044	601-95342	GUARDRAIL SPLICE PLATE, C, GALVANIZED	8.00 EACH
0045	801-06640	CONSTRUCTION SIGN, A	14.00 EACH
0046	801-06775	MAINTAINING TRAFFIC	1.00 LS

Call: 641

Contract: T -40340-B

Section No.: 1 PEDESTRIAN FLASHING BEACONS, INSTALLED

Line

Item No Item Code Description

Quantity Unit

0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	202-02240	PAVEMENT REMOVAL	79.00	SYS
0009	202-02278	CURB, CONCRETE, REMOVE	153.00	LFT
0010	202-02279	CURB AND GUTTER, REMOVE	619.00	LFT
0011	202-52710	SIDEWALK CONCRETE, REMOVE	337.00	SYS
0012	205-12108	STORM WATER MANAGEMENT BUDGET	1200.00	DOL
0013	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0014	211-09264	STRUCTURE BACKFILL, TYPE 1	4.00	CYS
0015	604-06070	SIDEWALK, CONCRETE	254.00	SYS
0016	604-08086	CURB RAMP, CONCRETE	242.00	SYS
0017	604-12083	DETECTABLE WARNING SURFACES	27.00	SYS
0018	605-06090	CURB, INTEGRAL CONCRETE	35.00	LFT
0019	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	604.00	LFT
0020	610-09108	PCCP FOR APPROACHES, 9 IN.	23.00	SYS
0021	628-09403	FIELD OFFICE, C	9.00	MOS
0022	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	11.00	LFT
0023	715-94530	ADJUST WATER VALVE TO GRADE	1.00	EACH
0024	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	2.00	EACH
0025	720-44000	CASTING, ADJUST TO GRADE	5.00	EACH
0026	720-45005	INLET, A2	1.00	EACH
0027	720-45015	INLET, A8	2.00	EACH
0028	801-06640	CONSTRUCTION SIGN, A	31.00	EACH
0029	801-06645	CONSTRUCTION SIGN, B	17.00	EACH
0030	801-06710	FLASHING ARROW SIGN	150.00	DAY
0031	801-06775	MAINTAINING TRAFFIC	1.00	LS
0032	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.00	EACH
0033	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	4.00	EACH
0034	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	161.00	LFT
0035	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	18.00	EACH
0036	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	7.00	EACH
0037	805-08464	RADIO INTERCONNECT	3.00	EACH
0038	805-08493	RADIO INTERCONNECTION SYSTEM TESTING	1.00	LS
0039	805-09089	RADIO YAGI ANTENNA	3.00	EACH
0040	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	24.00	EACH
0041	805-78412	SIGNAL POLE, PEDESTAL, 9FT	7.00	EACH
0042	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	4246.00	LFT

0043	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	3336.00	LFT
0044	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	456.00	LFT
0045	808-06368	TRANSVERSE MARKING, REMOVE	903.00	LFT
0046	808-06716	LINE, REMOVE	66.00	LFT
0047	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	414.00	LFT
0048	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	1148.00	LFT

Call: 651

Contract: T -40698-A

Section No.: 1 TRAFFIC SIGNAL VISIBILITY IMPROVEMENTS

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0006	628-09403	FIELD OFFICE, C	7.00	MOS
0007	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0008	801-06640	CONSTRUCTION SIGN, A	148.00	EACH
0009	801-06775	MAINTAINING TRAFFIC	1.00	LS
0010	802-04089	SIGN, SHEET, REMOVE	4.00	EACH
0011	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	1233.00	SFT
0012	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	57.00	SFT
0013	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	276.00	SFT
0014	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	17.00	EACH
0015	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0016	805-01824	SPAN, CATENARY, AND TETHER, TIGHTEN	5.00	EACH
0017	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	250.00	LFT
0018	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	135.00	EACH
0019	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	45.00	EACH
0020	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	4.00	EACH
0021	805-78415	SPAN, CATENARY, AND TETHER	63.00	EACH
0022	805-78420	DISCONNECT HANGER	68.00	EACH
0023	805-78445	SIGNAL SERVICE	16.00	EACH
0024	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	1450.00	LFT
0025	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	1306.00	LFT
0026	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	3407.00	LFT
0027	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	7835.00	LFT

Call: 661

Contract: T -41220-C

Section No.: 1 ITS TRAFFIC MANAGEMENT SYSTEMS

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0007	628-11729	CELLULAR TELEPHONE, TYPE A	5.00	EACH
	0008	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
	0009	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
	0010	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	60.00	MOS
	0011	628-11976	COMPUTER SYSTEM EQUIPMENT	5.00	EACH
	0012	801-06640	CONSTRUCTION SIGN, A	34.00	EACH
	0013	801-06645	CONSTRUCTION SIGN, B	12.00	EACH
	0014	801-06710	FLASHING ARROW SIGN	120.00	DAY
	0015	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0016	802-06402	DYNAMIC MESSAGE SIGN	1.00	EACH
	0017	802-06402	DYNAMIC MESSAGE SIGN	14.00	EACH
	0018	802-06402	DYNAMIC MESSAGE SIGN	28.00	EACH
	0019	802-06402	DYNAMIC MESSAGE SIGN	3.00	EACH
	0020	802-06402	DYNAMIC MESSAGE SIGN	51.00	EACH
	0021	802-06402	DYNAMIC MESSAGE SIGN	104.00	EACH
	0022	802-06402	DYNAMIC MESSAGE SIGN	20.00	EACH
	0023	802-06402	DYNAMIC MESSAGE SIGN	8.00	EACH
	0024	802-06402	DYNAMIC MESSAGE SIGN	40.00	EACH
	0025	802-06402	DYNAMIC MESSAGE SIGN	22.00	EACH
	0026	802-06402	DYNAMIC MESSAGE SIGN	9.00	EACH
	0027	802-06402	DYNAMIC MESSAGE SIGN	36.00	EACH

Call: 671

Contract: T -41686-A

Section No.: 1 TRAFFIC SIGNAL VISIBILITY IMPROVEMENTS

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS

0007	801-06640	CONSTRUCTION SIGN, A	40.00 EACH
0008	801-06710	FLASHING ARROW SIGN	150.00 DAY
0009	801-06775	MAINTAINING TRAFFIC	1.00 LS
0010	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	570.00 SFT
0011	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	85.00 SFT
0012	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	56.00 SFT
0013	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00 LS
0014	805-02445	CONTROLLER AND CABINET, P1	1.00 EACH
0015	805-03372	TETHER FOR SIGNAL	156.00 EACH
0016	805-06483	CONTROLLER	12.00 EACH
0017	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	596.00 EACH
0018	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	48.00 EACH
0019	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	40.00 EACH
0020	805-78415	SPAN, CATENARY, AND TETHER	25.00 EACH
0021	805-78420	DISCONNECT HANGER	28.00 EACH
0022	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	3350.00 LFT
0023	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	6220.00 LFT
0024	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	4460.00 LFT