

Schedule of Pay Items Letting Date February 5, 2020 Letting ID 200205

Call: 110

Contract: R -32577-A

Section No.: 1 ROAD RECONSTRUCTION

Line

| Item No | Item Code | Description | Quantity | Unit |
|----------------|------------------|--|-----------------|-------------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08440 | QUALITY ADJUSTMENTS, HMA | 1.00 | DOL |
| 0005 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0006 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0007 | 109-09489 | PAYMENT ADJUSTMENT PG ASPHALT BINDER | 1.00 | DOL |
| 0008 | 109-11362 | QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES | 1.00 | DOL |
| 0009 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0010 | 201-52370 | CLEARING RIGHT OF WAY | 1.00 | LS |
| 0011 | 202-02278 | CURB, CONCRETE, REMOVE | 3592.00 | LFT |
| 0012 | 202-52710 | SIDEWALK CONCRETE, REMOVE | 1192.00 | SYS |
| 0013 | 202-74035 | SIGN, REMOVE | 24.00 | EACH |
| 0014 | 202-96328 | FOUNDATION, STREET LIGHT, REMOVE | 1.00 | EACH |
| 0015 | 203-02000 | EXCAVATION, COMMON | 4439.00 | CYS |
| 0016 | 203-02070 | BORROW | 887.00 | CYS |
| 0017 | 205-12108 | STORM WATER MANAGEMENT BUDGET | 24800.00 | DOL |
| 0018 | 205-12109 | SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1 | 1.00 | LS |
| 0019 | 207-08264 | SUBGRADE TREATMENT, TYPE II | 3230.00 | SYS |
| 0020 | 207-09935 | SUBGRADE TREATMENT, TYPE IC | 10342.00 | SYS |
| 0021 | 211-02050 | B BORROW | 322.00 | CYS |
| 0022 | 211-09264 | STRUCTURE BACKFILL, TYPE 1 | 4363.00 | CYS |
| 0023 | 214-12243 | GEOTEXTILE FOR SUBGRADE TYPE 2A | 2280.00 | SYS |
| 0024 | 301-12232 | COMPACTED AGGREGATE NO. 5 | 345.00 | CYS |
| 0025 | 301-12234 | COMPACTED AGGREGATE NO. 53 | 2078.00 | CYS |
| 0026 | 303-07449 | COMPACTED AGGREGATE NO. 73 | 22.00 | TON |
| 0027 | 304-07490 | HMA PATCHING, TYPE B | 1292.00 | TON |
| 0028 | 306-08036 | MILLING, ASPHALT, 2 IN. | 20720.00 | SYS |
| 0029 | 401-07321 | QC/QA-HMA, 2, 64, SURFACE, 9.5 mm | 1635.00 | TON |
| 0030 | 401-07390 | QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm | 1427.00 | TON |
| 0031 | 401-10258 | JOINT ADHESIVE, SURFACE | 9837.00 | LFT |
| 0032 | 401-10259 | JOINT ADHESIVE, INTERMEDIATE | 14483.00 | LFT |
| 0033 | 401-11785 | LIQUID ASPHALT SEALANT | 9837.00 | LFT |

| | | | |
|------|-----------|--|-------------|
| 0034 | 406-05520 | ASPHALT FOR TACK COAT | 7.50 TON |
| 0035 | 601-02241 | GUARDRAIL, REMOVE | 77.00 LFT |
| 0036 | 604-03643 | BRICK PAVERS | 10.00 SYS |
| 0037 | 604-06070 | SIDEWALK, CONCRETE | 1977.00 SYS |
| 0038 | 604-08086 | CURB RAMP, CONCRETE | 250.00 SYS |
| 0039 | 604-12083 | DETECTABLE WARNING SURFACES | 39.00 SYS |
| 0040 | 605-06140 | CURB AND GUTTER, CONCRETE | 6329.00 LFT |
| 0041 | 605-06140 | CURB AND GUTTER, CONCRETE | 51.00 LFT |
| 0042 | 605-97305 | CURB AND GUTTER, TURNOUT COMBINED MODIFIED | 6.00 EACH |
| 0043 | 610-07487 | HMA FOR APPROACHES, TYPE B | 201.00 TON |
| 0044 | 610-08446 | PCCP FOR APPROACHES, 6 IN. | 527.00 SYS |
| 0045 | 610-09108 | PCCP FOR APPROACHES, 9 IN. | 2018.00 SYS |
| 0046 | 611-06497 | MAILBOX ASSEMBLY, SINGLE | 9.00 EACH |
| 0047 | 611-06498 | MAILBOX ASSEMBLY, DOUBLE | 2.00 EACH |
| 0048 | 611-08232 | MAILBOX ASSEMBLY, RESET SINGLE | 1.00 EACH |
| 0049 | 615-06505 | MONUMENT, B | 6.00 EACH |
| 0050 | 615-06527 | MONUMENT, SECTION CORNER | 2.00 EACH |
| 0051 | 616-06405 | RIPRAP, REVETMENT | 177.00 TON |
| 0052 | 616-12246 | GEOTEXTILE FOR RIPRAP TYPE 1A | 54.00 SYS |
| 0053 | 621-01004 | MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 4.00 EACH |
| 0054 | 621-06545 | FERTILIZER | 0.70 TON |
| 0055 | 621-06554 | SEED MIXTURE U | 320.00 LBS |
| 0056 | 621-06565 | MULCHING MATERIAL | 3.20 TON |
| 0057 | 621-06567 | WATER | 19.00 KGAL |
| 0058 | 621-06570 | TOPSOIL | 1320.00 CYS |
| 0059 | 621-06575 | SODDING, NURSERY | 4591.00 SYS |
| 0060 | 628-09403 | FIELD OFFICE, C | 18.00 MOS |
| 0061 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 2.00 EACH |
| 0062 | 715-02433 | VALVE, WITH BOX, RESTRAINED GATE, DUCTILE IRON, 12 IN. | 2.00 EACH |
| 0063 | 715-02532 | VALVE, WITH BOX, RESTRAINED GATE, DUCTILE IRON, 8 IN. | 1.00 EACH |
| 0064 | 715-05048 | PIPE, TYPE 4, CIRCULAR, 6 IN. | 633.00 LFT |
| 0065 | 715-05149 | PIPE, TYPE 2, CIRCULAR, 12 IN. | 3052.00 LFT |
| 0066 | 715-05149 | PIPE, TYPE 2, CIRCULAR, 12 IN. | 1307.00 LFT |
| 0067 | 715-05151 | PIPE, TYPE 2, CIRCULAR, 15 IN. | 12.00 LFT |
| 0068 | 715-05152 | PIPE, TYPE 2, CIRCULAR, 18 IN. | 389.00 LFT |
| 0069 | 715-05152 | PIPE, TYPE 2, CIRCULAR, 18 IN. | 492.00 LFT |
| 0070 | 715-05154 | PIPE, TYPE 2, CIRCULAR, 24 IN. | 487.00 LFT |
| 0071 | 715-05154 | PIPE, TYPE 2, CIRCULAR, 24 IN. | 732.00 LFT |
| 0072 | 715-05156 | PIPE, TYPE 2, CIRCULAR, 30 IN. | 1311.00 LFT |
| 0073 | 715-05156 | PIPE, TYPE 2, CIRCULAR, 30 IN. | 39.00 LFT |
| 0074 | 715-05168 | PIPE, TYPE 3, CIRCULAR, 12 IN. | 59.00 LFT |
| 0075 | 715-05408 | PIPE, SANITARY SEWER, 8 IN. | 208.00 LFT |

| | | | | |
|------|-----------|--|----------|------|
| 0076 | 715-09064 | VIDEO INSPECTION FOR PIPE | 8029.00 | LFT |
| 0077 | 715-11571 | WATER MAIN, DUCTILE IRON, 8 IN. | 27.00 | LFT |
| 0078 | 715-11879 | SEWER, SANITARY LATERAL, CONNECTIONS | 85.00 | LFT |
| 0079 | 715-46000 | PIPE END SECTION, DIAMETER 12 IN. | 7.00 | EACH |
| 0080 | 715-46005 | PIPE END SECTION, DIAMETER 15 IN. | 1.00 | EACH |
| 0081 | 715-46030 | PIPE END SECTION, DIAMETER 30 IN. | 2.00 | EACH |
| 0082 | 715-90853 | TAPPING SLEEVE WITH VALVE | 1.00 | EACH |
| 0083 | 715-92544 | WATER MAIN, DUCTILE IRON, 12 IN. | 480.00 | LFT |
| 0084 | 715-94780 | WATER MAIN, DUCTILE IRON, 6 IN. | 10.00 | LFT |
| 0085 | 720-01092 | MANHOLE, J15 MODIFIED | 18.00 | EACH |
| 0086 | 720-01092 | MANHOLE, J15 MODIFIED | 12.00 | EACH |
| 0087 | 720-03194 | MANHOLE | 1.00 | EACH |
| 0088 | 720-08241 | MANHOLE, K15 MODIFIED | 1.00 | EACH |
| 0089 | 720-44000 | CASTING, ADJUST TO GRADE | 21.00 | EACH |
| 0090 | 720-45010 | INLET, A3 | 5.00 | EACH |
| 0091 | 720-45235 | CATCH BASIN, E7 | 4.00 | EACH |
| 0092 | 720-45270 | PIPE CATCH BASIN, 18 IN. | 5.00 | EACH |
| 0093 | 720-45275 | PIPE CATCH BASIN, 24 IN. | 4.00 | EACH |
| 0094 | 720-45410 | MANHOLE, C4 | 3.00 | EACH |
| 0095 | 720-45510 | MANHOLE, C4 MODIFIED | 1.00 | EACH |
| 0096 | 720-94612 | MANHOLE, K4 | 5.00 | EACH |
| 0097 | 720-94840 | CASTING, WATER VALVE, ADJUST TO GRADE | 28.00 | EACH |
| 0098 | 720-95422 | MANHOLE, J4 | 5.00 | EACH |
| 0099 | 720-96999 | FIRE HYDRANT ASSEMBLY | 1.00 | EACH |
| 0100 | 720-97008 | FIRE HYDRANT ASSEMBLY RELOCATE | 3.00 | EACH |
| 0101 | 720-97958 | MANHOLE, K2 | 1.00 | EACH |
| 0102 | 720-98174 | INLET, B15 | 10.00 | EACH |
| 0103 | 720-98174 | INLET, B15 | 3.00 | EACH |
| 0104 | 720-98555 | INLET, C15 | 19.00 | EACH |
| 0105 | 720-98555 | INLET, C15 | 7.00 | EACH |
| 0106 | 801-03290 | CONSTRUCTION SIGN, C | 4.00 | EACH |
| 0107 | 801-03291 | CONSTRUCTION SIGN, D | 1.00 | EACH |
| 0108 | 801-04308 | ROAD CLOSURE SIGN ASSEMBLY | 7.00 | EACH |
| 0109 | 801-06207 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 19473.00 | LFT |
| 0110 | 801-06211 | TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW | 3.00 | EACH |
| 0111 | 801-06213 | TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (RXR) | 3.00 | EACH |
| 0112 | 801-06218 | TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN. | 83.00 | LFT |
| 0113 | 801-06625 | DETOUR ROUTE MARKER ASSEMBLY | 36.00 | EACH |
| 0114 | 801-06640 | CONSTRUCTION SIGN, A | 39.00 | EACH |
| 0115 | 801-06645 | CONSTRUCTION SIGN, B | 65.00 | EACH |
| 0116 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0117 | 801-07118 | BARRICADE, III-A | 60.00 | LFT |

| | | | | |
|------|-----------|---|---------|------|
| 0118 | 801-07119 | BARRICADE, III-B | 144.00 | LFT |
| 0119 | 802-04314 | SIGN | 2.00 | EACH |
| 0120 | 802-05701 | SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE | 331.00 | LFT |
| 0121 | 802-05702 | SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE | 42.00 | LFT |
| 0122 | 802-07060 | SIGN, SHEET, RELOCATE | 6.00 | EACH |
| 0123 | 802-09838 | SIGN, SHEET, WITH LEGEND, 0.080 IN. | 129.25 | SFT |
| 0124 | 802-09840 | SIGN, SHEET, WITH LEGEND, 0.100 IN. | 67.14 | SFT |
| 0125 | 805-01300 | TRAFFIC SIGNAL EQUIPMENT, REMOVE | 1.00 | EACH |
| 0126 | 805-01842 | HANDHOLE SIGNAL TYPE 1 | 7.00 | EACH |
| 0127 | 805-01844 | CONDUIT, STEEL, GALVANIZED, 2 IN. | 1121.00 | LFT |
| 0128 | 805-02150 | PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN. | 4.00 | EACH |
| 0129 | 805-03979 | EMERGENCY VEHICLE PREEMPTION DETECTOR TWO CHANNEL TWO DIRECTION | 2.00 | EACH |
| 0130 | 805-03980 | EMERGENCY VEHICLE CONFIRMATION LIGHT KIT | 2.00 | EACH |
| 0131 | 805-11377 | SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 35 FT. | 1.00 | EACH |
| 0132 | 805-11379 | SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 45 FT. | 1.00 | EACH |
| 0133 | 805-11384 | SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, B | 4.00 | EACH |
| 0134 | 805-11817 | PEDESTRIAN PUSH BUTTON, APS | 3.00 | EACH |
| 0135 | 805-11837 | SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 40 FT, COMBINATION ARM | 1.00 | EACH |
| 0136 | 805-11838 | SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 45 FT, COMBINATION ARM | 1.00 | EACH |
| 0137 | 805-12016 | UNINTERRUPTIBLE POWER SUPPLY | 1.00 | EACH |
| 0138 | 805-78109 | CONTROLLER AND CABINET, SECONDARY MENU DRIVEN, 8 PHASE | 1.00 | EACH |
| 0139 | 805-78205 | TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN. | 1.00 | EACH |
| 0140 | 805-78230 | TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN. | 7.00 | EACH |
| 0141 | 805-78445 | SIGNAL SERVICE | 1.00 | EACH |
| 0142 | 805-78467 | SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA | 105.00 | LFT |
| 0143 | 805-78470 | SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA | 5004.00 | LFT |
| 0144 | 805-78480 | SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA | 1149.00 | LFT |
| 0145 | 805-78485 | SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA | 749.00 | LFT |
| 0146 | 805-78490 | SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA | 1572.00 | LFT |
| 0147 | 805-78510 | SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA | 1941.00 | LFT |
| 0148 | 805-78785 | SIGNAL DETECTOR HOUSING | 11.00 | EACH |
| 0149 | 805-78795 | SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT | 1622.00 | LFT |
| 0150 | 805-78925 | CONTROLLER CABINET FOUNDATION, P1 | 1.00 | EACH |
| 0151 | 807-02191 | HANDHOLE LIGHTING | 3.00 | EACH |
| 0152 | 807-12202 | LUMINAIRE, LOW LUMEN ROADWAY | 2.00 | EACH |
| 0153 | 807-86805 | SERVICE POINT, I | 1.00 | EACH |
| 0154 | 807-86843 | WIRE, NO. 4 COPPER, 1/C | 920.00 | LFT |
| 0155 | 807-86889 | CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C | 296.00 | LFT |
| 0156 | 807-86910 | CONNECTOR KIT, UNFUSED | 5.00 | EACH |
| 0157 | 807-86915 | CONNECTOR KIT, FUSED | 5.00 | EACH |
| 0158 | 807-86925 | MULTIPLE COMPRESSION FITTING, WATERPROOFED | 10.00 | EACH |
| 0159 | 807-86930 | INSULATION LINK, NON-WATERPROOFED | 13.00 | EACH |

| | | | |
|------|-----------|---|-------------|
| 0160 | 807-86935 | INSULATION LINK, WATERPROOFED | 21.00 EACH |
| 0161 | 808-04298 | PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R | 2.00 EACH |
| 0162 | 808-06703 | LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 1355.00 LFT |
| 0163 | 808-12032 | GROOVING FOR PAVEMENT MARKINGS | 9677.00 LFT |
| 0164 | 808-75043 | LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN. | 840.00 LFT |
| 0165 | 808-75240 | LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN. | 554.00 LFT |
| 0166 | 808-75245 | LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 7768.00 LFT |
| 0167 | 808-75297 | TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN. | 310.00 LFT |
| 0168 | 808-75320 | PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW | 31.00 EACH |
| 0169 | 808-75325 | PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY | 9.00 EACH |
| 0170 | 808-92027 | LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN. | 127.00 LFT |
| 0171 | 808-96016 | LINE, THERMOPLASTIC, SOLID, YELLOW, 12 IN. | 35.00 LFT |

Call: 190

Contract: R -39504-A

Section No.: 1 NEW INTERCHANGE CONSTRUCTION

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|--|----------|------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 105-11823 | CONSTRUCTION ENGINEERING GPS ROVER | 1.00 | LS |
| 0003 | 107-09358 | INSPECTION HOLE, DEEPER THAN 3 FT | 20.00 | EACH |
| 0004 | 107-09367 | INSPECTION HOLE, 3 FT DEEP OR LESS | 10.00 | EACH |
| 0005 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0006 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0007 | 109-08440 | QUALITY ADJUSTMENTS, HMA | 1.00 | DOL |
| 0008 | 109-08441 | QUALITY ADJUSTMENTS, PCCP | 1.00 | DOL |
| 0009 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0010 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0011 | 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 1.00 | DOL |
| 0012 | 109-09489 | PAYMENT ADJUSTMENT PG ASPHALT BINDER | 1.00 | DOL |
| 0013 | 109-11362 | QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES | 10.00 | DOL |
| 0014 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0015 | 201-52370 | CLEARING RIGHT OF WAY | 1.00 | LS |
| 0016 | 202-01000 | STRUCTURES AND OBSTRUCTIONS, REMOVE | 1.00 | LS |
| 0017 | 202-02273 | CENTER CURB, CONCRETE, REMOVE | 246.00 | SYS |
| 0018 | 202-02278 | CURB, CONCRETE, REMOVE | 1198.00 | LFT |
| 0019 | 202-02279 | CURB AND GUTTER, REMOVE | 6499.00 | LFT |
| 0020 | 202-52710 | SIDEWALK CONCRETE, REMOVE | 24.00 | SYS |
| 0021 | 202-91385 | INLET, REMOVE | 60.00 | EACH |
| 0022 | 202-91840 | FENCE, CHAIN. LINK, REMOVE | 3027.00 | LFT |
| 0023 | 202-93047 | MANHOLE, REMOVE | 29.00 | EACH |
| 0024 | 202-93763 | LIGHT STANDARD AND FOUNDATION, REMOVE | 25.00 | EACH |

| | | | | |
|------|-----------|---|-----------|------|
| 0025 | 202-96133 | PIPE, REMOVE | 5733.00 | LFT |
| 0026 | 202-96133 | PIPE, REMOVE | 425.00 | LFT |
| 0027 | 202-99626 | FOUNDATION FOR SIGNING, REMOVE | 1.00 | EACH |
| 0028 | 203-02000 | EXCAVATION, COMMON | 159105.00 | CYS |
| 0029 | 203-02070 | BORROW | 5000.00 | CYS |
| 0030 | 203-02594 | TIEBACK | 206.00 | EACH |
| 0031 | 205-12108 | STORM WATER MANAGEMENT BUDGET | 250000.00 | DOL |
| 0032 | 205-12111 | SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2 | 1.00 | LS |
| 0033 | 206-51230 | EXCAVATION, FOUNDATION, UNCLASSIFIED | 741.70 | CYS |
| 0034 | 207-08264 | SUBGRADE TREATMENT, TYPE II | 569.00 | SYS |
| 0035 | 207-08266 | SUBGRADE TREATMENT, TYPE III | 25809.00 | SYS |
| 0036 | 207-09934 | SUBGRADE TREATMENT, TYPE IB | 71332.00 | SYS |
| 0037 | 207-09935 | SUBGRADE TREATMENT, TYPE IC | 9161.00 | SYS |
| 0038 | 208-02046 | GRADING IN GORE AREA | 4.00 | EACH |
| 0039 | 211-02050 | B BORROW | 3816.20 | CYS |
| 0040 | 211-06467 | AGGREGATE FOR END BENT BACKFILL | 243.80 | CYS |
| 0041 | 211-09264 | STRUCTURE BACKFILL, TYPE 1 | 35803.00 | CYS |
| 0042 | 211-09265 | STRUCTURE BACKFILL, TYPE 2 | 414.00 | CYS |
| 0043 | 211-09266 | STRUCTURE BACKFILL, TYPE 3 | 890.00 | CYS |
| 0044 | 211-09267 | STRUCTURE BACKFILL, TYPE 4 | 133.00 | CYS |
| 0045 | 214-12237 | GEOTEXTILE FOR PAVEMENT TYPE 1B | 78890.00 | SYS |
| 0046 | 214-12243 | GEOTEXTILE FOR SUBGRADE TYPE 2A | 42614.00 | SYS |
| 0047 | 215-07043 | CHEMICAL MODIFICATION, SOILS | 16336.00 | SYS |
| 0048 | 301-12232 | COMPACTED AGGREGATE NO. 5 | 1888.00 | CYS |
| 0049 | 301-12233 | COMPACTED AGGREGATE NO. 8 | 95.40 | CYS |
| 0050 | 301-12234 | COMPACTED AGGREGATE NO. 53 | 8141.00 | CYS |
| 0051 | 302-06464 | SUBBASE FOR PCCP | 1162.00 | CYS |
| 0052 | 302-07455 | DENSE GRADED SUBBASE | 251.10 | CYS |
| 0053 | 303-01180 | COMPACTED AGGREGATE NO. 53 | 7223.00 | TON |
| 0054 | 304-07783 | HMA PATCHING, TYPE D | 188.00 | TON |
| 0055 | 304-07789 | WIDENING WITH HMA, TYPE D | 592.00 | TON |
| 0056 | 306-08034 | MILLING, ASPHALT, 1 1/2 IN. | 14167.00 | SYS |
| 0057 | 401-06264 | PROFILOGRAPH, HMA | 1.00 | LS |
| 0058 | 401-07328 | QC/QA-HMA, 3, 70, SURFACE, 9.5 mm | 566.00 | TON |
| 0059 | 401-07329 | QC/QA-HMA, 4, 70, SURFACE, 9.5 mm | 2640.00 | TON |
| 0060 | 401-07398 | QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm | 6476.00 | TON |
| 0061 | 401-07399 | QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm | 4446.00 | TON |
| 0062 | 401-07424 | QC/QA-HMA, 3, 64, BASE, 19.0 mm | 14502.00 | TON |
| 0063 | 401-08364 | QC/QA-HMA, 4, 64, BASE, 19.0 mm | 9660.00 | TON |
| 0064 | 401-10258 | JOINT ADHESIVE, SURFACE | 47698.00 | LFT |
| 0065 | 401-10259 | JOINT ADHESIVE, INTERMEDIATE | 47698.00 | LFT |
| 0066 | 401-11785 | LIQUID ASPHALT SEALANT | 47698.00 | LFT |

| | | | |
|------|-----------|---|---------------|
| 0067 | 401-12137 | QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm | 11459.00 TON |
| 0068 | 402-07787 | HMA WEDGE AND LEVEL, TYPE D | 1070.00 TON |
| 0069 | 402-10087 | HMA FOR TEMPORARY PAVEMENT, D | 3608.00 TON |
| 0070 | 402-10087 | HMA FOR TEMPORARY PAVEMENT, D | 3608.00 TON |
| 0071 | 402-10087 | HMA FOR TEMPORARY PAVEMENT, D | 1804.00 TON |
| 0072 | 406-05520 | ASPHALT FOR TACK COAT | 86.00 TON |
| 0073 | 410-09530 | QC/QA-HMA, 4, 76, SURFACE, 9.5 mm - SMA | 3362.00 TON |
| 0074 | 501-06321 | QC/QA-PCCP, 10 IN. | 4230.00 SYS |
| 0075 | 503-05240 | D-1 CONTRACTION JOINT | 2637.00 LFT |
| 0076 | 601-02241 | GUARDRAIL, REMOVE | 822.00 LFT |
| 0077 | 601-06246 | IMPACT ATTENUATOR, R2-W1, TL-3 | 2.00 EACH |
| 0078 | 601-12281 | GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING | 2938.00 LFT |
| 0079 | 601-12284 | GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING | 3138.00 LFT |
| 0080 | 601-12291 | GUARDRAIL MGS TRANSITION WITH CURB | 5.00 EACH |
| 0081 | 601-12292 | GUARDRAIL MGS TRANSITION WITHOUT CURB | 8.00 EACH |
| 0082 | 601-12294 | GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR | 3.00 EACH |
| 0083 | 601-94689 | GUARDRAIL, END TREATMENT, OS | 8.00 EACH |
| 0084 | 601-94690 | GUARDRAIL, END TREATMENT, MS | 2.00 EACH |
| 0085 | 602-01064 | CONCRETE BARRIER | 2455.00 LFT |
| 0086 | 602-06729 | BARRIER, DELINEATOR | 13.00 EACH |
| 0087 | 602-11938 | CONCRETE BARRIER, MODIFIED SECTION | 160.00 CYS |
| 0088 | 603-06045 | FENCE, CHAIN LINK, 48 IN. | 6793.00 LFT |
| 0089 | 604-04452 | LIMESTONE | 192078.00 CFT |
| 0090 | 604-05528 | HMA FOR SIDEWALK | 684.00 TON |
| 0091 | 604-08086 | CURB RAMP, CONCRETE | 519.00 SYS |
| 0092 | 604-12083 | DETECTABLE WARNING SURFACES | 79.00 SYS |
| 0093 | 604-95344 | HAND RAIL, PEDESTRIAN | 2319.00 LFT |
| 0094 | 605-06105 | CURB, INTEGRAL CONCRETE, MODIFIED | 1000.00 LFT |
| 0095 | 605-06120 | CURB, CONCRETE | 1516.00 LFT |
| 0096 | 605-06140 | CURB AND GUTTER, CONCRETE | 6909.00 LFT |
| 0097 | 605-06155 | CURB AND GUTTER, CONCRETE, MODIFIED | 639.00 LFT |
| 0098 | 605-06160 | CURB AND GUTTER, B, CONCRETE, MODIFIED | 6330.00 LFT |
| 0099 | 605-06255 | CENTER CURB, D CONCRETE | 291.00 SYS |
| 0100 | 606-11064 | MILLED PCCP CORRUGATIONS, CONVENTIONAL | 813.00 LFT |
| 0101 | 606-12399 | MILLED HMA CORRUGATIONS, CONVENTIONAL | 4541.00 LFT |
| 0102 | 609-06259 | REINFORCED CONCRETE BRIDGE APPROACH, 12 IN. | 1509.00 SYS |
| 0103 | 610-07487 | HMA FOR APPROACHES, TYPE B | 733.00 TON |
| 0104 | 610-09108 | PCCP FOR APPROACHES, 9 IN. | 472.00 SYS |
| 0105 | 615-06490 | RIGHT-OF-WAY MARKER | 61.00 EACH |
| 0106 | 615-06505 | MONUMENT, B | 15.00 EACH |
| 0107 | 615-06510 | MONUMENT, C | 6.00 EACH |
| 0108 | 615-06527 | MONUMENT, SECTION CORNER | 1.00 EACH |

| | | | |
|------|-----------|--|---------------|
| 0109 | 616-05688 | RIPRAP, CLASS 1 | 154.00 TON |
| 0110 | 616-06405 | RIPRAP, REVETMENT | 903.00 TON |
| 0111 | 616-12246 | GEOTEXTILE FOR RIPRAP TYPE 1A | 2925.00 SYS |
| 0112 | 621-01004 | MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 2.00 EACH |
| 0113 | 621-06545 | FERTILIZER | 3.00 TON |
| 0114 | 621-06554 | SEED MIXTURE U | 1389.00 LBS |
| 0115 | 621-06565 | MULCHING MATERIAL | 14.00 TON |
| 0116 | 621-06567 | WATER | 62.00 KGAL |
| 0117 | 621-06570 | TOPSOIL | 1274.00 CYS |
| 0118 | 621-06574 | SODDING | 780.00 SYS |
| 0119 | 621-06575 | SODDING, NURSERY | 15283.00 SYS |
| 0120 | 628-09403 | FIELD OFFICE, C | 24.00 MOS |
| 0121 | 701-06011 | DYNAMIC PILE LOAD TEST | 3.00 EACH |
| 0122 | 701-09557 | TEST PILE, DYNAMIC, PRODUCTION | 298.00 LFT |
| 0123 | 701-09559 | TEST PILE, DYNAMIC, RESTRIKE | 3.00 EACH |
| 0124 | 701-09739 | PILE SHOE, HP 12 X 53 | 115.00 EACH |
| 0125 | 701-12361 | PREBORED HOLE, 24 IN | 202.00 LFT |
| 0126 | 701-51195 | PILE, STEEL H HP 12 X 53 | 9789.00 LFT |
| 0127 | 702-02925 | WATERPROOFING MEMBRANE SYSTEM | 13542.00 SFT |
| 0128 | 702-04325 | TEMPORARY SHORING | 1.00 LS |
| 0129 | 702-51005 | CONCRETE, A, SUBSTRUCTURE | 425.10 CYS |
| 0130 | 702-51015 | CONCRETE, B, FOOTINGS | 354.50 CYS |
| 0131 | 702-51863 | FIELD DRILLED HOLE IN CONCRETE | 230.00 EACH |
| 0132 | 702-92857 | CONCRETE, C, SUBSTRUCTURE | 336.70 CYS |
| 0133 | 703-06029 | REINFORCING BARS, EPOXY COATED | 676771.00 LBS |
| 0134 | 703-97936 | THREADED TIE BAR ASSEMBLY, EPOXY COATED | 883.00 EACH |
| 0135 | 704-51002 | CONCRETE, C, SUPERSTRUCTURE | 1179.50 CYS |
| 0136 | 706-06372 | CONCRETE BRIDGE RAILING TRANSITION, TTX | 4.00 EACH |
| 0137 | 706-51025 | RAILING, CONCRETE C | 234.90 LFT |
| 0138 | 706-94947 | RAILING, CONCRETE C, MODIFIED | 84.00 CYS |
| 0139 | 707-09865 | STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 49 IN. | 2041.00 LFT |
| 0140 | 709-07733 | ANTI-GRAFFITI COAT | 1.00 LS |
| 0141 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0142 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0143 | 714-11303 | STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 10 FT. X 4 FT. | 150.00 LFT |
| 0144 | 715-04985 | VAULT | 2.00 EACH |
| 0145 | 715-05024 | PIPE, TYPE 2, CIRCULAR, 36 IN. | 1175.00 LFT |
| 0146 | 715-05048 | PIPE, TYPE 4, CIRCULAR, 6 IN. | 26901.00 LFT |
| 0147 | 715-05049 | PIPE, TYPE 4, CIRCULAR, 8 IN. | 7200.00 LFT |
| 0148 | 715-05053 | PIPE, UNDERDRAIN, OUTLET 6 IN. | 2000.00 LFT |
| 0149 | 715-05053 | PIPE, UNDERDRAIN, OUTLET 6 IN. | 2766.00 LFT |
| 0150 | 715-05149 | PIPE, TYPE 2, CIRCULAR, 12 IN. | 5105.00 LFT |

| | | | | |
|------|-----------|---------------------------------------|----------|------|
| 0151 | 715-05151 | PIPE, TYPE 2, CIRCULAR, 15 IN. | 388.00 | LFT |
| 0152 | 715-05152 | PIPE, TYPE 2, CIRCULAR, 18 IN. | 2882.00 | LFT |
| 0153 | 715-05154 | PIPE, TYPE 2, CIRCULAR, 24 IN. | 1654.00 | LFT |
| 0154 | 715-05156 | PIPE, TYPE 2, CIRCULAR, 30 IN. | 284.00 | LFT |
| 0155 | 715-05161 | PIPE, TYPE 2, CIRCULAR, 48 IN. | 1402.00 | LFT |
| 0156 | 715-05162 | PIPE, TYPE 2, CIRCULAR, 54 IN. | 1710.00 | LFT |
| 0157 | 715-05596 | PIPE EXTENSION, CIRCULAR, 18 IN. | 10.00 | LFT |
| 0158 | 715-06492 | CONCRETE ANCHOR, 54 IN. | 4.00 | EACH |
| 0159 | 715-09064 | VIDEO INSPECTION FOR PIPE | 13440.00 | LFT |
| 0160 | 715-46000 | PIPE END SECTION, DIAMETER 12 IN. | 3.00 | EACH |
| 0161 | 715-46020 | PIPE END SECTION, DIAMETER 24 IN. | 3.00 | EACH |
| 0162 | 715-46040 | PIPE END SECTION, DIAMETER 36 IN. | 1.00 | EACH |
| 0163 | 716-07633 | PIPE INSTALLATION, TRENCHLESS, 24 IN. | 100.00 | LFT |
| 0164 | 716-07726 | PIPE INSTALLATION, TRENCHLESS, 54 IN. | 100.00 | LFT |
| 0165 | 718-06528 | OUTLET PROTECTOR, 1 | 10.00 | EACH |
| 0166 | 718-06529 | OUTLET PROTECTOR, 2 | 5.00 | EACH |
| 0167 | 718-06531 | OUTLET PROTECTOR, 3 | 5.00 | EACH |
| 0168 | 718-06532 | VIDEO INSPECTION FOR UNDERDRAINS | 3000.00 | LFT |
| 0169 | 718-12305 | GEOTEXTILES FOR UNDERDRAIN, TYPE 1A | 34134.00 | SYS |
| 0170 | 718-52610 | AGGREGATE FOR UNDERDRAINS | 3643.00 | CYS |
| 0171 | 720-02442 | PIPE PLUG EXISTING | 10.00 | EACH |
| 0172 | 720-09768 | CATCH BASIN, TYPE HA5 | 19.00 | EACH |
| 0173 | 720-44000 | CASTING, ADJUST TO GRADE | 6.00 | EACH |
| 0174 | 720-45042 | INLET, HA5 | 4.00 | EACH |
| 0175 | 720-45145 | INLET, J10 MODIFIED | 2.00 | EACH |
| 0176 | 720-45155 | INLET, M10 MODIFIED | 6.00 | EACH |
| 0177 | 720-45235 | CATCH BASIN, E7 | 8.00 | EACH |
| 0178 | 720-45250 | CATCH BASIN, K10 | 9.00 | EACH |
| 0179 | 720-45265 | PIPE CATCH BASIN, 15 IN. | 5.00 | EACH |
| 0180 | 720-45410 | MANHOLE, C4 | 39.00 | EACH |
| 0181 | 720-45415 | MANHOLE, D4 | 2.00 | EACH |
| 0182 | 720-45430 | MANHOLE, G4 | 1.00 | EACH |
| 0183 | 720-90129 | MANHOLE, J2 | 1.00 | EACH |
| 0184 | 720-93409 | INLET, B15 MODIFIED | 18.00 | EACH |
| 0185 | 720-93411 | INLET, C15 MODIFIED | 4.00 | EACH |
| 0186 | 720-93501 | MANHOLE, L4 | 7.00 | EACH |
| 0187 | 720-94612 | MANHOLE, K4 | 6.00 | EACH |
| 0188 | 720-94713 | CATCH BASIN, C15 MODIFIED | 14.00 | EACH |
| 0189 | 720-95164 | CATCH BASIN, B15 MODIFIED | 5.00 | EACH |
| 0190 | 720-95422 | MANHOLE, J4 | 16.00 | EACH |
| 0191 | 720-98174 | INLET, B15 | 7.00 | EACH |
| 0192 | 720-99416 | CATCH BASIN, B15 | 27.00 | EACH |

| | | | |
|------|-----------|--|---------------|
| 0193 | 720-99417 | CATCH BASIN, C15 | 2.00 EACH |
| 0194 | 732-09163 | TEST | 12.00 EACH |
| 0195 | 732-09163 | TEST | 196.00 EACH |
| 0196 | 734-10240 | CUT-WALL, NO. | 12384.00 SFT |
| 0197 | 734-10240 | CUT-WALL, NO. | 14337.00 SFT |
| 0198 | 734-10240 | CUT-WALL, NO. | 3515.00 SFT |
| 0199 | 801-01093 | TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY | 16.00 EACH |
| 0200 | 801-03290 | CONSTRUCTION SIGN, C | 18.00 EACH |
| 0201 | 801-04308 | ROAD CLOSURE SIGN ASSEMBLY | 23.00 EACH |
| 0202 | 801-06207 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 125418.00 LFT |
| 0203 | 801-06539 | TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN | 1.00 LS |
| 0204 | 801-06539 | TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN | 1.00 LS |
| 0205 | 801-06625 | DETOUR ROUTE MARKER ASSEMBLY | 21.00 EACH |
| 0206 | 801-06640 | CONSTRUCTION SIGN, A | 67.00 EACH |
| 0207 | 801-06645 | CONSTRUCTION SIGN, B | 13.00 EACH |
| 0208 | 801-06710 | FLASHING ARROW SIGN | 60.00 DAY |
| 0209 | 801-06775 | MAINTAINING TRAFFIC | 1.00 LS |
| 0210 | 801-07023 | ENERGY ABSORBING TERMINAL, CZ, TL-2 | 24.00 EACH |
| 0211 | 801-07119 | BARRICADE, III-B | 873.00 LFT |
| 0212 | 801-07120 | BARRICADE, III, PERMANENT | 72.00 LFT |
| 0213 | 801-08401 | TEMPORARY TRAFFIC BARRIER, TYPE 2 | 16060.00 LFT |
| 0214 | 801-12348 | TEMPORARY WORKSITE SPEED DISPLAY ASSEMBLY | 4.00 EACH |
| 0215 | 802-04089 | SIGN, SHEET, REMOVE | 13.00 EACH |
| 0216 | 802-04893 | REFERENCE POST | 14.00 EACH |
| 0217 | 802-05701 | SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE | 572.00 LFT |
| 0218 | 802-05702 | SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE | 165.00 LFT |
| 0219 | 802-05703 | SIGN POST, SQUARE TYPE 3 REINFORCED ANCHOR BASE | 157.00 LFT |
| 0220 | 802-07057 | SIGN, PANEL, WITH LEGEND | 699.00 SFT |
| 0221 | 802-07059 | SIGN, SHEET, AND SUPPORTS, REMOVE | 47.00 EACH |
| 0222 | 802-07060 | SIGN, SHEET, RELOCATE | 5.00 EACH |
| 0223 | 802-07135 | CABLE SPAN SIGN STRUCTURE FOUNDATION, IV | 4.00 EACH |
| 0224 | 802-09577 | OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE E | 1.00 EACH |
| 0225 | 802-09838 | SIGN, SHEET, WITH LEGEND, 0.080 IN. | 154.00 SFT |
| 0226 | 802-09840 | SIGN, SHEET, WITH LEGEND, 0.100 IN. | 487.00 SFT |
| 0227 | 802-09842 | SIGN, SHEET, WITH LEGEND, 0.125 IN. | 109.00 SFT |
| 0228 | 802-11886 | CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 48 IN. | 1.00 EACH |
| 0229 | 802-12222 | WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A | 8.00 EACH |
| 0230 | 802-12223 | WIDE FLANGE SIGN POST SUPPORT FOUNDATION, B | 4.00 EACH |
| 0231 | 802-12224 | WIDE FLANGE SIGN POST SUPPORT FOUNDATION, C | 2.00 EACH |
| 0232 | 802-76095 | STRUCTURAL STEEL, BREAKAWAY | 4221.00 LBS |
| 0233 | 802-76125 | OVERHEAD SIGN STRUCTURE, CABLESPAN | 2.00 EACH |
| 0234 | 804-11921 | DELINEATOR POST FLEXIBLE, TYPE II | 949.00 EACH |

| | | | |
|------|-----------|--|--------------|
| 0235 | 805-01300 | TRAFFIC SIGNAL EQUIPMENT, REMOVE | 4.00 EACH |
| 0236 | 805-01815 | SIGNAL POLE FOUNDATION, 36 IN. X 144 IN. | 10.00 EACH |
| 0237 | 805-01844 | CONDUIT, STEEL, GALVANIZED, 2 IN. | 4138.00 LFT |
| 0238 | 805-02087 | TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT | 1.00 LS |
| 0239 | 805-02150 | PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN. | 24.00 EACH |
| 0240 | 805-02445 | CONTROLLER AND CABINET, P1 | 2.00 EACH |
| 0241 | 805-02728 | CONDUIT, PVC, 1 IN. | 450.00 LFT |
| 0242 | 805-04973 | CONDUIT | 10.00 LFT |
| 0243 | 805-04973 | CONDUIT | 180.00 LFT |
| 0244 | 805-04973 | CONDUIT | 3400.00 LFT |
| 0245 | 805-04973 | CONDUIT | 1750.00 LFT |
| 0246 | 805-04973 | CONDUIT | 250.00 LFT |
| 0247 | 805-04973 | CONDUIT | 7360.00 LFT |
| 0248 | 805-06595 | CONDUIT, PVC, 2 IN. | 280.00 LFT |
| 0249 | 805-11744 | HANDHOLE SIGNAL TYPE 2 | 34.00 EACH |
| 0250 | 805-11763 | WIM STATION, REBUILD | 1.00 LS |
| 0251 | 805-11817 | PEDESTRIAN PUSH BUTTON, APS | 4.00 EACH |
| 0252 | 805-78205 | TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN. | 25.00 EACH |
| 0253 | 805-78225 | TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN. | 4.00 EACH |
| 0254 | 805-78415 | SPAN, CATENARY, AND TETHER | 8.00 EACH |
| 0255 | 805-78420 | DISCONNECT HANGER | 8.00 EACH |
| 0256 | 805-78445 | SIGNAL SERVICE | 2.00 EACH |
| 0257 | 805-78467 | SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA | 94.00 LFT |
| 0258 | 805-78480 | SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA | 1398.00 LFT |
| 0259 | 805-78485 | SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA | 8743.00 LFT |
| 0260 | 805-78490 | SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA | 7751.00 LFT |
| 0261 | 805-78510 | SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA | 10064.00 LFT |
| 0262 | 805-78746 | PREFORMED LOOP DETECTORS | 5680.00 LFT |
| 0263 | 805-78785 | SIGNAL DETECTOR HOUSING | 22.00 EACH |
| 0264 | 805-78925 | CONTROLLER CABINET FOUNDATION, P1 | 2.00 EACH |
| 0265 | 805-81032 | SIGNAL POLE, STEEL STRAIN, 30 FT | 10.00 EACH |
| 0266 | 805-86898 | CONDUIT, STEEL, GALVANIZED, 0.75 IN. | 1576.00 LFT |
| 0267 | 805-92504 | LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL | 71.00 EACH |
| 0268 | 807-02191 | HANDHOLE LIGHTING | 10.00 EACH |
| 0269 | 807-02194 | SERVICE POINT II MODIFIED | 2.00 EACH |
| 0270 | 807-02426 | WIRE, THW, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C | 5145.00 LFT |
| 0271 | 807-02782 | LUMINAIRE MAST ARM 12 FT | 4.00 EACH |
| 0272 | 807-03950 | LUMINAIRE ORNAMENTAL | 42.00 EACH |
| 0273 | 807-03950 | LUMINAIRE ORNAMENTAL | 40.00 EACH |
| 0274 | 807-03951 | LIGHT POLE ORNAMENTAL | 38.00 EACH |
| 0275 | 807-04651 | WIRE | 3680.00 LFT |
| 0276 | 807-05073 | JUNCTION BOX | 10.00 EACH |

| | | | |
|------|-----------|--|--------------|
| 0277 | 807-05073 | JUNCTION BOX | 4.00 EACH |
| 0278 | 807-06592 | CONDUIT, STEEL, GALVANIZED, 2 IN. | 2415.00 LFT |
| 0279 | 807-07580 | WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C | 8275.00 LFT |
| 0280 | 807-11980 | LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 30 IN. DIA X 96 IN. | 38.00 EACH |
| 0281 | 807-12206 | LUMINAIRE, UNDERPASS | 6.00 EACH |
| 0282 | 807-78590 | HANDHOLE | 7.00 EACH |
| 0283 | 807-82056 | CIRCUIT INSTALLATION, UNDERPASS, 6 LUMINAIRES | 1.00 EACH |
| 0284 | 807-86805 | SERVICE POINT, I | 1.00 EACH |
| 0285 | 807-86889 | CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C | 3740.00 LFT |
| 0286 | 807-86910 | CONNECTOR KIT, UNFUSED | 42.00 EACH |
| 0287 | 807-86915 | CONNECTOR KIT, FUSED | 42.00 EACH |
| 0288 | 807-86920 | MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED | 87.00 EACH |
| 0289 | 807-86925 | MULTIPLE COMPRESSION FITTING, WATERPROOFED | 36.00 EACH |
| 0290 | 807-86930 | INSULATION LINK, NON-WATERPROOFED | 84.00 EACH |
| 0291 | 807-86935 | INSULATION LINK, WATERPROOFED | 40.00 EACH |
| 0292 | 807-86950 | SIGN, UNDERPASS AND ROADWAY LIGHTING LOCATION IDENTIFICATION | 48.00 EACH |
| 0293 | 807-86955 | CABLE-DUCT MARKER | 8.00 EACH |
| 0294 | 807-86955 | CABLE-DUCT MARKER | 4.00 EACH |
| 0295 | 807-86955 | CABLE-DUCT MARKER | 6.00 EACH |
| 0296 | 808-01428 | TEMPORARY TRANSVERSE MARKINGS WHITE STOP LINE 24 IN | 516.00 LFT |
| 0297 | 808-03439 | TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN. | 1254.00 LFT |
| 0298 | 808-06701 | LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN. | 408.00 LFT |
| 0299 | 808-06702 | LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN. | 2889.00 LFT |
| 0300 | 808-06703 | LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 14986.00 LFT |
| 0301 | 808-06705 | LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN. | 4999.00 LFT |
| 0302 | 808-10031 | LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN. | 57.00 LFT |
| 0303 | 808-10033 | LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN. | 1275.00 LFT |
| 0304 | 808-10034 | LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN. | 1430.00 LFT |
| 0305 | 808-10051 | TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN. | 64.00 LFT |
| 0306 | 808-10054 | LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN. | 251.00 LFT |
| 0307 | 808-10094 | TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 12 IN. | 384.00 LFT |
| 0308 | 808-11481 | LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN. | 310.00 LFT |
| 0309 | 808-11482 | LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN. | 1210.00 LFT |
| 0310 | 808-11493 | LINE, THERMOPLASTIC, DOTTED, YELLOW, 4 IN. | 127.00 LFT |
| 0311 | 808-11548 | LINE, MULTI-COMPONENT, DOTTED, YELLOW, 4 IN. | 85.00 LFT |
| 0312 | 808-11698 | TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 27 IN. | 48.00 LFT |
| 0313 | 808-12032 | GROOVING FOR PAVEMENT MARKINGS | 47368.00 LFT |
| 0314 | 808-75240 | LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN. | 76.00 LFT |
| 0315 | 808-75245 | LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 15406.00 LFT |
| 0316 | 808-75260 | TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN. | 268.00 LFT |
| 0317 | 808-75278 | TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN. | 134.00 LFT |
| 0318 | 808-75297 | TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN. | 294.00 LFT |

| | | | |
|------|-----------|---|-------------|
| 0319 | 808-75320 | PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW | 40.00 EACH |
| 0320 | 808-75325 | PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY | 7.00 EACH |
| 0321 | 808-75996 | SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 586.00 EACH |
| 0322 | 808-75998 | SNOWPLOWABLE RAISED PAVEMENT MARKER | 586.00 EACH |
| 0323 | 808-92027 | LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN. | 473.00 LFT |
| 0324 | 809-04652 | SERVICE POINT | 1.00 EACH |

Call: 260

Contract: R -41827-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line

| Item No | Item Code | Description | Quantity | Unit |
|----------------|------------------|--|-----------------|-------------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0005 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0006 | 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 1.00 | DOL |
| 0007 | 109-11362 | QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES | 1.00 | DOL |
| 0008 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0009 | 201-52370 | CLEARING RIGHT OF WAY | 1.00 | LS |
| 0010 | 202-99187 | FENCE, FARM FIELD, REMOVE | 50.00 | LFT |
| 0011 | 203-02000 | EXCAVATION, COMMON | 1.00 | CYS |
| 0012 | 205-11626 | PUMP AROUND | 4.00 | EACH |
| 0013 | 205-12108 | STORM WATER MANAGEMENT BUDGET | 16775.00 | DOL |
| 0014 | 205-12109 | SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1 | 1.00 | LS |
| 0015 | 214-12244 | GEOTEXTILE FOR SUBGRADE TYPE 2B | 6.00 | SYS |
| 0016 | 301-12232 | COMPACTED AGGREGATE NO. 5 | 1.00 | CYS |
| 0017 | 301-12234 | COMPACTED AGGREGATE NO. 53 | 1.00 | CYS |
| 0018 | 601-06035 | GUARDRAIL, RESET | 50.00 | LFT |
| 0019 | 603-06040 | FENCE, FARM FIELD, 47 IN. | 50.00 | LFT |
| 0020 | 616-05689 | RIPRAP, CLASS 2 | 210.00 | TON |
| 0021 | 616-06405 | RIPRAP, REVETMENT | 126.00 | TON |
| 0022 | 616-12246 | GEOTEXTILE FOR RIPRAP TYPE 1A | 360.00 | SYS |
| 0023 | 621-01004 | MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 3.00 | EACH |
| 0024 | 621-06559 | MULCHED SEEDING R | 3145.00 | SYS |
| 0025 | 702-51005 | CONCRETE, A, SUBSTRUCTURE | 4.00 | CYS |
| 0026 | 725-10227 | LINER PIPE, THERMOPLASTIC, CIRCULAR, 18.9-19.0 SFT | 380.00 | LFT |
| 0027 | 725-11022 | LINER PIPE, THERMOPLASTIC, DEFORMED, 22.4-23.8 SFT | 319.00 | LFT |
| 0028 | 725-11036 | LINER PIPE, THERMOPLASTIC, CIRCULAR, 9.6-9.7 SFT | 240.00 | LFT |
| 0029 | 801-06640 | CONSTRUCTION SIGN, A | 28.00 | EACH |
| 0030 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |

Call: 270

Contract: R -41831-A

Section No.: 1

SMALL STRUCTURE PIPE LINING

| Line | | | | |
|---------|-----------|--|----------|------|
| Item No | Item Code | Description | Quantity | Unit |
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0005 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0006 | 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 1.00 | DOL |
| 0007 | 109-11362 | QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES | 1.00 | DOL |
| 0008 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0009 | 201-01015 | CLEARING AND GRUBBING | 1.00 | LS |
| 0010 | 201-52370 | CLEARING RIGHT OF WAY | 1.00 | LS |
| 0011 | 202-96133 | PIPE, REMOVE | 31.00 | LFT |
| 0012 | 203-02000 | EXCAVATION, COMMON | 570.00 | CYS |
| 0013 | 205-11626 | PUMP AROUND | 3.00 | EACH |
| 0014 | 205-12108 | STORM WATER MANAGEMENT BUDGET | 5239.00 | DOL |
| 0015 | 205-12109 | SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1 | 1.00 | LS |
| 0016 | 211-09265 | STRUCTURE BACKFILL, TYPE 2 | 570.00 | CYS |
| 0017 | 616-05689 | RIPRAP, CLASS 2 | 56.00 | TON |
| 0018 | 616-06405 | RIPRAP, REVETMENT | 168.00 | TON |
| 0019 | 616-06451 | RIPRAP, UNIFORM | 12.00 | TON |
| 0020 | 616-12246 | GEOTEXTILE FOR RIPRAP TYPE 1A | 67.00 | SYS |
| 0021 | 616-12248 | GEOTEXTILE FOR RIPRAP TYPE 2A | 121.00 | SYS |
| 0022 | 621-06559 | MULCHED SEEDING R | 2593.20 | SYS |
| 0023 | 621-06567 | WATER | 2.00 | KGAL |
| 0024 | 621-06574 | SODDING | 484.00 | SYS |
| 0025 | 702-51005 | CONCRETE, A, SUBSTRUCTURE | 39.90 | CYS |
| 0026 | 702-51015 | CONCRETE, B, FOOTINGS | 54.90 | CYS |
| 0027 | 703-06028 | REINFORCING BARS | 11395.00 | LBS |
| 0028 | 725-10226 | LINER PIPE, THERMOPLASTIC, CIRCULAR, 13.9-14.1 SFT | 245.33 | LFT |
| 0029 | 725-11042 | LINER PIPE, THERMOPLASTIC, CIRCULAR, 27.7-28.3 SFT | 224.33 | LFT |
| 0030 | 725-11860 | PIPE LINER CURED-IN-PLACE MIN AREA 19.6 SFT | 52.00 | LFT |
| 0031 | 801-04308 | ROAD CLOSURE SIGN ASSEMBLY | 2.00 | EACH |
| 0032 | 801-06625 | DETOUR ROUTE MARKER ASSEMBLY | 109.00 | EACH |
| 0033 | 801-06640 | CONSTRUCTION SIGN, A | 28.00 | EACH |
| 0034 | 801-06645 | CONSTRUCTION SIGN, B | 6.00 | EACH |
| 0035 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0036 | 801-07118 | BARRICADE, III-A | 48.00 | LFT |

| | | | | |
|------|-----------|--------------------------|--------|------|
| 0037 | 801-07119 | BARRICADE, III-B | 48.00 | LFT |
| 0038 | 801-12042 | TRUCK MOUNTED ATTENUATOR | 120.00 | DAY |
| 0039 | 804-06725 | DELINEATOR WITH POST, D1 | 2.00 | EACH |

Call: 280

Contract: R -41839-A

Section No.: 1 INTERSECTION IMPROVEMENTS WITH NEW SIGNALS

Line

| Item No | Item Code | Description | Quantity | Unit |
|----------------|------------------|--|-----------------|-------------|
| 0001 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0002 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0003 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0004 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0005 | 109-09489 | PAYMENT ADJUSTMENT PG ASPHALT BINDER | 1.00 | DOL |
| 0006 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0007 | 202-02240 | PAVEMENT REMOVAL | 975.00 | SYS |
| 0008 | 202-02273 | CENTER CURB, CONCRETE, REMOVE | 11.00 | SYS |
| 0009 | 203-02000 | EXCAVATION, COMMON | 85.00 | CYS |
| 0010 | 301-12234 | COMPACTED AGGREGATE NO. 53 | 85.00 | CYS |
| 0011 | 304-07490 | HMA PATCHING, TYPE B | 5.00 | TON |
| 0012 | 601-12281 | GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING | 181.25 | LFT |
| 0013 | 601-12294 | GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR | 1.00 | EACH |
| 0014 | 601-94689 | GUARDRAIL, END TREATMENT, OS | 1.00 | EACH |
| 0015 | 605-02493 | CURB, ISLAND CONCRETE | 485.00 | SYS |
| 0016 | 605-06145 | CURB AND GUTTER, B, CONCRETE | 275.00 | LFT |
| 0017 | 605-06200 | CENTER CURB, A CONCRETE | 4.00 | LFT |
| 0018 | 801-06640 | CONSTRUCTION SIGN, A | 9.00 | EACH |
| 0019 | 801-06645 | CONSTRUCTION SIGN, B | 3.00 | EACH |
| 0020 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0021 | 805-01842 | HANDHOLE SIGNAL TYPE 1 | 9.00 | EACH |
| 0022 | 805-02445 | CONTROLLER AND CABINET, P1 | 1.00 | EACH |
| 0023 | 805-02645 | SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN. | 3.00 | EACH |
| 0024 | 805-08214 | CONDUIT, PVC, 2 IN. SCHEDULE 40 | 500.00 | LFT |
| 0025 | 805-09451 | SIGNAL POLE, PEDESTAL, 15 FT | 2.00 | EACH |
| 0026 | 805-09539 | LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL | 4.00 | EACH |
| 0027 | 805-11375 | SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 25 FT. | 1.00 | EACH |
| 0028 | 805-11376 | SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 30 FT. | 1.00 | EACH |
| 0029 | 805-11382 | SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 60 FT. | 1.00 | EACH |
| 0030 | 805-11383 | SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, A | 2.00 | EACH |
| 0031 | 805-11384 | SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, B | 1.00 | EACH |
| 0032 | 805-11813 | CONDUIT, PVC, 2 IN. SCHEDULE 80 | 950.00 | LFT |
| 0033 | 805-78205 | TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN. | 8.00 | EACH |

| | | | |
|------|-----------|--|-------------|
| 0034 | 805-78445 | SIGNAL SERVICE | 1.00 EACH |
| 0035 | 805-78467 | SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA | 50.00 LFT |
| 0036 | 805-78470 | SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA | 2000.00 LFT |
| 0037 | 805-78485 | SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA | 800.00 LFT |
| 0038 | 805-78490 | SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA | 525.00 LFT |
| 0039 | 805-78510 | SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA | 2300.00 LFT |
| 0040 | 805-78785 | SIGNAL DETECTOR HOUSING | 5.00 EACH |
| 0041 | 805-78795 | SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT | 580.00 LFT |
| 0042 | 808-06723 | PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW | 2.00 EACH |
| 0043 | 808-10031 | LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN. | 200.00 LFT |
| 0044 | 808-10033 | LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN. | 100.00 LFT |
| 0045 | 808-10034 | LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN. | 700.00 LFT |
| 0046 | 808-10043 | LINE, MULTI-COMPONENT, SOLID, WHITE, 24 IN. | 72.00 LFT |

Call: 380

Contract: RS-38562-A

Section No.: 1 ASPHALT RESURFACE

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|--|----------|------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08440 | QUALITY ADJUSTMENTS, HMA | 1.00 | DOL |
| 0005 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0006 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0007 | 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 1.00 | DOL |
| 0008 | 109-09377 | QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS | 2.00 | DOL |
| 0009 | 109-09489 | PAYMENT ADJUSTMENT PG ASPHALT BINDER | 1.00 | DOL |
| 0010 | 109-11362 | QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES | 1.00 | DOL |
| 0011 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0012 | 201-52370 | CLEARING RIGHT OF WAY | 1.00 | LS |
| 0013 | 202-93741 | GUARDRAIL, END TREATMENT, REMOVE | 10.00 | EACH |
| 0014 | 203-02000 | EXCAVATION, COMMON | 514.00 | CYS |
| 0015 | 203-02010 | EXCAVATION, ROCK | 62.00 | CYS |
| 0016 | 203-02070 | BORROW | 1378.00 | CYS |
| 0017 | 205-11626 | PUMP AROUND | 1.00 | EACH |
| 0018 | 205-12108 | STORM WATER MANAGEMENT BUDGET | 31418.00 | DOL |
| 0019 | 205-12109 | SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1 | 1.00 | LS |
| 0020 | 207-08264 | SUBGRADE TREATMENT, TYPE II | 612.00 | SYS |
| 0021 | 207-09935 | SUBGRADE TREATMENT, TYPE IC | 768.00 | SYS |
| 0022 | 207-12498 | SUBGRADE TREATMENT, TYPE ID | 6709.00 | SYS |
| 0023 | 211-09265 | STRUCTURE BACKFILL, TYPE 2 | 177.00 | CYS |

| | | | | |
|------|-----------|---|-----------|------|
| 0024 | 211-09268 | STRUCTURE BACKFILL, TYPE 5 | 208.00 | CYS |
| 0025 | 214-11796 | GEOGRID, TYPE IB | 92.00 | SYS |
| 0026 | 301-12232 | COMPACTED AGGREGATE NO. 5 | 19.00 | CYS |
| 0027 | 301-12233 | COMPACTED AGGREGATE NO. 8 | 14.00 | CYS |
| 0028 | 301-12234 | COMPACTED AGGREGATE NO. 53 | 51.00 | CYS |
| 0029 | 302-07455 | DENSE GRADED SUBBASE | 10.00 | CYS |
| 0030 | 303-01180 | COMPACTED AGGREGATE NO. 53 | 6976.00 | TON |
| 0031 | 304-07490 | HMA PATCHING, TYPE B | 2609.00 | TON |
| 0032 | 306-08033 | MILLING, ASPHALT, 1 IN. | 137414.00 | SYS |
| 0033 | 306-08034 | MILLING, ASPHALT, 1 1/2 IN. | 17746.00 | SYS |
| 0034 | 306-08043 | MILLING, TRANSITION | 1745.00 | SYS |
| 0035 | 306-08432 | MILLING, APPROACH | 15288.00 | SYS |
| 0036 | 401-07321 | QC/QA-HMA, 2, 64, SURFACE, 9.5 mm | 16878.00 | TON |
| 0037 | 401-07390 | QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm | 69.00 | TON |
| 0038 | 401-07423 | QC/QA-HMA, 2, 64, BASE, 19.0 mm | 170.00 | TON |
| 0039 | 401-10258 | JOINT ADHESIVE, SURFACE | 84131.00 | LFT |
| 0040 | 401-10259 | JOINT ADHESIVE, INTERMEDIATE | 370.00 | LFT |
| 0041 | 401-11785 | LIQUID ASPHALT SEALANT | 136033.00 | LFT |
| 0042 | 401-12169 | INERTIAL PROFILER, HMA | 1.00 | LS |
| 0043 | 406-05520 | ASPHALT FOR TACK COAT | 52.00 | TON |
| 0044 | 601-02241 | GUARDRAIL, REMOVE | 3916.00 | LFT |
| 0045 | 604-06070 | SIDEWALK, CONCRETE | 176.00 | SYS |
| 0046 | 604-08086 | CURB RAMP, CONCRETE | 145.00 | SYS |
| 0047 | 604-12083 | DETECTABLE WARNING SURFACES | 16.00 | SYS |
| 0048 | 605-06120 | CURB, CONCRETE | 255.00 | LFT |
| 0049 | 605-06140 | CURB AND GUTTER, CONCRETE | 304.00 | LFT |
| 0050 | 606-12399 | MILLED HMA CORRUGATIONS, CONVENTIONAL | 58853.00 | LFT |
| 0051 | 610-07487 | HMA FOR APPROACHES, TYPE B | 2612.00 | TON |
| 0052 | 610-08446 | PCCP FOR APPROACHES, 6 IN. | 57.00 | SYS |
| 0053 | 611-08232 | MAILBOX ASSEMBLY, RESET SINGLE | 7.00 | EACH |
| 0054 | 615-06490 | RIGHT-OF-WAY MARKER | 6.00 | EACH |
| 0055 | 615-06505 | MONUMENT, B | 2.00 | EACH |
| 0056 | 615-06520 | MONUMENT, RE-ESTABLISH | 103.00 | EACH |
| 0057 | 616-05688 | RIPRAP, CLASS 1 | 72.00 | TON |
| 0058 | 616-06405 | RIPRAP, REVETMENT | 20.00 | TON |
| 0059 | 616-06451 | RIPRAP, UNIFORM | 19.00 | TON |
| 0060 | 616-12246 | GEOTEXTILE FOR RIPRAP TYPE 1A | 199.00 | SYS |
| 0061 | 621-01004 | MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 4.00 | EACH |
| 0062 | 621-06545 | FERTILIZER | 1.00 | TON |
| 0063 | 621-06554 | SEED MIXTURE U | 150.00 | LBS |
| 0064 | 621-06560 | MULCHED SEEDING U | 1638.00 | SYS |
| 0065 | 621-06565 | MULCHING MATERIAL | 1.50 | TON |

| | | | | |
|------|-----------|--|-----------|------|
| 0066 | 621-06737 | SEED MIXTURE, EMERGENT WETLAND | 1.00 | LBS |
| 0067 | 628-09403 | FIELD OFFICE, C | 8.00 | MOS |
| 0068 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 2.00 | EACH |
| 0069 | 702-51015 | CONCRETE, B, FOOTINGS | 31.00 | CYS |
| 0070 | 714-11695 | STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 8 FT. X 5 FT. | 56.00 | LFT |
| 0071 | 715-05121 | PIPE, TYPE 1, CIRCULAR, 18 IN. | 88.00 | LFT |
| 0072 | 715-05149 | PIPE, TYPE 2, CIRCULAR, 12 IN. | 17.00 | LFT |
| 0073 | 715-05151 | PIPE, TYPE 2, CIRCULAR, 15 IN. | 123.00 | LFT |
| 0074 | 715-05168 | PIPE, TYPE 3, CIRCULAR, 12 IN. | 42.00 | LFT |
| 0075 | 715-05169 | PIPE, TYPE 3, CIRCULAR, 15 IN. | 74.00 | LFT |
| 0076 | 715-05229 | PIPE, TYPE 1, DEFORMED, MIN. AREA 1.8 SFT | 46.00 | LFT |
| 0077 | 715-05237 | PIPE, TYPE 1, DEFORMED, MIN. AREA 6.4 SFT | 40.00 | LFT |
| 0078 | 715-08305 | HMA FOR STRUCTURE INSTALLATION, TYPE B | 65.00 | TON |
| 0079 | 715-46000 | PIPE END SECTION, DIAMETER 12 IN. | 5.00 | EACH |
| 0080 | 715-46005 | PIPE END SECTION, DIAMETER 15 IN. | 3.00 | EACH |
| 0081 | 715-46010 | PIPE END SECTION, DIAMETER 18 IN. | 4.00 | EACH |
| 0082 | 720-44000 | CASTING, ADJUST TO GRADE | 2.00 | EACH |
| 0083 | 720-45030 | INLET, E7 | 1.00 | EACH |
| 0084 | 720-45605 | STRUCTURE, MANHOLE, RECONSTRUCTED | 9.00 | LFT |
| 0085 | 720-94840 | CASTING, WATER VALVE, ADJUST TO GRADE | 3.00 | EACH |
| 0086 | 720-98174 | INLET, B15 | 1.00 | EACH |
| 0087 | 801-04308 | ROAD CLOSURE SIGN ASSEMBLY | 6.00 | EACH |
| 0088 | 801-06203 | TEMPORARY PAVEMENT MARKING, 4 IN. | 5772.00 | LFT |
| 0089 | 801-06625 | DETOUR ROUTE MARKER ASSEMBLY | 20.00 | EACH |
| 0090 | 801-06640 | CONSTRUCTION SIGN, A | 61.00 | EACH |
| 0091 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0092 | 801-07118 | BARRICADE, III-A | 48.00 | LFT |
| 0093 | 801-07119 | BARRICADE, III-B | 96.00 | LFT |
| 0094 | 808-06712 | LINE, PAINT, BROKEN, YELLOW, 4 IN. | 9040.00 | LFT |
| 0095 | 808-06713 | LINE, PAINT, SOLID, WHITE, 4 IN. | 112091.00 | LFT |
| 0096 | 808-06714 | LINE, PAINT, SOLID, YELLOW, 4 IN. | 62116.00 | LFT |
| 0097 | 808-06726 | TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN. | 102.00 | LFT |
| 0098 | 808-09381 | RETRO-REFLECTIVITY TESTING | 1.00 | LS |
| 0099 | 808-75100 | TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 6 IN. | 496.00 | LFT |
| 0100 | 808-75140 | PAVEMENT MESSAGE MARKING, PAINT, R X R | 1.00 | EACH |
| 0101 | 808-75996 | SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 1244.00 | EACH |
| 0102 | 808-75998 | SNOWPLOWABLE RAISED PAVEMENT MARKER | 2.00 | EACH |

Call: 394

Contract: RS-39272-A

Section No.: 1 CONCRETE PAVEMENT RESTORATION

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|--|-----------|------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08440 | QUALITY ADJUSTMENTS, HMA | 1.00 | DOL |
| 0005 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0006 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0007 | 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 1.00 | DOL |
| 0008 | 109-09377 | QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS | 1.00 | DOL |
| 0009 | 109-09489 | PAYMENT ADJUSTMENT PG ASPHALT BINDER | 1.00 | DOL |
| 0010 | 109-12573 | SPECIAL MAINTENANCE | 75000.00 | DOL |
| 0011 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0012 | 202-02240 | PAVEMENT REMOVAL | 1349.00 | SYS |
| 0013 | 202-62420 | BRIDGE RAILING, REMOVE | 315.00 | LFT |
| 0014 | 202-90277 | DETECTOR HOUSING, REMOVE | 5.00 | EACH |
| 0015 | 202-94954 | BARRIER WALL, CONCRETE, REMOVE | 2670.00 | LFT |
| 0016 | 203-02000 | EXCAVATION, COMMON | 167.00 | CYS |
| 0017 | 207-09935 | SUBGRADE TREATMENT, TYPE IC | 908.00 | SYS |
| 0018 | 207-09935 | SUBGRADE TREATMENT, TYPE IC | 12858.00 | SYS |
| 0019 | 213-09269 | FLOWABLE BACKFILL, NON-REMOVABLE | 65.00 | CYS |
| 0020 | 302-06464 | SUBBASE FOR PCCP | 3683.00 | CYS |
| 0021 | 302-07455 | DENSE GRADED SUBBASE | 226.00 | CYS |
| 0022 | 304-07491 | HMA PATCHING, TYPE C | 1422.00 | TON |
| 0023 | 304-07783 | HMA PATCHING, TYPE D | 33.00 | TON |
| 0024 | 306-08034 | MILLING, ASPHALT, 1 1/2 IN. | 108094.00 | SYS |
| 0025 | 306-08036 | MILLING, ASPHALT, 2 IN. | 3096.00 | SYS |
| 0026 | 306-08038 | MILLING, ASPHALT, 4 IN. | 4618.00 | SYS |
| 0027 | 401-06264 | PROFILOGRAPH, HMA | 1.00 | LS |
| 0028 | 401-07328 | QC/QA-HMA, 3, 70, SURFACE, 9.5 mm | 8606.00 | TON |
| 0029 | 401-07335 | QC/QA-HMA, 4, 76, SURFACE, 9.5 mm | 707.00 | TON |
| 0030 | 401-10258 | JOINT ADHESIVE, SURFACE | 64914.00 | LFT |
| 0031 | 401-11785 | LIQUID ASPHALT SEALANT | 64914.00 | LFT |
| 0032 | 402-10086 | HMA FOR TEMPORARY PAVEMENT, C | 472.00 | TON |
| 0033 | 406-05520 | ASPHALT FOR TACK COAT | 30.00 | TON |
| 0034 | 503-05310 | TERMINAL JOINT | 5450.00 | LFT |
| 0035 | 506-06333 | PCCP PATCHING, FULL DEPTH | 14731.00 | SYS |
| 0036 | 507-07505 | RETROFIT LOAD TRANSFER | 5418.00 | EACH |
| 0037 | 507-08271 | JOINTS IN PCCP, FILLED | 4941.00 | LFT |
| 0038 | 507-08272 | JOINTS IN PCCP, SAW AND SEAL | 12.00 | LFT |
| 0039 | 507-12191 | JOINT REPAIR, PARTIAL DEPTH | 16472.00 | SFT |
| 0040 | 507-12192 | JOINT REPAIR, BOTTOM-HALF | 1648.00 | SFT |
| 0041 | 601-03492 | GUARDRAIL MISCELLANEOUS MATERIAL AND LABOR FOR REPAIR | 1.00 | LS |

| | | | |
|------|-----------|---|--------------|
| 0042 | 601-06248 | IMPACT ATTENUATOR, R2-W3, TL-3 | 1.00 EACH |
| 0043 | 602-01064 | CONCRETE BARRIER | 2670.00 LFT |
| 0044 | 602-06729 | BARRIER, DELINEATOR | 206.00 EACH |
| 0045 | 605-02278 | CURB, REMOVE | 370.00 LFT |
| 0046 | 605-06121 | CURB, CONCRETE B | 370.00 LFT |
| 0047 | 609-08579 | REINFORCED CONCRETE BRIDGE APPROACH, 16 IN. | 1356.00 SYS |
| 0048 | 628-09403 | FIELD OFFICE, C | 12.00 MOS |
| 0049 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 1.00 EACH |
| 0050 | 702-51863 | FIELD DRILLED HOLE IN CONCRETE | 1221.00 EACH |
| 0051 | 703-06029 | REINFORCING BARS, EPOXY COATED | 89419.00 LBS |
| 0052 | 706-09959 | RAILING, CONCRETE FT | 315.00 LFT |
| 0053 | 706-11620 | CONCRETE BRIDGE RAILING TRANSITION, TFC | 2.00 EACH |
| 0054 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0055 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0056 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0057 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0058 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0059 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0060 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0061 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0062 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0063 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0064 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0065 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0066 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0067 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0068 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0069 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0070 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0071 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0072 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0073 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0074 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0075 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0076 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0077 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0078 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0079 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0080 | 710-09158 | PATCHING CONCRETE STRUCTURES | 34.00 SFT |
| 0081 | 720-44000 | CASTING, ADJUST TO GRADE | 2.00 EACH |
| 0082 | 722-51401 | BRIDGE DECK PATCHING, FULL DEPTH | 8550.00 SFT |
| 0083 | 722-51852 | BRIDGE DECK PATCHING, PARTIAL DEPTH | 24676.00 SFT |

| | | | | |
|------|-----------|---|-----------|------|
| 0084 | 724-12103 | PRE-COMPRESSED FOAM JOINT | 320.00 | LFT |
| 0085 | 738-09456 | POLYMERIC CONCRETE BRIDGE DECK OVERLAY | 54718.00 | SYS |
| 0086 | 801-01093 | TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY | 30.00 | EACH |
| 0087 | 801-03290 | CONSTRUCTION SIGN, C | 2.00 | EACH |
| 0088 | 801-04308 | ROAD CLOSURE SIGN ASSEMBLY | 34.00 | EACH |
| 0089 | 801-06201 | TEMPORARY PANEL SIGNS | 8102.00 | SFT |
| 0090 | 801-06202 | TEMPORARY PANEL SIGN SUPPORTS | 2290.00 | LFT |
| 0091 | 801-06203 | TEMPORARY PAVEMENT MARKING, 4 IN. | 398438.00 | LFT |
| 0092 | 801-06625 | DETOUR ROUTE MARKER ASSEMBLY | 171.00 | EACH |
| 0093 | 801-06640 | CONSTRUCTION SIGN, A | 81.00 | EACH |
| 0094 | 801-06710 | FLASHING ARROW SIGN | 211.00 | DAY |
| 0095 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0096 | 801-07118 | BARRICADE, III-A | 264.00 | LFT |
| 0097 | 801-08401 | TEMPORARY TRAFFIC BARRIER, TYPE 2 | 23030.00 | LFT |
| 0098 | 801-08403 | TEMPORARY TRAFFIC BARRIER TYPE 4 | 33806.00 | LFT |
| 0099 | 801-11642 | PORTABLE CHANGEABLE MESSAGE SIGN | 39.00 | EACH |
| 0100 | 801-12042 | TRUCK MOUNTED ATTENUATOR | 252.00 | DAY |
| 0101 | 801-97643 | TEMPORARY BUZZ STRIPS | 240.00 | LFT |
| 0102 | 802-09537 | BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN. MEDIAN OR SHOULDER | 4.00 | EACH |
| 0103 | 805-01844 | CONDUIT, STEEL, GALVANIZED, 2 IN. | 12.00 | LFT |
| 0104 | 805-10107 | WIRELESS MAGNETOMETER DETECTOR | 30.00 | EACH |
| 0105 | 805-78470 | SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA | 2176.00 | LFT |
| 0106 | 805-78510 | SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA | 828.00 | LFT |
| 0107 | 805-78785 | SIGNAL DETECTOR HOUSING | 5.00 | EACH |
| 0108 | 805-78795 | SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT | 696.00 | LFT |
| 0109 | 808-06716 | LINE, REMOVE | 242084.00 | LFT |
| 0110 | 808-09381 | RETRO-REFLECTIVITY TESTING | 1.00 | LS |
| 0111 | 808-10033 | LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN. | 158796.00 | LFT |
| 0112 | 808-10034 | LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN. | 152036.00 | LFT |
| 0113 | 808-10037 | LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN. | 27487.00 | LFT |
| 0114 | 808-10038 | TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE WHITE 24 IN. | 1878.00 | LFT |
| 0115 | 808-10051 | TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN. | 130.00 | LFT |
| 0116 | 808-10054 | LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN. | 88592.00 | LFT |
| 0117 | 808-10077 | PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW | 18.00 | EACH |
| 0118 | 808-11481 | LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN. | 36.00 | LFT |
| 0119 | 808-12032 | GROOVING FOR PAVEMENT MARKINGS | 324447.00 | LFT |
| 0120 | 808-75996 | SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 1247.00 | EACH |
| 0121 | 808-75998 | SNOWPLOWABLE RAISED PAVEMENT MARKER | 1247.00 | EACH |

Call: 410

Contract: RS-40066-A

Section No.: 1 ASPHALT RESURFACE

| Line | Item No | Item Code | Description | Quantity | Unit |
|------|---------|-----------|---|-----------|------|
| | 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| | 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| | 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| | 0004 | 109-08440 | QUALITY ADJUSTMENTS, HMA | 1.00 | DOL |
| | 0005 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| | 0006 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| | 0007 | 109-09377 | QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS | 1.00 | DOL |
| | 0008 | 109-09489 | PAYMENT ADJUSTMENT PG ASPHALT BINDER | 1.00 | DOL |
| | 0009 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| | 0010 | 207-12498 | SUBGRADE TREATMENT, TYPE ID | 8171.00 | SYS |
| | 0011 | 304-07490 | HMA PATCHING, TYPE B | 5001.00 | TON |
| | 0012 | 306-08036 | MILLING, ASPHALT, 2 IN. | 182479.00 | SYS |
| | 0013 | 306-08432 | MILLING, APPROACH | 14925.00 | SYS |
| | 0014 | 401-06264 | PROFILOGRAPH, HMA | 1.00 | LS |
| | 0015 | 401-07340 | QC/QA-HMA, 3, 64, SURFACE, 12.5 mm | 20073.00 | TON |
| | 0016 | 401-10258 | JOINT ADHESIVE, SURFACE | 94995.00 | LFT |
| | 0017 | 401-11785 | LIQUID ASPHALT SEALANT | 94995.00 | LFT |
| | 0018 | 406-05520 | ASPHALT FOR TACK COAT | 54.00 | TON |
| | 0019 | 408-12028 | CRACKS IN ASPHALT PAVEMENT, FILL | 5.00 | TON |
| | 0020 | 610-07487 | HMA FOR APPROACHES, TYPE B | 1642.00 | TON |
| | 0021 | 615-06525 | CASTING ADJUST TO GRADE, MONUMENT | 14.00 | EACH |
| | 0022 | 628-09403 | FIELD OFFICE, C | 8.00 | MOS |
| | 0023 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 2.00 | EACH |
| | 0024 | 702-90915 | CONCRETE, CLASS, A | 3.00 | CYS |
| | 0025 | 703-06029 | REINFORCING BARS, EPOXY COATED | 218.00 | LBS |
| | 0026 | 720-44000 | CASTING, ADJUST TO GRADE | 1.00 | EACH |
| | 0027 | 720-44000 | CASTING, ADJUST TO GRADE | 2.00 | EACH |
| | 0028 | 801-04308 | ROAD CLOSURE SIGN ASSEMBLY | 10.00 | EACH |
| | 0029 | 801-06203 | TEMPORARY PAVEMENT MARKING, 4 IN. | 8159.00 | LFT |
| | 0030 | 801-06207 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 8159.00 | LFT |
| | 0031 | 801-06209 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN. | 100.00 | LFT |
| | 0032 | 801-06640 | CONSTRUCTION SIGN, A | 79.00 | EACH |
| | 0033 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| | 0034 | 801-07118 | BARRICADE, III-A | 100.00 | LFT |
| | 0035 | 801-11642 | PORTABLE CHANGEABLE MESSAGE SIGN | 2.00 | EACH |
| | 0036 | 808-06712 | LINE, PAINT, BROKEN, YELLOW, 4 IN. | 10171.00 | LFT |
| | 0037 | 808-06713 | LINE, PAINT, SOLID, WHITE, 4 IN. | 163170.00 | LFT |
| | 0038 | 808-06714 | LINE, PAINT, SOLID, YELLOW, 4 IN. | 111350.00 | LFT |
| | 0039 | 808-09381 | RETRO-REFLECTIVITY TESTING | 1.00 | LS |
| | 0040 | 808-75297 | TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN. | 106.00 | LFT |

0041 808-75998 SNOWPLOWABLE RAISED PAVEMENT MARKER

1931.00 EACH

Call: 430

Contract: RS-40068-A

Section No.: 1 ASPHALT RESURFACE

Line

| Item No | Item Code | Description | Quantity | Unit |
|----------------|------------------|--|-----------------|-------------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08440 | QUALITY ADJUSTMENTS, HMA | 2.00 | DOL |
| 0005 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0006 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0007 | 109-09377 | QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS | 1.00 | DOL |
| 0008 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0009 | 207-09935 | SUBGRADE TREATMENT, TYPE IC | 243.00 | SYS |
| 0010 | 303-01180 | COMPACTED AGGREGATE NO. 53 | 2000.00 | TON |
| 0011 | 304-07491 | HMA PATCHING, TYPE C | 1387.00 | TON |
| 0012 | 306-08036 | MILLING, ASPHALT, 2 IN. | 161388.00 | SYS |
| 0013 | 306-08043 | MILLING, TRANSITION | 500.00 | SYS |
| 0014 | 306-08432 | MILLING, APPROACH | 12140.00 | SYS |
| 0015 | 401-06264 | PROFILOGRAPH, HMA | 1.00 | LS |
| 0016 | 401-07328 | QC/QA-HMA, 3, 70, SURFACE, 9.5 mm | 17753.00 | TON |
| 0017 | 401-10258 | JOINT ADHESIVE, SURFACE | 50586.00 | LFT |
| 0018 | 401-11785 | LIQUID ASPHALT SEALANT | 50586.00 | LFT |
| 0019 | 402-07452 | HMA WEDGE AND LEVEL, TYPE C | 100.00 | TON |
| 0020 | 406-05520 | ASPHALT FOR TACK COAT | 48.00 | TON |
| 0021 | 408-12028 | CRACKS IN ASPHALT PAVEMENT, FILL | 5.00 | TON |
| 0022 | 606-12400 | MILLED HMA CORRUGATIONS, SINUSOIDAL | 43016.00 | LFT |
| 0023 | 610-07488 | HMA FOR APPROACHES, TYPE C | 1335.00 | TON |
| 0024 | 615-06525 | CASTING ADJUST TO GRADE, MONUMENT | 1.00 | EACH |
| 0025 | 615-06527 | MONUMENT, SECTION CORNER | 15.00 | EACH |
| 0026 | 628-09403 | FIELD OFFICE, C | 6.00 | MOS |
| 0027 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 2.00 | EACH |
| 0028 | 702-90915 | CONCRETE, CLASS, A | 1.00 | CYS |
| 0029 | 703-06029 | REINFORCING BARS, EPOXY COATED | 8.00 | LBS |
| 0030 | 720-44000 | CASTING, ADJUST TO GRADE | 1.00 | EACH |
| 0031 | 801-01093 | TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY | 2.00 | EACH |
| 0032 | 801-06203 | TEMPORARY PAVEMENT MARKING, 4 IN. | 12647.00 | LFT |
| 0033 | 801-06207 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 12647.00 | LFT |
| 0034 | 801-06640 | CONSTRUCTION SIGN, A | 42.00 | EACH |
| 0035 | 801-06645 | CONSTRUCTION SIGN, B | 2.00 | EACH |

| | | | | |
|------|-----------|---|-----------|------|
| 0036 | 801-06710 | FLASHING ARROW SIGN | 160.00 | DAY |
| 0037 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0038 | 801-11642 | PORTABLE CHANGEABLE MESSAGE SIGN | 2.00 | EACH |
| 0039 | 808-06703 | LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 104430.00 | LFT |
| 0040 | 808-09381 | RETRO-REFLECTIVITY TESTING | 1.00 | LS |
| 0041 | 808-12032 | GROOVING FOR PAVEMENT MARKINGS | 160868.00 | LFT |
| 0042 | 808-75240 | LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN. | 12647.00 | LFT |
| 0043 | 808-75245 | LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 43791.00 | LFT |
| 0044 | 808-75297 | TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN. | 183.00 | LFT |
| 0045 | 808-75996 | SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 1167.00 | EACH |
| 0046 | 808-75998 | SNOWPLOWABLE RAISED PAVEMENT MARKER | 1167.00 | EACH |

Call: 440

Contract: RS-40071-A

Section No.: 1 ASPHALT RESURFACE

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|--|-----------|------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08440 | QUALITY ADJUSTMENTS, HMA | 1.00 | DOL |
| 0005 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0006 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0007 | 109-09377 | QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS | 1.00 | DOL |
| 0008 | 109-09489 | PAYMENT ADJUSTMENT PG ASPHALT BINDER | 1.00 | DOL |
| 0009 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0010 | 207-12498 | SUBGRADE TREATMENT, TYPE ID | 11615.00 | SYS |
| 0011 | 304-07490 | HMA PATCHING, TYPE B | 7163.00 | TON |
| 0012 | 306-08034 | MILLING, ASPHALT, 1 1/2 IN. | 192021.00 | SYS |
| 0013 | 306-08432 | MILLING, APPROACH | 13152.00 | SYS |
| 0014 | 401-06264 | PROFILOGRAPH, HMA | 1.00 | LS |
| 0015 | 401-07322 | QC/QA-HMA, 3, 64, SURFACE, 9.5 mm | 15842.00 | TON |
| 0016 | 401-10258 | JOINT ADHESIVE, SURFACE | 90920.00 | LFT |
| 0017 | 401-11785 | LIQUID ASPHALT SEALANT | 90920.00 | LFT |
| 0018 | 402-07451 | HMA WEDGE AND LEVEL, TYPE B | 400.00 | TON |
| 0019 | 406-05520 | ASPHALT FOR TACK COAT | 56.00 | TON |
| 0020 | 408-12028 | CRACKS IN ASPHALT PAVEMENT, FILL | 5.00 | TON |
| 0021 | 610-07487 | HMA FOR APPROACHES, TYPE B | 1085.00 | TON |
| 0022 | 615-06525 | CASTING ADJUST TO GRADE, MONUMENT | 8.00 | EACH |
| 0023 | 628-09403 | FIELD OFFICE, C | 12.00 | MOS |
| 0024 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 2.00 | EACH |
| 0025 | 702-90915 | CONCRETE, CLASS, A | 2.00 | CYS |

| | | | | |
|------|-----------|---|-----------|------|
| 0026 | 703-06029 | REINFORCING BARS, EPOXY COATED | 145.00 | LBS |
| 0027 | 720-44000 | CASTING, ADJUST TO GRADE | 2.00 | EACH |
| 0028 | 801-06203 | TEMPORARY PAVEMENT MARKING, 4 IN. | 7640.00 | LFT |
| 0029 | 801-06207 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 7640.00 | LFT |
| 0030 | 801-06209 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN. | 200.00 | LFT |
| 0031 | 801-06640 | CONSTRUCTION SIGN, A | 51.00 | EACH |
| 0032 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0033 | 801-11642 | PORTABLE CHANGEABLE MESSAGE SIGN | 2.00 | EACH |
| 0034 | 808-06703 | LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 153165.00 | LFT |
| 0035 | 808-09381 | RETRO-REFLECTIVITY TESTING | 1.00 | LS |
| 0036 | 808-10033 | LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN. | 1840.00 | LFT |
| 0037 | 808-10034 | LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN. | 1115.00 | LFT |
| 0038 | 808-10036 | LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN. | 154.00 | LFT |
| 0039 | 808-12032 | GROOVING FOR PAVEMENT MARKINGS | 288435.00 | LFT |
| 0040 | 808-75240 | LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN. | 3335.00 | LFT |
| 0041 | 808-75245 | LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 131935.00 | LFT |
| 0042 | 808-75297 | TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN. | 45.00 | LFT |
| 0043 | 808-75996 | SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 1826.00 | EACH |
| 0044 | 808-75998 | SNOWPLOWABLE RAISED PAVEMENT MARKER | 1826.00 | EACH |

Call: 550

Contract: B -40006-A

Section No.: 1 BRIDGE PAINTING

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|--|----------|------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0005 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0006 | 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 1.00 | DOL |
| 0007 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0008 | 619-11051 | CLEAN STEEL BRIDGE, QP-1, BRIDGE NO. | 1.00 | LS |
| 0009 | 619-11051 | CLEAN STEEL BRIDGE, QP-1, BRIDGE NO. | 1.00 | LS |
| 0010 | 619-11051 | CLEAN STEEL BRIDGE, QP-1, BRIDGE NO. | 1.00 | LS |
| 0011 | 619-11051 | CLEAN STEEL BRIDGE, QP-1, BRIDGE NO. | 1.00 | LS |
| 0012 | 619-11052 | CLEAN STEEL BRIDGE, QP-2, BRIDGE NO. | 1.00 | LS |
| 0013 | 619-11052 | CLEAN STEEL BRIDGE, QP-2, BRIDGE NO. | 1.00 | LS |
| 0014 | 619-51859 | PAINT STEEL BRIDGE, BRIDGE NO. | 1.00 | LS |
| 0015 | 619-51859 | PAINT STEEL BRIDGE, BRIDGE NO. | 1.00 | LS |
| 0016 | 619-51859 | PAINT STEEL BRIDGE, BRIDGE NO. | 1.00 | LS |
| 0017 | 619-51859 | PAINT STEEL BRIDGE, BRIDGE NO. | 1.00 | LS |

| | | | | |
|------|-----------|---------------------------------------|--------|------|
| 0018 | 619-51859 | PAINT STEEL BRIDGE, BRIDGE NO. | 1.00 | LS |
| 0019 | 619-51859 | PAINT STEEL BRIDGE, BRIDGE NO. | 1.00 | LS |
| 0020 | 628-09402 | FIELD OFFICE, B | 15.00 | MOS |
| 0021 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 1.00 | EACH |
| 0022 | 715-10238 | PIPE, ROADWAY DRAIN CASTING EXTENSION | 36.00 | EACH |
| 0023 | 801-06640 | CONSTRUCTION SIGN, A | 110.00 | EACH |
| 0024 | 801-06710 | FLASHING ARROW SIGN | 180.00 | DAY |
| 0025 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0026 | 801-12042 | TRUCK MOUNTED ATTENUATOR | 180.00 | DAY |

Call: 560

Contract: B -40009-A

Section No.: 1 REPLACE SUPERSTRUCTURE

Line

| Item No | Item Code | Description | Quantity | Unit |
|----------------|------------------|--|-----------------|-------------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08440 | QUALITY ADJUSTMENTS, HMA | 1.00 | DOL |
| 0005 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0006 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0007 | 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 1.00 | DOL |
| 0008 | 109-09489 | PAYMENT ADJUSTMENT PG ASPHALT BINDER | 1.00 | DOL |
| 0009 | 109-11362 | QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES | 1.00 | DOL |
| 0010 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0011 | 202-02240 | PAVEMENT REMOVAL | 4710.00 | SYS |
| 0012 | 202-02272 | PAVED SIDE DITCH, REMOVE | 35.00 | LFT |
| 0013 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0014 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0015 | 202-96133 | PIPE, REMOVE | 55.00 | LFT |
| 0016 | 203-02000 | EXCAVATION, COMMON | 2091.00 | CYS |
| 0017 | 203-08607 | LINEAR GRADING | 1273.80 | LFT |
| 0018 | 205-12108 | STORM WATER MANAGEMENT BUDGET | 36916.00 | DOL |
| 0019 | 205-12109 | SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1 | 1.00 | LS |
| 0020 | 207-09935 | SUBGRADE TREATMENT, TYPE IC | 7933.00 | SYS |
| 0021 | 207-09935 | SUBGRADE TREATMENT, TYPE IC | 7954.00 | SYS |
| 0022 | 211-02050 | B BORROW | 20.00 | CYS |
| 0023 | 211-09264 | STRUCTURE BACKFILL, TYPE 1 | 19.00 | CYS |
| 0024 | 211-09267 | STRUCTURE BACKFILL, TYPE 4 | 68.00 | CYS |
| 0025 | 214-12244 | GEOTEXTILE FOR SUBGRADE TYPE 2B | 7933.00 | SYS |
| 0026 | 301-12234 | COMPACTED AGGREGATE NO. 53 | 1312.00 | CYS |
| 0027 | 302-07455 | DENSE GRADED SUBBASE | 104.00 | CYS |

| | | | | |
|------|-----------|---|-----------|------|
| 0028 | 401-07335 | QC/QA-HMA, 4, 76, SURFACE, 9.5 mm | 602.00 | TON |
| 0029 | 401-07404 | QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm | 1004.00 | TON |
| 0030 | 401-07409 | QC/QA-HMA, 4, 64, BASE, 25.0 mm | 4421.00 | TON |
| 0031 | 401-10258 | JOINT ADHESIVE, SURFACE | 8422.00 | LFT |
| 0032 | 401-10259 | JOINT ADHESIVE, INTERMEDIATE | 8422.00 | LFT |
| 0033 | 401-11785 | LIQUID ASPHALT SEALANT | 16846.00 | LFT |
| 0034 | 401-12137 | QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm | 1096.00 | TON |
| 0035 | 402-10087 | HMA FOR TEMPORARY PAVEMENT, D | 5136.00 | TON |
| 0036 | 406-05521 | ASPHALT FOR TACK COAT | 30178.00 | SYS |
| 0037 | 601-02241 | GUARDRAIL, REMOVE | 2380.00 | LFT |
| 0038 | 601-12281 | GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING | 1281.30 | LFT |
| 0039 | 601-12284 | GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING | 575.00 | LFT |
| 0040 | 601-12292 | GUARDRAIL MGS TRANSITION WITHOUT CURB | 4.00 | EACH |
| 0041 | 601-94689 | GUARDRAIL, END TREATMENT, OS | 2.00 | EACH |
| 0042 | 601-94690 | GUARDRAIL, END TREATMENT, MS | 2.00 | EACH |
| 0043 | 602-06729 | BARRIER, DELINEATOR | 20.00 | EACH |
| 0044 | 606-12400 | MILLED HMA CORRUGATIONS, SINUSOIDAL | 5834.00 | LFT |
| 0045 | 609-06259 | REINFORCED CONCRETE BRIDGE APPROACH, 12 IN. | 624.00 | SYS |
| 0046 | 615-06510 | MONUMENT, C | 2.00 | EACH |
| 0047 | 616-05688 | RIPRAP, CLASS 1 | 300.00 | TON |
| 0048 | 616-06405 | RIPRAP, REVETMENT | 118.00 | TON |
| 0049 | 616-12251 | GEOTEXTILE FOR RIPRAP TYPE 3 | 321.00 | SYS |
| 0050 | 621-01004 | MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 2.00 | EACH |
| 0051 | 621-02770 | EROSION CONTROL BLANKET | 12701.00 | SYS |
| 0052 | 621-06559 | MULCHED SEEDING R | 12701.00 | SYS |
| 0053 | 621-06574 | SODDING | 106.60 | SYS |
| 0054 | 627-09331 | SAFETY TERMINAL TYPE, TL-4 | 2.00 | EACH |
| 0055 | 627-11647 | CABLE BARRIER SYSTEM, TYPE TL-4 RESET | 1813.00 | LFT |
| 0056 | 628-09402 | FIELD OFFICE, B | 12.00 | MOS |
| 0057 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 1.00 | EACH |
| 0058 | 629-12029 | PLANT GROWTH LAYER | 12701.00 | SYS |
| 0059 | 702-12076 | GRATES, BASINS, AND FITTINGS, CAST IRON | 2.00 | EACH |
| 0060 | 702-51005 | CONCRETE, A, SUBSTRUCTURE | 203.20 | CYS |
| 0061 | 703-06029 | REINFORCING BARS, EPOXY COATED | 215148.00 | LBS |
| 0062 | 703-97936 | THREADED TIE BAR ASSEMBLY, EPOXY COATED | 84.00 | EACH |
| 0063 | 704-51002 | CONCRETE, C, SUPERSTRUCTURE | 442.40 | CYS |
| 0064 | 706-09959 | RAILING, CONCRETE FT | 392.00 | LFT |
| 0065 | 706-11621 | CONCRETE BRIDGE RAILING TRANSITION, TFT | 8.00 | EACH |
| 0066 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0067 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0068 | 713-04858 | TEMPORARY BRIDGE | 1.00 | LS |
| 0069 | 713-51334 | TEMPORARY PIPE AND APPROACHES | 1.00 | LS |

| | | | | |
|------|-----------|--|----------|------|
| 0070 | 715-05161 | PIPE, TYPE 2, CIRCULAR, 48 IN. | 60.00 | LFT |
| 0071 | 715-07317 | CHECK VALVE | 1.00 | EACH |
| 0072 | 715-09064 | VIDEO INSPECTION FOR PIPE | 154.00 | LFT |
| 0073 | 715-10238 | PIPE, ROADWAY DRAIN CASTING EXTENSION | 2.00 | EACH |
| 0074 | 715-46010 | PIPE END SECTION, DIAMETER 18 IN. | 2.00 | EACH |
| 0075 | 716-07632 | PIPE INSTALLATION, TRENCHLESS, 18 IN. | 154.00 | LFT |
| 0076 | 718-08308 | UNDERDRAIN PATCHING | 1414.00 | LFT |
| 0077 | 720-45030 | INLET, E7 | 2.00 | EACH |
| 0078 | 720-45130 | INLET, E7 MODIFIED | 2.00 | EACH |
| 0079 | 801-01093 | TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY | 8.00 | EACH |
| 0080 | 801-03290 | CONSTRUCTION SIGN, C | 2.00 | EACH |
| 0081 | 801-06208 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN. | 23355.00 | LFT |
| 0082 | 801-06469 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN. | 14136.00 | LFT |
| 0083 | 801-06640 | CONSTRUCTION SIGN, A | 22.00 | EACH |
| 0084 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0085 | 801-07024 | ENERGY ABSORBING TERMINAL, CZ, TL-3 | 2.00 | EACH |
| 0086 | 801-08401 | TEMPORARY TRAFFIC BARRIER, TYPE 2 | 5410.00 | LFT |
| 0087 | 801-08508 | TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2 | 800.00 | LFT |
| 0088 | 801-12042 | TRUCK MOUNTED ATTENUATOR | 16.00 | DAY |
| 0089 | 801-97643 | TEMPORARY BUZZ STRIPS | 1728.00 | LFT |
| 0090 | 804-06770 | DELINEATOR POST | 5.00 | EACH |
| 0091 | 808-06716 | LINE, REMOVE | 14737.00 | LFT |
| 0092 | 808-10031 | LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN. | 1354.00 | LFT |
| 0093 | 808-10033 | LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN. | 5415.00 | LFT |
| 0094 | 808-10034 | LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN. | 5415.00 | LFT |
| 0095 | 808-12032 | GROOVING FOR PAVEMENT MARKINGS | 11440.00 | LFT |
| 0096 | 808-75998 | SNOWPLOWABLE RAISED PAVEMENT MARKER | 24.00 | EACH |

Call: 570

Contract: B -40011-A

Section No.: 1 BRIDGE DECK OVERLAY

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|--|----------|------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08440 | QUALITY ADJUSTMENTS, HMA | 1.00 | DOL |
| 0005 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0006 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0007 | 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 1.00 | DOL |
| 0008 | 109-09489 | PAYMENT ADJUSTMENT PG ASPHALT BINDER | 1.00 | DOL |
| 0009 | 109-11362 | QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES | 1.00 | DOL |

| | | | | |
|------|-----------|---|---------|------|
| 0010 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0011 | 201-52370 | CLEARING RIGHT OF WAY | 1.00 | LS |
| 0012 | 202-02273 | CENTER CURB, CONCRETE, REMOVE | 184.00 | SYS |
| 0013 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0014 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0015 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0016 | 203-02070 | BORROW | 48.00 | CYS |
| 0017 | 203-04523 | DEWATERING | 1.00 | LS |
| 0018 | 203-08607 | LINEAR GRADING | 400.00 | LFT |
| 0019 | 205-03371 | SEDIMENT, REMOVE | 98.00 | CYS |
| 0020 | 205-12108 | STORM WATER MANAGEMENT BUDGET | 3737.00 | DOL |
| 0021 | 205-12109 | SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1 | 1.00 | LS |
| 0022 | 207-08264 | SUBGRADE TREATMENT, TYPE II | 184.00 | SYS |
| 0023 | 207-09935 | SUBGRADE TREATMENT, TYPE IC | 114.00 | SYS |
| 0024 | 213-09269 | FLOWABLE BACKFILL, NON-REMOVABLE | 5.00 | CYS |
| 0025 | 301-12233 | COMPACTED AGGREGATE NO. 8 | 26.00 | CYS |
| 0026 | 302-07455 | DENSE GRADED SUBBASE | 15.00 | CYS |
| 0027 | 306-08034 | MILLING, ASPHALT, 1 1/2 IN. | 3414.00 | SYS |
| 0028 | 306-08041 | MILLING, PCCP | 1129.00 | SYS |
| 0029 | 306-08042 | MILLING, SCARIFICATION | 254.00 | SYS |
| 0030 | 306-08043 | MILLING, TRANSITION | 2733.00 | SYS |
| 0031 | 306-11553 | MILLING, ASPHALT, 3/4 IN. | 274.00 | SYS |
| 0032 | 401-07321 | QC/QA-HMA, 2, 64, SURFACE, 9.5 mm | 282.00 | TON |
| 0033 | 401-07328 | QC/QA-HMA, 3, 70, SURFACE, 9.5 mm | 96.00 | TON |
| 0034 | 401-07347 | QC/QA-HMA, 3, 70, SURFACE, 12.5 mm | 368.00 | TON |
| 0035 | 401-07398 | QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm | 16.00 | TON |
| 0036 | 401-07408 | QC/QA-HMA, 3, 64, BASE, 25.0 mm | 51.00 | TON |
| 0037 | 401-10258 | JOINT ADHESIVE, SURFACE | 3953.00 | LFT |
| 0038 | 401-10259 | JOINT ADHESIVE, INTERMEDIATE | 256.00 | LFT |
| 0039 | 401-11785 | LIQUID ASPHALT SEALANT | 3103.00 | LFT |
| 0040 | 402-10086 | HMA FOR TEMPORARY PAVEMENT, C | 92.00 | TON |
| 0041 | 406-05521 | ASPHALT FOR TACK COAT | 8025.00 | SYS |
| 0042 | 503-03489 | RETROFITTED TIE BARS | 12.00 | EACH |
| 0043 | 503-12173 | TERMINAL JOINT, POLYMER MODIFIED ASPHALT | 172.00 | LFT |
| 0044 | 506-06333 | PCCP PATCHING, FULL DEPTH | 117.00 | SYS |
| 0045 | 601-02241 | GUARDRAIL, REMOVE | 575.00 | LFT |
| 0046 | 601-12281 | GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING | 157.00 | LFT |
| 0047 | 601-12286 | GUARDRAIL, MGS W-BEAM, SHOP CURVED, 6 FT 3 IN SPACING | 13.00 | LFT |
| 0048 | 601-12292 | GUARDRAIL MGS TRANSITION WITHOUT CURB | 3.00 | EACH |
| 0049 | 601-12292 | GUARDRAIL MGS TRANSITION WITHOUT CURB | 1.00 | EACH |
| 0050 | 601-12294 | GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR | 1.00 | EACH |
| 0051 | 601-94689 | GUARDRAIL, END TREATMENT, OS | 5.00 | EACH |

| | | | |
|------|-----------|--|--------------|
| 0052 | 602-06729 | BARRIER, DELINEATOR | 40.00 EACH |
| 0053 | 605-06215 | CENTER CURB, D CONCRETE | 184.00 LFT |
| 0054 | 606-12399 | MILLED HMA CORRUGATIONS, CONVENTIONAL | 700.00 LFT |
| 0055 | 621-06559 | MULCHED SEEDING R | 640.00 SYS |
| 0056 | 628-09402 | FIELD OFFICE, B | 8.00 MOS |
| 0057 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 8.00 EACH |
| 0058 | 702-51863 | FIELD DRILLED HOLE IN CONCRETE | 586.00 EACH |
| 0059 | 703-06029 | REINFORCING BARS, EPOXY COATED | 2028.00 LBS |
| 0060 | 706-11620 | CONCRETE BRIDGE RAILING TRANSITION, TFC | 4.00 EACH |
| 0061 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0062 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0063 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0064 | 710-09158 | PATCHING CONCRETE STRUCTURES | 77.00 SFT |
| 0065 | 722-01066 | HYDRODEMOLITION | 5424.00 SYS |
| 0066 | 722-12380 | BRIDGE DECK OVERLAY, BUDGET | 77535.00 DOL |
| 0067 | 722-12382 | TRANSVERSE GROOVING | 5424.00 SYS |
| 0068 | 722-12463 | BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY | 573.00 SYS |
| 0069 | 722-12464 | BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE | 4851.00 SYS |
| 0070 | 722-51401 | BRIDGE DECK PATCHING, FULL DEPTH | 425.00 SFT |
| 0071 | 722-51842 | BRIDGE DECK OVERLAY, LATEX MODIFIED | 5424.00 SYS |
| 0072 | 722-51874 | OVERLAY DAM | 570.00 SFT |
| 0073 | 724-12103 | PRE-COMPRESSED FOAM JOINT | 579.00 LFT |
| 0074 | 727-90308 | EPOXY INJECTION, CRACK PREPARATION | 924.00 LFT |
| 0075 | 727-90309 | EPOXY INJECTION, EPOXY MATERIAL | 241.00 GAL |
| 0076 | 727-93560 | EPOXY INJECTION, FURNISHING EQUIPMENT | 1.00 LS |
| 0077 | 801-04308 | ROAD CLOSURE SIGN ASSEMBLY | 10.00 EACH |
| 0078 | 801-06207 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 17086.00 LFT |
| 0079 | 801-06211 | TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW | 4.00 EACH |
| 0080 | 801-06218 | TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN. | 145.00 LFT |
| 0081 | 801-06640 | CONSTRUCTION SIGN, A | 58.00 EACH |
| 0082 | 801-06645 | CONSTRUCTION SIGN, B | 25.00 EACH |
| 0083 | 801-06775 | MAINTAINING TRAFFIC | 1.00 LS |
| 0084 | 801-07118 | BARRICADE, III-A | 152.00 LFT |
| 0085 | 801-07119 | BARRICADE, III-B | 63.00 LFT |
| 0086 | 801-08401 | TEMPORARY TRAFFIC BARRIER, TYPE 2 | 1395.00 LFT |
| 0087 | 801-12042 | TRUCK MOUNTED ATTENUATOR | 4.00 DAY |
| 0088 | 801-12082 | FIXED TEMPORARY SIGNAL | 1.00 LS |
| 0089 | 801-94295 | SIGNAL HEAD RELOCATE | 16.00 EACH |
| 0090 | 805-78470 | SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA | 2116.00 LFT |
| 0091 | 805-78785 | SIGNAL DETECTOR HOUSING | 6.00 EACH |
| 0092 | 805-78795 | SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT | 681.00 LFT |
| 0093 | 808-06712 | LINE, PAINT, BROKEN, YELLOW, 4 IN. | 134.00 LFT |

| | | | | |
|------|-----------|---|---------|------|
| 0094 | 808-06713 | LINE, PAINT, SOLID, WHITE, 4 IN. | 1280.00 | LFT |
| 0095 | 808-06714 | LINE, PAINT, SOLID, YELLOW, 4 IN. | 105.00 | LFT |
| 0096 | 808-06716 | LINE, REMOVE | 6988.00 | LFT |
| 0097 | 808-10031 | LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN. | 457.00 | LFT |
| 0098 | 808-10033 | LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN. | 3914.00 | LFT |
| 0099 | 808-10034 | LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN. | 2347.00 | LFT |
| 0100 | 808-10038 | TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE WHITE 24 IN. | 150.00 | LFT |
| 0101 | 808-10051 | TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN. | 120.00 | LFT |
| 0102 | 808-10052 | PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY | 2.00 | EACH |
| 0103 | 808-10077 | PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW | 12.00 | EACH |
| 0104 | 808-12032 | GROOVING FOR PAVEMENT MARKINGS | 6718.00 | LFT |
| 0105 | 808-75998 | SNOWPLOWABLE RAISED PAVEMENT MARKER | 12.00 | EACH |

Call: 590

Contract: B -40101-A

Section No.: 1 BRIDGE DECK OVERLAY

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|--|----------|------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08440 | QUALITY ADJUSTMENTS, HMA | 1.00 | DOL |
| 0005 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0006 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0007 | 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 1.00 | DOL |
| 0008 | 109-09489 | PAYMENT ADJUSTMENT PG ASPHALT BINDER | 1.00 | DOL |
| 0009 | 109-11362 | QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES | 1.00 | DOL |
| 0010 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0011 | 202-02240 | PAVEMENT REMOVAL | 580.00 | SYS |
| 0012 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0013 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0014 | 202-93741 | GUARDRAIL, END TREATMENT, REMOVE | 8.00 | EACH |
| 0015 | 203-02000 | EXCAVATION, COMMON | 224.00 | CYS |
| 0016 | 203-02070 | BORROW | 150.00 | CYS |
| 0017 | 203-08607 | LINEAR GRADING | 450.00 | LFT |
| 0018 | 205-12108 | STORM WATER MANAGEMENT BUDGET | 26150.00 | DOL |
| 0019 | 205-12109 | SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1 | 1.00 | LS |
| 0020 | 206-51220 | EXCAVATION, WET | 602.00 | CYS |
| 0021 | 206-51235 | COFFERDAM | 1.00 | LS |
| 0022 | 206-51235 | COFFERDAM | 1.00 | LS |
| 0023 | 213-09269 | FLOWABLE BACKFILL, NON-REMOVABLE | 23.00 | CYS |
| 0024 | 302-07455 | DENSE GRADED SUBBASE | 100.00 | CYS |

| | | | |
|------|-----------|--|--------------|
| 0025 | 303-01180 | COMPACTED AGGREGATE NO. 53 | 188.00 TON |
| 0026 | 306-08043 | MILLING, TRANSITION | 1384.00 SYS |
| 0027 | 306-08599 | MILLING, ASPHALT, 1/2 IN. | 573.00 SYS |
| 0028 | 401-07322 | QC/QA-HMA, 3, 64, SURFACE, 9.5 mm | 218.00 TON |
| 0029 | 401-10258 | JOINT ADHESIVE, SURFACE | 1864.00 LFT |
| 0030 | 401-11785 | LIQUID ASPHALT SEALANT | 1864.00 LFT |
| 0031 | 406-05521 | ASPHALT FOR TACK COAT | 1956.00 SYS |
| 0032 | 507-08269 | CRACKS IN PCCP, FILLED | 28.00 LFT |
| 0033 | 601-02241 | GUARDRAIL, REMOVE | 1102.00 LFT |
| 0034 | 601-05071 | GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 7 | 1.00 EACH |
| 0035 | 601-12281 | GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING | 326.00 LFT |
| 0036 | 601-12292 | GUARDRAIL MGS TRANSITION WITHOUT CURB | 8.00 EACH |
| 0037 | 601-94689 | GUARDRAIL, END TREATMENT, OS | 7.00 EACH |
| 0038 | 602-06729 | BARRIER, DELINEATOR | 16.00 EACH |
| 0039 | 609-06259 | REINFORCED CONCRETE BRIDGE APPROACH, 12 IN. | 592.00 SYS |
| 0040 | 616-05688 | RIPRAP, CLASS 1 | 565.00 TON |
| 0041 | 616-05689 | RIPRAP, CLASS 2 | 650.00 TON |
| 0042 | 616-06405 | RIPRAP, REVETMENT | 85.00 TON |
| 0043 | 616-12246 | GEOTEXTILE FOR RIPRAP TYPE 1A | 130.00 SYS |
| 0044 | 616-93772 | INSPECTION HOLE | 6.00 EACH |
| 0045 | 621-01004 | MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 8.00 EACH |
| 0046 | 621-06559 | MULCHED SEEDING R | 1825.00 SYS |
| 0047 | 621-06567 | WATER | 0.50 KGAL |
| 0048 | 621-06574 | SODDING | 100.00 SYS |
| 0049 | 628-09401 | FIELD OFFICE, A | 12.00 MOS |
| 0050 | 628-11729 | CELLULAR TELEPHONE, TYPE A | 2.00 EACH |
| 0051 | 628-11731 | CELLULAR TELEPHONE, ADDITIONAL DATA | 1.00 DOL |
| 0052 | 628-11732 | CELLULAR TELEPHONE, ADDITIONAL MINUTES | 1.00 DOL |
| 0053 | 628-11782 | CELLULAR TELEPHONE SERVICE, 1000 MIN. | 24.00 MOS |
| 0054 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 2.00 EACH |
| 0055 | 701-93790 | CLEAN AND EPOXY COAT EXISTING PILES | 1.00 LS |
| 0056 | 701-93790 | CLEAN AND EPOXY COAT EXISTING PILES | 1.00 LS |
| 0057 | 702-51863 | FIELD DRILLED HOLE IN CONCRETE | 248.00 EACH |
| 0058 | 703-06029 | REINFORCING BARS, EPOXY COATED | 68594.00 LBS |
| 0059 | 703-08247 | EMBEDDED GALVANIC ANODE | 390.00 EACH |
| 0060 | 703-97936 | THREADED TIE BAR ASSEMBLY, EPOXY COATED | 250.00 EACH |
| 0061 | 704-51002 | CONCRETE, C, SUPERSTRUCTURE | 75.00 CYS |
| 0062 | 706-09960 | RAILING, CONCRETE FC | 389.00 LFT |
| 0063 | 706-11620 | CONCRETE BRIDGE RAILING TRANSITION, TFC | 8.00 EACH |
| 0064 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0065 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0066 | 709-51821 | SURFACE SEAL | 1.00 LS |

| | | | | |
|------|-----------|--|----------|------|
| 0067 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0068 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0069 | 710-09158 | PATCHING CONCRETE STRUCTURES | 292.00 | SFT |
| 0070 | 722-01066 | HYDRODEMOLITION | 400.00 | SYS |
| 0071 | 722-01066 | HYDRODEMOLITION | 431.00 | SYS |
| 0072 | 722-12380 | BRIDGE DECK OVERLAY, BUDGET | 16940.00 | DOL |
| 0073 | 722-12382 | TRANSVERSE GROOVING | 1466.00 | SYS |
| 0074 | 722-51401 | BRIDGE DECK PATCHING, FULL DEPTH | 25.00 | SFT |
| 0075 | 722-51401 | BRIDGE DECK PATCHING, FULL DEPTH | 25.00 | SFT |
| 0076 | 722-51401 | BRIDGE DECK PATCHING, FULL DEPTH | 27.00 | SFT |
| 0077 | 722-51401 | BRIDGE DECK PATCHING, FULL DEPTH | 25.00 | SFT |
| 0078 | 722-51401 | BRIDGE DECK PATCHING, FULL DEPTH | 195.00 | SFT |
| 0079 | 722-51401 | BRIDGE DECK PATCHING, FULL DEPTH | 209.00 | SFT |
| 0080 | 722-51852 | BRIDGE DECK PATCHING, PARTIAL DEPTH | 210.00 | SFT |
| 0081 | 722-51852 | BRIDGE DECK PATCHING, PARTIAL DEPTH | 142.00 | SFT |
| 0082 | 722-51852 | BRIDGE DECK PATCHING, PARTIAL DEPTH | 148.00 | SFT |
| 0083 | 722-51852 | BRIDGE DECK PATCHING, PARTIAL DEPTH | 102.00 | SFT |
| 0084 | 724-12103 | PRE-COMPRESSED FOAM JOINT | 54.00 | LFT |
| 0085 | 724-12157 | PREFORMED SILICONE JOINT | 128.00 | LFT |
| 0086 | 724-12461 | CONCRETE FOR PATCHING STRUCTURAL EXPANSION JOINT | 54.00 | SFT |
| 0087 | 738-09456 | POLYMERIC CONCRETE BRIDGE DECK OVERLAY | 1809.00 | SYS |
| 0088 | 801-01093 | TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY | 16.00 | EACH |
| 0089 | 801-03291 | CONSTRUCTION SIGN, D | 4.00 | EACH |
| 0090 | 801-04308 | ROAD CLOSURE SIGN ASSEMBLY | 2.00 | EACH |
| 0091 | 801-06207 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 6084.00 | LFT |
| 0092 | 801-06218 | TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN. | 88.00 | LFT |
| 0093 | 801-06625 | DETOUR ROUTE MARKER ASSEMBLY | 28.00 | EACH |
| 0094 | 801-06640 | CONSTRUCTION SIGN, A | 183.00 | EACH |
| 0095 | 801-06645 | CONSTRUCTION SIGN, B | 37.00 | EACH |
| 0096 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0097 | 801-07118 | BARRICADE, III-A | 96.00 | LFT |
| 0098 | 801-07119 | BARRICADE, III-B | 168.00 | LFT |
| 0099 | 801-08508 | TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2 | 1043.00 | LFT |
| 0100 | 801-11642 | PORTABLE CHANGEABLE MESSAGE SIGN | 8.00 | EACH |
| 0101 | 801-12081 | PORTABLE SIGNAL | 1.00 | LS |
| 0102 | 801-12081 | PORTABLE SIGNAL | 1.00 | LS |
| 0103 | 801-12482 | DRIVEWAY ASSISTANCE DEVICE | 4.00 | EACH |
| 0104 | 801-97643 | TEMPORARY BUZZ STRIPS | 88.00 | LFT |
| 0105 | 808-06712 | LINE, PAINT, BROKEN, YELLOW, 4 IN. | 830.00 | LFT |
| 0106 | 808-06713 | LINE, PAINT, SOLID, WHITE, 4 IN. | 6144.00 | LFT |
| 0107 | 808-06714 | LINE, PAINT, SOLID, YELLOW, 4 IN. | 1378.00 | LFT |
| 0108 | 808-06716 | LINE, REMOVE | 8253.00 | LFT |

0109 808-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE 15.00 EACH
 Call: 590
 Contract: B -40101-A
 Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|-------------------------------------|----------|------|
| 0110 | 722-51842 | BRIDGE DECK OVERLAY, LATEX MODIFIED | 896.00 | SYS |

Call: 590
 Contract: B -40101-A
 Section No.: 3 SILICA FUME MODIFIED CONCRETE OVERLAY

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|---|----------|------|
| 0111 | 722-01061 | BRIDGE DECK OVERLAY, SILICA FUME MODIFIED | 896.00 | SYS |

Call: 620
 Contract: B -40332-A
 Section No.: 1 BRIDGE REPLACEMENT

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|--|----------|------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08440 | QUALITY ADJUSTMENTS, HMA | 1.00 | DOL |
| 0005 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0006 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0007 | 109-09489 | PAYMENT ADJUSTMENT PG ASPHALT BINDER | 1.00 | DOL |
| 0008 | 109-11362 | QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES | 1.00 | DOL |
| 0009 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0010 | 201-52370 | CLEARING RIGHT OF WAY | 1.00 | LS |
| 0011 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0012 | 202-93741 | GUARDRAIL, END TREATMENT, REMOVE | 4.00 | EACH |
| 0013 | 203-02000 | EXCAVATION, COMMON | 910.30 | CYS |
| 0014 | 203-02070 | BORROW | 21.00 | CYS |
| 0015 | 203-51223 | EXCAVATION, WATERWAY | 180.00 | CYS |
| 0016 | 205-11626 | PUMP AROUND | 1.00 | EACH |
| 0017 | 205-12108 | STORM WATER MANAGEMENT BUDGET | 6422.00 | DOL |
| 0018 | 205-12109 | SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1 | 1.00 | LS |
| 0019 | 206-51230 | EXCAVATION, FOUNDATION, UNCLASSIFIED | 15.00 | CYS |
| 0020 | 207-08264 | SUBGRADE TREATMENT, TYPE II | 203.00 | SYS |
| 0021 | 207-08266 | SUBGRADE TREATMENT, TYPE III | 236.00 | SYS |
| 0022 | 207-09935 | SUBGRADE TREATMENT, TYPE IC | 1181.00 | SYS |

| | | | | |
|------|-----------|---|---------|------|
| 0023 | 211-06467 | AGGREGATE FOR END BENT BACKFILL | 22.00 | CYS |
| 0024 | 211-09265 | STRUCTURE BACKFILL, TYPE 2 | 172.00 | CYS |
| 0025 | 214-12243 | GEOTEXTILE FOR SUBGRADE TYPE 2A | 268.00 | SYS |
| 0026 | 301-12232 | COMPACTED AGGREGATE NO. 5 | 39.00 | CYS |
| 0027 | 301-12234 | COMPACTED AGGREGATE NO. 53 | 31.00 | CYS |
| 0028 | 302-07455 | DENSE GRADED SUBBASE | 49.50 | CYS |
| 0029 | 303-01180 | COMPACTED AGGREGATE NO. 53 | 62.00 | TON |
| 0030 | 306-08034 | MILLING, ASPHALT, 1 1/2 IN. | 113.00 | SYS |
| 0031 | 306-08043 | MILLING, TRANSITION | 242.00 | SYS |
| 0032 | 401-07328 | QC/QA-HMA, 3, 70, SURFACE, 9.5 mm | 99.00 | TON |
| 0033 | 401-07398 | QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm | 129.00 | TON |
| 0034 | 401-07424 | QC/QA-HMA, 3, 64, BASE, 19.0 mm | 332.00 | TON |
| 0035 | 401-10258 | JOINT ADHESIVE, SURFACE | 446.00 | LFT |
| 0036 | 401-10259 | JOINT ADHESIVE, INTERMEDIATE | 347.00 | LFT |
| 0037 | 406-05520 | ASPHALT FOR TACK COAT | 1.00 | TON |
| 0038 | 601-01522 | GUARDRAIL, TRANSITION, TYPE TGB | 1.00 | EACH |
| 0039 | 601-01700 | GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 1 | 1.00 | EACH |
| 0040 | 601-02241 | GUARDRAIL, REMOVE | 60.00 | LFT |
| 0041 | 601-12281 | GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING | 19.00 | LFT |
| 0042 | 601-12292 | GUARDRAIL MGS TRANSITION WITHOUT CURB | 3.00 | EACH |
| 0043 | 601-94689 | GUARDRAIL, END TREATMENT, OS | 3.00 | EACH |
| 0044 | 602-06729 | BARRIER, DELINEATOR | 12.00 | EACH |
| 0045 | 604-05528 | HMA FOR SIDEWALK | 32.00 | TON |
| 0046 | 605-06165 | CURB AND GUTTER, C, CONCRETE, MODIFIED | 330.00 | LFT |
| 0047 | 609-06259 | REINFORCED CONCRETE BRIDGE APPROACH, 12 IN. | 195.20 | SYS |
| 0048 | 610-07487 | HMA FOR APPROACHES, TYPE B | 33.00 | TON |
| 0049 | 610-08446 | PCCP FOR APPROACHES, 6 IN. | 100.00 | SYS |
| 0050 | 615-06505 | MONUMENT, B | 2.00 | EACH |
| 0051 | 616-05688 | RIPRAP, CLASS 1 | 444.00 | TON |
| 0052 | 616-06405 | RIPRAP, REVETMENT | 32.00 | TON |
| 0053 | 616-12249 | GEOTEXTILE FOR RIPRAP TYPE 2B | 593.00 | SYS |
| 0054 | 621-01004 | MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 1.00 | EACH |
| 0055 | 621-02770 | EROSION CONTROL BLANKET | 120.00 | SYS |
| 0056 | 621-06560 | MULCHED SEEDING U | 2200.00 | SYS |
| 0057 | 621-06567 | WATER | 1.00 | KGAL |
| 0058 | 621-06574 | SODDING | 22.00 | SYS |
| 0059 | 628-09402 | FIELD OFFICE, B | 10.00 | MOS |
| 0060 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 1.00 | EACH |
| 0061 | 701-09558 | TEST PILE, INDICATOR, PRODUCTION | 316.00 | LFT |
| 0062 | 701-09560 | TEST PILE, INDICATOR, RESTRIKE | 4.00 | EACH |
| 0063 | 701-09663 | PILE, STEEL PIPE, 0.312 IN., 14 IN. | 992.00 | LFT |
| 0064 | 701-09675 | PILE, STEEL PIPE, EPOXY COATED, 0.312 IN., 14 IN. | 112.00 | LFT |

| | | | | |
|------|-----------|--|----------|------|
| 0065 | 701-09679 | CONICAL PILE TIP, 14 IN. | 20.00 | EACH |
| 0066 | 702-51005 | CONCRETE, A, SUBSTRUCTURE | 27.40 | CYS |
| 0067 | 702-92857 | CONCRETE, C, SUBSTRUCTURE | 30.60 | CYS |
| 0068 | 703-06028 | REINFORCING BARS | 4898.00 | LBS |
| 0069 | 703-06029 | REINFORCING BARS, EPOXY COATED | 49788.00 | LBS |
| 0070 | 703-97936 | THREADED TIE BAR ASSEMBLY, EPOXY COATED | 36.00 | EACH |
| 0071 | 704-51002 | CONCRETE, C, SUPERSTRUCTURE | 116.20 | CYS |
| 0072 | 706-06351 | CONCRETE BRIDGE RAILING TRANSITION, TPF-1 | 2.00 | EACH |
| 0073 | 706-06353 | CONCRETE BRIDGE RAILING TRANSITION, TPS-1 | 2.00 | EACH |
| 0074 | 706-11404 | RAILING, STEEL PF-1 | 96.00 | LFT |
| 0075 | 706-11418 | RAILING, STEEL PS-1 | 96.00 | LFT |
| 0076 | 706-11602 | RAILING, CONCRETE PF-1 | 6.50 | CYS |
| 0077 | 706-11604 | RAILING, CONCRETE PS-1 | 9.20 | CYS |
| 0078 | 707-09029 | STRUCTURAL MEMBER, CONCRETE, BOX BEAM, 12 IN. X 48 IN. | 425.00 | LFT |
| 0079 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0080 | 715-05151 | PIPE, TYPE 2, CIRCULAR, 15 IN. | 24.00 | LFT |
| 0081 | 715-05152 | PIPE, TYPE 2, CIRCULAR, 18 IN. | 270.00 | LFT |
| 0082 | 715-05407 | PIPE, END BENT DRAIN, 6 IN. | 112.00 | LFT |
| 0083 | 718-12309 | GEOTEXTILE FOR UNDERDRAIN, TYPE 3 | 70.00 | SYS |
| 0084 | 720-45410 | MANHOLE, C4 | 3.00 | EACH |
| 0085 | 720-98174 | INLET, B15 | 3.00 | EACH |
| 0086 | 731-03915 | ARCHITECTURAL SURFACE TREATMENT | 1030.00 | SFT |
| 0087 | 801-04308 | ROAD CLOSURE SIGN ASSEMBLY | 7.00 | EACH |
| 0088 | 801-06625 | DETOUR ROUTE MARKER ASSEMBLY | 23.00 | EACH |
| 0089 | 801-06640 | CONSTRUCTION SIGN, A | 23.00 | EACH |
| 0090 | 801-06645 | CONSTRUCTION SIGN, B | 12.00 | EACH |
| 0091 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0092 | 801-07118 | BARRICADE, III-A | 72.00 | LFT |
| 0093 | 801-07119 | BARRICADE, III-B | 32.00 | LFT |
| 0094 | 802-04893 | REFERENCE POST | 1.00 | EACH |
| 0095 | 802-05701 | SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE | 45.00 | LFT |
| 0096 | 802-07059 | SIGN, SHEET, AND SUPPORTS, REMOVE | 5.00 | EACH |
| 0097 | 802-09838 | SIGN, SHEET, WITH LEGEND, 0.080 IN. | 17.00 | SFT |
| 0098 | 808-06713 | LINE, PAINT, SOLID, WHITE, 4 IN. | 1170.00 | LFT |
| 0099 | 808-06714 | LINE, PAINT, SOLID, YELLOW, 4 IN. | 1170.00 | LFT |
| 0100 | 808-06726 | TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN. | 13.00 | LFT |

Call: 630

Contract: B -40531-A

Section No.: 1 RAISE BRIDGE/LOWER PAVEMENT

Line

Item No Item Code Description

Quantity Unit

| | | | | |
|------|-----------|--|----------|------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08440 | QUALITY ADJUSTMENTS, HMA | 1.00 | DOL |
| 0005 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0006 | 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 1.00 | DOL |
| 0007 | 109-09377 | QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS | 1.00 | DOL |
| 0008 | 109-09489 | PAYMENT ADJUSTMENT PG ASPHALT BINDER | 1.00 | DOL |
| 0009 | 109-11362 | QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES | 1.00 | DOL |
| 0010 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0011 | 201-52370 | CLEARING RIGHT OF WAY | 1.00 | LS |
| 0012 | 202-02240 | PAVEMENT REMOVAL | 3515.00 | SYS |
| 0013 | 202-02272 | PAVED SIDE DITCH, REMOVE | 26.00 | LFT |
| 0014 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0015 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0016 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0017 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0018 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0019 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0020 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0021 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0022 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0023 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0024 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0025 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0026 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0027 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0028 | 202-93741 | GUARDRAIL, END TREATMENT, REMOVE | 6.00 | EACH |
| 0029 | 203-02000 | EXCAVATION, COMMON | 1899.20 | CYS |
| 0030 | 203-02070 | BORROW | 2734.00 | CYS |
| 0031 | 203-04523 | DEWATERING | 1.00 | LS |
| 0032 | 203-08607 | LINEAR GRADING | 719.00 | LFT |
| 0033 | 205-12108 | STORM WATER MANAGEMENT BUDGET | 46492.00 | DOL |
| 0034 | 205-12109 | SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1 | 1.00 | LS |
| 0035 | 206-98327 | SHEET PILING STEEL S=30.2 | 17458.00 | SFT |
| 0036 | 207-08264 | SUBGRADE TREATMENT, TYPE II | 163.00 | SYS |
| 0037 | 207-09934 | SUBGRADE TREATMENT, TYPE IB | 5174.00 | SYS |
| 0038 | 207-12498 | SUBGRADE TREATMENT, TYPE ID | 71.00 | SYS |
| 0039 | 211-09266 | STRUCTURE BACKFILL, TYPE 3 | 185.00 | CYS |
| 0040 | 211-09267 | STRUCTURE BACKFILL, TYPE 4 | 3.00 | CYS |
| 0041 | 213-09269 | FLOWABLE BACKFILL, NON-REMOVABLE | 2.00 | CYS |
| 0042 | 301-12234 | COMPACTED AGGREGATE NO. 53 | 409.00 | CYS |

| | | | | |
|------|-----------|---|-----------|------|
| 0043 | 302-06464 | SUBBASE FOR PCCP | 169.00 | CYS |
| 0044 | 302-07455 | DENSE GRADED SUBBASE | 607.00 | CYS |
| 0045 | 303-01180 | COMPACTED AGGREGATE NO. 53 | 867.00 | TON |
| 0046 | 304-07490 | HMA PATCHING, TYPE B | 1502.00 | TON |
| 0047 | 304-07783 | HMA PATCHING, TYPE D | 525.00 | TON |
| 0048 | 306-08034 | MILLING, ASPHALT, 1 1/2 IN. | 276680.00 | SYS |
| 0049 | 306-08043 | MILLING, TRANSITION | 2729.00 | SYS |
| 0050 | 306-08432 | MILLING, APPROACH | 2616.00 | SYS |
| 0051 | 306-08432 | MILLING, APPROACH | 1757.00 | SYS |
| 0052 | 401-07321 | QC/QA-HMA, 2, 64, SURFACE, 9.5 mm | 5765.00 | TON |
| 0053 | 401-07329 | QC/QA-HMA, 4, 70, SURFACE, 9.5 mm | 17024.00 | TON |
| 0054 | 401-07335 | QC/QA-HMA, 4, 76, SURFACE, 9.5 mm | 852.00 | TON |
| 0055 | 401-07390 | QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm | 663.00 | TON |
| 0056 | 401-07423 | QC/QA-HMA, 2, 64, BASE, 19.0 mm | 804.00 | TON |
| 0057 | 401-10258 | JOINT ADHESIVE, SURFACE | 193821.00 | LFT |
| 0058 | 401-10259 | JOINT ADHESIVE, INTERMEDIATE | 3210.00 | LFT |
| 0059 | 401-11785 | LIQUID ASPHALT SEALANT | 193821.00 | LFT |
| 0060 | 401-12169 | INERTIAL PROFILER, HMA | 1.00 | LS |
| 0061 | 402-05494 | HMA TRANSVERSE RUMBLE STRIPS | 300.00 | LFT |
| 0062 | 406-05520 | ASPHALT FOR TACK COAT | 117.79 | TON |
| 0063 | 408-07478 | CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL | 11.00 | TON |
| 0064 | 414-11468 | ULTRATHIN BONDED WEARING COURSE 9.5 mm | 12954.00 | SYS |
| 0065 | 502-03289 | QUALITY ASSURANCE ADJUSTMENT | 1.00 | DOL |
| 0066 | 502-06329 | PCCP, 12 IN. | 232.00 | SYS |
| 0067 | 503-03489 | RETROFITTED TIE BARS | 987.00 | EACH |
| 0068 | 503-12173 | TERMINAL JOINT, POLYMER MODIFIED ASPHALT | 938.00 | LFT |
| 0069 | 503-12480 | TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT | 768.00 | SFT |
| 0070 | 506-06333 | PCCP PATCHING, FULL DEPTH | 885.00 | SYS |
| 0071 | 506-06334 | PCCP PATCHING, PARTIAL DEPTH | 1953.00 | SYS |
| 0072 | 507-07480 | PROFILING, PCCP | 12954.00 | SYS |
| 0073 | 507-08272 | JOINTS IN PCCP, SAW AND SEAL | 3446.00 | LFT |
| 0074 | 601-01522 | GUARDRAIL, TRANSITION, TYPE TGB | 6.00 | EACH |
| 0075 | 601-01740 | GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4 | 1.00 | EACH |
| 0076 | 601-02241 | GUARDRAIL, REMOVE | 8899.00 | LFT |
| 0077 | 601-12281 | GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING | 3229.50 | LFT |
| 0078 | 601-12282 | GUARDRAIL, MGS W-BEAM, 3 FT 1.5 IN SPACING | 50.00 | LFT |
| 0079 | 601-12283 | GUARDRAIL, MGS W-BEAM, 1 FT 6.75 IN SPACING | 25.00 | LFT |
| 0080 | 601-12284 | GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING | 1500.00 | LFT |
| 0081 | 601-12289 | GUARDRAIL MGS, HEIGHT TRANSITION | 7.00 | EACH |
| 0082 | 601-12292 | GUARDRAIL MGS TRANSITION WITHOUT CURB | 26.00 | EACH |
| 0083 | 601-94689 | GUARDRAIL, END TREATMENT, OS | 16.00 | EACH |
| 0084 | 601-94690 | GUARDRAIL, END TREATMENT, MS | 13.00 | EACH |

| | | | |
|------|-----------|---|---------------|
| 0085 | 602-06729 | BARRIER, DELINEATOR | 132.00 EACH |
| 0086 | 603-06060 | FENCE, FARM FIELD, RESET | 240.00 LFT |
| 0087 | 605-05523 | CURB, HMA | 40.00 LFT |
| 0088 | 606-12399 | MILLED HMA CORRUGATIONS, CONVENTIONAL | 2096.00 LFT |
| 0089 | 606-12400 | MILLED HMA CORRUGATIONS, SINUSOIDAL | 115609.00 LFT |
| 0090 | 609-06259 | REINFORCED CONCRETE BRIDGE APPROACH, 12 IN. | 1761.00 SYS |
| 0091 | 609-06259 | REINFORCED CONCRETE BRIDGE APPROACH, 12 IN. | 1877.00 SYS |
| 0092 | 610-07487 | HMA FOR APPROACHES, TYPE B | 46.00 TON |
| 0093 | 610-07788 | HMA FOR APPROACHES, TYPE D | 353.00 TON |
| 0094 | 611-06497 | MAILBOX ASSEMBLY, SINGLE | 2.00 EACH |
| 0095 | 615-06505 | MONUMENT, B | 5.00 EACH |
| 0096 | 616-05688 | RIPRAP, CLASS 1 | 624.00 TON |
| 0097 | 616-06405 | RIPRAP, REVETMENT | 1474.00 TON |
| 0098 | 616-12246 | GEOTEXTILE FOR RIPRAP TYPE 1A | 1859.00 SYS |
| 0099 | 616-12248 | GEOTEXTILE FOR RIPRAP TYPE 2A | 713.00 SYS |
| 0100 | 616-51367 | SLOPEWALL, CONCRETE, 4 IN. | 8.00 SYS |
| 0101 | 621-01004 | MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 22.00 EACH |
| 0102 | 621-02770 | EROSION CONTROL BLANKET | 908.00 SYS |
| 0103 | 621-04258 | SEED MIXTURE | 5.00 LBS |
| 0104 | 621-06545 | FERTILIZER | 1.00 TON |
| 0105 | 621-06553 | SEED MIXTURE R | 39.00 LBS |
| 0106 | 621-06559 | MULCHED SEEDING R | 663.00 SYS |
| 0107 | 621-06560 | MULCHED SEEDING U | 2350.00 SYS |
| 0108 | 621-06565 | MULCHING MATERIAL | 1.00 TON |
| 0109 | 621-06567 | WATER | 0.60 KGAL |
| 0110 | 621-06574 | SODDING | 48.00 SYS |
| 0111 | 622-05641 | PLANT, DECIDUOUS SHRUB, 36 TO 48 IN. | 1.00 EACH |
| 0112 | 622-05648 | PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER | 1.00 EACH |
| 0113 | 622-05649 | PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN. | 2.00 EACH |
| 0114 | 628-09402 | FIELD OFFICE, B | 18.00 MOS |
| 0115 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 1.00 EACH |
| 0116 | 702-51005 | CONCRETE, A, SUBSTRUCTURE | 4.00 CYS |
| 0117 | 702-51863 | FIELD DRILLED HOLE IN CONCRETE | 1217.00 EACH |
| 0118 | 702-92857 | CONCRETE, C, SUBSTRUCTURE | 39.90 CYS |
| 0119 | 703-06028 | REINFORCING BARS | 489.00 LBS |
| 0120 | 703-06029 | REINFORCING BARS, EPOXY COATED | 514737.00 LBS |
| 0121 | 703-97936 | THREADED TIE BAR ASSEMBLY, EPOXY COATED | 2151.00 EACH |
| 0122 | 704-51002 | CONCRETE, C, SUPERSTRUCTURE | 850.70 CYS |
| 0123 | 706-11600 | RAILING, CONCRETE FC | 65.40 CYS |
| 0124 | 706-11600 | RAILING, CONCRETE FC | 14.00 CYS |
| 0125 | 706-11601 | RAILING, CONCRETE FT | 40.00 CYS |
| 0126 | 706-11620 | CONCRETE BRIDGE RAILING TRANSITION, TFC | 14.00 EACH |

| | | | | |
|------|-----------|---|-----------|------|
| 0127 | 706-11620 | CONCRETE BRIDGE RAILING TRANSITION, TFC | 32.00 | EACH |
| 0128 | 706-11621 | CONCRETE BRIDGE RAILING TRANSITION, TFT | 8.00 | EACH |
| 0129 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0130 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0131 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0132 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0133 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0134 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0135 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0136 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0137 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0138 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0139 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0140 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0141 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0142 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0143 | 709-51821 | SURFACE SEAL | 1.00 | LS |
| 0144 | 710-09158 | PATCHING CONCRETE STRUCTURES | 3601.00 | SFT |
| 0145 | 711-51038 | STRUCTURAL STEEL | 1.00 | LS |
| 0146 | 711-51864 | DRILLED HOLE | 248.00 | EACH |
| 0147 | 718-08308 | UNDERDRAIN PATCHING | 280.00 | LFT |
| 0148 | 718-09979 | UNDERDRAIN OUTLET CLEANING | 6.00 | EACH |
| 0149 | 718-12305 | GEOTEXTILES FOR UNDERDRAIN, TYPE 1A | 556.00 | SYS |
| 0150 | 718-12307 | GEOTEXTILE FOR UNDERDRAIN, TYPE 2A | 120.00 | SYS |
| 0151 | 722-01066 | HYDRODEMOLITION | 9311.00 | SYS |
| 0152 | 722-12380 | BRIDGE DECK OVERLAY, BUDGET | 164475.00 | DOL |
| 0153 | 722-12382 | TRANSVERSE GROOVING | 11223.00 | SYS |
| 0154 | 722-12463 | BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY | 7069.00 | SYS |
| 0155 | 722-12464 | BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE | 2242.00 | SYS |
| 0156 | 722-51401 | BRIDGE DECK PATCHING, FULL DEPTH | 2185.00 | SFT |
| 0157 | 722-51874 | OVERLAY DAM | 570.00 | SFT |
| 0158 | 724-12103 | PRE-COMPRESSED FOAM JOINT | 796.00 | LFT |
| 0159 | 726-11773 | BEARING ASSEMBLY RESET | 47.00 | EACH |
| 0160 | 732-11770 | AGGREGATE FOR DRAINAGE FILL | 299.00 | CYS |
| 0161 | 801-01093 | TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY | 40.00 | EACH |
| 0162 | 801-04308 | ROAD CLOSURE SIGN ASSEMBLY | 23.00 | EACH |
| 0163 | 801-06207 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 79792.00 | LFT |
| 0164 | 801-06469 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN. | 1690.00 | LFT |
| 0165 | 801-06625 | DETOUR ROUTE MARKER ASSEMBLY | 209.00 | EACH |
| 0166 | 801-06640 | CONSTRUCTION SIGN, A | 239.00 | EACH |
| 0167 | 801-06645 | CONSTRUCTION SIGN, B | 40.00 | EACH |
| 0168 | 801-06710 | FLASHING ARROW SIGN | 375.00 | DAY |

| | | | | |
|------|-----------|---|-----------|------|
| 0169 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0170 | 801-07118 | BARRICADE, III-A | 608.00 | LFT |
| 0171 | 801-07119 | BARRICADE, III-B | 144.00 | LFT |
| 0172 | 801-08401 | TEMPORARY TRAFFIC BARRIER, TYPE 2 | 4266.00 | LFT |
| 0173 | 801-08508 | TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2 | 3600.00 | LFT |
| 0174 | 801-12348 | TEMPORARY WORKSITE SPEED DISPLAY ASSEMBLY | 6.00 | EACH |
| 0175 | 802-04089 | SIGN, SHEET, REMOVE | 3.00 | EACH |
| 0176 | 802-05701 | SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE | 52.00 | LFT |
| 0177 | 802-07060 | SIGN, SHEET, RELOCATE | 1.00 | EACH |
| 0178 | 802-09838 | SIGN, SHEET, WITH LEGEND, 0.080 IN. | 12.00 | SFT |
| 0179 | 802-09840 | SIGN, SHEET, WITH LEGEND, 0.100 IN. | 31.50 | SFT |
| 0180 | 805-78470 | SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA | 4900.00 | LFT |
| 0181 | 805-78795 | SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT | 1740.00 | LFT |
| 0182 | 807-02191 | HANDHOLE LIGHTING | 2.00 | EACH |
| 0183 | 807-06592 | CONDUIT, STEEL, GALVANIZED, 2 IN. | 145.00 | LFT |
| 0184 | 807-86843 | WIRE, NO. 4 COPPER, 1/C | 580.00 | LFT |
| 0185 | 807-97237 | WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C | 105.00 | LFT |
| 0186 | 808-04298 | PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R | 4.00 | EACH |
| 0187 | 808-06701 | LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN. | 13697.00 | LFT |
| 0188 | 808-06703 | LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 68832.00 | LFT |
| 0189 | 808-06705 | LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN. | 6138.00 | LFT |
| 0190 | 808-06713 | LINE, PAINT, SOLID, WHITE, 4 IN. | 2600.00 | LFT |
| 0191 | 808-06714 | LINE, PAINT, SOLID, YELLOW, 4 IN. | 2600.00 | LFT |
| 0192 | 808-06716 | LINE, REMOVE | 39935.00 | LFT |
| 0193 | 808-06723 | PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW | 2.00 | EACH |
| 0194 | 808-09381 | RETRO-REFLECTIVITY TESTING | 1.00 | LS |
| 0195 | 808-10031 | LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN. | 5103.00 | LFT |
| 0196 | 808-10033 | LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN. | 13505.00 | LFT |
| 0197 | 808-10034 | LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN. | 16030.00 | LFT |
| 0198 | 808-10036 | LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN. | 976.00 | LFT |
| 0199 | 808-10037 | LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN. | 4030.00 | LFT |
| 0200 | 808-10038 | TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE WHITE 24 IN. | 370.00 | LFT |
| 0201 | 808-12032 | GROOVING FOR PAVEMENT MARKINGS | 192545.00 | LFT |
| 0202 | 808-75245 | LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 66969.00 | LFT |
| 0203 | 808-75272 | TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN. | 1750.00 | LFT |
| 0204 | 808-75297 | TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN. | 362.00 | LFT |
| 0205 | 808-75320 | PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW | 13.00 | EACH |
| 0206 | 808-75325 | PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY | 10.00 | EACH |
| 0207 | 808-75996 | SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 1029.00 | EACH |
| 0208 | 808-75998 | SNOWPLOWABLE RAISED PAVEMENT MARKER | 961.00 | EACH |

Call: 630

Contract: B -40531-A

Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY

Line

| Item No | Item Code | Description | Quantity | Unit |
|----------------|------------------|-------------------------------------|-----------------|-------------|
| 0209 | 722-51842 | BRIDGE DECK OVERLAY, LATEX MODIFIED | 9403.00 | SYS |

Call: 630

Contract: B -40531-A

Section No.: 3 SILICA FUME MODIFIED CONCRETE OVERLAY

Line

| Item No | Item Code | Description | Quantity | Unit |
|----------------|------------------|---|-----------------|-------------|
| 0210 | 722-01061 | BRIDGE DECK OVERLAY, SILICA FUME MODIFIED | 9403.00 | SYS |

Call: 690

Contract: B -41018-A

Section No.: 1 SMALL STRUCTURE MAINTENANCE AND REPAIR

Line

| Item No | Item Code | Description | Quantity | Unit |
|----------------|------------------|--|-----------------|-------------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0005 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0006 | 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 1.00 | DOL |
| 0007 | 109-11362 | QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES | 1.00 | DOL |
| 0008 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0009 | 201-52370 | CLEARING RIGHT OF WAY | 1.00 | LS |
| 0010 | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS | 1.00 | LS |
| 0011 | 203-02020 | EXCAVATION, UNCLASSIFIED | 35.00 | CYS |
| 0012 | 205-12108 | STORM WATER MANAGEMENT BUDGET | 2300.00 | DOL |
| 0013 | 205-12109 | SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1 | 1.00 | LS |
| 0014 | 206-51235 | COFFERDAM | 1.00 | LS |
| 0015 | 211-09268 | STRUCTURE BACKFILL, TYPE 5 | 35.00 | CYS |
| 0016 | 601-06035 | GUARDRAIL, RESET | 25.00 | LFT |
| 0017 | 621-01004 | MOBILIZATION AND DEMOBILIZATION FOR SEEDING | 1.00 | EACH |
| 0018 | 621-02318 | SEED MIXTURE, PRAIRIE GRASS | 1.30 | LBS |
| 0019 | 702-51005 | CONCRETE, A, SUBSTRUCTURE | 20.00 | CYS |
| 0020 | 703-06028 | REINFORCING BARS | 3284.00 | LBS |
| 0021 | 722-51852 | BRIDGE DECK PATCHING, PARTIAL DEPTH | 70.00 | SFT |
| 0022 | 724-12103 | PRE-COMPRESSED FOAM JOINT | 140.00 | LFT |
| 0023 | 801-06640 | CONSTRUCTION SIGN, A | 46.00 | EACH |
| 0024 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |

Call: 720

Contract: B -41866-A

Section No.: 1

BRIDGE THIN DECK OVERLAY

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|--|----------|------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0003 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0004 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0005 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0006 | 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 1.00 | DOL |
| 0007 | 109-09377 | QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS | 1.00 | DOL |
| 0008 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0009 | 201-52370 | CLEARING RIGHT OF WAY | 1.00 | LS |
| 0010 | 202-02240 | PAVEMENT REMOVAL | 1370.00 | SYS |
| 0011 | 202-02273 | CENTER CURB, CONCRETE, REMOVE | 54.00 | SYS |
| 0012 | 202-52710 | SIDEWALK CONCRETE, REMOVE | 90.00 | SYS |
| 0013 | 202-62420 | BRIDGE RAILING, REMOVE | 35.00 | LFT |
| 0014 | 203-02070 | BORROW | 2.00 | CYS |
| 0015 | 207-09935 | SUBGRADE TREATMENT, TYPE IC | 1220.00 | SYS |
| 0016 | 214-12244 | GEOTEXTILE FOR SUBGRADE TYPE 2B | 1220.00 | SYS |
| 0017 | 301-12234 | COMPACTED AGGREGATE NO. 53 | 10.00 | CYS |
| 0018 | 302-06464 | SUBBASE FOR PCCP | 308.00 | CYS |
| 0019 | 503-05240 | D-1 CONTRACTION JOINT | 168.00 | LFT |
| 0020 | 503-12476 | JOINTED REINFORCED CONCRETE PAVEMENT 12 IN. | 760.00 | SYS |
| 0021 | 503-12478 | TERMINAL JOINT, TYPE PCCP | 200.00 | LFT |
| 0022 | 503-12479 | EXPANSION JOINT WITH LOAD TRANSFER | 168.00 | LFT |
| 0023 | 503-12480 | TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT | 3764.00 | SFT |
| 0024 | 507-07482 | CRACKS IN PCCP, ROUT AND SEAL | 2189.00 | LFT |
| 0025 | 507-08269 | CRACKS IN PCCP, FILLED | 5466.00 | LFT |
| 0026 | 507-08271 | JOINTS IN PCCP, FILLED | 500.00 | LFT |
| 0027 | 507-08272 | JOINTS IN PCCP, SAW AND SEAL | 500.00 | LFT |
| 0028 | 601-06035 | GUARDRAIL, RESET | 25.00 | LFT |
| 0029 | 604-02007 | SIDEWALK, CONCRETE, RECONSTRUCT | 90.00 | SYS |
| 0030 | 605-06250 | CENTER CURB, C CONCRETE | 54.00 | SYS |
| 0031 | 609-06259 | REINFORCED CONCRETE BRIDGE APPROACH, 12 IN. | 474.00 | SYS |
| 0032 | 616-12246 | GEOTEXTILE FOR RIPRAP TYPE 1A | 20.00 | SYS |
| 0033 | 619-11052 | CLEAN STEEL BRIDGE, QP-2, BRIDGE NO. | 1.00 | LS |
| 0034 | 619-12459 | DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO | 1.00 | LS |
| 0035 | 619-51859 | PAINT STEEL BRIDGE, BRIDGE NO. | 1.00 | LS |
| 0036 | 628-09403 | FIELD OFFICE, C | 8.00 | MOS |
| 0037 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 3.00 | EACH |

| | | | |
|------|-----------|---|---------------|
| 0038 | 702-51863 | FIELD DRILLED HOLE IN CONCRETE | 46.00 EACH |
| 0039 | 703-06029 | REINFORCING BARS, EPOXY COATED | 31721.00 LBS |
| 0040 | 704-51002 | CONCRETE, C, SUPERSTRUCTURE | 9.80 CYS |
| 0041 | 706-06372 | CONCRETE BRIDGE RAILING TRANSITION, TTX | 4.00 EACH |
| 0042 | 706-92612 | RAILING, CONCRETE C, MODIFIED | 35.00 LFT |
| 0043 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0044 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0045 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0046 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0047 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0048 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0049 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0050 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0051 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0052 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0053 | 709-51821 | SURFACE SEAL | 1.00 LS |
| 0054 | 710-09158 | PATCHING CONCRETE STRUCTURES | 121.00 SFT |
| 0055 | 715-05048 | PIPE, TYPE 4, CIRCULAR, 6 IN. | 160.00 LFT |
| 0056 | 718-52610 | AGGREGATE FOR UNDERDRAINS | 18.00 CYS |
| 0057 | 722-12380 | BRIDGE DECK OVERLAY, BUDGET | 40530.00 DOL |
| 0058 | 722-12382 | TRANSVERSE GROOVING | 2270.00 SYS |
| 0059 | 722-12464 | BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE | 2270.00 SYS |
| 0060 | 722-51401 | BRIDGE DECK PATCHING, FULL DEPTH | 500.00 SFT |
| 0061 | 722-51852 | BRIDGE DECK PATCHING, PARTIAL DEPTH | 7880.00 SFT |
| 0062 | 724-04163 | STRUCTURAL EXPANSION JOINT SEAL, REPLACE | 2710.00 LFT |
| 0063 | 724-11063 | STRUCTURAL EXPANSION JOINT, SS, REPLACE | 821.00 LFT |
| 0064 | 724-12103 | PRE-COMPRESSED FOAM JOINT | 215.00 LFT |
| 0065 | 727-90308 | EPOXY INJECTION, CRACK PREPARATION | 104.00 LFT |
| 0066 | 727-90309 | EPOXY INJECTION, EPOXY MATERIAL | 22.00 GAL |
| 0067 | 727-93560 | EPOXY INJECTION, FURNISHING EQUIPMENT | 1.00 LS |
| 0068 | 727-93560 | EPOXY INJECTION, FURNISHING EQUIPMENT | 1.00 LS |
| 0069 | 738-09456 | POLYMERIC CONCRETE BRIDGE DECK OVERLAY | 20292.00 SYS |
| 0070 | 801-03290 | CONSTRUCTION SIGN, C | 26.00 EACH |
| 0071 | 801-04308 | ROAD CLOSURE SIGN ASSEMBLY | 3.00 EACH |
| 0072 | 801-06203 | TEMPORARY PAVEMENT MARKING, 4 IN. | 83694.00 LFT |
| 0073 | 801-06207 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN. | 290261.00 LFT |
| 0074 | 801-06577 | TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN. | 36.00 LFT |
| 0075 | 801-06586 | TEMPORARY PAVEMENT MARKING, 8 IN. | 5740.00 LFT |
| 0076 | 801-06625 | DETOUR ROUTE MARKER ASSEMBLY | 58.00 EACH |
| 0077 | 801-06640 | CONSTRUCTION SIGN, A | 114.00 EACH |
| 0078 | 801-06645 | CONSTRUCTION SIGN, B | 13.00 EACH |
| 0079 | 801-06710 | FLASHING ARROW SIGN | 50.00 DAY |

| | | | | |
|------|-----------|---|-----------|------|
| 0080 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0081 | 801-07024 | ENERGY ABSORBING TERMINAL, CZ, TL-3 | 1.00 | EACH |
| 0082 | 801-07118 | BARRICADE, III-A | 96.00 | LFT |
| 0083 | 801-07119 | BARRICADE, III-B | 72.00 | LFT |
| 0084 | 801-07612 | TEMPORARY PAVEMENT MARKING, 24 IN. | 660.00 | LFT |
| 0085 | 801-08401 | TEMPORARY TRAFFIC BARRIER, TYPE 2 | 16272.00 | LFT |
| 0086 | 801-08508 | TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2 | 3573.00 | LFT |
| 0087 | 801-11642 | PORTABLE CHANGEABLE MESSAGE SIGN | 4.00 | EACH |
| 0088 | 801-12042 | TRUCK MOUNTED ATTENUATOR | 28.00 | DAY |
| 0089 | 801-97643 | TEMPORARY BUZZ STRIPS | 4085.00 | LFT |
| 0090 | 802-11843 | RADAR SPEED DISPLAY SIGN ASSEMBLY | 4.00 | EACH |
| 0091 | 808-06716 | LINE, REMOVE | 186545.00 | LFT |
| 0092 | 808-09381 | RETRO-REFLECTIVITY TESTING | 1.00 | LS |
| 0093 | 808-10031 | LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN. | 7160.00 | LFT |
| 0094 | 808-10033 | LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN. | 34528.00 | LFT |
| 0095 | 808-10034 | LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN. | 28249.00 | LFT |
| 0096 | 808-10037 | LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN. | 3142.00 | LFT |
| 0097 | 808-10038 | TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE WHITE 24 IN. | 3820.00 | LFT |
| 0098 | 808-10054 | LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN. | 15814.00 | LFT |
| 0099 | 808-12032 | GROOVING FOR PAVEMENT MARKINGS | 92384.00 | LFT |
| 0100 | 808-75996 | SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 161.00 | EACH |

Call: 720

Contract: B -41866-A

Section No.: 2 BRIDGE DECK OVERLAY SILICA FUME

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|---|----------|------|
| 0101 | 722-01061 | BRIDGE DECK OVERLAY, SILICA FUME MODIFIED | 2270.00 | SYS |

Call: 720

Contract: B -41866-A

Section No.: 3 BRIDGE DECK OVERLAY LATEX MODIFIED

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|-------------------------------------|----------|------|
| 0102 | 722-51842 | BRIDGE DECK OVERLAY, LATEX MODIFIED | 2270.00 | SYS |

Call: 830

Contract: T -40050-A

Section No.: 1 TRAFFIC SIGNAL VISIBILITY IMPROVEMENTS

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|--------------------|----------|------|
| 0001 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0002 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |

| | | | | |
|------|-----------|--|----------|------|
| 0003 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0004 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0005 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0006 | 628-09403 | FIELD OFFICE, C | 12.00 | MOS |
| 0007 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 2.00 | EACH |
| 0008 | 801-06710 | FLASHING ARROW SIGN | 176.00 | DAY |
| 0009 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0010 | 801-92448 | CONSTRUCTION SIGNS MOBILE | 1404.00 | DAY |
| 0011 | 802-04089 | SIGN, SHEET, REMOVE | 65.00 | EACH |
| 0012 | 802-09838 | SIGN, SHEET, WITH LEGEND, 0.080 IN. | 60.00 | SFT |
| 0013 | 802-09840 | SIGN, SHEET, WITH LEGEND, 0.100 IN. | 977.00 | SFT |
| 0014 | 805-01300 | TRAFFIC SIGNAL EQUIPMENT, REMOVE | 85.00 | EACH |
| 0015 | 805-01579 | MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS | 1.00 | LS |
| 0016 | 805-01824 | SPAN, CATENARY, AND TETHER, TIGHTEN | 248.00 | EACH |
| 0017 | 805-02445 | CONTROLLER AND CABINET, P1 | 5.00 | EACH |
| 0018 | 805-03372 | TETHER FOR SIGNAL | 36.00 | EACH |
| 0019 | 805-06483 | CONTROLLER | 20.00 | EACH |
| 0020 | 805-09539 | LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL | 29.00 | EACH |
| 0021 | 805-12325 | TRAFFIC SIGNAL HEAD OPTICALLY PROGRAMED | 1.00 | EACH |
| 0022 | 805-78205 | TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN. | 675.00 | EACH |
| 0023 | 805-78225 | TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN. | 100.00 | EACH |
| 0024 | 805-78230 | TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN. | 20.00 | EACH |
| 0025 | 805-78245 | TRAFFIC SIGNAL HEAD, OPTICALLY PROGRAMMED, 3 SECTION, 12 IN. | 10.00 | EACH |
| 0026 | 805-78415 | SPAN, CATENARY, AND TETHER | 248.00 | EACH |
| 0027 | 805-78420 | DISCONNECT HANGER | 38.00 | EACH |
| 0028 | 805-78485 | SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA | 35145.00 | LFT |
| 0029 | 805-78490 | SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA | 6892.00 | LFT |
| 0030 | 805-78495 | SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA | 16084.00 | LFT |
| 0031 | 805-92504 | LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL | 19.00 | EACH |

Call: 850

Contract: T -41836-A

Section No.: 1 NEW SIGNAL INSTALLATION

Line

| Item No | Item Code | Description | Quantity | Unit |
|---------|-----------|--|----------|------|
| 0001 | 105-06845 | CONSTRUCTION ENGINEERING | 1.00 | LS |
| 0002 | 107-09358 | INSPECTION HOLE, DEEPER THAN 3 FT | 16.00 | EACH |
| 0003 | 109-08359 | LIQUIDATED DAMAGES | 1.00 | DOL |
| 0004 | 109-08360 | CONTRACT LIENS | 1.00 | DOL |
| 0005 | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES | 1.00 | DOL |
| 0006 | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS | 1.00 | DOL |
| 0007 | 109-08463 | PROJECT ESTIMATE ADJUSTMENT | 1.00 | DOL |

| | | | | |
|------|-----------|---|---------|------|
| 0008 | 110-01001 | MOBILIZATION AND DEMOBILIZATION | 1.00 | LS |
| 0009 | 201-52370 | CLEARING RIGHT OF WAY | 1.00 | LS |
| 0010 | 202-01000 | STRUCTURES AND OBSTRUCTIONS, REMOVE | 1.00 | LS |
| 0011 | 202-93741 | GUARDRAIL, END TREATMENT, REMOVE | 2.00 | EACH |
| 0012 | 202-93995 | SIGNAL POLE FOUNDATION, REMOVE | 6.00 | EACH |
| 0013 | 202-93999 | SIGNAL POLE, REMOVE | 6.00 | EACH |
| 0014 | 203-02000 | EXCAVATION, COMMON | 68.00 | CYS |
| 0015 | 601-02241 | GUARDRAIL, REMOVE | 103.00 | LFT |
| 0016 | 621-06553 | SEED MIXTURE R | 205.00 | LBS |
| 0017 | 628-09402 | FIELD OFFICE, B | 9.00 | MOS |
| 0018 | 628-11976 | COMPUTER SYSTEM EQUIPMENT | 1.00 | EACH |
| 0019 | 801-06640 | CONSTRUCTION SIGN, A | 240.00 | EACH |
| 0020 | 801-06775 | MAINTAINING TRAFFIC | 1.00 | LS |
| 0021 | 802-09838 | SIGN, SHEET, WITH LEGEND, 0.080 IN. | 15.00 | SFT |
| 0022 | 802-09842 | SIGN, SHEET, WITH LEGEND, 0.125 IN. | 186.00 | SFT |
| 0023 | 805-01815 | SIGNAL POLE FOUNDATION, 36 IN. X 144 IN. | 16.00 | EACH |
| 0024 | 805-01820 | SIGNAL POLE, STEEL STRAIN, INSTALL | 4.00 | EACH |
| 0025 | 805-01842 | HANDHOLE SIGNAL TYPE 1 | 27.00 | EACH |
| 0026 | 805-02445 | CONTROLLER AND CABINET, P1 | 4.00 | EACH |
| 0027 | 805-07842 | VEHICLE DETECTION SYSTEM | 1.00 | EACH |
| 0028 | 805-11813 | CONDUIT, PVC, 2 IN. SCHEDULE 80 | 4676.00 | LFT |
| 0029 | 805-78205 | TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN. | 34.00 | EACH |
| 0030 | 805-78225 | TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN. | 2.00 | EACH |
| 0031 | 805-78415 | SPAN, CATENARY, AND TETHER | 16.00 | EACH |
| 0032 | 805-78420 | DISCONNECT HANGER | 16.00 | EACH |
| 0033 | 805-78445 | SIGNAL SERVICE | 4.00 | EACH |
| 0034 | 805-78467 | SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA | 198.00 | LFT |
| 0035 | 805-78470 | SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA | 6784.00 | LFT |
| 0036 | 805-78485 | SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA | 1019.00 | LFT |
| 0037 | 805-78490 | SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA | 4478.00 | LFT |
| 0038 | 805-78510 | SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA | 9096.00 | LFT |
| 0039 | 805-78785 | SIGNAL DETECTOR HOUSING | 26.00 | EACH |
| 0040 | 805-78795 | SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT | 2294.00 | LFT |
| 0041 | 805-78925 | CONTROLLER CABINET FOUNDATION, P1 | 4.00 | EACH |
| 0042 | 805-81060 | SIGNAL POLE, STEEL STRAIN, 36 FT | 12.00 | EACH |
| 0043 | 808-05866 | PAVEMENT MESSAGE MARKING, REMOVE | 4.00 | SYS |
| 0044 | 808-06368 | TRANSVERSE MARKING, REMOVE | 185.00 | LFT |
| 0045 | 808-06703 | LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN. | 309.00 | LFT |
| 0046 | 808-06716 | LINE, REMOVE | 1623.00 | LFT |
| 0047 | 808-75245 | LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN. | 650.00 | LFT |
| 0048 | 808-75297 | TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN. | 212.00 | LFT |
| 0049 | 808-75320 | PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW | 2.00 | EACH |