

Schedule of Pay Items Letting Date February 5, 2020 Letting ID 200205

Call: 160

Contract: R -38073-A

Section No.: 1 ADDED TRAVEL LANES

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02637	PIPE ABANDON AND GROUT FILL	1398.00	LFT
0014	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00	LS
0015	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0016	203-02000	EXCAVATION, COMMON	147134.00	CYS
0017	203-02100	EXCAVATION, PEAT	1198.00	CYS
0018	203-51223	EXCAVATION, WATERWAY	1385.00	CYS
0019	204-08415	STAKE, SETTLEMENT	6.00	EACH
0020	205-11626	PUMP AROUND	3.00	EACH
0021	205-12108	STORM WATER MANAGEMENT BUDGET	70000.00	DOL
0022	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0023	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	334.00	CYS
0024	207-08264	SUBGRADE TREATMENT, TYPE II	291.00	SYS
0025	207-08266	SUBGRADE TREATMENT, TYPE III	22462.00	SYS
0026	207-09934	SUBGRADE TREATMENT, TYPE IB	58626.00	SYS
0027	207-09935	SUBGRADE TREATMENT, TYPE IC	378.00	SYS
0028	211-06467	AGGREGATE FOR END BENT BACKFILL	164.00	CYS
0029	211-09264	STRUCTURE BACKFILL, TYPE 1	2443.00	CYS
0030	211-09265	STRUCTURE BACKFILL, TYPE 2	1733.00	CYS
0031	211-09268	STRUCTURE BACKFILL, TYPE 5	79.00	CYS
0032	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	465.00	CYS
0033	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	1705.00	SYS

0034	217-11917	DRYING SOILS FOR EMBANKMENT	2421.00 TON
0035	301-12232	COMPACTED AGGREGATE NO. 5	233.00 CYS
0036	301-12234	COMPACTED AGGREGATE NO. 53	117.00 CYS
0037	302-07455	DENSE GRADED SUBBASE	79.00 CYS
0038	303-01180	COMPACTED AGGREGATE NO. 53	9080.00 TON
0039	304-07494	WIDENING WITH HMA, TYPE C	90.00 TON
0040	306-08034	MILLING, ASPHALT, 1 1/2 IN.	5053.00 SYS
0041	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	366.00 TON
0042	401-07339	QC/QA-HMA, 2, 64, SURFACE, 12.5 mm	1583.00 TON
0043	401-07403	QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	4492.00 TON
0044	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	11017.00 TON
0045	401-10258	JOINT ADHESIVE, SURFACE	18054.00 LFT
0046	401-10259	JOINT ADHESIVE, INTERMEDIATE	16219.00 LFT
0047	401-11785	LIQUID ASPHALT SEALANT	18374.00 LFT
0048	401-11897	QC/QA-HMA, 2, 64, INTERMEDIATE, 25.0 mm	3247.00 TON
0049	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	5480.00 TON
0050	402-10086	HMA FOR TEMPORARY PAVEMENT, C	1881.00 TON
0051	406-05520	ASPHALT FOR TACK COAT	34.00 TON
0052	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00 TON
0053	410-10128	QC/QA-HMA, 3, 76, SURFACE, 9.5 mm - SMA	2766.00 TON
0054	415-11527	BASE SEAL	32.00 TON
0055	502-11564	PCCP, 7 IN.	245.00 SYS
0056	503-05240	D-1 CONTRACTION JOINT	128.00 LFT
0057	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	1.00 EACH
0058	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	1.00 EACH
0059	601-94689	GUARDRAIL, END TREATMENT, OS	1.00 EACH
0060	601-94689	GUARDRAIL, END TREATMENT, OS	1.00 EACH
0061	603-91714	FENCE, RAIL WOOD	216.00 LFT
0062	604-05528	HMA FOR SIDEWALK	1995.00 TON
0063	604-06070	SIDEWALK, CONCRETE	178.00 SYS
0064	604-08086	CURB RAMP, CONCRETE	274.00 SYS
0065	604-12083	DETECTABLE WARNING SURFACES	40.00 SYS
0066	605-06090	CURB, INTEGRAL CONCRETE	248.00 LFT
0067	605-06120	CURB, CONCRETE	9096.00 LFT
0068	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	10833.00 LFT
0069	605-06160	CURB AND GUTTER, B, CONCRETE, MODIFIED	301.00 LFT
0070	605-06250	CENTER CURB, C CONCRETE	285.00 SYS
0071	605-97937	CURB AND GUTTER, ROLL CURB	325.00 LFT
0072	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	469.00 SYS
0073	610-07487	HMA FOR APPROACHES, TYPE B	149.00 TON
0074	610-08446	PCCP FOR APPROACHES, 6 IN.	63.00 SYS
0075	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00 EACH

0076	615-06490	RIGHT-OF-WAY MARKER	25.00 EACH
0077	615-06505	MONUMENT, B	22.00 EACH
0078	615-06510	MONUMENT, C	11.00 EACH
0079	615-06515	MONUMENT, D	1.00 EACH
0080	615-06527	MONUMENT, SECTION CORNER	2.00 EACH
0081	616-05688	RIPRAP, CLASS 1	1186.00 TON
0082	616-06405	RIPRAP, REVETMENT	484.00 TON
0083	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	2923.00 SYS
0084	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	6.00 EACH
0085	621-02770	EROSION CONTROL BLANKET	793.00 SYS
0086	621-04258	SEED MIXTURE	24.00 LBS
0087	621-06545	FERTILIZER	8.00 TON
0088	621-06554	SEED MIXTURE U	3885.00 LBS
0089	621-06565	MULCHING MATERIAL	39.00 TON
0090	621-06567	WATER	24.00 KGAL
0091	621-06574	SODDING	11157.00 SYS
0092	622-05639	PLANT, DECIDUOUS SHRUB, 18 TO 24 IN.	38.00 EACH
0093	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 TO 2 IN.	76.00 EACH
0094	622-52436	SIGN, DO NOT MOW OR SPRAY	5.00 EACH
0095	628-09402	FIELD OFFICE, B	24.00 MOS
0096	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0097	701-06011	DYNAMIC PILE LOAD TEST	2.00 EACH
0098	701-09557	TEST PILE, DYNAMIC, PRODUCTION	128.00 LFT
0099	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.00 EACH
0100	701-12360	PREBORED HOLE, 21 IN	1276.00 LFT
0101	701-51195	PILE, STEEL H HP 12 X 53	1728.00 LFT
0102	702-51863	FIELD DRILLED HOLE IN CONCRETE	326.00 EACH
0103	703-06029	REINFORCING BARS, EPOXY COATED	147810.00 LBS
0104	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	616.00 EACH
0105	704-51002	CONCRETE, C, SUPERSTRUCTURE	730.50 CYS
0106	704-51006	CONCRETE, C, SUPERSTRUCTURE, MODIFIED	75.70 CYS
0107	706-06353	CONCRETE BRIDGE RAILING TRANSITION, TPS-1	4.00 EACH
0108	706-11418	RAILING, STEEL PS-1	257.00 LFT
0109	706-51020	RAILING, CONCRETE C	43.70 CYS
0110	707-09921	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 54 IN. X 49 IN.	1428.00 LFT
0111	709-51821	SURFACE SEAL	1.00 LS
0112	713-11199	TEMPORARY PIPE	195.00 LFT
0113	714-11103	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 16 FT X 7 FT	190.00 LFT
0114	714-12023	STRUCTURE, COATED REINFORCED CONCRETE BOX SECTIONS, 14 FT X 5 FT	66.00 LFT
0115	715-04855	PIPE END SECTION, DIA 42 IN.	4.00 EACH
0116	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	60.00 LFT
0117	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	74.00 LFT

0118	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	20848.00	LFT
0119	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	901.00	LFT
0120	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	174.00	LFT
0121	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	31.00	LFT
0122	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	2687.00	LFT
0123	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	2358.00	LFT
0124	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	1191.00	LFT
0125	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	877.00	LFT
0126	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	674.00	LFT
0127	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	176.00	LFT
0128	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	48.00	LFT
0129	715-05407	PIPE, END BENT DRAIN, 6 IN.	220.00	LFT
0130	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	4.00	TON
0131	715-09064	VIDEO INSPECTION FOR PIPE	8320.00	LFT
0132	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0133	715-46005	PIPE END SECTION, DIAMETER 15 IN.	14.00	EACH
0134	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0135	715-46020	PIPE END SECTION, DIAMETER 24 IN.	3.00	EACH
0136	715-46030	PIPE END SECTION, DIAMETER 30 IN.	2.00	EACH
0137	715-46040	PIPE END SECTION, DIAMETER 36 IN.	3.00	EACH
0138	718-06529	OUTLET PROTECTOR, 2	1.00	EACH
0139	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00	LFT
0140	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	14285.00	SYS
0141	718-52610	AGGREGATE FOR UNDERDRAINS	1651.00	CYS
0142	720-44000	CASTING, ADJUST TO GRADE	3.00	EACH
0143	720-45030	INLET, E7	5.00	EACH
0144	720-45410	MANHOLE, C4	23.00	EACH
0145	720-94612	MANHOLE, K4	3.00	EACH
0146	720-95422	MANHOLE, J4	4.00	EACH
0147	720-98174	INLET, B15	33.00	EACH
0148	720-98555	INLET, C15	31.00	EACH
0149	720-99416	CATCH BASIN, B15	3.00	EACH
0150	720-99417	CATCH BASIN, C15	14.00	EACH
0151	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	EACH
0152	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	34590.00	LFT
0153	801-06586	TEMPORARY PAVEMENT MARKING, 8 IN.	200.00	LFT
0154	801-06625	DETOUR ROUTE MARKER ASSEMBLY	56.00	EACH
0155	801-06640	CONSTRUCTION SIGN, A	33.00	EACH
0156	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0157	801-06775	MAINTAINING TRAFFIC	1.00	LS
0158	801-07119	BARRICADE, III-B	290.00	LFT
0159	801-07612	TEMPORARY PAVEMENT MARKING, 24 IN.	60.00	LFT

0160	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1138.00	LFT
0161	801-11692	TEMPORARY PAVEMENT MARKING, 12 IN.	140.00	LFT
0162	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	682.00	LFT
0163	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	96.00	LFT
0164	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	22.00	EACH
0165	802-07060	SIGN, SHEET, RELOCATE	5.00	EACH
0166	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	159.00	SFT
0167	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	345.00	SFT
0168	807-02191	HANDHOLE LIGHTING	1.00	EACH
0169	807-02934	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. X 36 IN. X 96 IN.	8.00	EACH
0170	807-04866	LUMINAIRE	8.00	EACH
0171	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	210.00	LFT
0172	807-83492	LIGHT POLE, ROADWAY, 30 FT E.M.H. 10 FT MAST ARM, ANCHOR BASE	7.00	EACH
0173	807-83502	LIGHT POLE, ROADWAY, 30 FT E.M.H. 15 FT MAST ARM, ANCHOR BASE	1.00	EACH
0174	807-86805	SERVICE POINT, I	1.00	EACH
0175	807-86910	CONNECTOR KIT, UNFUSED	8.00	EACH
0176	807-86915	CONNECTOR KIT, FUSED	8.00	EACH
0177	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	18.00	EACH
0178	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	4.00	EACH
0179	807-86930	INSULATION LINK, NON-WATERPROOFED	18.00	EACH
0180	807-86935	INSULATION LINK, WATERPROOFED	4.00	EACH
0181	807-86950	SIGN, UNDERPASS AND ROADWAY LIGHTING LOCATION IDENTIFICATION	8.00	EACH
0182	807-87556	WIRE, TW/THW, NO. 10 COPPER, STRANDED	1440.00	LFT
0183	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	613.00	LFT
0184	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	611.00	LFT
0185	808-06368	TRANSVERSE MARKING, REMOVE	30.00	LFT
0186	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	2210.00	LFT
0187	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	16339.00	LFT
0188	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	165.00	LFT
0189	808-06716	LINE, REMOVE	5430.00	LFT
0190	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0191	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	10.00	LFT
0192	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	270.00	LFT
0193	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	4.00	EACH
0194	808-11478	LINE, THERMOPLASTIC, DOTTED, WHITE, 8 IN.	64.00	LFT
0195	808-11698	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 27 IN.	90.00	LFT
0196	808-12032	GROOVING FOR PAVEMENT MARKINGS	43477.00	LFT
0197	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	26374.00	LFT
0198	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	150.00	LFT
0199	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	24.00	LFT
0200	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	31.00	EACH
0201	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	2.00	EACH

0202	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	315.00 EACH
0203	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	245.00 LFT

Call: 230

Contract: R -40812-A

Section No.: 1 ASPHALT RESURFACE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0013	203-02000	EXCAVATION, COMMON	34041.00	CYS
0014	203-02010	EXCAVATION, ROCK	2530.00	CYS
0015	203-02070	BORROW	6295.00	CYS
0016	203-51223	EXCAVATION, WATERWAY	2403.00	CYS
0017	205-12108	STORM WATER MANAGEMENT BUDGET	105527.00	DOL
0018	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0019	206-51215	EXCAVATION, X	64.00	CYS
0020	206-51220	EXCAVATION, WET	100.00	CYS
0021	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	148.00	CYS
0022	207-08264	SUBGRADE TREATMENT, TYPE II	4481.00	SYS
0023	207-09934	SUBGRADE TREATMENT, TYPE IB	6209.00	SYS
0024	207-09935	SUBGRADE TREATMENT, TYPE IC	20247.00	SYS
0025	211-02050	B BORROW	4343.00	CYS
0026	211-06467	AGGREGATE FOR END BENT BACKFILL	62.00	CYS
0027	211-09264	STRUCTURE BACKFILL, TYPE 1	412.00	CYS
0028	211-09265	STRUCTURE BACKFILL, TYPE 2	120.00	CYS
0029	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	2978.00	SYS
0030	301-12231	COMPACTED AGGREGATE NO. 2	991.00	CYS
0031	301-12234	COMPACTED AGGREGATE NO. 53	2359.00	CYS
0032	302-07455	DENSE GRADED SUBBASE	53.00	CYS
0033	303-01180	COMPACTED AGGREGATE NO. 53	1906.00	TON
0034	306-08043	MILLING, TRANSITION	51.00	SYS

0035	306-08599	MILLING, ASPHALT, 1/2 IN.	6115.00	SYS
0036	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	2402.00	TON
0037	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	3253.00	TON
0038	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	3709.00	TON
0039	401-10258	JOINT ADHESIVE, SURFACE	20582.00	LFT
0040	401-10259	JOINT ADHESIVE, INTERMEDIATE	4501.00	LFT
0041	401-11785	LIQUID ASPHALT SEALANT	20582.00	LFT
0042	402-07451	HMA WEDGE AND LEVEL, TYPE B	388.00	TON
0043	406-05520	ASPHALT FOR TACK COAT	13.00	TON
0044	601-01848	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 5	1.00	EACH
0045	601-06374	GUARDRAIL, TRANSITION, TGS-1	4.00	EACH
0046	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0047	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	38.00	LFT
0048	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	315.00	SYS
0049	610-07487	HMA FOR APPROACHES, TYPE B	1317.00	TON
0050	611-06497	MAILBOX ASSEMBLY, SINGLE	30.00	EACH
0051	611-06498	MAILBOX ASSEMBLY, DOUBLE	8.00	EACH
0052	615-06490	RIGHT-OF-WAY MARKER	6.00	EACH
0053	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0054	616-05688	RIPRAP, CLASS 1	690.00	TON
0055	616-06405	RIPRAP, REVETMENT	1811.00	TON
0056	616-06451	RIPRAP, UNIFORM	6.00	TON
0057	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	3907.00	SYS
0058	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0059	621-02770	EROSION CONTROL BLANKET	1689.00	SYS
0060	621-06545	FERTILIZER	5.00	TON
0061	621-06553	SEED MIXTURE R	2033.00	LBS
0062	621-06565	MULCHING MATERIAL	25.00	TON
0063	621-06574	SODDING	4578.00	SYS
0064	621-08161	PERMANENT TURF REINFORCEMENT MAT	17.00	SYS
0065	628-09403	FIELD OFFICE, C	27.00	MOS
0066	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0067	628-11977	COMPUTER SYSTEM	1.00	EACH
0068	701-02938	CORED HOLE IN ROCK, 24 IN	36.00	LFT
0069	701-09739	PILE SHOE, HP 12 X 53	12.00	EACH
0070	701-51195	PILE, STEEL H HP 12 X 53	144.00	LFT
0071	702-51005	CONCRETE, A, SUBSTRUCTURE	97.00	CYS
0072	702-51015	CONCRETE, B, FOOTINGS	54.00	CYS
0073	703-06028	REINFORCING BARS	18715.00	LBS
0074	703-06029	REINFORCING BARS, EPOXY COATED	96300.00	LBS
0075	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	38.00	EACH
0076	704-51002	CONCRETE, C, SUPERSTRUCTURE	432.00	CYS

0077	706-06344	RAILING, STEEL TS-1	263.00	LFT
0078	709-51821	SURFACE SEAL	1.00	LS
0079	714-11304	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 7 FT. X 4 FT.	52.00	LFT
0080	715-04555	PIPE END SECTION, MIN. AREA 5.1 SFT	2.00	EACH
0081	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	75.00	LFT
0082	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	96.00	LFT
0083	715-05125	PIPE, TYPE 1, CIRCULAR, 30 IN.	147.00	LFT
0084	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	186.00	LFT
0085	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	1393.00	LFT
0086	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	54.00	LFT
0087	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	126.00	LFT
0088	715-05407	PIPE, END BENT DRAIN, 6 IN.	189.00	LFT
0089	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	66.00	TON
0090	715-08447	PIPE, TYPE 1, DEFORMED, MIN. AREA 5.1 SFT	46.00	LFT
0091	715-09064	VIDEO INSPECTION FOR PIPE	719.00	LFT
0092	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00	EACH
0093	715-46005	PIPE END SECTION, DIAMETER 15 IN.	59.00	EACH
0094	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0095	715-46020	PIPE END SECTION, DIAMETER 24 IN.	6.00	EACH
0096	715-46030	PIPE END SECTION, DIAMETER 30 IN.	2.00	EACH
0097	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	901.00	SYS
0098	718-52610	AGGREGATE FOR UNDERDRAINS	65.00	CYS
0099	720-45030	INLET, E7	3.00	EACH
0100	720-45035	INLET, F7	1.00	EACH
0101	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0102	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7796.00	LFT
0103	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	600.00	LFT
0104	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	45.00	LFT
0105	801-06625	DETOUR ROUTE MARKER ASSEMBLY	22.00	EACH
0106	801-06640	CONSTRUCTION SIGN, A	34.00	EACH
0107	801-06775	MAINTAINING TRAFFIC	1.00	LS
0108	801-07119	BARRICADE, III-B	168.00	LFT
0109	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	244.00	LFT
0110	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	97.00	SFT
0111	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	36.00	SFT
0112	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	1004.00	LFT
0113	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	16943.00	LFT
0114	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	8197.00	LFT
0115	808-06716	LINE, REMOVE	228.00	LFT
0116	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	1.00	EACH
0117	808-06724	PAVEMENT MESSAGE MARKING, PAINT, ONLY	1.00	EACH
0118	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	54.00	LFT