

Schedule of Pay Items Letting Date July 8, 2020 Letting ID 200708

Call: 131

Contract: R -39071-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-02245	TREE 6 IN., REMOVE	23.00 EACH
0011	201-02250	TREE 10 IN., REMOVE	8.00 EACH
0012	202-52710	SIDEWALK CONCRETE, REMOVE	1994.00 SYS
0013	205-12108	STORMWATER MANAGEMENT BUDGET	2900.00 DOL
0014	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00 LS
0015	207-09935	SUBGRADE TREATMENT, TYPE IC	570.00 SYS
0016	211-09265	STRUCTURE BACKFILL, TYPE 2	93.00 CYS
0017	303-01180	COMPACTED AGGREGATE NO. 53	60.00 TON
0018	304-07490	HMA PATCHING, TYPE B	250.00 TON
0019	306-08034	MILLING, ASPHALT, 1 1/2 IN.	8205.00 SYS
0020	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	560.00 TON
0021	402-07451	HMA WEDGE AND LEVEL, TYPE B	44.00 TON
0022	406-05521	ASPHALT FOR TACK COAT	6994.00 SYS
0023	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	52.00 TON
0024	604-06070	SIDEWALK, CONCRETE	3011.00 SYS
0025	604-07823	STAMPED CONCRETE SIDEWALK	678.00 SYS
0026	604-08086	CURB RAMP, CONCRETE	214.00 SYS
0027	604-12083	DETECTABLE WARNING SURFACES	60.00 SYS
0028	605-02278	CURB, REMOVE	2034.00 LFT
0029	605-06120	CURB, CONCRETE	125.00 LFT
0030	605-06140	CURB AND GUTTER, CONCRETE	755.00 LFT
0031	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	1288.00 LFT

0032	610-08446	PCCP FOR APPROACHES, 6 IN.	96.00	SYS
0033	618-03812	BENCH	8.00	EACH
0034	618-04181	BICYCLE RACK	8.00	EACH
0035	618-97672	TRASH RECEPTACLE	8.00	EACH
0036	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0037	621-06575	SODDING, NURSERY	275.00	SYS
0038	621-07643	TREE PROTECTION	38.00	EACH
0039	621-98038	MULCH HARDWOOD SHREDDED BARK	26.00	CYS
0040	622-04648	TREE GRATE	38.00	EACH
0041	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	38.00	EACH
0042	622-05654	PLANT, PERENNIAL	906.00	EACH
0043	628-09401	FIELD OFFICE, A	9.00	MOS
0044	715-05147	PIPE, TYPE 2, CIRCULAR, 8 IN.	61.00	LFT
0045	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	290.00	LFT
0046	715-08627	PIPE, TYPE 2, CIRCULAR, 4 IN.	90.00	LFT
0047	715-09064	VIDEO INSPECTION FOR PIPE	301.00	LFT
0048	716-09396	PIPE INSTALLATION, TRENCHLESS, 2 IN.	1610.00	LFT
0049	720-07309	TRENCH DRAIN	20.00	LFT
0050	720-44000	CASTING, ADJUST TO GRADE	3.00	EACH
0051	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	3.00	EACH
0052	720-44055	CASTING, 10, FURNISH AND ADJUST TO GRADE	1.00	EACH
0053	720-44296	INLET, CAP	2.00	EACH
0054	720-45250	CATCH BASIN, K10	11.00	EACH
0055	720-45410	MANHOLE, C4	6.00	EACH
0056	720-90984	MANHOLE, C2	2.00	EACH
0057	720-94208	MANHOLE, C10	1.00	EACH
0058	801-06640	CONSTRUCTION SIGN, A	29.00	EACH
0059	801-06645	CONSTRUCTION SIGN, B	18.00	EACH
0060	801-06775	MAINTAINING TRAFFIC	1.00	LS
0061	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	545.00	LFT
0062	802-03896	BOLLARD	15.00	EACH
0063	802-04089	SIGN, SHEET, REMOVE	1.00	EACH
0064	802-04314	SIGN	7.00	EACH
0065	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	439.00	LFT
0066	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	21.00	EACH
0067	802-07060	SIGN, SHEET, RELOCATE	6.00	EACH
0068	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	157.00	SFT

0069	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	200.00	LFT
0070	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	2070.00	LFT
0071	807-02191	HANDHOLE LIGHTING	18.00	EACH
0072	807-02426	WIRE, THW, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	4290.00	LFT
0073	807-03950	LUMINAIRE ORNAMENTAL	24.00	EACH
0074	807-03951	LIGHT POLE ORNAMENTAL	24.00	EACH
0075	807-04653	LIGHTING FOUNDATION	24.00	EACH
0076	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	2145.00	LFT
0077	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	630.00	LFT
0078	807-86805	SERVICE POINT, I	2.00	EACH
0079	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	1920.00	LFT
0080	807-86910	CONNECTOR KIT, UNFUSED	24.00	EACH
0081	807-86915	CONNECTOR KIT, FUSED	24.00	EACH
0082	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	63.00	EACH
0083	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	4.00	EACH
0084	807-86930	INSULATION LINK, NON-WATERPROOFED	48.00	EACH
0085	807-86935	INSULATION LINK, WATERPROOFED	4.00	EACH
0086	807-86950	SIGN, UNDERPASS AND ROADWAY LIGHTING LOCATION IDENTIFICATION	24.00	EACH
0087	808-02977	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	12.00	EACH
0088	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	910.00	LFT
0089	808-04298	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, R X R	2.00	EACH
0090	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1664.00	LFT
0091	808-09314	LINE, PAINT, SOLID, BLUE, 4 IN.	401.00	LFT
0092	808-12316	TRANSVERSE MARKING, PAINT, PARKING LINE, WHITE 4"	2055.00	LFT
0093	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	119.00	LFT
0094	808-95933	CURB, PAINTING, YELLOW	819.00	LFT
0095	808-97222	PAVEMENT MESSAGE MARKING, PAINT, ADA ACCESSIBLE SYMBOL	3.00	EACH

Call: 661

Contract: B -42687-A

Section No.: 1 IDIQ BRIDGE REHABILITATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0002	109-08360	CONTRACT LIENS	1.00 DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0007	110-07025	MOBILIZATION AND DEMOBILIZATION	5.00 EACH
0008	201-02245	TREE 6 IN., REMOVE	3.00 EACH
0009	201-02250	TREE 10 IN., REMOVE	3.00 EACH
0010	201-02255	TREE 18 IN., REMOVE	3.00 EACH
0011	201-02260	TREE 30 IN., REMOVE	3.00 EACH
0012	201-02265	TREE 48 IN., REMOVE	3.00 EACH
0013	201-02270	TREE 60 IN., REMOVE	3.00 EACH
0014	202-02240	PAVEMENT REMOVAL	500.00 SYS
0015	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0016	202-51368	SLOPEWALL, REMOVE	500.00 SYS
0017	202-52710	SIDEWALK CONCRETE, REMOVE	100.00 SYS
0018	202-93615	CONCRETE, REMOVE	100.00 SYS
0019	202-96133	PIPE, REMOVE	50.00 LFT
0020	203-02000	EXCAVATION, COMMON	75.00 CYS
0021	207-08268	SUBGRADE TREATMENT, TYPE IV	100.00 SYS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	100.00 SYS
0023	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	200.00 CYS
0024	213-09270	FLOWABLE BACKFILL, REMOVABLE	300.00 CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	150.00 TON
0026	303-07449	COMPACTED AGGREGATE NO. 73	150.00 TON
0027	402-07452	HMA WEDGE AND LEVEL, TYPE C	400.00 TON
0028	402-07787	HMA WEDGE AND LEVEL, TYPE D	400.00 TON
0029	406-05520	ASPHALT FOR TACK COAT	10.00 TON
0030	502-06327	PCCP, 10 IN.	100.00 SYS
0031	502-06329	PCCP, 12 IN.	100.00 SYS

0032	503-05240	D-1 CONTRACTION JOINT	100.00	LFT
0033	503-05310	TERMINAL JOINT	100.00	LFT
0034	506-06333	PCCP PATCHING, FULL DEPTH	100.00	SYS
0035	506-06334	PCCP PATCHING, PARTIAL DEPTH	100.00	SYS
0036	604-06070	SIDEWALK, CONCRETE	50.00	SYS
0037	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	100.00	SYS
0038	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	100.00	SYS
0039	616-05688	RIPRAP, CLASS 1	150.00	TON
0040	616-06405	RIPRAP, REVETMENT	150.00	TON
0041	616-51366	SLOPEWALL, CONCRETE, 5 IN.	600.00	SYS
0042	616-51367	SLOPEWALL, CONCRETE, 4 IN.	600.00	SYS
0043	616-93772	INSPECTION HOLE	6.00	EACH
0044	702-51005	CONCRETE, A, SUBSTRUCTURE	25.00	CYS
0045	702-90915	CONCRETE, CLASS, A	25.00	CYS
0046	703-06029	REINFORCING BARS, EPOXY COATED	500.00	LBS
0047	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	50.00	EACH
0048	706-51020	RAILING, CONCRETE C	50.00	CYS
0049	711-04297	STRUCTURAL STEEL, FIELD CUT	60.00	SQIN
0050	711-11599	REPAIR WELD	15.00	IN
0051	711-51864	DRILLED HOLE	8.00	EACH
0052	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00	LS
0053	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	200.00	SFT
0054	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	500.00	SFT
0055	722-97116	BRIDGE DECK OVERLAY, PATCHING	500.00	SFT
0056	724-03276	STRUCTURAL EXPANSION JOINT SEALING SYS	144.00	LFT
0057	801-06640	CONSTRUCTION SIGN, A	5.00	EACH
0058	801-06645	CONSTRUCTION SIGN, B	5.00	EACH
0059	801-06710	FLASHING ARROW SIGN	10.00	DAY
0060	801-07118	BARRICADE, III-A	72.00	LFT
0061	801-12042	TRUCK MOUNTED ATTENUATOR	20.00	DAY
0062	801-12440	MAINTAINING TRAFFIC, IDIQ	1.00	DOL
0063	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1000.00	LFT
0064	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1000.00	LFT