

**Schedule of Pay Items Letting Date May 7, 2020 Letting ID 200507**

Call: 221

Contract: R -40774-A

Section No.: 1            SMALL STRUCTURE REPLACEMENT

<b>Line</b>			<b>Quantity</b>	<b>Unit</b>
<b>Item No</b>	<b>Item Code</b>	<b>Description</b>		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	103.00	SYS
0012	202-07553	REGULATED MATERIALS, REMOVE, TYPE Y	86.00	CYS
0013	202-07554	REGULATED MATERIALS, TRANSPORT, TYPE Y	86.00	CYS
0014	202-07555	REGULATED MATERIALS, DISPOSE, TYPE Y	86.00	CYS
0015	202-94954	BARRIER WALL, CONCRETE, REMOVE	190.00	LFT
0016	203-02070	BORROW	36.00	CYS
0017	205-11583	MANUFACTURED SURFACE PROTECTION PRODUCT TYPE	111.00	SYS
0018	205-11626	PUMP AROUND	2.00	EACH
0019	205-12108	STORMWATER MANAGEMENT BUDGET	2800.00	DOL
0020	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00	LS
0021	207-12498	SUBGRADE TREATMENT, TYPE ID	241.00	SYS
0022	211-09264	STRUCTURE BACKFILL, TYPE 1	19.00	CYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	318.00	CYS
0024	301-12234	COMPACTED AGGREGATE NO. 53	12.00	CYS
0025	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	13.00	TON
0026	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	22.00	TON
0027	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	86.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	115.00	LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	115.00	LFT
0030	402-10087	HMA FOR TEMPORARY PAVEMENT, D	42.00	TON
0031	601-06035	GUARDRAIL, RESET	50.00	LFT

0032	602-11938	CONCRETE BARRIER, MODIFIED SECTION	35.00	CYS
0033	616-05689	RIPRAP, CLASS 2	146.00	TON
0034	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	138.00	SYS
0035	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0036	621-06559	MULCHED SEEDING R	383.00	SYS
0037	628-09402	FIELD OFFICE, B	8.00	MOS
0038	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0039	628-11730	CELLULAR TELEPHONE, TYPE B	1.00	EACH
0040	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0041	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0042	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	16.00	MOS
0043	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0044	628-11977	COMPUTER SYSTEM	1.00	EACH
0045	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	43.00	LFT
0046	715-06691	CONCRETE ANCHOR, 96 IN.	1.00	EACH
0047	715-06910	PIPE, TYPE 2, CIRCULAR, 96 IN.	92.00	LFT
0048	716-11716	PIPE INSTALLATION, TRENCHLESS,	54.00	LFT
0049	718-08308	UNDERDRAIN PATCHING	46.00	LFT
0050	720-45070	INLET, P12A	2.00	EACH
0051	720-45425	MANHOLE, F4	1.00	EACH
0052	720-45430	MANHOLE, G4	1.00	EACH
0053	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	11459.00	LFT
0054	801-06640	CONSTRUCTION SIGN, A	10.00	EACH
0055	801-06775	MAINTAINING TRAFFIC	1.00	LS
0056	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	350.00	LFT
0057	801-08507	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 1	60.00	LFT
0058	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	530.00	LFT
0059	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	170.00	LFT
0060	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1297.00	LFT
0061	808-06716	LINE, REMOVE	3007.00	LFT
0062	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1835.00	LFT

Call: 501

Contract: B -30550-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0012	203-02000	EXCAVATION, COMMON	2184.00	CYS
0013	203-02070	BORROW	685.00	CYS
0014	203-04523	DEWATERING	1.00	LS
0015	203-51223	EXCAVATION, WATERWAY	555.00	CYS
0016	205-11626	PUMP AROUND	4.00	EACH
0017	205-12108	STORMWATER MANAGEMENT BUDGET	26950.00	DOL
0018	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00	LS
0019	206-51220	EXCAVATION, WET	18.00	CYS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	4228.00	SYS
0021	211-09264	STRUCTURE BACKFILL, TYPE 1	17.20	CYS
0022	213-09270	FLOWABLE BACKFILL, REMOVABLE	22.00	CYS
0023	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	180.00	SYS
0024	301-12234	COMPACTED AGGREGATE NO. 53	1663.00	CYS
0025	302-06464	SUBBASE FOR PCCP	46.00	CYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	238.00	TON
0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	134.00	SYS
0028	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	303.00	TON
0029	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	692.00	TON
0030	401-10258	JOINT ADHESIVE, SURFACE	1042.00	LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	992.00	LFT

0032	401-11785	LIQUID ASPHALT SEALANT	1042.00	LFT
0033	406-05521	ASPHALT FOR TACK COAT	3882.00	SYS
0034	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH
0035	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	1.00	EACH
0036	601-02241	GUARDRAIL, REMOVE	398.00	LFT
0037	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	57.00	LFT
0038	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	3.00	EACH
0039	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0040	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	19.00	LFT
0041	602-06729	BARRIER, DELINEATOR	10.00	EACH
0042	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	184.00	SYS
0043	610-07487	HMA FOR APPROACHES, TYPE B	57.00	TON
0044	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0045	615-06490	RIGHT-OF-WAY MARKER	7.00	EACH
0046	615-06505	MONUMENT, B	5.00	EACH
0047	616-05688	RIPRAP, CLASS 1	23.00	TON
0048	616-06405	RIPRAP, REVETMENT	1153.00	TON
0049	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1898.00	SYS
0050	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0051	621-02770	EROSION CONTROL BLANKET	500.00	SYS
0052	621-06545	FERTILIZER	1.00	TON
0053	621-06553	SEED MIXTURE R	268.00	LBS
0054	621-06565	MULCHING MATERIAL	4.00	TON
0055	621-06567	WATER	4.00	KGAL
0056	621-06574	SODDING	962.00	SYS
0057	621-12612	SEED MIXTURE FLOODPLAIN	54.00	LBS
0058	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	6.00	EACH
0059	628-09402	FIELD OFFICE, B	12.00	MOS
0060	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0061	701-02945	PILE, STEEL H, REINFORCED CONCRETE ENCASED, HP 12 X 74	130.00	LFT
0062	701-09558	TEST PILE, INDICATOR, PRODUCTION	303.00	LFT
0063	701-09560	TEST PILE, INDICATOR, RESTRIKE	4.00	EACH
0064	701-09683	PILE SHOE, HP 12 X 74	18.00	EACH
0065	701-95780	PILE, STEEL H, HP 12 X 74	905.00	LFT
0066	703-06029	REINFORCING BARS, EPOXY COATED	79361.00	LBS
0067	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	36.00	EACH
0068	704-51002	CONCRETE, C, SUPERSTRUCTURE	290.50	CYS

0069	706-11600	RAILING, CONCRETE FC	21.00	CYS
0070	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0071	709-51821	SURFACE SEAL	1.00	LS
0072	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	32.00	LFT
0073	715-05175	PIPE, TYPE 3, CIRCULAR, 30 IN.	40.00	LFT
0074	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0075	715-46030	PIPE END SECTION, DIAMETER 30 IN.	2.00	EACH
0076	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0077	801-06625	DETOUR ROUTE MARKER ASSEMBLY	20.00	EACH
0078	801-06640	CONSTRUCTION SIGN, A	14.00	EACH
0079	801-06775	MAINTAINING TRAFFIC	1.00	LS
0080	801-07118	BARRICADE, III-A	72.00	LFT
0081	801-07119	BARRICADE, III-B	60.00	LFT
0082	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	11.00	LFT
0083	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	5.00	EACH
0084	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	6.00	SFT
0085	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	300.00	LFT
0086	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2400.00	LFT
0087	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1200.00	LFT
0088	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	16.00	EACH
0089	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	16.00	EACH