

**Schedule of Pay Items Letting Date May 7, 2020 Letting ID 200507**

Call: 431

Contract: RS-42483-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00 LS
0014	205-11626	PUMP AROUND	6.00 EACH
0015	205-12108	STORMWATER MANAGEMENT BUDGET	2442.00 DOL
0016	205-12111	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 2	1.00 LS
0017	207-12498	SUBGRADE TREATMENT, TYPE ID	804.00 SYS
0018	211-09264	STRUCTURE BACKFILL, TYPE 1	162.00 CYS
0019	303-01180	COMPACTED AGGREGATE NO. 53	587.00 TON
0020	304-07490	HMA PATCHING, TYPE B	1269.00 TON
0021	306-08043	MILLING, TRANSITION	358.00 SYS
0022	306-08563	MILLING, ASPHALT, 1 1/4 IN.	52690.00 SYS
0023	401-06264	PROFILOGRAPH, HMA	1.00 LS
0024	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	4374.00 TON
0025	401-10258	JOINT ADHESIVE, SURFACE	19470.00 LFT
0026	401-11785	LIQUID ASPHALT SEALANT	19470.00 LFT
0027	406-05520	ASPHALT FOR TACK COAT	15.00 TON
0028	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	13290.00 LFT
0029	610-07487	HMA FOR APPROACHES, TYPE B	208.00 TON
0030	615-06525	CASTING ADJUST TO GRADE, MONUMENT	3.00 EACH
0031	621-02770	EROSION CONTROL BLANKET	90.00 SYS

0032	621-06545	FERTILIZER	1.00	TON
0033	621-06553	SEED MIXTURE R	4.00	LBS
0034	621-06565	MULCHING MATERIAL	1.00	TON
0035	628-09402	FIELD OFFICE, B	3.00	MOS
0036	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0037	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	60.00	LFT
0038	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	66.00	LFT
0039	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	150.00	LFT
0040	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	78.00	TON
0041	715-08447	PIPE, TYPE 1, DEFORMED, MIN. AREA 5.1 SFT	60.00	LFT
0042	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4034.00	LFT
0043	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	88.00	LFT
0044	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	88.00	LFT
0045	801-06640	CONSTRUCTION SIGN, A	26.00	EACH
0046	801-06775	MAINTAINING TRAFFIC	1.00	LS
0047	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	138.00	SFT
0048	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0049	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	32405.00	LFT
0050	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	4070.00	LFT
0051	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	3860.00	LFT
0052	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	88.00	LFT
0053	808-12032	GROOVING FOR PAVEMENT MARKINGS	40335.00	LFT