

Schedule of Pay Items Letting Date May 28, 2020 Letting ID 200528

Call: 291

Contract: R -42580-A

Section No.: 1 RAMP IMPROVEMENTS

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	202-02240	PAVEMENT REMOVAL	873.00 SYS
0011	202-02272	PAVED SIDE DITCH, REMOVE	53.00 LFT
0012	202-02273	CENTER CURB, CONCRETE, REMOVE	161.00 SYS
0013	202-02278	CURB, CONCRETE, REMOVE	107.00 LFT
0014	202-74055	OVERHEAD SIGN STRUCTURE, BOX TRUSS, REMOVE	3.00 EACH
0015	202-86946	HANDHOLE, REMOVE	3.00 EACH
0016	202-91385	INLET, REMOVE	2.00 EACH
0017	202-93741	GUARDRAIL, END TREATMENT, REMOVE	2.00 EACH
0018	202-96133	PIPE, REMOVE	55.00 LFT
0019	203-02000	EXCAVATION, COMMON	1079.00 CYS
0020	203-02070	BORROW	431.00 CYS
0021	205-12108	STORMWATER MANAGEMENT BUDGET	274323.00 DOL
0022	205-12109	SWQCP PREPARATION AND IMPLEMENTATION, LEVEL 1	1.00 LS
0023	207-08266	SUBGRADE TREATMENT, TYPE III	31.00 SYS
0024	207-12498	SUBGRADE TREATMENT, TYPE ID	3913.00 SYS
0025	211-09265	STRUCTURE BACKFILL, TYPE 2	13.00 CYS
0026	301-12234	COMPACTED AGGREGATE NO. 53	8.00 CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	444.00 TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	3559.00 SYS
0029	306-08043	MILLING, TRANSITION	533.00 SYS
0030	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	572.00 TON
0031	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	476.00 TON

0032	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	1986.00 TON
0033	401-10258	JOINT ADHESIVE, SURFACE	10030.00 LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	4962.00 LFT
0035	401-11785	LIQUID ASPHALT SEALANT	10030.00 LFT
0036	406-05520	ASPHALT FOR TACK COAT	3.00 TON
0037	601-02241	GUARDRAIL, REMOVE	767.00 LFT
0038	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1450.00 LFT
0039	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	2.00 EACH
0040	601-94689	GUARDRAIL, END TREATMENT, OS	1.00 EACH
0041	601-94690	GUARDRAIL, END TREATMENT, MS	1.00 EACH
0042	604-05528	HMA FOR SIDEWALK	3.00 TON
0043	605-06120	CURB, CONCRETE	115.00 LFT
0044	605-06121	CURB, CONCRETE B	444.00 LFT
0045	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	14.00 LFT
0046	616-06405	RIPRAP, REVETMENT	913.00 TON
0047	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	687.00 SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0049	621-06554	SEED MIXTURE U	121.00 LBS
0050	621-06574	SODDING	155.00 SYS
0051	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	8.00 EACH
0052	628-09402	FIELD OFFICE, B	6.00 MOS
0053	629-12029	PLANT GROWTH LAYER	4000.00 SYS
0054	702-51001	CONCRETE, A, SUPERSTRUCTURE	17.00 CYS
0055	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	50.00 LFT
0056	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	25.00 LFT
0057	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	131.00 LFT
0058	715-05756	PIPE EXTENSION, CIRCULAR, 12 IN.	9.00 LFT
0059	715-09064	VIDEO INSPECTION FOR PIPE	156.00 LFT
0060	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00 EACH
0061	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00 EACH
0062	718-06528	OUTLET PROTECTOR, 1	2.00 EACH
0063	720-44000	CASTING, ADJUST TO GRADE	2.00 EACH
0064	720-45075	INLET, R13	1.00 EACH
0065	720-45410	MANHOLE, C4	1.00 EACH
0066	720-94847	INLET, R13 MODIFIED	2.00 EACH
0067	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	10.00 EACH
0068	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00 EACH

0069	801-06201	TEMPORARY PANEL SIGNS	550.00	SFT
0070	801-06202	TEMPORARY PANEL SIGN SUPPORTS	223.00	LFT
0071	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	19684.00	LFT
0072	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	5998.00	LFT
0073	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	4740.00	LFT
0074	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	2.00	EACH
0075	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	3264.00	LFT
0076	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	245.00	LFT
0077	801-06625	DETOUR ROUTE MARKER ASSEMBLY	23.00	EACH
0078	801-06640	CONSTRUCTION SIGN, A	85.00	EACH
0079	801-06645	CONSTRUCTION SIGN, B	1.00	EACH
0080	801-06710	FLASHING ARROW SIGN	67.00	DAY
0081	801-06775	MAINTAINING TRAFFIC	1.00	LS
0082	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	5.00	EACH
0083	801-07118	BARRICADE, III-A	160.00	LFT
0084	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	6972.00	LFT
0085	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0086	801-12388	TEMPORARY PAVEMENT MARKING, REMOVABLE, 9 IN	3100.00	LFT
0087	801-12389	TEMPORARY PAVEMENT MARKING, REMOVABLE, 25 IN	254.00	LFT
0088	801-12544	AUTOMATED WORK ZONE INFORMATION SYSTEM	2.00	EACH
0089	801-12544	AUTOMATED WORK ZONE INFORMATION SYSTEM	1.00	EACH
0090	802-02475	SIGN, PANEL, RELOCATE	2.00	EACH
0091	802-03783	SIGN, PANEL, REMOVE	8.00	EACH
0092	802-04089	SIGN, SHEET, REMOVE	1.00	EACH
0093	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	49.00	LFT
0094	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	164.00	LFT
0095	802-07057	SIGN, PANEL, WITH LEGEND	2345.00	SFT
0096	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	33.00	EACH
0097	802-07060	SIGN, SHEET, RELOCATE	5.00	EACH
0098	802-09221	OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE A	1.00	EACH
0099	802-09222	OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE B	1.00	EACH
0100	802-09224	OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE D	1.00	EACH
0101	802-09536	BOX TRUSS SIGN STRUCTURE FOUNDATION, 45 IN. CONCRETE BARRIER WALL	2.00	EACH
0102	802-09537	BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN. MEDIAN OR SHOULDER	4.00	EACH
0103	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	12.00	SFT
0104	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	140.00	SFT
0105	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	18.00	SFT

0106	802-12223	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, B	2.00 EACH
0107	802-76095	STRUCTURAL STEEL, BREAKAWAY	1287.00 LBS
0108	807-02191	HANDHOLE LIGHTING	4.00 EACH
0109	807-02426	WIRE, THW, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	975.00 LFT
0110	807-02603	LIGHT STANDARD RELOCATE	2.00 EACH
0111	807-02934	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. X 36 IN. X 96 IN.	2.00 EACH
0112	807-12343	CABLE, POLE CIRCUIT, XHHW, NO 10 COPPER, STRANDED, 1/C	180.00 LFT
0113	807-86910	CONNECTOR KIT, UNFUSED	2.00 EACH
0114	807-86915	CONNECTOR KIT, FUSED	13.00 EACH
0115	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	4.00 EACH
0116	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	2.00 EACH
0117	807-86930	INSULATION LINK, NON-WATERPROOFED	4.00 EACH
0118	807-86935	INSULATION LINK, WATERPROOFED	2.00 EACH
0119	808-06702	LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	240.00 LFT
0120	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2306.00 LFT
0121	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	1859.00 LFT
0122	808-06716	LINE, REMOVE	92.00 LFT
0123	808-11484	LINE, MULTI-COMPONENT, DOTTED, WHITE, 5 IN.	102.00 LFT
0124	808-12032	GROOVING FOR PAVEMENT MARKINGS	5859.00 LFT
0125	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1352.00 LFT
0126	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	92.00 LFT
0127	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	6.00 EACH
0128	808-75994	PRISMATIC REFLECTOR	156.00 EACH
0129	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	43.00 EACH
0130	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	84.00 EACH

Call: 891

Contract: T -42596-A

Section No.: 1 ITS COMMUNICATIONS SYSTEMS

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0007	201-01015	CLEARING AND GRUBBING	1.00 LS
0008	715-04985	VAULT	15.00 EACH
0009	801-06640	CONSTRUCTION SIGN, A	15.00 EACH
0010	801-06645	CONSTRUCTION SIGN, B	15.00 EACH
0011	801-06775	MAINTAINING TRAFFIC	1.00 LS
0012	805-04973	CONDUIT	1244.00 LFT
0013	805-04973	CONDUIT	28723.00 LFT
0014	805-04973	CONDUIT	280.00 LFT
0015	805-04973	CONDUIT	9909.00 LFT
0016	805-04973	CONDUIT	28723.00 LFT
0017	805-04973	CONDUIT	280.00 LFT
0018	805-04973	CONDUIT	9909.00 LFT
0019	807-04651	WIRE	38755.00 LFT
0020	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	630.00 LFT
0021	807-78590	HANDHOLE	129.00 EACH
0022	807-78590	HANDHOLE	25.00 EACH
0023	807-86955	CABLE-DUCT MARKER	88.00 EACH
0024	807-86955	CABLE-DUCT MARKER	46.00 EACH
0025	809-04970	FIBER OPTIC	160.00 EACH
0026	809-04970	FIBER OPTIC	15.00 EACH
0027	809-04970	FIBER OPTIC	18.00 EACH
0028	809-04970	FIBER OPTIC	16.00 EACH
0029	809-94971	FIBER OPTIC CABLE	50854.00 LFT
0030	809-94971	FIBER OPTIC CABLE	4354.00 LFT