

Schedule of Pay Items Letting Date October 7, 2020 Letting ID 201007

Call: 120

Contract: R -37800-A

Section No.: 1 SLIDE CORRECTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	203-02000	EXCAVATION, COMMON	371.00 CYS
0014	203-02010	EXCAVATION, ROCK	674.00 CYS
0015	203-02070	BORROW	364.00 CYS
0016	203-02132	EXPLORATORY DRILLING	2000.00 LFT
0017	205-11626	PUMP AROUND	1.00 EACH
0018	205-12108	STORMWATER MANAGEMENT BUDGET	12000.00 DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0020	205-12618	SWQCP PREPARATION	1.00 LS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	153.00 SYS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	1811.00 SYS
0023	211-09264	STRUCTURE BACKFILL, TYPE 1	162.00 CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	652.00 TON
0025	304-07493	WIDENING WITH HMA, TYPE B	388.00 TON
0026	306-08034	MILLING, ASPHALT, 1 1/2 IN.	6394.00 SYS
0027	306-11872	MILLING, PROFILE	6394.00 SYS
0028	401-06264	PROFILOGRAPH, HMA	1.00 LS
0029	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	603.00 TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	882.00 TON
0031	401-10258	JOINT ADHESIVE, SURFACE	2928.00 LFT

0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	2928.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	8784.00	LFT
0034	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0035	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	2.00	TON
0036	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0037	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0038	601-02241	GUARDRAIL, REMOVE	1288.00	LFT
0039	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	2289.00	LFT
0040	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	5.00	EACH
0041	601-94689	GUARDRAIL, END TREATMENT, OS	7.00	EACH
0042	610-07487	HMA FOR APPROACHES, TYPE B	42.00	TON
0043	615-06490	RIGHT-OF-WAY MARKER	61.00	EACH
0044	615-06505	MONUMENT, B	19.00	EACH
0045	615-06510	MONUMENT, C	2.00	EACH
0046	616-05688	RIPRAP, CLASS 1	56.00	TON
0047	616-06405	RIPRAP, REVETMENT	99.00	TON
0048	616-06451	RIPRAP, UNIFORM	426.00	TON
0049	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	784.00	SYS
0050	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.00	EACH
0051	621-06545	FERTILIZER	1.30	TON
0052	621-06553	SEED MIXTURE R	249.00	LBS
0053	621-06565	MULCHING MATERIAL	3.00	TON
0054	628-09403	FIELD OFFICE, C	24.00	MOS
0055	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0056	702-44240	CONCRETE, A, STRUCTURES	34.00	CYS
0057	703-06028	REINFORCING BARS	6012.00	LBS
0058	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	2070.00	LFT
0059	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	1230.00	LFT
0060	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	82.00	LFT
0061	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	135.00	LFT
0062	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	106.00	TON
0063	715-10166	PIPE, TYPE 1, DEFORMED, MIN. AREA 37.0 SFT	60.00	LFT
0064	715-10167	CONCRETE ANCHOR, MIN. AREA 37.0 SFT	1.00	EACH
0065	715-46020	PIPE END SECTION, DIAMETER 24 IN.	3.00	EACH
0066	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	2070.00	LFT
0067	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	748.00	SYS
0068	718-52610	AGGREGATE FOR UNDERDRAINS	116.00	CYS

0069	720-45025	INLET, D6	3.00 EACH
0070	734-10240	CUT-WALL, NO.	1320.00 SFT
0071	734-10240	CUT-WALL, NO.	3520.00 SFT
0072	734-10240	CUT-WALL, NO.	5040.00 SFT
0073	734-10240	CUT-WALL, NO.	1824.00 SFT
0074	734-10240	CUT-WALL, NO.	1272.00 SFT
0075	734-10240	CUT-WALL, NO.	9588.00 SFT
0076	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00 EACH
0077	801-06625	DETOUR ROUTE MARKER ASSEMBLY	62.00 EACH
0078	801-06640	CONSTRUCTION SIGN, A	32.00 EACH
0079	801-06775	MAINTAINING TRAFFIC	1.00 LS
0080	801-07118	BARRICADE, III-A	96.00 LFT
0081	801-07119	BARRICADE, III-B	120.00 LFT
0082	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	7.00 EACH
0083	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	79.00 LFT
0084	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	80.00 SFT
0085	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7030.00 LFT
0086	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0087	808-12032	GROOVING FOR PAVEMENT MARKINGS	6701.00 LFT
0088	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7030.00 LFT

Call: 130

Contract: R -39819-A

Section No.: 1 REPLACE SUPERSTRUCTURE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	212.00	SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	202-90277	DETECTOR HOUSING, REMOVE	1.00	EACH
0015	203-02000	EXCAVATION, COMMON	33.00	CYS
0016	203-08607	LINEAR GRADING	545.00	LFT
0017	205-12108	STORMWATER MANAGEMENT BUDGET	14767.00	DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	205-12618	SWQCP PREPARATION	1.00	LS
0020	206-51225	EXCAVATION, DRY	19.00	CYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	98.00	SYS
0022	207-12498	SUBGRADE TREATMENT, TYPE ID	920.00	SYS
0023	211-09267	STRUCTURE BACKFILL, TYPE 4	18.00	CYS
0024	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	309.00	SYS
0025	301-12234	COMPACTED AGGREGATE NO. 53	42.00	CYS
0026	302-06464	SUBBASE FOR PCCP	53.00	CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	2263.00	TON
0028	304-12625	HMA PATCHING FULL DEPTH TYPE C	596.00	TON
0029	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	1256.00	TON
0030	306-08036	MILLING, ASPHALT, 2 IN.	164765.00	SYS
0031	306-08043	MILLING, TRANSITION	880.00	SYS

0032	306-08432	MILLING, APPROACH	5851.00	SYS
0033	306-08599	MILLING, ASPHALT, 1/2 IN.	196.00	SYS
0034	401-06264	PROFILOGRAPH, HMA	1.00	LS
0035	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	13992.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	114656.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	60.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	114716.00	LFT
0039	406-05520	ASPHALT FOR TACK COAT	44.30	TON
0040	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	7.00	TON
0041	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	160.00	SFT
0042	601-02241	GUARDRAIL, REMOVE	564.00	LFT
0043	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	175.00	LFT
0044	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0045	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0046	602-06729	BARRIER, DELINEATOR	8.00	EACH
0047	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	720.00	LFT
0048	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	106760.00	LFT
0049	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	212.00	SYS
0050	610-07488	HMA FOR APPROACHES, TYPE C	485.00	TON
0051	616-06405	RIPRAP, REVETMENT	160.00	TON
0052	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	292.00	SYS
0053	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0054	621-06559	MULCHED SEEDING R	1750.00	SYS
0055	621-06574	SODDING	32.00	SYS
0056	628-09403	FIELD OFFICE, C	18.00	MOS
0057	702-92857	CONCRETE, C, SUBSTRUCTURE	32.40	CYS
0058	703-06029	REINFORCING BARS, EPOXY COATED	74789.00	LBS
0059	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	46.00	EACH
0060	704-51002	CONCRETE, C, SUPERSTRUCTURE	189.20	CYS
0061	706-09960	RAILING, CONCRETE FC	144.00	LFT
0062	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0063	709-51821	SURFACE SEAL	1.00	LS
0064	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0065	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	EACH
0066	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	175911.00	LFT
0067	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	2.00	EACH
0068	801-06625	DETOUR ROUTE MARKER ASSEMBLY	49.00	EACH

0069	801-06640	CONSTRUCTION SIGN, A	68.00	EACH
0070	801-06645	CONSTRUCTION SIGN, B	16.00	EACH
0071	801-06775	MAINTAINING TRAFFIC	1.00	LS
0072	801-07118	BARRICADE, III-A	96.00	LFT
0073	801-07119	BARRICADE, III-B	288.00	LFT
0074	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0075	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	703.00	LFT
0076	805-78785	SIGNAL DETECTOR HOUSING	2.00	EACH
0077	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	231.00	LFT
0078	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	66539.00	LFT
0079	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	89.00	LFT
0080	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	706.00	LFT
0081	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0082	808-12032	GROOVING FOR PAVEMENT MARKINGS	66539.00	LFT
0083	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	2.00	EACH
0084	808-75073	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, ONLY	2.00	EACH
0085	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	6230.00	LFT
0086	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	23784.00	LFT
0087	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	48.00	LFT
0088	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	2.00	EACH
0089	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	2.00	EACH
0090	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	558.00	EACH
0091	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	558.00	EACH
0092	808-97643	BUZZ STRIPS	144.00	LFT

Call: 140

Contract: R -39879-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line			Quantity Unit	
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	5.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-98488	PIPE END SECTION, REMOVE	2.00	EACH
0012	203-02055	EMBANKMENT	75.00	CYS
0013	205-12108	STORMWATER MANAGEMENT BUDGET	2.00	DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0015	205-12618	SWQCP PREPARATION	1.00	LS
0016	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	6.00	EACH
0017	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	35.00	CYS
0018	616-05688	RIPRAP, CLASS 1	200.00	TON
0019	616-05689	RIPRAP, CLASS 2	134.00	TON
0020	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	521.00	SYS
0021	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0022	621-02770	EROSION CONTROL BLANKET	180.00	SYS
0023	621-06559	MULCHED SEEDING R	350.00	SYS
0024	628-09403	FIELD OFFICE, C	12.00	MOS
0025	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0026	702-51863	FIELD DRILLED HOLE IN CONCRETE	6.00	EACH
0027	715-04857	SAFETY METAL END SECTION	1.00	EACH
0028	715-06338	PIPE EXTENSION, CIRCULAR, 66 IN.	20.00	LFT
0029	715-07626	CONCRETE ANCHOR, 66 IN.	2.00	EACH
0030	715-95325	INVERT, CONCRETE PAVED	159.00	LFT
0031	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1400.00	LFT

0032	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	800.00	LFT
0033	801-06640	CONSTRUCTION SIGN, A	20.00	EACH
0034	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0035	801-06775	MAINTAINING TRAFFIC	1.00	LS
0036	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0037	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH

Call: 150

Contract: R -39884-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	202-93741	GUARDRAIL, END TREATMENT, REMOVE	8.00 EACH
0011	207-12498	SUBGRADE TREATMENT, TYPE ID	1664.00 SYS
0012	211-02050	B BORROW	1252.00 CYS
0013	303-01180	COMPACTED AGGREGATE NO. 53	1636.00 TON
0014	304-12627	HMA PATCHING FULL DEPTH TYPE D	1739.00 TON
0015	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	759.00 TON
0016	306-08036	MILLING, ASPHALT, 2 IN.	527734.00 SYS
0017	306-08432	MILLING, APPROACH	15149.00 SYS
0018	401-06264	PROFILOGRAPH, HMA	1.00 LS
0019	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	58053.00 TON
0020	401-10258	JOINT ADHESIVE, SURFACE	273778.00 LFT
0021	401-11785	LIQUID ASPHALT SEALANT	273778.00 LFT
0022	406-05520	ASPHALT FOR TACK COAT	138.00 TON
0023	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	25.00 TON
0024	601-02241	GUARDRAIL, REMOVE	2644.00 LFT
0025	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1056.30 LFT
0026	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	1312.50 LFT
0027	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	2.00 EACH
0028	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	6.00 EACH
0029	601-94689	GUARDRAIL, END TREATMENT, OS	4.00 EACH
0030	601-94690	GUARDRAIL, END TREATMENT, MS	4.00 EACH
0031	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	207482.00 LFT

0032	610-07788	HMA FOR APPROACHES, TYPE D	1667.00	TON
0033	628-09402	FIELD OFFICE, B	10.00	MOS
0034	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0035	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	1690.00	LFT
0036	718-06528	OUTLET PROTECTOR, 1	169.00	EACH
0037	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	201045.00	LFT
0038	801-03290	CONSTRUCTION SIGN, C	4.00	EACH
0039	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0040	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	29091.00	LFT
0041	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	29091.00	LFT
0042	801-06625	DETOUR ROUTE MARKER ASSEMBLY	130.00	EACH
0043	801-06640	CONSTRUCTION SIGN, A	128.00	EACH
0044	801-06645	CONSTRUCTION SIGN, B	108.00	EACH
0045	801-06710	FLASHING ARROW SIGN	240.00	DAY
0046	801-06775	MAINTAINING TRAFFIC	1.00	LS
0047	801-07118	BARRICADE, III-A	176.00	LFT
0048	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	6.00	EACH
0049	801-12324	LAW ENFORCEMENT OFFICER	400.00	HRS
0050	801-12348	TEMPORARY WORKSITE SPEED DISPLAY ASSEMBLY	4.00	EACH
0051	801-12647	LAW ENFORCEMENT OFFICER TRAINING	1.00	DOL
0052	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0053	808-12032	GROOVING FOR PAVEMENT MARKINGS	255235.00	LFT
0054	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	119503.00	LFT
0055	808-75053	LINE, PREFORMED PLASTIC, SOLID, WHITE, 8 IN.	1936.00	LFT
0056	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	105916.00	LFT
0057	808-75059	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	27880.00	LFT
0058	808-75067	TRANSVERSE MARKING, PREFORMED PLASTIC, STOP LINE, WHITE, 24 IN.	463.00	LFT
0059	808-75510	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	264.00	LFT
0060	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1888.00	EACH
0061	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1888.00	EACH

Call: 160

Contract: R -39927-A

Section No.: 1

SMALL STRUCTURE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	6.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-01015	CLEARING AND GRUBBING	1.00 LS
0013	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0014	202-07553	REGULATED MATERIALS, REMOVE, TYPE Y	40.00 CYS
0015	202-07554	REGULATED MATERIALS, TRANSPORT, TYPE Y	40.00 CYS
0016	202-07555	REGULATED MATERIALS, DISPOSE, TYPE Y	40.00 CYS
0017	203-02000	EXCAVATION, COMMON	85.00 CYS
0018	203-02070	BORROW	40.00 CYS
0019	205-11626	PUMP AROUND	2.00 EACH
0020	205-12108	STORMWATER MANAGEMENT BUDGET	7935.00 DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0022	205-12618	SWQCP PREPARATION	1.00 LS
0023	207-12498	SUBGRADE TREATMENT, TYPE ID	255.00 SYS
0024	211-09265	STRUCTURE BACKFILL, TYPE 2	624.00 CYS
0025	211-09268	STRUCTURE BACKFILL, TYPE 5	349.00 CYS
0026	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	136.00 SYS
0027	301-12233	COMPACTED AGGREGATE NO. 8	43.00 CYS
0028	303-01180	COMPACTED AGGREGATE NO. 53	78.00 TON
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1067.00 SYS
0030	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	109.00 TON
0031	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	34.00 TON

0032	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	79.00	TON
0033	401-10258	JOINT ADHESIVE, SURFACE	590.00	LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	159.00	LFT
0035	401-11785	LIQUID ASPHALT SEALANT	590.00	LFT
0036	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0037	615-06490	RIGHT-OF-WAY MARKER	16.00	EACH
0038	615-06500	MONUMENT, A	4.00	EACH
0039	616-06405	RIPRAP, REVETMENT	462.00	TON
0040	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	711.00	SYS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0042	621-06559	MULCHED SEEDING R	302.00	SYS
0043	628-09402	FIELD OFFICE, B	8.00	MOS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0045	702-04325	TEMPORARY SHORING	1.00	LS
0046	714-11073	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 9 FT. X 6 FT.	55.00	LFT
0047	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	66.00	LFT
0048	715-05257	PIPE, TYPE 1, DEFORMED, MIN. AREA 24.75 SFT	54.00	LFT
0049	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	51.00	SYS
0050	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00	EACH
0051	801-06625	DETOUR ROUTE MARKER ASSEMBLY	64.00	EACH
0052	801-06640	CONSTRUCTION SIGN, A	20.00	EACH
0053	801-06775	MAINTAINING TRAFFIC	1.00	LS
0054	801-07118	BARRICADE, III-A	96.00	LFT
0055	801-07119	BARRICADE, III-B	108.00	LFT
0056	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	30.00	LFT
0057	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	672.00	LFT
0058	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	530.00	LFT
0059	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	52.00	LFT
0060	808-75140	PAVEMENT MESSAGE MARKING, PAINT, R X R	1.00	EACH
0061	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	9.00	EACH
0062	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	9.00	EACH

Call: 180

Contract: R -40388-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	5.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	10.00 EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0013	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0014	202-93741	GUARDRAIL, END TREATMENT, REMOVE	2.00 EACH
0015	203-02000	EXCAVATION, COMMON	1601.00 CYS
0016	203-02070	BORROW	2469.00 CYS
0017	205-12108	STORMWATER MANAGEMENT BUDGET	10028.00 DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0019	205-12618	SWQCP PREPARATION	1.00 LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	70.00 SYS
0021	207-09934	SUBGRADE TREATMENT, TYPE IB	7947.00 SYS
0022	211-02050	B BORROW	301.00 CYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	34.00 CYS
0024	301-12234	COMPACTED AGGREGATE NO. 53	1523.00 CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	747.00 TON
0026	306-08036	MILLING, ASPHALT, 2 IN.	309.00 SYS
0027	401-07403	QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	606.00 TON
0028	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1072.00 TON
0029	401-10258	JOINT ADHESIVE, SURFACE	3822.00 LFT
0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	3822.00 LFT
0031	401-11785	LIQUID ASPHALT SEALANT	3822.00 LFT

0032	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	1108.00	TON
0033	406-05520	ASPHALT FOR TACK COAT	5.00	TON
0034	410-12320	QC/QA-HMA, 3, 76, SURFACE, 12.5 mm - SMA	635.00	TON
0035	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
0036	502-11564	PCCP, 7 IN.	1257.00	SYS
0037	503-05240	D-1 CONTRACTION JOINT	216.00	LFT
0038	601-02241	GUARDRAIL, REMOVE	33.00	LFT
0039	601-06037	GUARDRAIL, END TREATMENT, I	2.00	EACH
0040	604-06070	SIDEWALK, CONCRETE	157.00	SYS
0041	604-08086	CURB RAMP, CONCRETE	46.00	SYS
0042	604-12083	DETECTABLE WARNING SURFACES	8.00	SYS
0043	605-06140	CURB AND GUTTER, CONCRETE	755.00	LFT
0044	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	192.00	LFT
0045	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	1190.00	LFT
0046	605-06160	CURB AND GUTTER, B, CONCRETE, MODIFIED	588.00	LFT
0047	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	41.00	LFT
0048	610-07487	HMA FOR APPROACHES, TYPE B	20.00	TON
0049	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0050	615-06505	MONUMENT, B	12.00	EACH
0051	615-06515	MONUMENT, D	8.00	EACH
0052	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0053	616-06405	RIPRAP, REVETMENT	4.00	TON
0054	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	9.00	SYS
0055	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0056	621-06559	MULCHED SEEDING R	2079.00	SYS
0057	621-06560	MULCHED SEEDING U	598.00	SYS
0058	621-06567	WATER	7.00	KGAL
0059	621-06575	SODDING, NURSERY	1625.00	SYS
0060	628-09402	FIELD OFFICE, B	12.00	MOS
0061	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0062	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	2072.00	LFT
0063	715-05049	PIPE, TYPE 4, CIRCULAR, 8 IN.	10.00	LFT
0064	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	15.00	LFT
0065	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	81.00	LFT
0066	715-09064	VIDEO INSPECTION FOR PIPE	96.00	LFT
0067	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0068	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH

0069	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	2072.00	LFT
0070	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	1423.00	SYS
0071	718-52610	AGGREGATE FOR UNDERDRAINS	164.00	CYS
0072	720-45030	INLET, E7	1.00	EACH
0073	720-98174	INLET, B15	1.00	EACH
0074	720-98555	INLET, C15	1.00	EACH
0075	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00	EACH
0076	801-06625	DETOUR ROUTE MARKER ASSEMBLY	40.00	EACH
0077	801-06640	CONSTRUCTION SIGN, A	44.00	EACH
0078	801-06775	MAINTAINING TRAFFIC	1.00	LS
0079	801-07118	BARRICADE, III-A	96.00	LFT
0080	801-07119	BARRICADE, III-B	192.00	LFT
0081	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	193.00	LFT
0082	802-05705	SIGN POST, SQUARE TYPE 2 UNREINFORCED ANCHOR BASE	124.00	LFT
0083	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	116.00	SFT
0084	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	147.00	SFT
0085	804-76350	DELINEATOR WITH POST, D3	3.00	EACH
0086	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1620.00	LFT
0087	805-78069	CONTROLLER AND CABINET, SECONDARY MENU DRIVEN, 4 PHASE	1.00	EACH
0088	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0089	807-02191	HANDHOLE LIGHTING	9.00	EACH
0090	807-11941	LIGHT POLE, 30 FT. E.M.H. 5.0 FT. MAST ARM, TRANSFORMER	10.00	EACH
0091	807-11981	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. DIA X 96 IN.	11.00	EACH
0092	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	11.00	EACH
0093	807-84492	LIGHT POLE, 30 FT. E.M.H. 10.0 FT. MAST ARM, TRANSFORMER BASE	1.00	EACH
0094	807-86810	SERVICE POINT, II	1.00	EACH
0095	807-95888	WIRE, NO 8 COPPER, 1/C	1620.00	LFT
0096	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	64.00	LFT
0097	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2263.00	LFT
0098	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	140.00	LFT
0099	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	159.00	LFT
0100	808-12032	GROOVING FOR PAVEMENT MARKINGS	4304.00	LFT
0101	808-12148	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 36 IN.	48.00	LFT
0102	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1447.00	LFT
0103	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	186.00	LFT

Call: 190

Contract: R -41009-A

Section No.: 1 SMALL STRUCTURE MAINTENANCE AND REPAIR

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0009	203-02000	EXCAVATION, COMMON	1.00 CYS
0010	205-11626	PUMP AROUND	1.00 EACH
0011	205-12108	STORMWATER MANAGEMENT BUDGET	5779.00 DOL
0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0013	205-12618	SWQCP PREPARATION	1.00 LS
0014	211-06467	AGGREGATE FOR END BENT BACKFILL	12.00 CYS
0015	214-12236	GEOTEXTILE FOR PAVEMENT TYPE 1A	235.00 SYS
0016	616-06405	RIPRAP, REVETMENT	218.00 TON
0017	616-06451	RIPRAP, UNIFORM	49.00 TON
0018	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	361.00 SYS
0019	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00 EACH
0020	621-06545	FERTILIZER	1.00 TON
0021	621-06553	SEED MIXTURE R	27.00 LBS
0022	621-06565	MULCHING MATERIAL	1.00 TON
0023	628-09401	FIELD OFFICE, A	3.00 MOS
0024	628-11729	CELLULAR TELEPHONE, TYPE A	1.00 EACH
0025	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0026	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0027	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	3.00 MOS
0028	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0029	628-11977	COMPUTER SYSTEM	1.00 EACH
0030	702-51863	FIELD DRILLED HOLE IN CONCRETE	4.00 EACH
0031	702-90915	CONCRETE, CLASS, A	5.00 CYS

0032	703-06028	REINFORCING BARS	648.00	LBS
0033	715-05217	PIPE, TYPE 5, CIRCULAR, 12 IN.	18.00	LFT
0034	715-05218	PIPE, TYPE 5, CIRCULAR, 15 IN.	5.00	LFT
0035	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0036	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0037	801-06775	MAINTAINING TRAFFIC	1.00	LS
0038	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	11.00	LFT
0039	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH

Call: 200

Contract: R -41089-B

Section No.: 1 CONCRETE PAVEMENT RESTORATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	202-52710	SIDEWALK CONCRETE, REMOVE	100.00 SYS
0010	205-12108	STORMWATER MANAGEMENT BUDGET	20300.00 DOL
0011	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0012	207-12498	SUBGRADE TREATMENT, TYPE ID	152.00 SYS
0013	503-03489	RETROFITTED TIE BARS	13.00 EACH
0014	503-05240	D-1 CONTRACTION JOINT	51.00 LFT
0015	506-06333	PCCP PATCHING, FULL DEPTH	152.00 SYS
0016	507-07482	CRACKS IN PCCP, ROUT AND SEAL	56.00 LFT
0017	507-08272	JOINTS IN PCCP, SAW AND SEAL	87622.00 LFT
0018	507-12191	JOINT REPAIR, PARTIAL DEPTH	1272.00 SFT
0019	507-12192	JOINT REPAIR, BOTTOM-HALF	120.00 SFT
0020	604-06070	SIDEWALK, CONCRETE	17.00 SYS
0021	604-08086	CURB RAMP, CONCRETE	83.00 SYS
0022	604-12083	DETECTABLE WARNING SURFACES	15.00 SYS
0023	605-02278	CURB, REMOVE	109.00 LFT
0024	605-06120	CURB, CONCRETE	178.00 LFT
0025	628-09402	FIELD OFFICE, B	6.00 MOS
0026	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0027	720-44000	CASTING, ADJUST TO GRADE	3.00 EACH
0028	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	9.00 EACH
0029	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	49762.00 LFT
0030	801-06640	CONSTRUCTION SIGN, A	20.00 EACH
0031	801-06645	CONSTRUCTION SIGN, B	10.00 EACH

0032	801-06710	FLASHING ARROW SIGN	120.00	DAY
0033	801-06775	MAINTAINING TRAFFIC	1.00	LS
0034	801-07118	BARRICADE, III-A	16.00	LFT
0035	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	950.00	LFT
0036	801-11990	TEMPORARY CURB RAMP	2.00	EACH
0037	808-06716	LINE, REMOVE	49762.00	LFT
0038	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0039	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	4660.00	LFT
0040	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	21503.00	LFT
0041	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	19528.00	LFT
0042	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	4050.00	LFT
0043	808-10042	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW 12 IN.	1561.00	LFT
0044	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	169.00	LFT
0045	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	105.00	LFT
0046	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	23.00	EACH
0047	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	37.00	EACH
0048	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	21.00	LFT
0049	808-12032	GROOVING FOR PAVEMENT MARKINGS	49762.00	LFT
0050	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	243.00	EACH
0051	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	243.00	EACH

Call: 210

Contract: R -41115-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-02271	HEADWALL, REMOVE	2.00 EACH
0012	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0013	202-96133	PIPE, REMOVE	42.00 LFT
0014	203-02000	EXCAVATION, COMMON	55.00 CYS
0015	205-11626	PUMP AROUND	3.00 EACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	3800.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	205-12618	SWQCP PREPARATION	1.00 LS
0019	206-51220	EXCAVATION, WET	120.00 CYS
0020	207-12498	SUBGRADE TREATMENT, TYPE ID	189.00 SYS
0021	211-02050	B BORROW	40.00 CYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	181.00 CYS
0023	211-09268	STRUCTURE BACKFILL, TYPE 5	51.00 CYS
0024	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	48.00 SYS
0025	301-12233	COMPACTED AGGREGATE NO. 8	64.00 CYS
0026	301-12234	COMPACTED AGGREGATE NO. 53	64.00 CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	19.00 TON
0028	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	14.00 TON
0029	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	24.00 TON
0030	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	58.00 TON
0031	401-10258	JOINT ADHESIVE, SURFACE	50.00 LFT

0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	50.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	50.00	LFT
0034	406-05521	ASPHALT FOR TACK COAT	350.00	SYS
0035	615-06490	RIGHT-OF-WAY MARKER	36.00	EACH
0036	616-05688	RIPRAP, CLASS 1	87.00	TON
0037	616-06405	RIPRAP, REVETMENT	43.00	TON
0038	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	87.00	SYS
0039	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	473.00	SYS
0040	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0041	621-02770	EROSION CONTROL BLANKET	114.00	SYS
0042	621-06559	MULCHED SEEDING R	3330.00	SYS
0043	702-51005	CONCRETE, A, SUBSTRUCTURE	13.00	CYS
0044	702-51015	CONCRETE, B, FOOTINGS	13.20	CYS
0045	703-06029	REINFORCING BARS, EPOXY COATED	2178.00	LBS
0046	714-11179	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 8 FT. X 6 FT.	89.00	LFT
0047	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	10.00	LFT
0048	720-95422	MANHOLE, J4	1.00	EACH
0049	725-10203	PIPE LINER, CURED-IN-PLACE, 72 IN	35.00	LFT
0050	725-11861	PIPE LINER, CURED-IN-PLACE, MIN AREA 11.4 SFT	31.00	LFT
0051	801-06625	DETOUR ROUTE MARKER ASSEMBLY	60.00	EACH
0052	801-06640	CONSTRUCTION SIGN, A	36.00	EACH
0053	801-06775	MAINTAINING TRAFFIC	1.00	LS
0054	801-07118	BARRICADE, III-A	180.00	LFT
0055	801-07119	BARRICADE, III-B	180.00	LFT
0056	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	100.00	LFT
0057	808-12032	GROOVING FOR PAVEMENT MARKINGS	113.00	LFT
0058	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	13.00	LFT

Call: 220

Contract: R -41292-A

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	203-02000	EXCAVATION, COMMON	255.00	CYS
0010	205-11626	PUMP AROUND	1.00	EACH
0011	205-12108	STORMWATER MANAGEMENT BUDGET	5520.00	DOL
0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0013	205-12618	SWQCP PREPARATION	1.00	LS
0014	601-06035	GUARDRAIL, RESET	300.00	LFT
0015	603-06060	FENCE, FARM FIELD, RESET	100.00	LFT
0016	616-06405	RIPRAP, REVETMENT	376.00	TON
0017	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	376.00	SYS
0018	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0019	621-06559	MULCHED SEEDING R	1333.00	SYS
0020	628-09402	FIELD OFFICE, B	12.00	MOS
0021	628-11729	CELLULAR TELEPHONE, TYPE A	3.00	EACH
0022	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0023	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0024	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	36.00	MOS
0025	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0026	628-11977	COMPUTER SYSTEM	3.00	EACH
0027	714-96273	HEADWALL RECONSTRUCT	1.00	LS
0028	725-10226	LINER PIPE, THERMOPLASTIC, CIRCULAR, 13.9-14.1 SFT	145.00	LFT
0029	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0030	801-06710	FLASHING ARROW SIGN	45.00	DAY
0031	801-06775	MAINTAINING TRAFFIC	1.00	LS

0032	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	320.00	LFT
------	-----------	-----------------------------------	--------	-----

Call: 230

Contract: R -41329-A

Section No.: 1 NEW BARRIER WALL

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	202-06541	REMOVE	2.00 EACH
0011	202-96133	PIPE, REMOVE	575.00 LFT
0012	203-02000	EXCAVATION, COMMON	1652.00 CYS
0013	203-02070	BORROW	269.00 CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	2024.00 DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0016	207-12498	SUBGRADE TREATMENT, TYPE ID	755.00 SYS
0017	211-02050	B BORROW	321.00 CYS
0018	211-09264	STRUCTURE BACKFILL, TYPE 1	10.30 CYS
0019	301-12234	COMPACTED AGGREGATE NO. 53	8.70 CYS
0020	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	54.00 TON
0021	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	92.00 TON
0022	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	336.00 TON
0023	401-10258	JOINT ADHESIVE, SURFACE	594.00 LFT
0024	401-11785	LIQUID ASPHALT SEALANT	594.00 LFT
0025	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0026	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	1391.00 LFT
0027	616-06451	RIPRAP, UNIFORM	5.00 TON
0028	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	8.90 SYS
0029	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0030	621-03787	SEED MIXTURE D	9.00 LBS
0031	621-06565	MULCHING MATERIAL	1.00 TON

0032	621-06570	TOPSOIL	269.00	CYS
0033	621-06574	SODDING	1061.00	SYS
0034	627-09327	CABLE BARRIER SYSTEM, TYPE TL-4	17617.00	LFT
0035	627-09331	SAFETY TERMINAL TYPE, TL-4	16.00	EACH
0036	627-10178	CABLE BARRIER SYSTEM, TYPE TL-4 SPARE PARTS	1.00	LS
0037	628-09403	FIELD OFFICE, C	9.00	MOS
0038	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	393.00	LFT
0039	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	54.00	LFT
0040	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	43.00	LFT
0041	715-97836	GRATED BOX END SECTION, II, 4:1, DIAMETER 15 IN.	2.00	EACH
0042	718-06531	OUTLET PROTECTOR, 3	3.00	EACH
0043	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	265.00	SYS
0044	718-52610	AGGREGATE FOR UNDERDRAINS	25.00	CYS
0045	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0046	801-06640	CONSTRUCTION SIGN, A	36.00	EACH
0047	801-06710	FLASHING ARROW SIGN	128.00	DAY
0048	801-06775	MAINTAINING TRAFFIC	1.00	LS
0049	801-07118	BARRICADE, III-A	96.00	LFT
0050	801-07119	BARRICADE, III-B	48.00	LFT
0051	801-12042	TRUCK MOUNTED ATTENUATOR	128.00	DAY
0052	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	39.00	LFT
0053	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	12.00	EACH
0054	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	25.80	SFT
0055	808-06368	TRANSVERSE MARKING, REMOVE	372.00	LFT
0056	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	310.00	LFT
0057	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	1140.00	LFT
0058	808-06716	LINE, REMOVE	3023.00	LFT
0059	808-11953	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 18 IN.	32.00	LFT
0060	808-12032	GROOVING FOR PAVEMENT MARKINGS	3765.00	LFT
0061	808-75060	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE 12 IN.	590.00	LFT
0062	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2315.00	LFT
0063	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	8.00	EACH
0064	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	2.00	EACH

Call: 240

Contract: R -41841-A

Section No.: 1 ADDED TRAVEL LANES

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	15.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	15.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0010	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0011	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0012	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0014	113-01614	PARTNERING OVERHEAD	1.00	LS
0015	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0016	202-02240	PAVEMENT REMOVAL	173076.00	SYS
0017	202-02859	GRATED BOX END SECTION, REMOVE	4.00	EACH
0018	202-12024	CABLE BARRIER, REMOVE	24028.00	LFT
0019	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0020	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0021	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0022	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0023	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0024	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0025	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0026	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0027	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0028	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0029	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0030	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0031	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS

0032	202-86946	HANDHOLE, REMOVE	2.00 EACH
0033	202-91385	INLET, REMOVE	9.00 EACH
0034	202-93741	GUARDRAIL, END TREATMENT, REMOVE	27.00 EACH
0035	202-93763	LIGHT STANDARD AND FOUNDATION, REMOVE	15.00 EACH
0036	202-95027	IMPACT ATTENUATOR, REMOVE	2.00 EACH
0037	203-02000	EXCAVATION, COMMON	232876.00 CYS
0038	205-11626	PUMP AROUND	14.00 EACH
0039	205-12108	STORMWATER MANAGEMENT BUDGET	860082.00 DOL
0040	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0041	205-12618	SWQCP PREPARATION	1.00 LS
0042	206-51225	EXCAVATION, DRY	535.00 CYS
0043	207-09935	SUBGRADE TREATMENT, TYPE IC	43687.00 SYS
0044	207-12377	CEMENT STABILIZED SUBGRADE	456022.00 SYS
0045	211-06467	AGGREGATE FOR END BENT BACKFILL	295.00 CYS
0046	211-09264	STRUCTURE BACKFILL, TYPE 1	20979.00 CYS
0047	211-09267	STRUCTURE BACKFILL, TYPE 4	3248.00 CYS
0048	211-09268	STRUCTURE BACKFILL, TYPE 5	112.00 CYS
0049	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	674859.00 SYS
0050	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	820.00 SYS
0051	215-12447	CEMENT STABILIZATION OF FOUNDATION SOIL	456022.00 SYS
0052	301-12233	COMPACTED AGGREGATE NO. 8	1056.00 CYS
0053	301-12234	COMPACTED AGGREGATE NO. 53	40119.00 CYS
0054	302-06464	SUBBASE FOR PCCP	206.00 CYS
0055	303-01180	COMPACTED AGGREGATE NO. 53	26309.00 TON
0056	306-11619	MILLING, ASPHALT, 5 IN.	2334.00 SYS
0057	309-12646	CEMENT TREATED PERMEABLE BASE	225769.00 SYS
0058	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	395.00 TON
0059	401-10258	JOINT ADHESIVE, SURFACE	1200.00 LFT
0060	401-10259	JOINT ADHESIVE, INTERMEDIATE	1200.00 LFT
0061	401-11785	LIQUID ASPHALT SEALANT	1200.00 LFT
0062	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	36109.00 TON
0063	402-10087	HMA FOR TEMPORARY PAVEMENT, D	28834.00 TON
0064	406-05520	ASPHALT FOR TACK COAT	34.00 TON
0065	410-11777	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm - SMA	265.00 TON
0066	501-06266	PROFILOGRAPH PCCP	1.00 LS
0067	501-06324	QC/QA-PCCP, 13 IN.	443168.00 SYS
0068	501-12644	PAVEMENT INSTRUMENTATION AND DATA COLLECTION	1.00 LS

0069	503-05240	D-1 CONTRACTION JOINT	283393.00	LFT
0070	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	2125.00	SYS
0071	503-12478	TERMINAL JOINT, TYPE PCCP	474.00	LFT
0072	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	474.00	LFT
0073	601-02241	GUARDRAIL, REMOVE	11411.00	LFT
0074	601-06246	IMPACT ATTENUATOR, R2-W1, TL-3	6.00	EACH
0075	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	11163.00	LFT
0076	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	3.00	EACH
0077	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	15.00	EACH
0078	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	17.00	EACH
0079	601-94689	GUARDRAIL, END TREATMENT, OS	23.00	EACH
0080	602-01064	CONCRETE BARRIER	28972.00	LFT
0081	602-06729	BARRIER, DELINEATOR	767.00	EACH
0082	602-11938	CONCRETE BARRIER, MODIFIED SECTION	196.00	CYS
0083	603-06040	FENCE, FARM FIELD, 47 IN.	932.00	LFT
0084	606-11064	MILLED PCCP CORRUGATIONS, CONVENTIONAL	123494.00	LFT
0085	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	600.00	LFT
0086	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	107.00	SYS
0087	609-06260	REINFORCED CONCRETE BRIDGE APPROACH, 13 IN.	820.00	SYS
0088	615-06510	MONUMENT, C	6.00	EACH
0089	615-06515	MONUMENT, D	25.00	EACH
0090	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0091	616-05688	RIPRAP, CLASS 1	4828.00	TON
0092	616-05689	RIPRAP, CLASS 2	593.00	TON
0093	616-06405	RIPRAP, REVETMENT	1756.00	TON
0094	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	6456.00	SYS
0095	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	3320.00	SYS
0096	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	2641.00	SYS
0097	616-51367	SLOPEWALL, CONCRETE, 4 IN.	174.00	SYS
0098	616-93019	RIPRAP, GROUTED, 18 IN.	392.00	SYS
0099	620-01754	SOUND BARRIER PANELS GROUND MOUNTED TYPE	29869.00	SFT
0100	620-01756	SOUND BARRIER ERECTION GROUND MOUNTED TYPE	29869.00	SFT
0101	620-08426	SOUND BARRIER DESIGN AND LAYOUT	1.00	LS
0102	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0103	621-02770	EROSION CONTROL BLANKET	86567.00	SYS
0104	621-03909	SEED MIXTURE, NATIVE	590.00	LBS
0105	621-06545	FERTILIZER	24.00	TON

0106	621-06553	SEED MIXTURE R	6780.00	LBS
0107	621-06565	MULCHING MATERIAL	70.00	TON
0108	621-06567	WATER	2.00	kGAL
0109	621-06570	TOPSOIL	895.00	CYS
0110	621-06574	SODDING	13805.00	SYS
0111	621-08161	PERMANENT TURF REINFORCEMENT MAT	394.00	SYS
0112	627-09327	CABLE BARRIER SYSTEM, TYPE TL-4	1000.00	LFT
0113	627-09331	SAFETY TERMINAL TYPE, TL-4	2.00	EACH
0114	627-10178	CABLE BARRIER SYSTEM, TYPE TL-4 SPARE PARTS	1.00	LS
0115	628-09403	FIELD OFFICE, C	28.00	MOS
0116	628-11729	CELLULAR TELEPHONE, TYPE A	2.00	EACH
0117	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0118	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0119	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	56.00	MOS
0120	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0121	628-11977	COMPUTER SYSTEM	2.00	EACH
0122	701-06011	DYNAMIC PILE LOAD TEST	4.00	EACH
0123	701-09557	TEST PILE, DYNAMIC, PRODUCTION	300.00	LFT
0124	701-09559	TEST PILE, DYNAMIC, RESTRIKE	4.00	EACH
0125	701-09679	CONICAL PILE TIP, 14 IN.	44.00	EACH
0126	701-09826	PILE, STEEL PIPE, 0.5 IN., 14 IN.	2400.00	LFT
0127	702-04325	TEMPORARY SHORING	1.00	LS
0128	702-51863	FIELD DRILLED HOLE IN CONCRETE	72.00	EACH
0129	702-92857	CONCRETE, C, SUBSTRUCTURE	125.00	CYS
0130	703-06029	REINFORCING BARS, EPOXY COATED	337004.00	LBS
0131	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	1184.00	EACH
0132	704-51002	CONCRETE, C, SUPERSTRUCTURE	518.00	CYS
0133	706-09959	RAILING, CONCRETE FT	532.00	LFT
0134	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	4.00	EACH
0135	707-09634	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 48 IN. X 49 IN.	1554.00	LFT
0136	709-51821	SURFACE SEAL	1.00	LS
0137	709-51821	SURFACE SEAL	1.00	LS
0138	714-11074	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 12 FT X 3 FT	198.00	LFT
0139	714-11096	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 8 FT. X 3 FT.	224.00	LFT
0140	714-11118	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 10 FT. X 3 FT.	196.00	LFT
0141	714-11173	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 3 FT.	195.00	LFT
0142	714-11174	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT. X 4 FT.	188.00	LFT

0143	714-11182	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 10 FT. X 5 FT.	478.50	LFT
0144	714-11196	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 12 FT. X 7 FT.	247.00	LFT
0145	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	115.00	LFT
0146	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	94703.00	LFT
0147	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	9060.00	LFT
0148	715-05146	PIPE, TYPE 2, CIRCULAR, 6 IN.	475.00	LFT
0149	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1611.00	LFT
0150	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	4258.00	LFT
0151	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	6446.00	LFT
0152	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	11468.00	LFT
0153	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	2458.00	LFT
0154	715-05162	PIPE, TYPE 2, CIRCULAR, 54 IN.	164.00	LFT
0155	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	160.00	LFT
0156	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	15.00	LFT
0157	715-05407	PIPE, END BENT DRAIN, 6 IN.	360.00	LFT
0158	715-06004	CONCRETE ANCHOR, 48 IN.	1.00	EACH
0159	715-06492	CONCRETE ANCHOR, 54 IN.	1.00	EACH
0160	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	27.00	TON
0161	715-09064	VIDEO INSPECTION FOR PIPE	23958.00	LFT
0162	715-11665	PIPE END SECTION, DIAMETER 6 IN.	18.00	EACH
0163	715-12172	CONCRETE ANCHOR, MIN. AREA 40 SFT	1.00	EACH
0164	715-12405	PIPE, TYPE 3, CIRCULAR 6 INCH	480.00	LFT
0165	715-12656	PIPE TYPE 2 DEFORMED MIN AREA 40 SFT	164.00	LFT
0166	715-46000	PIPE END SECTION, DIAMETER 12 IN.	12.00	EACH
0167	715-46005	PIPE END SECTION, DIAMETER 15 IN.	4.00	EACH
0168	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0169	715-46020	PIPE END SECTION, DIAMETER 24 IN.	15.00	EACH
0170	715-46040	PIPE END SECTION, DIAMETER 36 IN.	2.00	EACH
0171	716-07631	PIPE INSTALLATION, TRENCHLESS, 15 IN.	88.00	LFT
0172	716-07632	PIPE INSTALLATION, TRENCHLESS, 18 IN.	90.00	LFT
0173	716-07633	PIPE INSTALLATION, TRENCHLESS, 24 IN.	735.00	LFT
0174	716-07637	PIPE INSTALLATION, TRENCHLESS, 48 IN.	60.00	LFT
0175	718-06528	OUTLET PROTECTOR, 1	130.00	EACH
0176	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	10000.00	LFT
0177	718-11685	UNDERDRAIN CLEANOUT PORT	61.00	EACH
0178	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	87150.00	SYS
0179	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	383.00	SYS

0180	718-52610	AGGREGATE FOR UNDERDRAINS	11230.00	CYS
0181	720-02442	PIPE PLUG EXISTING	4.00	EACH
0182	720-07300	INLET, TYPE H WITH SLOTTED DRAIN.	2.00	EACH
0183	720-07302	INLET, TYPE HA WITH SLOTTED DRAIN.	2.00	EACH
0184	720-08660	MANHOLE, J5 MODIFIED	23.00	EACH
0185	720-44000	CASTING, ADJUST TO GRADE	2.00	EACH
0186	720-45041	INLET, H5	4.00	EACH
0187	720-45042	INLET, HA5	5.00	EACH
0188	720-45065	INLET, N12	4.00	EACH
0189	720-45066	INLET, N12 MODIFIED	4.00	EACH
0190	720-45070	INLET, P12A	1.00	EACH
0191	720-45141	INLET, H5 MODIFIED	44.00	EACH
0192	720-45141	INLET, H5 MODIFIED	48.00	EACH
0193	720-45141	INLET, H5 MODIFIED	7.00	EACH
0194	720-45141	INLET, H5 MODIFIED	1.00	EACH
0195	720-45410	MANHOLE, C4	4.00	EACH
0196	720-45430	MANHOLE, G4	2.00	EACH
0197	720-93501	MANHOLE, L4	1.00	EACH
0198	720-94612	MANHOLE, K4	3.00	EACH
0199	720-95310	INLET, P12A MODIFIED	4.00	EACH
0200	724-12103	PRE-COMPRESSED FOAM JOINT	474.00	LFT
0201	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	9.00	EACH
0202	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0203	801-04746	ENERGY ABSORBING TERMINAL, CZ, TL-	10.00	EACH
0204	801-06198	PATROLLER	480.00	DAY
0205	801-06201	TEMPORARY PANEL SIGNS	648.00	SFT
0206	801-06202	TEMPORARY PANEL SIGN SUPPORTS	307.00	LFT
0207	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	199560.00	LFT
0208	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	315537.00	LFT
0209	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	3463.00	LFT
0210	801-06586	TEMPORARY PAVEMENT MARKING, 8 IN.	4793.00	LFT
0211	801-06625	DETOUR ROUTE MARKER ASSEMBLY	48.00	EACH
0212	801-06640	CONSTRUCTION SIGN, A	74.00	EACH
0213	801-06645	CONSTRUCTION SIGN, B	16.00	EACH
0214	801-06710	FLASHING ARROW SIGN	1440.00	DAY
0215	801-06775	MAINTAINING TRAFFIC	1.00	LS
0216	801-06808	TRUCK, TOW	2400.00	HRS

0217	801-07118	BARRICADE, III-A	132.00	LFT
0218	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	60174.00	LFT
0219	801-08403	TEMPORARY TRAFFIC BARRIER TYPE 4	3000.00	LFT
0220	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	6261.00	LFT
0221	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	15.00	EACH
0222	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0223	801-12324	LAW ENFORCEMENT OFFICER	1200.00	HRS
0224	801-12544	AUTOMATED WORK ZONE INFORMATION SYSTEM	2.00	EACH
0225	801-12647	LAW ENFORCEMENT OFFICER TRAINING	1.00	DOL
0226	801-12652	QUEUE TRUCK	300.00	DAY
0227	801-52817	TEMPORARY CROSSOVER, B	2.00	EACH
0228	802-02475	SIGN, PANEL, RELOCATE	3.00	EACH
0229	802-03126	SIGN OVERHEAD RELOCATE	6.00	EACH
0230	802-03706	SIGN, PANEL, INSTALL	2.00	EACH
0231	802-03783	SIGN, PANEL, REMOVE	9.00	EACH
0232	802-04089	SIGN, SHEET, REMOVE	108.00	EACH
0233	802-04893	REFERENCE POST	60.00	EACH
0234	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	202.00	LFT
0235	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	196.00	LFT
0236	802-05703	SIGN POST, SQUARE TYPE 3 REINFORCED ANCHOR BASE	98.00	LFT
0237	802-07057	SIGN, PANEL, WITH LEGEND	681.00	SFT
0238	802-09221	OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE A	1.00	EACH
0239	802-09536	BOX TRUSS SIGN STRUCTURE FOUNDATION, 45 IN. CONCRETE BARRIER WALL	1.00	EACH
0240	802-09537	BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN. MEDIAN OR SHOULDER	1.00	EACH
0241	802-09577	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE E	2.00	EACH
0242	802-09578	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	4.00	EACH
0243	802-09580	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 45 IN.	3.00	EACH
0244	802-09581	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 36 IN.	3.00	EACH
0245	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	32.00	SFT
0246	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	521.00	SFT
0247	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	292.00	SFT
0248	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	6.00	EACH
0249	802-12224	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, C	2.00	EACH
0250	802-12532	RODENT SCREEN	9.00	EACH
0251	802-74050	SIGN, OVERHEAD, REMOVE	11.00	EACH
0252	802-74055	OVERHEAD SIGN STRUCTURE, BOX TRUSS, REMOVE	3.00	EACH
0253	802-74080	OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	5.00	EACH

0254	802-76095	STRUCTURAL STEEL, BREAKAWAY	2763.00	LBS
0255	802-91122	SIGN GROUND MOUNTED RESET	4.00	EACH
0256	804-06770	DELINEATOR POST	165.00	EACH
0257	805-01842	HANDHOLE SIGNAL TYPE 1	6.00	EACH
0258	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	211.00	LFT
0259	805-90187	CONDUIT, STEEL, GALVANIZED, 4 IN.	132.00	LFT
0260	805-95568	CONDUIT, PVC, 4 IN.	6170.00	LFT
0261	807-02191	HANDHOLE LIGHTING	10.00	EACH
0262	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	5581.00	LFT
0263	807-11981	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. DIA X 96 IN.	14.00	EACH
0264	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	20.00	EACH
0265	807-84748	LIGHT POLE, 40 FT. E.M.H., 8.0 FT. MAST ARM, TRANSFORMER BASE	14.00	EACH
0266	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	2268.00	LFT
0267	807-86910	CONNECTOR KIT, UNFUSED	20.00	EACH
0268	807-86915	CONNECTOR KIT, FUSED	20.00	EACH
0269	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	60.00	EACH
0270	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.00	EACH
0271	807-86930	INSULATION LINK, NON-WATERPROOFED	40.00	EACH
0272	807-86935	INSULATION LINK, WATERPROOFED	40.00	EACH
0273	808-06716	LINE, REMOVE	146628.00	LFT
0274	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0275	808-11882	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 5 IN.	1291.00	LFT
0276	808-12567	LINE, PREFORMED PLASTIC, SOLID, 6 IN. WHITE WITH BLACK TRIM	63786.00	LFT
0277	808-12568	LINE, PREFORMED PLASTIC, SOLID, 6 IN. YELLOW WITH BLACK TRIM	63435.00	LFT
0278	808-12569	LINE, PREFORMED, PLASTIC, BROKEN, BLACK, 5 IN	30446.00	LFT
0279	808-12570	LINE, PREFORMED, PLASTIC, DOTTED, BLACK, 5 IN	1291.00	LFT
0280	808-75053	LINE, PREFORMED PLASTIC, SOLID, WHITE, 8 IN.	7571.00	LFT
0281	808-75056	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, WHITE, 8 IN.	924.00	LFT
0282	808-75061	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	30446.00	LFT
0283	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	2.00	EACH
0284	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	807.00	EACH
0285	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1662.00	EACH
0286	808-91662	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSHATCH LINE, WHITE 12 IN.	1316.00	LFT
0287	809-04969	SPLICE	3.00	EACH
0288	809-06128	CCTV ASSEMBLY	1.00	EACH
0289	809-06128	CCTV ASSEMBLY	3.00	EACH
0290	809-94971	FIBER OPTIC CABLE	3601.00	LFT

Call: 250

Contract: R -41849-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0013	113-01614	PARTNERING OVERHEAD	1.00	LS
0014	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0015	202-02240	PAVEMENT REMOVAL	105870.00	SYS
0016	202-02272	PAVED SIDE DITCH, REMOVE	160.00	LFT
0017	202-02279	CURB AND GUTTER, REMOVE	414.00	LFT
0018	202-02928	CATCH BASIN, REMOVE	30.00	EACH
0019	202-12024	CABLE BARRIER, REMOVE	20322.00	LFT
0020	202-12026	SAFETY TERMINAL, REMOVE	12.00	EACH
0021	202-51133	RAILING, REMOVE	425.00	LFT
0022	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0023	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0024	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0025	202-93741	GUARDRAIL, END TREATMENT, REMOVE	13.00	EACH
0026	202-96133	PIPE, REMOVE	3243.00	LFT
0027	202-96151	TRANSPORTATION OF SALVAGEABLE ITEMS	1.00	LS
0028	203-02000	EXCAVATION, COMMON	4773.00	CYS
0029	203-02020	EXCAVATION, UNCLASSIFIED	605.00	CYS
0030	205-11626	PUMP AROUND	2.00	EACH
0031	205-12108	STORMWATER MANAGEMENT BUDGET	283301.00	DOL

0032	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0033	205-12618	SWQCP PREPARATION	1.00	LS
0034	207-08264	SUBGRADE TREATMENT, TYPE II	302.00	SYS
0035	207-09935	SUBGRADE TREATMENT, TYPE IC	4315.00	SYS
0036	207-12498	SUBGRADE TREATMENT, TYPE ID	39523.00	SYS
0037	211-02050	B BORROW	343.00	CYS
0038	211-06467	AGGREGATE FOR END BENT BACKFILL	20.00	CYS
0039	211-09265	STRUCTURE BACKFILL, TYPE 2	5133.00	CYS
0040	211-09266	STRUCTURE BACKFILL, TYPE 3	1785.00	CYS
0041	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	25.00	CYS
0042	213-09270	FLOWABLE BACKFILL, REMOVABLE	50.00	CYS
0043	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	283352.00	SYS
0044	301-12232	COMPACTED AGGREGATE NO. 5	4.00	CYS
0045	301-12234	COMPACTED AGGREGATE NO. 53	827.00	CYS
0046	302-06464	SUBBASE FOR PCCP	449.00	CYS
0047	303-01180	COMPACTED AGGREGATE NO. 53	277.00	TON
0048	304-07783	HMA PATCHING, TYPE D	974.00	TON
0049	304-12627	HMA PATCHING FULL DEPTH TYPE D	1670.00	TON
0050	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	4970.00	TON
0051	305-97019	RUBBLIZING PCCP	1814.00	SYS
0052	306-08033	MILLING, ASPHALT, 1 IN.	1100.00	SYS
0053	306-08034	MILLING, ASPHALT, 1 1/2 IN.	387580.00	SYS
0054	306-08159	MILLING, ASPHALT	1100.00	SYS
0055	401-06264	PROFILOGRAPH, HMA	1.00	LS
0056	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	66.00	TON
0057	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	7499.00	TON
0058	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	2048.00	TON
0059	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	76.00	TON
0060	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	130.00	TON
0061	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	60.00	TON
0062	401-10258	JOINT ADHESIVE, SURFACE	252303.00	LFT
0063	401-10259	JOINT ADHESIVE, INTERMEDIATE	197.00	LFT
0064	401-11785	LIQUID ASPHALT SEALANT	297.00	LFT
0065	402-10087	HMA FOR TEMPORARY PAVEMENT, D	18178.00	TON
0066	406-05520	ASPHALT FOR TACK COAT	137.00	TON
0067	410-09530	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm - SMA	22410.00	TON
0068	503-12477	TERMINAL JOINT, TYPE HMA	63.00	LFT

0069	506-06333	PCCP PATCHING, FULL DEPTH	978.00	SYS
0070	506-06334	PCCP PATCHING, PARTIAL DEPTH	151.00	SYS
0071	507-07480	PROFILING, PCCP	2641.00	SYS
0072	601-02241	GUARDRAIL, REMOVE	17947.00	LFT
0073	601-06246	IMPACT ATTENUATOR, R2-W1, TL-3	4.00	EACH
0074	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	17200.00	LFT
0075	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	1125.00	LFT
0076	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	4.00	EACH
0077	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	17.00	EACH
0078	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	9.00	EACH
0079	601-94689	GUARDRAIL, END TREATMENT, OS	17.00	EACH
0080	602-01064	CONCRETE BARRIER	17887.00	LFT
0081	602-06729	BARRIER, DELINEATOR	952.00	EACH
0082	603-06060	FENCE, FARM FIELD, RESET	200.00	LFT
0083	605-06145	CURB AND GUTTER, B, CONCRETE	1862.00	LFT
0084	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	50.00	LFT
0085	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	172104.00	LFT
0086	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	1811.50	SYS
0087	615-06505	MONUMENT, B	2.00	EACH
0088	615-06510	MONUMENT, C	9.00	EACH
0089	616-05688	RIPRAP, CLASS 1	2785.00	TON
0090	616-05689	RIPRAP, CLASS 2	1392.00	TON
0091	616-06405	RIPRAP, REVETMENT	1228.00	TON
0092	616-06451	RIPRAP, UNIFORM	81.00	TON
0093	616-09997	DITCH DETENTION CHECK	16.00	EACH
0094	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	5944.00	SYS
0095	616-93772	INSPECTION HOLE	15.00	EACH
0096	619-11049	CLEAN STEEL BRIDGE, PARTIAL, QP-1 BRIDGE NO.	1.00	LS
0097	619-12460	DISPOSAL OF CLEANING WASTE NONHAZARDOUS, BRIDGE NO	1.00	LS
0098	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0099	620-01754	SOUND BARRIER PANELS GROUND MOUNTED TYPE	44612.00	SFT
0100	620-01756	SOUND BARRIER ERECTION GROUND MOUNTED TYPE	44612.00	SFT
0101	620-08426	SOUND BARRIER DESIGN AND LAYOUT	1.00	LS
0102	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0103	621-06545	FERTILIZER	5.00	TON
0104	621-06554	SEED MIXTURE U	2262.00	LBS
0105	621-06559	MULCHED SEEDING R	4765.00	SYS

0106	621-06565	MULCHING MATERIAL	23.00 TON
0107	621-06567	WATER	15.00 kGAL
0108	621-06574	SODDING	3782.00 SYS
0109	627-09327	CABLE BARRIER SYSTEM, TYPE TL-4	2069.00 LFT
0110	627-09331	SAFETY TERMINAL TYPE, TL-4	2.00 EACH
0111	628-09403	FIELD OFFICE, C	36.00 MOS
0112	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00 EACH
0113	628-11977	COMPUTER SYSTEM	4.00 EACH
0114	701-09558	TEST PILE, INDICATOR, PRODUCTION	768.70 LFT
0115	701-09560	TEST PILE, INDICATOR, RESTRIKE	14.00 EACH
0116	701-09683	PILE SHOE, HP 12 X 74	123.00 EACH
0117	701-09739	PILE SHOE, HP 12 X 53	58.00 EACH
0118	701-51195	PILE, STEEL H HP 12 X 53	1526.60 LFT
0119	701-95780	PILE, STEEL H, HP 12 X 74	8508.60 LFT
0120	702-04325	TEMPORARY SHORING	1.00 LS
0121	702-51005	CONCRETE, A, SUBSTRUCTURE	350.40 CYS
0122	702-51015	CONCRETE, B, FOOTINGS	563.60 CYS
0123	702-51863	FIELD DRILLED HOLE IN CONCRETE	1128.00 EACH
0124	702-92857	CONCRETE, C, SUBSTRUCTURE	47.90 CYS
0125	703-06028	REINFORCING BARS	23884.00 LBS
0126	703-06029	REINFORCING BARS, EPOXY COATED	529691.00 LBS
0127	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	609.00 EACH
0128	704-51002	CONCRETE, C, SUPERSTRUCTURE	841.60 CYS
0129	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.00 EACH
0130	706-11404	RAILING, STEEL PF-1	442.00 LFT
0131	706-11601	RAILING, CONCRETE FT	82.00 CYS
0132	706-11602	RAILING, CONCRETE PF-1	26.10 CYS
0133	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	8.00 EACH
0134	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00 LS
0135	709-51821	SURFACE SEAL	1.00 LS
0136	709-51821	SURFACE SEAL	1.00 LS
0137	711-05395	REPLACE	18.00 EACH
0138	711-05395	REPLACE	18.00 EACH
0139	711-05395	REPLACE	36.00 EACH
0140	711-05728	REPAIR	109.00 EACH
0141	711-11599	REPAIR WELD	30.00 IN
0142	711-12407	HANGER CABLES	7.00 LFT

0143	711-51038	STRUCTURAL STEEL	1.00	LS
0144	711-51820	TEMPORARY SUPPORT	1.00	LS
0145	714-11150	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 4 FT X 2 FT-6 IN.	270.00	LFT
0146	715-02397	SAFETY METAL END SECTION, 4:1, DIA 36 IN.	3.00	EACH
0147	715-03475	SAFETY METAL END SECTION, 4:1, DIA 15 IN.	3.00	EACH
0148	715-03476	SAFETY METAL END SECTION, 4:1, DIA 24 IN.	1.00	EACH
0149	715-03584	SAFETY METAL END SECTION, 4:1, DIA 18 IN.	2.00	EACH
0150	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	663.00	LFT
0151	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	78473.00	LFT
0152	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	2033.00	LFT
0153	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	50.00	LFT
0154	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	2567.00	LFT
0155	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	626.00	LFT
0156	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	334.00	LFT
0157	715-05327	PIPE, TYPE 2, DEFORMED, MIN. AREA 1.83 SFT	881.00	LFT
0158	715-05331	PIPE, TYPE 2, DEFORMED, MIN. AREA 3.3 SFT	576.00	LFT
0159	715-05407	PIPE, END BENT DRAIN, 6 IN.	110.00	LFT
0160	715-05423	PIPE, SLOTTED DRAIN, 15 IN.	1726.00	LFT
0161	715-05424	PIPE, SLOTTED DRAIN, 18 IN.	1626.00	LFT
0162	715-06471	PIPE END SECTION, MIN. AREA 3.3 SFT	3.00	EACH
0163	715-07029	SAFETY METAL END SECTION, 4:1, MIN AREA 3.3 SFT	2.00	EACH
0164	715-08171	PIPE, TYPE 1, DEFORMED, MIN. AREA 12.9 SFT	148.00	LFT
0165	715-08448	PIPE, TYPE 2, DEFORMED, MIN. AREA 10.2 SFT	371.00	LFT
0166	715-09064	VIDEO INSPECTION FOR PIPE	6281.00	LFT
0167	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0168	715-46005	PIPE END SECTION, DIAMETER 15 IN.	25.00	EACH
0169	715-46010	PIPE END SECTION, DIAMETER 18 IN.	5.00	EACH
0170	715-46020	PIPE END SECTION, DIAMETER 24 IN.	3.00	EACH
0171	715-46040	PIPE END SECTION, DIAMETER 36 IN.	5.00	EACH
0172	715-46055	PIPE END SECTION, MIN. AREA 1.8 SFT	8.00	EACH
0173	715-92037	PIPE PVC 4 IN	60.00	LFT
0174	716-07631	PIPE INSTALLATION, TRENCHLESS, 15 IN.	400.00	LFT
0175	716-07632	PIPE INSTALLATION, TRENCHLESS, 18 IN.	440.00	LFT
0176	716-07633	PIPE INSTALLATION, TRENCHLESS, 24 IN.	51.00	LFT
0177	718-06528	OUTLET PROTECTOR, 1	58.00	EACH
0178	718-06529	OUTLET PROTECTOR, 2	11.00	EACH
0179	718-06531	OUTLET PROTECTOR, 3	3.00	EACH

0180	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	6500.00	LFT
0181	718-11685	UNDERDRAIN CLEANOUT PORT	49.00	EACH
0182	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	40784.00	SYS
0183	718-52610	AGGREGATE FOR UNDERDRAINS	5375.00	CYS
0184	720-08628	SLOTTED DRAIN PIPE CLEANOUT PORT TYPE II	2.00	EACH
0185	720-45040	INLET, G7	3.00	EACH
0186	720-45140	INLET, G7 MODIFIED	2.00	EACH
0187	720-45141	INLET, H5 MODIFIED	61.00	EACH
0188	720-45265	PIPE CATCH BASIN, 15 IN.	1.00	EACH
0189	720-93472	CATCH BASIN, A4	2.00	EACH
0190	720-98174	INLET, B15	2.00	EACH
0191	720-98555	INLET, C15	2.00	EACH
0192	722-01066	HYDRODEMOLITION	740.00	SYS
0193	722-12380	BRIDGE DECK OVERLAY, BUDGET	54780.00	DOL
0194	722-12382	TRANSVERSE GROOVING	1882.00	SYS
0195	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	768.00	SYS
0196	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	400.00	SFT
0197	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	240.00	SFT
0198	722-51874	OVERLAY DAM	126.00	SFT
0199	722-97116	BRIDGE DECK OVERLAY, PATCHING	440.00	SFT
0200	724-12103	PRE-COMPRESSED FOAM JOINT	151.00	LFT
0201	724-12420	BRIDGE JOINT NOSING	124.00	SFT
0202	724-12461	CONCRETE FOR PATCHING STRUCTURAL EXPANSION JOINT	60.00	SFT
0203	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	2641.00	SYS
0204	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	16.00	EACH
0205	801-03290	CONSTRUCTION SIGN, C	46.00	EACH
0206	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00	EACH
0207	801-04746	ENERGY ABSORBING TERMINAL, CZ, TL-	13.00	EACH
0208	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	61561.00	LFT
0209	801-06204	TEMPORARY PAVEMENT MARKING, 5 IN.	8519.00	LFT
0210	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	121371.00	LFT
0211	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	11247.00	LFT
0212	801-06212	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (ONLY)	18.00	EACH
0213	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	8200.00	LFT
0214	801-06625	DETOUR ROUTE MARKER ASSEMBLY	147.00	EACH
0215	801-06640	CONSTRUCTION SIGN, A	215.00	EACH
0216	801-06645	CONSTRUCTION SIGN, B	72.00	EACH

0217	801-06710	FLASHING ARROW SIGN	1419.00	DAY
0218	801-06775	MAINTAINING TRAFFIC	1.00	LS
0219	801-07118	BARRICADE, III-A	320.00	LFT
0220	801-07119	BARRICADE, III-B	48.00	LFT
0221	801-07606	TEMPORARY Crossover DRAINAGE PIPE	800.00	LFT
0222	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	21130.00	LFT
0223	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	45830.00	LFT
0224	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	980.00	LFT
0225	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	18.00	EACH
0226	801-12031	TEMPORARY PORTABLE RUMBLE STRIPS	28.00	DAY
0227	801-12042	TRUCK MOUNTED ATTENUATOR	56.00	DAY
0228	801-12324	LAW ENFORCEMENT OFFICER	292.00	HRS
0229	801-12544	AUTOMATED WORK ZONE INFORMATION SYSTEM	4.00	EACH
0230	801-12544	AUTOMATED WORK ZONE INFORMATION SYSTEM	4.00	EACH
0231	801-12647	LAW ENFORCEMENT OFFICER TRAINING	1.00	DOL
0232	801-12652	QUEUE TRUCK	56.00	DAY
0233	801-52817	TEMPORARY Crossover, B	2.00	EACH
0234	802-02475	SIGN, PANEL, RELOCATE	6.00	EACH
0235	802-03126	SIGN OVERHEAD RELOCATE	3.00	EACH
0236	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	238.00	LFT
0237	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	231.00	LFT
0238	802-06402	DYNAMIC MESSAGE SIGN	2.00	EACH
0239	802-07057	SIGN, PANEL, WITH LEGEND	1715.00	SFT
0240	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	37.00	EACH
0241	802-07061	OVERHEAD SIGN STRUCTURE, DMS BOX TRUSS	2.00	EACH
0242	802-09580	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 45 IN.	3.00	EACH
0243	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	98.00	SFT
0244	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	203.00	SFT
0245	802-09897	BOX TRUSS SIGN STRUCTURE FOUNDATION, DMS 45 IN. HEIGHT	2.00	EACH
0246	802-09898	BOX TRUSS SIGN STRUCTURE FOUNDATION, DMS 36 IN. HEIGHT	2.00	EACH
0247	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	12.00	EACH
0248	802-12223	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, B	16.00	EACH
0249	802-12224	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, C	4.00	EACH
0250	802-74040	SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	15.00	EACH
0251	802-76095	STRUCTURAL STEEL, BREAKAWAY	16040.00	LBS
0252	805-04973	CONDUIT	39.00	LFT
0253	805-04973	CONDUIT	854.00	LFT

0254	805-04973	CONDUIT	44.00	LFT
0255	805-09845	CONTACT CLOSURE CARD	1.00	EACH
0256	805-09846	RECEIVER PROCESSOR	1.00	EACH
0257	805-10107	WIRELESS MAGNETOMETER DETECTOR	12.00	EACH
0258	807-04651	WIRE	948.00	LFT
0259	807-04651	WIRE	948.00	LFT
0260	807-78590	HANDHOLE	10.00	EACH
0261	808-06716	LINE, REMOVE	75449.00	LFT
0262	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0263	808-11882	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 5 IN.	331.00	LFT
0264	808-12032	GROOVING FOR PAVEMENT MARKINGS	343129.00	LFT
0265	808-12134	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 4 IN.	4351.00	LFT
0266	808-12454	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 8 IN.	405.00	LFT
0267	808-12567	LINE, PREFORMED PLASTIC, SOLID, 6 IN. WHITE WITH BLACK TRIM	17348.00	LFT
0268	808-12568	LINE, PREFORMED PLASTIC, SOLID, 6 IN. YELLOW WITH BLACK TRIM	17381.00	LFT
0269	808-12569	LINE, PREFORMED, PLASTIC, BROKEN, BLACK, 5 IN	5215.00	LFT
0270	808-12570	LINE, PREFORMED, PLASTIC, DOTTED, BLACK, 5 IN	331.00	LFT
0271	808-12593	LINE, PREFORMED, PLASTIC, DOTTED, BLACK, 4 IN	1773.00	LFT
0272	808-12633	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSHATCH LINE YELLOW, 24 IN.	555.00	LFT
0273	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	586.00	LFT
0274	808-75052	LINE, PREFORMED PLASTIC, SOLID, WHITE, 6 IN.	84731.00	LFT
0275	808-75053	LINE, PREFORMED PLASTIC, SOLID, WHITE, 8 IN.	7724.00	LFT
0276	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	586.00	LFT
0277	808-75057	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 6 IN.	84391.00	LFT
0278	808-75061	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	42441.00	LFT
0279	808-75071	PAVEMENT MESSAGE MARKING, PREFORMED PLASTIC, LANE INDICATION ARROW	2.00	EACH
0280	808-75510	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	723.00	LFT
0281	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	772.00	EACH
0282	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	3456.00	EACH
0283	809-04652	SERVICE POINT	3.00	EACH
0284	809-04652	SERVICE POINT	1.00	EACH
0285	809-04982	CABLE	487.00	LFT
0286	809-06101	FOUNDATION	2.00	EACH
0287	809-06128	CCTV ASSEMBLY	4.00	EACH
0288	809-08398	ITS CONTROLLER CABINET	2.00	EACH
0289	809-08399	ITS CONTROLLER CABINET FOUNDATION	2.00	EACH
0290	809-09343	ITS	4.00	EACH

0291	809-09343	ITS	2.00 EACH
0292	809-09343	ITS	2.00 EACH
0293	809-09343	ITS	1.00 EACH
0294	809-09343	ITS	1.00 EACH
0295	809-11707	ITS FIELD SWITCH	4.00 EACH

Call: 250

Contract: R -41849-A

Section No.: 2 ADDED TRAVEL LANES, HMA

Line

Item No	Item Code	Description	Quantity	Unit
0296	203-02000	EXCAVATION, COMMON	122042.00	CYS
0297	207-12377	CEMENT STABILIZED SUBGRADE	281288.00	SYS
0298	301-12234	COMPACTED AGGREGATE NO. 53	44095.00	CYS
0299	303-01180	COMPACTED AGGREGATE NO. 53	20385.00	TON
0300	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	10655.00	TON
0301	401-07371	QC/QA-HMA, 2, 64, INTERMEDIATE, 12.5 mm	10789.00	TON
0302	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	57076.00	TON
0303	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	93997.00	TON
0304	401-10258	JOINT ADHESIVE, SURFACE	154231.00	LFT
0305	401-10259	JOINT ADHESIVE, INTERMEDIATE	154231.00	LFT
0306	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	46788.00	TON
0307	406-05520	ASPHALT FOR TACK COAT	336.00	TON
0308	410-11777	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm - SMA	18799.00	TON
0309	410-12485	QC/QA HMA 4, 76, INTERMEDIATE 12.5-SMA	18799.00	TON
0310	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	76107.00	LFT
0311	702-90915	CONCRETE, CLASS, A	163.00	CYS
0312	808-75052	LINE, PREFORMED PLASTIC, SOLID, WHITE, 6 IN.	38155.00	LFT
0313	808-75057	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 6 IN.	40855.00	LFT

Call: 250

Contract: R -41849-A

Section No.: 3 ADDED TRAVEL LANES, PCCP

Line

Item No	Item Code	Description	Quantity	Unit
0314	203-02000	EXCAVATION, COMMON	101492.00	CYS
0315	207-09935	SUBGRADE TREATMENT, TYPE IC	2231.00	SYS
0316	207-12377	CEMENT STABILIZED SUBGRADE	278940.00	SYS
0317	301-12234	COMPACTED AGGREGATE NO. 53	46473.00	CYS
0318	302-06464	SUBBASE FOR PCCP	503.00	CYS
0319	303-01180	COMPACTED AGGREGATE NO. 53	7466.00	TON
0320	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	41861.00	TON
0321	501-06266	PROFILOGRAPH PCCP	1.00	LS
0322	501-06322	QC/QA-PCCP, 11 IN.	272523.00	SYS
0323	503-05240	D-1 CONTRACTION JOINT	149147.00	LFT
0324	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	2231.00	SYS
0325	503-12478	TERMINAL JOINT, TYPE PCCP	502.00	LFT
0326	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	502.00	LFT
0327	606-11064	MILLED PCCP CORRUGATIONS, CONVENTIONAL	76107.00	LFT
0328	702-90915	CONCRETE, CLASS, A	130.00	CYS
0329	703-06029	REINFORCING BARS, EPOXY COATED	2377.00	LBS
0330	724-12103	PRE-COMPRESSED FOAM JOINT	502.00	LFT
0331	808-12567	LINE, PREFORMED PLASTIC, SOLID, 6 IN. WHITE WITH BLACK TRIM	38155.00	LFT
0332	808-12568	LINE, PREFORMED PLASTIC, SOLID, 6 IN. YELLOW WITH BLACK TRIM	40855.00	LFT
0333	808-12569	LINE, PREFORMED, PLASTIC, BROKEN, BLACK, 5 IN	18063.00	LFT
0334	808-12571	LINE, PREFORMED, PLASTIC, DOTTED, BLACK, 8 IN	405.00	LFT
0335	808-12593	LINE, PREFORMED, PLASTIC, DOTTED, BLACK, 4 IN	474.00	LFT

Call: 250

Contract: R -41849-A

Section No.: 4 ADDED TRAVEL LANES, LATEX MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0336	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1298.00	SYS

Call: 250
Contract: R -41849-A
Section No.: 5 ADDED TRAVEL LANES, SILICA FUME MODIFIED CONCRETE

Line				
Item No	Item Code	Description	Quantity	Unit
0337	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	1298.00	SYS

Call: 260

Contract: R -42002-A

Section No.: 1 SLIDE CORRECTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	203-02020	EXCAVATION, UNCLASSIFIED	4295.00 CYS
0012	205-11626	PUMP AROUND	1.00 EACH
0013	205-12108	STORMWATER MANAGEMENT BUDGET	2531.00 DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0015	205-12618	SWQCP PREPARATION	1.00 LS
0016	207-09935	SUBGRADE TREATMENT, TYPE IC	587.00 SYS
0017	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	587.00 SYS
0018	301-12231	COMPACTED AGGREGATE NO. 2	147.00 CYS
0019	301-12232	COMPACTED AGGREGATE NO. 5	118.00 CYS
0020	303-01180	COMPACTED AGGREGATE NO. 53	75.00 TON
0021	306-08034	MILLING, ASPHALT, 1 1/2 IN.	332.00 SYS
0022	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	49.00 TON
0023	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	72.00 TON
0024	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	178.00 TON
0025	401-10258	JOINT ADHESIVE, SURFACE	320.00 LFT
0026	401-10259	JOINT ADHESIVE, INTERMEDIATE	190.00 LFT
0027	401-11785	LIQUID ASPHALT SEALANT	320.00 LFT
0028	406-05521	ASPHALT FOR TACK COAT	1840.00 SYS
0029	615-06490	RIGHT-OF-WAY MARKER	7.00 EACH
0030	616-06405	RIPRAP, REVETMENT	4990.00 TON
0031	616-06451	RIPRAP, UNIFORM	106.00 TON

0032	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	144.00	SYS
0033	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	1160.00	SYS
0034	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0035	621-02770	EROSION CONTROL BLANKET	386.00	SYS
0036	621-06559	MULCHED SEEDING R	386.00	SYS
0037	628-09402	FIELD OFFICE, B	6.00	MOS
0038	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0039	628-11977	COMPUTER SYSTEM	1.00	EACH
0040	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	335.00	LFT
0041	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	64.00	LFT
0042	718-06528	OUTLET PROTECTOR, 1	1.00	EACH
0043	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	162.00	SYS
0044	718-52610	AGGREGATE FOR UNDERDRAINS	9.00	CYS
0045	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	EACH
0046	801-06625	DETOUR ROUTE MARKER ASSEMBLY	36.00	EACH
0047	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0048	801-06775	MAINTAINING TRAFFIC	1.00	LS
0049	801-07118	BARRICADE, III-A	50.00	LFT
0050	801-07119	BARRICADE, III-B	30.00	LFT
0051	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH
0052	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	1.00	EACH
0053	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	640.00	LFT
0054	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	640.00	LFT
0055	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	8.00	EACH

Call: 280

Contract: R -42678-B

Section No.: 1 IDIQ, PATCH AND REHAB PAVEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0002	109-08360	CONTRACT LIENS	1.00 DOL
0003	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	50000.00 DOL
0009	201-02245	TREE 6 IN., REMOVE	3.00 EACH
0010	201-02250	TREE 10 IN., REMOVE	3.00 EACH
0011	201-02255	TREE 18 IN., REMOVE	3.00 EACH
0012	201-02260	TREE 30 IN., REMOVE	3.00 EACH
0013	201-02265	TREE 48 IN., REMOVE	3.00 EACH
0014	201-02270	TREE 60 IN., REMOVE	3.00 EACH
0015	202-02240	PAVEMENT REMOVAL	400.00 SYS
0016	202-52710	SIDEWALK CONCRETE, REMOVE	28.00 SYS
0017	203-02000	EXCAVATION, COMMON	6.00 CYS
0018	303-01180	COMPACTED AGGREGATE NO. 53	25.00 TON
0019	303-07449	COMPACTED AGGREGATE NO. 73	25.00 TON
0020	304-12625	HMA PATCHING FULL DEPTH TYPE C	100.00 TON
0021	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	120.00 TON
0022	304-12627	HMA PATCHING FULL DEPTH TYPE D	100.00 TON
0023	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	120.00 TON
0024	306-08159	MILLING, ASPHALT	12500.00 SYS
0025	401-10258	JOINT ADHESIVE, SURFACE	12500.00 LFT
0026	401-11785	LIQUID ASPHALT SEALANT	12500.00 LFT
0027	402-07452	HMA WEDGE AND LEVEL, TYPE C	100.00 TON
0028	402-07787	HMA WEDGE AND LEVEL, TYPE D	100.00 TON
0029	406-05521	ASPHALT FOR TACK COAT	12500.00 SYS
0030	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	3.00 TON
0031	503-05240	D-1 CONTRACTION JOINT	144.00 LFT

0032	506-06333	PCCP PATCHING, FULL DEPTH	180.00	SYS
0033	506-06334	PCCP PATCHING, PARTIAL DEPTH	180.00	SYS
0034	507-07505	RETROFIT LOAD TRANSFER	50.00	EACH
0035	507-08269	CRACKS IN PCCP, FILLED	12500.00	LFT
0036	507-08272	JOINTS IN PCCP, SAW AND SEAL	12500.00	LFT
0037	604-06070	SIDEWALK, CONCRETE	3.00	SYS
0038	604-08086	CURB RAMP, CONCRETE	25.00	SYS
0039	604-12083	DETECTABLE WARNING SURFACES	9.00	SYS
0040	605-01870	CURB, CONCRETE A	100.00	LFT
0041	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	16.00	EACH
0042	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00	EACH
0043	801-06640	CONSTRUCTION SIGN, A	100.00	EACH
0044	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0045	801-06710	FLASHING ARROW SIGN	50.00	DAY
0046	801-07119	BARRICADE, III-B	200.00	LFT
0047	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	600.00	LFT
0048	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	5.00	EACH
0049	801-12348	TEMPORARY WORKSITE SPEED DISPLAY ASSEMBLY	16.00	EACH
0050	801-12440	MAINTAINING TRAFFIC, IDIQ	150000.00	DOL
0051	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	5280.00	LFT
0052	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	5280.00	LFT
0053	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	5280.00	LFT
0054	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	5280.00	LFT
0055	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	5280.00	LFT
0056	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	5280.00	LFT
0057	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	5280.00	LFT
0058	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	5280.00	LFT

Call: 300

Contract: RS-39891-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-02240	PAVEMENT REMOVAL	156.00 SYS
0014	202-52710	SIDEWALK CONCRETE, REMOVE	19.00 SYS
0015	202-93741	GUARDRAIL, END TREATMENT, REMOVE	1.00 EACH
0016	203-02000	EXCAVATION, COMMON	10.00 CYS
0017	205-12108	STORMWATER MANAGEMENT BUDGET	20000.00 DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0019	205-12618	SWQCP PREPARATION	1.00 LS
0020	207-12498	SUBGRADE TREATMENT, TYPE ID	12674.00 SYS
0021	211-09265	STRUCTURE BACKFILL, TYPE 2	661.00 CYS
0022	301-12234	COMPACTED AGGREGATE NO. 53	555.00 CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	2903.00 TON
0024	303-07449	COMPACTED AGGREGATE NO. 73	1779.00 TON
0025	304-12623	HMA PATCHING FULL DEPTH TYPE B	7371.00 TON
0026	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	311.00 TON
0027	304-12625	HMA PATCHING FULL DEPTH TYPE C	330.00 TON
0028	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	251.00 TON
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	358993.00 SYS
0030	306-08036	MILLING, ASPHALT, 2 IN.	3362.00 SYS
0031	306-08159	MILLING, ASPHALT	1223.00 SYS

0032	306-08432	MILLING, APPROACH	14220.00	SYS
0033	306-08599	MILLING, ASPHALT, 1/2 IN.	73309.00	SYS
0034	401-06264	PROFILOGRAPH, HMA	1.00	LS
0035	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	18201.00	TON
0036	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	11419.00	TON
0037	401-07339	QC/QA-HMA, 2, 64, SURFACE, 12.5 mm	8569.00	TON
0038	401-10258	JOINT ADHESIVE, SURFACE	208181.00	LFT
0039	401-11785	LIQUID ASPHALT SEALANT	275187.00	LFT
0040	406-05520	ASPHALT FOR TACK COAT	167.00	TON
0041	601-02241	GUARDRAIL, REMOVE	263.00	LFT
0042	601-09238	HAND DIG GUARDRAIL POST HOLES	16.00	EACH
0043	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	6.00	EACH
0044	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0045	601-94690	GUARDRAIL, END TREATMENT, MS	2.00	EACH
0046	604-06070	SIDEWALK, CONCRETE	19.00	SYS
0047	604-08086	CURB RAMP, CONCRETE	66.00	SYS
0048	604-12083	DETECTABLE WARNING SURFACES	11.00	SYS
0049	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	2.00	SYS
0050	605-06120	CURB, CONCRETE	23.00	LFT
0051	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	88959.00	LFT
0052	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	101059.00	LFT
0053	610-07487	HMA FOR APPROACHES, TYPE B	999.00	TON
0054	610-07488	HMA FOR APPROACHES, TYPE C	230.00	TON
0055	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	5.00	EACH
0056	615-06520	MONUMENT, RE-ESTABLISH	3.00	EACH
0057	615-06525	CASTING ADJUST TO GRADE, MONUMENT	1.00	EACH
0058	616-05688	RIPRAP, CLASS 1	6.00	TON
0059	616-05689	RIPRAP, CLASS 2	10.00	TON
0060	616-06405	RIPRAP, REVETMENT	17.00	TON
0061	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	10.00	SYS
0062	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	20.00	SYS
0063	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	13.00	EACH
0064	621-02770	EROSION CONTROL BLANKET	246.00	SYS
0065	621-06553	SEED MIXTURE R	5.00	LBS
0066	621-06559	MULCHED SEEDING R	359.00	SYS
0067	628-09402	FIELD OFFICE, B	13.00	MOS
0068	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	EACH

0069	715-03475	SAFETY METAL END SECTION, 4:1, DIA 15 IN.	18.00 EACH
0070	715-03584	SAFETY METAL END SECTION, 4:1, DIA 18 IN.	4.00 EACH
0071	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	172.00 LFT
0072	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	671.00 LFT
0073	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	198.00 LFT
0074	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	487.00 TON
0075	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	204.00 TON
0076	715-09064	VIDEO INSPECTION FOR PIPE	1041.00 LFT
0077	715-46040	PIPE END SECTION, DIAMETER 36 IN.	2.00 EACH
0078	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00 EACH
0079	720-44000	CASTING, ADJUST TO GRADE	4.00 EACH
0080	720-45070	INLET, P12A	2.00 EACH
0081	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00 EACH
0082	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	5.00 EACH
0083	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	12080.00 LFT
0084	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	12080.00 LFT
0085	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	5.00 EACH
0086	801-06214	TEMPORARY TRANSVERSE PAVEMENT MARKING, 6 IN.	95.00 LFT
0087	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	155.00 LFT
0088	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	155.00 LFT
0089	801-06640	CONSTRUCTION SIGN, A	111.00 EACH
0090	801-06645	CONSTRUCTION SIGN, B	6.00 EACH
0091	801-06710	FLASHING ARROW SIGN	180.00 DAY
0092	801-06775	MAINTAINING TRAFFIC	1.00 LS
0093	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	6.00 EACH
0094	801-07118	BARRICADE, III-A	100.00 LFT
0095	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	187.00 LFT
0096	801-11990	TEMPORARY CURB RAMP	4.00 EACH
0097	801-92448	CONSTRUCTION SIGNS MOBILE	820.00 DAY
0098	802-91122	SIGN GROUND MOUNTED RESET	1.00 EACH
0099	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	162.00 LFT
0100	805-78785	SIGNAL DETECTOR HOUSING	1.00 EACH
0101	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	47.00 LFT
0102	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	13165.00 LFT
0103	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	138418.00 LFT
0104	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	51860.00 LFT
0105	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS

0106	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	12820.00	LFT
0107	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	52206.00	LFT
0108	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	50208.00	LFT
0109	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	264.00	LFT
0110	808-10038	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE WHITE 24 IN.	46.00	LFT
0111	808-10058	LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN.	108.00	LFT
0112	808-10119	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW, 24 IN.	60.00	LFT
0113	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	90.00	LFT
0114	808-12032	GROOVING FOR PAVEMENT MARKINGS	26737.00	LFT
0115	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	300.00	LFT
0116	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	143.00	LFT
0117	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	5.00	EACH
0118	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1368.00	EACH
0119	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	811.00	EACH

Call: 310

Contract: RS-39994-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	6.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-52710	SIDEWALK CONCRETE, REMOVE	83.00 SYS
0013	202-90277	DETECTOR HOUSING, REMOVE	54.00 EACH
0014	203-02000	EXCAVATION, COMMON	16.00 CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	7689.00 DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0017	207-12498	SUBGRADE TREATMENT, TYPE ID	323.00 SYS
0018	302-07455	DENSE GRADED SUBBASE	27.00 CYS
0019	304-12627	HMA PATCHING FULL DEPTH TYPE D	148.00 TON
0020	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	1064.00 TON
0021	306-08034	MILLING, ASPHALT, 1 1/2 IN.	112981.00 SYS
0022	306-08432	MILLING, APPROACH	7450.00 SYS
0023	401-06264	PROFILOGRAPH, HMA	1.00 LS
0024	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	9515.00 TON
0025	401-10258	JOINT ADHESIVE, SURFACE	42361.00 LFT
0026	401-11785	LIQUID ASPHALT SEALANT	42361.00 LFT
0027	406-05520	ASPHALT FOR TACK COAT	31.00 TON
0028	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.00 TON
0029	503-03489	RETROFITTED TIE BARS	26.00 EACH
0030	503-05240	D-1 CONTRACTION JOINT	48.00 LFT
0031	506-06333	PCCP PATCHING, FULL DEPTH	164.00 SYS

0032	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	6.25	LFT
0033	601-94690	GUARDRAIL, END TREATMENT, MS	2.00	EACH
0034	604-06070	SIDEWALK, CONCRETE	85.00	SYS
0035	604-08086	CURB RAMP, CONCRETE	41.00	SYS
0036	604-12083	DETECTABLE WARNING SURFACES	8.00	SYS
0037	605-02278	CURB, REMOVE	140.00	LFT
0038	605-06120	CURB, CONCRETE	140.00	LFT
0039	610-07487	HMA FOR APPROACHES, TYPE B	75.00	TON
0040	610-07488	HMA FOR APPROACHES, TYPE C	541.00	TON
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0042	621-06560	MULCHED SEEDING U	289.00	SYS
0043	621-06567	WATER	1.00	KGAL
0044	621-06575	SODDING, NURSERY	53.00	SYS
0045	628-09402	FIELD OFFICE, B	6.00	MOS
0046	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0047	628-11977	COMPUTER SYSTEM	1.00	EACH
0048	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0049	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	50920.00	LFT
0050	801-06640	CONSTRUCTION SIGN, A	43.00	EACH
0051	801-06645	CONSTRUCTION SIGN, B	7.00	EACH
0052	801-06710	FLASHING ARROW SIGN	180.00	DAY
0053	801-06775	MAINTAINING TRAFFIC	1.00	LS
0054	801-07118	BARRICADE, III-A	84.00	LFT
0055	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0056	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0057	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	6.00	EACH
0058	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	5.00	EACH
0059	805-05405	SIGNAL POLE, PEDESTAL, 4FT	1.00	EACH
0060	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	118.00	LFT
0061	805-11817	PEDESTRIAN PUSH BUTTON, APS	6.00	EACH
0062	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	19120.00	LFT
0063	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	994.00	LFT
0064	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	1043.00	LFT
0065	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	2806.00	LFT
0066	805-78785	SIGNAL DETECTOR HOUSING	54.00	EACH
0067	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	6370.00	LFT
0068	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	4.00	EACH

0069	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	6630.00	LFT
0070	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	32073.00	LFT
0071	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	1319.00	LFT
0072	808-06716	LINE, REMOVE	101.00	LFT
0073	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0074	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	58.00	LFT
0075	808-12032	GROOVING FOR PAVEMENT MARKINGS	63673.00	LFT
0076	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	23593.00	LFT
0077	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	124.00	LFT
0078	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	1419.00	LFT
0079	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	504.00	LFT
0080	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	79.00	EACH
0081	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	641.00	EACH
0082	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	641.00	EACH

Call: 330

Contract: RS-40613-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	207-12498	SUBGRADE TREATMENT, TYPE ID	165.00 SYS
0011	303-01180	COMPACTED AGGREGATE NO. 53	588.00 TON
0012	304-12625	HMA PATCHING FULL DEPTH TYPE C	374.00 TON
0013	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	158.00 TON
0014	306-08036	MILLING, ASPHALT, 2 IN.	80893.00 SYS
0015	306-08432	MILLING, APPROACH	3317.00 SYS
0016	401-06264	PROFILOGRAPH, HMA	1.00 LS
0017	401-07340	QC/QA-HMA, 3, 64, SURFACE, 12.5 mm	8899.00 TON
0018	401-10258	JOINT ADHESIVE, SURFACE	25718.00 LFT
0019	401-11785	LIQUID ASPHALT SEALANT	25718.00 LFT
0020	406-05520	ASPHALT FOR TACK COAT	23.00 TON
0021	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	5.00 TON
0022	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	29190.00 LFT
0023	610-07488	HMA FOR APPROACHES, TYPE C	366.00 TON
0024	628-09403	FIELD OFFICE, C	6.00 MOS
0025	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0026	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2948.00 LFT
0027	801-06640	CONSTRUCTION SIGN, A	37.00 EACH
0028	801-06775	MAINTAINING TRAFFIC	1.00 LS
0029	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	54586.00 LFT
0030	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0031	808-12032	GROOVING FOR PAVEMENT MARKINGS	2000.00 LFT

0032	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	4060.00	LFT
0033	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	31300.00	LFT
0034	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	181.00	LFT
0035	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	2.00	EACH
0036	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	606.00	EACH
0037	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	606.00	EACH

Call: 340

Contract: RS-40946-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	207-12498	SUBGRADE TREATMENT, TYPE ID	1563.00 SYS
0011	304-12623	HMA PATCHING FULL DEPTH TYPE B	1031.00 TON
0012	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	100.00 TON
0013	306-08432	MILLING, APPROACH	14674.00 SYS
0014	306-10163	MILLING ASPHALT, 2 1/2 IN	232006.00 SYS
0015	401-06264	PROFILOGRAPH, HMA	1.00 LS
0016	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	31901.00 TON
0017	401-10258	JOINT ADHESIVE, SURFACE	86438.00 LFT
0018	401-11785	LIQUID ASPHALT SEALANT	86438.00 LFT
0019	406-05520	ASPHALT FOR TACK COAT	68.00 TON
0020	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	5.00 TON
0021	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	52800.00 LFT
0022	610-07487	HMA FOR APPROACHES, TYPE B	2105.00 TON
0023	615-01469	MONUMENT SECTION CORNER INSTALL	1.00 EACH
0024	615-06525	CASTING ADJUST TO GRADE, MONUMENT	1.00 EACH
0025	628-09403	FIELD OFFICE, C	18.00 MOS
0026	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00 EACH
0027	720-44000	CASTING, ADJUST TO GRADE	2.00 EACH
0028	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	10730.00 LFT
0029	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	10730.00 LFT
0030	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	100.00 LFT
0031	801-06640	CONSTRUCTION SIGN, A	46.00 EACH

0032	801-06775	MAINTAINING TRAFFIC	1.00	LS
0033	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0034	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	15514.00	LFT
0035	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	145138.00	LFT
0036	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	35858.00	LFT
0037	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0038	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	905.00	LFT
0039	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1237.00	EACH
0040	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1237.00	EACH

Call: 360

Contract: RS-41097-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	10.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-52710	SIDEWALK CONCRETE, REMOVE	244.00 SYS
0014	202-93741	GUARDRAIL, END TREATMENT, REMOVE	16.00 EACH
0015	205-12108	STORMWATER MANAGEMENT BUDGET	2000.00 DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0017	207-12498	SUBGRADE TREATMENT, TYPE ID	1937.00 SYS
0018	303-01180	COMPACTED AGGREGATE NO. 53	750.00 TON
0019	304-12623	HMA PATCHING FULL DEPTH TYPE B	1278.00 TON
0020	306-08036	MILLING, ASPHALT, 2 IN.	37757.00 SYS
0021	306-08432	MILLING, APPROACH	1686.00 SYS
0022	401-06264	PROFILOGRAPH, HMA	1.00 LS
0023	401-07339	QC/QA-HMA, 2, 64, SURFACE, 12.5 mm	4271.00 TON
0024	401-10258	JOINT ADHESIVE, SURFACE	14082.00 LFT
0025	401-10259	JOINT ADHESIVE, INTERMEDIATE	2214.00 LFT
0026	401-11785	LIQUID ASPHALT SEALANT	14082.00 LFT
0027	406-05520	ASPHALT FOR TACK COAT	10.00 TON
0028	604-06070	SIDEWALK, CONCRETE	153.00 SYS
0029	604-08086	CURB RAMP, CONCRETE	77.00 SYS
0030	604-12083	DETECTABLE WARNING SURFACES	20.00 SYS
0031	605-06120	CURB, CONCRETE	468.00 LFT

0032	610-07487	HMA FOR APPROACHES, TYPE B	47.00	TON
0033	621-06575	SODDING, NURSERY	82.00	SYS
0034	628-09403	FIELD OFFICE, C	9.00	MOS
0035	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0036	720-44000	CASTING, ADJUST TO GRADE	8.00	EACH
0037	720-96995	CLEAN INLET	8.00	EACH
0038	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	4604.00	LFT
0039	801-06640	CONSTRUCTION SIGN, A	40.00	EACH
0040	801-06645	CONSTRUCTION SIGN, B	5.00	EACH
0041	801-06775	MAINTAINING TRAFFIC	1.00	LS
0042	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	50.00	LFT
0043	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	33.00	SFT
0044	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	20086.00	LFT
0045	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0046	808-12032	GROOVING FOR PAVEMENT MARKINGS	39084.00	LFT
0047	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1080.00	LFT
0048	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	17918.00	LFT
0049	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	790.00	LFT
0050	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	212.00	EACH

Call: 370

Contract: RS-41098-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	202-90277	DETECTOR HOUSING, REMOVE	6.00 EACH
0011	203-02000	EXCAVATION, COMMON	83.00 CYS
0012	207-12498	SUBGRADE TREATMENT, TYPE ID	1832.00 SYS
0013	303-01180	COMPACTED AGGREGATE NO. 53	166.00 TON
0014	304-12625	HMA PATCHING FULL DEPTH TYPE C	1511.00 TON
0015	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	1222.00 TON
0016	306-08034	MILLING, ASPHALT, 1 1/2 IN.	50815.00 SYS
0017	306-08432	MILLING, APPROACH	2245.00 SYS
0018	401-06264	PROFILOGRAPH, HMA	1.00 LS
0019	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	4193.00 TON
0020	401-10258	JOINT ADHESIVE, SURFACE	28802.00 LFT
0021	401-11785	LIQUID ASPHALT SEALANT	28802.00 LFT
0022	406-05520	ASPHALT FOR TACK COAT	15.00 TON
0023	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	3.00 TON
0024	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	12195.00 LFT
0025	610-07487	HMA FOR APPROACHES, TYPE B	186.00 TON
0026	615-06527	MONUMENT, SECTION CORNER	4.00 EACH
0027	628-09402	FIELD OFFICE, B	6.00 MOS
0028	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	2724.00 LFT
0029	801-06640	CONSTRUCTION SIGN, A	32.00 EACH
0030	801-06775	MAINTAINING TRAFFIC	1.00 LS
0031	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	170.00 LFT

0032	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	2070.00	LFT
0033	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	340.00	LFT
0034	805-78785	SIGNAL DETECTOR HOUSING	6.00	EACH
0035	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	642.00	LFT
0036	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	28414.00	LFT
0037	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	956.00	LFT
0038	808-06716	LINE, REMOVE	110.00	LFT
0039	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0040	808-12032	GROOVING FOR PAVEMENT MARKINGS	23980.00	LFT
0041	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	3250.00	LFT
0042	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2811.00	LFT
0043	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	150.00	LFT
0044	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	202.00	LFT
0045	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	5.00	EACH
0046	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	4.00	EACH
0047	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	240.00	EACH
0048	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	744.00	LFT

Call: 380

Contract: RS-41111-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	12.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	12.00 EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0010	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0011	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0012	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0014	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0015	202-02240	PAVEMENT REMOVAL	4198.00 SYS
0016	202-02279	CURB AND GUTTER, REMOVE	98.00 LFT
0017	202-52710	SIDEWALK CONCRETE, REMOVE	50.00 SYS
0018	202-74045	SIGN AND SUPPORTS, CHANNEL POSTS, REMOVE	2.00 EACH
0019	202-91385	INLET, REMOVE	1.00 EACH
0020	202-93741	GUARDRAIL, END TREATMENT, REMOVE	16.00 EACH
0021	202-96133	PIPE, REMOVE	144.00 LFT
0022	203-02000	EXCAVATION, COMMON	435.00 CYS
0023	205-11626	PUMP AROUND	1.00 EACH
0024	205-12108	STORMWATER MANAGEMENT BUDGET	14546.00 DOL
0025	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0026	205-12618	SWQCP PREPARATION	1.00 LS
0027	207-08264	SUBGRADE TREATMENT, TYPE II	1357.00 SYS
0028	207-09935	SUBGRADE TREATMENT, TYPE IC	275.00 SYS
0029	207-12498	SUBGRADE TREATMENT, TYPE ID	14894.00 SYS
0030	211-09265	STRUCTURE BACKFILL, TYPE 2	257.00 CYS
0031	301-12232	COMPACTED AGGREGATE NO. 5	55.00 CYS

0032	303-01180	COMPACTED AGGREGATE NO. 53	3332.00	TON
0033	304-07494	WIDENING WITH HMA, TYPE C	99.00	TON
0034	304-12625	HMA PATCHING FULL DEPTH TYPE C	9971.00	TON
0035	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	849.00	TON
0036	306-08036	MILLING, ASPHALT, 2 IN.	84707.00	SYS
0037	306-08037	MILLING, ASPHALT, 3 IN.	73453.00	SYS
0038	306-08038	MILLING, ASPHALT, 4 IN.	6425.00	SYS
0039	306-08043	MILLING, TRANSITION	3396.00	SYS
0040	306-08432	MILLING, APPROACH	8784.00	SYS
0041	401-06264	PROFILOGRAPH, HMA	1.00	LS
0042	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	13857.00	TON
0043	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	24155.00	TON
0044	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	131.00	TON
0045	401-11785	LIQUID ASPHALT SEALANT	65437.00	LFT
0046	406-05520	ASPHALT FOR TACK COAT	107.00	TON
0047	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	9.00	TON
0048	601-02241	GUARDRAIL, REMOVE	1181.00	LFT
0049	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	682.00	LFT
0050	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	4.00	EACH
0051	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	8.00	EACH
0052	601-94689	GUARDRAIL, END TREATMENT, OS	16.00	EACH
0053	604-06070	SIDEWALK, CONCRETE	26.00	SYS
0054	604-08086	CURB RAMP, CONCRETE	25.00	SYS
0055	604-12083	DETECTABLE WARNING SURFACES	7.00	SYS
0056	605-06120	CURB, CONCRETE	98.00	LFT
0057	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	46700.00	LFT
0058	610-07488	HMA FOR APPROACHES, TYPE C	1601.00	TON
0059	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	32.00	EACH
0060	615-06520	MONUMENT, RE-ESTABLISH	24.00	EACH
0061	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0062	616-05688	RIPRAP, CLASS 1	138.00	TON
0063	616-06451	RIPRAP, UNIFORM	52.00	TON
0064	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	231.00	SYS
0065	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	166.00	SYS
0066	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0067	621-02770	EROSION CONTROL BLANKET	802.00	SYS
0068	621-03787	SEED MIXTURE D	2.00	LBS

0069	621-06559	MULCHED SEEDING R	3427.00	SYS
0070	621-06567	WATER	1.00	kGAL
0071	621-06570	TOPSOIL	83.00	CYS
0072	621-06574	SODDING	65.00	SYS
0073	621-06575	SODDING, NURSERY	174.00	SYS
0074	628-09402	FIELD OFFICE, B	9.00	MOS
0075	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0076	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0077	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0078	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	9.00	MOS
0079	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0080	628-11977	COMPUTER SYSTEM	1.00	EACH
0081	714-11179	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 8 FT. X 6 FT.	66.00	LFT
0082	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	33.00	LFT
0083	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	79.00	LFT
0084	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	20.00	TON
0085	715-46010	PIPE END SECTION, DIAMETER 18 IN.	5.00	EACH
0086	720-45035	INLET, F7	1.00	EACH
0087	720-45410	MANHOLE, C4	1.00	EACH
0088	720-90349	MANHOLE, C8	1.00	EACH
0089	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	3.00	EACH
0090	801-01506	TEMPORARY PAVEMENT MESSAGE MARKING, (RXR)	2.00	EACH
0091	801-04308	ROAD CLOSURE SIGN ASSEMBLY	38.00	EACH
0092	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	5952.00	LFT
0093	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5952.00	LFT
0094	801-06213	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (RXR)	2.00	EACH
0095	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	203.00	LFT
0096	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	203.00	LFT
0097	801-06625	DETOUR ROUTE MARKER ASSEMBLY	60.00	EACH
0098	801-06640	CONSTRUCTION SIGN, A	67.00	EACH
0099	801-06645	CONSTRUCTION SIGN, B	21.00	EACH
0100	801-06775	MAINTAINING TRAFFIC	1.00	LS
0101	801-07118	BARRICADE, III-A	288.00	LFT
0102	801-07119	BARRICADE, III-B	1143.00	LFT
0103	801-92448	CONSTRUCTION SIGNS MOBILE	1447.00	DAY
0104	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	20.00	LFT
0105	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	7.00	SFT

0106	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	7.00	SFT
0107	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0108	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	116367.00	LFT
0109	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	40668.00	LFT
0110	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	11834.00	LFT
0111	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	214.00	LFT
0112	808-10053	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, R X R	2.00	EACH
0113	808-12032	GROOVING FOR PAVEMENT MARKINGS	129852.00	LFT
0114	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	910.00	EACH
0115	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	211.00	EACH

Call: 390

Contract: RS-41157-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	207-12498	SUBGRADE TREATMENT, TYPE ID	88.00 SYS
0011	303-07449	COMPACTED AGGREGATE NO. 73	351.00 TON
0012	304-12625	HMA PATCHING FULL DEPTH TYPE C	71.00 TON
0013	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	206.00 TON
0014	306-08036	MILLING, ASPHALT, 2 IN.	117755.00 SYS
0015	306-08432	MILLING, APPROACH	3280.00 SYS
0016	401-06264	PROFILOGRAPH, HMA	1.00 LS
0017	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	12954.00 TON
0018	401-10258	JOINT ADHESIVE, SURFACE	49551.00 LFT
0019	401-11785	LIQUID ASPHALT SEALANT	98863.00 LFT
0020	406-05520	ASPHALT FOR TACK COAT	31.00 TON
0021	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	6.50 TON
0022	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	49312.00 LFT
0023	610-07487	HMA FOR APPROACHES, TYPE B	361.00 TON
0024	628-09402	FIELD OFFICE, B	12.00 MOS
0025	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0026	628-11977	COMPUTER SYSTEM	1.00 EACH
0027	801-03290	CONSTRUCTION SIGN, C	5.00 EACH
0028	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7337.00 LFT
0029	801-06640	CONSTRUCTION SIGN, A	37.00 EACH
0030	801-06775	MAINTAINING TRAFFIC	1.00 LS
0031	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	596.00 LFT

0032	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	959.00	LFT
0033	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	59882.00	LFT
0034	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	48359.00	LFT
0035	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0036	808-12032	GROOVING FOR PAVEMENT MARKINGS	4556.00	LFT
0037	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	881.00	LFT
0038	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	44.00	LFT
0039	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	14.00	EACH
0040	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	5.00	EACH
0041	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	876.00	EACH
0042	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	876.00	EACH
0043	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	4556.00	LFT

Call: 430

Contract: B -38540-C

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0013	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0014	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00 LS
0015	202-02240	PAVEMENT REMOVAL	3691.00 SYS
0016	202-02271	HEADWALL, REMOVE	4.00 EACH
0017	202-02637	PIPE ABANDON AND GROUT FILL	148.00 LFT
0018	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0019	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0020	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0021	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0022	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0023	202-91385	INLET, REMOVE	2.00 EACH
0024	202-96133	PIPE, REMOVE	51.00 LFT
0025	203-02000	EXCAVATION, COMMON	3580.00 CYS
0026	203-02070	BORROW	245.00 CYS
0027	205-11626	PUMP AROUND	2.00 EACH
0028	205-12108	STORMWATER MANAGEMENT BUDGET	88438.00 DOL
0029	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0030	205-12618	SWQCP PREPARATION	1.00 LS
0031	206-51220	EXCAVATION, WET	63.00 CYS

0032	207-09935	SUBGRADE TREATMENT, TYPE IC	4877.00	SYS
0033	211-09264	STRUCTURE BACKFILL, TYPE 1	6.00	CYS
0034	211-09265	STRUCTURE BACKFILL, TYPE 2	1.00	CYS
0035	211-09268	STRUCTURE BACKFILL, TYPE 5	2104.00	CYS
0036	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	3987.60	SYS
0037	301-12232	COMPACTED AGGREGATE NO. 5	70.00	CYS
0038	301-12234	COMPACTED AGGREGATE NO. 53	615.00	CYS
0039	302-06464	SUBBASE FOR PCCP	647.00	CYS
0040	303-01180	COMPACTED AGGREGATE NO. 53	560.00	TON
0041	306-08036	MILLING, ASPHALT, 2 IN.	3771.00	SYS
0042	306-08037	MILLING, ASPHALT, 3 IN.	949.00	SYS
0043	306-08038	MILLING, ASPHALT, 4 IN.	317.00	SYS
0044	306-08043	MILLING, TRANSITION	1166.00	SYS
0045	306-08595	MILLING, ASPHALT, 3 1/2 IN.	423.00	SYS
0046	401-06264	PROFILOGRAPH, HMA	1.00	LS
0047	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	1004.00	TON
0048	401-07353	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm	476.00	TON
0049	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1791.00	TON
0050	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	470.00	TON
0051	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	728.00	TON
0052	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	1831.00	TON
0053	401-10258	JOINT ADHESIVE, SURFACE	13635.00	LFT
0054	401-10259	JOINT ADHESIVE, INTERMEDIATE	6452.00	LFT
0055	401-11785	LIQUID ASPHALT SEALANT	13635.00	LFT
0056	406-05521	ASPHALT FOR TACK COAT	30354.00	SYS
0057	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	4.00	TON
0058	502-06329	PCCP, 12 IN.	683.00	SYS
0059	503-03489	RETROFITTED TIE BARS	34.00	EACH
0060	503-05240	D-1 CONTRACTION JOINT	292.00	LFT
0061	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	644.00	SFT
0062	506-06333	PCCP PATCHING, FULL DEPTH	27.00	SYS
0063	507-07505	RETROFIT LOAD TRANSFER	78.00	EACH
0064	507-12191	JOINT REPAIR, PARTIAL DEPTH	1728.00	SFT
0065	601-02241	GUARDRAIL, REMOVE	3352.00	LFT
0066	601-06035	GUARDRAIL, RESET	857.00	LFT
0067	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1000.50	LFT
0068	601-12287	GUARDRAIL, MGS, LONG SPAN, TYPE 1	4.00	EACH

0069	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	19.00	EACH
0070	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	20.00	EACH
0071	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	5.00	EACH
0072	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0073	602-06729	BARRIER, DELINEATOR	32.00	EACH
0074	606-11064	MILLED PCCP CORRUGATIONS, CONVENTIONAL	292.00	LFT
0075	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	7691.00	LFT
0076	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	3217.00	LFT
0077	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	1725.10	SYS
0078	609-06262	REINFORCED CONCRETE BRIDGE APPROACH, 14 IN.	298.00	SYS
0079	616-05688	RIPRAP, CLASS 1	92.00	TON
0080	616-06405	RIPRAP, REVETMENT	70.00	TON
0081	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	108.00	SYS
0082	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	957.00	SYS
0083	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0084	621-06559	MULCHED SEEDING R	4291.00	SYS
0085	702-51863	FIELD DRILLED HOLE IN CONCRETE	172.00	EACH
0086	702-90915	CONCRETE, CLASS, A	4.00	CYS
0087	703-06029	REINFORCING BARS, EPOXY COATED	125389.00	LBS
0088	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	842.00	EACH
0089	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	20.00	EACH
0090	709-51821	SURFACE SEAL	1.00	LS
0091	709-51821	SURFACE SEAL	1.00	LS
0092	709-51821	SURFACE SEAL	1.00	LS
0093	709-51821	SURFACE SEAL	1.00	LS
0094	709-51821	SURFACE SEAL	1.00	LS
0095	709-51821	SURFACE SEAL	1.00	LS
0096	709-51821	SURFACE SEAL	1.00	LS
0097	710-09158	PATCHING CONCRETE STRUCTURES	980.00	SFT
0098	714-11076	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 9 FT X 8 FT	120.00	LFT
0099	714-11187	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 12 FT. X 6 FT.	130.00	LFT
0100	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	2886.00	LFT
0101	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	284.00	LFT
0102	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	52.00	LFT
0103	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	24.00	LFT
0104	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	149.00	LFT
0105	715-07758	GRATED BOX END SECTION, II, 6:1, MIN. AREA 7.4 SFT.	2.00	EACH

0106	718-06526	HMA FOR UNDERDRAINS	797.00	TON
0107	718-06528	OUTLET PROTECTOR, 1	12.00	EACH
0108	718-08308	UNDERDRAIN PATCHING	3444.00	LFT
0109	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	1769.00	SYS
0110	718-52610	AGGREGATE FOR UNDERDRAINS	202.00	CYS
0111	720-90984	MANHOLE, C2	2.00	EACH
0112	722-01066	HYDRODEMOLITION	2502.00	SYS
0113	722-12380	BRIDGE DECK OVERLAY, BUDGET	90735.00	DOL
0114	722-12382	TRANSVERSE GROOVING	2797.00	SYS
0115	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	2217.00	SYS
0116	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	285.00	SYS
0117	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	1332.00	SFT
0118	722-51874	OVERLAY DAM	96.00	SFT
0119	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0120	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00	EACH
0121	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	80631.00	LFT
0122	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	9645.00	LFT
0123	801-06625	DETOUR ROUTE MARKER ASSEMBLY	46.00	EACH
0124	801-06640	CONSTRUCTION SIGN, A	257.00	EACH
0125	801-06645	CONSTRUCTION SIGN, B	68.00	EACH
0126	801-06710	FLASHING ARROW SIGN	450.00	DAY
0127	801-06775	MAINTAINING TRAFFIC	1.00	LS
0128	801-07118	BARRICADE, III-A	830.00	LFT
0129	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2890.00	LFT
0130	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	2760.00	LFT
0131	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	12.00	EACH
0132	801-12324	LAW ENFORCEMENT OFFICER	1000.00	HRS
0133	801-12647	LAW ENFORCEMENT OFFICER TRAINING	1.00	DOL
0134	801-97643	TEMPORARY BUZZ STRIPS	3456.00	LFT
0135	804-06770	DELINEATOR POST	7.00	EACH
0136	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	220.00	LFT
0137	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2275.00	LFT
0138	808-06716	LINE, REMOVE	14360.00	LFT
0139	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	508.00	LFT
0140	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	18531.00	LFT
0141	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	18241.00	LFT
0142	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	4125.00	LFT

0143	808-11481	LINE, MULTI-COMPONENT, DOTTED, WHITE, 4 IN.	360.00	LFT
0144	808-12032	GROOVING FOR PAVEMENT MARKINGS	4281.00	LFT
0145	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1786.00	LFT
0146	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	18.00	EACH
0147	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	16.00	EACH
0148	808-97323	LINE, THERMOPLASTIC, FOR BUZZ STRIPS, 8 IN.	3456.00	LFT

Call: 430
 Contract: B -38540-C
 Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0149	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	2502.00	SYS

Call: 430
 Contract: B -38540-C
 Section No.: 3 SILICA FUME MODIFIED OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0150	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	2502.00	SYS

Call: 440

Contract: B -39740-B

Section No.: 1

BRIDGE REHABILITATION OR REPAIR

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0012	203-02000	EXCAVATION, COMMON	245.00 CYS
0013	205-12108	STORMWATER MANAGEMENT BUDGET	20000.00 DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0015	205-12618	SWQCP PREPARATION	1.00 LS
0016	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	65.00 CYS
0017	206-51235	COFFERDAM	1.00 LS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	710.00 SYS
0019	211-06467	AGGREGATE FOR END BENT BACKFILL	24.00 CYS
0020	211-09265	STRUCTURE BACKFILL, TYPE 2	1153.00 CYS
0021	301-12234	COMPACTED AGGREGATE NO. 53	7.00 CYS
0022	306-08043	MILLING, TRANSITION	297.00 SYS
0023	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	83.00 TON
0024	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	98.00 TON
0025	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	156.00 TON
0026	401-10258	JOINT ADHESIVE, SURFACE	308.00 LFT
0027	401-10259	JOINT ADHESIVE, INTERMEDIATE	308.00 LFT
0028	401-11785	LIQUID ASPHALT SEALANT	924.00 LFT
0029	406-05521	ASPHALT FOR TACK COAT	2427.00 SYS
0030	616-05689	RIPRAP, CLASS 2	306.00 TON
0031	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	300.00 SYS

0032	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0033	621-06560	MULCHED SEEDING U	800.00 SYS
0034	622-05651	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	2.00 EACH
0035	628-09402	FIELD OFFICE, B	12.00 MOS
0036	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0037	702-51005	CONCRETE, A, SUBSTRUCTURE	17.00 CYS
0038	702-51015	CONCRETE, B, FOOTINGS	15.40 CYS
0039	702-51863	FIELD DRILLED HOLE IN CONCRETE	528.00 EACH
0040	703-06029	REINFORCING BARS, EPOXY COATED	38831.00 LBS
0041	704-51002	CONCRETE, C, SUPERSTRUCTURE	258.60 CYS
0042	706-51020	RAILING, CONCRETE C	62.80 CYS
0043	710-09158	PATCHING CONCRETE STRUCTURES	300.00 SFT
0044	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	280.00 LFT
0045	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	140.00 SYS
0046	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	200.00 SFT
0047	727-90308	EPOXY INJECTION, CRACK PREPARATION	150.00 LFT
0048	727-90309	EPOXY INJECTION, EPOXY MATERIAL	10.00 GAL
0049	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00 LS
0050	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00 EACH
0051	801-06625	DETOUR ROUTE MARKER ASSEMBLY	16.00 EACH
0052	801-06640	CONSTRUCTION SIGN, A	5.00 EACH
0053	801-06775	MAINTAINING TRAFFIC	1.00 LS
0054	801-07118	BARRICADE, III-A	48.00 LFT
0055	801-07119	BARRICADE, III-B	96.00 LFT
0056	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	616.00 LFT

Call: 446

Contract: B -39880-B

Section No.: 1 SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	205-11626	PUMP AROUND	1.00	EACH
0010	205-12108	STORMWATER MANAGEMENT BUDGET	2484.00	DOL
0011	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0012	205-12618	SWQCP PREPARATION	1.00	LS
0013	616-05689	RIPRAP, CLASS 2	35.00	TON
0014	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	40.00	SYS
0015	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0016	621-06559	MULCHED SEEDING R	1621.00	SYS
0017	628-09401	FIELD OFFICE, A	3.00	MOS
0018	725-11709	PIPE LINER, CURED-IN-PLACE, MIN AREA 12.5 SFT	185.00	LFT
0019	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0020	801-06710	FLASHING ARROW SIGN	30.00	DAY
0021	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 450

Contract: B -40112-A

Section No.: 1 BRIDGE DECK OVERLAY

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	634.00	SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-51368	SLOPEWALL, REMOVE	196.00	SYS
0017	203-02000	EXCAVATION, COMMON	652.00	CYS
0018	203-02070	BORROW	180.00	CYS
0019	203-08607	LINEAR GRADING	370.00	LFT
0020	205-12108	STORMWATER MANAGEMENT BUDGET	9300.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	1474.00	SYS
0023	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	160.00	CYS
0024	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	2033.00	SYS
0025	302-06464	SUBBASE FOR PCCP	160.00	CYS
0026	304-12627	HMA PATCHING FULL DEPTH TYPE D	3.00	TON
0027	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	73.00	TON
0028	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	109.00	TON
0029	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	347.00	TON
0030	401-10258	JOINT ADHESIVE, SURFACE	3518.00	LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	3518.00	LFT

0032	401-11785	LIQUID ASPHALT SEALANT	3518.00	LFT
0033	402-10087	HMA FOR TEMPORARY PAVEMENT, D	456.00	TON
0034	406-05521	ASPHALT FOR TACK COAT	786.00	SYS
0035	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	844.00	SFT
0036	506-06333	PCCP PATCHING, FULL DEPTH	115.00	SYS
0037	601-02241	GUARDRAIL, REMOVE	157.00	LFT
0038	601-06035	GUARDRAIL, RESET	150.00	LFT
0039	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	2.00	EACH
0040	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0041	602-06729	BARRIER, DELINEATOR	8.00	EACH
0042	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	629.40	SYS
0043	616-06405	RIPRAP, REVETMENT	716.00	TON
0044	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	982.00	SYS
0045	616-51367	SLOPEWALL, CONCRETE, 4 IN.	196.00	SYS
0046	616-93772	INSPECTION HOLE	36.00	EACH
0047	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0048	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0049	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0050	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0051	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0052	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0053	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0054	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0055	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0056	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0057	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0058	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0059	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0060	621-06559	MULCHED SEEDING R	688.00	SYS
0061	621-06567	WATER	4.00	KGAL
0062	621-06574	SODDING	358.00	SYS
0063	628-09402	FIELD OFFICE, B	12.00	MOS
0064	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0065	702-51863	FIELD DRILLED HOLE IN CONCRETE	26.00	EACH
0066	703-06029	REINFORCING BARS, EPOXY COATED	40121.00	LBS
0067	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	254.00	EACH
0068	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	10.00	EACH

0069	709-51821	SURFACE SEAL	1.00	LS
0070	709-51821	SURFACE SEAL	1.00	LS
0071	709-51821	SURFACE SEAL	1.00	LS
0072	709-51821	SURFACE SEAL	1.00	LS
0073	709-51821	SURFACE SEAL	1.00	LS
0074	709-51821	SURFACE SEAL	1.00	LS
0075	709-51821	SURFACE SEAL	1.00	LS
0076	709-51821	SURFACE SEAL	1.00	LS
0077	710-09158	PATCHING CONCRETE STRUCTURES	622.00	SFT
0078	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0079	722-01066	HYDRODEMOLITION	9255.00	SYS
0080	722-12380	BRIDGE DECK OVERLAY, BUDGET	237600.00	DOL
0081	722-12382	TRANSVERSE GROOVING	9255.00	SYS
0082	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	9255.00	SYS
0083	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	4169.00	SFT
0084	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1226.00	SFT
0085	722-51874	OVERLAY DAM	583.00	SFT
0086	727-90308	EPOXY INJECTION, CRACK PREPARATION	1934.00	LFT
0087	727-90309	EPOXY INJECTION, EPOXY MATERIAL	10.00	GAL
0088	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0089	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0090	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0091	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0092	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	40712.00	LFT
0093	801-06640	CONSTRUCTION SIGN, A	49.00	EACH
0094	801-06645	CONSTRUCTION SIGN, B	16.00	EACH
0095	801-06710	FLASHING ARROW SIGN	330.00	DAY
0096	801-06775	MAINTAINING TRAFFIC	1.00	LS
0097	801-07118	BARRICADE, III-A	24.00	LFT
0098	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	4480.00	LFT
0099	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	6.00	EACH
0100	808-06716	LINE, REMOVE	21806.00	LFT
0101	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	13122.00	LFT
0102	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	11442.00	LFT
0103	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	2968.00	LFT
0104	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	106.00	EACH

Call: 450
Contract: B -40112-A
Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY

Line			Quantity Unit	
Item No	Item Code	Description		
0105	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	9255.00	SYS

Call: 450
Contract: B -40112-A
Section No.: 3 SILICA FUME MODIFIED CONCRETE OVERLAY

Line			Quantity Unit	
Item No	Item Code	Description		
0106	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	9255.00	SYS

Call: 460

Contract: B -40114-C

Section No.: 1 BRIDGE DECK OVERLAY

Line			Quantity Unit	
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-01015	CLEARING AND GRUBBING	1.00	LS
0012	201-02245	TREE 6 IN., REMOVE	3.00	EACH
0013	202-02240	PAVEMENT REMOVAL	430.00	SYS
0014	203-08607	LINEAR GRADING	1030.00	LFT
0015	205-11626	PUMP AROUND	1.00	EACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	14813.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	243.00	SYS
0020	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	243.00	SYS
0021	301-12234	COMPACTED AGGREGATE NO. 53	41.00	CYS
0022	302-07455	DENSE GRADED SUBBASE	43.00	CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	40.00	TON
0024	303-07449	COMPACTED AGGREGATE NO. 73	62.00	TON
0025	306-08039	MILLING, ASPHALT REMOVAL	470.00	SYS
0026	306-08043	MILLING, TRANSITION	1300.00	SYS
0027	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	127.00	TON
0028	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	34.00	TON
0029	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	147.00	TON
0030	401-10258	JOINT ADHESIVE, SURFACE	450.00	LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	60.00	LFT

0032	401-11785	LIQUID ASPHALT SEALANT	450.00	LFT
0033	406-05521	ASPHALT FOR TACK COAT	2030.00	SYS
0034	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0035	503-12477	TERMINAL JOINT, TYPE HMA	48.00	LFT
0036	506-06333	PCCP PATCHING, FULL DEPTH	5.00	SYS
0037	507-07482	CRACKS IN PCCP, ROUT AND SEAL	130.00	LFT
0038	507-08272	JOINTS IN PCCP, SAW AND SEAL	188.00	LFT
0039	601-02241	GUARDRAIL, REMOVE	172.00	LFT
0040	601-06035	GUARDRAIL, RESET	23.00	LFT
0041	601-06374	GUARDRAIL, TRANSITION, TGS-1	4.00	EACH
0042	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0043	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	248.00	LFT
0044	602-06729	BARRIER, DELINEATOR	14.00	EACH
0045	605-06125	CURB, CONCRETE, MODIFIED	83.00	LFT
0046	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	173.00	SYS
0047	616-05688	RIPRAP, CLASS 1	653.00	TON
0048	616-06405	RIPRAP, REVETMENT	59.00	TON
0049	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	603.00	SYS
0050	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0051	621-06559	MULCHED SEEDING R	331.00	SYS
0052	621-06574	SODDING	38.00	SYS
0053	628-09402	FIELD OFFICE, B	6.00	MOS
0054	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0055	702-51863	FIELD DRILLED HOLE IN CONCRETE	40.00	EACH
0056	703-01540	THREADED TIE BAR ASSEMBLY	122.00	EACH
0057	703-06029	REINFORCING BARS, EPOXY COATED	9796.00	LBS
0058	703-08247	EMBEDDED GALVANIC ANODE	190.00	EACH
0059	708-51813	PNEUMATICALLY PLACED MORTAR	118.00	SFT
0060	708-51814	WELDED STEEL WIRE REINFORCEMENT	18.00	SFT
0061	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0062	709-51821	SURFACE SEAL	1.00	LS
0063	709-51821	SURFACE SEAL	1.00	LS
0064	710-09158	PATCHING CONCRETE STRUCTURES	25.00	SFT
0065	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	22.00	EACH
0066	722-01066	HYDRODEMOLITION	470.00	SYS
0067	722-12380	BRIDGE DECK OVERLAY, BUDGET	8398.29	DOL
0068	722-12382	TRANSVERSE GROOVING	470.00	SYS

0069	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	470.00	SYS
0070	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	423.00	SFT
0071	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	150.00	SFT
0072	722-51874	OVERLAY DAM	85.00	SFT
0073	724-12103	PRE-COMPRESSED FOAM JOINT	48.00	LFT
0074	727-90308	EPOXY INJECTION, CRACK PREPARATION	22.00	LFT
0075	727-90309	EPOXY INJECTION, EPOXY MATERIAL	4.00	GAL
0076	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0077	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	366.00	SYS
0078	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.00	EACH
0079	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0080	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2976.00	LFT
0081	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0082	801-06625	DETOUR ROUTE MARKER ASSEMBLY	39.00	EACH
0083	801-06640	CONSTRUCTION SIGN, A	90.00	EACH
0084	801-06775	MAINTAINING TRAFFIC	1.00	LS
0085	801-07118	BARRICADE, III-A	48.00	LFT
0086	801-07119	BARRICADE, III-B	16.00	LFT
0087	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	838.00	LFT
0088	801-12081	PORTABLE SIGNAL	1.00	LS
0089	802-04089	SIGN, SHEET, REMOVE	1.00	EACH
0090	802-04893	REFERENCE POST	2.00	EACH
0091	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	12.00	LFT
0092	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	10.50	SFT
0093	808-06716	LINE, REMOVE	1676.00	LFT
0094	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1692.00	LFT
0095	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	220.00	LFT
0096	808-12032	GROOVING FOR PAVEMENT MARKINGS	1616.00	LFT
0097	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	7.00	EACH
0098	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	6.00	EACH

Call: 460

Contract: B -40114-C

Section No.: 2 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0099	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	470.00	SYS

Call: 460
Contract: B -40114-C
Section No.: 3 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

Line				
Item No	Item Code	Description	Quantity	Unit
0100	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	470.00	SYS

Call: 470

Contract: B -40370-A

Section No.: 1

BRIDGE REHABILITATION OR REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	730.00	SYS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0013	202-52710	SIDEWALK CONCRETE, REMOVE	77.00	SYS
0014	202-74035	SIGN, REMOVE	3.00	EACH
0015	203-02000	EXCAVATION, COMMON	2195.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	17000.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	206-51235	COFFERDAM	1.00	LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	393.00	SYS
0021	211-09266	STRUCTURE BACKFILL, TYPE 3	1806.00	CYS
0022	214-12236	GEOTEXTILE FOR PAVEMENT TYPE 1A	604.00	SYS
0023	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	646.00	SYS
0024	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	306.00	SYS
0025	301-12232	COMPACTED AGGREGATE NO. 5	102.00	CYS
0026	302-06464	SUBBASE FOR PCCP	302.00	CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	103.00	TON
0028	306-08036	MILLING, ASPHALT, 2 IN.	900.00	SYS
0029	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	143.00	TON
0030	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	65.00	TON
0031	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	130.00	TON

0032	401-10258	JOINT ADHESIVE, SURFACE	176.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	58.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	176.00	LFT
0035	406-05521	ASPHALT FOR TACK COAT	1706.00	SYS
0036	503-12477	TERMINAL JOINT, TYPE HMA	84.00	LFT
0037	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	1.00	EACH
0038	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0039	604-06070	SIDEWALK, CONCRETE	57.00	SYS
0040	604-08086	CURB RAMP, CONCRETE	32.00	SYS
0041	605-02278	CURB, REMOVE	133.00	LFT
0042	605-06120	CURB, CONCRETE	102.00	LFT
0043	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	306.00	SYS
0044	616-05688	RIPRAP, CLASS 1	545.00	TON
0045	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0046	621-06560	MULCHED SEEDING U	743.00	SYS
0047	621-12612	SEED MIXTURE FLOODPLAIN	2.00	LBS
0048	622-52436	SIGN, DO NOT MOW OR SPRAY	1.00	EACH
0049	628-09402	FIELD OFFICE, B	12.00	MOS
0050	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0051	702-02925	WATERPROOFING MEMBRANE SYSTEM	10912.00	SFT
0052	702-03607	CORED HOLE IN CONCRETE	12.00	EACH
0053	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	3.00	EACH
0054	702-51863	FIELD DRILLED HOLE IN CONCRETE	470.00	EACH
0055	703-06029	REINFORCING BARS, EPOXY COATED	173900.00	LBS
0056	703-08247	EMBEDDED GALVANIC ANODE	850.00	EACH
0057	704-51002	CONCRETE, C, SUPERSTRUCTURE	507.60	CYS
0058	706-51020	RAILING, CONCRETE C	62.90	CYS
0059	708-51813	PNEUMATICALLY PLACED MORTAR	3010.00	SFT
0060	708-51814	WELDED STEEL WIRE REINFORCEMENT	3010.00	SFT
0061	709-51821	SURFACE SEAL	1.00	LS
0062	710-09158	PATCHING CONCRETE STRUCTURES	360.00	SFT
0063	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	796.00	LFT
0064	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	3.00	EACH
0065	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	139.00	SYS
0066	724-12103	PRE-COMPRESSED FOAM JOINT	84.00	LFT
0067	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0068	801-06625	DETOUR ROUTE MARKER ASSEMBLY	19.00	EACH

0069	801-06640	CONSTRUCTION SIGN, A	19.00	EACH
0070	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
0071	801-06775	MAINTAINING TRAFFIC	1.00	LS
0072	801-07118	BARRICADE, III-A	96.00	LFT
0073	801-07119	BARRICADE, III-B	156.00	LFT
0074	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0075	805-01842	HANDHOLE SIGNAL TYPE 1	1.00	EACH
0076	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	535.00	LFT
0077	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	1194.00	LFT
0078	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	1088.00	LFT
0079	805-78785	SIGNAL DETECTOR HOUSING	3.00	EACH
0080	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	357.00	LFT
0081	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	180.00	LFT
0082	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	646.00	LFT
0083	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	28.00	LFT
0084	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	186.00	LFT

Call: 480

Contract: B -40408-A

Section No.: 1 BRIDGE REPLACEMENT

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0012	202-99187	FENCE, FARM FIELD, REMOVE	176.00	LFT
0013	203-02000	EXCAVATION, COMMON	1565.00	CYS
0014	203-02020	EXCAVATION, UNCLASSIFIED	591.00	CYS
0015	203-02070	BORROW	55.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	15000.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	206-51235	COFFERDAM	1.00	LS
0020	207-08268	SUBGRADE TREATMENT, TYPE IV	1881.00	SYS
0021	211-02050	B BORROW	1185.00	CYS
0022	211-09264	STRUCTURE BACKFILL, TYPE 1	13.00	CYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	19.00	CYS
0024	211-09268	STRUCTURE BACKFILL, TYPE 5	1250.00	CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	469.00	TON
0026	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	135.00	TON
0027	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	227.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	550.00	LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	550.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	550.00	LFT
0031	401-11897	QC/QA-HMA, 2, 64, INTERMEDIATE, 25.0 mm	371.00	TON

0032	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0033	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	3.00 EACH
0034	601-02241	GUARDRAIL, REMOVE	163.00 LFT
0035	601-12422	GUARDRAIL W-BEAM STRUCTURE TOP-MOUNTED POSTS	9.00 EACH
0036	601-94689	GUARDRAIL, END TREATMENT, OS	1.00 EACH
0037	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	100.00 LFT
0038	603-06040	FENCE, FARM FIELD, 47 IN.	176.00 LFT
0039	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00 EACH
0040	615-06490	RIGHT-OF-WAY MARKER	13.00 EACH
0041	615-06505	MONUMENT, B	4.00 EACH
0042	615-06510	MONUMENT, C	1.00 EACH
0043	615-06527	MONUMENT, SECTION CORNER	1.00 EACH
0044	615-08351	PLAQUE	1.00 EACH
0045	616-06405	RIPRAP, REVETMENT	29.00 TON
0046	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	45.00 SYS
0047	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0048	621-06559	MULCHED SEEDING R	1310.00 SYS
0049	621-06567	WATER	209.00 kGAL
0050	621-06574	SODDING	1327.00 SYS
0051	628-09401	FIELD OFFICE, A	12.00 MOS
0052	628-09409	MOBILE INTERNET SERVICE	12.00 MOS
0053	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0054	628-11977	COMPUTER SYSTEM	1.00 EACH
0055	701-09558	TEST PILE, INDICATOR, PRODUCTION	180.00 LFT
0056	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00 EACH
0057	701-09663	PILE, STEEL PIPE, 0.312 IN., 14 IN.	4062.00 LFT
0058	704-09031	ARTICULATING CONCRETE MATTRESS	344.00 SYS
0059	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	50.00 LFT
0060	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	45.00 LFT
0061	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00 EACH
0062	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00 EACH
0063	723-12599	STRUCTURE, COATED REINFORCED CONCRETE, 3-SIDED SECTIONS, 504 IN X 120 IN	64.00 LFT
0064	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00 EACH
0065	801-06625	DETOUR ROUTE MARKER ASSEMBLY	16.00 EACH
0066	801-06640	CONSTRUCTION SIGN, A	14.00 EACH
0067	801-06775	MAINTAINING TRAFFIC	1.00 LS
0068	801-07118	BARRICADE, III-A	72.00 LFT

0069	801-07119	BARRICADE, III-B	96.00	LFT
0070	802-04089	SIGN, SHEET, REMOVE	4.00	EACH
0071	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	139.00	LFT
0072	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	47.00	SFT
0073	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1100.00	LFT
0074	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1100.00	LFT

Call: 490

Contract: B -40466-A

Section No.: 1 REPLACE SUPERSTRUCTURE

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	2220.00	SYS
0013	202-02772	CASTING, REMOVE	4.00	EACH
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-51368	SLOPEWALL, REMOVE	176.00	SYS
0017	202-94954	BARRIER WALL, CONCRETE, REMOVE	2160.00	LFT
0018	203-02000	EXCAVATION, COMMON	380.00	CYS
0019	203-02070	BORROW	135.00	CYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	16064.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	207-12498	SUBGRADE TREATMENT, TYPE ID	2114.00	SYS
0023	211-06467	AGGREGATE FOR END BENT BACKFILL	140.00	CYS
0024	211-09265	STRUCTURE BACKFILL, TYPE 2	112.00	CYS
0025	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	72.00	CYS
0026	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	2382.00	SYS
0027	302-06464	SUBBASE FOR PCCP	522.00	CYS
0028	303-01180	COMPACTED AGGREGATE NO. 53	237.00	TON
0029	306-08041	MILLING, PCCP	4668.00	SYS
0030	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	194.00	TON
0031	401-10258	JOINT ADHESIVE, SURFACE	14000.00	LFT

0032	401-11785	LIQUID ASPHALT SEALANT	14000.00	LFT
0033	402-10087	HMA FOR TEMPORARY PAVEMENT, D	2160.00	TON
0034	406-05520	ASPHALT FOR TACK COAT	5.00	TON
0035	503-03489	RETROFITTED TIE BARS	192.00	EACH
0036	503-05240	D-1 CONTRACTION JOINT	558.00	LFT
0037	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	1448.00	SYS
0038	503-12478	TERMINAL JOINT, TYPE PCCP	186.00	LFT
0039	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	186.00	LFT
0040	601-02241	GUARDRAIL, REMOVE	775.00	LFT
0041	601-03464	GUARDRAIL, STEEL CURVED TERMINAL END SECTION	2.00	EACH
0042	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	500.00	LFT
0043	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0044	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0045	602-06729	BARRIER, DELINEATOR	78.00	EACH
0046	602-91266	CONCRETE MEDIAN BARRIER MODIFIED	2160.00	LFT
0047	607-06335	PAVED SIDE DITCH, A	212.00	LFT
0048	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	604.00	SYS
0049	616-06405	RIPRAP, REVETMENT	278.00	TON
0050	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	509.00	SYS
0051	616-51367	SLOPEWALL, CONCRETE, 4 IN.	140.00	SYS
0052	616-93772	INSPECTION HOLE	16.00	EACH
0053	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0054	621-06559	MULCHED SEEDING R	2334.00	SYS
0055	621-06567	WATER	2.00	KGAL
0056	621-06574	SODDING	186.00	SYS
0057	628-09402	FIELD OFFICE, B	16.00	MOS
0058	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0059	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0060	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0061	628-11781	CELLULAR TELEPHONE SERVICE, 750 MIN.	16.00	MOS
0062	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0063	702-04325	TEMPORARY SHORING	1.00	LS
0064	702-04325	TEMPORARY SHORING	1.00	LS
0065	702-51863	FIELD DRILLED HOLE IN CONCRETE	1112.00	EACH
0066	702-92857	CONCRETE, C, SUBSTRUCTURE	132.00	CYS
0067	703-06029	REINFORCING BARS, EPOXY COATED	205728.00	LBS
0068	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	104.00	EACH

0069	704-51002	CONCRETE, C, SUPERSTRUCTURE	456.60	CYS
0070	706-11601	RAILING, CONCRETE FT	70.20	CYS
0071	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	4.00	EACH
0072	707-09865	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 49 IN.	1410.00	LFT
0073	709-51821	SURFACE SEAL	1.00	LS
0074	709-51821	SURFACE SEAL	1.00	LS
0075	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	304.00	LFT
0076	715-05407	PIPE, END BENT DRAIN, 6 IN.	240.00	LFT
0077	715-46005	PIPE END SECTION, DIAMETER 15 IN.	4.00	EACH
0078	720-45025	INLET, D6	4.00	EACH
0079	724-12103	PRE-COMPRESSED FOAM JOINT	188.00	LFT
0080	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0081	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	8826.00	LFT
0082	801-06204	TEMPORARY PAVEMENT MARKING, 5 IN.	685.00	LFT
0083	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	29147.00	LFT
0084	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	6172.00	LFT
0085	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00	EACH
0086	801-06640	CONSTRUCTION SIGN, A	73.00	EACH
0087	801-06645	CONSTRUCTION SIGN, B	32.00	EACH
0088	801-06710	FLASHING ARROW SIGN	360.00	DAY
0089	801-06775	MAINTAINING TRAFFIC	1.00	LS
0090	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00	EACH
0091	801-07118	BARRICADE, III-A	120.00	LFT
0092	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	1760.00	LFT
0093	801-08507	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 1	5080.00	LFT
0094	801-52817	TEMPORARY CROSSEVER, B	2.00	EACH
0095	801-97643	TEMPORARY BUZZ STRIPS	1728.00	LFT
0096	802-02475	SIGN, PANEL, RELOCATE	2.00	EACH
0097	802-04089	SIGN, SHEET, REMOVE	2.00	EACH
0098	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0099	802-09577	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE E	2.00	EACH
0100	802-09581	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 36 IN.	2.00	EACH
0101	808-06716	LINE, REMOVE	17043.00	LFT
0102	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	4010.00	LFT
0103	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	4010.00	LFT
0104	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	685.00	LFT
0105	808-11484	LINE, MULTI-COMPONENT, DOTTED, WHITE, 5 IN.	806.00	LFT

0106	808-12032	GROOVING FOR PAVEMENT MARKINGS	8903.00	LFT
0107	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	7.00	EACH

Call: 500

Contract: B -40956-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0010	203-08607	LINEAR GRADING	416.00 LFT
0011	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	1.00 EACH
0012	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	3.00 TON
0013	306-08039	MILLING, ASPHALT REMOVAL	14.00 SYS
0014	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00 LS
0015	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0016	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0017	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00 LS
0018	619-95315	CLEAN AND PAINT BEARING ASSEMBLIES, BRIDGE NO.	1.00 LS
0019	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00 EACH
0020	621-06559	MULCHED SEEDING R	141.00 SYS
0021	628-09402	FIELD OFFICE, B	12.00 MOS
0022	628-11729	CELLULAR TELEPHONE, TYPE A	1.00 EACH
0023	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0024	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0025	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	12.00 MOS
0026	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0027	628-11977	COMPUTER SYSTEM	1.00 EACH
0028	709-51821	SURFACE SEAL	1.00 LS
0029	709-51821	SURFACE SEAL	1.00 LS
0030	709-51821	SURFACE SEAL	1.00 LS
0031	709-51821	SURFACE SEAL	1.00 LS

0032	709-51821	SURFACE SEAL	1.00	LS
0033	709-51821	SURFACE SEAL	1.00	LS
0034	710-09158	PATCHING CONCRETE STRUCTURES	4.00	SFT
0035	711-51038	STRUCTURAL STEEL	1.00	LS
0036	711-51038	STRUCTURAL STEEL	1.00	LS
0037	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00	LS
0038	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00	LS
0039	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	222.00	SFT
0040	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	897.00	SFT
0041	724-04163	STRUCTURAL EXPANSION JOINT SEAL, REPLACE	73.00	LFT
0042	724-09626	STRUCTURAL EXPANSION JOINT SEAL, SS, REPLACE	188.00	LFT
0043	724-12103	PRE-COMPRESSED FOAM JOINT	73.00	LFT
0044	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	1213.00	SYS
0045	801-03291	CONSTRUCTION SIGN, D	1.00	EACH
0046	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0047	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	27339.00	LFT
0048	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	18895.00	LFT
0049	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	22.00	LFT
0050	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	66.00	LFT
0051	801-06625	DETOUR ROUTE MARKER ASSEMBLY	30.00	EACH
0052	801-06640	CONSTRUCTION SIGN, A	142.00	EACH
0053	801-06645	CONSTRUCTION SIGN, B	9.00	EACH
0054	801-06710	FLASHING ARROW SIGN	77.00	DAY
0055	801-06775	MAINTAINING TRAFFIC	1.00	LS
0056	801-07118	BARRICADE, III-A	96.00	LFT
0057	801-07119	BARRICADE, III-B	240.00	LFT
0058	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	768.00	LFT
0059	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	8.00	EACH
0060	801-12042	TRUCK MOUNTED ATTENUATOR	42.00	DAY
0061	801-12081	PORTABLE SIGNAL	1.00	LS
0062	801-12081	PORTABLE SIGNAL	1.00	LS
0063	801-12081	PORTABLE SIGNAL	1.00	LS
0064	801-12081	PORTABLE SIGNAL	1.00	LS
0065	801-12482	DRIVEWAY ASSISTANCE DEVICE	1.00	EACH
0066	801-97643	TEMPORARY BUZZ STRIPS	396.00	LFT
0067	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	180.00	LFT
0068	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2166.00	LFT

0069	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1266.00	LFT
0070	808-06716	LINE, REMOVE	2036.00	LFT
0071	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	4.00	EACH

Call: 510

Contract: B -41001-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	304-12625	HMA PATCHING FULL DEPTH TYPE C	750.00	TON
0011	306-08034	MILLING, ASPHALT, 1 1/2 IN.	2865.00	SYS
0012	401-07334	QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	240.00	TON
0013	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0014	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	1499.00	SFT
0015	628-09403	FIELD OFFICE, C	6.00	MOS
0016	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0017	709-51821	SURFACE SEAL	1.00	LS
0018	709-51821	SURFACE SEAL	1.00	LS
0019	709-51821	SURFACE SEAL	1.00	LS
0020	709-51821	SURFACE SEAL	1.00	LS
0021	709-51821	SURFACE SEAL	1.00	LS
0022	709-51821	SURFACE SEAL	1.00	LS
0023	709-51821	SURFACE SEAL	1.00	LS
0024	709-51821	SURFACE SEAL	1.00	LS
0025	709-51821	SURFACE SEAL	1.00	LS
0026	709-51821	SURFACE SEAL	1.00	LS
0027	709-51821	SURFACE SEAL	1.00	LS
0028	709-51821	SURFACE SEAL	1.00	LS
0029	709-51821	SURFACE SEAL	1.00	LS
0030	709-51821	SURFACE SEAL	1.00	LS
0031	709-51821	SURFACE SEAL	1.00	LS

0032	709-51821	SURFACE SEAL	1.00	LS
0033	709-51821	SURFACE SEAL	1.00	LS
0034	709-51821	SURFACE SEAL	1.00	LS
0035	709-51821	SURFACE SEAL	1.00	LS
0036	709-51821	SURFACE SEAL	1.00	LS
0037	709-51821	SURFACE SEAL	1.00	LS
0038	709-51821	SURFACE SEAL	1.00	LS
0039	709-51821	SURFACE SEAL	1.00	LS
0040	709-51821	SURFACE SEAL	1.00	LS
0041	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	264.00	SFT
0042	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	2275.00	SFT
0043	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	3740.00	SYS
0044	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	16.00	EACH
0045	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	12000.00	LFT
0046	801-06640	CONSTRUCTION SIGN, A	32.00	EACH
0047	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0048	801-06710	FLASHING ARROW SIGN	120.00	DAY
0049	801-06775	MAINTAINING TRAFFIC	1.00	LS
0050	801-07118	BARRICADE, III-A	96.00	LFT
0051	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	8.00	EACH
0052	801-12042	TRUCK MOUNTED ATTENUATOR	120.00	DAY
0053	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	1.00	SYS
0054	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	1372.00	LFT
0055	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2685.00	LFT
0056	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2070.00	LFT
0057	808-06716	LINE, REMOVE	6127.00	LFT
0058	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	1.00	EACH
0059	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	29.00	EACH

Call: 520

Contract: B -41074-A

Section No.: 1

BRIDGE DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-02240	PAVEMENT REMOVAL	474.00 SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0015	202-51368	SLOPEWALL, REMOVE	284.00 SYS
0016	203-02000	EXCAVATION, COMMON	140.00 CYS
0017	205-12108	STORMWATER MANAGEMENT BUDGET	6377.00 DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0019	205-12618	SWQCP PREPARATION	1.00 LS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	544.00 SYS
0021	211-06467	AGGREGATE FOR END BENT BACKFILL	20.00 CYS
0022	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	678.00 SYS
0023	301-12234	COMPACTED AGGREGATE NO. 53	43.00 CYS
0024	302-06464	SUBBASE FOR PCCP	68.00 CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	94.00 TON
0026	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	20.00 TON
0027	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	33.00 TON
0028	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	141.00 TON
0029	401-10258	JOINT ADHESIVE, SURFACE	143.00 LFT
0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	143.00 LFT
0031	401-11785	LIQUID ASPHALT SEALANT	143.00 LFT

0032	406-05521	ASPHALT FOR TACK COAT	466.00	SYS
0033	503-12477	TERMINAL JOINT, TYPE HMA	88.00	LFT
0034	507-07482	CRACKS IN PCCP, ROUT AND SEAL	264.00	LFT
0035	507-08271	JOINTS IN PCCP, FILLED	382.00	LFT
0036	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH
0037	601-02241	GUARDRAIL, REMOVE	370.00	LFT
0038	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	4.00	EACH
0039	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0040	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	25.00	LFT
0041	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	270.00	SYS
0042	616-05688	RIPRAP, CLASS 1	214.00	TON
0043	616-06405	RIPRAP, REVETMENT	446.00	TON
0044	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	588.00	SYS
0045	619-12460	DISPOSAL OF CLEANING WASTE NONHAZARDOUS, BRIDGE NO	1.00	LS
0046	619-95315	CLEAN AND PAINT BEARING ASSEMBLIES, BRIDGE NO.	1.00	LS
0047	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0048	621-06559	MULCHED SEEDING R	356.00	SYS
0049	621-12612	SEED MIXTURE FLOODPLAIN	10.00	LBS
0050	628-09402	FIELD OFFICE, B	6.00	MOS
0051	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0052	628-11977	COMPUTER SYSTEM	1.00	EACH
0053	702-04325	TEMPORARY SHORING	1.00	LS
0054	702-51863	FIELD DRILLED HOLE IN CONCRETE	92.00	EACH
0055	703-06029	REINFORCING BARS, EPOXY COATED	26670.00	LBS
0056	703-08247	EMBEDDED GALVANIC ANODE	32.00	EACH
0057	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	182.00	EACH
0058	704-51002	CONCRETE, C, SUPERSTRUCTURE	34.60	CYS
0059	706-11600	RAILING, CONCRETE FC	2.60	CYS
0060	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0061	708-01112	GROUT, NON-SHRINK	0.50	CYS
0062	709-51821	SURFACE SEAL	1.00	LS
0063	709-51821	SURFACE SEAL	1.00	LS
0064	710-09158	PATCHING CONCRETE STRUCTURES	116.00	SFT
0065	713-04331	TEMPORARY CAUSEWAY	1.00	LS
0066	722-01066	HYDRODEMOLITION	517.00	SYS
0067	722-12380	BRIDGE DECK OVERLAY, BUDGET	9285.00	DOL
0068	722-12382	TRANSVERSE GROOVING	835.00	SYS

0069	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	517.00	SYS
0070	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	50.00	SFT
0071	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	374.00	SFT
0072	724-12103	PRE-COMPRESSED FOAM JOINT	88.00	LFT
0073	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	304.00	SYS
0074	801-04746	ENERGY ABSORBING TERMINAL, CZ, TL-	2.00	EACH
0075	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	14600.00	LFT
0076	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	60.00	LFT
0077	801-06640	CONSTRUCTION SIGN, A	52.00	EACH
0078	801-06645	CONSTRUCTION SIGN, B	42.00	EACH
0079	801-06775	MAINTAINING TRAFFIC	1.00	LS
0080	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	375.00	LFT
0081	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	200.00	LFT
0082	801-12042	TRUCK MOUNTED ATTENUATOR	28.00	DAY
0083	801-12081	PORTABLE SIGNAL	1.00	LS
0084	801-97643	TEMPORARY BUZZ STRIPS	864.00	LFT
0085	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	40.00	LFT
0086	802-07057	SIGN, PANEL, WITH LEGEND	15.00	SFT
0087	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	1556.00	LFT
0088	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	3300.00	LFT
0089	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	6904.00	LFT
0090	808-06716	LINE, REMOVE	4931.00	LFT
0091	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	3.00	EACH

Call: 520

Contract: B -41074-A

Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY OPTION

Line

Item No	Item Code	Description	Quantity	Unit
0092	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	565.00	SYS

Call: 520

Contract: B -41074-A

Section No.: 3 SILICA FUME MODIFIED CONCRETE OVERLAY OPTION

Line

Item No	Item Code	Description	Quantity	Unit
0093	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	565.00	SYS

Call: 530

Contract: B -41204-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	200.00	SYS
0012	202-51368	SLOPEWALL, REMOVE	90.00	SYS
0013	202-91385	INLET, REMOVE	4.00	EACH
0014	202-96133	PIPE, REMOVE	80.00	LFT
0015	203-02000	EXCAVATION, COMMON	1068.00	CYS
0016	207-09935	SUBGRADE TREATMENT, TYPE IC	1236.00	SYS
0017	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	11.00	EACH
0018	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	69.00	CYS
0019	302-07455	DENSE GRADED SUBBASE	4.00	CYS
0020	306-08034	MILLING, ASPHALT, 1 1/2 IN.	550.00	SYS
0021	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	50.00	TON
0022	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	102.00	TON
0023	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	170.00	TON
0024	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	272.00	TON
0025	401-07414	QC/QA-HMA, 4, 70, BASE, 25.0 mm	680.00	TON
0026	401-10258	JOINT ADHESIVE, SURFACE	3184.00	LFT
0027	401-10259	JOINT ADHESIVE, INTERMEDIATE	2780.00	LFT
0028	401-11785	LIQUID ASPHALT SEALANT	3184.00	LFT
0029	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0030	601-02241	GUARDRAIL, REMOVE	480.00	LFT
0031	601-06035	GUARDRAIL, RESET	300.00	LFT

0032	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	6.00 EACH
0033	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	6.00 EACH
0034	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	950.00 LFT
0035	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	22.00 SYS
0036	616-06405	RIPRAP, REVETMENT	106.00 TON
0037	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	196.00 SYS
0038	616-51366	SLOPEWALL, CONCRETE, 5 IN.	90.00 SYS
0039	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0040	621-06559	MULCHED SEEDING R	2000.00 SYS
0041	621-06574	SODDING	72.00 SYS
0042	628-09402	FIELD OFFICE, B	10.00 MOS
0043	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00 EACH
0044	702-51005	CONCRETE, A, SUBSTRUCTURE	1.00 CYS
0045	702-51863	FIELD DRILLED HOLE IN CONCRETE	20.00 EACH
0046	703-06029	REINFORCING BARS, EPOXY COATED	1157.00 LBS
0047	703-08247	EMBEDDED GALVANIC ANODE	622.00 EACH
0048	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	42.00 EACH
0049	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00 LS
0050	709-51821	SURFACE SEAL	1.00 LS
0051	709-51821	SURFACE SEAL	1.00 LS
0052	709-51821	SURFACE SEAL	1.00 LS
0053	709-51821	SURFACE SEAL	1.00 LS
0054	709-51821	SURFACE SEAL	1.00 LS
0055	709-51821	SURFACE SEAL	1.00 LS
0056	709-51821	SURFACE SEAL	1.00 LS
0057	709-51821	SURFACE SEAL	1.00 LS
0058	710-09158	PATCHING CONCRETE STRUCTURES	465.00 SFT
0059	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00 LS
0060	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00 LS
0061	722-01066	HYDRODEMOLITION	1864.00 SYS
0062	722-12380	BRIDGE DECK OVERLAY, BUDGET	70000.00 DOL
0063	722-12382	TRANSVERSE GROOVING	1864.00 SYS
0064	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	1864.00 SYS
0065	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	2650.00 SFT
0066	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1700.00 SFT
0067	722-51874	OVERLAY DAM	164.00 SFT
0068	724-12103	PRE-COMPRESSED FOAM JOINT	176.00 LFT

0069	727-90308	EPOXY INJECTION, CRACK PREPARATION	200.00	LFT
0070	727-90309	EPOXY INJECTION, EPOXY MATERIAL	32.00	GAL
0071	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0072	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	3825.00	SYS
0073	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0074	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00	EACH
0075	801-04746	ENERGY ABSORBING TERMINAL, CZ, TL-	2.00	EACH
0076	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	24725.00	LFT
0077	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	22.00	LFT
0078	801-06625	DETOUR ROUTE MARKER ASSEMBLY	46.00	EACH
0079	801-06640	CONSTRUCTION SIGN, A	197.00	EACH
0080	801-06645	CONSTRUCTION SIGN, B	62.00	EACH
0081	801-06710	FLASHING ARROW SIGN	234.00	DAY
0082	801-06775	MAINTAINING TRAFFIC	1.00	LS
0083	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	EACH
0084	801-07118	BARRICADE, III-A	536.00	LFT
0085	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	3098.00	LFT
0086	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	720.00	LFT
0087	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	14.00	EACH
0088	801-12042	TRUCK MOUNTED ATTENUATOR	110.00	DAY
0089	801-12081	PORTABLE SIGNAL	1.00	LS
0090	802-04893	REFERENCE POST	4.00	EACH
0091	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1750.00	LFT
0092	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1750.00	LFT
0093	808-06716	LINE, REMOVE	8540.00	LFT
0094	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	4084.00	LFT
0095	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2814.00	LFT
0096	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	2035.00	LFT
0097	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	56.00	EACH
0098	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	94.00	EACH

Call: 530

Contract: B -41204-A

Section No.: 2 BRIDGE DECK OVERLAY LATEX MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0099	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1864.00	SYS

Call: 530
Contract: B -41204-A
Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED CONCRETE

Line				
Item No	Item Code	Description	Quantity	Unit
0100	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	1864.00	SYS

Call: 540

Contract: B -41205-A

Section No.: 1 BRIDGE PAINTING

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	5356.00	SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	202-62420	BRIDGE RAILING, REMOVE	21.00	LFT
0018	202-74035	SIGN, REMOVE	1.00	EACH
0019	203-02000	EXCAVATION, COMMON	26.00	CYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	42000.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	220.00	CYS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	2686.00	SYS
0024	207-12498	SUBGRADE TREATMENT, TYPE ID	2728.00	SYS
0025	211-06467	AGGREGATE FOR END BENT BACKFILL	216.00	CYS
0026	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	8.00	EACH
0027	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	5.00	CYS
0028	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	228.00	SYS
0029	301-12233	COMPACTED AGGREGATE NO. 8	56.00	CYS
0030	301-12234	COMPACTED AGGREGATE NO. 53	38.00	CYS
0031	302-06464	SUBBASE FOR PCCP	474.00	CYS

0032	302-07455	DENSE GRADED SUBBASE	456.00	CYS
0033	304-12623	HMA PATCHING FULL DEPTH TYPE B	188.00	TON
0034	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	14.00	TON
0035	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	18.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	60.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	60.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	60.00	LFT
0039	401-12495	QC/QA HMA 4, 76, INTERMEDIATE, OG 9.5 MM	408.00	TON
0040	406-05521	ASPHALT FOR TACK COAT	452.00	SYS
0041	501-06326	QC/QA-PCCP, 15 IN.	2728.00	SYS
0042	503-03489	RETROFITTED TIE BARS	48.00	EACH
0043	503-05240	D-1 CONTRACTION JOINT	314.00	LFT
0044	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	1344.00	SYS
0045	503-12477	TERMINAL JOINT, TYPE HMA	68.00	LFT
0046	503-12478	TERMINAL JOINT, TYPE PCCP	314.00	LFT
0047	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	314.00	LFT
0048	507-07482	CRACKS IN PCCP, ROUT AND SEAL	84.00	LFT
0049	507-08269	CRACKS IN PCCP, FILLED	210.00	LFT
0050	507-08271	JOINTS IN PCCP, FILLED	50.00	LFT
0051	507-08272	JOINTS IN PCCP, SAW AND SEAL	50.00	LFT
0052	601-02241	GUARDRAIL, REMOVE	788.00	LFT
0053	601-06035	GUARDRAIL, RESET	40.00	LFT
0054	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	176.00	LFT
0055	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	8.00	EACH
0056	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	2.00	EACH
0057	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	6.00	EACH
0058	603-06065	FENCE, CHAIN LINK, RESET	50.00	LFT
0059	605-02278	CURB, REMOVE	240.00	LFT
0060	605-06090	CURB, INTEGRAL CONCRETE	240.00	LFT
0061	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	1284.40	SYS
0062	616-06405	RIPRAP, REVETMENT	32.00	TON
0063	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	524.00	SYS
0064	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0065	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0066	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0067	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0068	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS

0069	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0070	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0071	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0072	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0073	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0074	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0075	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0076	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0077	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0078	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0079	621-06574	SODDING	16.00	SYS
0080	628-09402	FIELD OFFICE, B	12.00	MOS
0081	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0082	702-51863	FIELD DRILLED HOLE IN CONCRETE	104.00	EACH
0083	702-92857	CONCRETE, C, SUBSTRUCTURE	8.60	CYS
0084	703-06029	REINFORCING BARS, EPOXY COATED	113740.00	LBS
0085	703-08247	EMBEDDED GALVANIC ANODE	86.00	EACH
0086	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	534.00	EACH
0087	704-51002	CONCRETE, C, SUPERSTRUCTURE	187.60	CYS
0088	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00	EACH
0089	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	4.00	EACH
0090	706-92612	RAILING, CONCRETE C, MODIFIED	21.00	LFT
0091	706-94947	RAILING, CONCRETE C, MODIFIED	8.80	CYS
0092	709-51821	SURFACE SEAL	1.00	LS
0093	709-51821	SURFACE SEAL	1.00	LS
0094	709-51821	SURFACE SEAL	1.00	LS
0095	709-51821	SURFACE SEAL	1.00	LS
0096	709-51821	SURFACE SEAL	1.00	LS
0097	710-09158	PATCHING CONCRETE STRUCTURES	20.00	SFT
0098	711-51864	DRILLED HOLE	128.00	EACH
0099	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS
0100	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS
0101	711-51878	JACKING AND SUPPORTING, GIRDERS	1.00	LS
0102	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	960.00	LFT
0103	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00	LS
0104	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	632.00	SYS
0105	718-52610	AGGREGATE FOR UNDERDRAINS	84.00	CYS

0106	720-01355	INLET, CLEAN EXISTING	12.00 EACH
0107	722-01066	HYDRODEMOLITION	3350.00 SYS
0108	722-12380	BRIDGE DECK OVERLAY, BUDGET	59889.00 DOL
0109	722-12382	TRANSVERSE GROOVING	4446.00 SYS
0110	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	858.00 SYS
0111	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	2492.00 SYS
0112	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	411.00 SFT
0113	724-11063	STRUCTURAL EXPANSION JOINT, SS, REPLACE	156.00 LFT
0114	724-12103	PRE-COMPRESSED FOAM JOINT	382.00 LFT
0115	726-11448	BEARING ASSEMBLY, EXPANSION, TYPE 1	4.00 EACH
0116	726-92406	BEARING ASSEMBLY ELASTOMERIC	12.00 EACH
0117	801-04308	ROAD CLOSURE SIGN ASSEMBLY	16.00 EACH
0118	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	36665.00 LFT
0119	801-06625	DETOUR ROUTE MARKER ASSEMBLY	103.00 EACH
0120	801-06640	CONSTRUCTION SIGN, A	141.00 EACH
0121	801-06645	CONSTRUCTION SIGN, B	29.00 EACH
0122	801-06710	FLASHING ARROW SIGN	240.00 DAY
0123	801-06775	MAINTAINING TRAFFIC	1.00 LS
0124	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00 EACH
0125	801-07118	BARRICADE, III-A	396.00 LFT
0126	801-07119	BARRICADE, III-B	288.00 LFT
0127	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	3462.00 LFT
0128	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00 EACH
0129	801-12031	TEMPORARY PORTABLE RUMBLE STRIPS	240.00 DAY
0130	802-04893	REFERENCE POST	3.00 EACH
0131	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	690.00 LFT
0132	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	690.00 LFT
0133	808-06716	LINE, REMOVE	4320.00 LFT
0134	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	1556.00 LFT
0135	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	3290.00 LFT
0136	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	3290.00 LFT
0137	808-10101	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 8 IN.	80.00 LFT
0138	808-12032	GROOVING FOR PAVEMENT MARKINGS	5888.00 LFT
0139	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	18.00 EACH

Call: 540
Contract: B -41205-A
Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY

Line			Quantity Unit	
Item No	Item Code	Description		
0140	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	3350.00	SYS

Call: 540
Contract: B -41205-A
Section No.: 3 SILICA FUME CONCRETE OVERLAY

Line			Quantity Unit	
Item No	Item Code	Description		
0141	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	3350.00	SYS

Call: 550

Contract: B -41398-B

Section No.: 1 BRIDGE DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0012	205-12108	STORMWATER MANAGEMENT BUDGET	5983.75 DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0014	306-08034	MILLING, ASPHALT, 1 1/2 IN.	405.00 SYS
0015	306-08041	MILLING, PCCP	11.00 SYS
0016	306-08043	MILLING, TRANSITION	268.00 SYS
0017	401-07353	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm	232.00 TON
0018	401-10258	JOINT ADHESIVE, SURFACE	1200.00 LFT
0019	401-11785	LIQUID ASPHALT SEALANT	1200.00 LFT
0020	402-12364	ASPHALTIC PLUG JOINT	101.00 LFT
0021	406-12347	ASPHALT EMULSION FOR TACK COAT	2.00 TON
0022	702-51863	FIELD DRILLED HOLE IN CONCRETE	9.00 EACH
0023	709-51821	SURFACE SEAL	1.00 LS
0024	710-09158	PATCHING CONCRETE STRUCTURES	45.00 SFT
0025	720-96995	CLEAN INLET	1.00 EACH
0026	722-12380	BRIDGE DECK OVERLAY, BUDGET	1000.00 DOL
0027	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	1087.00 SYS
0028	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	296.00 SFT
0029	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1973.00 SFT
0030	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	1.00 EACH
0031	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1200.00 LFT

0032	801-06640	CONSTRUCTION SIGN, A	17.00 EACH
0033	801-06645	CONSTRUCTION SIGN, B	1.00 EACH
0034	801-06710	FLASHING ARROW SIGN	18.00 DAY
0035	801-06775	MAINTAINING TRAFFIC	1.00 LS
0036	801-07118	BARRICADE, III-A	24.00 LFT
0037	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	760.00 LFT
0038	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00 EACH
0039	808-12032	GROOVING FOR PAVEMENT MARKINGS	500.00 LFT
0040	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	400.00 LFT
0041	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	400.00 LFT
0042	808-75061	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	100.00 LFT
0043	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	4.00 EACH
0044	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	4.00 EACH

Call: 560

Contract: B -41786-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	104-05404	DESIGN/BUILD	1.00	LS
0002	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0003	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	4.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	247.00	SYS
0013	202-62420	BRIDGE RAILING, REMOVE	465.00	LFT
0014	203-02070	BORROW	1.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	24500.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	206-51235	COFFERDAM	1.00	LS
0019	211-09268	STRUCTURE BACKFILL, TYPE 5	210.00	CYS
0020	301-12232	COMPACTED AGGREGATE NO. 5	1.00	CYS
0021	301-12234	COMPACTED AGGREGATE NO. 53	1.00	CYS
0022	302-07455	DENSE GRADED SUBBASE	42.00	CYS
0023	306-08043	MILLING, TRANSITION	1137.00	SYS
0024	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	54.00	TON
0025	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	42.00	TON
0026	401-10258	JOINT ADHESIVE, SURFACE	480.00	LFT
0027	401-11785	LIQUID ASPHALT SEALANT	480.00	LFT
0028	406-05521	ASPHALT FOR TACK COAT	1137.00	SYS
0029	601-02241	GUARDRAIL, REMOVE	560.00	LFT
0030	601-06035	GUARDRAIL, RESET	1.00	LFT
0031	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	212.50	LFT

0032	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00 EACH
0033	601-94689	GUARDRAIL, END TREATMENT, OS	4.00 EACH
0034	602-06729	BARRIER, DELINEATOR	12.00 EACH
0035	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	247.00 SYS
0036	616-05688	RIPRAP, CLASS 1	176.00 TON
0037	616-06405	RIPRAP, REVETMENT	540.00 TON
0038	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	998.00 SYS
0039	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0040	621-06559	MULCHED SEEDING R	1000.00 SYS
0041	628-09403	FIELD OFFICE, C	12.00 MOS
0042	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0043	702-51863	FIELD DRILLED HOLE IN CONCRETE	1440.00 EACH
0044	703-01540	THREADED TIE BAR ASSEMBLY	107.00 EACH
0045	703-06029	REINFORCING BARS, EPOXY COATED	29016.00 LBS
0046	706-09960	RAILING, CONCRETE FC	464.80 LFT
0047	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00 EACH
0048	709-51821	SURFACE SEAL	1.00 LS
0049	710-09158	PATCHING CONCRETE STRUCTURES	220.00 SFT
0050	715-05407	PIPE, END BENT DRAIN, 6 IN.	140.00 LFT
0051	722-01066	HYDRODEMOLITION	1418.00 SYS
0052	722-12380	BRIDGE DECK OVERLAY, BUDGET	26600.00 DOL
0053	722-12382	TRANSVERSE GROOVING	1665.00 SYS
0054	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	1033.00 SYS
0055	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	385.00 SYS
0056	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	600.00 SFT
0057	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1665.00 SYS
0058	722-51874	OVERLAY DAM	171.00 SFT
0059	724-12103	PRE-COMPRESSED FOAM JOINT	85.00 LFT
0060	732-11770	AGGREGATE FOR DRAINAGE FILL	11.00 CYS
0061	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00 EACH
0062	801-03291	CONSTRUCTION SIGN, D	1.00 EACH
0063	801-04308	ROAD CLOSURE SIGN ASSEMBLY	13.00 EACH
0064	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3280.00 LFT
0065	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00 LFT
0066	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00 EACH
0067	801-06640	CONSTRUCTION SIGN, A	31.00 EACH
0068	801-06645	CONSTRUCTION SIGN, B	6.00 EACH

0069	801-06775	MAINTAINING TRAFFIC	1.00	LS
0070	801-07118	BARRICADE, III-A	144.00	LFT
0071	801-07119	BARRICADE, III-B	72.00	LFT
0072	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	600.00	LFT
0073	801-12081	PORTABLE SIGNAL	1.00	LS
0074	808-06716	LINE, REMOVE	1920.00	LFT
0075	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1372.00	LFT
0076	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1372.00	LFT
0077	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	8.00	EACH

Call: 570

Contract: B -42167-A

Section No.: 1 SUBSTRUCTURE REPAIR AND REHABILITATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	601-06035	GUARDRAIL, RESET	20.00	LFT
0009	602-06729	BARRIER, DELINEATOR	4.00	EACH
0010	628-09403	FIELD OFFICE, C	6.00	MOS
0011	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0012	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0013	724-12103	PRE-COMPRESSED FOAM JOINT	130.00	LFT
0014	724-12461	CONCRETE FOR PATCHING STRUCTURAL EXPANSION JOINT	40.00	SFT
0015	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3090.00	LFT
0016	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	2340.00	LFT
0017	801-06640	CONSTRUCTION SIGN, A	91.00	EACH
0018	801-06710	FLASHING ARROW SIGN	35.00	DAY
0019	801-06775	MAINTAINING TRAFFIC	1.00	LS
0020	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	7.00	EACH
0021	801-12042	TRUCK MOUNTED ATTENUATOR	42.00	DAY

Call: 580

Contract: B -42274-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	96.00	SFT
0008	709-51821	SURFACE SEAL	1.00	LS
0009	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	104.00	SFT
0010	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	579.00	SYS
0011	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0012	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	8000.00	LFT
0013	801-06640	CONSTRUCTION SIGN, A	20.00	EACH
0014	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0015	801-06710	FLASHING ARROW SIGN	20.00	DAY
0016	801-06775	MAINTAINING TRAFFIC	1.00	LS
0017	801-07118	BARRICADE, III-A	120.00	LFT
0018	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0019	801-12042	TRUCK MOUNTED ATTENUATOR	20.00	DAY
0020	808-06716	LINE, REMOVE	413.00	LFT
0021	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	60.00	LFT
0022	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	212.00	LFT
0023	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	212.00	LFT

Call: 590

Contract: B -42351-B

Section No.: 1 SUBSTRUCTURE REPAIR AND REHABILITATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	202-51368	SLOPEWALL, REMOVE	214.00 SYS
0009	202-91385	INLET, REMOVE	1.00 EACH
0010	202-96133	PIPE, REMOVE	37.00 LFT
0011	202-98488	PIPE END SECTION, REMOVE	1.00 EACH
0012	203-02000	EXCAVATION, COMMON	163.00 CYS
0013	205-12108	STORMWATER MANAGEMENT BUDGET	5500.00 DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0015	211-02050	B BORROW	15.00 CYS
0016	303-01180	COMPACTED AGGREGATE NO. 53	10.00 TON
0017	616-06405	RIPRAP, REVETMENT	30.00 TON
0018	616-06451	RIPRAP, UNIFORM	15.00 TON
0019	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	70.00 SYS
0020	616-51367	SLOPEWALL, CONCRETE, 4 IN.	303.00 SYS
0021	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0022	621-02770	EROSION CONTROL BLANKET	159.00 SYS
0023	621-06560	MULCHED SEEDING U	159.00 SYS
0024	702-51863	FIELD DRILLED HOLE IN CONCRETE	48.00 EACH
0025	703-06029	REINFORCING BARS, EPOXY COATED	266.00 LBS
0026	715-09938	PIPE, BRIDGE DECK DRAIN SYSTEM	1.00 LS
0027	801-06640	CONSTRUCTION SIGN, A	26.00 EACH
0028	801-06775	MAINTAINING TRAFFIC	1.00 LS
0029	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	200.00 LFT

Call: 610

Contract: M -42875-A

Section No.: 1 ROADSIDE MAINTENANCE, TREE REMOVAL AND TRIMMING

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0005	201-01015	CLEARING AND GRUBBING	1.00	LS
0006	201-02250	TREE 10 IN., REMOVE	4.00	EACH
0007	201-02255	TREE 18 IN., REMOVE	11.00	EACH
0008	201-02260	TREE 30 IN., REMOVE	8.00	EACH
0009	201-02265	TREE 48 IN., REMOVE	8.00	EACH
0010	801-06640	CONSTRUCTION SIGN, A	6.00	EACH
0011	801-06710	FLASHING ARROW SIGN	31.00	DAY
0012	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 620

Contract: M -43104-A

Section No.: 1 GUARDRAIL, MAINTENANCE OR REPAIR

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0007	601-01128	GUARDRAIL, TRANSITION, TYPE WGB	1.00 EACH
0008	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00 EACH
0009	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00 EACH
0010	601-01700	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 1	2.00 EACH
0011	601-02211	GUARDRAIL POST, 8.5 LBS PER LFT, 7 FT LONG, GALVANIZED	350.00 EACH
0012	601-02800	GUARDRAIL, TRANSITION, TGT	1.00 EACH
0013	601-03452	EXCAVATION OF DAMAGED STEEL BEAM GUARDRAIL BURIED END SECTION LABOR ONLY	6.00 EACH
0014	601-03453	GUARDRAIL, CLAMP BAR, 7.125 IN., ALUMINUM	30.00 EACH
0015	601-03456	GUARDRAIL POST, WOOD TYPE W5	8.00 EACH
0016	601-03599	GUARDRAIL, THRIE BEAM, RAIL SECTION, 12 FT. 6 IN	2.00 EACH
0017	601-06035	GUARDRAIL, RESET	50.00 LFT
0018	601-06248	IMPACT ATTENUATOR, R2-W3, TL-3	1.00 EACH
0019	601-06273	GUARDRAIL, END TREATMENT, SKT-350	10.00 EACH
0020	601-06273	GUARDRAIL, END TREATMENT, SKT-350	10.00 EACH
0021	601-06774	COMBINATION ATTENUATING TERMINAL	1.00 EACH
0022	601-06854	GUARDRAIL, W-BEAM, NESTED	1.00 EACH
0023	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	1.00 EACH
0024	601-09238	HAND DIG GUARDRAIL POST HOLES	50.00 EACH
0025	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	250.00 LFT
0026	601-12287	GUARDRAIL, MGS, LONG SPAN, TYPE 1	1.00 EACH
0027	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	1.00 EACH
0028	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00 EACH
0029	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	1.00 EACH
0030	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	1.00 EACH
0031	601-12293	GUARDRAIL, MGS, STRUCTURE, TOP-MOUNTED POST	1.00 EACH

0032	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	1.00 EACH
0033	601-12404	MODIFIED MGS W-BEAM POST	1.00 EACH
0034	601-61320	CURVED SECTION, STEEL BEAM GUARDRAIL GALVANIZED, 12 GA.	1000.00 LFT
0035	601-61340	GUARDRAIL POST, 15.5 LBS PER FT., GALVANIZED, 6 FT. 3 IN. LONG	40.00 EACH
0036	601-61350	GUARDRAIL POST BRACKET, 15.5 LBS PER LFT., GALVANIZED, 1 FT. 2.25 IN.	80.00 EACH
0037	601-61370	GUARDRAIL POST BRACKET, 8.5 LBS PER LFT., GALVANIZED 1 FT. 2.25 IN.	125.00 EACH
0038	601-61380	GUARDRAIL TERMINAL SECTION, FLAT END, GALVANIZED	1.00 EACH
0039	601-61390	GUARDRAIL TERMINAL END SECTION, CURVED, SINGLE FACE, GALVANIZED	10.00 EACH
0040	601-61400	GUARDRAIL BURIED END, GALVANIZED, SINGLE FACE	1.00 EACH
0041	601-61550	GUARDRAIL TERMINAL END SECTION, ALUMINUM	5.00 EACH
0042	601-62070	GUARDRAIL, STEEL BEAM, GALVANIZED	25000.00 LFT
0043	601-62090	GUARDRAIL, STEEL BEAM, INSTALL	15.00 LFT
0044	601-62100	GUARDRAIL POST, STEEL, INSTALL	5.00 EACH
0045	601-62110	GUARDRAIL, CHANNEL, 6.7 LBS PER LFT., INSTALL	50.00 LFT
0046	601-62120	GUARDRAIL POST BRACKET, INSTALL	3.00 EACH
0047	601-62150	GUARDRAIL POST, 15.5 LBS PER LFT, GALVANIZED, 7 FT 0 IN. LONG	2.00 EACH
0048	601-62297	GUARDRAIL STANDARD TERMINAL CONNECTOR, MICHIGAN END SHOE	1.00 EACH
0049	601-62530	GUARDRAIL PIER CONNECTION, ES	1.00 EACH
0050	601-62540	GUARDRAIL POST, PLUMB	900.00 EACH
0051	601-62550	GUARDRAIL, TUBING, ELLIPTICAL, ALUMINUM	250.00 LFT
0052	601-62580	GUARDRAIL SPLICE BAR, ALUMINUM	25.00 EACH
0053	601-62630	GUARDRAIL POST, ALUMINUM, 6 FT. 3 IN.	1.00 EACH
0054	601-62640	GUARDRAIL POST, ALUMINUM, 5 FT. 3 IN.	5.00 EACH
0055	601-62680	GUARDRAIL TERMINAL SECTION, SINGLE FACE, BURIED END, ALUMINUM	1.00 EACH
0056	601-90382	GUARDRAIL POST, ALUMINUM, 7 FT.	1.00 EACH
0057	601-90389	GUARDRAIL TERMINAL SECTION, GALVANIZED, 11 IN.	1.00 EACH
0058	601-91198	GUARDRAIL POST, MODIFIED	4.00 EACH
0059	601-91504	GUARDRAIL POST, W1, 10 IN X 10 IN	1.00 EACH
0060	601-91505	GUARDRAIL POST, W2, 8 IN. X 8 IN.	5.00 EACH
0061	601-91510	GUARDRAIL POST, W3, 8 IN. X 8 IN.	5.00 EACH
0062	601-91511	GUARDRAIL POST, W4, 8 IN. X 8 IN.	5.00 EACH
0063	601-91542	GUARDRAIL BLOCKOUT, 6 IN. X 8 IN., B1	5.00 EACH
0064	601-91575	GUARDRAIL BLOCKOUT, 6 IN. X 8 IN., B2	5.00 EACH
0065	601-91576	GUARDRAIL BLOCKOUT, 6 IN. X 8 IN., B3	5.00 EACH
0066	601-91649	GUARDRAIL THRIE BEAM TRANSITION SECTION, GALVANIZED	8.00 EACH
0067	601-91653	GUARDRAIL THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	2.00 EACH
0068	601-93346	GUARDRAIL CONNECTOR, AS	5.00 EACH

0069	601-94689	GUARDRAIL, END TREATMENT, OS	20.00 EACH
0070	601-94690	GUARDRAIL, END TREATMENT, MS	8.00 EACH
0071	601-95342	GUARDRAIL SPLICE PLATE, C, GALVANIZED	4.00 EACH
0072	601-95972	GUARDRAIL POST (CRT), 8 IN X 6 IN TREATED LUMBER, 6 FT. 0 IN. LONG	15.00 EACH
0073	601-98636	GUARDRAIL CHANNEL, 10 kg PER m, GALVANIZED, 125 mm	100.00 LFT
0074	601-98637	GUARDRAIL BURIED END, TERMINAL CONNECTOR, GALVANIZED	1.00 EACH
0075	601-98638	GUARDRAIL SPLICE PLATE, ALUMINUM	1.00 EACH
0076	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	1500.00 LFT
0077	601-99108	GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN. SPACING	150.00 LFT
0078	601-99123	GUARDRAIL, TRANSITION, GP	1.00 EACH
0079	627-09327	CABLE BARRIER SYSTEM, TYPE TL-4	100.00 LFT
0080	627-09910	CABLE LINE POST LESS SOCKET, REPAIR	500.00 EACH
0081	627-09911	TERMINAL POST LESS SOCKET, REPAIR	16.00 EACH
0082	627-09912	CABLE RELEASE POST LESS SOCKET, REPAIR	1.00 EACH
0083	627-09913	CABLE SOCKET WITH CONCRETE, REPAIR	1.00 EACH
0084	627-09914	ANCHOR TERMINAL FITTING, REPAIR	8.00 EACH
0085	627-09915	CABLE SPLICE, REPAIR	1.00 EACH
0086	627-09916	RETENTION CABLE, REPAIR	4.00 EACH
0087	627-11647	CABLE BARRIER SYSTEM, TYPE TL-4 RESET	1000.00 LFT
0088	706-01515	BRIDGE BRACKET A, ALUMINUM	1.00 EACH
0089	706-05587	BRIDGE BARRIER RAIL BRACKET, CONCRETE, INSTALL	1.00 EACH
0090	706-06347	RAILING, STEEL CF-1	50.00 LFT
0091	706-62380	BRIDGE RAILING POST, 5A	3.00 EACH
0092	706-62390	BRIDGE RAILING POST, 6	1.00 EACH
0093	706-62400	BRIDGE RAILING POST, 7	1.00 EACH
0094	706-90672	BRIDGE RAILING POST, ALUMINUM, 5	5.00 EACH
0095	706-94133	RAILING, TUBE, GALVANIZED STEEL	1.00 LFT
0096	706-95431	BARRIER X CONCRETE BRIDGE RAILING BRACKET TYPE A	1.00 EACH
0097	706-95432	BARRIER X CONCRETE BRIDGE RAILING BRACKET TYPE B	1.00 EACH
0098	706-95433	BARRIER X CONCRETE BRIDGE RAILING BRACKET TYPE C	1.00 EACH
0099	706-98639	BRIDGE RAILING SPLICE BAR, ALUMINUM	1.00 EACH
0100	711-51823	EXPANSION ANCHOR 0.75 IN	1.00 EACH
0101	801-03290	CONSTRUCTION SIGN, C	4.00 EACH
0102	801-06775	MAINTAINING TRAFFIC	1.00 LS
0103	801-12042	TRUCK MOUNTED ATTENUATOR	72.00 DAY
0104	802-97573	ANGLE POST	1.00 EACH
0105	803-61430	BRIDGE BRACKET A GALVANIZED	1.00 EACH

0106	803-61440	BRIDGE BRACKET B GALVANIZED	1.00 EACH
------	-----------	-----------------------------	-----------

Call: 700

Contract: T -40341-A

Section No.: 1 SAFETY IMPROVEMENTS

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0009	202-02278	CURB, CONCRETE, REMOVE	1648.00 LFT
0010	202-52710	SIDEWALK CONCRETE, REMOVE	1175.00 SYS
0011	202-74035	SIGN, REMOVE	2.00 EACH
0012	202-91385	INLET, REMOVE	13.00 EACH
0013	202-94747	POST, REMOVE	1.00 EACH
0014	203-02000	EXCAVATION, COMMON	69.00 CYS
0015	203-02070	BORROW	34.00 CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	4620.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	211-09265	STRUCTURE BACKFILL, TYPE 2	40.00 CYS
0019	304-12625	HMA PATCHING FULL DEPTH TYPE C	104.00 TON
0020	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1734.00 SYS
0021	604-06070	SIDEWALK, CONCRETE	669.00 SYS
0022	604-08086	CURB RAMP, CONCRETE	537.00 SYS
0023	604-12083	DETECTABLE WARNING SURFACES	676.00 SYS
0024	605-06120	CURB, CONCRETE	1730.00 LFT
0025	610-07488	HMA FOR APPROACHES, TYPE C	145.00 TON
0026	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	1.00 EACH
0027	621-06575	SODDING, NURSERY	225.00 SYS
0028	628-09402	FIELD OFFICE, B	12.00 MOS
0029	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0030	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	133.00 LFT
0031	720-01355	INLET, CLEAN EXISTING	4.00 EACH

0032	720-03194	MANHOLE	1.00 EACH
0033	720-44000	CASTING, ADJUST TO GRADE	27.00 EACH
0034	720-44000	CASTING, ADJUST TO GRADE	12.00 EACH
0035	720-44015	CASTING, 2, FURNISH AND ADJUST TO GRADE	1.00 EACH
0036	720-45010	INLET, A3	3.00 EACH
0037	720-45015	INLET, A8	3.00 EACH
0038	720-45075	INLET, R13	3.00 EACH
0039	720-97896	INLET, A4	1.00 EACH
0040	801-06775	MAINTAINING TRAFFIC	1.00 LS
0041	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	244.00 LFT
0042	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	36.00 SFT
0043	802-91122	SIGN GROUND MOUNTED RESET	19.00 EACH
0044	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	166.00 LFT
0045	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	4.00 EACH
0046	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	4.00 EACH
0047	805-04133	SIGNAL POLE, PEDESTAL, 12FT	4.00 EACH
0048	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	4.00 EACH
0049	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	947.00 LFT
0050	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	947.00 LFT
0051	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	234.00 LFT
0052	808-05929	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 8 IN.	1170.00 LFT
0053	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	340.00 LFT
0054	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	446.00 LFT
0055	808-95933	CURB, PAINTING, YELLOW	280.00 LFT

Call: 710

Contract: T -40357-A

Section No.: 1 SAFETY REVISIONS

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0010	202-02240	PAVEMENT REMOVAL	98.00 SYS
0011	202-02278	CURB, CONCRETE, REMOVE	2802.00 LFT
0012	202-05545	REGULATED MATERIALS, DISPOSE, TYPE C	5.00 CYS
0013	202-05550	REGULATED MATERIALS, REMOVE, TYPE C	5.00 CYS
0014	202-05555	REGULATED MATERIALS, TRANSPORT, TYPE C	5.00 CYS
0015	202-05571	TESTING FOR WASTES	1.00 EACH
0016	202-52710	SIDEWALK CONCRETE, REMOVE	967.00 SYS
0017	203-02000	EXCAVATION, COMMON	11.00 CYS
0018	205-12108	STORMWATER MANAGEMENT BUDGET	14400.00 DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0020	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	149.00 TON
0021	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1208.00 SYS
0022	306-08041	MILLING, PCCP	189.00 SYS
0023	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0024	601-02241	GUARDRAIL, REMOVE	24.00 LFT
0025	601-03464	GUARDRAIL, STEEL CURVED TERMINAL END SECTION	2.00 EACH
0026	603-06065	FENCE, CHAIN LINK, RESET	46.00 LFT
0027	604-06070	SIDEWALK, CONCRETE	485.00 SYS
0028	604-08086	CURB RAMP, CONCRETE	810.00 SYS
0029	604-12083	DETECTABLE WARNING SURFACES	173.00 SYS
0030	605-06120	CURB, CONCRETE	1990.00 LFT
0031	605-06125	CURB, CONCRETE, MODIFIED	159.00 LFT

0032	605-52807	CURB AND GUTTER, COMBINED	61.00	LFT
0033	605-97937	CURB AND GUTTER, ROLL CURB	1005.00	LFT
0034	610-07713	PCCP FOR APPROACHES, 8 IN.	108.00	SYS
0035	610-08446	PCCP FOR APPROACHES, 6 IN.	13.00	SYS
0036	621-06567	WATER	1.00	KGAL
0037	621-06570	TOPSOIL	66.00	CYS
0038	621-06575	SODDING, NURSERY	176.00	SYS
0039	720-44000	CASTING, ADJUST TO GRADE	20.00	EACH
0040	720-44015	CASTING, 2, FURNISH AND ADJUST TO GRADE	3.00	EACH
0041	720-45005	INLET, A2	1.00	EACH
0042	801-06640	CONSTRUCTION SIGN, A	39.00	EACH
0043	801-06645	CONSTRUCTION SIGN, B	54.00	EACH
0044	801-06775	MAINTAINING TRAFFIC	1.00	LS
0045	802-07060	SIGN, SHEET, RELOCATE	40.00	EACH
0046	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	80.00	SFT
0047	805-11799	RECTANGULAR RAPID FLASHING BEACON	4.00	EACH
0048	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	184.00	LFT
0049	808-11698	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 27 IN.	77.00	LFT
0050	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	38.00	LFT

Call: 720

Contract: T -41038-A

Section No.: 1 TRAFFIC SIGNAL VISIBILITY IMPROVEMENTS

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	628-09403	FIELD OFFICE, C	6.00	MOS
0008	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0009	801-06640	CONSTRUCTION SIGN, A	132.00	EACH
0010	801-06775	MAINTAINING TRAFFIC	1.00	LS
0011	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	686.00	SFT
0012	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	209.00	SFT
0013	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	493.00	SFT
0014	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	15.00	EACH
0015	805-01842	HANDHOLE SIGNAL TYPE 1	1.00	EACH
0016	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	250.00	LFT
0017	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	136.00	EACH
0018	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	8.00	EACH
0019	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	10.00	EACH
0020	805-78415	SPAN, CATENARY, AND TETHER	58.00	EACH
0021	805-78420	DISCONNECT HANGER	58.00	EACH
0022	805-78445	SIGNAL SERVICE	15.00	EACH
0023	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	1375.00	LFT
0024	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	2119.00	LFT
0025	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	1897.00	LFT
0026	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	13665.00	LFT
0027	805-79020	TRAFFIC SIGNAL INSTALLATION	1.00	LS

Call: 730

Contract: T -41039-A

Section No.: 1 VISIBILITY IMPROVEMENT

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0006	628-09403	FIELD OFFICE, C	6.00	MOS
0007	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0008	801-06640	CONSTRUCTION SIGN, A	48.00	EACH
0009	801-06645	CONSTRUCTION SIGN, B	24.00	EACH
0010	801-06775	MAINTAINING TRAFFIC	1.00	LS
0011	802-04089	SIGN, SHEET, REMOVE	20.00	EACH
0012	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	130.00	LFT
0013	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	160.00	LFT
0014	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	17.00	EACH
0015	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	79.00	SFT
0016	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	372.00	SFT
0017	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	7.00	EACH
0018	805-06742	SOLAR POWERED FLASHING BEACON ASSEMBLY	5.00	EACH
0019	808-06716	LINE, REMOVE	100.00	LFT
0020	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	150.00	LFT
0021	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	400.00	LFT
0022	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	181.00	LFT
0023	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	12.00	EACH
0024	808-97643	BUZZ STRIPS	24.00	LFT

Call: 750

Contract: T -41796-A

Section No.: 1 TRAFFIC SIGNALS MODERNIZATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	202-02279	CURB AND GUTTER, REMOVE	233.00	LFT
0010	202-52710	SIDEWALK CONCRETE, REMOVE	40.00	SYS
0011	205-12108	STORMWATER MANAGEMENT BUDGET	2100.00	DOL
0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0013	304-12625	HMA PATCHING FULL DEPTH TYPE C	29.00	TON
0014	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0015	604-06070	SIDEWALK, CONCRETE	32.00	SYS
0016	604-08086	CURB RAMP, CONCRETE	106.00	SYS
0017	604-12083	DETECTABLE WARNING SURFACES	19.00	SYS
0018	605-06150	CURB AND GUTTER, C, CONCRETE	233.00	LFT
0019	621-06567	WATER	1.00	KGAL
0020	621-06575	SODDING, NURSERY	52.00	SYS
0021	628-09402	FIELD OFFICE, B	12.00	MOS
0022	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0023	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	130.00	LFT
0024	801-06640	CONSTRUCTION SIGN, A	8.00	EACH
0025	801-06645	CONSTRUCTION SIGN, B	14.00	EACH
0026	801-06710	FLASHING ARROW SIGN	30.00	DAY
0027	801-06775	MAINTAINING TRAFFIC	1.00	LS
0028	801-07118	BARRICADE, III-A	40.00	LFT
0029	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0030	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	225.00	SFT
0031	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	2.00	EACH

0032	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	7.00 EACH
0033	805-01830	CONFLICT MONITOR CHANGEOUT	1.00 EACH
0034	805-01842	HANDHOLE SIGNAL TYPE 1	4.00 EACH
0035	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	1.00 EACH
0036	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	16.00 EACH
0037	805-02445	CONTROLLER AND CABINET, P1	1.00 EACH
0038	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	4.00 EACH
0039	805-04602	CONTROLLER, REWIRE	1.00 EACH
0040	805-04782	VIDEO VEHICLE DETECTOR SYSTEM	8.00 EACH
0041	805-05405	SIGNAL POLE, PEDESTAL, 4FT	4.00 EACH
0042	805-11814	CONDUIT, HDPE, 2 IN. SCHEDULE 40	185.00 LFT
0043	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00 EACH
0044	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	15.00 EACH
0045	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	8.00 EACH
0046	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	1.00 EACH
0047	805-78415	SPAN, CATENARY, AND TETHER	8.00 EACH
0048	805-78420	DISCONNECT HANGER	8.00 EACH
0049	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	1073.00 LFT
0050	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	9351.00 LFT
0051	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00 EACH
0052	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	7.00 EACH
0053	808-06368	TRANSVERSE MARKING, REMOVE	50.00 LFT
0054	808-74815	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 12 IN.	50.00 LFT
0055	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	50.00 LFT

Call: 760

Contract: T -41798-A

Section No.: 1 TRAFFIC SIGNALS MODERNIZATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0010	202-02279	CURB AND GUTTER, REMOVE	1000.00 LFT
0011	202-52710	SIDEWALK CONCRETE, REMOVE	495.00 SYS
0012	205-12108	STORMWATER MANAGEMENT BUDGET	7132.10 DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0014	304-12625	HMA PATCHING FULL DEPTH TYPE C	183.80 TON
0015	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0016	604-06070	SIDEWALK, CONCRETE	81.00 SYS
0017	604-08086	CURB RAMP, CONCRETE	390.20 SYS
0018	604-12083	DETECTABLE WARNING SURFACES	69.20 SYS
0019	605-06150	CURB AND GUTTER, C, CONCRETE	900.30 LFT
0020	621-06567	WATER	0.50 kGAL
0021	621-06575	SODDING, NURSERY	117.80 SYS
0022	628-09402	FIELD OFFICE, B	12.00 MOS
0023	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0024	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	48.00 LFT
0025	720-44000	CASTING, ADJUST TO GRADE	1.00 EACH
0026	720-44296	INLET, CAP	3.00 EACH
0027	720-45010	INLET, A3	3.00 EACH
0028	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	130.00 LFT
0029	801-06640	CONSTRUCTION SIGN, A	50.00 EACH
0030	801-06645	CONSTRUCTION SIGN, B	55.00 EACH
0031	801-06710	FLASHING ARROW SIGN	90.00 DAY

0032	801-06775	MAINTAINING TRAFFIC	1.00	LS
0033	801-07118	BARRICADE, III-A	280.00	LFT
0034	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0035	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	120.00	LFT
0036	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	997.50	SFT
0037	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	12.00	SFT
0038	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	7.00	EACH
0039	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	11.00	EACH
0040	805-01830	CONFLICT MONITOR CHANGEOUT	6.00	EACH
0041	805-01842	HANDHOLE SIGNAL TYPE 1	7.00	EACH
0042	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	11.00	EACH
0043	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	38.00	EACH
0044	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	12.00	EACH
0045	805-04602	CONTROLLER, REWIRE	7.00	EACH
0046	805-04782	VIDEO VEHICLE DETECTOR SYSTEM	28.00	EACH
0047	805-07212	SPLICE KIT	7.00	EACH
0048	805-11814	CONDUIT, HDPE, 2 IN. SCHEDULE 40	210.00	LFT
0049	805-11817	PEDESTRIAN PUSH BUTTON, APS	52.00	EACH
0050	805-12650	SIGNAL POLE PEDESTAL 5 FT	8.00	EACH
0051	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	63.00	EACH
0052	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	16.00	EACH
0053	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	1.00	EACH
0054	805-78415	SPAN, CATENARY, AND TETHER	22.00	EACH
0055	805-78420	DISCONNECT HANGER	24.00	EACH
0056	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	2914.00	LFT
0057	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	16708.00	LFT
0058	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	11.00	EACH
0059	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	5.00	EACH
0060	808-06368	TRANSVERSE MARKING, REMOVE	900.00	LFT
0061	808-74815	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 12 IN.	600.00	LFT
0062	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	300.00	LFT

Call: 770

Contract: T -42566-A

Section No.: 1 NEW SIGNAL INSTALLATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0009	202-74035	SIGN, REMOVE	3.00 EACH
0010	202-74080	OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	1.00 EACH
0011	202-93741	GUARDRAIL, END TREATMENT, REMOVE	1.00 EACH
0012	203-02000	EXCAVATION, COMMON	429.00 CYS
0013	207-12498	SUBGRADE TREATMENT, TYPE ID	643.00 SYS
0014	303-01180	COMPACTED AGGREGATE NO. 53	152.00 TON
0015	304-12625	HMA PATCHING FULL DEPTH TYPE C	65.00 TON
0016	601-02241	GUARDRAIL, REMOVE	195.00 LFT
0017	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	43.75 LFT
0018	601-12282	GUARDRAIL, MGS W-BEAM, 3 FT 1.5 IN SPACING	115.67 LFT
0019	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	1.00 EACH
0020	601-94689	GUARDRAIL, END TREATMENT, OS	1.00 EACH
0021	605-06255	CENTER CURB, D CONCRETE	545.00 SYS
0022	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0023	621-06559	MULCHED SEEDING R	100.00 SYS
0024	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2925.00 LFT
0025	801-06640	CONSTRUCTION SIGN, A	11.00 EACH
0026	801-06645	CONSTRUCTION SIGN, B	3.00 EACH
0027	801-06710	FLASHING ARROW SIGN	30.00 DAY
0028	801-06775	MAINTAINING TRAFFIC	1.00 LS
0029	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	11.50 LFT
0030	802-07057	SIGN, PANEL, WITH LEGEND	320.00 SFT
0031	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	19.00 SFT

0032	802-12224	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, C	2.00 EACH
0033	802-76095	STRUCTURAL STEEL, BREAKAWAY	2085.00 LBS
0034	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00 EACH
0035	805-01842	HANDHOLE SIGNAL TYPE 1	6.00 EACH
0036	805-02445	CONTROLLER AND CABINET, P1	1.00 EACH
0037	805-08244	CELLULAR MODEM KIT	1.00 EACH
0038	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL	5.00 EACH
0039	805-11813	CONDUIT, PVC, 2 IN. SCHEDULE 80	1060.00 LFT
0040	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	6.00 EACH
0041	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	1.00 EACH
0042	805-78415	SPAN, CATENARY, AND TETHER	3.00 EACH
0043	805-78420	DISCONNECT HANGER	3.00 EACH
0044	805-78445	SIGNAL SERVICE	1.00 EACH
0045	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	35.00 LFT
0046	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	1490.00 LFT
0047	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	235.00 LFT
0048	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	30.00 LFT
0049	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	325.00 LFT
0050	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	1790.00 LFT
0051	805-78785	SIGNAL DETECTOR HOUSING	4.00 EACH
0052	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	485.00 LFT
0053	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00 EACH
0054	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	4.00 EACH
0055	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	250.00 LFT
0056	808-06716	LINE, REMOVE	465.00 LFT
0057	808-12032	GROOVING FOR PAVEMENT MARKINGS	3900.00 LFT
0058	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	2300.00 LFT
0059	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1350.00 LFT
0060	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	74.00 LFT
0061	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	4.00 EACH
0062	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	12.00 EACH
0063	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	12.00 EACH