

Schedule of Pay Items Letting Date October 7, 2020 Letting ID 201007

Call: 170

Contract: R -40312-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	203-02000	EXCAVATION, COMMON	1767.00 CYS
0012	203-02070	BORROW	92.00 CYS
0013	205-12108	STORMWATER MANAGEMENT BUDGET	6000.00 DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0015	205-12618	SWQCP PREPARATION	1.00 LS
0016	207-12635	SUBGRADE TREATMENT, TYPE IBC	4126.00 SYS
0017	211-09265	STRUCTURE BACKFILL, TYPE 2	190.00 CYS
0018	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	826.00 SYS
0019	301-12234	COMPACTED AGGREGATE NO. 53	1041.00 CYS
0020	306-08036	MILLING, ASPHALT, 2 IN.	545.00 SYS
0021	401-07352	QC/QA-HMA, 3, 76, SURFACE, 12.5 mm	383.00 TON
0022	401-07403	QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	486.00 TON
0023	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	488.00 TON
0024	401-10258	JOINT ADHESIVE, SURFACE	1332.00 LFT
0025	401-10259	JOINT ADHESIVE, INTERMEDIATE	1212.00 LFT
0026	401-11785	LIQUID ASPHALT SEALANT	1332.00 LFT
0027	406-05520	ASPHALT FOR TACK COAT	3.00 TON
0028	502-06999	PCCP, 8 IN.	225.00 SYS
0029	503-05240	D-1 CONTRACTION JOINT	100.00 LFT
0030	604-06070	SIDEWALK, CONCRETE	181.00 SYS
0031	604-08086	CURB RAMP, CONCRETE	134.00 SYS

0032	604-12083	DETECTABLE WARNING SURFACES	27.00	SYS
0033	605-06120	CURB, CONCRETE	164.00	LFT
0034	605-06140	CURB AND GUTTER, CONCRETE	874.00	LFT
0035	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	450.00	LFT
0036	605-06255	CENTER CURB, D CONCRETE	14.00	SYS
0037	605-97937	CURB AND GUTTER, ROLL CURB	253.00	LFT
0038	605-97937	CURB AND GUTTER, ROLL CURB	232.00	LFT
0039	615-06490	RIGHT-OF-WAY MARKER	11.00	EACH
0040	615-06505	MONUMENT, B	3.00	EACH
0041	615-06510	MONUMENT, C	4.00	EACH
0042	616-06405	RIPRAP, REVETMENT	11.00	TON
0043	616-11736	DECORATIVE STONE	43.00	TON
0044	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	22.00	SYS
0045	621-06567	WATER	7.00	KGAL
0046	621-06570	TOPSOIL	104.00	CYS
0047	621-06575	SODDING, NURSERY	1724.00	SYS
0048	622-05640	PLANT, DECIDUOUS SHRUB, 24 TO 36 IN.	14.00	EACH
0049	622-05651	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 TO 3.5 IN.	7.00	EACH
0050	628-09403	FIELD OFFICE, C	9.00	MOS
0051	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0052	628-11977	COMPUTER SYSTEM	1.00	EACH
0053	710-11640	MASONRY COLUMN	2.00	EACH
0054	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	708.00	LFT
0055	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	62.00	LFT
0056	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	356.00	LFT
0057	715-09064	VIDEO INSPECTION FOR PIPE	356.00	LFT
0058	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	770.00	LFT
0059	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	594.00	SYS
0060	718-52610	AGGREGATE FOR UNDERDRAINS	65.00	CYS
0061	720-03194	MANHOLE	1.00	EACH
0062	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0063	720-45030	INLET, E7	1.00	EACH
0064	720-45410	MANHOLE, C4	2.00	EACH
0065	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	4.00	EACH
0066	720-98174	INLET, B15	3.00	EACH
0067	720-98555	INLET, C15	3.00	EACH
0068	801-03290	CONSTRUCTION SIGN, C	4.00	EACH

0069	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00 EACH
0070	801-06625	DETOUR ROUTE MARKER ASSEMBLY	35.00 EACH
0071	801-06640	CONSTRUCTION SIGN, A	15.00 EACH
0072	801-06645	CONSTRUCTION SIGN, B	10.00 EACH
0073	801-06775	MAINTAINING TRAFFIC	1.00 LS
0074	801-07118	BARRICADE, III-A	156.00 LFT
0075	801-07119	BARRICADE, III-B	132.00 LFT
0076	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	246.00 LFT
0077	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	116.00 LFT
0078	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	4.00 EACH
0079	802-07060	SIGN, SHEET, RELOCATE	1.00 EACH
0080	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	133.84 SFT
0081	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	52.36 SFT
0082	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	21.00 SFT
0083	805-02445	CONTROLLER AND CABINET, P1	1.00 EACH
0084	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00 EACH
0085	807-02191	HANDHOLE LIGHTING	1.00 EACH
0086	807-02194	SERVICE POINT II MODIFIED	1.00 EACH
0087	807-02428	LIGHTING FOUNDATION, CONCRETE WITH GROUND 30 IN. X 30 IN. X 96 IN.	5.00 EACH
0088	807-03951	LIGHT POLE ORNAMENTAL	5.00 EACH
0089	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	175.00 LFT
0090	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	494.00 LFT
0091	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	200.00 LFT
0092	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	755.00 LFT
0093	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	92.00 LFT
0094	808-11698	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 27 IN.	69.00 LFT
0095	808-12032	GROOVING FOR PAVEMENT MARKINGS	2942.00 LFT
0096	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2095.00 LFT
0097	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	18.00 EACH