

Schedule of Pay Items Letting Date September 2, 2020 Letting ID 200902

Call: 221

Contract: R -43156-A

Section No.: 1 SMALL STRUCTURE, NEW

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	203-02000	EXCAVATION, COMMON	675.00 CYS
0012	205-12108	STORMWATER MANAGEMENT BUDGET	7938.00 DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0014	205-12618	SWQCP PREPARATION	1.00 LS
0015	207-12498	SUBGRADE TREATMENT, TYPE ID	534.00 SYS
0016	211-09265	STRUCTURE BACKFILL, TYPE 2	660.00 CYS
0017	301-12233	COMPACTED AGGREGATE NO. 8	40.00 CYS
0018	303-01180	COMPACTED AGGREGATE NO. 53	44.00 TON
0019	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	39.00 TON
0020	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	67.00 TON
0021	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	218.00 TON
0022	401-10258	JOINT ADHESIVE, SURFACE	300.00 LFT
0023	401-10259	JOINT ADHESIVE, INTERMEDIATE	300.00 LFT
0024	401-11785	LIQUID ASPHALT SEALANT	300.00 LFT
0025	406-05521	ASPHALT FOR TACK COAT	1441.00 SYS
0026	615-06490	RIGHT-OF-WAY MARKER	11.00 EACH
0027	615-06505	MONUMENT, B	2.00 EACH
0028	616-05688	RIPRAP, CLASS 1	86.00 TON
0029	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	110.00 SYS
0030	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0031	621-06559	MULCHED SEEDING R	1938.00 SYS

0032	621-06574	SODDING	99.00	SYS
0033	628-09402	FIELD OFFICE, B	8.00	MOS
0034	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0035	702-51015	CONCRETE, B, FOOTINGS	16.40	CYS
0036	702-93722	CONCRETE, C,	18.90	CYS
0037	703-06029	REINFORCING BARS, EPOXY COATED	3971.00	LBS
0038	715-05052	PIPE, TYPE 4, CIRCULAR, 12 IN.	44.00	LFT
0039	715-05141	PIPE, TYPE 1, CIRCULAR, 84 IN.	154.00	LFT
0040	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	68.00	LFT
0041	715-07150	CONCRETE ANCHOR, 84 IN.	1.00	EACH
0042	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0043	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0044	720-45410	MANHOLE, C4	1.00	EACH
0045	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0046	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	338.00	LFT
0047	801-06625	DETOUR ROUTE MARKER ASSEMBLY	50.00	EACH
0048	801-06640	CONSTRUCTION SIGN, A	8.00	EACH
0049	801-06775	MAINTAINING TRAFFIC	1.00	LS
0050	801-07118	BARRICADE, III-A	72.00	LFT
0051	801-07119	BARRICADE, III-B	48.00	LFT
0052	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	38.00	LFT
0053	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	300.00	LFT
0054	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.00	EACH
0055	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2.00	EACH