

**Schedule of Pav Items Letting Date August 11, 2021 Letting ID 210811**

Call: 120

Contract: R -38979-A

Section No.: 1            SMALL STRUCTURE REPLACEMENT

<b>Line</b>				
<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-96133	PIPE, REMOVE	18.00	LFT
0013	202-96133	PIPE, REMOVE	216.00	LFT
0014	203-02000	EXCAVATION, COMMON	545.00	CYS
0015	205-11626	PUMP AROUND	1.00	EACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	7250.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	206-51220	EXCAVATION, WET	78.00	CYS
0020	207-12498	SUBGRADE TREATMENT, TYPE ID	749.00	SYS
0021	211-09265	STRUCTURE BACKFILL, TYPE 2	25.00	CYS
0022	211-09268	STRUCTURE BACKFILL, TYPE 5	80.00	CYS
0023	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	173.00	SYS
0024	301-12232	COMPACTED AGGREGATE NO. 5	13.00	CYS
0025	301-12234	COMPACTED AGGREGATE NO. 53	88.00	CYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	39.00	TON
0027	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	10.00	TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	20.00	SYS
0029	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	76.00	TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	98.00	TON
0031	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	316.00	TON
0032	401-10258	JOINT ADHESIVE, SURFACE	546.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	546.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	546.00	LFT
0035	406-05520	ASPHALT FOR TACK COAT	1.00	TON

0036	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	1.00 EACH
0037	616-05689	RIPRAP, CLASS 2	197.00 TON
0038	616-06405	RIPRAP, REVETMENT	26.00 TON
0039	616-06405	RIPRAP, REVETMENT	79.00 TON
0040	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	110.00 SYS
0041	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	58.00 SYS
0042	621-02770	EROSION CONTROL BLANKET	440.00 SYS
0043	621-06559	MULCHED SEEDING R	440.00 SYS
0044	621-06567	WATER	1.00 KGAL
0045	621-06574	SODDING	52.00 SYS
0046	628-09401	FIELD OFFICE, A	4.00 MOS
0047	714-11682	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS 6 FT. X 4 FT.	92.00 LFT
0048	715-05841	CONCRETE ANCHOR, 60 IN.	1.00 EACH
0049	715-05908	PIPE EXTENSION, CIRCULAR, 60 IN.	18.00 LFT
0050	725-11288	PIPE LINER, CURED-IN-PLACE, 60"	173.00 LFT
0051	801-03291	CONSTRUCTION SIGN, D	4.00 EACH
0052	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00 EACH
0053	801-06625	DETOUR ROUTE MARKER ASSEMBLY	22.00 EACH
0054	801-06640	CONSTRUCTION SIGN, A	38.00 EACH
0055	801-06645	CONSTRUCTION SIGN, B	8.00 EACH
0056	801-06775	MAINTAINING TRAFFIC	1.00 LS
0057	801-07118	BARRICADE, III-A	60.00 LFT
0058	801-07119	BARRICADE, III-B	60.00 LFT
0059	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	339.00 LFT
0060	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	314.00 LFT

Call: 130

Contract: R -40285-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

<b>Line</b>			<b>Quantity Unit</b>
<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-02278	CURB, CONCRETE, REMOVE	489.00 LFT

0012	202-02279	CURB AND GUTTER, REMOVE	570.00	LFT
0013	202-51133	RAILING, REMOVE	211.00	LFT
0014	202-91385	INLET, REMOVE	5.00	EACH
0015	202-93999	SIGNAL POLE, REMOVE	2.00	EACH
0016	202-96133	PIPE, REMOVE	297.00	LFT
0017	203-02000	EXCAVATION, COMMON	2264.00	CYS
0018	203-02070	BORROW	10547.00	CYS
0019	203-07042	EMBANKMENT FOUNDATION SOILS TREATMENT	1000.00	SYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	19610.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	207-08264	SUBGRADE TREATMENT, TYPE II	78.00	SYS
0023	207-08266	SUBGRADE TREATMENT, TYPE III	1215.00	SYS
0024	207-12635	SUBGRADE TREATMENT, TYPE IBC	13227.00	SYS
0025	211-09264	STRUCTURE BACKFILL, TYPE 1	1795.00	CYS
0026	214-11796	GEOGRID, TYPE IB	78.00	SYS
0027	301-12234	COMPACTED AGGREGATE NO. 53	1730.00	CYS
0028	302-07455	DENSE GRADED SUBBASE	5.00	CYS
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	311.00	SYS
0030	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1082.00	TON
0031	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1358.00	TON
0032	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	1362.00	TON
0033	401-10258	JOINT ADHESIVE, SURFACE	4084.00	LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	3934.00	LFT
0035	401-11785	LIQUID ASPHALT SEALANT	4084.00	LFT
0036	401-12139	QC/QA-HMA, 4, 76, BASE, OG, 19.0 mm	1659.00	TON
0037	402-10084	HMA FOR TEMPORARY PAVEMENT, B	79.00	TON
0038	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0039	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
0040	502-11564	PCCP, 7 IN.	707.00	SYS
0041	601-02241	GUARDRAIL, REMOVE	231.00	LFT
0042	604-05528	HMA FOR SIDEWALK	219.00	TON
0043	604-06070	SIDEWALK, CONCRETE	254.00	SYS
0044	604-08086	CURB RAMP, CONCRETE	231.00	SYS
0045	604-12083	DETECTABLE WARNING SURFACES	36.00	SYS
0046	604-95344	HAND RAIL, PEDESTRIAN	117.00	LFT
0047	605-06120	CURB, CONCRETE	1761.00	LFT
0048	605-06140	CURB AND GUTTER, CONCRETE	866.00	LFT
0049	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	1438.00	LFT
0050	605-06255	CENTER CURB, D CONCRETE	103.00	SYS
0051	605-97937	CURB AND GUTTER, ROLL CURB	377.00	LFT
0052	610-09108	PCCP FOR APPROACHES, 9 IN.	56.00	SYS
0053	615-01469	MONUMENT SECTION CORNER INSTALL	2.00	EACH

0054	615-06490	RIGHT-OF-WAY MARKER	16.00 EACH
0055	615-06505	MONUMENT, B	2.00 EACH
0056	616-06405	RIPRAP, REVETMENT	303.00 TON
0057	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	560.00 SYS
0058	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0059	621-06545	FERTILIZER	1.00 TON
0060	621-06554	SEED MIXTURE U	179.00 LBS
0061	621-06565	MULCHING MATERIAL	2.00 TON
0062	621-06567	WATER	6.00 KGAL
0063	621-06574	SODDING	230.00 SYS
0064	621-06575	SODDING, NURSERY	1259.00 SYS
0065	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	538.00 LFT
0066	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	2025.00 LFT
0067	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	529.00 LFT
0068	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	443.00 LFT
0069	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	92.00 LFT
0070	715-09064	VIDEO INSPECTION FOR PIPE	1061.00 LFT
0071	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00 EACH
0072	715-46040	PIPE END SECTION, DIAMETER 36 IN.	1.00 EACH
0073	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	1614.00 SYS
0074	718-52610	AGGREGATE FOR UNDERDRAINS	161.00 CYS
0075	720-02367	MANHOLE, J10	1.00 EACH
0076	720-44296	INLET, CAP	1.00 EACH
0077	720-45030	INLET, E7	1.00 EACH
0078	720-45040	INLET, G7	1.00 EACH
0079	720-45045	INLET, J10	1.00 EACH
0080	720-45055	INLET, M10	7.00 EACH
0081	720-45410	MANHOLE, C4	2.00 EACH
0082	720-94208	MANHOLE, C10	5.00 EACH
0083	720-94612	MANHOLE, K4	1.00 EACH
0084	720-95422	MANHOLE, J4	1.00 EACH
0085	720-98174	INLET, B15	2.00 EACH
0086	720-98555	INLET, C15	2.00 EACH
0087	801-03290	CONSTRUCTION SIGN, C	4.00 EACH
0088	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00 EACH
0089	801-06625	DETOUR ROUTE MARKER ASSEMBLY	54.00 EACH
0090	801-06640	CONSTRUCTION SIGN, A	12.00 EACH
0091	801-06775	MAINTAINING TRAFFIC	1.00 LS
0092	801-07118	BARRICADE, III-A	360.00 LFT
0093	801-07119	BARRICADE, III-B	156.00 LFT
0094	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	595.00 LFT
0095	802-05705	SIGN POST, SQUARE TYPE 2 UNREINFORCED ANCHOR BASE	74.00 LFT

0096	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	3.00 EACH
0097	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	6.00 EACH
0098	802-07060	SIGN, SHEET, RELOCATE	5.00 EACH
0099	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	311.00 SFT
0100	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	167.00 SFT
0101	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	10.00 SFT
0102	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00 EACH
0103	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00 LS
0104	807-02191	HANDHOLE LIGHTING	8.00 EACH
0105	807-02428	LIGHTING FOUNDATION, CONCRETE WITH GROUND 30 IN. X 30 IN. X 96 IN.	8.00 EACH
0106	807-03934	LIGHT STRUCTURE, REMOVE	1.00 EACH
0107	807-03951	LIGHT POLE ORNAMENTAL	8.00 EACH
0108	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	357.00 LFT
0109	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	860.00 LFT
0110	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	8.00 EACH
0111	807-12343	CABLE, POLE CIRCUIT, XHHW, NO 10 COPPER, STRANDED, 1/C	224.00 LFT
0112	807-86810	SERVICE POINT, II	1.00 EACH
0113	807-86910	CONNECTOR KIT, UNFUSED	8.00 EACH
0114	807-86915	CONNECTOR KIT, FUSED	12.00 EACH
0115	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.00 EACH
0116	807-86935	INSULATION LINK, WATERPROOFED	44.00 EACH
0117	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	280.00 LFT
0118	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	117.00 LFT
0119	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2289.00 LFT
0120	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	112.00 LFT
0121	808-11478	LINE, THERMOPLASTIC, DOTTED, WHITE, 8 IN.	104.00 LFT
0122	808-11650	LINE, THERMOPLASTIC, DOTTED, WHITE, 6 IN.	88.00 LFT
0123	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	778.00 LFT
0124	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2763.00 LFT
0125	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	16.00 EACH

Call: 140

Contract: R -40286-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

**Line**

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL

0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	203-02000	EXCAVATION, COMMON	6176.00	CYS
0012	203-02070	BORROW	2723.00	CYS
0013	205-12108	STORMWATER MANAGEMENT BUDGET	38800.00	DOL
0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0015	205-12618	SWQCP PREPARATION	1.00	LS
0016	207-08264	SUBGRADE TREATMENT, TYPE II	161.00	SYS
0017	207-12635	SUBGRADE TREATMENT, TYPE IBC	11854.00	SYS
0018	211-09264	STRUCTURE BACKFILL, TYPE 1	4068.00	CYS
0019	215-12637	CHEMICAL MODIFICATION, SOILS, CEMENT	2931.00	SYS
0020	301-12234	COMPACTED AGGREGATE NO. 53	1086.00	CYS
0021	302-07455	DENSE GRADED SUBBASE	27.00	CYS
0022	303-07449	COMPACTED AGGREGATE NO. 73	118.00	TON
0023	304-12625	HMA PATCHING FULL DEPTH TYPE C	7.00	TON
0024	306-08036	MILLING, ASPHALT, 2 IN.	492.00	SYS
0025	401-07345	QC/QA-HMA, 2, 70, SURFACE, 12.5 mm	1045.00	TON
0026	401-07397	QC/QA-HMA, 2, 70, INTERMEDIATE, 19.0 mm	1236.00	TON
0027	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	1731.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	1523.00	LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	1523.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	1523.00	LFT
0031	406-05520	ASPHALT FOR TACK COAT	5.00	TON
0032	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
0033	502-06457	PCCP, 9 IN.	339.00	SYS
0034	502-06627	PCCP, 6 IN.	512.00	SYS
0035	503-05240	D-1 CONTRACTION JOINT	252.00	LFT
0036	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	1.00	EACH
0037	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	182.00	LFT
0038	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00	EACH
0039	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0040	604-05528	HMA FOR SIDEWALK	121.00	TON
0041	604-08086	CURB RAMP, CONCRETE	258.00	SYS
0042	604-12083	DETECTABLE WARNING SURFACES	36.00	SYS
0043	605-06120	CURB, CONCRETE	1735.00	LFT
0044	605-06140	CURB AND GUTTER, CONCRETE	3854.00	LFT
0045	605-06160	CURB AND GUTTER, B, CONCRETE, MODIFIED	308.00	LFT
0046	605-06255	CENTER CURB, D CONCRETE	11.00	SYS
0047	605-90726	CURB, CONCRETE, DEPRESSED	80.00	LFT
0048	605-96305	CURB AND GUTTER, CONCRETE DEPRESSED	80.00	LFT

0049	610-08446	PCCP FOR APPROACHES, 6 IN.	161.00	SYS
0050	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00	EACH
0051	615-06490	RIGHT-OF-WAY MARKER	34.00	EACH
0052	615-06505	MONUMENT, B	15.00	EACH
0053	615-06510	MONUMENT, C	2.00	EACH
0054	615-06515	MONUMENT, D	10.00	EACH
0055	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0056	616-06405	RIPRAP, REVETMENT	36.00	TON
0057	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	18.00	SYS
0058	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0059	621-06545	FERTILIZER	1.00	TON
0060	621-06554	SEED MIXTURE U	440.00	LBS
0061	621-06565	MULCHING MATERIAL	5.00	TON
0062	621-06567	WATER	2.00	KGAL
0063	621-06575	SODDING, NURSERY	479.00	SYS
0064	628-09403	FIELD OFFICE, C	12.00	MOS
0065	628-11977	COMPUTER SYSTEM	1.00	EACH
0066	629-12029	PLANT GROWTH LAYER	10718.00	SYS
0067	715-05032	PIPE, TYPE 2, CIRCULAR, 15 IN.	590.00	LFT
0068	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	4043.00	LFT
0069	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1572.00	LFT
0070	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	419.00	LFT
0071	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	350.00	LFT
0072	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	1487.00	LFT
0073	715-09064	VIDEO INSPECTION FOR PIPE	4418.00	LFT
0074	715-09475	STORMWATER QUALITY STRUCTURE	1.00	EACH
0075	715-46030	PIPE END SECTION, DIAMETER 30 IN.	2.00	EACH
0076	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	4043.00	LFT
0077	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	4345.00	SYS
0078	718-52610	AGGREGATE FOR UNDERDRAINS	537.00	CYS
0079	720-01092	MANHOLE, J15 MODIFIED	2.00	EACH
0080	720-45030	INLET, E7	3.00	EACH
0081	720-45410	MANHOLE, C4	17.00	EACH
0082	720-92884	MANHOLE, K4 MODIFIED	2.00	EACH
0083	720-94612	MANHOLE, K4	3.00	EACH
0084	720-95422	MANHOLE, J4	10.00	EACH
0085	720-98174	INLET, B15	20.00	EACH
0086	720-98555	INLET, C15	24.00	EACH
0087	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0088	801-06625	DETOUR ROUTE MARKER ASSEMBLY	45.00	EACH
0089	801-06640	CONSTRUCTION SIGN, A	35.00	EACH
0090	801-06645	CONSTRUCTION SIGN, B	4.00	EACH

0091	801-06775	MAINTAINING TRAFFIC	1.00	LS
0092	801-07118	BARRICADE, III-A	48.00	LFT
0093	801-07119	BARRICADE, III-B	48.00	LFT
0094	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	265.00	LFT
0095	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	288.00	LFT
0096	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	143.00	SFT
0097	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	108.00	SFT
0098	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	12.00	SFT
0099	807-02191	HANDHOLE LIGHTING	6.00	EACH
0100	807-02428	LIGHTING FOUNDATION, CONCRETE WITH GROUND 30 IN. X 30 IN. X 96 IN.	12.00	EACH
0101	807-03950	LUMINAIRE ORNAMENTAL	12.00	EACH
0102	807-03951	LIGHT POLE ORNAMENTAL	12.00	EACH
0103	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	248.00	LFT
0104	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1136.00	LFT
0105	807-86810	SERVICE POINT, II	1.00	EACH
0106	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	912.00	LFT
0107	807-86910	CONNECTOR KIT, UNFUSED	12.00	EACH
0108	807-86915	CONNECTOR KIT, FUSED	12.00	EACH
0109	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	28.00	EACH
0110	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	8.00	EACH
0111	807-86930	INSULATION LINK, NON-WATERPROOFED	20.00	EACH
0112	807-86935	INSULATION LINK, WATERPROOFED	24.00	EACH
0113	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	480.00	LFT
0114	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	188.00	LFT
0115	808-12032	GROOVING FOR PAVEMENT MARKINGS	4373.00	LFT
0116	808-12148	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 36 IN.	73.00	LFT
0117	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	234.00	LFT
0118	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4139.00	LFT
0119	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	12.00	EACH
0120	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	45.00	EACH

Call: 150

Contract: R -40475-A

Section No.: 1 ASPHALT RESURFACE

**Line**

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL



0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	207-12498	SUBGRADE TREATMENT, TYPE ID	1037.00	SYS
0011	214-12456	GEOTEXTILE FOR PAVEMENT, INTERLAYER	14349.00	SYS
0012	303-01180	COMPACTED AGGREGATE NO. 53	81.00	TON
0013	304-12625	HMA PATCHING FULL DEPTH TYPE C	571.00	TON
0014	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	1.00	TON
0015	306-08038	MILLING, ASPHALT, 4 IN.	14349.00	SYS
0016	306-08432	MILLING, APPROACH	3014.00	SYS
0017	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1185.00	TON
0018	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1974.00	TON
0019	401-10258	JOINT ADHESIVE, SURFACE	11500.00	LFT
0020	401-10259	JOINT ADHESIVE, INTERMEDIATE	11500.00	LFT
0021	401-11785	LIQUID ASPHALT SEALANT	11500.00	LFT
0022	406-05520	ASPHALT FOR TACK COAT	10.00	TON
0023	604-06070	SIDEWALK, CONCRETE	102.00	SYS
0024	604-08086	CURB RAMP, CONCRETE	89.00	SYS
0025	604-12083	DETECTABLE WARNING SURFACES	11.00	SYS
0026	605-06120	CURB, CONCRETE	5.00	LFT
0027	610-07488	HMA FOR APPROACHES, TYPE C	664.00	TON
0028	720-44000	CASTING, ADJUST TO GRADE	5.00	EACH
0029	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	578.00	LFT
0030	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	578.00	LFT
0031	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	72.00	LFT
0032	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	72.00	LFT
0033	801-06640	CONSTRUCTION SIGN, A	29.00	EACH
0034	801-06645	CONSTRUCTION SIGN, B	20.00	EACH
0035	801-06775	MAINTAINING TRAFFIC	1.00	LS
0036	801-07118	BARRICADE, III-A	84.00	LFT
0037	801-12324	LAW ENFORCEMENT OFFICER	60.00	HRS
0038	801-92448	CONSTRUCTION SIGNS MOBILE	540.00	DAY
0039	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	12.00	LFT
0040	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	2.00	EACH
0041	802-97428	SIGN POST, TUBULAR	12.00	LFT
0042	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0043	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	9305.00	LFT
0044	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	5736.00	LFT
0045	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	1210.00	LFT
0046	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	72.00	LFT
0047	808-10064	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT ADA ACCESIBLE SYMBOL	1.00	EACH
0048	808-10094	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 12 IN.	815.00	LFT

0049	808-12032	GROOVING FOR PAVEMENT MARKINGS	16251.00	LFT
0050	808-12753	TRANSVERSE MARKING, MULTI-COMPONENT, PARKING LINE, WHITE 4 IN.	603.00	LFT
0051	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	528.00	LFT
0052	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	18.00	EACH

Call: 160

Contract: R -40565-A

Section No.: 1 ASPHALT RESURFACE

**Line**

<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02279	CURB AND GUTTER, REMOVE	1336.00	LFT
0014	202-86946	HANDHOLE, REMOVE	4.00	EACH
0015	202-90277	DETECTOR HOUSING, REMOVE	8.00	EACH
0016	202-93615	CONCRETE, REMOVE	867.00	SYS
0017	203-02070	BORROW	21.00	CYS
0018	205-12108	STORMWATER MANAGEMENT BUDGET	2475.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	1331.00	TON
0021	306-08034	MILLING, ASPHALT, 1 1/2 IN.	23746.00	SYS
0022	306-08432	MILLING, APPROACH	2821.00	SYS
0023	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1960.00	TON
0024	401-10258	JOINT ADHESIVE, SURFACE	11560.00	LFT
0025	401-11785	LIQUID ASPHALT SEALANT	11560.00	LFT
0026	406-05520	ASPHALT FOR TACK COAT	8.00	TON
0027	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.00	TON
0028	604-06070	SIDEWALK, CONCRETE	288.00	SYS
0029	604-08086	CURB RAMP, CONCRETE	515.00	SYS
0030	604-12083	DETECTABLE WARNING SURFACES	69.00	SYS
0031	604-95344	HAND RAIL, PEDESTRIAN	15.00	LFT
0032	605-02278	CURB, REMOVE	94.00	LFT

0033	605-06120	CURB, CONCRETE	50.00	LFT
0034	605-06140	CURB AND GUTTER, CONCRETE	1469.00	LFT
0035	610-07488	HMA FOR APPROACHES, TYPE C	233.00	TON
0036	615-06490	RIGHT-OF-WAY MARKER	20.00	EACH
0037	615-06520	MONUMENT, RE-ESTABLISH	2.00	EACH
0038	621-06575	SODDING, NURSERY	258.00	SYS
0039	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0040	628-12683	FIELD OFFICE, D	12.00	MOS
0041	702-51005	CONCRETE, A, SUBSTRUCTURE	0.60	CYS
0042	702-51863	FIELD DRILLED HOLE IN CONCRETE	6.00	EACH
0043	703-06029	REINFORCING BARS, EPOXY COATED	122.00	LBS
0044	720-44000	CASTING, ADJUST TO GRADE	11.00	EACH
0045	720-44000	CASTING, ADJUST TO GRADE	4.00	EACH
0046	720-44055	CASTING, 10, FURNISH AND ADJUST TO GRADE	3.00	EACH
0047	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	6.00	EACH
0048	720-98136	FIRE HYDRANT, RESET	2.00	EACH
0049	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2940.00	LFT
0050	801-06640	CONSTRUCTION SIGN, A	46.00	EACH
0051	801-06645	CONSTRUCTION SIGN, B	98.00	EACH
0052	801-06775	MAINTAINING TRAFFIC	1.00	LS
0053	801-07118	BARRICADE, III-A	96.00	LFT
0054	801-12042	TRUCK MOUNTED ATTENUATOR	40.00	DAY
0055	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	73.00	SFT
0056	802-91122	SIGN GROUND MOUNTED RESET	6.00	EACH
0057	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0058	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0059	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00	EACH
0060	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	14.00	EACH
0061	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0062	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	11.00	EACH
0063	805-11744	HANDHOLE SIGNAL TYPE 2	9.00	EACH
0064	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	1412.00	LFT
0065	805-11817	PEDESTRIAN PUSH BUTTON, APS	14.00	EACH
0066	805-12016	UNINTERRUPTIBLE POWER SUPPLY	1.00	EACH
0067	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	8.00	EACH
0068	805-78415	SPAN, CATENARY, AND TETHER	4.00	EACH
0069	805-78420	DISCONNECT HANGER	4.00	EACH
0070	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	51.00	LFT
0071	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	5752.00	LFT
0072	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	1231.00	LFT
0073	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	2007.00	LFT
0074	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	1113.00	LFT

0075	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	1673.00	LFT
0076	805-78785	SIGNAL DETECTOR HOUSING	13.00	EACH
0077	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1856.00	LFT
0078	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0079	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	4.00	EACH
0080	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	11.00	EACH
0081	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0082	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	707.00	LFT
0083	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	10182.00	LFT
0084	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	1945.00	LFT
0085	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	521.00	LFT
0086	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	23.00	EACH
0087	808-10056	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 6 IN.	2239.00	LFT
0088	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	27.00	EACH
0089	808-10099	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 24 IN.	128.00	LFT
0090	808-12032	GROOVING FOR PAVEMENT MARKINGS	12834.00	LFT

Call: 170

Contract: R -40601-A

Section No.: 1            SMALL STRUCTURE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0012	202-91385	INLET, REMOVE	1.00	EACH
	0013	202-92607	SIGN POST, CHANNEL, REMOVE	5.00	EACH
	0014	203-02000	EXCAVATION, COMMON	864.00	CYS
	0015	203-02070	BORROW	15.00	CYS
	0016	205-12108	STORMWATER MANAGEMENT BUDGET	11585.00	DOL
	0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0018	207-09935	SUBGRADE TREATMENT, TYPE IC	2072.00	SYS
	0019	207-12498	SUBGRADE TREATMENT, TYPE ID	525.00	SYS
	0020	211-09264	STRUCTURE BACKFILL, TYPE 1	65.00	CYS

0021	211-09265	STRUCTURE BACKFILL, TYPE 2	3.00	CYS
0022	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	1146.00	SYS
0023	301-12231	COMPACTED AGGREGATE NO. 2	12.00	CYS
0024	301-12232	COMPACTED AGGREGATE NO. 5	183.00	CYS
0025	301-12234	COMPACTED AGGREGATE NO. 53	12.00	CYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	331.00	TON
0027	306-08043	MILLING, TRANSITION	214.00	SYS
0028	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	62.00	TON
0029	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	156.00	TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	92.00	TON
0031	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	259.00	TON
0032	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1020.00	TON
0033	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	169.00	TON
0034	401-10258	JOINT ADHESIVE, SURFACE	2777.00	LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	2697.00	LFT
0036	401-11785	LIQUID ASPHALT SEALANT	2777.00	LFT
0037	406-05521	ASPHALT FOR TACK COAT	5072.00	SYS
0038	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0039	615-06505	MONUMENT, B	2.00	EACH
0040	616-05688	RIPRAP, CLASS 1	64.00	TON
0041	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	64.00	SYS
0042	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0043	621-06559	MULCHED SEEDING R	648.00	SYS
0044	621-06567	WATER	1.00	KGAL
0045	621-06574	SODDING	40.00	SYS
0046	715-05595	PIPE EXTENSION, CIRCULAR, 15 IN.	12.00	LFT
0047	715-08171	PIPE, TYPE 1, DEFORMED, MIN. AREA 12.9 SFT	54.00	LFT
0048	715-11576	SAFETY METAL END SECTION, 4:1, MIN AREA 12.9 SFT	2.00	EACH
0049	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	153.00	SYS
0050	720-45069	INLET, P12	1.00	EACH
0051	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0052	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5073.00	LFT
0053	801-06625	DETOUR ROUTE MARKER ASSEMBLY	26.00	EACH
0054	801-06640	CONSTRUCTION SIGN, A	64.00	EACH
0055	801-06645	CONSTRUCTION SIGN, B	12.00	EACH
0056	801-06710	FLASHING ARROW SIGN	60.00	DAY
0057	801-06775	MAINTAINING TRAFFIC	1.00	LS
0058	801-07118	BARRICADE, III-A	108.00	LFT
0059	801-07119	BARRICADE, III-B	72.00	LFT
0060	802-04089	SIGN, SHEET, REMOVE	5.00	EACH
0061	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	66.00	LFT
0062	802-07060	SIGN, SHEET, RELOCATE	4.00	EACH

0063	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	19.00	SFT
0064	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	59.00	SFT
0065	802-76055	SIGN POST, A	30.00	LFT
0066	804-06725	DELINEATOR WITH POST, D1	2.00	EACH
0067	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	110.00	LFT
0068	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	260.00	LFT
0069	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1005.00	LFT
0070	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	605.00	LFT
0071	808-11776	TRANSVERSE MARKING, MULTI-COMPONENT, YIELD LINE, WHITE, 24 IN.	89.00	LFT
0072	808-12032	GROOVING FOR PAVEMENT MARKINGS	1610.00	LFT
0073	808-75035	LINE, PAINT, SOLID, WHITE, 24 IN.	14.00	LFT

Call: 180

Contract: R -41143-A

Section No.: 1 ADA SIDEWALK AND RAMP CONSTRUCTION

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	205-12108	STORMWATER MANAGEMENT BUDGET	2400.00	DOL
	0009	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0010	207-08264	SUBGRADE TREATMENT, TYPE II	104.10	SYS
	0011	604-06070	SIDEWALK, CONCRETE	721.00	SYS
	0012	604-08086	CURB RAMP, CONCRETE	61.70	SYS
	0013	604-12083	DETECTABLE WARNING SURFACES	12.80	SYS
	0014	610-08446	PCCP FOR APPROACHES, 6 IN.	104.10	SYS
	0015	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	1.00	EACH
	0016	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
	0017	621-06560	MULCHED SEEDING U	389.80	SYS
	0018	801-06640	CONSTRUCTION SIGN, A	3.00	EACH
	0019	801-06645	CONSTRUCTION SIGN, B	96.00	EACH
	0020	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0021	801-07118	BARRICADE, III-A	144.00	LFT
	0022	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	40.50	LFT
	0023	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
	0024	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	24.00	SFT

Call: 190

Contract: R -41799-A

Section No.: 1

BIKE/PEDESTRIAN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	2.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	202-02278	CURB, CONCRETE, REMOVE	1088.00	LFT
0012	202-52710	SIDEWALK CONCRETE, REMOVE	570.00	SYS
0013	203-02000	EXCAVATION, COMMON	227.00	CYS
0014	306-08034	MILLING, ASPHALT, 1 1/2 IN.	605.00	SYS
0015	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	49.00	TON
0016	604-06070	SIDEWALK, CONCRETE	621.00	SYS
0017	604-07092	BED COURSE MATERIAL	454.00	TON
0018	604-08086	CURB RAMP, CONCRETE	314.00	SYS
0019	604-12083	DETECTABLE WARNING SURFACES	39.00	SYS
0020	605-06120	CURB, CONCRETE	32.00	LFT
0021	605-06140	CURB AND GUTTER, CONCRETE	1185.00	LFT
0022	621-06575	SODDING, NURSERY	115.00	SYS
0023	628-09403	FIELD OFFICE, C	6.00	MOS
0024	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0025	720-07309	TRENCH DRAIN	122.00	LFT
0026	720-11721	CASTING TRENCH DRAIN	122.00	LFT
0027	720-44000	CASTING, ADJUST TO GRADE	11.00	EACH
0028	720-44025	CASTING, 4, FURNISH AND ADJUST TO GRADE	2.00	EACH
0029	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0030	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3760.00	LFT
0031	801-06625	DETOUR ROUTE MARKER ASSEMBLY	8.00	EACH
0032	801-06640	CONSTRUCTION SIGN, A	13.00	EACH
0033	801-06645	CONSTRUCTION SIGN, B	26.00	EACH
0034	801-06710	FLASHING ARROW SIGN	30.00	DAY
0035	801-06775	MAINTAINING TRAFFIC	1.00	LS
0036	801-07118	BARRICADE, III-A	72.00	LFT
0037	801-07119	BARRICADE, III-B	216.00	LFT

0038	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	16.00	SFT
0039	802-91122	SIGN GROUND MOUNTED RESET	3.00	EACH
0040	805-01842	HANDHOLE SIGNAL TYPE 1	1.00	EACH
0041	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	22.00	EACH
0042	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	14.00	EACH
0043	805-05405	SIGNAL POLE, PEDESTAL, 4FT	15.00	EACH
0044	805-06595	CONDUIT, PVC, 2 IN.	148.00	LFT
0045	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	22.00	EACH
0046	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	148.00	LFT
0047	808-06716	LINE, REMOVE	1400.00	LFT
0048	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	200.00	LFT
0049	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	960.00	LFT

Call: 200

Contract: R -42114-A

Section No.: 1                      SMALL STRUCTURE PIPE LINING

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	4.00	EACH
	0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0004	109-08360	CONTRACT LIENS	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	201-01015	CLEARING AND GRUBBING	1.00	LS
	0010	203-02055	EMBANKMENT	42.00	CYS
	0011	205-12108	STORMWATER MANAGEMENT BUDGET	10000.00	DOL
	0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0013	205-12618	SWQCP PREPARATION	1.00	LS
	0014	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	10.00	EACH
	0015	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	50.00	CYS
	0016	616-05688	RIPRAP, CLASS 1	40.00	TON
	0017	616-06405	RIPRAP, REVETMENT	24.00	TON
	0018	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	102.00	SYS
	0019	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
	0020	621-02770	EROSION CONTROL BLANKET	225.00	SYS
	0021	621-06559	MULCHED SEEDING R	350.00	SYS
	0022	621-09815	ARTICULATED CONCRETE BLOCK	70.00	SYS
	0023	702-51863	FIELD DRILLED HOLE IN CONCRETE	10.00	EACH
	0024	715-06691	CONCRETE ANCHOR, 96 IN.	2.00	EACH



0025	715-11775	PIPE EXTENSION, CIRCULAR, 96 IN.	10.00	LFT
0026	715-12757	PIPE END SECTION, DIA 96 IN.	1.00	EACH
0027	715-95325	INVERT, CONCRETE PAVED	167.00	LFT
0028	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	1725.00	LFT
0029	801-06640	CONSTRUCTION SIGN, A	8.00	EACH
0030	801-06775	MAINTAINING TRAFFIC	1.00	LS
0031	801-07119	BARRICADE, III-B	20.00	LFT
0032	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH

Call: 210

Contract: R -42124-A

Section No.: 1 PCCP CLEANING AND SEALING JOINTS

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02278	CURB, CONCRETE, REMOVE	190.00	LFT
0014	202-52710	SIDEWALK CONCRETE, REMOVE	573.00	SYS
0015	202-74035	SIGN, REMOVE	1.00	EACH
0016	203-02000	EXCAVATION, COMMON	317.00	CYS
0017	203-02070	BORROW	8.00	CYS
0018	205-12108	STORMWATER MANAGEMENT BUDGET	1.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	512.00	SYS
0021	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	512.00	SYS
0022	302-07455	DENSE GRADED SUBBASE	86.00	CYS
0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	4499.00	SYS
0024	306-08043	MILLING, TRANSITION	15200.00	SYS
0025	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	895.00	TON
0026	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	307.00	TON
0027	401-10258	JOINT ADHESIVE, SURFACE	7055.00	LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	1434.00	LFT

0029	401-11785	LIQUID ASPHALT SEALANT	7055.00	LFT
0030	406-05521	ASPHALT FOR TACK COAT	17488.00	SYS
0031	503-03489	RETROFITTED TIE BARS	382.00	EACH
0032	503-05240	D-1 CONTRACTION JOINT	168.00	LFT
0033	506-06333	PCCP PATCHING, FULL DEPTH	528.00	SYS
0034	507-07482	CRACKS IN PCCP, ROUT AND SEAL	450.00	LFT
0035	509-12191	JOINT REPAIR, PARTIAL DEPTH	1054.00	SFT
0036	509-12192	JOINT REPAIR, BOTTOM-HALF	100.00	SFT
0037	510-12756	SME PENETRATING SEALER FOR PCC JOINTS	599648.00	LFT
0038	604-06070	SIDEWALK, CONCRETE	495.00	SYS
0039	604-08086	CURB RAMP, CONCRETE	428.00	SYS
0040	604-12083	DETECTABLE WARNING SURFACES	67.00	SYS
0041	605-06120	CURB, CONCRETE	225.00	LFT
0042	610-07487	HMA FOR APPROACHES, TYPE B	371.00	TON
0043	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0044	621-06560	MULCHED SEEDING U	613.00	SYS
0045	621-06567	WATER	2.00	KGAL
0046	621-06575	SODDING, NURSERY	148.00	SYS
0047	628-09403	FIELD OFFICE, C	18.00	MOS
0048	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0049	702-51005	CONCRETE, A, SUBSTRUCTURE	2.00	CYS
0050	702-51015	CONCRETE, B, FOOTINGS	2.00	CYS
0051	703-06028	REINFORCING BARS	255.00	LBS
0052	720-44000	CASTING, ADJUST TO GRADE	14.00	EACH
0053	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00	LS
0054	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	118.00	LFT
0055	801-06640	CONSTRUCTION SIGN, A	59.00	EACH
0056	801-06645	CONSTRUCTION SIGN, B	61.00	EACH
0057	801-06710	FLASHING ARROW SIGN	300.00	DAY
0058	801-06735	TUBULAR MARKER, PERMANENT	28.00	EACH
0059	801-06775	MAINTAINING TRAFFIC	1.00	LS
0060	801-07118	BARRICADE, III-A	48.00	LFT
0061	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	590.00	LFT
0062	801-09087	TEMPORARY PAVEMENT MARKING, REMOVABLE, 12 IN.	2569.00	LFT
0063	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0064	801-11990	TEMPORARY CURB RAMP	6.00	EACH
0065	801-12042	TRUCK MOUNTED ATTENUATOR	120.00	DAY
0066	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	32.00	SYS
0067	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	10.00	LFT
0068	802-07060	SIGN, SHEET, RELOCATE	1.00	EACH
0069	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	60.00	SFT
0070	802-74050	SIGN, OVERHEAD, REMOVE	5.00	EACH

0071	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0072	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	8.00	EACH
0073	805-05698	SIGNAL POLE FOUNDATION, 30 IN. X 30 IN. X 84 IN.	8.00	EACH
0074	805-06595	CONDUIT, PVC, 2 IN.	196.00	LFT
0075	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00	EACH
0076	805-12650	SIGNAL POLE PEDESTAL 5 FT	7.00	EACH
0077	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	8.00	EACH
0078	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	1.00	EACH
0079	805-78415	SPAN, CATENARY, AND TETHER	4.00	EACH
0080	805-78420	DISCONNECT HANGER	4.00	EACH
0081	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	1544.00	LFT
0082	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	431.00	LFT
0083	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	400.00	LFT
0084	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	320.00	LFT
0085	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	69.00	LFT
0086	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	15.00	LFT
0087	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.00	EACH
0088	805-93067	CONTROLLER CABINET, P	1.00	EACH
0089	808-06368	TRANSVERSE MARKING, REMOVE	981.00	LFT
0090	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	28058.00	LFT
0091	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	10933.00	LFT
0092	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	130667.00	LFT
0093	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	115493.00	LFT
0094	808-06723	PAVEMENT MESSAGE MARKING, PAINT, LANE INDICATION ARROW	65.00	EACH
0095	808-06724	PAVEMENT MESSAGE MARKING, PAINT, ONLY	13.00	EACH
0096	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	583.00	LFT
0097	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0098	808-12186	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, 12 IN.	830.00	LFT
0099	808-75078	TRANSVERSE MARKING, PAINT, CROSSHATCH LINE, YELLOW, 12 IN.	781.00	LFT
0100	808-75140	PAVEMENT MESSAGE MARKING, PAINT, R X R	4.00	EACH
0101	808-75994	PRISMATIC REFLECTOR	50.00	EACH
0102	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	119.00	EACH
0103	809-06114	ANTENNA	1.00	EACH

Call: 220

Contract: R -42137-A

Section No.: 1 ASPHALT RESURFACE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL

0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-91385	INLET, REMOVE	7.00	EACH
0013	202-93615	CONCRETE, REMOVE	25.00	SYS
0014	202-96133	PIPE, REMOVE	47.00	LFT
0015	202-98488	PIPE END SECTION, REMOVE	4.00	EACH
0016	205-11626	PUMP AROUND	2.00	EACH
0017	205-12108	STORMWATER MANAGEMENT BUDGET	1160.00	DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	205-12618	SWQCP PREPARATION	1.00	LS
0020	207-12498	SUBGRADE TREATMENT, TYPE ID	3195.00	SYS
0021	211-09264	STRUCTURE BACKFILL, TYPE 1	6.00	CYS
0022	211-09268	STRUCTURE BACKFILL, TYPE 5	22.00	CYS
0023	304-12623	HMA PATCHING FULL DEPTH TYPE B	1809.00	TON
0024	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	212.00	TON
0025	304-12627	HMA PATCHING FULL DEPTH TYPE D	722.00	TON
0026	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	1135.00	TON
0027	306-08036	MILLING, ASPHALT, 2 IN.	333476.00	SYS
0028	306-08432	MILLING, APPROACH	432.00	SYS
0029	401-11785	LIQUID ASPHALT SEALANT	187580.00	LFT
0030	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0031	406-05520	ASPHALT FOR TACK COAT	91.00	TON
0032	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	5.00	TON
0033	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	18.00	TON
0034	410-09530	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm - SMA	36683.00	TON
0035	410-12466	VOID REDUCING ASPHALT MEMBRANE FOR SMA	234479.00	LFT
0036	412-09355	FOG SEAL	93790.00	SYS
0037	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	187580.00	LFT
0038	610-07487	HMA FOR APPROACHES, TYPE B	48.00	TON
0039	616-06405	RIPRAP, REVETMENT	20.00	TON
0040	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	30.00	SYS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0042	621-06559	MULCHED SEEDING R	2626.00	SYS
0043	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0044	628-12683	FIELD OFFICE, D	20.00	MOS
0045	715-03475	SAFETY METAL END SECTION, 4:1, DIA 15 IN.	4.00	EACH

0046	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	32.00	LFT
0047	716-07631	PIPE INSTALLATION, TRENCHLESS, 15 IN.	674.00	LFT
0048	720-45065	INLET, N12	2.00	EACH
0049	720-45070	INLET, P12A	5.00	EACH
0050	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0051	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	375160.00	LFT
0052	801-06204	TEMPORARY PAVEMENT MARKING, 5 IN.	18762.00	LFT
0053	801-06640	CONSTRUCTION SIGN, A	28.00	EACH
0054	801-06710	FLASHING ARROW SIGN	80.00	DAY
0055	801-06775	MAINTAINING TRAFFIC	1.00	LS
0056	801-12042	TRUCK MOUNTED ATTENUATOR	80.00	DAY
0057	801-12324	LAW ENFORCEMENT OFFICER	160.00	HRS
0058	808-06702	LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	23451.00	LFT
0059	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	93790.00	LFT
0060	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0061	808-12032	GROOVING FOR PAVEMENT MARKINGS	211031.00	LFT
0062	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	93790.00	LFT
0063	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1176.00	EACH
0064	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	1176.00	EACH

Call: 230

Contract: R -42138-A

Section No.: 1 PCCP CLEANING AND SEALING JOINTS

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
	0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	205-12108	STORMWATER MANAGEMENT BUDGET	300.00	DOL
	0010	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0011	205-12618	SWQCP PREPARATION	1.00	LS
	0012	207-12498	SUBGRADE TREATMENT, TYPE ID	261.00	SYS
	0013	302-06464	SUBBASE FOR PCCP	66.00	CYS
	0014	303-01180	COMPACTED AGGREGATE NO. 53	366.00	TON
	0015	503-03489	RETROFITTED TIE BARS	20.00	EACH
	0016	503-05240	D-1 CONTRACTION JOINT	140.00	LFT
	0017	506-06333	PCCP PATCHING, FULL DEPTH	261.00	SYS

0018	506-06334	PCCP PATCHING, PARTIAL DEPTH	6.00	SYS
0019	507-08271	JOINTS IN PCCP, FILLED	105157.00	LFT
0020	601-06035	GUARDRAIL, RESET	175.00	LFT
0021	616-06451	RIPRAP, UNIFORM	209.00	TON
0022	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	425.00	SYS
0023	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0024	621-06559	MULCHED SEEDING R	238.00	SYS
0025	628-09403	FIELD OFFICE, C	10.00	MOS
0026	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0027	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0028	801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.00	EACH
0029	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2118.00	LFT
0030	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	2570.00	LFT
0031	801-06625	DETOUR ROUTE MARKER ASSEMBLY	47.00	EACH
0032	801-06640	CONSTRUCTION SIGN, A	36.00	EACH
0033	801-06710	FLASHING ARROW SIGN	40.00	DAY
0034	801-06775	MAINTAINING TRAFFIC	1.00	LS
0035	801-07119	BARRICADE, III-B	45.00	LFT
0036	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	625.00	LFT
0037	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	1.00	EACH
0038	801-12042	TRUCK MOUNTED ATTENUATOR	40.00	DAY
0039	801-12324	LAW ENFORCEMENT OFFICER	40.00	HRS
0040	808-06716	LINE, REMOVE	1675.00	LFT
0041	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1575.00	LFT
0042	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	100.00	LFT
0043	808-75994	PRISMATIC REFLECTOR	660.00	EACH
0044	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	78.00	EACH

Call: 240

Contract: R -43118-A

Section No.: 1 IDIQ, PAVEMENT PATCHING

Line	Item No	Item Code	Description	Quantity	Unit
	0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0002	109-08360	CONTRACT LIENS	1.00	DOL
	0003	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	225000.00	DOL
	0009	201-02245	TREE 6 IN., REMOVE	50.00	EACH

0010	201-02250	TREE 10 IN., REMOVE	50.00 EACH
0011	201-02255	TREE 18 IN., REMOVE	25.00 EACH
0012	201-02260	TREE 30 IN., REMOVE	15.00 EACH
0013	201-02265	TREE 48 IN., REMOVE	5.00 EACH
0014	201-02270	TREE 60 IN., REMOVE	2.00 EACH
0015	203-08607	LINEAR GRADING	1000.00 LFT
0016	207-08268	SUBGRADE TREATMENT, TYPE IV	200.00 SYS
0017	207-12498	SUBGRADE TREATMENT, TYPE ID	200.00 SYS
0018	302-06464	SUBBASE FOR PCCP	50.00 CYS
0019	303-01180	COMPACTED AGGREGATE NO. 53	100.00 TON
0020	303-07449	COMPACTED AGGREGATE NO. 73	100.00 TON
0021	304-12625	HMA PATCHING FULL DEPTH TYPE C	400.00 TON
0022	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	200.00 TON
0023	304-12627	HMA PATCHING FULL DEPTH TYPE D	1000.00 TON
0024	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	500.00 TON
0025	306-08036	MILLING, ASPHALT, 2 IN.	4000.00 SYS
0026	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	200.00 TON
0027	401-07353	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm	200.00 TON
0028	401-10258	JOINT ADHESIVE, SURFACE	1500.00 LFT
0029	401-11785	LIQUID ASPHALT SEALANT	1500.00 LFT
0030	406-05520	ASPHALT FOR TACK COAT	5.00 TON
0031	503-03489	RETROFITTED TIE BARS	75.00 EACH
0032	503-05240	D-1 CONTRACTION JOINT	108.00 LFT
0033	506-06333	PCCP PATCHING, FULL DEPTH	200.00 SYS
0034	506-06334	PCCP PATCHING, PARTIAL DEPTH	50.00 SYS
0035	507-07480	PROFILING, PCCP	200.00 SYS
0036	507-08272	JOINTS IN PCCP, SAW AND SEAL	500.00 LFT
0037	509-12191	JOINT REPAIR, PARTIAL DEPTH	300.00 SFT
0038	509-12192	JOINT REPAIR, BOTTOM-HALF	50.00 SFT
0039	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	20.00 EACH
0040	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2500.00 LFT
0041	801-06640	CONSTRUCTION SIGN, A	150.00 EACH
0042	801-06645	CONSTRUCTION SIGN, B	25.00 EACH
0043	801-06710	FLASHING ARROW SIGN	30.00 DAY
0044	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00 EACH
0045	801-12440	MAINTAINING TRAFFIC, IDIQ	225000.00 DOL
0046	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	1000.00 LFT
0047	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	1000.00 LFT
0048	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	5000.00 LFT
0049	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1000.00 LFT
0050	808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	250.00 LFT
0051	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	15.00 EACH

Call: 280

Contract: R -43814-A

Section No.: 1 DEMOLITION, REMOVE BUILDINGS, FOUNDATIONS

<b>Line</b>			<b>Quantity Unit</b>	
<b>Item No</b>	<b>Item Code</b>	<b>Description</b>		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	202-02240	PAVEMENT REMOVAL	43.00	SYS
0010	202-02278	CURB, CONCRETE, REMOVE	2853.00	LFT
0011	202-02279	CURB AND GUTTER, REMOVE	131.00	LFT
0012	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00	LS
0013	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00	LS
0014	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00	LS
0015	202-52710	SIDEWALK CONCRETE, REMOVE	848.00	SYS
0016	202-74035	SIGN, REMOVE	1.00	EACH
0017	202-91385	INLET, REMOVE	4.00	EACH
0018	202-93047	MANHOLE, REMOVE	5.00	EACH
0019	202-96133	PIPE, REMOVE	455.00	LFT
0020	203-02000	EXCAVATION, COMMON	5830.00	CYS
0021	203-02070	BORROW	7287.00	CYS
0022	205-12108	STORMWATER MANAGEMENT BUDGET	41258.00	DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0024	205-12618	SWQCP PREPARATION	1.00	LS
0025	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0026	621-06554	SEED MIXTURE U	1088.00	LBS
0027	621-06565	MULCHING MATERIAL	12.00	TON
0028	621-06570	TOPSOIL	1421.00	CYS
0029	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 310

Contract: B -30285-A

Section No.: 1 BRIDGE REPLACEMENT

<b>Line</b>			<b>Quantity Unit</b>	
<b>Item No</b>	<b>Item Code</b>	<b>Description</b>		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS



0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	2650.00	SYS
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0014	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0015	203-02020	EXCAVATION, UNCLASSIFIED	1475.00	CYS
0016	203-02070	BORROW	3965.00	CYS
0017	203-51223	EXCAVATION, WATERWAY	509.00	CYS
0018	205-12108	STORMWATER MANAGEMENT BUDGET	31302.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	205-12618	SWQCP PREPARATION	1.00	LS
0021	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	610.00	CYS
0022	206-51235	COFFERDAM	1.00	LS
0023	206-93520	TEMPORARY SHEET PILING	488.00	SFT
0024	207-12498	SUBGRADE TREATMENT, TYPE ID	4216.00	SYS
0025	211-06467	AGGREGATE FOR END BENT BACKFILL	104.00	CYS
0026	211-09265	STRUCTURE BACKFILL, TYPE 2	16.00	CYS
0027	214-12236	GEOTEXTILE FOR PAVEMENT TYPE 1A	21.00	SYS
0028	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	412.00	SYS
0029	302-06464	SUBBASE FOR PCCP	104.00	CYS
0030	303-01180	COMPACTED AGGREGATE NO. 53	407.00	TON
0031	306-08034	MILLING, ASPHALT, 1 1/2 IN.	478.00	SYS
0032	306-08043	MILLING, TRANSITION	586.00	SYS
0033	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	385.00	TON
0034	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	520.00	TON
0035	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1642.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	4015.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	2980.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	4015.00	LFT
0039	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0040	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.00	TON
0041	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	1.00	EACH
0042	601-02241	GUARDRAIL, REMOVE	800.00	LFT
0043	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	169.00	LFT

0044	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	8.00 EACH
0045	601-94689	GUARDRAIL, END TREATMENT, OS	7.00 EACH
0046	602-06729	BARRIER, DELINEATOR	16.00 EACH
0047	603-06040	FENCE, FARM FIELD, 47 IN.	245.00 LFT
0048	603-91748	FENCE GATE, FARM FIELD, 47 IN. X 16 FT	1.00 EACH
0049	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	424.00 SYS
0050	615-06490	RIGHT-OF-WAY MARKER	15.00 EACH
0051	615-06505	MONUMENT, B	5.00 EACH
0052	616-05688	RIPRAP, CLASS 1	1361.00 TON
0053	616-06405	RIPRAP, REVETMENT	227.00 TON
0054	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	2314.00 SYS
0055	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00 EACH
0056	621-02770	EROSION CONTROL BLANKET	4675.00 SYS
0057	621-03909	SEED MIXTURE, NATIVE	48.00 LBS
0058	621-06559	MULCHED SEEDING R	2394.00 SYS
0059	621-06567	WATER	3.00 KGAL
0060	621-06574	SODDING	227.00 SYS
0061	621-98038	MULCH HARDWOOD SHREDDED BARK	77.00 CYS
0062	622-52436	SIGN, DO NOT MOW OR SPRAY	40.00 EACH
0063	622-91786	SEEDLING	309.00 EACH
0064	628-09403	FIELD OFFICE, C	14.00 MOS
0065	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0066	629-12029	PLANT GROWTH LAYER	5140.00 SYS
0067	701-02938	CORED HOLE IN ROCK, 24 IN	108.00 LFT
0068	701-06011	DYNAMIC PILE LOAD TEST	4.00 EACH
0069	701-09557	TEST PILE, DYNAMIC, PRODUCTION	182.00 LFT
0070	701-09559	TEST PILE, DYNAMIC, RESTRIKE	4.00 EACH
0071	701-09739	PILE SHOE, HP 12 X 53	18.00 EACH
0072	701-51195	PILE, STEEL H HP 12 X 53	1136.00 LFT
0073	702-92857	CONCRETE, C, SUBSTRUCTURE	90.40 CYS
0074	703-06029	REINFORCING BARS, EPOXY COATED	128916.00 LBS
0075	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	948.00 EACH
0076	704-51002	CONCRETE, C, SUPERSTRUCTURE	331.00 CYS
0077	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00 EACH
0078	706-51020	RAILING, CONCRETE C	37.80 CYS
0079	707-09865	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 49 IN.	1372.00 LFT
0080	709-51821	SURFACE SEAL	1.00 LS
0081	709-51821	SURFACE SEAL	1.00 LS
0082	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	80.00 LFT
0083	715-05407	PIPE, END BENT DRAIN, 6 IN.	256.00 LFT
0084	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00 EACH
0085	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	240.00 SYS

0086	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00 EACH
0087	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	8712.00 LFT
0088	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3188.00 LFT
0089	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	96.00 LFT
0090	801-06640	CONSTRUCTION SIGN, A	48.00 EACH
0091	801-06775	MAINTAINING TRAFFIC	1.00 LS
0092	801-07118	BARRICADE, III-A	32.00 LFT
0093	801-07119	BARRICADE, III-B	32.00 LFT
0094	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1610.00 LFT
0095	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	230.00 LFT
0096	801-12081	PORTABLE SIGNAL	1.00 LS
0097	801-97643	TEMPORARY BUZZ STRIPS	576.00 LFT
0098	802-04893	REFERENCE POST	2.00 EACH
0099	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	7.50 LFT
0100	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	16.00 LFT
0101	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	18.00 SFT
0102	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	456.00 LFT
0103	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	3642.00 LFT
0104	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1123.00 LFT
0105	808-06716	LINE, REMOVE	4307.00 LFT
0106	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	14.00 EACH
0107	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	14.00 EACH

Call: 320

Contract: B -40416-A

Section No.: 1 BRIDGE DECK REPLACEMENT

**Line**

<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	<b>Quantity</b>	<b>Unit</b>
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-03135	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	10.00	SFT
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0013	203-02000	EXCAVATION, COMMON	50.00	CYS
0014	203-02070	BORROW	390.00	CYS

0015	205-12108	STORMWATER MANAGEMENT BUDGET	8353.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	207-12498	SUBGRADE TREATMENT, TYPE ID	732.00	SYS
0019	211-06467	AGGREGATE FOR END BENT BACKFILL	1.00	CYS
0020	211-09264	STRUCTURE BACKFILL, TYPE 1	7.00	CYS
0021	211-09266	STRUCTURE BACKFILL, TYPE 3	160.00	CYS
0022	302-06464	SUBBASE FOR PCCP	84.00	CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	122.00	TON
0024	303-07449	COMPACTED AGGREGATE NO. 73	11.00	TON
0025	304-07493	WIDENING WITH HMA, TYPE B	147.00	TON
0026	306-11872	MILLING, PROFILE	582.00	SYS
0027	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	65.00	TON
0028	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	12.00	TON
0029	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	16.00	TON
0030	401-10258	JOINT ADHESIVE, SURFACE	665.00	LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	30.00	LFT
0032	401-11785	LIQUID ASPHALT SEALANT	665.00	LFT
0033	406-05521	ASPHALT FOR TACK COAT	1524.00	SYS
0034	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	0.50	TON
0035	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	2.00	EACH
0036	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	1.00	EACH
0037	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0038	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	50.00	LFT
0039	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0040	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0041	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	31.25	LFT
0042	602-06729	BARRIER, DELINEATOR	8.00	EACH
0043	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	206.20	SYS
0044	616-06405	RIPRAP, REVETMENT	220.00	TON
0045	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	327.00	SYS
0046	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0047	621-02770	EROSION CONTROL BLANKET	863.00	SYS
0048	621-06559	MULCHED SEEDING R	355.00	SYS
0049	621-06565	MULCHING MATERIAL	0.50	TON
0050	621-06567	WATER	0.50	KGAL
0051	621-06574	SODDING	44.00	SYS
0052	621-12612	SEED MIXTURE FLOODPLAIN	13.00	LBS
0053	628-09403	FIELD OFFICE, C	17.00	MOS
0054	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0055	702-51015	CONCRETE, B, FOOTINGS	6.00	CYS
0056	702-51863	FIELD DRILLED HOLE IN CONCRETE	114.00	EACH

0057	702-92857	CONCRETE, C, SUBSTRUCTURE	19.00	CYS
0058	703-06029	REINFORCING BARS, EPOXY COATED	28649.00	LBS
0059	704-51002	CONCRETE, C, SUPERSTRUCTURE	33.00	CYS
0060	706-09960	RAILING, CONCRETE FC	107.40	LFT
0061	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0062	709-51821	SURFACE SEAL	1.00	LS
0063	710-09158	PATCHING CONCRETE STRUCTURES	15.00	SFT
0064	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	30.00	LFT
0065	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	EACH
0066	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	14.00	SYS
0067	724-12103	PRE-COMPRESSED FOAM JOINT	82.00	LFT
0068	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0069	801-06625	DETOUR ROUTE MARKER ASSEMBLY	16.00	EACH
0070	801-06640	CONSTRUCTION SIGN, A	28.00	EACH
0071	801-06645	CONSTRUCTION SIGN, B	12.00	EACH
0072	801-06775	MAINTAINING TRAFFIC	1.00	LS
0073	801-07118	BARRICADE, III-A	48.00	LFT
0074	801-07119	BARRICADE, III-B	72.00	LFT
0075	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	6.00	EACH
0076	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	15.50	LFT
0077	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	6.25	SFT
0078	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0079	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	637.00	LFT
0080	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	564.00	LFT
0081	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	8.00	EACH

Call: 330

Contract: B -40443-A

Section No.: 1 BRIDGE DECK OVERLAY

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS

0012	202-02240	PAVEMENT REMOVAL	215.00	SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	203-02000	EXCAVATION, COMMON	224.00	CYS
0015	203-08607	LINEAR GRADING	1100.00	LFT
0016	205-12108	STORMWATER MANAGEMENT BUDGET	13500.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	207-12498	SUBGRADE TREATMENT, TYPE ID	389.00	SYS
0020	211-06467	AGGREGATE FOR END BENT BACKFILL	33.00	CYS
0021	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	96.00	SYS
0022	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	495.00	SYS
0023	302-06464	SUBBASE FOR PCCP	54.00	CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	248.00	TON
0025	304-07494	WIDENING WITH HMA, TYPE C	145.00	TON
0026	304-12625	HMA PATCHING FULL DEPTH TYPE C	242.00	TON
0027	306-08043	MILLING, TRANSITION	920.00	SYS
0028	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	76.00	TON
0029	401-10258	JOINT ADHESIVE, SURFACE	1230.00	LFT
0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	1230.00	LFT
0031	401-11785	LIQUID ASPHALT SEALANT	1230.00	LFT
0032	406-05521	ASPHALT FOR TACK COAT	1720.00	SYS
0033	503-12477	TERMINAL JOINT, TYPE HMA	88.00	LFT
0034	601-01700	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 1	3.00	EACH
0035	601-02241	GUARDRAIL, REMOVE	1049.00	LFT
0036	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	708.00	LFT
0037	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	4.00	EACH
0038	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0039	602-06729	BARRIER, DELINEATOR	34.00	EACH
0040	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	212.00	SYS
0041	616-05689	RIPRAP, CLASS 2	1700.00	TON
0042	616-06405	RIPRAP, REVETMENT	39.00	TON
0043	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	589.00	SYS
0044	619-98427	CLEAN DRAINS	14.00	EACH
0045	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0046	621-06559	MULCHED SEEDING R	1311.00	SYS
0047	621-06574	SODDING	26.00	SYS
0048	628-09403	FIELD OFFICE, C	14.00	MOS
0049	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0050	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	2.00	EACH
0051	702-51863	FIELD DRILLED HOLE IN CONCRETE	1092.00	EACH
0052	703-06029	REINFORCING BARS, EPOXY COATED	90911.00	LBS
0053	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	236.00	EACH

0054	704-51002	CONCRETE, C, SUPERSTRUCTURE	107.00	CYS
0055	706-11600	RAILING, CONCRETE FC	127.00	CYS
0056	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0057	707-05984	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 45 IN. X 16 IN.	228.00	LFT
0058	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0059	709-51821	SURFACE SEAL	1.00	LS
0060	709-51821	SURFACE SEAL	1.00	LS
0061	710-09158	PATCHING CONCRETE STRUCTURES	300.00	SFT
0062	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	820.00	LFT
0063	715-05407	PIPE, END BENT DRAIN, 6 IN.	104.00	LFT
0064	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	10.00	EACH
0065	718-06526	HMA FOR UNDERDRAINS	23.00	TON
0066	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	668.00	SYS
0067	718-52610	AGGREGATE FOR UNDERDRAINS	95.00	CYS
0068	722-01066	HYDRODEMOLITION	3226.00	SYS
0069	722-12380	BRIDGE DECK OVERLAY, BUDGET	52749.00	DOL
0070	722-12382	TRANSVERSE GROOVING	3226.00	SYS
0071	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	3226.00	SYS
0072	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	300.00	SFT
0073	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	146.00	SFT
0074	724-11063	STRUCTURAL EXPANSION JOINT, SS, REPLACE	94.00	LFT
0075	724-12103	PRE-COMPRESSED FOAM JOINT	88.00	LFT
0076	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	811.00	SYS
0077	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.00	EACH
0078	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4976.00	LFT
0079	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	1788.00	LFT
0080	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	48.00	LFT
0081	801-06640	CONSTRUCTION SIGN, A	48.00	EACH
0082	801-06645	CONSTRUCTION SIGN, B	20.00	EACH
0083	801-06775	MAINTAINING TRAFFIC	1.00	LS
0084	801-07118	BARRICADE, III-A	96.00	LFT
0085	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	830.00	LFT
0086	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	180.00	LFT
0087	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0088	801-12081	PORTABLE SIGNAL	1.00	LS
0089	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0090	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	280.00	LFT
0091	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2200.00	LFT
0092	808-06716	LINE, REMOVE	1405.00	LFT
0093	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	330.00	LFT
0094	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	330.00	LFT
0095	808-12032	GROOVING FOR PAVEMENT MARKINGS	2480.00	LFT

Call: 330  
 Contract: B -40443-A  
 Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

Line			Quantity Unit	
Item No	Item Code	Description	Quantity	Unit
0096	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	3226.00	SYS

Call: 330  
 Contract: B -40443-A  
 Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED CONCRETE

Line			Quantity Unit	
Item No	Item Code	Description	Quantity	Unit
0097	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	3226.00	SYS

Call: 340  
 Contract: B -40488-A  
 Section No.: 1 BRIDGE DECK OVERLAY

Line			Quantity Unit	
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	168.00	SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	202-96128	GUTTER, CONCRETE, REMOVE	192.00	LFT
0015	203-02000	EXCAVATION, COMMON	1201.00	CYS
0016	203-02070	BORROW	225.00	CYS
0017	203-51223	EXCAVATION, WATERWAY	481.00	CYS
0018	205-12108	STORMWATER MANAGEMENT BUDGET	53973.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	205-12618	SWQCP PREPARATION	1.00	LS
0021	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	27.00	CYS
0022	206-51235	COFFERDAM	1.00	LS
0023	206-51235	COFFERDAM	1.00	LS



0024	206-51235	COFFERDAM	1.00	LS
0025	207-09935	SUBGRADE TREATMENT, TYPE IC	340.00	SYS
0026	207-12498	SUBGRADE TREATMENT, TYPE ID	630.00	SYS
0027	211-02050	B BORROW	250.00	CYS
0028	211-09265	STRUCTURE BACKFILL, TYPE 2	20.00	CYS
0029	211-09267	STRUCTURE BACKFILL, TYPE 4	8.00	CYS
0030	211-09268	STRUCTURE BACKFILL, TYPE 5	75.00	CYS
0031	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	4.00	CYS
0032	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	190.00	SYS
0033	301-12233	COMPACTED AGGREGATE NO. 8	3.70	CYS
0034	301-12234	COMPACTED AGGREGATE NO. 53	33.00	CYS
0035	302-06464	SUBBASE FOR PCCP	43.00	CYS
0036	303-01180	COMPACTED AGGREGATE NO. 53	249.00	TON
0037	304-07493	WIDENING WITH HMA, TYPE B	126.00	TON
0038	306-08043	MILLING, TRANSITION	2222.00	SYS
0039	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	200.00	TON
0040	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	141.00	TON
0041	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	96.00	TON
0042	401-10258	JOINT ADHESIVE, SURFACE	1943.00	LFT
0043	401-10259	JOINT ADHESIVE, INTERMEDIATE	1367.00	LFT
0044	401-11785	LIQUID ASPHALT SEALANT	1943.00	LFT
0045	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0046	601-02241	GUARDRAIL, REMOVE	669.00	LFT
0047	601-06035	GUARDRAIL, RESET	200.00	LFT
0048	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	106.30	LFT
0049	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0050	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0051	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	183.00	SYS
0052	615-06490	RIGHT-OF-WAY MARKER	11.00	EACH
0053	615-06505	MONUMENT, B	10.00	EACH
0054	616-05688	RIPRAP, CLASS 1	360.00	TON
0055	616-05689	RIPRAP, CLASS 2	374.00	TON
0056	616-06405	RIPRAP, REVETMENT	156.00	TON
0057	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1316.00	SYS
0058	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	406.00	SYS
0059	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0060	621-02356	SEEDING WETLAND	2.00	LBS
0061	621-02770	EROSION CONTROL BLANKET	1201.00	SYS
0062	621-06559	MULCHED SEEDING R	2851.00	SYS
0063	621-06565	MULCHING MATERIAL	1.00	TON
0064	621-06567	WATER	1.00	KGAL
0065	621-06574	SODDING	10.00	SYS

0066	621-09815	ARTICULATED CONCRETE BLOCK	750.00	SYS
0067	621-12612	SEED MIXTURE FLOODPLAIN	9.00	LBS
0068	621-52448	SIGN, DO NOT SPRAY	4.00	EACH
0069	622-52436	SIGN, DO NOT MOW OR SPRAY	6.00	EACH
0070	628-09403	FIELD OFFICE, C	12.00	MOS
0071	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0072	702-51005	CONCRETE, A, SUBSTRUCTURE	1.20	CYS
0073	702-51015	CONCRETE, B, FOOTINGS	23.00	CYS
0074	703-06028	REINFORCING BARS	1946.00	LBS
0075	703-06029	REINFORCING BARS, EPOXY COATED	46623.00	LBS
0076	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	38.00	EACH
0077	704-51002	CONCRETE, C, SUPERSTRUCTURE	119.30	CYS
0078	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.00	EACH
0079	706-11404	RAILING, STEEL PF-1	141.00	LFT
0080	706-11602	RAILING, CONCRETE PF-1	7.60	CYS
0081	709-51821	SURFACE SEAL	1.00	LS
0082	709-51821	SURFACE SEAL	1.00	LS
0083	714-11475	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 20 FT. X 4 FT.	60.00	LFT
0084	722-01066	HYDRODEMOLITION	748.00	SYS
0085	722-12380	BRIDGE DECK OVERLAY, BUDGET	10540.00	DOL
0086	722-12382	TRANSVERSE GROOVING	748.00	SYS
0087	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	748.00	SYS
0088	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	135.00	SFT
0089	801-04308	ROAD CLOSURE SIGN ASSEMBLY	17.00	EACH
0090	801-06625	DETOUR ROUTE MARKER ASSEMBLY	67.00	EACH
0091	801-06640	CONSTRUCTION SIGN, A	55.00	EACH
0092	801-06775	MAINTAINING TRAFFIC	1.00	LS
0093	801-07118	BARRICADE, III-A	148.00	LFT
0094	801-07119	BARRICADE, III-B	132.00	LFT
0095	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH
0096	802-04893	REFERENCE POST	3.00	EACH
0097	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	20.00	LFT
0098	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	6.00	SFT
0099	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2682.00	LFT
0100	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	2682.00	LFT
0101	808-12032	GROOVING FOR PAVEMENT MARKINGS	5364.00	LFT
0102	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	14.00	EACH

Call: 340

Contract: B -40488-A

Section No.: 2 LATEX MODIFIED CONCRETE OVERLAY OPTION

Line

Item No	Item Code	Description	Quantity	Unit
0103	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	748.00	SYS

Call: 340

Contract: B -40488-A

Section No.: 3                      SILICA FUME MODIFIED CONCRETE OVERLAY OPTION

**Line**

Item No	Item Code	Description	Quantity	Unit
0104	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	748.00	SYS

Call: 350

Contract: B -40598-A

Section No.: 1                      SMALL STRUCTURE PIPE LINING

**Line**

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	113-01614	PARTNERING OVERHEAD	1.00	LS
0011	201-01015	CLEARING AND GRUBBING	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	2442.00	SYS
0013	202-02272	PAVED SIDE DITCH, REMOVE	32.00	LFT
0014	202-02637	PIPE ABANDON AND GROUT FILL	160.00	LFT
0015	202-12017	SIGNAL CABLE, REMOVE	6931.00	LFT
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0018	202-86946	HANDHOLE, REMOVE	2.00	EACH
0019	202-91385	INLET, REMOVE	6.00	EACH
0020	202-93741	GUARDRAIL, END TREATMENT, REMOVE	2.00	EACH
0021	202-94954	BARRIER WALL, CONCRETE, REMOVE	120.00	LFT
0022	202-96133	PIPE, REMOVE	26.00	LFT
0023	202-96531	FENCE RIGHT-OF-WAY, REMOVE	236.00	LFT
0024	203-02000	EXCAVATION, COMMON	454.00	CYS
0025	203-08607	LINEAR GRADING	818.00	LFT
0026	205-12108	STORMWATER MANAGEMENT BUDGET	20797.00	DOL
0027	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS

0028	205-12618	SWQCP PREPARATION	1.00	LS
0029	206-51220	EXCAVATION, WET	180.00	CYS
0030	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	512.00	CYS
0031	206-51235	COFFERDAM	1.00	LS
0032	207-09935	SUBGRADE TREATMENT, TYPE IC	2394.00	SYS
0033	211-02050	B BORROW	30.00	CYS
0034	211-06467	AGGREGATE FOR END BENT BACKFILL	116.00	CYS
0035	211-09267	STRUCTURE BACKFILL, TYPE 4	53.00	CYS
0036	213-09270	FLOWABLE BACKFILL, REMOVABLE	10.00	CYS
0037	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	2394.00	SYS
0038	302-06464	SUBBASE FOR PCCP	546.00	CYS
0039	303-01180	COMPACTED AGGREGATE NO. 53	580.00	TON
0040	502-03289	QUALITY ASSURANCE ADJUSTMENT	1.00	DOL
0041	502-06332	PCCP, 15 IN.	566.00	SYS
0042	503-05240	D-1 CONTRACTION JOINT	254.00	LFT
0043	503-12478	TERMINAL JOINT, TYPE PCCP	256.00	LFT
0044	503-12668	JOINTED REINFORCED CONCRETE PAVEMENT 15 IN.	1130.00	SYS
0045	601-02241	GUARDRAIL, REMOVE	611.00	LFT
0046	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	532.00	LFT
0047	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0048	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0049	602-06729	BARRIER, DELINEATOR	12.00	EACH
0050	602-91266	CONCRETE MEDIAN BARRIER MODIFIED	120.00	LFT
0051	603-06040	FENCE, FARM FIELD, 47 IN.	236.00	LFT
0052	606-11064	MILLED PCCP CORRUGATIONS, CONVENTIONAL	240.00	LFT
0053	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	592.00	SYS
0054	615-06520	MONUMENT, RE-ESTABLISH	1.00	EACH
0055	616-05688	RIPRAP, CLASS 1	13.00	TON
0056	616-06405	RIPRAP, REVETMENT	23.00	TON
0057	616-06406	RIPRAP, REVETMENT	2097.00	SYS
0058	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	64.00	SYS
0059	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	256.00	SYS
0060	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	2097.00	SYS
0061	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0062	621-06559	MULCHED SEEDING R	4777.00	SYS
0063	621-06560	MULCHED SEEDING U	1468.00	SYS
0064	621-06574	SODDING	195.00	SYS
0065	628-12683	FIELD OFFICE, D	12.00	MOS
0066	701-06011	DYNAMIC PILE LOAD TEST	8.00	EACH
0067	701-09557	TEST PILE, DYNAMIC, PRODUCTION	196.00	LFT
0068	701-09559	TEST PILE, DYNAMIC, RESTRIKE	8.00	EACH
0069	701-09663	PILE, STEEL PIPE, 0.312 IN., 14 IN.	2788.00	LFT

0070	702-04325	TEMPORARY SHORING	1.00	LS
0071	702-51005	CONCRETE, A, SUBSTRUCTURE	207.20	CYS
0072	702-51015	CONCRETE, B, FOOTINGS	38.80	CYS
0073	702-51863	FIELD DRILLED HOLE IN CONCRETE	216.00	EACH
0074	703-01540	THREADED TIE BAR ASSEMBLY	64.00	EACH
0075	703-06028	REINFORCING BARS	19234.00	LBS
0076	703-06029	REINFORCING BARS, EPOXY COATED	179344.00	LBS
0077	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	1158.00	EACH
0078	704-51002	CONCRETE, C, SUPERSTRUCTURE	519.20	CYS
0079	706-11601	RAILING, CONCRETE FT	54.40	CYS
0080	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	4.00	EACH
0081	707-05982	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 28 IN. X 12 IN.	1808.00	LFT
0082	709-51821	SURFACE SEAL	1.00	LS
0083	709-51821	SURFACE SEAL	1.00	LS
0084	710-09158	PATCHING CONCRETE STRUCTURES	240.00	SFT
0085	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	208.00	LFT
0086	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	141.00	LFT
0087	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	92.00	LFT
0088	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	99.00	LFT
0089	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH
0090	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	EACH
0091	718-06529	OUTLET PROTECTOR, 2	2.00	EACH
0092	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	121.00	SYS
0093	718-52610	AGGREGATE FOR UNDERDRAINS	10.00	CYS
0094	720-45041	INLET, H5	3.00	EACH
0095	722-12382	TRANSVERSE GROOVING	2172.00	SYS
0096	725-08296	PIPE LINER, CURED-IN-PLACE, 48 IN	200.00	LFT
0097	725-11300	PIPE LINER, CURED-IN-PLACE, MIN AREA 8.9 SFT	160.00	LFT
0098	727-90308	EPOXY INJECTION, CRACK PREPARATION	200.00	LFT
0099	727-90309	EPOXY INJECTION, EPOXY MATERIAL	4.00	GAL
0100	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0101	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0102	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	39316.00	LFT
0103	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	1710.00	LFT
0104	801-06640	CONSTRUCTION SIGN, A	148.00	EACH
0105	801-06645	CONSTRUCTION SIGN, B	25.00	EACH
0106	801-06650	TEMPORARY RAISED PAVEMENT MARKER, GRADE 2	238.00	EACH
0107	801-06710	FLASHING ARROW SIGN	840.00	DAY
0108	801-06775	MAINTAINING TRAFFIC	1.00	LS
0109	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00	EACH
0110	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1666.00	LFT
0111	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH

0112	801-12031	TEMPORARY PORTABLE RUMBLE STRIPS	720.00	DAY
0113	802-11843	RADAR SPEED DISPLAY SIGN ASSEMBLY	4.00	EACH
0114	805-04973	CONDUIT	1128.00	LFT
0115	805-04973	CONDUIT	634.00	LFT
0116	807-12733	HANDHOLE, ATMS	2.00	EACH
0117	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	1020.00	LFT
0118	808-06716	LINE, REMOVE	10378.00	LFT
0119	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	6583.00	LFT
0120	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	6590.00	LFT
0121	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	3294.00	LFT
0122	808-75994	PRISMATIC REFLECTOR	344.00	EACH
0123	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	40.00	EACH
0124	809-04969	SPLICE	196.00	EACH
0125	809-94971	FIBER OPTIC CABLE	6931.00	LFT

Call: 350

Contract: B -40598-A

Section No.: 2 BRIDGE DECK OVERLAY LATEX MODIFIED CONCRETE

**Line**

Item No	Item Code	Description	Quantity	Unit
0126	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	1580.00	SYS

Call: 350

Contract: B -40598-A

Section No.: 3 BRIDGE DECK OVERLAY SILICA FUME MODIFIED CONCRETE

**Line**

Item No	Item Code	Description	Quantity	Unit
0127	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	1580.00	SYS

Call: 360

Contract: B -41168-A

Section No.: 1 BRIDGE REHABILITATION

**Line**

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS

0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0012	203-02000	EXCAVATION, COMMON	57.00	CYS
0013	203-02055	EMBANKMENT	995.00	CYS
0014	203-02070	BORROW	199.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	26700.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	106.00	CYS
0019	206-51235	COFFERDAM	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	45.00	SYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	788.00	SYS
0022	211-06467	AGGREGATE FOR END BENT BACKFILL	27.00	CYS
0023	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	133.00	SYS
0024	302-06464	SUBBASE FOR PCCP	34.00	CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	135.00	TON
0026	304-07493	WIDENING WITH HMA, TYPE B	8.00	TON
0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	564.00	SYS
0028	306-08043	MILLING, TRANSITION	234.00	SYS
0029	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	133.00	TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	99.00	TON
0031	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	119.00	TON
0032	401-10258	JOINT ADHESIVE, SURFACE	1143.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	893.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	1143.00	LFT
0035	406-05521	ASPHALT FOR TACK COAT	2207.00	SYS
0036	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	4.00	EACH
0037	601-02241	GUARDRAIL, REMOVE	413.00	LFT
0038	601-09238	HAND DIG GUARDRAIL POST HOLES	1.00	EACH
0039	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0040	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	181.00	LFT
0041	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	133.00	SYS
0042	615-06505	MONUMENT, B	2.00	EACH
0043	615-06530	BENCH MARK POST	1.00	EACH
0044	616-06405	RIPRAP, REVETMENT	114.00	TON
0045	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	151.00	SYS
0046	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	1156.00	SYS
0047	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0048	621-02770	EROSION CONTROL BLANKET	264.00	SYS
0049	621-06559	MULCHED SEEDING R	264.00	SYS
0050	628-09401	FIELD OFFICE, A	10.00	MOS
0051	701-02938	CORED HOLE IN ROCK, 24 IN	18.00	LFT

0052	701-09558	TEST PILE, INDICATOR, PRODUCTION	70.00	LFT
0053	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00	EACH
0054	701-09739	PILE SHOE, HP 12 X 53	10.00	EACH
0055	701-09891	PILE SHOE, HP 12 X 84	3.00	EACH
0056	701-51195	PILE, STEEL H HP 12 X 53	200.00	LFT
0057	701-95782	PILE, STEEL H, HP, 12 X 84	90.00	LFT
0058	702-03607	CORED HOLE IN CONCRETE	10.00	EACH
0059	702-51005	CONCRETE, A, SUBSTRUCTURE	18.00	CYS
0060	702-92857	CONCRETE, C, SUBSTRUCTURE	30.00	CYS
0061	703-01540	THREADED TIE BAR ASSEMBLY	28.00	EACH
0062	703-06028	REINFORCING BARS	36245.00	LBS
0063	704-51002	CONCRETE, C, SUPERSTRUCTURE	67.00	CYS
0064	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.00	EACH
0065	706-09962	RAILING, CONCRETE PF-1	139.00	LFT
0066	706-11404	RAILING, STEEL PF-1	157.00	LFT
0067	709-51821	SURFACE SEAL	1.00	LS
0068	711-51038	STRUCTURAL STEEL	1.00	LS
0069	715-05407	PIPE, END BENT DRAIN, 6 IN.	122.00	LFT
0070	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	69.00	SYS
0071	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0072	801-06625	DETOUR ROUTE MARKER ASSEMBLY	17.00	EACH
0073	801-06640	CONSTRUCTION SIGN, A	6.00	EACH
0074	801-06775	MAINTAINING TRAFFIC	1.00	LS
0075	801-07118	BARRICADE, III-A	48.00	LFT
0076	801-07119	BARRICADE, III-B	60.00	LFT
0077	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	204.00	LFT
0078	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	850.00	LFT
0079	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	225.00	LFT
0080	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	225.00	LFT
0081	808-12032	GROOVING FOR PAVEMENT MARKINGS	1573.00	LFT
0082	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	724.00	LFT

Call: 370

Contract: B -42100-A

Section No.: 1            REPAIR OR REPLACE JOINTS

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL



0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0009	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS
0010	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0011	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0012	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0013	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0014	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0015	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0016	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0017	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0018	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0019	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0020	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0021	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0022	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0023	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0024	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0025	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0026	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0027	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0028	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0029	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0030	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0031	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0032	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0033	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0034	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0035	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0036	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0037	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0038	628-09403	FIELD OFFICE, C	12.00	MOS
0039	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0040	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	10.00	SFT
0041	724-12103	PRE-COMPRESSED FOAM JOINT	192.00	LFT
0042	724-12420	BRIDGE JOINT NOSING	335.00	SFT
0043	724-12461	CONCRETE FOR PATCHING STRUCTURAL EXPANSION JOINT	20.00	SFT
0044	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	24.00	EACH
0045	801-04308	ROAD CLOSURE SIGN ASSEMBLY	12.00	EACH
0046	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	30143.00	LFT
0047	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	20218.00	LFT

0048	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	4400.00	LFT
0049	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	4265.00	LFT
0050	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	110.00	LFT
0051	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	2100.00	LFT
0052	801-06625	DETOUR ROUTE MARKER ASSEMBLY	42.00	EACH
0053	801-06640	CONSTRUCTION SIGN, A	135.00	EACH
0054	801-06645	CONSTRUCTION SIGN, B	63.00	EACH
0055	801-06710	FLASHING ARROW SIGN	61.00	DAY
0056	801-06775	MAINTAINING TRAFFIC	1.00	LS
0057	801-07118	BARRICADE, III-A	144.00	LFT
0058	801-07119	BARRICADE, III-B	144.00	LFT
0059	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	8.00	EACH
0060	801-12081	PORTABLE SIGNAL	1.00	LS
0061	801-12652	QUEUE TRUCK	30.00	DAY
0062	808-01428	TEMPORARY TRANSVERSE MARKINGS WHITE STOP LINE 24 IN	24.00	LFT
0063	808-11882	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 5 IN.	12.00	LFT
0064	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	30.00	LFT
0065	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	10.00	LFT
0066	808-75061	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	30.00	LFT

Call: 380

Contract: B -42111-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	97.00	SFT
	0009	602-06729	BARRIER, DELINEATOR	36.00	EACH
	0010	628-09403	FIELD OFFICE, C	6.00	MOS
	0011	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
	0012	709-51821	SURFACE SEAL	1.00	LS
	0013	709-51821	SURFACE SEAL	1.00	LS
	0014	709-51821	SURFACE SEAL	1.00	LS
	0015	709-51821	SURFACE SEAL	1.00	LS
	0016	710-09158	PATCHING CONCRETE STRUCTURES	120.00	SFT
	0017	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	534.00	SFT

0018	724-12103	PRE-COMPRESSED FOAM JOINT	92.00	LFT
0019	727-90308	EPOXY INJECTION, CRACK PREPARATION	800.00	LFT
0020	727-90309	EPOXY INJECTION, EPOXY MATERIAL	3.00	GAL
0021	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0022	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0023	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0024	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	2971.00	SYS
0025	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	EACH
0026	801-06196	DETOUR ROUTE MARKER ASSEMBLY, MULTIPLE ROUTES	25.00	EACH
0027	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5400.00	LFT
0028	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	2500.00	LFT
0029	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	96.00	LFT
0030	801-06640	CONSTRUCTION SIGN, A	57.00	EACH
0031	801-06645	CONSTRUCTION SIGN, B	18.00	EACH
0032	801-06775	MAINTAINING TRAFFIC	1.00	LS
0033	801-07118	BARRICADE, III-A	304.00	LFT
0034	801-07119	BARRICADE, III-B	20.00	LFT
0035	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	8.00	EACH
0036	801-12081	PORTABLE SIGNAL	1.00	LS
0037	801-12482	DRIVEWAY ASSISTANCE DEVICE	2.00	EACH
0038	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	10800.00	LFT
0039	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1260.00	LFT
0040	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	557.00	LFT
0041	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	123.00	LFT
0042	808-75994	PRISMATIC REFLECTOR	14.00	EACH

Call: 390

Contract: B -42122-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

**Line**

<b>Item No</b>	<b>Item Code</b>	<b>Description</b>	<b>Quantity Unit</b>	
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	602-06729	BARRIER, DELINEATOR	42.00	EACH
0009	628-09403	FIELD OFFICE, C	6.00	MOS
0010	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0011	709-51821	SURFACE SEAL	1.00	LS

0012	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	569.00	SFT
0013	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	3165.00	SYS
0014	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	4.00	EACH
0015	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	13500.00	LFT
0016	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	8000.00	LFT
0017	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	4.00	EACH
0018	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	60.00	LFT
0019	801-06640	CONSTRUCTION SIGN, A	43.00	EACH
0020	801-06710	FLASHING ARROW SIGN	60.00	DAY
0021	801-06775	MAINTAINING TRAFFIC	1.00	LS
0022	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	9.00	EACH
0023	801-12081	PORTABLE SIGNAL	1.00	LS
0024	801-12482	DRIVEWAY ASSISTANCE DEVICE	1.00	EACH
0025	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	300.00	LFT
0026	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2700.00	LFT
0027	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1580.00	LFT
0028	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	4.00	EACH
0029	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	4.00	EACH
0030	808-95933	CURB, PAINTING, YELLOW	808.00	LFT

Call: 400

Contract: B -42156-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0007	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0008	203-02000	EXCAVATION, COMMON	166.00	CYS
	0009	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	96.00	SFT
	0010	507-08271	JOINTS IN PCCP, FILLED	430.00	LFT
	0011	601-06035	GUARDRAIL, RESET	50.00	LFT
	0012	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
	0013	621-02770	EROSION CONTROL BLANKET	290.00	SYS
	0014	621-06559	MULCHED SEEDING R	290.00	SYS
	0015	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
	0016	628-12683	FIELD OFFICE, D	4.00	MOS
	0017	709-51821	SURFACE SEAL	1.00	LS

0018	710-09158	PATCHING CONCRETE STRUCTURES	16.00	SFT
0019	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	17.00	SFT
0020	727-90308	EPOXY INJECTION, CRACK PREPARATION	47.00	LFT
0021	727-90309	EPOXY INJECTION, EPOXY MATERIAL	4.00	GAL
0022	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0023	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	859.00	SYS
0024	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	EACH
0025	801-06625	DETOUR ROUTE MARKER ASSEMBLY	35.00	EACH
0026	801-06640	CONSTRUCTION SIGN, A	15.00	EACH
0027	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0028	801-06775	MAINTAINING TRAFFIC	1.00	LS
0029	801-07118	BARRICADE, III-A	80.00	LFT
0030	801-07119	BARRICADE, III-B	40.00	LFT
0031	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	50.00	LFT
0032	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	430.00	LFT

Call: 410

Contract: B -42403-A

Section No.: 1            SMALL STRUCTURE PIPE LINING

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0011	202-96133	PIPE, REMOVE	16.00	LFT
	0012	205-11626	PUMP AROUND	3.00	EACH
	0013	205-12108	STORMWATER MANAGEMENT BUDGET	400.00	DOL
	0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0015	205-12618	SWQCP PREPARATION	1.00	LS
	0016	211-09264	STRUCTURE BACKFILL, TYPE 1	18.00	CYS
	0017	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	30.00	SYS
	0018	301-12232	COMPACTED AGGREGATE NO. 5	5.00	CYS
	0019	301-12234	COMPACTED AGGREGATE NO. 53	5.00	CYS
	0020	304-12623	HMA PATCHING FULL DEPTH TYPE B	13.00	TON
	0021	507-08271	JOINTS IN PCCP, FILLED	91.00	LFT

0022	616-05689	RIPRAP, CLASS 2	40.00	TON
0023	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	29.00	SYS
0024	621-06560	MULCHED SEEDING U	60.00	SYS
0025	709-51821	SURFACE SEAL	1.00	LS
0026	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	8.00	LFT
0027	715-05164	PIPE, TYPE 2, CIRCULAR, 66 IN.	8.00	LFT
0028	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	EACH
0029	720-91110	MANHOLE, N4	1.00	EACH
0030	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	261.00	SFT
0031	725-11038	LINER PIPE, THERMOPLASTIC, CIRCULAR, 15.9-16.0 SFT	130.00	LFT
0032	725-11868	PIPE LINER, CURED-IN-PLACE, MIN AREA 18.1 SFT	145.00	LFT
0033	727-90308	EPOXY INJECTION, CRACK PREPARATION	50.00	LFT
0034	727-90309	EPOXY INJECTION, EPOXY MATERIAL	6.00	GAL
0035	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0036	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	320.00	SYS
0037	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3840.00	LFT
0038	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	3070.00	LFT
0039	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	48.00	LFT
0040	801-06640	CONSTRUCTION SIGN, A	34.00	EACH
0041	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0042	801-06775	MAINTAINING TRAFFIC	1.00	LS
0043	801-12042	TRUCK MOUNTED ATTENUATOR	12.00	DAY
0044	801-12081	PORTABLE SIGNAL	1.00	LS
0045	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	17.00	LFT
0046	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	133.00	LFT
0047	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	67.00	LFT
0048	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.00	EACH

Call: 420

Contract: B -42677-A

Section No.: 1 IDIQ, DISTRICT WIDE BRIDGE MAINTENANCE

Line			Quantity	Unit
Item No	Item Code	Description		
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	155618.10	DOL
0008	202-02240	PAVEMENT REMOVAL	50.00	SYS
0009	202-51368	SLOPEWALL, REMOVE	200.00	SYS

0010	203-02000	EXCAVATION, COMMON	75.00	CYS
0011	203-02070	BORROW	50.00	CYS
0012	203-08607	LINEAR GRADING	400.00	LFT
0013	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	50.00	CYS
0014	303-01180	COMPACTED AGGREGATE NO. 53	50.00	TON
0015	304-12627	HMA PATCHING FULL DEPTH TYPE D	25.00	TON
0016	304-12628	HMA PATCHING PARTIAL DEPTH TYPE D	25.00	TON
0017	503-12173	TERMINAL JOINT, POLYMER MODIFIED ASPHALT	50.00	LFT
0018	506-06333	PCCP PATCHING, FULL DEPTH	100.00	SYS
0019	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	150.00	SYS
0020	616-05688	RIPRAP, CLASS 1	75.00	TON
0021	616-06405	RIPRAP, REVETMENT	75.00	TON
0022	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	100.00	SYS
0023	616-51367	SLOPEWALL, CONCRETE, 4 IN.	100.00	SYS
0024	616-93772	INSPECTION HOLE	12.00	EACH
0025	619-98427	CLEAN DRAINS	10.00	EACH
0026	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0027	621-06559	MULCHED SEEDING R	100.00	SYS
0028	628-09403	FIELD OFFICE, C	14.00	MOS
0029	628-11976	COMPUTER SYSTEM EQUIPMENT	14.00	EACH
0030	703-06029	REINFORCING BARS, EPOXY COATED	50.00	LBS
0031	708-51813	PNEUMATICALLY PLACED MORTAR	100.00	SFT
0032	709-12077	FIBER WRAP CONCRETE CASING SYSTEM	300.00	SFT
0033	709-51821	SURFACE SEAL	1.00	LS
0034	710-09158	PATCHING CONCRETE STRUCTURES	700.00	SFT
0035	711-11599	REPAIR WELD	24.00	IN
0036	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	850.00	SYS
0037	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	200.00	SFT
0038	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	150.00	SFT
0039	724-03276	STRUCTURAL EXPANSION JOINT SEALING SYS	50.00	LFT
0040	724-09626	STRUCTURAL EXPANSION JOINT SEAL, SS, REPLACE	50.00	LFT
0041	724-11063	STRUCTURAL EXPANSION JOINT, SS, REPLACE	50.00	LFT
0042	724-12103	PRE-COMPRESSED FOAM JOINT	50.00	LFT
0043	724-12157	PREFORMED SILICONE JOINT	50.00	LFT
0044	727-90308	EPOXY INJECTION, CRACK PREPARATION	10.00	LFT
0045	727-90309	EPOXY INJECTION, EPOXY MATERIAL	20.00	GAL
0046	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0047	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	850.00	SYS
0048	801-06640	CONSTRUCTION SIGN, A	20.00	EACH
0049	801-06645	CONSTRUCTION SIGN, B	10.00	EACH
0050	801-06710	FLASHING ARROW SIGN	30.00	DAY
0051	801-07118	BARRICADE, III-A	80.00	LFT

0052 801-12440 MAINTAINING TRAFFIC, IDIQ

61000.00 DOL

Call: 430

Contract: B -42914-A

Section No.: 1 BRIDGE DECK PATCHING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-04299	FORCE ACCOUNT WORK	25000.00	DOL
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	205-12108	STORMWATER MANAGEMENT BUDGET	1780.00	DOL
0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0013	305-97019	RUBBLIZING PCCP	160.00	SYS
0014	601-06035	GUARDRAIL, RESET	25.00	LFT
0015	605-06120	CURB, CONCRETE	30.00	LFT
0016	616-02281	GROUT FOR RIPRAP	18.00	CYS
0017	616-06405	RIPRAP, REVETMENT	5.00	TON
0018	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0019	619-95315	CLEAN AND PAINT BEARING ASSEMBLIES, BRIDGE NO.	1.00	LS
0020	621-06575	SODDING, NURSERY	36.00	SYS
0021	628-09403	FIELD OFFICE, C	7.00	MOS
0022	628-11729	CELLULAR TELEPHONE, TYPE A	7.00	EACH
0023	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0024	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0025	628-11781	CELLULAR TELEPHONE SERVICE, 750 MIN.	7.00	MOS
0026	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0027	628-12685	TELEPHONE SERVICE, A	7.00	MOS
0028	710-09158	PATCHING CONCRETE STRUCTURES	15.00	SFT
0029	711-51038	STRUCTURAL STEEL	1.00	LS
0030	711-90114	JACKING AND SUPPORTING, SUPERSTRUCTURE	1.00	LS
0031	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	466.00	SFT
0032	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	466.00	SFT
0033	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	32.00	EACH
0034	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6344.00	LFT
0035	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	1500.00	LFT



0036	801-06640	CONSTRUCTION SIGN, A	93.00	EACH
0037	801-06710	FLASHING ARROW SIGN	102.00	DAY
0038	801-06775	MAINTAINING TRAFFIC	1.00	LS
0039	801-07119	BARRICADE, III-B	24.00	LFT
0040	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	455.00	LFT
0041	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	8.00	EACH
0042	801-12042	TRUCK MOUNTED ATTENUATOR	60.00	DAY
0043	801-12348	TEMPORARY WORKSITE SPEED DISPLAY ASSEMBLY	6.00	EACH
0044	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	120.00	LFT
0045	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	460.00	LFT
0046	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	460.00	LFT
0047	808-06716	LINE, REMOVE	1040.00	LFT

Call: 440

Contract: B -42916-A

Section No.: 1 BRIDGE MAINTENANCE AND REPAIR

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	205-12108	STORMWATER MANAGEMENT BUDGET	3488.00	DOL
	0010	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0011	305-97019	RUBBLIZING PCCP	467.00	SYS
	0012	601-06035	GUARDRAIL, RESET	50.00	LFT
	0013	605-06120	CURB, CONCRETE	160.00	LFT
	0014	616-02281	GROUT FOR RIPRAP	51.00	CYS
	0015	616-06405	RIPRAP, REVETMENT	20.00	TON
	0016	619-04981	CLEAN AND PAINT	1.00	LS
	0017	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
	0018	619-95315	CLEAN AND PAINT BEARING ASSEMBLIES, BRIDGE NO.	1.00	LS
	0019	621-06575	SODDING, NURSERY	115.00	SYS
	0020	628-09403	FIELD OFFICE, C	12.00	MOS
	0021	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
	0022	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
	0023	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
	0024	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	12.00	MOS

0025	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0026	628-12685	TELEPHONE SERVICE, A	12.00 MOS
0027	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00 LS
0028	710-09158	PATCHING CONCRETE STRUCTURES	305.00 SFT
0029	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	25.00 SFT
0030	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	50.00 SFT
0031	801-06640	CONSTRUCTION SIGN, A	22.00 EACH
0032	801-06775	MAINTAINING TRAFFIC	1.00 LS
0033	801-12042	TRUCK MOUNTED ATTENUATOR	45.00 DAY

Call: 450

Contract: B -42917-A

Section No.: 1 DEBRIS REMOVAL FROM CHANNEL

**Line**

Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0007	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00 LS
0008	628-09401	FIELD OFFICE, A	3.00 MOS
0009	628-11729	CELLULAR TELEPHONE, TYPE A	1.00 EACH
0010	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0011	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0012	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	3.00 MOS
0013	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0014	628-11977	COMPUTER SYSTEM	1.00 EACH
0015	628-12685	TELEPHONE SERVICE, A	3.00 MOS
0016	801-06640	CONSTRUCTION SIGN, A	24.00 EACH
0017	801-06775	MAINTAINING TRAFFIC	1.00 LS

Call: 460

Contract: B -43421-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

**Line**

Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL

0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	507-08272	JOINTS IN PCCP, SAW AND SEAL	314.00	LFT
0009	628-09403	FIELD OFFICE, C	12.00	MOS
0010	709-51821	SURFACE SEAL	1.00	LS
0011	709-51821	SURFACE SEAL	1.00	LS
0012	709-51821	SURFACE SEAL	1.00	LS
0013	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1493.00	SFT
0014	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	8061.00	SYS
0015	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0016	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	16530.00	LFT
0017	801-06625	DETOUR ROUTE MARKER ASSEMBLY	40.00	EACH
0018	801-06640	CONSTRUCTION SIGN, A	80.00	EACH
0019	801-06710	FLASHING ARROW SIGN	28.00	DAY
0020	801-06775	MAINTAINING TRAFFIC	1.00	LS
0021	801-07118	BARRICADE, III-A	216.00	LFT
0022	801-07119	BARRICADE, III-B	144.00	LFT
0023	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2255.00	LFT
0024	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1822.00	LFT
0025	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	557.00	LFT
0026	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	46.00	EACH
0027	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	46.00	EACH

Call: 500

Contract: M -43525-A

Section No.: 1 TREE REMOVAL AND TRIMMING

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0006	201-01015	CLEARING AND GRUBBING	1.00	LS
	0007	201-02245	TREE 6 IN., REMOVE	10.00	EACH
	0008	201-02245	TREE 6 IN., REMOVE	2.00	EACH
	0009	201-02250	TREE 10 IN., REMOVE	14.00	EACH
	0010	201-02250	TREE 10 IN., REMOVE	2.00	EACH
	0011	201-02255	TREE 18 IN., REMOVE	18.00	EACH
	0012	201-02255	TREE 18 IN., REMOVE	4.00	EACH
	0013	201-02260	TREE 30 IN., REMOVE	20.00	EACH

0014	201-02260	TREE 30 IN., REMOVE	2.00 EACH
0015	201-02265	TREE 48 IN., REMOVE	12.00 EACH
0016	201-02265	TREE 48 IN., REMOVE	1.00 EACH
0017	201-02270	TREE 60 IN., REMOVE	3.00 EACH
0018	201-02270	TREE 60 IN., REMOVE	1.00 EACH
0019	202-91922	STUMP, REMOVE	35.00 EACH
0020	801-06640	CONSTRUCTION SIGN, A	6.00 EACH
0021	801-06710	FLASHING ARROW SIGN	20.00 DAY
0022	801-06775	MAINTAINING TRAFFIC	1.00 LS
0023	801-12042	TRUCK MOUNTED ATTENUATOR	20.00 DAY
0024	801-92448	CONSTRUCTION SIGNS MOBILE	330.00 DAY

Call: 510

Contract: M -43527-A

Section No.: 1 LIGHTING MAINTENANCE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0007	202-01845	CONDUIT, REMOVE	300.00	LFT
	0008	202-86946	HANDHOLE, REMOVE	5.00	EACH
	0009	202-95579	SERVICE POINT, REMOVE	1.00	EACH
	0010	702-90915	CONCRETE, CLASS, A	1.00	CYS
	0011	711-95290	FIELD WELDING	1.00	LFT
	0012	715-04612	PIPE	101.00	LFT
	0013	715-04994	METER	1.00	EACH
	0014	715-04994	METER	5.00	EACH
	0015	801-06710	FLASHING ARROW SIGN	20.00	DAY
	0016	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0017	801-12042	TRUCK MOUNTED ATTENUATOR	20.00	DAY
	0018	801-92448	CONSTRUCTION SIGNS MOBILE	60.00	DAY
	0019	805-86898	CONDUIT, STEEL, GALVANIZED, 0.75 IN.	450.00	LFT
	0020	805-87715	GROUND ROD WITH CONNECTOR	1.00	EACH
	0021	805-87780	CIRCUIT BREAKER	5.00	EACH
	0022	805-91703	CONDUIT, STEEL, GALVANIZED, 1.5 IN.	10.00	LFT
	0023	805-91706	ANCHOR BOLT REPAIR	4.00	EACH
	0024	805-91711	EXPANSION FITTING, 1.5 IN.	1.00	EACH
	0025	805-95518	CONDUIT, FLEXIBLE, 2 IN.	100.00	LFT

0026	805-95520	EXPANSION FITTING 2.0 IN.	1.00 EACH
0027	805-95521	EXPANSION FITTING 0.75 IN.	2.00 EACH
0028	807-01562	POWER DISCONNECT PLUG FOR HIGH MAST TOWER	5.00 EACH
0029	807-01563	HIGH MAST TOWER LOCATING PIN, STAINLESS STEEL	1.00 EACH
0030	807-01617	HANDHOLE COVER AND RING	1.00 EACH
0031	807-02191	HANDHOLE LIGHTING	1.00 EACH
0032	807-02579	MAST ARM, 15FT	1.00 EACH
0033	807-02778	LUMINAIRE, MAST ARM, 5 FT	1.00 EACH
0034	807-02780	LUMINAIRE, MAST ARM, 8 FT	1.00 EACH
0035	807-02781	LUMINAIRE, MAST ARM, 10 FT	1.00 EACH
0036	807-02783	LUMINAIRE MAST ARM 15 FT	1.00 EACH
0037	807-02784	LUMINAIRE, MAST ARM, 20 FT	1.00 EACH
0038	807-02785	LUMINAIRE, MAST ARM, 25 FT	1.00 EACH
0039	807-04507	TRANSFORMER	1.00 EACH
0040	807-04651	WIRE	1200.00 LFT
0041	807-04651	WIRE	100.00 LFT
0042	807-04651	WIRE	100.00 LFT
0043	807-04651	WIRE	100.00 LFT
0044	807-04651	WIRE	100.00 LFT
0045	807-04654	LIGHT POLE	1.00 EACH
0046	807-04654	LIGHT POLE	1.00 EACH
0047	807-04654	LIGHT POLE	1.00 EACH
0048	807-04654	LIGHT POLE	1.00 EACH
0049	807-04654	LIGHT POLE	1.00 EACH
0050	807-04654	LIGHT POLE	1.00 EACH
0051	807-04654	LIGHT POLE	1.00 EACH
0052	807-04654	LIGHT POLE	1.00 EACH
0053	807-04654	LIGHT POLE	1.00 EACH
0054	807-04866	LUMINAIRE	2.00 EACH
0055	807-04940	MAST ARM	10.00 EACH
0056	807-04967	CABLE	155.00 LFT
0057	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	25.00 LFT
0058	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	2500.00 LFT
0059	807-07703	HIGH MAST TOWER	2.00 EACH
0060	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	2.00 EACH
0061	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	4.00 EACH
0062	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	2.00 EACH
0063	807-12201	LUMINAIRE, HIGH MAST	5.00 EACH
0064	807-12203	LUMINAIRE, LOW LUMEN-LOW MOUNTING HEIGHT ROADWAY	1.00 EACH
0065	807-12206	LUMINAIRE, UNDERPASS	2.00 EACH
0066	807-86805	SERVICE POINT, I	1.00 EACH
0067	807-86810	SERVICE POINT, II	1.00 EACH

0068	807-86843	WIRE, NO. 4 COPPER, 1/C	7000.00	LFT
0069	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	250.00	LFT
0070	807-86910	CONNECTOR KIT, UNFUSED	20.00	EACH
0071	807-86915	CONNECTOR KIT, FUSED	20.00	EACH
0072	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	30.00	EACH
0073	807-86930	INSULATION LINK, NON-WATERPROOFED	30.00	EACH
0074	807-86955	CABLE-DUCT MARKER	2.00	EACH
0075	807-87085	ELECTRICIAN	25.00	HRS
0076	807-87098	CALLOUT REPAIR	2.00	EACH
0077	807-87595	REPLACEMENT OF CABLE CLAMPS ON HIGHMAST TOWER LUMINAIRE, RIN	2.00	EACH
0078	807-87640	BREAKAWAY COUPLING	5.00	SET
0079	807-87800	CABLE DUCT, INSTALL	750.00	LFT
0080	807-91704	LIGHT POLE HANDHOLE COVER	5.00	EACH
0081	807-91705	CONDUIT POLYETHYLENE REPAIR	2.00	EACH
0082	807-92870	TRANSFORMER BASE HANDHOLE	2.00	EACH
0083	807-93649	SHAFT FOR POST TOP LUMINAIRE, 16 FT M.H.	1.00	EACH
0084	807-93650	FOUNDATION, ANCHOR BOLTS AND REINFORCING STEEL FOR ROADWAY LIGHT	1.00	SET
0085	807-93651	FOUNDATION, ANCHOR BOLTS & REINFORCING STEEL , FOR POST TOP LIGHT	1.00	SET
0086	807-94480	LIGHT STANDARD, INSTALL	20.00	EACH
0087	807-95508	VANDAL SHIELD, LEXAN	1.00	EACH
0088	807-95513	SERVICE POINT MAIN BREAKER	4.00	EACH
0089	807-95514	SERVICE POINT RISER	1.00	EACH
0090	807-95515	SERVICE POINT WEATHERHEAD	1.00	EACH
0091	807-95516	RELAY SWITCH	5.00	EACH
0092	807-95522	PIPE STRAP	10.00	EACH
0093	807-95523	WATERPROOFING OF ELECTRICAL CONNECTOR	25.00	EACH
0094	807-95525	LIGHTING SUPPORT	2.00	EACH
0095	807-95705	BREAKAWAY ALUMINUM TRANSFORMER BASE	15.00	EACH
0096	807-95709	PHOTOCELLS	1.00	EACH
0097	807-96183	SHAFT FOR 30 FT M.H., TWIN 10 FT MAST ARM	1.00	EACH
0098	807-96184	SHAFT FOR 30 FT M.H. TWIN 12 FT MAST ARM	1.00	EACH
0099	807-96203	LIGHT POLE, HIGH MAST, TOWER SUSPENSION CABLE	3.00	EACH
0100	807-96204	LOWERING AND RAISING OF TOWER	1.00	EACH
0101	807-96236	LIGHT POLE, HIGH MAST, TOWER POWER CABLE	2.00	EACH
0102	807-96868	LUMINAIRE INSTALL	4.00	EACH
0103	807-98716	KELLUM GRIP STAINLESS STEEL	1.00	EACH
0104	809-04652	SERVICE POINT	4.00	EACH

Call: 550

Contract: T -40358-B

Section No.: 1 PEDESTRIAN FACILITIES IMPROVEMENTS

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02273	CENTER CURB, CONCRETE, REMOVE	43.00	SYS
0012	202-02278	CURB, CONCRETE, REMOVE	955.00	LFT
0013	202-02279	CURB AND GUTTER, REMOVE	1087.00	LFT
0014	202-52710	SIDEWALK CONCRETE, REMOVE	1058.00	SYS
0015	202-90277	DETECTOR HOUSING, REMOVE	8.00	EACH
0016	202-91385	INLET, REMOVE	1.00	EACH
0017	202-96133	PIPE, REMOVE	7.00	LFT
0018	203-02000	EXCAVATION, COMMON	10.00	CYS
0019	205-12108	STORMWATER MANAGEMENT BUDGET	20990.00	DOL
0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	33.00	SYS
0022	211-09264	STRUCTURE BACKFILL, TYPE 1	7.00	CYS
0023	214-11796	GEOGRID, TYPE IB	9.00	SYS
0024	302-07455	DENSE GRADED SUBBASE	2.00	CYS
0025	304-07494	WIDENING WITH HMA, TYPE C	16.00	TON
0026	304-12625	HMA PATCHING FULL DEPTH TYPE C	46.00	TON
0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	4323.00	SYS
0028	306-08432	MILLING, APPROACH	194.00	SYS
0029	401-10258	JOINT ADHESIVE, SURFACE	2665.00	LFT
0030	401-11785	LIQUID ASPHALT SEALANT	2665.00	LFT
0031	406-05521	ASPHALT FOR TACK COAT	4536.00	SYS
0032	604-06070	SIDEWALK, CONCRETE	699.00	SYS
0033	604-08086	CURB RAMP, CONCRETE	487.00	SYS
0034	604-12083	DETECTABLE WARNING SURFACES	95.00	SYS
0035	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	4.00	SYS
0036	605-06120	CURB, CONCRETE	75.00	LFT
0037	605-06125	CURB, CONCRETE, MODIFIED	456.00	LFT
0038	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	1106.00	LFT
0039	605-06255	CENTER CURB, D CONCRETE	16.00	SYS
0040	610-07488	HMA FOR APPROACHES, TYPE C	338.00	TON
0041	610-09108	PCCP FOR APPROACHES, 9 IN.	9.00	SYS

0042	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0043	621-06560	MULCHED SEEDING U	481.00 SYS
0044	621-06567	WATER	1.00 KGAL
0045	621-06570	TOPSOIL	10.00 CYS
0046	621-06575	SODDING, NURSERY	445.00 SYS
0047	628-09401	FIELD OFFICE, A	12.00 MOS
0048	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0049	628-12685	TELEPHONE SERVICE, A	12.00 MOS
0050	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	18.00 LFT
0051	715-09064	VIDEO INSPECTION FOR PIPE	18.00 LFT
0052	720-44000	CASTING, ADJUST TO GRADE	17.00 EACH
0053	720-44070	CASTING, 13, FURNISH AND ADJUST TO GRADE	1.00 EACH
0054	720-45010	INLET, A3	1.00 EACH
0055	720-45045	INLET, J10	1.00 EACH
0056	801-02595	CONTROLLER RESET TIMING	7.00 EACH
0057	801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.00 EACH
0058	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4320.00 LFT
0059	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	1584.00 LFT
0060	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	13.00 EACH
0061	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	144.00 LFT
0062	801-06625	DETOUR ROUTE MARKER ASSEMBLY	4.00 EACH
0063	801-06640	CONSTRUCTION SIGN, A	108.00 EACH
0064	801-06645	CONSTRUCTION SIGN, B	118.00 EACH
0065	801-06710	FLASHING ARROW SIGN	218.00 DAY
0066	801-06775	MAINTAINING TRAFFIC	1.00 LS
0067	801-07118	BARRICADE, III-A	207.00 LFT
0068	801-07119	BARRICADE, III-B	198.00 LFT
0069	801-11990	TEMPORARY CURB RAMP	33.00 EACH
0070	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	654.00 SYS
0071	802-07060	SIGN, SHEET, RELOCATE	2.00 EACH
0072	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	57.00 SFT
0073	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	216.00 SFT
0074	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.00 EACH
0075	805-01842	HANDHOLE SIGNAL TYPE 1	3.00 EACH
0076	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	3.00 EACH
0077	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	795.00 LFT
0078	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	8.00 EACH
0079	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	52.00 EACH
0080	805-04133	SIGNAL POLE, PEDESTAL, 12FT	20.00 EACH
0081	805-05405	SIGNAL POLE, PEDESTAL, 4FT	32.00 EACH
0082	805-06595	CONDUIT, PVC, 2 IN.	490.00 LFT
0083	805-11799	RECTANGULAR RAPID FLASHING BEACON	12.00 EACH



0084	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00 EACH
0085	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	44.00 EACH
0086	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	3440.00 LFT
0087	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	6890.00 LFT
0088	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	1192.00 LFT
0089	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	4174.00 LFT
0090	805-78785	SIGNAL DETECTOR HOUSING	8.00 EACH
0091	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1112.00 LFT
0092	805-96309	PEDESTRIAN PUSH BUTTON, RETROFIT	4.00 EACH
0093	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	3173.00 LFT
0094	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	240.00 LFT
0095	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	286.00 LFT
0096	808-06716	LINE, REMOVE	1032.00 LFT
0097	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	15.00 LFT
0098	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	426.00 LFT
0099	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	956.00 LFT
0100	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	1243.00 LFT
0101	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	6.00 EACH