

Schedule of Pav Items Letting Date May 5, 2021 Letting ID 210505

Call: 120

Contract: R -37922-A

Section No.: 1 ROAD RECONSTRUCTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	50.00	SYS
0013	202-90747	RETAINING WALL, REMOVE	154.00	LFT
0014	202-96430	FENCE AND POSTS, REMOVE	1.00	LS
0015	203-02000	EXCAVATION, COMMON	7914.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	20900.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	2532.00	SYS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	23240.00	SYS
0021	211-09265	STRUCTURE BACKFILL, TYPE 2	642.00	CYS
0022	214-11796	GEOGRID, TYPE IB	1234.00	SYS
0023	301-12232	COMPACTED AGGREGATE NO. 5	415.00	CYS
0024	301-12234	COMPACTED AGGREGATE NO. 53	1704.00	CYS
0025	302-07455	DENSE GRADED SUBBASE	284.00	CYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	438.00	TON
0027	303-07449	COMPACTED AGGREGATE NO. 73	47.00	TON
0028	304-07494	WIDENING WITH HMA, TYPE C	146.00	TON
0029	304-12625	HMA PATCHING FULL DEPTH TYPE C	20.00	TON
0030	306-08038	MILLING, ASPHALT, 4 IN.	10444.00	SYS
0031	306-08042	MILLING, SCARIFICATION	17433.00	SYS

0032	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	2255.00	TON
0033	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	3758.00	TON
0034	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	6047.00	TON
0035	401-10258	JOINT ADHESIVE, SURFACE	15951.00	LFT
0036	401-10259	JOINT ADHESIVE, INTERMEDIATE	15951.00	LFT
0037	401-11785	LIQUID ASPHALT SEALANT	15951.00	LFT
0038	402-10086	HMA FOR TEMPORARY PAVEMENT, C	42.00	TON
0039	406-05520	ASPHALT FOR TACK COAT	19.00	TON
0040	601-02241	GUARDRAIL, REMOVE	60.00	LFT
0041	604-06070	SIDEWALK, CONCRETE	4.00	SYS
0042	605-06120	CURB, CONCRETE	154.00	LFT
0043	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	3615.00	LFT
0044	605-08636	CURB AND GUTTER, TURNOUT COMBINED	173.00	LFT
0045	605-97305	CURB AND GUTTER, TURNOUT COMBINED MODIFIED	1.00	EACH
0046	605-97937	CURB AND GUTTER, ROLL CURB	186.00	LFT
0047	610-07487	HMA FOR APPROACHES, TYPE B	392.00	TON
0048	610-08446	PCCP FOR APPROACHES, 6 IN.	795.00	SYS
0049	610-09108	PCCP FOR APPROACHES, 9 IN.	888.00	SYS
0050	611-06497	MAILBOX ASSEMBLY, SINGLE	24.00	EACH
0051	611-06498	MAILBOX ASSEMBLY, DOUBLE	12.00	EACH
0052	615-01469	MONUMENT SECTION CORNER INSTALL	3.00	EACH
0053	615-06505	MONUMENT, B	8.00	EACH
0054	616-06405	RIPRAP, REVETMENT	145.00	TON
0055	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	424.00	SYS
0056	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	4653.00	SYS
0057	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0058	621-06545	FERTILIZER	2.00	TON
0059	621-06554	SEED MIXTURE U	550.00	LBS
0060	621-06565	MULCHING MATERIAL	6.00	TON
0061	621-06567	WATER	5.00	KGAL
0062	621-06575	SODDING, NURSERY	50.00	SYS
0063	628-09403	FIELD OFFICE, C	20.00	MOS
0064	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0065	715-05118	PIPE, TYPE 1, CIRCULAR, 12 IN.	709.00	LFT
0066	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	60.00	LFT
0067	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	67.00	LFT
0068	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	62.00	LFT

0069	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	739.00	LFT
0070	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	698.00	LFT
0071	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	1119.00	LFT
0072	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	42.00	LFT
0073	715-05233	PIPE, TYPE 1, DEFORMED, MIN. AREA 3.3 SFT	11.00	LFT
0074	715-06471	PIPE END SECTION, MIN. AREA 3.3 SFT	2.00	EACH
0075	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	30.00	TON
0076	715-46000	PIPE END SECTION, DIAMETER 12 IN.	63.00	EACH
0077	715-46005	PIPE END SECTION, DIAMETER 15 IN.	5.00	EACH
0078	715-46010	PIPE END SECTION, DIAMETER 18 IN.	5.00	EACH
0079	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	EACH
0080	720-02367	MANHOLE, J10	1.00	EACH
0081	720-44000	CASTING, ADJUST TO GRADE	10.00	EACH
0082	720-45030	INLET, E7	2.00	EACH
0083	720-45035	INLET, F7	6.00	EACH
0084	720-45045	INLET, J10	1.00	EACH
0085	720-45055	INLET, M10	3.00	EACH
0086	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0087	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	17953.00	LFT
0088	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	6260.00	LFT
0089	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	365.00	LFT
0090	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	3.00	EACH
0091	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00	EACH
0092	801-06640	CONSTRUCTION SIGN, A	17.00	EACH
0093	801-06645	CONSTRUCTION SIGN, B	25.00	EACH
0094	801-06775	MAINTAINING TRAFFIC	1.00	LS
0095	801-07119	BARRICADE, III-B	190.00	LFT
0096	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	634.00	LFT
0097	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	254.00	SFT
0098	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	71.00	SFT
0099	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	7441.00	LFT
0100	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0101	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	170.00	LFT
0102	808-12032	GROOVING FOR PAVEMENT MARKINGS	22925.00	LFT
0103	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	2942.00	LFT
0104	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	12010.00	LFT
0105	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	362.00	LFT

0106	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	23.00 EACH
------	-----------	---	------------

Call: 130

Contract: R -40179-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	202-06580	CONTAMINATED SOIL, REMOVE	1.00	CYS
0010	203-02000	EXCAVATION, COMMON	400.00	CYS
0011	205-12108	STORMWATER MANAGEMENT BUDGET	6100.00	DOL
0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0013	205-12618	SWQCP PREPARATION	1.00	LS
0014	207-08264	SUBGRADE TREATMENT, TYPE II	1698.00	SYS
0015	207-09935	SUBGRADE TREATMENT, TYPE IC	574.00	SYS
0016	301-12234	COMPACTED AGGREGATE NO. 53	186.00	CYS
0017	401-10258	JOINT ADHESIVE, SURFACE	101.00	LFT
0018	401-10259	JOINT ADHESIVE, INTERMEDIATE	101.00	LFT
0019	401-11785	LIQUID ASPHALT SEALANT	101.00	LFT
0020	406-05520	ASPHALT FOR TACK COAT	0.10	TON
0021	603-02736	FENCE, WOOD, RESET	35.00	LFT
0022	604-06070	SIDEWALK, CONCRETE	1097.00	SYS
0023	604-08086	CURB RAMP, CONCRETE	28.00	SYS
0024	604-12083	DETECTABLE WARNING SURFACES	7.00	SYS
0025	605-06140	CURB AND GUTTER, CONCRETE	1185.00	LFT
0026	610-07487	HMA FOR APPROACHES, TYPE B	315.00	TON
0027	610-08446	PCCP FOR APPROACHES, 6 IN.	301.00	SYS
0028	610-09108	PCCP FOR APPROACHES, 9 IN.	212.00	SYS
0029	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	9.00	EACH
0030	616-06405	RIPRAP, REVETMENT	14.00	TON
0031	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	44.00	SYS

0032	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0033	621-06560	MULCHED SEEDING U	981.00 SYS
0034	628-09403	FIELD OFFICE, C	6.00 MOS
0035	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0036	720-45030	INLET, E7	1.00 EACH
0037	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7048.00 LFT
0038	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	2611.00 LFT
0039	801-06640	CONSTRUCTION SIGN, A	8.00 EACH
0040	801-06775	MAINTAINING TRAFFIC	1.00 LS
0041	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	21.00 LFT
0042	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	18.00 SFT
0043	802-91122	SIGN GROUND MOUNTED RESET	3.00 EACH
0044	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	101.00 LFT
0045	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	30.00 LFT

Call: 140

Contract: R -40506-A

Section No.: 1 ROAD RECONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0009	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0013	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0014	202-02240	PAVEMENT REMOVAL	68316.00 SYS
0015	202-12024	CABLE BARRIER, REMOVE	7482.00 LFT
0016	202-93741	GUARDRAIL, END TREATMENT, REMOVE	15.00 EACH
0017	203-02000	EXCAVATION, COMMON	41791.00 CYS
0018	205-12108	STORMWATER MANAGEMENT BUDGET	42100.00 DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0020	205-12618	SWQCP PREPARATION	1.00 LS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	13410.00 SYS
0022	207-12635	SUBGRADE TREATMENT, TYPE IBC	74094.00 SYS
0023	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	81228.00 SYS
0024	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	16444.00 SYS
0025	301-12231	COMPACTED AGGREGATE NO. 2	4470.00 CYS
0026	301-12234	COMPACTED AGGREGATE NO. 53	12136.00 CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	36778.00 TON
0028	306-08038	MILLING, ASPHALT, 4 IN.	19922.00 SYS
0029	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	3024.00 TON
0030	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	2009.00 TON
0031	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	3017.00 TON

0032	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	7370.00	TON
0033	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	8799.00	TON
0034	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	33489.00	TON
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	31299.00	LFT
0036	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	11579.00	TON
0037	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0038	401-12439	VOID REDUCING ASPHALT MEMBRANE	31299.00	LFT
0039	402-10087	HMA FOR TEMPORARY PAVEMENT, D	7343.00	TON
0040	406-05520	ASPHALT FOR TACK COAT	79.00	TON
0041	410-09530	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm - SMA	4386.00	TON
0042	601-02241	GUARDRAIL, REMOVE	6419.00	LFT
0043	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	5200.00	LFT
0044	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	3.00	EACH
0045	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	12.00	EACH
0046	601-94689	GUARDRAIL, END TREATMENT, OS	15.00	EACH
0047	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	31296.00	LFT
0048	616-05688	RIPRAP, CLASS 1	195.00	TON
0049	616-05689	RIPRAP, CLASS 2	36.00	TON
0050	616-06405	RIPRAP, REVETMENT	96.00	TON
0051	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	532.00	SYS
0052	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	12.00	EACH
0053	621-06559	MULCHED SEEDING R	50779.00	SYS
0054	621-06574	SODDING	4409.00	SYS
0055	627-09327	CABLE BARRIER SYSTEM, TYPE TL-4	7482.00	LFT
0056	627-09331	SAFETY TERMINAL TYPE, TL-4	12.00	EACH
0057	627-10178	CABLE BARRIER SYSTEM, TYPE TL-4 SPARE PARTS	1.00	LS
0058	628-09403	FIELD OFFICE, C	18.00	MOS
0059	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	31114.00	LFT
0060	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	4367.00	LFT
0061	718-04986	CLEANOUT	113.00	EACH
0062	718-06531	OUTLET PROTECTOR, 3	63.00	EACH
0063	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	12000.00	LFT
0064	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	17763.00	SYS
0065	718-52610	AGGREGATE FOR UNDERDRAINS	1886.00	CYS
0066	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	375201.00	LFT
0067	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	15127.00	LFT
0068	801-06640	CONSTRUCTION SIGN, A	61.00	EACH

0069	801-06645	CONSTRUCTION SIGN, B	19.00 EACH
0070	801-06710	FLASHING ARROW SIGN	360.00 DAY
0071	801-06775	MAINTAINING TRAFFIC	1.00 LS
0072	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	8.00 EACH
0073	801-07118	BARRICADE, III-A	160.00 LFT
0074	801-07119	BARRICADE, III-B	280.00 LFT
0075	801-07606	TEMPORARY Crossover DRAINAGE PIPE	4053.00 LFT
0076	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	19329.00 LFT
0077	801-08507	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 1	1032.00 LFT
0078	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	8.00 EACH
0079	801-52817	TEMPORARY Crossover, B	6.00 EACH
0080	801-97643	TEMPORARY BUZZ STRIPS	1728.00 LFT
0081	802-91122	SIGN GROUND MOUNTED RESET	9.00 EACH
0082	804-11920	DELINEATOR POST FLEXIBLE, TYPE I	176.00 EACH
0083	808-06702	LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	34089.00 LFT
0084	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	50879.00 LFT
0085	808-06716	LINE, REMOVE	131381.00 LFT
0086	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0087	808-12032	GROOVING FOR PAVEMENT MARKINGS	35226.00 LFT
0088	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	44287.00 LFT
0089	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	200.00 EACH
0090	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	200.00 EACH

Call: 144

Contract: R -40625-B

Section No.: 1 ROAD RECONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-02240	PAVEMENT REMOVAL	3500.00 SYS
0012	202-02278	CURB, CONCRETE, REMOVE	1688.00 LFT
0013	202-06541	REMOVE	5.00 EACH
0014	202-52710	SIDEWALK CONCRETE, REMOVE	952.00 SYS
0015	202-91385	INLET, REMOVE	7.00 EACH
0016	202-93047	MANHOLE, REMOVE	3.00 EACH
0017	202-96133	PIPE, REMOVE	500.00 LFT
0018	202-97009	FIRE HYDRANT ASSEMBLY, REMOVE	2.00 EACH
0019	203-02000	EXCAVATION, COMMON	1795.00 CYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	5227.00 DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0022	205-12618	SWQCP PREPARATION	1.00 LS
0023	207-08264	SUBGRADE TREATMENT, TYPE II	5840.00 SYS
0024	211-09265	STRUCTURE BACKFILL, TYPE 2	2427.00 CYS
0025	211-09265	STRUCTURE BACKFILL, TYPE 2	817.00 CYS
0026	301-12234	COMPACTED AGGREGATE NO. 53	660.00 CYS
0027	302-07455	DENSE GRADED SUBBASE	170.00 CYS
0028	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	310.00 TON
0029	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	725.00 TON
0030	401-10258	JOINT ADHESIVE, SURFACE	1450.00 LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	1450.00 LFT

0032	401-11785	LIQUID ASPHALT SEALANT	1450.00	LFT
0033	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0034	604-06070	SIDEWALK, CONCRETE	730.00	SYS
0035	604-08086	CURB RAMP, CONCRETE	140.00	SYS
0036	604-12083	DETECTABLE WARNING SURFACES	20.00	SYS
0037	605-06140	CURB AND GUTTER, CONCRETE	1880.00	LFT
0038	610-07788	HMA FOR APPROACHES, TYPE D	30.00	TON
0039	610-08446	PCCP FOR APPROACHES, 6 IN.	100.00	SYS
0040	610-09108	PCCP FOR APPROACHES, 9 IN.	890.00	SYS
0041	615-06505	MONUMENT, B	2.00	EACH
0042	616-11736	DECORATIVE STONE	90.00	TON
0043	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	450.00	SYS
0044	618-06192	WALL	85.00	LFT
0045	621-06575	SODDING, NURSERY	1620.00	SYS
0046	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0047	715-01902	WATER SERVICE LINE, 2 IN	150.00	LFT
0048	715-03033	BLOW OFF ASSEMBLY	1.00	EACH
0049	715-05146	PIPE, TYPE 2, CIRCULAR, 6 IN.	54.00	LFT
0050	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	978.00	LFT
0051	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	304.00	LFT
0052	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	119.00	LFT
0053	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	160.00	LFT
0054	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	739.00	LFT
0055	715-09064	VIDEO INSPECTION FOR PIPE	1648.00	LFT
0056	715-09883	VALVE WITH BOX	2.00	EACH
0057	715-12674	GATE VALVE AND VALVE BOX 12 IN	4.00	EACH
0058	715-90853	TAPPING SLEEVE WITH VALVE	1.00	EACH
0059	715-90853	TAPPING SLEEVE WITH VALVE	2.00	EACH
0060	715-90853	TAPPING SLEEVE WITH VALVE	2.00	EACH
0061	715-91739	WATER SERVICE LINE, 0.75 IN	70.00	LFT
0062	715-92525	WATER MAIN, 10 IN	14.00	LFT
0063	715-93403	WATER SERVICE CONNECTION, 0.75 IN.	3.00	EACH
0064	715-93911	WATER MAIN, 4 IN	90.00	LFT
0065	715-93913	WATER MAIN, 8 IN.	42.00	LFT
0066	715-96670	WATER MAIN, DUCTILE IRON, 12 IN.	1286.00	LFT
0067	720-44000	CASTING, ADJUST TO GRADE	4.00	EACH
0068	720-45045	INLET, J10	20.00	EACH

0069	720-45055	INLET, M10	26.00 EACH
0070	720-45415	MANHOLE, D4	12.00 EACH
0071	720-96999	FIRE HYDRANT ASSEMBLY	4.00 EACH
0072	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00 EACH
0073	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	2102.00 LFT
0074	801-06625	DETOUR ROUTE MARKER ASSEMBLY	18.00 EACH
0075	801-06640	CONSTRUCTION SIGN, A	8.00 EACH
0076	801-06645	CONSTRUCTION SIGN, B	15.00 EACH
0077	801-06775	MAINTAINING TRAFFIC	1.00 LS
0078	801-07119	BARRICADE, III-B	96.00 LFT
0079	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	174.00 LFT
0080	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	19.00 EACH
0081	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	9.00 SFT
0082	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	76.00 SFT
0083	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2240.00 LFT
0084	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	72.00 LFT
0085	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	188.00 LFT

Call: 150

Contract: R -40821-A

Section No.: 1 STORM SEWER REPAIR OR REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	1.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00 LS
0013	202-02637	PIPE ABANDON AND GROUT FILL	1900.00 LFT
0014	202-91385	INLET, REMOVE	11.00 EACH
0015	202-96133	PIPE, REMOVE	200.00 LFT
0016	203-02000	EXCAVATION, COMMON	710.00 CYS
0017	203-02070	BORROW	65.00 CYS
0018	205-11626	PUMP AROUND	1.00 EACH
0019	205-12108	STORMWATER MANAGEMENT BUDGET	7745.00 DOL
0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0021	205-12618	SWQCP PREPARATION	1.00 LS
0022	207-08264	SUBGRADE TREATMENT, TYPE II	1402.00 SYS
0023	207-12498	SUBGRADE TREATMENT, TYPE ID	1828.00 SYS
0024	211-09265	STRUCTURE BACKFILL, TYPE 2	3383.00 CYS
0025	211-09268	STRUCTURE BACKFILL, TYPE 5	377.00 CYS
0026	214-11796	GEOGRID, TYPE IB	638.00 SYS
0027	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	258.00 SYS
0028	301-12233	COMPACTED AGGREGATE NO. 8	36.00 CYS
0029	301-12234	COMPACTED AGGREGATE NO. 53	146.00 CYS
0030	303-01180	COMPACTED AGGREGATE NO. 53	872.00 TON
0031	303-07449	COMPACTED AGGREGATE NO. 73	54.00 TON

0032	304-07494	WIDENING WITH HMA, TYPE C	183.00 TON
0033	306-08043	MILLING, TRANSITION	317.00 SYS
0034	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	143.00 TON
0035	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	149.00 TON
0036	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	476.00 TON
0037	406-05520	ASPHALT FOR TACK COAT	2.00 TON
0038	605-06120	CURB, CONCRETE	59.00 LFT
0039	610-07487	HMA FOR APPROACHES, TYPE B	525.00 TON
0040	615-06490	RIGHT-OF-WAY MARKER	18.00 EACH
0041	615-06505	MONUMENT, B	2.00 EACH
0042	615-06527	MONUMENT, SECTION CORNER	1.00 EACH
0043	616-06405	RIPRAP, REVETMENT	124.00 TON
0044	616-06451	RIPRAP, UNIFORM	18.00 TON
0045	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	257.00 SYS
0046	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0047	621-06559	MULCHED SEEDING R	466.00 SYS
0048	621-06575	SODDING, NURSERY	1678.00 SYS
0049	628-09403	FIELD OFFICE, C	6.00 MOS
0050	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0051	714-12519	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 9 FT X 6 FT	66.00 LFT
0052	715-05032	PIPE, TYPE 2, CIRCULAR, 15 IN.	32.00 LFT
0053	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	39.00 LFT
0054	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	91.00 LFT
0055	715-05153	PIPE, TYPE 2, CIRCULAR, 21 IN.	8.00 LFT
0056	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	42.00 LFT
0057	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	1725.00 LFT
0058	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	202.00 LFT
0059	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	40.00 LFT
0060	715-06004	CONCRETE ANCHOR, 48 IN.	1.00 EACH
0061	715-09064	VIDEO INSPECTION FOR PIPE	2139.00 LFT
0062	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00 EACH
0063	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00 EACH
0064	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00 EACH
0065	720-45030	INLET, E7	11.00 EACH
0066	720-45130	INLET, E7 MODIFIED	3.00 EACH
0067	720-93501	MANHOLE, L4	1.00 EACH
0068	720-94612	MANHOLE, K4	14.00 EACH

0069	720-98869	MANHOLE, L4 MODIFIED	1.00 EACH
0070	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00 EACH
0071	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2035.00 LFT
0072	801-06625	DETOUR ROUTE MARKER ASSEMBLY	25.00 EACH
0073	801-06640	CONSTRUCTION SIGN, A	28.00 EACH
0074	801-06775	MAINTAINING TRAFFIC	1.00 LS
0075	801-07118	BARRICADE, III-A	96.00 LFT
0076	801-07119	BARRICADE, III-B	48.00 LFT
0077	802-04893	REFERENCE POST	2.00 EACH
0078	802-91122	SIGN GROUND MOUNTED RESET	2.00 EACH
0079	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2204.00 LFT
0080	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	43.00 LFT
0081	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	4.00 EACH
0082	808-12032	GROOVING FOR PAVEMENT MARKINGS	2247.00 LFT
0083	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.00 EACH
0084	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2.00 EACH

Call: 160

Contract: R -40853-A

Section No.: 1 ENVIRONMENTAL MITIGATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	201-06587	CLEARING AND GRUBBING	1.50 ACRE
0010	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00 LS
0011	203-02000	EXCAVATION, COMMON	2255.00 CYS
0012	203-02020	EXCAVATION, UNCLASSIFIED	20772.00 CYS
0013	204-12510	MONITORING WELL	2.00 EACH
0014	205-12108	STORMWATER MANAGEMENT BUDGET	37003.00 DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0016	205-12618	SWQCP PREPARATION	1.00 LS
0017	603-06040	FENCE, FARM FIELD, 47 IN.	110.00 LFT
0018	603-91748	FENCE GATE, FARM FIELD, 47 IN. X 16 FT	1.00 EACH
0019	616-05688	RIPRAP, CLASS 1	2226.00 TON
0020	616-05689	RIPRAP, CLASS 2	4305.00 TON
0021	616-06396	RIPRAP	2700.00 TON
0022	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	120.00 SYS
0023	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0024	621-02770	EROSION CONTROL BLANKET	7920.00 SYS
0025	621-04258	SEED MIXTURE	97.80 LBS
0026	621-04258	SEED MIXTURE	4300.80 LBS
0027	621-04258	SEED MIXTURE	1669.50 LBS
0028	621-06545	FERTILIZER	2.00 TON
0029	621-06565	MULCHING MATERIAL	44.00 TON
0030	621-06737	SEED MIXTURE, EMERGENT WETLAND	54.00 LBS
0031	621-09508	INVASIVE SPECIES CONTROL	1.00 LS

0032	622-05641	PLANT, DECIDUOUS SHRUB, 36 TO 48 IN.	1484.00 EACH
0033	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	9829.00 EACH
0034	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	7.00 EACH
0035	622-10003	LIVE PLANT STAKING	2995.00 EACH
0036	622-10003	LIVE PLANT STAKING	3650.00 EACH
0037	622-91786	SEEDLING	49141.00 EACH
0038	622-98200	SIGN, DO NOT DISTURB	159.00 EACH
0039	624-92647	HERBICIDE TREATMENT	125.00 ACRE
0040	628-09403	FIELD OFFICE, C	24.00 MOS
0041	628-11730	CELLULAR TELEPHONE, TYPE B	1.00 EACH
0042	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0043	628-11783	CELLULAR TELEPHONE SERVICE, 2000 MIN.	24.00 MOS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0045	628-11977	COMPUTER SYSTEM	1.00 EACH
0046	712-99107	LOG DEFLECTOR	14.00 EACH
0047	713-04643	TEMPORARY ACCESS LANE	1.00 LS
0048	719-09505	TILE INTERCEPT TRENCH EXCAVATION AND LOCATION	350.00 LFT
0049	801-06640	CONSTRUCTION SIGN, A	17.00 EACH
0050	801-06775	MAINTAINING TRAFFIC	1.00 LS
0051	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	24.00 SFT
0052	802-96994	SIGN POST, WOOD 4 IN. X 6 IN.	80.00 LFT
0053	804-06770	DELINEATOR POST	157.00 EACH

Call: 170

Contract: R -40869-A

Section No.: 1 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	6229.00	SYS
0014	202-02273	CENTER CURB, CONCRETE, REMOVE	522.00	SYS
0015	202-02278	CURB, CONCRETE, REMOVE	3704.00	LFT
0016	202-02279	CURB AND GUTTER, REMOVE	363.00	LFT
0017	202-02928	CATCH BASIN, REMOVE	10.00	EACH
0018	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00	LS
0019	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0020	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0021	202-52710	SIDEWALK CONCRETE, REMOVE	246.00	SYS
0022	202-93047	MANHOLE, REMOVE	2.00	EACH
0023	202-93741	GUARDRAIL, END TREATMENT, REMOVE	1.00	EACH
0024	202-93763	LIGHT STANDARD AND FOUNDATION, REMOVE	3.00	EACH
0025	202-93995	SIGNAL POLE FOUNDATION, REMOVE	4.00	EACH
0026	202-93999	SIGNAL POLE, REMOVE	4.00	EACH
0027	202-95027	IMPACT ATTENUATOR, REMOVE	2.00	EACH
0028	202-96133	PIPE, REMOVE	1304.00	LFT
0029	203-02000	EXCAVATION, COMMON	21445.00	CYS
0030	203-02070	BORROW	3475.00	CYS
0031	205-12108	STORMWATER MANAGEMENT BUDGET	116170.00	DOL

0032	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0033	205-12618	SWQCP PREPARATION	1.00	LS
0034	207-08264	SUBGRADE TREATMENT, TYPE II	867.00	SYS
0035	207-12498	SUBGRADE TREATMENT, TYPE ID	820.00	SYS
0036	207-12635	SUBGRADE TREATMENT, TYPE IBC	13999.00	SYS
0037	211-09265	STRUCTURE BACKFILL, TYPE 2	744.00	CYS
0038	211-09268	STRUCTURE BACKFILL, TYPE 5	6.00	CYS
0039	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	410.00	SYS
0040	301-12232	COMPACTED AGGREGATE NO. 5	17.00	CYS
0041	301-12234	COMPACTED AGGREGATE NO. 53	1309.00	CYS
0042	303-01180	COMPACTED AGGREGATE NO. 53	1459.00	TON
0043	401-07334	QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	993.00	TON
0044	401-07403	QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	1755.00	TON
0045	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	5742.00	TON
0046	401-10258	JOINT ADHESIVE, SURFACE	7696.00	LFT
0047	401-10259	JOINT ADHESIVE, INTERMEDIATE	7696.00	LFT
0048	401-11785	LIQUID ASPHALT SEALANT	7696.00	LFT
0049	401-12138	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 25.0 mm	880.00	TON
0050	402-10086	HMA FOR TEMPORARY PAVEMENT, C	190.00	TON
0051	406-05520	ASPHALT FOR TACK COAT	14.00	TON
0052	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	180.00	SFT
0053	601-02241	GUARDRAIL, REMOVE	979.00	LFT
0054	601-06246	IMPACT ATTENUATOR, R2-W1, TL-3	2.00	EACH
0055	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	550.00	LFT
0056	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	1.00	EACH
0057	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	2.00	EACH
0058	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0059	602-06729	BARRIER, DELINEATOR	5.00	EACH
0060	603-06045	FENCE, CHAIN LINK, 48 IN.	409.00	LFT
0061	604-06070	SIDEWALK, CONCRETE	591.00	SYS
0062	604-08086	CURB RAMP, CONCRETE	139.00	SYS
0063	604-12083	DETECTABLE WARNING SURFACES	25.00	SYS
0064	605-02493	CURB, ISLAND CONCRETE	1869.00	SYS
0065	605-06120	CURB, CONCRETE	1787.00	LFT
0066	605-06121	CURB, CONCRETE B	1688.00	LFT
0067	605-06235	CENTER CURB, D CONCRETE MODIFIED	1388.00	LFT
0068	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	23.00	LFT

0069	605-52807	CURB AND GUTTER, COMBINED	2542.00	LFT
0070	610-07487	HMA FOR APPROACHES, TYPE B	92.00	TON
0071	610-09108	PCCP FOR APPROACHES, 9 IN.	202.00	SYS
0072	615-06490	RIGHT-OF-WAY MARKER	21.00	EACH
0073	615-06505	MONUMENT, B	9.00	EACH
0074	616-06405	RIPRAP, REVETMENT	384.00	TON
0075	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	656.00	SYS
0076	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0077	621-06545	FERTILIZER	2.00	TON
0078	621-06554	SEED MIXTURE U	659.00	LBS
0079	621-06565	MULCHING MATERIAL	7.00	TON
0080	621-06567	WATER	7.00	kGAL
0081	621-06574	SODDING	329.00	SYS
0082	621-06575	SODDING, NURSERY	1363.00	SYS
0083	628-09403	FIELD OFFICE, C	24.00	MOS
0084	702-51005	CONCRETE, A, SUBSTRUCTURE	8.00	CYS
0085	702-51015	CONCRETE, B, FOOTINGS	7.00	CYS
0086	703-06029	REINFORCING BARS, EPOXY COATED	8556.00	LBS
0087	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	2.00	EACH
0088	706-11404	RAILING, STEEL PF-1	109.00	LFT
0089	706-11602	RAILING, CONCRETE PF-1	38.00	CYS
0090	709-51821	SURFACE SEAL	1.00	LS
0091	709-51821	SURFACE SEAL	1.00	LS
0092	709-51821	SURFACE SEAL	1.00	LS
0093	710-09158	PATCHING CONCRETE STRUCTURES	680.00	SFT
0094	711-04121	ANCHOR BOLT, AB1	16.00	EACH
0095	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	2115.00	LFT
0096	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	105.00	LFT
0097	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	208.00	LFT
0098	715-05146	PIPE, TYPE 2, CIRCULAR, 6 IN.	14.00	LFT
0099	715-05147	PIPE, TYPE 2, CIRCULAR, 8 IN.	6.00	LFT
0100	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1196.00	LFT
0101	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	48.00	LFT
0102	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	1182.00	LFT
0103	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	155.00	LFT
0104	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	882.00	LFT
0105	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	98.00	LFT

0106	715-05889	PIPE EXTENSION, CIRCULAR, 30 IN.	65.00	LFT
0107	715-08306	HMA FOR STRUCTURE INSTALLATION, TYPE C	53.00	TON
0108	715-09064	VIDEO INSPECTION FOR PIPE	3483.00	LFT
0109	715-46000	PIPE END SECTION, DIAMETER 12 IN.	19.00	EACH
0110	715-46005	PIPE END SECTION, DIAMETER 15 IN.	4.00	EACH
0111	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0112	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	EACH
0113	715-46030	PIPE END SECTION, DIAMETER 30 IN.	3.00	EACH
0114	718-06529	OUTLET PROTECTOR, 2	2.00	EACH
0115	718-06531	OUTLET PROTECTOR, 3	2.00	EACH
0116	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	1598.00	SYS
0117	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	132.00	SYS
0118	718-52610	AGGREGATE FOR UNDERDRAINS	198.00	CYS
0119	720-01092	MANHOLE, J15 MODIFIED	1.00	EACH
0120	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00	EACH
0121	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00	EACH
0122	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00	EACH
0123	720-03757	MANHOLE, C15	6.00	EACH
0124	720-03757	MANHOLE, C15	3.00	EACH
0125	720-44000	CASTING, ADJUST TO GRADE	3.00	EACH
0126	720-44000	CASTING, ADJUST TO GRADE	1.00	EACH
0127	720-45030	INLET, E7	1.00	EACH
0128	720-45040	INLET, G7	2.00	EACH
0129	720-45042	INLET, HA5	14.00	EACH
0130	720-45045	INLET, J10	10.00	EACH
0131	720-45410	MANHOLE, C4	4.00	EACH
0132	720-95310	INLET, P12A MODIFIED	5.00	EACH
0133	720-95422	MANHOLE, J4	1.00	EACH
0134	720-98068	MANHOLE, E2	1.00	EACH
0135	720-98174	INLET, B15	13.00	EACH
0136	720-98555	INLET, C15	4.00	EACH
0137	722-01066	HYDRODEMOLITION	2750.00	SYS
0138	722-12380	BRIDGE DECK OVERLAY, BUDGET	51992.00	DOL
0139	722-12381	BRIDGE DECK OVERLAY, LMC-VE	2750.00	SYS
0140	722-12382	TRANSVERSE GROOVING	2750.00	SYS
0141	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	2750.00	SYS
0142	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	454.00	SFT

0143	722-51874	OVERLAY DAM	556.00	SFT
0144	724-12103	PRE-COMPRESSED FOAM JOINT	322.00	LFT
0145	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	1.00	EACH
0146	801-03290	CONSTRUCTION SIGN, C	5.00	EACH
0147	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0148	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	12168.00	LFT
0149	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	308.00	LFT
0150	801-06625	DETOUR ROUTE MARKER ASSEMBLY	112.00	EACH
0151	801-06640	CONSTRUCTION SIGN, A	80.00	EACH
0152	801-06645	CONSTRUCTION SIGN, B	5.00	EACH
0153	801-06710	FLASHING ARROW SIGN	658.00	DAY
0154	801-06775	MAINTAINING TRAFFIC	1.00	LS
0155	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00	EACH
0156	801-07118	BARRICADE, III-A	376.00	LFT
0157	801-07119	BARRICADE, III-B	48.00	LFT
0158	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	1620.00	LFT
0159	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	6.00	EACH
0160	801-94295	SIGNAL HEAD RELOCATE	6.00	EACH
0161	802-02475	SIGN, PANEL, RELOCATE	1.00	EACH
0162	802-03783	SIGN, PANEL, REMOVE	2.00	EACH
0163	802-04089	SIGN, SHEET, REMOVE	31.00	EACH
0164	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	354.00	LFT
0165	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	55.00	LFT
0166	802-07057	SIGN, PANEL, WITH LEGEND	761.00	SFT
0167	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	25.00	EACH
0168	802-07060	SIGN, SHEET, RELOCATE	4.00	EACH
0169	802-07135	CABLE SPAN SIGN STRUCTURE FOUNDATION, IV	2.00	EACH
0170	802-09222	OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE B	1.00	EACH
0171	802-09537	BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN. MEDIAN OR SHOULDER	2.00	EACH
0172	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	255.00	SFT
0173	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	338.00	SFT
0174	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	84.00	SFT
0175	802-10187	OVERHEAD SIGN STRUCTURE, TRI-CHORD TYPE F	1.00	EACH
0176	802-10194	TRI-CHORD SIGN STRUCTURE FOUNDATION, DRILLED SHAFT	2.00	EACH
0177	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	4.00	EACH
0178	802-74040	SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	2.00	EACH
0179	802-74055	OVERHEAD SIGN STRUCTURE, BOX TRUSS, REMOVE	1.00	EACH

0180	802-76095	STRUCTURAL STEEL, BREAKAWAY	641.00	LBS
0181	802-76125	OVERHEAD SIGN STRUCTURE, CABLESPAN	1.00	EACH
0182	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0183	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00	LS
0184	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	10.00	EACH
0185	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	2772.00	LFT
0186	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	8.00	EACH
0187	805-02445	CONTROLLER AND CABINET, P1	2.00	EACH
0188	805-08244	CELLULAR MODEM KIT	3.00	EACH
0189	805-11378	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 40 FT.	1.00	EACH
0190	805-11382	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 60 FT.	2.00	EACH
0191	805-11384	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, B	3.00	EACH
0192	805-11744	HANDHOLE SIGNAL TYPE 2	22.00	EACH
0193	805-11771	SIGNAL POLE, PEDESTAL, 16 FT	6.00	EACH
0194	805-12016	UNINTERRUPTIBLE POWER SUPPLY	2.00	EACH
0195	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	40.00	EACH
0196	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	5.00	EACH
0197	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	8.00	EACH
0198	805-78415	SPAN, CATENARY, AND TETHER	6.00	EACH
0199	805-78420	DISCONNECT HANGER	9.00	EACH
0200	805-78445	SIGNAL SERVICE	4.00	EACH
0201	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	3170.00	LFT
0202	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	9910.00	LFT
0203	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	4910.00	LFT
0204	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	4430.00	LFT
0205	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	9580.00	LFT
0206	805-78785	SIGNAL DETECTOR HOUSING	23.00	EACH
0207	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2831.00	LFT
0208	805-78925	CONTROLLER CABINET FOUNDATION, P1	2.00	EACH
0209	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	8.00	EACH
0210	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	2.00	EACH
0211	807-02191	HANDHOLE LIGHTING	3.00	EACH
0212	807-02778	LUMINAIRE, MAST ARM, 5 FT	2.00	EACH
0213	807-02934	LIGHTING FOUNDATION, CONCRETE WITH GROUNDING 36 IN. X 36 IN. X 96 IN.	10.00	EACH
0214	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	2.00	EACH
0215	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	10.00	EACH
0216	807-12343	CABLE, POLE CIRCUIT, XHHW, NO 10 COPPER, STRANDED, 1/C	1440.00	LFT

0217	807-85740	LIGHT POLE, 40 FT. E.M.H. 5.0 FT. MAST ARM, BREAKAWAY BASE	5.00 EACH
0218	807-85752	LIGHT POLE, 40 FT. E.M.H. 10.0 FT. MAST ARM, BREAKAWAY BASE	5.00 EACH
0219	807-86805	SERVICE POINT, I	1.00 EACH
0220	807-86910	CONNECTOR KIT, UNFUSED	12.00 EACH
0221	807-86915	CONNECTOR KIT, FUSED	12.00 EACH
0222	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	20.00 EACH
0223	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	10.00 EACH
0224	807-86930	INSULATION LINK, NON-WATERPROOFED	24.00 EACH
0225	807-86935	INSULATION LINK, WATERPROOFED	12.00 EACH
0226	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	1163.00 LFT
0227	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	16.00 SYS
0228	808-05929	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 8 IN.	803.00 LFT
0229	808-06368	TRANSVERSE MARKING, REMOVE	434.00 LFT
0230	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1940.00 LFT
0231	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	14688.00 LFT
0232	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	343.00 LFT
0233	808-06716	LINE, REMOVE	33741.00 LFT
0234	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0235	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	303.00 LFT
0236	808-11493	LINE, THERMOPLASTIC, DOTTED, YELLOW, 4 IN.	129.00 LFT
0237	808-12032	GROOVING FOR PAVEMENT MARKINGS	26078.00 LFT
0238	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	1134.00 LFT
0239	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	1080.00 LFT
0240	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	8675.00 LFT
0241	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	585.00 LFT
0242	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	488.00 LFT
0243	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	38.00 EACH
0244	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	122.00 EACH
0245	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	131.00 EACH

Call: 174

Contract: R -41043-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-02271	HEADWALL, REMOVE	3.00 EACH
0014	202-02278	CURB, CONCRETE, REMOVE	25.00 LFT
0015	202-02279	CURB AND GUTTER, REMOVE	36.00 LFT
0016	202-52710	SIDEWALK CONCRETE, REMOVE	141.00 SYS
0017	202-90277	DETECTOR HOUSING, REMOVE	2.00 EACH
0018	202-96133	PIPE, REMOVE	49.00 LFT
0019	202-98488	PIPE END SECTION, REMOVE	1.00 EACH
0020	203-02000	EXCAVATION, COMMON	685.00 CYS
0021	203-08607	LINEAR GRADING	44.00 LFT
0022	205-12108	STORMWATER MANAGEMENT BUDGET	9028.00 DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0024	205-12618	SWQCP PREPARATION	1.00 LS
0025	207-08264	SUBGRADE TREATMENT, TYPE II	135.00 SYS
0026	207-12498	SUBGRADE TREATMENT, TYPE ID	1985.00 SYS
0027	211-09265	STRUCTURE BACKFILL, TYPE 2	20.00 CYS
0028	214-11796	GEOGRID, TYPE IB	135.00 SYS
0029	303-01180	COMPACTED AGGREGATE NO. 53	235.00 TON
0030	304-07493	WIDENING WITH HMA, TYPE B	70.00 TON
0031	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	356.00 TON

0032	306-08034	MILLING, ASPHALT, 1 1/2 IN.	14035.00	SYS
0033	306-08432	MILLING, APPROACH	1965.00	SYS
0034	306-11872	MILLING, PROFILE	22335.00	SYS
0035	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1158.00	TON
0036	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1845.00	TON
0037	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	320.00	TON
0038	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	645.00	TON
0039	401-10258	JOINT ADHESIVE, SURFACE	22301.00	LFT
0040	401-10259	JOINT ADHESIVE, INTERMEDIATE	2394.00	LFT
0041	401-11785	LIQUID ASPHALT SEALANT	24695.00	LFT
0042	406-05520	ASPHALT FOR TACK COAT	11.50	TON
0043	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0044	603-02736	FENCE, WOOD, RESET	20.00	LFT
0045	604-06070	SIDEWALK, CONCRETE	127.00	SYS
0046	604-08086	CURB RAMP, CONCRETE	95.00	SYS
0047	604-12083	DETECTABLE WARNING SURFACES	19.00	SYS
0048	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	4.00	SYS
0049	604-95344	HAND RAIL, PEDESTRIAN	158.00	LFT
0050	605-06105	CURB, INTEGRAL CONCRETE, MODIFIED	39.00	LFT
0051	605-06140	CURB AND GUTTER, CONCRETE	19.00	LFT
0052	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	112.00	LFT
0053	610-07487	HMA FOR APPROACHES, TYPE B	229.00	TON
0054	615-06490	RIGHT-OF-WAY MARKER	21.00	EACH
0055	615-06505	MONUMENT, B	5.00	EACH
0056	615-06520	MONUMENT, RE-ESTABLISH	4.00	EACH
0057	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0058	621-06560	MULCHED SEEDING U	3725.00	SYS
0059	621-06570	TOPSOIL	130.00	CYS
0060	621-06575	SODDING, NURSERY	11.00	SYS
0061	715-02628	SAFETY METAL END SECTION, 6:1, DIA 15 IN.	2.00	EACH
0062	715-04798	SAFETY METAL END SECTION, 4:1, DIA 21 IN.	1.00	EACH
0063	715-05122	PIPE, TYPE 1, CIRCULAR, 21 IN.	8.00	LFT
0064	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	40.00	LFT
0065	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	63.00	LFT
0066	715-46005	PIPE END SECTION, DIAMETER 15 IN.	3.00	EACH
0067	720-45335	CATCH BASIN, E7 MODIFIED	1.00	EACH
0068	801-03290	CONSTRUCTION SIGN, C	2.00	EACH

0069	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	40239.00	LFT
0070	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	7060.00	LFT
0071	801-06217	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 6 IN.	90.00	LFT
0072	801-06640	CONSTRUCTION SIGN, A	48.00	EACH
0073	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0074	801-06775	MAINTAINING TRAFFIC	1.00	LS
0075	801-07119	BARRICADE, III-B	96.00	LFT
0076	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1810.00	LFT
0077	801-11990	TEMPORARY CURB RAMP	4.00	EACH
0078	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	35.00	SYS
0079	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	133.00	LFT
0080	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	85.00	SFT
0081	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	2.00	EACH
0082	805-11799	RECTANGULAR RAPID FLASHING BEACON	2.00	EACH
0083	805-78370	PEDESTRIAN PUSH BUTTON, NON-APS	2.00	EACH
0084	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	480.00	LFT
0085	805-78785	SIGNAL DETECTOR HOUSING	2.00	EACH
0086	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	320.00	LFT
0087	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	2.00	EACH
0088	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	14303.00	LFT
0089	808-06716	LINE, REMOVE	6425.00	LFT
0090	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0091	808-12032	GROOVING FOR PAVEMENT MARKINGS	28007.00	LFT
0092	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	3100.00	LFT
0093	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	10556.00	LFT
0094	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	184.00	LFT
0095	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	600.00	LFT
0096	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	29.00	EACH
0097	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	2.00	EACH
0098	808-75340	PAVEMENT MESSAGE MARKING, THERMOPLASTIC R X R	1.00	EACH

Call: 176

Contract: R -41069-B

Section No.: 1

SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	205-11626	PUMP AROUND	8.00	EACH
0010	205-12108	STORMWATER MANAGEMENT BUDGET	40000.00	DOL
0011	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0012	205-12618	SWQCP PREPARATION	1.00	LS
0013	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	4.00	SYS
0014	301-12232	COMPACTED AGGREGATE NO. 5	2.00	CYS
0015	301-12234	COMPACTED AGGREGATE NO. 53	2.00	CYS
0016	616-05688	RIPRAP, CLASS 1	70.00	TON
0017	616-06405	RIPRAP, REVETMENT	209.00	TON
0018	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	470.00	SYS
0019	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.00	EACH
0020	621-06559	MULCHED SEEDING R	14680.00	SYS
0021	628-09403	FIELD OFFICE, C	9.00	MOS
0022	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0023	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0024	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0025	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	9.00	MOS
0026	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0027	715-11643	PIPE END SECTION, ENERGY DISSIPATOR	1.00	EACH
0028	725-10014	PIPE LINER CURED-IN-PLACE MIN AREA 8.8 SFT	462.00	LFT
0029	725-11288	PIPE LINER, CURED-IN-PLACE, 60"	304.00	LFT
0030	725-11741	PIPE LINER, CURED-IN-PLACE, MIN AREA 21.9 SFT	159.00	LFT
0031	725-12011	LINER PIPE, INFRASTEEL	658.00	LFT

0032	725-12054	PIPE LINER, CURED-IN-PLACE, MIN AREA 30.1 SFT	408.00	LFT
0033	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 180

Contract: R -41101-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	19.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-02278	CURB, CONCRETE, REMOVE	46.00 LFT
0014	202-02279	CURB AND GUTTER, REMOVE	507.00 LFT
0015	202-52710	SIDEWALK CONCRETE, REMOVE	273.00 SYS
0016	202-90277	DETECTOR HOUSING, REMOVE	19.00 EACH
0017	205-12108	STORMWATER MANAGEMENT BUDGET	2600.00 DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0019	207-12498	SUBGRADE TREATMENT, TYPE ID	994.00 SYS
0020	304-12624	HMA PATCHING PARTIAL DEPTH TYPE B	693.00 TON
0021	304-12625	HMA PATCHING FULL DEPTH TYPE C	875.00 TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	41710.00 SYS
0023	306-08432	MILLING, APPROACH	3685.00 SYS
0024	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	3443.00 TON
0025	401-10258	JOINT ADHESIVE, SURFACE	18814.00 LFT
0026	401-11785	LIQUID ASPHALT SEALANT	18814.00 LFT
0027	406-05520	ASPHALT FOR TACK COAT	11.00 TON
0028	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	3.00 TON
0029	604-06070	SIDEWALK, CONCRETE	189.00 SYS
0030	604-08086	CURB RAMP, CONCRETE	106.00 SYS
0031	604-12083	DETECTABLE WARNING SURFACES	37.00 SYS

0032	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	1.00	SYS
0033	605-06120	CURB, CONCRETE	227.00	LFT
0034	605-06140	CURB AND GUTTER, CONCRETE	507.00	LFT
0035	610-07487	HMA FOR APPROACHES, TYPE B	305.00	TON
0036	621-06575	SODDING, NURSERY	174.00	SYS
0037	628-09403	FIELD OFFICE, C	6.00	MOS
0038	720-44000	CASTING, ADJUST TO GRADE	2.00	EACH
0039	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	11.00	EACH
0040	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	19490.00	LFT
0041	801-06640	CONSTRUCTION SIGN, A	30.00	EACH
0042	801-06645	CONSTRUCTION SIGN, B	13.00	EACH
0043	801-06775	MAINTAINING TRAFFIC	1.00	LS
0044	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	6466.00	LFT
0045	805-78785	SIGNAL DETECTOR HOUSING	19.00	EACH
0046	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2221.00	LFT
0047	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	40.00	LFT
0048	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	18311.00	LFT
0049	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0050	808-12032	GROOVING FOR PAVEMENT MARKINGS	38979.00	LFT
0051	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	20627.00	LFT
0052	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	437.00	LFT
0053	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	367.00	LFT
0054	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	16.00	EACH
0055	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	334.00	EACH
0056	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	334.00	EACH

Call: 190

Contract: R -41540-A

Section No.: 1 ASPHALT RESURFACE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	202-90277	DETECTOR HOUSING, REMOVE	9.00	EACH
0012	202-93741	GUARDRAIL, END TREATMENT, REMOVE	41.00	EACH
0013	202-94749	CURB, ASPHALT, REMOVE	29519.00	LFT
0014	203-02000	EXCAVATION, COMMON	2838.00	CYS
0015	203-02070	BORROW	528.00	CYS
0016	203-08607	LINEAR GRADING	3600.00	LFT
0017	203-08607	LINEAR GRADING	10000.00	LFT
0018	205-12108	STORMWATER MANAGEMENT BUDGET	216597.00	DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	281.00	SYS
0021	207-08266	SUBGRADE TREATMENT, TYPE III	7310.00	SYS
0022	207-12498	SUBGRADE TREATMENT, TYPE ID	11088.00	SYS
0023	301-12234	COMPACTED AGGREGATE NO. 53	1232.00	CYS
0024	303-01180	COMPACTED AGGREGATE NO. 53	820.00	TON
0025	303-07449	COMPACTED AGGREGATE NO. 73	5326.00	TON
0026	304-12625	HMA PATCHING FULL DEPTH TYPE C	2580.00	TON
0027	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	7553.00	TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	464510.00	SYS
0029	306-08432	MILLING, APPROACH	9223.00	SYS
0030	401-06264	PROFILOGRAPH, HMA	1.00	LS
0031	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	38322.00	TON

0032	401-11785	LIQUID ASPHALT SEALANT	323100.00	LFT
0033	401-12439	VOID REDUCING ASPHALT MEMBRANE	227000.00	LFT
0034	402-10086	HMA FOR TEMPORARY PAVEMENT, C	3544.00	TON
0035	406-05520	ASPHALT FOR TACK COAT	122.00	TON
0036	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	20.00	TON
0037	601-02241	GUARDRAIL, REMOVE	31686.00	LFT
0038	601-05999	CURVED TERMINAL END	34.00	EACH
0039	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	34263.00	LFT
0040	601-12286	GUARDRAIL, MGS W-BEAM, SHOP CURVED, 6 FT 3 IN SPACING	100.00	LFT
0041	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	4.00	EACH
0042	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	2.00	EACH
0043	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	5.00	EACH
0044	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	1.00	EACH
0045	601-92948	GUARDRAIL, ADJUST HEIGHT	70.00	LFT
0046	601-94689	GUARDRAIL, END TREATMENT, OS	34.00	EACH
0047	601-94690	GUARDRAIL, END TREATMENT, MS	2.00	EACH
0048	605-05523	CURB, HMA	29859.00	LFT
0049	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	196924.00	LFT
0050	610-07488	HMA FOR APPROACHES, TYPE C	823.00	TON
0051	615-06525	CASTING ADJUST TO GRADE, MONUMENT	2.00	EACH
0052	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0053	621-06559	MULCHED SEEDING R	16680.00	SYS
0054	628-09403	FIELD OFFICE, C	15.00	MOS
0055	628-11729	CELLULAR TELEPHONE, TYPE A	2.00	EACH
0056	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0057	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0058	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	30.00	MOS
0059	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0060	628-12685	TELEPHONE SERVICE, A	15.00	MOS
0061	715-01354	CLEAN EXISTING PIPE	3120.00	LFT
0062	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	5.00	EACH
0063	720-44000	CASTING, ADJUST TO GRADE	4.00	EACH
0064	720-44000	CASTING, ADJUST TO GRADE	104.00	EACH
0065	720-44055	CASTING, 10, FURNISH AND ADJUST TO GRADE	10.00	EACH
0066	720-45615	STRUCTURE, INLET, RECONSTRUCTED	150.00	LFT
0067	720-96995	CLEAN INLET	104.00	EACH
0068	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	22.00	EACH

0069	801-04308	ROAD CLOSURE SIGN ASSEMBLY	31.00 EACH
0070	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	222100.00 LFT
0071	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	491721.00 LFT
0072	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	47.00 EACH
0073	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	1068.00 LFT
0074	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	16000.00 LFT
0075	801-06640	CONSTRUCTION SIGN, A	125.00 EACH
0076	801-06645	CONSTRUCTION SIGN, B	2.00 EACH
0077	801-06710	FLASHING ARROW SIGN	455.00 DAY
0078	801-06775	MAINTAINING TRAFFIC	1.00 LS
0079	801-07118	BARRICADE, III-A	1777.00 LFT
0080	801-07119	BARRICADE, III-B	160.00 LFT
0081	801-07606	TEMPORARY CROSSOVER DRAINAGE PIPE	545.00 LFT
0082	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	5.00 EACH
0083	801-12042	TRUCK MOUNTED ATTENUATOR	245.00 DAY
0084	801-52817	TEMPORARY CROSSOVER, B	1.00 EACH
0085	801-94295	SIGNAL HEAD RELOCATE	11.00 EACH
0086	802-07060	SIGN, SHEET, RELOCATE	80.00 EACH
0087	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	100.00 LFT
0088	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	4050.00 LFT
0089	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	3325.00 LFT
0090	805-78785	SIGNAL DETECTOR HOUSING	9.00 EACH
0091	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1350.00 LFT
0092	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	25.00 SYS
0093	808-06368	TRANSVERSE MARKING, REMOVE	220.00 LFT
0094	808-06716	LINE, REMOVE	82979.00 LFT
0095	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0096	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	118791.00 LFT
0097	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	116686.00 LFT
0098	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	384.00 LFT
0099	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	6.00 EACH
0100	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	47.00 EACH
0101	808-12032	GROOVING FOR PAVEMENT MARKINGS	269621.00 LFT
0102	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	4805.00 LFT
0103	808-75053	LINE, PREFORMED PLASTIC, SOLID, WHITE, 8 IN.	630.00 LFT
0104	808-75059	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 4 IN.	28710.00 LFT
0105	808-75510	TRANSVERSE MARKING, PREFORMED PLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	136.00 LFT

0106	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	1542.00 EACH
------	-----------	---	--------------

Call: 200

Contract: R -41770-A

Section No.: 1 ROAD ENHANCEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	3414.00	SYS
0012	202-02279	CURB AND GUTTER, REMOVE	1588.00	LFT
0013	202-52710	SIDEWALK CONCRETE, REMOVE	685.00	SYS
0014	202-94425	APRON, REMOVE	576.00	SYS
0015	203-02000	EXCAVATION, COMMON	1730.00	CYS
0016	203-02070	BORROW	450.00	CYS
0017	205-12108	STORMWATER MANAGEMENT BUDGET	10161.00	DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	205-12618	SWQCP PREPARATION	1.00	LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	1565.00	SYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	6213.00	SYS
0022	211-09264	STRUCTURE BACKFILL, TYPE 1	703.00	CYS
0023	214-11796	GEOGRID, TYPE IB	1565.00	SYS
0024	302-07455	DENSE GRADED SUBBASE	261.00	CYS
0025	304-07494	WIDENING WITH HMA, TYPE C	705.00	TON
0026	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	332.00	TON
0027	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	553.00	TON
0028	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	2109.00	TON
0029	401-10258	JOINT ADHESIVE, SURFACE	4658.00	LFT
0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	4658.00	LFT
0031	401-11785	LIQUID ASPHALT SEALANT	4658.00	LFT

0032	406-05520	ASPHALT FOR TACK COAT	4.00	TON
0033	604-06070	SIDEWALK, CONCRETE	1951.00	SYS
0034	604-08086	CURB RAMP, CONCRETE	121.00	SYS
0035	604-12083	DETECTABLE WARNING SURFACES	22.00	SYS
0036	605-06255	CENTER CURB, D CONCRETE	222.00	SYS
0037	605-52807	CURB AND GUTTER, COMBINED	2588.00	LFT
0038	610-09108	PCCP FOR APPROACHES, 9 IN.	1565.00	SYS
0039	621-06567	WATER	8.00	KGAL
0040	621-06570	TOPSOIL	216.00	CYS
0041	621-06575	SODDING, NURSERY	1938.00	SYS
0042	628-09403	FIELD OFFICE, C	12.00	MOS
0043	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0044	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	799.00	LFT
0045	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	495.00	LFT
0046	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	71.00	LFT
0047	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	137.00	LFT
0048	715-07317	CHECK VALVE	1.00	EACH
0049	715-09064	VIDEO INSPECTION FOR PIPE	3107.00	LFT
0050	715-09529	PIPE, TYPE 4, CIRCULAR, 48 IN.	1570.00	LFT
0051	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	9744.00	SYS
0052	718-52610	AGGREGATE FOR UNDERDRAINS	1713.00	CYS
0053	720-45075	INLET, R13	3.00	EACH
0054	720-45410	MANHOLE, C4	1.00	EACH
0055	720-92884	MANHOLE, K4 MODIFIED	1.00	EACH
0056	720-93501	MANHOLE, L4	1.00	EACH
0057	720-94612	MANHOLE, K4	16.00	EACH
0058	720-95409	MANHOLE, J4 MODIFIED	11.00	EACH
0059	720-98174	INLET, B15	10.00	EACH
0060	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	4.00	EACH
0061	801-02595	CONTROLLER RESET TIMING	1.00	EACH
0062	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	15964.00	LFT
0063	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00	LS
0064	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	250.00	LFT
0065	801-06640	CONSTRUCTION SIGN, A	33.00	EACH
0066	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0067	801-06775	MAINTAINING TRAFFIC	1.00	LS
0068	801-07118	BARRICADE, III-A	108.00	LFT

0069	801-11990	TEMPORARY CURB RAMP	2.00 EACH
0070	801-94295	SIGNAL HEAD RELOCATE	8.00 EACH
0071	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	58.00 LFT
0072	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	4.00 EACH
0073	802-07060	SIGN, SHEET, RELOCATE	1.00 EACH
0074	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	60.00 SFT
0075	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	14.00 SFT
0076	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	12.00 EACH
0077	805-01824	SPAN, CATENARY, AND TETHER, TIGHTEN	4.00 EACH
0078	805-01843	SIGNAL HANDHOLE ADJUST TO GRADE	3.00 EACH
0079	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	8.00 EACH
0080	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	6.00 EACH
0081	805-03372	TETHER FOR SIGNAL	2.00 EACH
0082	805-05405	SIGNAL POLE, PEDESTAL, 4FT	5.00 EACH
0083	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	90.00 LFT
0084	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL	6.00 EACH
0085	805-11744	HANDHOLE SIGNAL TYPE 2	1.00 EACH
0086	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	348.00 LFT
0087	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00 EACH
0088	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	8.00 EACH
0089	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	1519.00 LFT
0090	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	532.00 LFT
0091	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	3576.00 LFT
0092	805-78785	SIGNAL DETECTOR HOUSING	12.00 EACH
0093	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	2.00 EACH
0094	807-02191	HANDHOLE LIGHTING	5.00 EACH
0095	807-03950	LUMINAIRE ORNAMENTAL	41.00 EACH
0096	807-03951	LIGHT POLE ORNAMENTAL	41.00 EACH
0097	807-04653	LIGHTING FOUNDATION	41.00 EACH
0098	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	1221.00 LFT
0099	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	4828.00 LFT
0100	807-86810	SERVICE POINT, II	1.00 EACH
0101	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	1271.00 LFT
0102	807-86910	CONNECTOR KIT, UNFUSED	41.00 EACH
0103	807-86915	CONNECTOR KIT, FUSED	41.00 EACH
0104	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	98.00 EACH
0105	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	20.00 EACH

0106	807-86930	INSULATION LINK, NON-WATERPROOFED	88.00 EACH
0107	807-86935	INSULATION LINK, WATERPROOFED	20.00 EACH
0108	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	891.00 LFT
0109	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	904.00 LFT
0110	808-06716	LINE, REMOVE	1612.00 LFT
0111	808-12032	GROOVING FOR PAVEMENT MARKINGS	4477.00 LFT
0112	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3573.00 LFT
0113	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	161.00 LFT
0114	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	584.00 LFT
0115	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	8.00 EACH
0116	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	3.00 EACH

Call: 206

Contract: R -41722-B

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	3.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	3.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02272	PAVED SIDE DITCH, REMOVE	1368.00	LFT
0013	202-52710	SIDEWALK CONCRETE, REMOVE	80.00	SYS
0014	202-90747	RETAINING WALL, REMOVE	20.00	LFT
0015	202-91840	FENCE, CHAIN. LINK, REMOVE	288.00	LFT
0016	202-96133	PIPE, REMOVE	51.00	LFT
0017	203-02000	EXCAVATION, COMMON	5388.00	CYS
0018	203-02010	EXCAVATION, ROCK	143.00	CYS
0019	203-02070	BORROW	11945.00	CYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	43000.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	205-12618	SWQCP PREPARATION	1.00	LS
0023	206-93520	TEMPORARY SHEET PILING	5995.00	SFT
0024	207-08264	SUBGRADE TREATMENT, TYPE II	1074.00	SYS
0025	207-08266	SUBGRADE TREATMENT, TYPE III	8425.00	SYS
0026	207-09935	SUBGRADE TREATMENT, TYPE IC	14.00	SYS
0027	211-02050	B BORROW	1451.00	CYS
0028	211-09264	STRUCTURE BACKFILL, TYPE 1	193.00	CYS
0029	211-09266	STRUCTURE BACKFILL, TYPE 3	2200.00	CYS
0030	211-09268	STRUCTURE BACKFILL, TYPE 5	16.00	CYS
0031	301-12233	COMPACTED AGGREGATE NO. 8	3.30	CYS

0032	301-12234	COMPACTED AGGREGATE NO. 53	2297.00	CYS
0033	303-08210	COMPACTED AGGREGATE NO. 53 TEMPORARY FOR DRIVEWAYS	120.00	TON
0034	304-07494	WIDENING WITH HMA, TYPE C	10.00	TON
0035	406-05520	ASPHALT FOR TACK COAT	3.40	TON
0036	603-06065	FENCE, CHAIN LINK, RESET	138.00	LFT
0037	604-05528	HMA FOR SIDEWALK	1170.00	TON
0038	604-06070	SIDEWALK, CONCRETE	15.60	SYS
0039	604-08086	CURB RAMP, CONCRETE	139.00	SYS
0040	604-12083	DETECTABLE WARNING SURFACES	26.00	SYS
0041	604-95344	HAND RAIL, PEDESTRIAN	520.00	LFT
0042	605-06140	CURB AND GUTTER, CONCRETE	60.00	LFT
0043	610-07487	HMA FOR APPROACHES, TYPE B	709.00	TON
0044	615-06490	RIGHT-OF-WAY MARKER	4.00	EACH
0045	616-06451	RIPRAP, UNIFORM	663.00	TON
0046	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1474.00	SYS
0047	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	88.00	SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0049	621-06545	FERTILIZER	1.30	TON
0050	621-06554	SEED MIXTURE U	667.00	LBS
0051	621-06565	MULCHING MATERIAL	7.00	TON
0052	621-06574	SODDING	445.00	SYS
0053	628-09403	FIELD OFFICE, C	14.00	MOS
0054	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0055	628-11977	COMPUTER SYSTEM	1.00	EACH
0056	714-11053	STRUCTURE EXTENSION, REINFORCED CONCRETE, BOX SECTIONS, 10 FT. X 8 FT.	6.00	LFT
0057	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	10.00	LFT
0058	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	11.00	LFT
0059	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	58.00	LFT
0060	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	34.00	LFT
0061	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	22.00	LFT
0062	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	11.00	LFT
0063	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	48.00	LFT
0064	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	22.00	LFT
0065	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	100.00	LFT
0066	715-09064	VIDEO INSPECTION FOR PIPE	305.00	LFT
0067	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00	EACH
0068	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH

0069	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00 EACH
0070	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00 EACH
0071	715-46030	PIPE END SECTION, DIAMETER 30 IN.	1.00 EACH
0072	718-06528	OUTLET PROTECTOR, 1	1.00 EACH
0073	720-44000	CASTING, ADJUST TO GRADE	2.00 EACH
0074	720-45005	INLET, A2	1.00 EACH
0075	720-45235	CATCH BASIN, E7	2.00 EACH
0076	720-45265	PIPE CATCH BASIN, 15 IN.	1.00 EACH
0077	720-45410	MANHOLE, C4	1.00 EACH
0078	720-45615	STRUCTURE, INLET, RECONSTRUCTED	12.10 LFT
0079	720-94612	MANHOLE, K4	1.00 EACH
0080	731-93947	LEVELING PAD, CONCRETE	520.00 LFT
0081	732-11770	AGGREGATE FOR DRAINAGE FILL	153.00 CYS
0082	732-11811	MODULAR BLOCK WALL ERECTION	4305.00 SFT
0083	732-11812	MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	4305.00 SFT
0084	801-06640	CONSTRUCTION SIGN, A	58.00 EACH
0085	801-06775	MAINTAINING TRAFFIC	1.00 LS
0086	801-07119	BARRICADE, III-B	96.00 LFT
0087	802-02475	SIGN, PANEL, RELOCATE	2.00 EACH
0088	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	422.00 LFT
0089	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	20.00 EACH
0090	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	27.00 EACH
0091	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	83.00 SFT
0092	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	4.00 EACH
0093	802-76095	STRUCTURAL STEEL, BREAKAWAY	1381.00 LBS
0094	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00 LS
0095	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	75.00 LFT
0096	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	2.00 EACH
0097	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	2.00 EACH
0098	805-11817	PEDESTRIAN PUSH BUTTON, APS	2.00 EACH
0099	805-78412	SIGNAL POLE, PEDESTAL, 9FT	2.00 EACH
0100	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	260.00 LFT
0101	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	260.00 LFT
0102	807-03594	RELOCATE EXISTING LIGHT	3.00 EACH
0103	808-02977	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	8.00 EACH
0104	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	17730.00 LFT
0105	808-06716	LINE, REMOVE	146.00 LFT

0106	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	55.00	LFT
0107	808-11960	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 24 IN.	430.00	LFT
0108	808-75100	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 6 IN.	482.00	LFT
0109	808-75330	PAVEMENT MESSAGE MARKING, THERMOPLASTIC PED XING	8.00	EACH

Call: 210

Contract: R -43035-A

Section No.: 1 ASPHALT RESURFACE

Line

Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	303-07449	COMPACTED AGGREGATE NO. 73	187.00	TON
0010	306-08034	MILLING, ASPHALT, 1 1/2 IN.	16632.00	SYS
0011	306-08432	MILLING, APPROACH	783.00	SYS
0012	401-06264	PROFILOGRAPH, HMA	1.00	LS
0013	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1373.00	TON
0014	401-10258	JOINT ADHESIVE, SURFACE	7458.00	LFT
0015	401-11785	LIQUID ASPHALT SEALANT	7458.00	LFT
0016	406-05520	ASPHALT FOR TACK COAT	7.00	TON
0017	610-07487	HMA FOR APPROACHES, TYPE B	65.00	TON
0018	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	495.00	LFT
0019	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	495.00	LFT
0020	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0021	801-06775	MAINTAINING TRAFFIC	1.00	LS
0022	801-92448	CONSTRUCTION SIGNS MOBILE	150.00	DAY
0023	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	1220.00	LFT
0024	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	10010.00	LFT
0025	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1126.00	LFT
0026	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	77.00	EACH
0027	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	77.00	EACH

Call: 220

Contract: R -43522-A

Section No.: 1 ROAD RECONSTRUCTION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00	LS
0013	203-02000	EXCAVATION, COMMON	48431.00	CYS
0014	204-08415	STAKE, SETTLEMENT	4.00	EACH
0015	205-11626	PUMP AROUND	3.00	EACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	164500.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	2305.00	SYS
0020	207-12636	SUBGRADE TREATMENT, TYPE IBL	40405.00	SYS
0021	211-09265	STRUCTURE BACKFILL, TYPE 2	329.00	CYS
0022	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	40.00	CYS
0023	301-12231	COMPACTED AGGREGATE NO. 2	14.00	CYS
0024	301-12233	COMPACTED AGGREGATE NO. 8	14.00	CYS
0025	301-12234	COMPACTED AGGREGATE NO. 53	6432.00	CYS
0026	303-01180	COMPACTED AGGREGATE NO. 53	4417.00	TON
0027	303-07449	COMPACTED AGGREGATE NO. 73	169.00	TON
0028	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	3019.00	TON
0029	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	5076.00	TON
0030	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	9319.00	TON
0031	401-10258	JOINT ADHESIVE, SURFACE	24386.00	LFT

0032	401-10259	JOINT ADHESIVE, INTERMEDIATE	24386.00	LFT
0033	401-11785	LIQUID ASPHALT SEALANT	24386.00	LFT
0034	406-05520	ASPHALT FOR TACK COAT	24.00	TON
0035	605-06121	CURB, CONCRETE B	1566.00	LFT
0036	610-07487	HMA FOR APPROACHES, TYPE B	554.00	TON
0037	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	16.00	EACH
0038	615-06505	MONUMENT, B	19.00	EACH
0039	615-06527	MONUMENT, SECTION CORNER	2.00	EACH
0040	616-05688	RIPRAP, CLASS 1	394.00	TON
0041	616-06405	RIPRAP, REVETMENT	5414.00	TON
0042	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	15319.00	SYS
0043	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0044	621-06545	FERTILIZER	4.00	TON
0045	621-06553	SEED MIXTURE R	1381.00	LBS
0046	621-06565	MULCHING MATERIAL	19.00	TON
0047	621-06574	SODDING	3738.00	SYS
0048	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0049	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0050	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0051	628-11783	CELLULAR TELEPHONE SERVICE, 2000 MIN.	20.00	MOS
0052	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0053	628-11977	COMPUTER SYSTEM	1.00	EACH
0054	628-12683	FIELD OFFICE, D	20.00	MOS
0055	702-51010	CONCRETE, B, ABOVE FOOTINGS	22.00	CYS
0056	715-05125	PIPE, TYPE 1, CIRCULAR, 30 IN.	315.00	LFT
0057	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	366.00	LFT
0058	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	205.00	LFT
0059	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	426.00	LFT
0060	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	175.00	LFT
0061	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0062	715-46005	PIPE END SECTION, DIAMETER 15 IN.	18.00	EACH
0063	715-46010	PIPE END SECTION, DIAMETER 18 IN.	8.00	EACH
0064	715-46030	PIPE END SECTION, DIAMETER 30 IN.	7.00	EACH
0065	720-01092	MANHOLE, J15 MODIFIED	1.00	EACH
0066	720-45510	MANHOLE, C4 MODIFIED	1.00	EACH
0067	720-98174	INLET, B15	2.00	EACH
0068	720-98555	INLET, C15	3.00	EACH

0069	801-06625	DETOUR ROUTE MARKER ASSEMBLY	66.00	EACH
0070	801-06640	CONSTRUCTION SIGN, A	6.00	EACH
0071	801-06775	MAINTAINING TRAFFIC	1.00	LS
0072	801-07119	BARRICADE, III-B	24.00	LFT
0073	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	237.00	LFT
0074	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	74.00	SFT
0075	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	95.00	SFT
0076	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	15746.00	LFT
0077	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0078	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	17371.00	LFT
0079	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	49.00	LFT

Call: 230

Contract: R -43575-A

Section No.: 1 CONCRETE PAVEMENT RESTORATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	214-12490	GEOTEXTILE FOR PAVEMENT TYPE 3A	4020.00	SYS
0010	301-12234	COMPACTED AGGREGATE NO. 53	670.00	CYS
0011	304-12626	HMA PATCHING PARTIAL DEPTH TYPE C	1542.00	TON
0012	306-08042	MILLING, SCARIFICATION	3104.00	SYS
0013	506-12712	PCC BONDED OVERLAY PATCHING 4 INCH	3104.00	SYS
0014	615-06520	MONUMENT, RE-ESTABLISH	4.00	EACH
0015	628-09403	FIELD OFFICE, C	16.00	MOS
0016	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0017	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0018	801-06625	DETOUR ROUTE MARKER ASSEMBLY	44.00	EACH
0019	801-06640	CONSTRUCTION SIGN, A	259.00	EACH
0020	801-06645	CONSTRUCTION SIGN, B	124.00	EACH
0021	801-06775	MAINTAINING TRAFFIC	1.00	LS
0022	801-07118	BARRICADE, III-A	1120.00	LFT
0023	801-07119	BARRICADE, III-B	96.00	LFT
0024	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	5.00	EACH
0025	801-12324	LAW ENFORCEMENT OFFICER	200.00	HRS
0026	805-78746	PREFORMED LOOP DETECTORS	39.00	LFT
0027	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2734.00	LFT
0028	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1330.00	LFT
0029	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	50.00	LFT
0030	808-12032	GROOVING FOR PAVEMENT MARKINGS	4114.00	LFT
0031	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	54.00	EACH

0032	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	54.00 EACH
------	-----------	-------------------------------------	------------

Call: 310

Contract: B -35155-A

Section No.: 1 BRIDGE PAINTING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	960.00	SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	203-02000	EXCAVATION, COMMON	254.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	6000.00	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	29.00	CYS
0019	206-93520	TEMPORARY SHEET PILING	265.00	SFT
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	1030.00	SYS
0021	211-06467	AGGREGATE FOR END BENT BACKFILL	29.00	CYS
0022	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	2.00	CYS
0023	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	1010.00	SYS
0024	302-06464	SUBBASE FOR PCCP	238.00	CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	163.00	TON
0026	306-08043	MILLING, TRANSITION	1749.00	SYS
0027	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	151.00	TON
0028	401-10258	JOINT ADHESIVE, SURFACE	1330.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	1330.00	LFT
0030	406-05521	ASPHALT FOR TACK COAT	1836.00	SYS
0031	503-03489	RETROFITTED TIE BARS	134.00	EACH

0032	503-05240	D-1 CONTRACTION JOINT	142.00	LFT
0033	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	620.00	SYS
0034	503-12478	TERMINAL JOINT, TYPE PCCP	150.00	LFT
0035	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	138.00	LFT
0036	601-02241	GUARDRAIL, REMOVE	340.00	LFT
0037	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	25.00	LFT
0038	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	4.00	EACH
0039	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	4.00	EACH
0040	602-06729	BARRIER, DELINEATOR	22.00	EACH
0041	603-01159	FENCE, CHAIN LINK, PVC COATED, 42 IN.	102.00	LFT
0042	605-06095	CURB, INTEGRAL B CONCRETE	160.00	LFT
0043	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	342.00	SYS
0044	616-06405	RIPRAP, REVETMENT	174.00	TON
0045	616-06455	SLOPEWALL	2.00	SYS
0046	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	234.00	SYS
0047	616-93772	INSPECTION HOLE	2.00	EACH
0048	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0049	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0050	619-12506	CLEAN STEEL BRIDGE TOP FLANGES QP-2 BRIDGE NO.	1.00	LS
0051	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0052	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0053	621-06559	MULCHED SEEDING R	386.00	SYS
0054	621-06574	SODDING	116.00	SYS
0055	628-09403	FIELD OFFICE, C	12.00	MOS
0056	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0057	702-04325	TEMPORARY SHORING	1.00	LS
0058	702-51005	CONCRETE, A, SUBSTRUCTURE	55.60	CYS
0059	703-06028	REINFORCING BARS	7042.00	LBS
0060	703-06029	REINFORCING BARS, EPOXY COATED	263197.00	LBS
0061	703-96512	BAR SPLICE	210.00	EACH
0062	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	1394.00	EACH
0063	704-51002	CONCRETE, C, SUPERSTRUCTURE	880.60	CYS
0064	706-11601	RAILING, CONCRETE FT	98.60	CYS
0065	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	4.00	EACH
0066	709-51821	SURFACE SEAL	1.00	LS
0067	710-09158	PATCHING CONCRETE STRUCTURES	80.00	SFT
0068	711-51038	STRUCTURAL STEEL	1.00	LS

0069	711-96479	BOLT, REMOVE	1816.00 EACH
0070	711-96800	STUD SHEAR CONNECTORS	14870.00 EACH
0071	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	122.00 SYS
0072	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	220.00 SFT
0073	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	4305.00 SFT
0074	724-12103	PRE-COMPRESSED FOAM JOINT	150.00 LFT
0075	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00 EACH
0076	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	30998.00 LFT
0077	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4420.00 LFT
0078	801-06625	DETOUR ROUTE MARKER ASSEMBLY	21.00 EACH
0079	801-06640	CONSTRUCTION SIGN, A	54.00 EACH
0080	801-06645	CONSTRUCTION SIGN, B	16.00 EACH
0081	801-06710	FLASHING ARROW SIGN	480.00 DAY
0082	801-06775	MAINTAINING TRAFFIC	1.00 LS
0083	801-07118	BARRICADE, III-A	96.00 LFT
0084	801-07119	BARRICADE, III-B	48.00 LFT
0085	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	628.00 LFT
0086	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	2188.00 LFT
0087	801-12031	TEMPORARY PORTABLE RUMBLE STRIPS	1500.00 DAY
0088	802-04893	REFERENCE POST	2.00 EACH
0089	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	6.00 SFT
0090	802-76055	SIGN POST, A	24.00 LFT
0091	808-06716	LINE, REMOVE	29079.00 LFT
0092	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0093	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	4044.00 LFT
0094	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	16168.00 LFT
0095	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	16168.00 LFT
0096	808-12032	GROOVING FOR PAVEMENT MARKINGS	16184.00 LFT

Call: 314

Contract: B -39052-A

Section No.: 1

NEW BRIDGE CONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-01015	CLEARING AND GRUBBING	1.00 LS
0013	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0014	202-02240	PAVEMENT REMOVAL	15531.00 SYS
0015	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0016	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0017	202-91385	INLET, REMOVE	10.00 EACH
0018	202-96133	PIPE, REMOVE	3754.00 LFT
0019	202-96430	FENCE AND POSTS, REMOVE	1.00 LS
0020	203-02000	EXCAVATION, COMMON	46990.00 CYS
0021	203-02070	BORROW	404215.00 CYS
0022	203-02235	BREAKING PAVEMENT	10848.00 SYS
0023	204-02290	SETTLEMENT PLATE	10.00 EACH
0024	204-08553	DATA LOGGING SYSTEM	4.00 EACH
0025	204-12717	VIBRATING WIRE PRESSURE CELL	4.00 EACH
0026	204-12718	GROUND IMPROVEMENT	884.00 SYS
0027	205-11626	PUMP AROUND	1.00 EACH
0028	205-12108	STORMWATER MANAGEMENT BUDGET	200000.00 DOL
0029	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0030	205-12618	SWQCP PREPARATION	1.00 LS
0031	207-08264	SUBGRADE TREATMENT, TYPE II	1677.00 SYS

0032	207-09935	SUBGRADE TREATMENT, TYPE IC	1040.00	SYS
0033	207-12377	CEMENT STABILIZED SUBGRADE	55802.00	SYS
0034	211-02050	B BORROW	9972.00	CYS
0035	211-09264	STRUCTURE BACKFILL, TYPE 1	803.00	CYS
0036	211-09266	STRUCTURE BACKFILL, TYPE 3	19902.00	CYS
0037	214-12237	GEOTEXTILE FOR PAVEMENT TYPE 1B	55802.00	SYS
0038	214-12243	GEOTEXTILE FOR SUBGRADE TYPE 2A	19737.00	SYS
0039	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	1040.00	SYS
0040	217-11917	DRYING SOILS FOR EMBANKMENT	3727.00	TON
0041	301-12231	COMPACTED AGGREGATE NO. 2	1232.00	CYS
0042	301-12232	COMPACTED AGGREGATE NO. 5	1808.00	CYS
0043	301-12233	COMPACTED AGGREGATE NO. 8	130.00	CYS
0044	301-12234	COMPACTED AGGREGATE NO. 53	29603.00	CYS
0045	302-06464	SUBBASE FOR PCCP	80.00	CYS
0046	303-01180	COMPACTED AGGREGATE NO. 53	13656.00	TON
0047	306-08034	MILLING, ASPHALT, 1 1/2 IN.	28572.00	SYS
0048	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	424.00	TON
0049	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1914.00	TON
0050	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	4223.00	TON
0051	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	97.00	TON
0052	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1446.00	TON
0053	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	5519.00	TON
0054	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	2313.00	TON
0055	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	18152.00	TON
0056	401-10258	JOINT ADHESIVE, SURFACE	55777.00	LFT
0057	401-10259	JOINT ADHESIVE, INTERMEDIATE	34522.00	LFT
0058	401-11785	LIQUID ASPHALT SEALANT	55777.00	LFT
0059	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	6372.00	TON
0060	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0061	402-07787	HMA WEDGE AND LEVEL, TYPE D	578.00	TON
0062	402-10086	HMA FOR TEMPORARY PAVEMENT, C	1626.00	TON
0063	406-05520	ASPHALT FOR TACK COAT	72.00	TON
0064	503-12477	TERMINAL JOINT, TYPE HMA	178.00	LFT
0065	601-05999	CURVED TERMINAL END	2.00	EACH
0066	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	1012.50	LFT
0067	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN SPACING	1062.50	LFT
0068	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH

0069	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00 EACH
0070	601-94689	GUARDRAIL, END TREATMENT, OS	4.00 EACH
0071	601-94690	GUARDRAIL, END TREATMENT, MS	2.00 EACH
0072	602-06729	BARRIER, DELINEATOR	16.00 EACH
0073	603-06040	FENCE, FARM FIELD, 47 IN.	7640.00 LFT
0074	603-06045	FENCE, CHAIN LINK, 48 IN.	250.00 LFT
0075	605-06120	CURB, CONCRETE	63.00 LFT
0076	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	13793.00 LFT
0077	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	404.00 SYS
0078	610-07487	HMA FOR APPROACHES, TYPE B	369.00 TON
0079	615-06490	RIGHT-OF-WAY MARKER	17.00 EACH
0080	615-06505	MONUMENT, B	36.00 EACH
0081	615-06527	MONUMENT, SECTION CORNER	1.00 EACH
0082	616-05688	RIPRAP, CLASS 1	34.00 TON
0083	616-06405	RIPRAP, REVETMENT	1256.00 TON
0084	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	2132.00 SYS
0085	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00 EACH
0086	621-06545	FERTILIZER	10.00 TON
0087	621-06553	SEED MIXTURE R	5125.00 LBS
0088	621-06565	MULCHING MATERIAL	51.00 TON
0089	621-06567	WATER	492.00 kGAL
0090	621-06574	SODDING	6489.00 SYS
0091	621-06575	SODDING, NURSERY	8609.00 SYS
0092	628-09403	FIELD OFFICE, C	36.00 MOS
0093	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0094	701-06011	DYNAMIC PILE LOAD TEST	2.00 EACH
0095	701-08122	PILE, STEEL PIPE, 0.375 IN., 14 IN.	2686.00 LFT
0096	701-09557	TEST PILE, DYNAMIC, PRODUCTION	178.00 LFT
0097	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00 EACH
0098	701-09679	CONICAL PILE TIP, 14 IN.	36.00 EACH
0099	702-92857	CONCRETE, C, SUBSTRUCTURE	80.00 CYS
0100	703-01540	THREADED TIE BAR ASSEMBLY	92.00 EACH
0101	703-06029	REINFORCING BARS, EPOXY COATED	160930.00 LBS
0102	704-51002	CONCRETE, C, SUPERSTRUCTURE	424.00 CYS
0103	706-09959	RAILING, CONCRETE FT	570.00 LFT
0104	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	4.00 EACH
0105	706-51020	RAILING, CONCRETE C	673.00 CYS

0106	707-09383	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 60 IN. X 61 IN.	1215.00	LFT
0107	709-51821	SURFACE SEAL	1.00	LS
0108	709-51821	SURFACE SEAL	1.00	LS
0109	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	18379.00	LFT
0110	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	2465.00	LFT
0111	715-05129	PIPE, TYPE 1, CIRCULAR, 54 IN.	228.00	LFT
0112	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	140.00	LFT
0113	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	227.00	LFT
0114	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	40.00	LFT
0115	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	111.00	LFT
0116	715-05257	PIPE, TYPE 1, DEFORMED, MIN. AREA 24.75 SFT	165.00	LFT
0117	715-06492	CONCRETE ANCHOR, 54 IN.	4.00	EACH
0118	715-09064	VIDEO INSPECTION FOR PIPE	911.00	LFT
0119	715-09205	CONCRETE ANCHOR, MIN. AREA 23.3 SFT	2.00	EACH
0120	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0121	715-46010	PIPE END SECTION, DIAMETER 18 IN.	5.00	EACH
0122	715-46020	PIPE END SECTION, DIAMETER 24 IN.	6.00	EACH
0123	716-07726	PIPE INSTALLATION, TRENCHLESS, 54 IN.	78.00	LFT
0124	718-06528	OUTLET PROTECTOR, 1	24.00	EACH
0125	718-06531	OUTLET PROTECTOR, 3	10.00	EACH
0126	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00	LFT
0127	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	12665.00	SYS
0128	718-52610	AGGREGATE FOR UNDERDRAINS	1451.00	CYS
0129	720-95310	INLET, P12A MODIFIED	8.00	EACH
0130	724-12103	PRE-COMPRESSED FOAM JOINT	178.00	LFT
0131	731-93945	FACE PANELS, CONCRETE	13051.00	SFT
0132	731-93946	WALL ERECTION	13051.00	SFT
0133	731-93947	LEVELING PAD, CONCRETE	792.00	LFT
0134	735-10241	TEMPORARY WIRE FACING	17394.00	SFT
0135	735-10242	TEMPORARY WALL ERECTION	17394.00	SFT
0136	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	9.00	EACH
0137	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00	EACH
0138	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	71028.00	LFT
0139	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	48.00	LFT
0140	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	10348.00	LFT
0141	801-06625	DETOUR ROUTE MARKER ASSEMBLY	38.00	EACH
0142	801-06640	CONSTRUCTION SIGN, A	47.00	EACH

0143	801-06645	CONSTRUCTION SIGN, B	7.00 EACH
0144	801-06710	FLASHING ARROW SIGN	1440.00 DAY
0145	801-06775	MAINTAINING TRAFFIC	1.00 LS
0146	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	2.00 EACH
0147	801-07118	BARRICADE, III-A	168.00 LFT
0148	801-07119	BARRICADE, III-B	120.00 LFT
0149	801-07606	TEMPORARY Crossover DRAINAGE PIPE	500.00 LFT
0150	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	9102.00 LFT
0151	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	2155.00 LFT
0152	801-12348	TEMPORARY WORKSITE SPEED DISPLAY ASSEMBLY	2.00 EACH
0153	801-52817	TEMPORARY Crossover, B	2.00 EACH
0154	801-94295	SIGNAL HEAD RELOCATE	12.00 EACH
0155	802-02475	SIGN, PANEL, RELOCATE	3.00 EACH
0156	802-04893	REFERENCE POST	4.00 EACH
0157	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	61.00 LFT
0158	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	25.00 LFT
0159	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	32.00 EACH
0160	802-07060	SIGN, SHEET, RELOCATE	1.00 EACH
0161	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	17.00 SFT
0162	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	38.00 SFT
0163	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	4.00 EACH
0164	802-12223	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, B	2.00 EACH
0165	802-12224	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, C	4.00 EACH
0166	802-76095	STRUCTURAL STEEL, BREAKAWAY	5803.00 LBS
0167	804-06770	DELINEATOR POST	34.00 EACH
0168	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	4549.00 LFT
0169	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	19347.00 LFT
0170	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0171	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	82.00 LFT
0172	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	326.00 LFT
0173	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	326.00 LFT
0174	808-12032	GROOVING FOR PAVEMENT MARKINGS	42830.00 LFT
0175	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	18193.00 LFT
0176	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	147.00 LFT
0177	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	4.00 EACH
0178	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	150.00 EACH

Call: 320

Contract: B -40643-A

Section No.: 1 REPLACE SUPERSTRUCTURE

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	2444.00	SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0016	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0017	203-02000	EXCAVATION, COMMON	10387.00	CYS
0018	203-02070	BORROW	4401.00	CYS
0019	205-11626	PUMP AROUND	2.00	EACH
0020	205-12108	STORMWATER MANAGEMENT BUDGET	78200.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	205-12618	SWQCP PREPARATION	1.00	LS
0023	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	375.00	CYS
0024	206-51235	COFFERDAM	1.00	LS
0025	207-09935	SUBGRADE TREATMENT, TYPE IC	1964.00	SYS
0026	207-12498	SUBGRADE TREATMENT, TYPE ID	4229.00	SYS
0027	207-12635	SUBGRADE TREATMENT, TYPE IBC	21141.00	SYS
0028	211-06467	AGGREGATE FOR END BENT BACKFILL	23.00	CYS
0029	211-09265	STRUCTURE BACKFILL, TYPE 2	51.00	CYS
0030	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	49.00	CYS
0031	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	3287.00	SYS

0032	301-12231	COMPACTED AGGREGATE NO. 2	12.00	CYS
0033	301-12234	COMPACTED AGGREGATE NO. 53	2489.00	CYS
0034	302-06464	SUBBASE FOR PCCP	837.00	CYS
0035	303-01180	COMPACTED AGGREGATE NO. 53	5067.00	TON
0036	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	15.00	TON
0037	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	1346.00	TON
0038	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	25.00	TON
0039	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	2732.00	TON
0040	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	107.00	TON
0041	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	6602.00	TON
0042	401-10258	JOINT ADHESIVE, SURFACE	12171.00	LFT
0043	401-10259	JOINT ADHESIVE, INTERMEDIATE	12171.00	LFT
0044	401-11785	LIQUID ASPHALT SEALANT	4111.00	LFT
0045	406-05520	ASPHALT FOR TACK COAT	15.00	TON
0046	501-06323	QC/QA-PCCP, 12 IN.	1881.00	SYS
0047	503-05240	D-1 CONTRACTION JOINT	1432.00	LFT
0048	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	1040.00	SYS
0049	503-12477	TERMINAL JOINT, TYPE HMA	54.00	LFT
0050	503-12478	TERMINAL JOINT, TYPE PCCP	236.00	LFT
0051	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	236.00	LFT
0052	601-02241	GUARDRAIL, REMOVE	2490.00	LFT
0053	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	2525.00	LFT
0054	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	4.00	EACH
0055	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	10.00	EACH
0056	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	2.00	EACH
0057	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0058	601-94690	GUARDRAIL, END TREATMENT, MS	1.00	EACH
0059	602-06729	BARRIER, DELINEATOR	34.00	EACH
0060	603-06060	FENCE, FARM FIELD, RESET	210.00	LFT
0061	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	10568.00	LFT
0062	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	736.00	SYS
0063	616-05688	RIPRAP, CLASS 1	1708.00	TON
0064	616-06405	RIPRAP, REVETMENT	227.00	TON
0065	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	2574.00	SYS
0066	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	18.00	SYS
0067	616-93772	INSPECTION HOLE	6.00	EACH
0068	619-11050	CLEAN STEEL BRIDGE, PARTIAL, QP-2, BRIDGE NO.	1.00	LS

0069	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0070	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	5.00	EACH
0071	621-02770	EROSION CONTROL BLANKET	3544.00	SYS
0072	621-06559	MULCHED SEEDING R	44524.00	SYS
0073	621-06574	SODDING	126.00	SYS
0074	621-12612	SEED MIXTURE FLOODPLAIN	5.00	LBS
0075	628-09403	FIELD OFFICE, C	18.00	MOS
0076	629-12029	PLANT GROWTH LAYER	39669.00	SYS
0077	701-09558	TEST PILE, INDICATOR, PRODUCTION	652.00	LFT
0078	701-09560	TEST PILE, INDICATOR, RESTRIKE	8.00	EACH
0079	701-09739	PILE SHOE, HP 12 X 53	36.00	EACH
0080	701-51195	PILE, STEEL H HP 12 X 53	2024.00	LFT
0081	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	1.00	EACH
0082	702-51005	CONCRETE, A, SUBSTRUCTURE	127.60	CYS
0083	702-51015	CONCRETE, B, FOOTINGS	13.00	CYS
0084	702-51863	FIELD DRILLED HOLE IN CONCRETE	188.00	EACH
0085	702-92857	CONCRETE, C, SUBSTRUCTURE	23.10	CYS
0086	703-06028	REINFORCING BARS	17464.00	LBS
0087	703-06029	REINFORCING BARS, EPOXY COATED	321216.00	LBS
0088	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	974.00	EACH
0089	704-51002	CONCRETE, C, SUPERSTRUCTURE	921.30	CYS
0090	706-11600	RAILING, CONCRETE FC	2.40	CYS
0091	706-11601	RAILING, CONCRETE FT	52.40	CYS
0092	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0093	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	8.00	EACH
0094	709-51821	SURFACE SEAL	1.00	LS
0095	709-51821	SURFACE SEAL	1.00	LS
0096	709-51821	SURFACE SEAL	1.00	LS
0097	709-51821	SURFACE SEAL	1.00	LS
0098	709-51821	SURFACE SEAL	1.00	LS
0099	710-09158	PATCHING CONCRETE STRUCTURES	225.00	SFT
0100	711-04121	ANCHOR BOLT, AB1	11.00	EACH
0101	711-51038	STRUCTURAL STEEL	1.00	LS
0102	711-51864	DRILLED HOLE	648.00	EACH
0103	711-51878	JACKING AND SUPPORTING, GIRDERS	1.00	LS
0104	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	9927.00	LFT
0105	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	420.00	LFT

0106	715-05407	PIPE, END BENT DRAIN, 6 IN.	107.00	LFT
0107	715-07251	PIPE EXTENSION, DEFORMED, MIN. AREA 8.9 SFT	34.00	LFT
0108	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	1.00	EACH
0109	718-06526	HMA FOR UNDERDRAINS	183.00	TON
0110	718-06528	OUTLET PROTECTOR, 1	4.00	EACH
0111	718-06529	OUTLET PROTECTOR, 2	19.00	EACH
0112	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	4591.00	SYS
0113	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	84.00	SYS
0114	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	23.00	SYS
0115	718-52610	AGGREGATE FOR UNDERDRAINS	360.00	CYS
0116	722-01066	HYDRODEMOLITION	631.00	SYS
0117	722-12380	BRIDGE DECK OVERLAY, BUDGET	11315.00	DOL
0118	722-12382	TRANSVERSE GROOVING	1360.00	SYS
0119	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	631.00	SYS
0120	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	284.00	SFT
0121	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	20.00	SFT
0122	724-12103	PRE-COMPRESSED FOAM JOINT	290.00	LFT
0123	725-11300	PIPE LINER, CURED-IN-PLACE, MIN AREA 8.9 SFT	285.00	LFT
0124	738-09456	POLYMERIC CONCRETE BRIDGE DECK OVERLAY	1400.00	SYS
0125	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.00	EACH
0126	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0127	801-04746	ENERGY ABSORBING TERMINAL, CZ, TL-	4.00	EACH
0128	801-06204	TEMPORARY PAVEMENT MARKING, 5 IN.	2860.00	LFT
0129	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	22890.00	LFT
0130	801-06625	DETOUR ROUTE MARKER ASSEMBLY	61.00	EACH
0131	801-06640	CONSTRUCTION SIGN, A	72.00	EACH
0132	801-06645	CONSTRUCTION SIGN, B	12.00	EACH
0133	801-06710	FLASHING ARROW SIGN	40.00	DAY
0134	801-06775	MAINTAINING TRAFFIC	1.00	LS
0135	801-07118	BARRICADE, III-A	96.00	LFT
0136	801-07119	BARRICADE, III-B	288.00	LFT
0137	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	4881.00	LFT
0138	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	729.00	LFT
0139	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0140	801-12042	TRUCK MOUNTED ATTENUATOR	40.00	DAY
0141	801-12324	LAW ENFORCEMENT OFFICER	200.00	HRS
0142	802-04893	REFERENCE POST	4.00	EACH

0143	802-05702	SIGN POST, SQUARE TYPE 2 REINFORCED ANCHOR BASE	56.00	LFT
0144	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	34.00	SFT
0145	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	690.00	LFT
0146	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	690.00	LFT
0147	808-06716	LINE, REMOVE	15609.00	LFT
0148	808-12032	GROOVING FOR PAVEMENT MARKINGS	10927.00	LFT
0149	808-75051	LINE, PREFORMED PLASTIC, SOLID, WHITE, 4 IN.	6260.00	LFT
0150	808-75054	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 4 IN.	4389.00	LFT
0151	808-75061	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 5 IN.	278.00	LFT
0152	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	27.00	EACH
0153	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	25.00	EACH

Call: 320

Contract: B -40643-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0154	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	664.00	SYS

Call: 320

Contract: B -40643-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0155	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	664.00	SYS

Call: 330

Contract: B -40655-A

Section No.: 1 BRIDGE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-02240	PAVEMENT REMOVAL	1200.00 SYS
0012	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0013	202-74035	SIGN, REMOVE	3.00 EACH
0014	203-02000	EXCAVATION, COMMON	1053.00 CYS
0015	203-51223	EXCAVATION, WATERWAY	245.00 CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	16502.50 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	205-12618	SWQCP PREPARATION	1.00 LS
0019	206-51215	EXCAVATION, X	163.00 CYS
0020	206-51220	EXCAVATION, WET	39.00 CYS
0021	206-51225	EXCAVATION, DRY	21.00 CYS
0022	206-51235	COFFERDAM	1.00 LS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	1200.00 SYS
0024	211-09267	STRUCTURE BACKFILL, TYPE 4	12.00 CYS
0025	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	193.00 SYS
0026	302-06464	SUBBASE FOR PCCP	41.00 CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	320.00 TON
0028	306-08043	MILLING, TRANSITION	645.00 SYS
0029	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	153.00 TON
0030	401-07362	QC/QA-HMA, 3, 70, INTERMEDIATE, 9.5 mm	165.00 TON
0031	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	726.00 TON

0032	401-10258	JOINT ADHESIVE, SURFACE	2527.50	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	2527.50	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	2527.50	LFT
0035	402-07451	HMA WEDGE AND LEVEL, TYPE B	251.00	TON
0036	406-05521	ASPHALT FOR TACK COAT	2902.00	SYS
0037	601-02241	GUARDRAIL, REMOVE	883.00	LFT
0038	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	175.00	LFT
0039	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0040	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0041	602-06729	BARRIER, DELINEATOR	6.00	EACH
0042	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	162.80	SYS
0043	610-07487	HMA FOR APPROACHES, TYPE B	105.00	TON
0044	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	1.00	EACH
0045	615-06505	MONUMENT, B	2.00	EACH
0046	616-05689	RIPRAP, CLASS 2	1116.00	TON
0047	616-06405	RIPRAP, REVETMENT	15.00	TON
0048	616-06451	RIPRAP, UNIFORM	359.00	TON
0049	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1524.00	SYS
0050	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0051	621-06545	FERTILIZER	0.60	TON
0052	621-06553	SEED MIXTURE R	296.00	LBS
0053	621-06565	MULCHING MATERIAL	3.00	TON
0054	621-06574	SODDING	248.00	SYS
0055	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0056	628-12683	FIELD OFFICE, D	12.00	MOS
0057	628-12685	TELEPHONE SERVICE, A	12.00	MOS
0058	701-02938	CORED HOLE IN ROCK, 24 IN	70.00	LFT
0059	701-09739	PILE SHOE, HP 12 X 53	14.00	EACH
0060	701-51195	PILE, STEEL H HP 12 X 53	217.00	LFT
0061	702-51005	CONCRETE, A, SUBSTRUCTURE	84.60	CYS
0062	702-51015	CONCRETE, B, FOOTINGS	70.00	CYS
0063	703-06028	REINFORCING BARS	29484.00	LBS
0064	703-06029	REINFORCING BARS, EPOXY COATED	71053.00	LBS
0065	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	32.00	EACH
0066	704-51002	CONCRETE, C, SUPERSTRUCTURE	213.30	CYS
0067	706-11600	RAILING, CONCRETE FC	17.60	CYS
0068	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH

0069	709-51821	SURFACE SEAL	1.00	LS
0070	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0071	801-06625	DETOUR ROUTE MARKER ASSEMBLY	27.00	EACH
0072	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0073	801-06775	MAINTAINING TRAFFIC	1.00	LS
0074	801-07118	BARRICADE, III-A	48.00	LFT
0075	801-07119	BARRICADE, III-B	48.00	LFT
0076	802-05704	SIGN POST, SQUARE TYPE 1 UNREINFORCED ANCHOR BASE	27.00	LFT
0077	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	6.25	SFT
0078	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	12.00	SFT
0079	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	211.00	LFT
0080	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1685.00	LFT
0081	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	842.50	LFT
0082	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	21.00	EACH

Call: 340

Contract: B -41109-A

Section No.: 1

BRIDGE DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-02240	PAVEMENT REMOVAL	400.00 SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0014	203-02000	EXCAVATION, COMMON	310.00 CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	5265.00 DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0017	205-12618	SWQCP PREPARATION	1.00 LS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	617.00 SYS
0019	211-06467	AGGREGATE FOR END BENT BACKFILL	10.00 CYS
0020	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	635.00 SYS
0021	301-12234	COMPACTED AGGREGATE NO. 53	49.00 CYS
0022	302-06464	SUBBASE FOR PCCP	60.00 CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	252.00 TON
0024	306-08034	MILLING, ASPHALT, 1 1/2 IN.	196.00 SYS
0025	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	41.00 TON
0026	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	41.00 TON
0027	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	178.00 TON
0028	401-10258	JOINT ADHESIVE, SURFACE	300.00 LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	180.00 LFT
0030	401-11785	LIQUID ASPHALT SEALANT	300.00 LFT
0031	406-05521	ASPHALT FOR TACK COAT	782.00 SYS

0032	503-12477	TERMINAL JOINT, TYPE HMA	88.00	LFT
0033	601-02241	GUARDRAIL, REMOVE	720.00	LFT
0034	601-09238	HAND DIG GUARDRAIL POST HOLES	2.00	EACH
0035	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	344.00	LFT
0036	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00	EACH
0037	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0038	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	276.00	SYS
0039	616-06405	RIPRAP, REVETMENT	221.00	TON
0040	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0041	621-06559	MULCHED SEEDING R	222.00	SYS
0042	621-12612	SEED MIXTURE FLOODPLAIN	4.00	LBS
0043	628-09403	FIELD OFFICE, C	6.00	MOS
0044	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0045	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0046	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0047	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	6.00	MOS
0048	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0049	628-11977	COMPUTER SYSTEM	1.00	EACH
0050	702-51863	FIELD DRILLED HOLE IN CONCRETE	96.00	EACH
0051	703-06029	REINFORCING BARS, EPOXY COATED	23464.00	LBS
0052	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	48.00	EACH
0053	704-51002	CONCRETE, C, SUPERSTRUCTURE	25.20	CYS
0054	706-11600	RAILING, CONCRETE FC	2.40	CYS
0055	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0056	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00	LS
0057	709-51821	SURFACE SEAL	1.00	LS
0058	710-09158	PATCHING CONCRETE STRUCTURES	37.00	SFT
0059	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS
0060	713-04331	TEMPORARY CAUSEWAY	1.00	LS
0061	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	4.00	EACH
0062	722-01066	HYDRODEMOLITION	334.00	SYS
0063	722-12380	BRIDGE DECK OVERLAY, BUDGET	6303.00	DOL
0064	722-12382	TRANSVERSE GROOVING	659.00	SYS
0065	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	334.00	SYS
0066	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	50.00	SFT
0067	724-12103	PRE-COMPRESSED FOAM JOINT	88.00	LFT
0068	726-92406	BEARING ASSEMBLY ELASTOMERIC	24.00	EACH

0069	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0070	801-06625	DETOUR ROUTE MARKER ASSEMBLY	42.00	EACH
0071	801-06640	CONSTRUCTION SIGN, A	11.00	EACH
0072	801-06775	MAINTAINING TRAFFIC	1.00	LS
0073	801-07118	BARRICADE, III-A	84.00	LFT
0074	801-07119	BARRICADE, III-B	78.00	LFT
0075	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0076	802-91122	SIGN GROUND MOUNTED RESET	6.00	EACH
0077	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	168.00	LFT
0078	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	474.00	LFT
0079	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	620.00	LFT
0080	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	3.00	EACH

Call: 340

Contract: B -41109-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0081	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	383.00	SYS

Call: 340

Contract: B -41109-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0082	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	383.00	SYS

Call: 344

Contract: B -41951-B

Section No.: 1 BRIDGE DECK REPLACEMENT AND PAINTING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	50.00	SYS
0012	202-02278	CURB, CONCRETE, REMOVE	185.00	LFT
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	202-91385	INLET, REMOVE	1.00	EACH
0015	203-02000	EXCAVATION, COMMON	126.00	CYS
0016	203-02020	EXCAVATION, UNCLASSIFIED	100.00	CYS
0017	205-12108	STORMWATER MANAGEMENT BUDGET	10030.00	DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	205-12618	SWQCP PREPARATION	1.00	LS
0020	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	55.60	CYS
0021	206-51235	COFFERDAM	1.00	LS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	430.00	SYS
0023	211-06467	AGGREGATE FOR END BENT BACKFILL	26.60	CYS
0024	214-12244	GEOTEXTILE FOR SUBGRADE TYPE 2B	430.00	SYS
0025	301-12234	COMPACTED AGGREGATE NO. 53	50.80	CYS
0026	302-06464	SUBBASE FOR PCCP	48.00	CYS
0027	304-07493	WIDENING WITH HMA, TYPE B	37.40	TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1396.00	SYS
0029	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	115.20	TON
0030	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	36.90	TON
0031	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	162.30	TON

0032	401-10258	JOINT ADHESIVE, SURFACE	403.50	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	212.50	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	403.50	LFT
0035	406-05521	ASPHALT FOR TACK COAT	2792.00	SYS
0036	503-12477	TERMINAL JOINT, TYPE HMA	75.00	LFT
0037	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0038	601-02241	GUARDRAIL, REMOVE	780.00	LFT
0039	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	1.00	EACH
0040	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	50.00	LFT
0041	601-12291	GUARDRAIL MGS TRANSITION WITH CURB	2.00	EACH
0042	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	2.00	EACH
0043	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0044	605-06090	CURB, INTEGRAL CONCRETE	190.00	LFT
0045	605-06121	CURB, CONCRETE B	235.00	LFT
0046	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	193.00	SYS
0047	616-05688	RIPRAP, CLASS 1	1212.00	TON
0048	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	1086.00	SYS
0049	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0050	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0051	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0052	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0053	621-06559	MULCHED SEEDING R	2670.00	SYS
0054	628-09403	FIELD OFFICE, C	12.00	MOS
0055	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0056	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	8.00	EACH
0057	702-51005	CONCRETE, A, SUBSTRUCTURE	22.60	CYS
0058	703-06029	REINFORCING BARS, EPOXY COATED	155199.00	LBS
0059	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	32.00	EACH
0060	704-51002	CONCRETE, C, SUPERSTRUCTURE	357.40	CYS
0061	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	3.00	EACH
0062	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	1.00	EACH
0063	706-11404	RAILING, STEEL PF-1	856.30	LFT
0064	706-11602	RAILING, CONCRETE PF-1	52.60	CYS
0065	709-51821	SURFACE SEAL	1.00	LS
0066	710-09158	PATCHING CONCRETE STRUCTURES	200.00	SFT
0067	711-51038	STRUCTURAL STEEL	1.00	LS
0068	711-51864	DRILLED HOLE	564.00	EACH

0069	711-51877	JACKING AND SUPPORTING, BEAMS	1.00	LS
0070	711-96800	STUD SHEAR CONNECTORS	1422.00	EACH
0071	713-04331	TEMPORARY CAUSEWAY	1.00	LS
0072	715-05407	PIPE, END BENT DRAIN, 6 IN.	120.00	LFT
0073	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00	EACH
0074	720-44000	CASTING, ADJUST TO GRADE	2.00	EACH
0075	724-12103	PRE-COMPRESSED FOAM JOINT	75.00	LFT
0076	801-03290	CONSTRUCTION SIGN, C	10.00	EACH
0077	801-03291	CONSTRUCTION SIGN, D	8.00	EACH
0078	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0079	801-06625	DETOUR ROUTE MARKER ASSEMBLY	11.00	EACH
0080	801-06640	CONSTRUCTION SIGN, A	11.00	EACH
0081	801-06645	CONSTRUCTION SIGN, B	5.00	EACH
0082	801-06775	MAINTAINING TRAFFIC	1.00	LS
0083	801-06775	MAINTAINING TRAFFIC	1.00	LS
0084	801-07118	BARRICADE, III-A	48.00	LFT
0085	801-07119	BARRICADE, III-B	12.00	LFT
0086	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	4.00	SFT
0087	802-11648	SIGN POST	1.00	EACH
0088	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1568.00	LFT
0089	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1568.00	LFT
0090	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	24.00	LFT
0091	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	1.00	EACH
0092	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	1.00	EACH
0093	808-12032	GROOVING FOR PAVEMENT MARKINGS	1424.00	LFT

Call: 350

Contract: B -42911-A

Section No.: 1 BRIDGE MAINTENANCE AND REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	306-08034	MILLING, ASPHALT, 1 1/2 IN.	729.00	SYS
0010	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	61.00	TON
0011	619-98427	CLEAN DRAINS	6.00	EACH
0012	628-09401	FIELD OFFICE, A	6.00	MOS
0013	628-11729	CELLULAR TELEPHONE, TYPE A	2.00	EACH
0014	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0015	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0016	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	12.00	MOS
0017	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0018	628-11977	COMPUTER SYSTEM	2.00	EACH
0019	628-12685	TELEPHONE SERVICE, A	6.00	MOS
0020	709-51821	SURFACE SEAL	1.00	LS
0021	709-51821	SURFACE SEAL	1.00	LS
0022	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	90.00	SFT
0023	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	446.00	SFT
0024	724-12103	PRE-COMPRESSED FOAM JOINT	136.00	LFT
0025	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0026	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	10088.00	LFT
0027	801-06640	CONSTRUCTION SIGN, A	26.00	EACH
0028	801-06710	FLASHING ARROW SIGN	120.00	DAY
0029	801-06775	MAINTAINING TRAFFIC	1.00	LS
0030	801-07119	BARRICADE, III-B	156.00	LFT
0031	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH

0032	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1252.00	LFT
0033	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1252.00	LFT
0034	808-06716	LINE, REMOVE	2834.00	LFT
0035	808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	643.00	LFT
0036	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6.00	EACH

Call: 410

Contract: M -43593-A

Section No.: 1 TREE REMOVAL AND TRIMMING

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0005	201-02245	TREE 6 IN., REMOVE	1.00	EACH
0006	201-02250	TREE 10 IN., REMOVE	9.00	EACH
0007	201-02255	TREE 18 IN., REMOVE	46.00	EACH
0008	201-02260	TREE 30 IN., REMOVE	10.00	EACH
0009	201-02265	TREE 48 IN., REMOVE	3.00	EACH
0010	801-06640	CONSTRUCTION SIGN, A	6.00	EACH
0011	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 510

Contract: T -41259-A

Section No.: 1 GUARDRAIL ATTENUATORS, NEW OR MODERNIZE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0009	202-02271	HEADWALL, REMOVE	4.00 EACH
0010	202-02272	PAVED SIDE DITCH, REMOVE	15.00 LFT
0011	202-93741	GUARDRAIL, END TREATMENT, REMOVE	31.00 EACH
0012	203-02000	EXCAVATION, COMMON	450.00 CYS
0013	203-02070	BORROW	215.00 CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	19560.00 DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0016	205-12618	SWQCP PREPARATION	1.00 LS
0017	211-09264	STRUCTURE BACKFILL, TYPE 1	8.00 CYS
0018	303-01180	COMPACTED AGGREGATE NO. 53	1733.00 TON
0019	601-01839	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 6	1.00 EACH
0020	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	5.00 EACH
0021	601-02241	GUARDRAIL, REMOVE	2150.00 LFT
0022	601-02625	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM, CURVED, 2, MODIFIED	2.00 EACH
0023	601-05585	GUARDRAIL, TERMINAL SYSTEM, W- BEAM, CURVED, 8	1.00 EACH
0024	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	1.00 EACH
0025	601-09238	HAND DIG GUARDRAIL POST HOLES	34.00 EACH
0026	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	219.00 LFT
0027	601-12289	GUARDRAIL MGS, HEIGHT TRANSITION	23.00 EACH
0028	601-94689	GUARDRAIL, END TREATMENT, OS	23.00 EACH
0029	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	157.00 LFT
0030	616-06451	RIPRAP, UNIFORM	40.00 TON
0031	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	110.00 SYS

0032	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00 EACH
0033	621-02770	EROSION CONTROL BLANKET	2835.00 SYS
0034	621-06559	MULCHED SEEDING R	5810.00 SYS
0035	628-09401	FIELD OFFICE, A	8.00 MOS
0036	628-11729	CELLULAR TELEPHONE, TYPE A	1.00 EACH
0037	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0038	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0039	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	8.00 MOS
0040	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0041	628-11977	COMPUTER SYSTEM	1.00 EACH
0042	715-03476	SAFETY METAL END SECTION, 4:1, DIA 24 IN.	1.00 EACH
0043	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	50.00 LFT
0044	715-05597	PIPE EXTENSION, CIRCULAR, 24 IN.	20.00 LFT
0045	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00 EACH
0046	715-99044	GRATED BOX END SECTION, II, 6:1, DIAMETER 18 IN.	1.00 EACH
0047	801-06640	CONSTRUCTION SIGN, A	54.00 EACH
0048	801-06775	MAINTAINING TRAFFIC	1.00 LS

Call: 520

Contract: T -41261-A

Section No.: 1 TRAFFIC SIGNAL MODERNIZATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	6.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-02278	CURB, CONCRETE, REMOVE	170.00 LFT
0012	202-52710	SIDEWALK CONCRETE, REMOVE	121.00 SYS
0013	202-90277	DETECTOR HOUSING, REMOVE	16.00 EACH
0014	202-92607	SIGN POST, CHANNEL, REMOVE	5.00 EACH
0015	203-02000	EXCAVATION, COMMON	2.00 CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	530.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	111.00 SYS
0019	304-12625	HMA PATCHING FULL DEPTH TYPE C	29.00 TON
0020	604-06070	SIDEWALK, CONCRETE	60.00 SYS
0021	604-08086	CURB RAMP, CONCRETE	76.00 SYS
0022	604-12083	DETECTABLE WARNING SURFACES	13.00 SYS
0023	605-06120	CURB, CONCRETE	63.00 LFT
0024	605-06140	CURB AND GUTTER, CONCRETE	186.00 LFT
0025	621-06575	SODDING, NURSERY	72.00 SYS
0026	628-09401	FIELD OFFICE, A	6.00 MOS
0027	628-11729	CELLULAR TELEPHONE, TYPE A	1.00 EACH
0028	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0029	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0030	628-11780	CELLULAR TELEPHONE SERVICE, 500 MIN.	6.00 MOS
0031	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH

0032	628-11977	COMPUTER SYSTEM	6.00 EACH
0033	720-44000	CASTING, ADJUST TO GRADE	1.00 EACH
0034	801-02617	TEMPORARY POLE WOOD WITH DOWN GUYS AND ANCHORS	2.00 EACH
0035	801-06640	CONSTRUCTION SIGN, A	17.00 EACH
0036	801-06645	CONSTRUCTION SIGN, B	5.00 EACH
0037	801-06775	MAINTAINING TRAFFIC	1.00 LS
0038	802-05701	SIGN POST, SQUARE TYPE 1 REINFORCED ANCHOR BASE	50.00 LFT
0039	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	131.00 SFT
0040	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	199.00 SFT
0041	802-91122	SIGN GROUND MOUNTED RESET	2.00 EACH
0042	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	4.00 EACH
0043	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00 LS
0044	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	14.00 EACH
0045	805-01842	HANDHOLE SIGNAL TYPE 1	1.00 EACH
0046	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00 LS
0047	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	6.00 EACH
0048	805-04133	SIGNAL POLE, PEDESTAL, 12FT	5.00 EACH
0049	805-06483	CONTROLLER	1.00 EACH
0050	805-07190	TRAFFIC SIGNAL HEAD, 1 SECTION, 12 IN.	16.00 EACH
0051	805-08244	CELLULAR MODEM KIT	3.00 EACH
0052	805-11814	CONDUIT, HDPE, 2 IN. SCHEDULE 40	2065.00 LFT
0053	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	1445.00 LFT
0054	805-11817	PEDESTRIAN PUSH BUTTON, APS	6.00 EACH
0055	805-78010	CONTROLLER AND CABINET, FLASHER SOLID STATE	2.00 EACH
0056	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	14.00 EACH
0057	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	3.00 EACH
0058	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	3.00 EACH
0059	805-78415	SPAN, CATENARY, AND TETHER	16.00 EACH
0060	805-78420	DISCONNECT HANGER	15.00 EACH
0061	805-78445	SIGNAL SERVICE	3.00 EACH
0062	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GA	290.00 LFT
0063	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GA	5674.00 LFT
0064	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GA	3630.00 LFT
0065	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GA	3710.00 LFT
0066	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GA	420.00 LFT
0067	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GA	2050.00 LFT
0068	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GA	8400.00 LFT

0069	805-78785	SIGNAL DETECTOR HOUSING	16.00 EACH
0070	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1919.00 LFT
0071	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00 EACH
0072	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	14.00 EACH
0073	805-92504	LOOP DETECTOR DELAY AMPLIFIER, 2 CHANNEL	8.00 EACH
0074	805-93067	CONTROLLER CABINET, P	1.00 EACH
0075	808-06368	TRANSVERSE MARKING, REMOVE	136.00 LFT
0076	808-06716	LINE, REMOVE	394.00 LFT
0077	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	394.00 LFT
0078	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	136.00 LFT

Call: 526

Contract: T -41274-B

Section No.: 1 ITS TRAFFIC MANAGEMENT SYSTEMS

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	6.00 EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-06587	CLEARING AND GRUBBING	0.10 ACRE
0011	205-12108	STORMWATER MANAGEMENT BUDGET	26809.73 DOL
0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0013	211-09194	B BORROW	17.00 TON
0014	601-06246	IMPACT ATTENUATOR, R2-W1, TL-3	6.00 EACH
0015	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN SPACING	462.50 LFT
0016	601-12292	GUARDRAIL MGS TRANSITION WITHOUT CURB	4.00 EACH
0017	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	5.00 EACH
0018	601-94689	GUARDRAIL, END TREATMENT, OS	2.00 EACH
0019	602-91266	CONCRETE MEDIAN BARRIER MODIFIED	64.00 LFT
0020	616-05688	RIPRAP, CLASS 1	16.00 TON
0021	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.00 EACH
0022	621-06560	MULCHED SEEDING U	1710.00 SYS
0023	628-09403	FIELD OFFICE, C	12.00 MOS
0024	703-06029	REINFORCING BARS, EPOXY COATED	1652.90 LBS
0025	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	14.00 EACH
0026	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00 EACH
0027	801-06625	DETOUR ROUTE MARKER ASSEMBLY	18.00 EACH
0028	801-06640	CONSTRUCTION SIGN, A	106.00 EACH
0029	801-06645	CONSTRUCTION SIGN, B	40.00 EACH
0030	801-06710	FLASHING ARROW SIGN	200.00 DAY
0031	801-06775	MAINTAINING TRAFFIC	1.00 LS

0032	801-07118	BARRICADE, III-A	64.00	LFT
0033	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	4600.00	LFT
0034	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0035	801-12042	TRUCK MOUNTED ATTENUATOR	18.00	DAY
0036	802-06402	DYNAMIC MESSAGE SIGN	5.00	EACH
0037	802-07061	OVERHEAD SIGN STRUCTURE, DMS BOX TRUSS	5.00	EACH
0038	802-09537	BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN. MEDIAN OR SHOULDER	10.00	EACH
0039	805-02645	SIGNAL POLE FOUNDATION 24 IN. X 24 IN. X 36 IN.	3.00	EACH
0040	805-09846	RECEIVER PROCESSOR	9.00	EACH
0041	805-10107	WIRELESS MAGNETOMETER DETECTOR	72.00	EACH
0042	805-10108	WIRELESS REPEATER	3.00	EACH
0043	805-11689	SIGNAL POLE, PEDESTAL, 20 FT	3.00	EACH
0044	805-11744	HANDHOLE SIGNAL TYPE 2	9.00	EACH
0045	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	7627.00	LFT
0046	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	540.00	LFT
0047	807-04651	WIRE	12040.00	LFT
0048	807-04651	WIRE	12040.00	LFT
0049	807-04651	WIRE	820.00	LFT
0050	807-04651	WIRE	820.00	LFT
0051	807-78590	HANDHOLE	59.00	EACH
0052	809-04652	SERVICE POINT	14.00	EACH
0053	809-04652	SERVICE POINT	12.00	EACH
0054	809-04982	CABLE	1500.00	LFT
0055	809-06101	FOUNDATION	9.00	EACH
0056	809-08398	ITS CONTROLLER CABINET	9.00	EACH
0057	809-09343	ITS	9.00	EACH
0058	809-09343	ITS	14.00	EACH
0059	809-09343	ITS	5.00	EACH
0060	809-09343	ITS	48.00	EACH
0061	809-09343	ITS	3.00	EACH
0062	809-09343	ITS	6.00	EACH
0063	809-09343	ITS	14.00	EACH
0064	809-12723	SERVICE POINT, ATMS, CONNECTION ALLOWANCE	11200.00	DOL

Call: 530

Contract: T -43514-A

Section No.: 1 CENTERLINE RUMBLE STRIPES INSTALLATION

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	401-11785	LIQUID ASPHALT SEALANT	30301.00	LFT
0010	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	30301.00	LFT
0011	801-06640	CONSTRUCTION SIGN, A	6.00	EACH
0012	801-06775	MAINTAINING TRAFFIC	1.00	LS
0013	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	7770.00	LFT
0014	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	61931.00	LFT
0015	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2761.00	LFT
0016	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0017	808-75994	PRISMATIC REFLECTOR	824.00	EACH
0018	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	206.00	EACH