

Schedule of Pay Items Letting Date December 21, 2022 Letting ID 221221

Call: 111

Contract: B -44236-B

Section No.: 1 TOLL GANTRY MODERNIZATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0009	202-93741	GUARDRAIL, END TREATMENT, REMOVE	3.00 EACH
0010	202-94954	BARRIER WALL, CONCRETE, REMOVE	92.00 LFT
0011	203-02000	EXCAVATION, COMMON	345.00 CYS
0012	205-12108	STORMWATER MANAGEMENT BUDGET	80000.00 DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0014	211-02050	B BORROW	70.00 CYS
0015	211-09266	STRUCTURE BACKFILL, TYPE 3	141.00 CYS
0016	214-12236	GEOTEXTILE FOR PAVEMENT, TYPE 1A	31.00 SYS
0017	303-01180	COMPACTED AGGREGATE NO. 53	95.00 TON
0018	601-02241	GUARDRAIL, REMOVE	12.50 LFT
0019	601-02565	GUARDRAIL, W-BEAM 12 FT 6 IN. SPACING	125.00 LFT
0020	601-05999	CURVED TERMINAL END	1.00 EACH
0021	601-09238	HAND DIG GUARDRAIL POST HOLES	12.00 EACH
0022	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	3.00 EACH
0023	601-94689	GUARDRAIL, END TREATMENT, OS	2.00 EACH
0024	602-01064	CONCRETE BARRIER	18.00 LFT
0025	603-01752	FENCE GATE, CHAIN LINK, 96 IN. X 5 FT	4.00 EACH
0026	603-01932	FENCE, CHAIN LINK, 96 IN.	296.00 LFT
0027	628-09403	FIELD OFFICE, C	12.00 MOS
0028	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0029	702-51863	FIELD DRILLED HOLE IN CONCRETE	24.00 EACH
0030	732-11770	AGGREGATE FOR DRAINAGE FILL	20.00 CYS
0031	732-11811	MODULAR BLOCK WALL ERECTION	460.00 SFT

0032	732-11812	MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	460.00	SFT
0033	801-04308	ROAD CLOSURE SIGN ASSEMBLY	22.00	EACH
0034	801-06640	CONSTRUCTION SIGN, A	244.00	EACH
0035	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0036	801-06710	FLASHING ARROW SIGN	252.00	DAY
0037	801-06775	MAINTAINING TRAFFIC	1.00	LS
0038	801-07119	BARRICADE, III-B	430.00	LFT
0039	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	240.00	LFT
0040	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	37.00	EACH
0041	801-12042	TRUCK MOUNTED ATTENUATOR	160.00	DAY
0042	801-12324	LAW ENFORCEMENT OFFICER	184.00	HRS
0043	802-09221	OVERHEAD SIGN STRUCTURE, BOX TRUSS, TYPE A	6.00	EACH
0044	802-09536	BOX TRUSS SIGN STRUCTURE FOUNDATION, 45 IN. CONCRETE BARRIER WALL	4.00	EACH
0045	802-09537	BOX TRUSS SIGN STRUCTURE FOUNDATION, 36 IN. MEDIAN OR SHOULDER	8.00	EACH
0046	802-91122	SIGN GROUND MOUNTED RESET	3.00	EACH
0047	805-78785	SIGNAL DETECTOR HOUSING	29.00	EACH
0048	807-02560	ELECTRICAL WORK	1.00	LS
0049	809-08399	ITS CONTROLLER CABINET FOUNDATION	4.00	EACH