

**Schedule of Pay Items   Letting Date   March 9, 2022   Letting ID   220309**

Call: 501

Contract: B -39781-B

Section No.: 1              BRIDGE DECK REPLACEMENT

| Line    |           |                                                                                          |          |      |
|---------|-----------|------------------------------------------------------------------------------------------|----------|------|
| Item No | Item Code | Description                                                                              | Quantity | Unit |
| 0001    | 105-06845 | CONSTRUCTION ENGINEERING                                                                 | 1.00     | LS   |
| 0002    | 105-12018 | UTILITY PROTECTION                                                                       | 1.00     | LS   |
| 0003    | 109-08359 | LIQUIDATED DAMAGES                                                                       | 1.00     | DOL  |
| 0004    | 109-08360 | CONTRACT LIENS                                                                           | 1.00     | DOL  |
| 0005    | 109-08440 | QUALITY ADJUSTMENTS, HMA                                                                 | 1.00     | DOL  |
| 0006    | 109-08443 | QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES                                   | 1.00     | DOL  |
| 0007    | 109-08444 | QUALITY ADJUSTMENTS, FAILED MATERIALS                                                    | 1.00     | DOL  |
| 0008    | 109-08463 | PROJECT ESTIMATE ADJUSTMENT                                                              | 1.00     | DOL  |
| 0009    | 109-09489 | PAYMENT ADJUSTMENT PG ASPHALT BINDER                                                     | 1.00     | DOL  |
| 0010    | 109-11362 | QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES | 1.00     | DOL  |
| 0011    | 110-01001 | MOBILIZATION AND DEMOBILIZATION                                                          | 1.00     | LS   |
| 0012    | 201-52370 | CLEARING RIGHT OF WAY                                                                    | 1.00     | LS   |
| 0013    | 202-01261 | TESTING FOR ASBESTOS                                                                     | 2.00     | EACH |
| 0014    | 202-02240 | PAVEMENT REMOVAL                                                                         | 236.00   | SYS  |
| 0015    | 202-02637 | PIPE ABANDON AND GROUT FILL                                                              | 24.00    | LFT  |
| 0016    | 202-03729 | REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE                                          | 80.00    | LFT  |
| 0017    | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS                                                       | 1.00     | LS   |
| 0018    | 202-51328 | PRESENT STRUCTURE, REMOVE PORTIONS                                                       | 1.00     | LS   |
| 0019    | 202-93741 | GUARDRAIL, END TREATMENT, REMOVE                                                         | 1.00     | EACH |
| 0020    | 202-96133 | PIPE, REMOVE                                                                             | 477.00   | LFT  |
| 0021    | 203-02000 | EXCAVATION, COMMON                                                                       | 385.00   | CYS  |
| 0022    | 205-12108 | STORMWATER MANAGEMENT BUDGET                                                             | 16000.00 | DOL  |
| 0023    | 205-12616 | STORMWATER MANAGEMENT IMPLEMENTATION                                                     | 1.00     | LS   |
| 0024    | 205-12618 | SWQCP PREPARATION                                                                        | 1.00     | LS   |
| 0025    | 206-51230 | EXCAVATION, FOUNDATION, UNCLASSIFIED                                                     | 50.00    | CYS  |
| 0026    | 206-51235 | COFFERDAM                                                                                | 1.00     | LS   |
| 0027    | 207-09935 | SUBGRADE TREATMENT, TYPE IC                                                              | 824.00   | SYS  |
| 0028    | 211-06467 | AGGREGATE FOR END BENT BACKFILL                                                          | 50.00    | CYS  |
| 0029    | 211-09194 | B BORROW                                                                                 | 32.00    | TON  |
| 0030    | 213-09269 | FLOWABLE BACKFILL, NON-REMOVABLE                                                         | 266.00   | CYS  |
| 0031    | 214-12239 | GEOTEXTILE FOR PAVEMENT TYPE 2B                                                          | 824.00   | SYS  |

|      |           |                                                 |         |      |
|------|-----------|-------------------------------------------------|---------|------|
| 0032 | 301-12234 | COMPACTED AGGREGATE NO. 53                      | 244.00  | CYS  |
| 0033 | 302-06464 | SUBBASE FOR PCCP                                | 64.00   | CYS  |
| 0034 | 303-01180 | COMPACTED AGGREGATE NO. 53                      | 146.00  | TON  |
| 0035 | 306-08043 | MILLING, TRANSITION                             | 4175.00 | SYS  |
| 0036 | 401-07322 | QC/QA-HMA, 3, 64, SURFACE, 9.5 mm               | 381.00  | TON  |
| 0037 | 401-07390 | QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm         | 484.00  | TON  |
| 0038 | 401-07407 | QC/QA-HMA, 2, 64, BASE, 25.0 mm                 | 240.00  | TON  |
| 0039 | 401-10258 | JOINT ADHESIVE, SURFACE                         | 3600.00 | LFT  |
| 0040 | 401-10259 | JOINT ADHESIVE, INTERMEDIATE                    | 2520.00 | LFT  |
| 0041 | 401-11785 | LIQUID ASPHALT SEALANT                          | 3600.00 | LFT  |
| 0042 | 406-05521 | ASPHALT FOR TACK COAT                           | 7951.00 | SYS  |
| 0043 | 503-12477 | TERMINAL JOINT, TYPE HMA                        | 128.00  | LFT  |
| 0044 | 601-02241 | GUARDRAIL, REMOVE                               | 1185.00 | LFT  |
| 0045 | 601-06035 | GUARDRAIL, RESET                                | 1050.00 | LFT  |
| 0046 | 601-12281 | GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING        | 443.75  | LFT  |
| 0047 | 601-12289 | GUARDRAIL, MGS, HEIGHT TRANSITION               | 7.00    | EACH |
| 0048 | 601-12292 | GUARDRAIL, MGS, TRANSITION WITHOUT CURB         | 8.00    | EACH |
| 0049 | 601-94689 | GUARDRAIL, END TREATMENT, OS                    | 1.00    | EACH |
| 0050 | 602-06729 | BARRIER, DELINEATOR                             | 26.00   | EACH |
| 0051 | 603-97461 | TEMPORARY FENCE                                 | 700.00  | LFT  |
| 0052 | 609-06259 | REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.     | 313.60  | SYS  |
| 0053 | 616-06405 | RIPRAP, REVETMENT                               | 1160.00 | TON  |
| 0054 | 616-12249 | GEOTEXTILE FOR RIPRAP TYPE 2B                   | 150.00  | SYS  |
| 0055 | 616-12251 | GEOTEXTILE FOR RIPRAP TYPE 3                    | 1490.00 | SYS  |
| 0056 | 619-11052 | CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.            | 1.00    | LS   |
| 0057 | 619-11052 | CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.            | 1.00    | LS   |
| 0058 | 619-12459 | DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO. | 1.00    | LS   |
| 0059 | 619-12459 | DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO. | 1.00    | LS   |
| 0060 | 619-12506 | CLEAN STEEL BRIDGE TOP FLANGES QP-2 BRIDGE NO.  | 1.00    | LS   |
| 0061 | 619-12506 | CLEAN STEEL BRIDGE TOP FLANGES QP-2 BRIDGE NO.  | 1.00    | LS   |
| 0062 | 619-51859 | PAINT STEEL BRIDGE, BRIDGE NO.                  | 1.00    | LS   |
| 0063 | 619-51859 | PAINT STEEL BRIDGE, BRIDGE NO.                  | 1.00    | LS   |
| 0064 | 621-01004 | MOBILIZATION AND DEMOBILIZATION FOR SEEDING     | 2.00    | EACH |
| 0065 | 621-06559 | MULCHED SEEDING R                               | 5000.00 | SYS  |
| 0066 | 621-06567 | WATER                                           | 2.00    | KGAL |
| 0067 | 621-06574 | SODDING                                         | 44.00   | SYS  |
| 0068 | 622-05639 | PLANT, DECIDUOUS SHRUB, 18 IN. TO 24 IN.        | 30.00   | EACH |

|      |           |                                                       |               |
|------|-----------|-------------------------------------------------------|---------------|
| 0069 | 622-05649 | PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. TO 2 IN. | 66.00 EACH    |
| 0070 | 628-11976 | COMPUTER SYSTEM EQUIPMENT                             | 4.00 EACH     |
| 0071 | 628-12683 | FIELD OFFICE, D                                       | 18.00 MOS     |
| 0072 | 702-12076 | GRATES, BASINS, AND FITTINGS, CAST IRON               | 16.00 EACH    |
| 0073 | 702-51005 | CONCRETE, A, SUBSTRUCTURE                             | 57.40 CYS     |
| 0074 | 702-92857 | CONCRETE, C, SUBSTRUCTURE                             | 68.00 CYS     |
| 0075 | 703-06028 | REINFORCING BARS                                      | 6384.00 LBS   |
| 0076 | 703-06029 | REINFORCING BARS, EPOXY COATED                        | 210105.00 LBS |
| 0077 | 703-08247 | EMBEDDED GALVANIC ANODE                               | 200.00 EACH   |
| 0078 | 703-97936 | THREADED TIE BAR ASSEMBLY, EPOXY COATED               | 76.00 EACH    |
| 0079 | 704-51002 | CONCRETE, C, SUPERSTRUCTURE                           | 518.90 CYS    |
| 0080 | 706-09960 | RAILING, CONCRETE FC                                  | 956.00 LFT    |
| 0081 | 706-11620 | CONCRETE BRIDGE RAILING TRANSITION, TFC               | 8.00 EACH     |
| 0082 | 709-51821 | SURFACE SEAL                                          | 1.00 LS       |
| 0083 | 709-51821 | SURFACE SEAL                                          | 1.00 LS       |
| 0084 | 710-09158 | PATCHING CONCRETE STRUCTURES                          | 400.00 SFT    |
| 0085 | 711-51038 | STRUCTURAL STEEL                                      | 1.00 LS       |
| 0086 | 711-51038 | STRUCTURAL STEEL                                      | 1.00 LS       |
| 0087 | 711-51864 | DRILLED HOLE                                          | 84.00 EACH    |
| 0088 | 711-95291 | JACKING AND SUPPORTING, STEEL BEAMS                   | 1.00 LS       |
| 0089 | 711-95291 | JACKING AND SUPPORTING, STEEL BEAMS                   | 1.00 LS       |
| 0090 | 711-96800 | STUD SHEAR CONNECTORS                                 | 4424.00 EACH  |
| 0091 | 713-04331 | TEMPORARY CAUSEWAY                                    | 1.00 LS       |
| 0092 | 713-04331 | TEMPORARY CAUSEWAY                                    | 1.00 LS       |
| 0093 | 715-02745 | GATE VALVE WITH VALVE BOX 8 IN.                       | 12.00 EACH    |
| 0094 | 715-05407 | PIPE, END BENT DRAIN, 6 IN.                           | 220.00 LFT    |
| 0095 | 715-07794 | WATER MAIN CONNECTIONS                                | 4.00 EACH     |
| 0096 | 715-07794 | WATER MAIN CONNECTIONS                                | 4.00 EACH     |
| 0097 | 715-07806 | PIPE STEEL CASING                                     | 477.00 LFT    |
| 0098 | 715-07806 | PIPE STEEL CASING                                     | 477.00 LFT    |
| 0099 | 715-08083 | CONCRETE ANCHOR, MIN. AREA 58 SFT                     | 16.00 EACH    |
| 0100 | 715-10238 | PIPE, ROADWAY DRAIN CASTING EXTENSION                 | 16.00 EACH    |
| 0101 | 715-11571 | WATER MAIN, DUCTILE IRON, 8 IN.                       | 717.00 LFT    |
| 0102 | 715-12674 | GATE VALVE AND VALVE BOX 12 IN.                       | 4.00 EACH     |
| 0103 | 715-92544 | WATER MAIN, DUCTILE IRON, 12 IN.                      | 637.00 LFT    |
| 0104 | 718-12309 | GEOTEXTILE FOR UNDERDRAIN, TYPE 3                     | 140.00 SYS    |
| 0105 | 726-92406 | BEARING ASSEMBLY ELASTOMERIC                          | 28.00 EACH    |

|      |           |                                             |             |
|------|-----------|---------------------------------------------|-------------|
| 0106 | 801-03290 | CONSTRUCTION SIGN, C                        | 8.00 EACH   |
| 0107 | 801-04308 | ROAD CLOSURE SIGN ASSEMBLY                  | 14.00 EACH  |
| 0108 | 801-06625 | DETOUR ROUTE MARKER ASSEMBLY                | 47.00 EACH  |
| 0109 | 801-06640 | CONSTRUCTION SIGN, A                        | 15.00 EACH  |
| 0110 | 801-06645 | CONSTRUCTION SIGN, B                        | 2.00 EACH   |
| 0111 | 801-06775 | MAINTAINING TRAFFIC                         | 1.00 LS     |
| 0112 | 801-07118 | BARRICADE, III-A                            | 96.00 LFT   |
| 0113 | 801-07119 | BARRICADE, III-B                            | 108.00 LFT  |
| 0114 | 802-04089 | SIGN, SHEET, REMOVE                         | 1.00 EACH   |
| 0115 | 802-91122 | SIGN GROUND MOUNTED RESET                   | 11.00 EACH  |
| 0116 | 803-61430 | BRIDGE BRACKET A GALVANIZED                 | 26.00 EACH  |
| 0117 | 803-61430 | BRIDGE BRACKET A GALVANIZED                 | 26.00 EACH  |
| 0118 | 808-06712 | LINE, PAINT, BROKEN, YELLOW, 4 IN.          | 220.00 LFT  |
| 0119 | 808-06713 | LINE, PAINT, SOLID, WHITE, 4 IN.            | 3540.00 LFT |
| 0120 | 808-06714 | LINE, PAINT, SOLID, YELLOW, 4 IN.           | 2490.00 LFT |
| 0121 | 808-75996 | SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE | 28.00 EACH  |
| 0122 | 808-75998 | SNOWPLOWABLE RAISED PAVEMENT MARKER         | 28.00 EACH  |