

Schedule of Pay Items Letting Date May 5, 2022 Letting ID 220505

Call: 110

Contract: R -37647-B

Section No.: 1 ROAD RECONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-02240	PAVEMENT REMOVAL	9000.00 SYS
0012	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0013	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0014	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0015	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0016	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0017	202-03135	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	120.00 SFT
0018	203-02000	EXCAVATION, COMMON	9470.00 CYS
0019	205-12108	STORMWATER MANAGEMENT BUDGET	25499.00 DOL
0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0021	205-12618	SWQCP PREPARATION	1.00 LS
0022	207-08264	SUBGRADE TREATMENT, TYPE II	1109.00 SYS
0023	207-08268	SUBGRADE TREATMENT, TYPE IV	13676.00 SYS
0024	207-09935	SUBGRADE TREATMENT, TYPE IC	354.00 SYS
0025	211-09264	STRUCTURE BACKFILL, TYPE 1	5646.00 CYS
0026	302-07455	DENSE GRADED SUBBASE	184.00 CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	2413.00 TON
0028	304-12625	HMA PATCHING FULL DEPTH, TYPE C	394.00 TON
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1456.00 SYS
0030	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	822.00 TON
0031	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	107.00 TON

0032	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1892.00	TON
0033	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	1917.00	TON
0034	401-10258	JOINT ADHESIVE, SURFACE	5133.00	LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	4769.00	LFT
0036	401-11785	LIQUID ASPHALT SEALANT	5133.00	LFT
0037	406-05520	ASPHALT FOR TACK COAT	5.90	TON
0038	604-06070	SIDEWALK, CONCRETE	3355.00	SYS
0039	604-08086	CURB RAMP, CONCRETE	380.00	SYS
0040	604-12083	DETECTABLE WARNING SURFACES	45.00	SYS
0041	604-44251	STEPS, CONCRETE	15.00	CYS
0042	604-92237	HAND RAIL, STEEL	156.00	LFT
0043	605-06120	CURB, CONCRETE	370.00	LFT
0044	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	5201.00	LFT
0045	610-07487	HMA FOR APPROACHES, TYPE B	750.00	TON
0046	610-08446	PCCP FOR APPROACHES, 6 IN.	1013.00	SYS
0047	610-09108	PCCP FOR APPROACHES, 9 IN.	97.00	SYS
0048	621-06567	WATER	21.92	KGAL
0049	621-06570	TOPSOIL	63.00	CYS
0050	621-06575	SODDING, NURSERY	5490.00	SYS
0051	621-08161	PERMANENT TURF REINFORCEMENT MAT	25.00	SYS
0052	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. TO 2 IN.	124.00	EACH
0053	628-09401	FIELD OFFICE, A	15.00	MOS
0054	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0055	628-11977	COMPUTER SYSTEM	1.00	EACH
0056	715-02744	GATE VALVE AND VALVE BOX 6 IN.	2.00	EACH
0057	715-02745	GATE VALVE WITH VALVE BOX 8 IN.	14.00	EACH
0058	715-02874	CURB STOP AND BOX	68.00	EACH
0059	715-04965	WATER SERVICE LINE	1823.00	LFT
0060	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	6343.00	LFT
0061	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	2278.00	LFT
0062	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	1044.00	LFT
0063	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	519.00	LFT
0064	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	502.00	LFT
0065	715-05203	PIPE, TYPE 4, CIRCULAR, 4 IN.	456.00	LFT
0066	715-05408	PIPE, SANITARY SEWER, 8 IN.	2551.00	LFT
0067	715-08048	STORMWATER TREATMENT SYSTEM	1.00	EACH
0068	715-11879	SEWER, SANITARY LATERAL, CONNECTIONS	1717.00	LFT

0069	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00 EACH
0070	715-90853	TAPPING SLEEVE WITH VALVE	1.00 EACH
0071	715-93913	WATER MAIN, 8 IN.	3486.00 LFT
0072	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	6237.00 SYS
0073	718-52610	AGGREGATE FOR UNDERDRAINS	688.00 CYS
0074	720-10114	SANITARY DROP MANHOLE	1.00 EACH
0075	720-11756	MANHOLE INTERIOR PROTECTIVE COATING	4.00 EACH
0076	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	6.00 EACH
0077	720-45075	INLET, R13	1.00 EACH
0078	720-45240	CATCH BASIN, J10	17.00 EACH
0079	720-45250	CATCH BASIN, K10	38.00 EACH
0080	720-45410	MANHOLE, C4	13.00 EACH
0081	720-45510	MANHOLE, C4 MODIFIED	10.00 EACH
0082	720-96999	FIRE HYDRANT ASSEMBLY	9.00 EACH
0083	731-93947	LEVELING PAD, CONCRETE	368.00 LFT
0084	732-11770	AGGREGATE FOR DRAINAGE FILL	191.00 CYS
0085	732-11810	MODULAR BLOCK WALL	986.00 SFT
0086	732-11811	MODULAR BLOCK WALL ERECTION	986.00 SFT
0087	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2700.00 LFT
0088	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	292.00 LFT
0089	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00 LS
0090	801-06625	DETOUR ROUTE MARKER ASSEMBLY	49.00 EACH
0091	801-06640	CONSTRUCTION SIGN, A	46.00 EACH
0092	801-06645	CONSTRUCTION SIGN, B	28.00 EACH
0093	801-06775	MAINTAINING TRAFFIC	1.00 LS
0094	801-07118	BARRICADE, III-A	168.00 LFT
0095	801-07119	BARRICADE, III-B	96.00 LFT
0096	801-11990	TEMPORARY CURB RAMP	2.00 EACH
0097	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	28.00 SYS
0098	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	130.00 LFT
0099	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	73.75 SFT
0100	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	69.00 SFT
0101	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	19.50 SFT
0102	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00 EACH
0103	805-01579	MISCELLANEOUS EQUIPMENT FOR TRAFFIC SIGNALS	1.00 LS
0104	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00 EACH
0105	805-01842	HANDHOLE, SIGNAL, TYPE 1	5.00 EACH

0106	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	8.00 EACH
0107	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	1.00 EACH
0108	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	244.00 LFT
0109	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	445.00 LFT
0110	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00 EACH
0111	805-78109	CONTROLLER AND CABINET, SECONDARY MENU DRIVEN, 8 PHASE	1.00 EACH
0112	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	8.00 EACH
0113	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	2.00 EACH
0114	805-78415	SPAN, CATENARY, AND TETHER	1.00 EACH
0115	805-78420	DISCONNECT HANGER	4.00 EACH
0116	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	3768.00 LFT
0117	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	1435.00 LFT
0118	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	1196.00 LFT
0119	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	584.00 LFT
0120	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	2556.00 LFT
0121	805-78785	SIGNAL DETECTOR HOUSING	8.00 EACH
0122	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1224.00 LFT
0123	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00 EACH
0124	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	4.00 EACH
0125	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	1.00 EACH
0126	808-12032	GROOVING FOR PAVEMENT MARKINGS	6429.00 LFT
0127	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	470.00 LFT
0128	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	5283.00 LFT
0129	808-75274	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 8 IN.	696.00 LFT
0130	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	155.00 LFT
0131	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	270.00 LFT
0132	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	1366.00 LFT
0133	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	4.00 EACH

Call: 111

Contract: R -34096-A

Section No.: 1 ENHANCEMENT, BIKE AND PEDESTRIAN FACILITIES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	20.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-01015	CLEARING AND GRUBBING	1.00 LS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0013	203-02000	EXCAVATION, COMMON	4611.00 CYS
0014	203-02010	EXCAVATION, ROCK	65.00 CYS
0015	203-02070	BORROW	3898.00 CYS
0016	203-02588	LAGGING, PRECAST CONCRETE	285.00 SYS
0017	205-11626	PUMP AROUND	2.00 EACH
0018	205-12108	STORMWATER MANAGEMENT BUDGET	44009.00 DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0020	205-12618	SWQCP PREPARATION	1.00 LS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	4848.00 SYS
0022	207-08266	SUBGRADE TREATMENT, TYPE III	4412.00 SYS
0023	207-12498	SUBGRADE TREATMENT, TYPE ID	883.00 SYS
0024	211-02050	B BORROW	1116.00 CYS
0025	211-09264	STRUCTURE BACKFILL, TYPE 1	173.00 CYS
0026	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	1.00 EACH
0027	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	3.00 CYS
0028	214-11796	GEOGRID, TYPE IB	7891.00 SYS
0029	301-12234	COMPACTED AGGREGATE NO. 53	2063.00 CYS
0030	302-07455	DENSE GRADED SUBBASE	23.00 CYS
0031	304-12623	HMA PATCHING FULL DEPTH, TYPE B	261.00 TON

0032	306-08159	MILLING, ASPHALT	1973.00	SYS
0033	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	647.00	TON
0034	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1749.00	TON
0035	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	216.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	9959.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	9959.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	9959.00	LFT
0039	402-07451	HMA WEDGE AND LEVEL, TYPE B	109.00	TON
0040	406-05520	ASPHALT FOR TACK COAT	2.00	TON
0041	601-02241	GUARDRAIL, REMOVE	772.00	LFT
0042	601-04793	GUARDRAIL	213.00	LFT
0043	601-06038	GUARDRAIL, END TREATMENT, II	1.00	EACH
0044	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	2.00	EACH
0045	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0046	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	57.00	LFT
0047	601-99106	GUARDRAIL, W-BEAM, 3 FT 1.5 IN. SPACING	360.00	LFT
0048	605-06145	CURB AND GUTTER, B, CONCRETE	840.00	LFT
0049	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	12.00	LFT
0050	605-97937	CURB AND GUTTER, ROLL CURB	14.00	LFT
0051	607-06335	PAVED SIDE DITCH, A	25.00	LFT
0052	610-07487	HMA FOR APPROACHES, TYPE B	154.00	TON
0053	610-08446	PCCP FOR APPROACHES, 6 IN.	13.00	SYS
0054	610-09108	PCCP FOR APPROACHES, 9 IN.	121.00	SYS
0055	611-06497	MAILBOX ASSEMBLY, SINGLE	11.00	EACH
0056	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	16.00	EACH
0057	616-05688	RIPRAP, CLASS 1	317.00	TON
0058	616-06405	RIPRAP, REVETMENT	240.00	TON
0059	616-06451	RIPRAP, UNIFORM	116.00	TON
0060	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	587.00	SYS
0061	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0062	621-02770	EROSION CONTROL BLANKET	2255.00	SYS
0063	621-06559	MULCHED SEEDING R	2845.00	SYS
0064	621-06560	MULCHED SEEDING U	3889.00	SYS
0065	621-06574	SODDING	769.00	SYS
0066	622-52436	SIGN, DO NOT MOW OR SPRAY	2.00	EACH
0067	628-09401	FIELD OFFICE, A	12.00	MOS
0068	701-02938	CORED HOLE IN ROCK, 24 IN.	507.00	LFT

0069	702-51015	CONCRETE, B, FOOTINGS	87.00	CYS
0070	702-51863	FIELD DRILLED HOLE IN CONCRETE	140.00	EACH
0071	702-92857	CONCRETE, C, SUBSTRUCTURE	2.00	CYS
0072	703-06029	REINFORCING BARS, EPOXY COATED	2259.00	LBS
0073	704-51002	CONCRETE, C, SUPERSTRUCTURE	7.00	CYS
0074	711-51038	STRUCTURAL STEEL	1.00	LS
0075	712-04784	STRUCTURE	2.00	EACH
0076	714-12229	STRUCTURE EXTENSION, REINFORCED CONCRETE, BOX SECTIONS, 6 FT X 4 FT	12.00	LFT
0077	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	4.00	LFT
0078	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	16.00	LFT
0079	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	312.00	LFT
0080	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	57.00	LFT
0081	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	50.00	LFT
0082	715-05407	PIPE, END BENT DRAIN, 6 IN.	426.00	LFT
0083	715-05422	PIPE, SLOTTED DRAIN, 12 IN.	80.00	LFT
0084	715-46000	PIPE END SECTION, DIAMETER 12 IN.	16.00	EACH
0085	715-46005	PIPE END SECTION, DIAMETER 15 IN.	4.00	EACH
0086	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0087	718-06531	OUTLET PROTECTOR, 3	1.00	EACH
0088	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	428.00	SYS
0089	732-11770	AGGREGATE FOR DRAINAGE FILL	133.00	CYS
0090	801-06640	CONSTRUCTION SIGN, A	24.00	EACH
0091	801-06645	CONSTRUCTION SIGN, B	18.00	EACH
0092	801-06775	MAINTAINING TRAFFIC	1.00	LS
0093	801-12081	PORTABLE SIGNAL	1.00	LS
0094	801-92448	CONSTRUCTION SIGNS MOBILE	360.00	DAY
0095	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	321.00	LFT
0096	802-07060	SIGN, SHEET, RELOCATE	11.00	EACH
0097	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	108.00	SFT
0098	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	9226.00	LFT
0099	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1732.00	LFT
0100	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	16.00	LFT
0101	808-12176	LINE, PAINT, DOTTED, YELLOW, 4 IN.	175.00	LFT

Call: 121

Contract: R -39840-A

Section No.: 1 ROAD REHABILITATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	202-02240	PAVEMENT REMOVAL	12181.00 SYS
0011	202-02278	CURB, CONCRETE, REMOVE	304.00 LFT
0012	202-02772	CASTING, REMOVE	5.00 EACH
0013	202-02928	CATCH BASIN, REMOVE	12.00 EACH
0014	202-03875	CONCRETE STEPS, REMOVE	28.00 EACH
0015	202-52710	SIDEWALK CONCRETE, REMOVE	250.00 SYS
0016	202-90747	RETAINING WALL, REMOVE	682.00 LFT
0017	202-91385	INLET, REMOVE	5.00 EACH
0018	202-91922	STUMP, REMOVE	9.00 EACH
0019	202-93047	MANHOLE, REMOVE	10.00 EACH
0020	202-96133	PIPE, REMOVE	3848.00 LFT
0021	203-02000	EXCAVATION, COMMON	846.00 CYS
0022	203-02070	BORROW	1827.00 CYS
0023	205-12108	STORMWATER MANAGEMENT BUDGET	12847.00 DOL
0024	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0025	205-12618	SWQCP PREPARATION	1.00 LS
0026	207-08264	SUBGRADE TREATMENT, TYPE II	3497.00 SYS
0027	207-09935	SUBGRADE TREATMENT, TYPE IC	11055.00 SYS
0028	211-02050	B BORROW	49.00 CYS
0029	211-09265	STRUCTURE BACKFILL, TYPE 2	4002.00 CYS
0030	211-09266	STRUCTURE BACKFILL, TYPE 3	148.00 CYS
0031	214-11796	GEOGRID, TYPE IB	549.00 SYS

0032	302-07455	DENSE GRADED SUBBASE	591.00	CYS
0033	304-07493	WIDENING WITH HMA, TYPE B	46.00	TON
0034	306-08034	MILLING, ASPHALT, 1 1/2 IN.	539.00	SYS
0035	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	735.00	TON
0036	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1158.00	TON
0037	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	2780.00	TON
0038	401-10258	JOINT ADHESIVE, SURFACE	3521.00	LFT
0039	401-10259	JOINT ADHESIVE, INTERMEDIATE	3426.00	LFT
0040	401-11785	LIQUID ASPHALT SEALANT	3426.00	LFT
0041	406-05520	ASPHALT FOR TACK COAT	7.00	TON
0042	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00	TON
0043	604-06070	SIDEWALK, CONCRETE	3008.00	SYS
0044	604-08086	CURB RAMP, CONCRETE	160.00	SYS
0045	604-12083	DETECTABLE WARNING SURFACES	35.00	SYS
0046	604-44251	STEPS, CONCRETE	17.00	CYS
0047	605-06120	CURB, CONCRETE	540.00	LFT
0048	605-52807	CURB AND GUTTER, COMBINED	3431.00	LFT
0049	610-07487	HMA FOR APPROACHES, TYPE B	430.00	TON
0050	610-08446	PCCP FOR APPROACHES, 6 IN.	2948.00	SYS
0051	610-09108	PCCP FOR APPROACHES, 9 IN.	549.00	SYS
0052	615-06505	MONUMENT, B	3.00	EACH
0053	621-06567	WATER	23.00	KGAL
0054	621-06575	SODDING, NURSERY	5652.00	SYS
0055	628-09403	FIELD OFFICE, C	14.00	MOS
0056	629-12029	PLANT GROWTH LAYER	5652.00	SYS
0057	715-05146	PIPE, TYPE 2, CIRCULAR, 6 IN.	152.00	LFT
0058	715-05147	PIPE, TYPE 2, CIRCULAR, 8 IN.	6.00	LFT
0059	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	267.00	LFT
0060	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	655.00	LFT
0061	715-05408	PIPE, SANITARY SEWER, 8 IN.	36.00	LFT
0062	715-05409	PIPE, SANITARY SEWER, 10 IN.	18.00	LFT
0063	715-05413	PIPE, SANITARY SEWER, 18 IN.	576.00	LFT
0064	715-05415	PIPE, SANITARY SEWER, 24 IN.	26.00	LFT
0065	715-05712	PIPE, SANITARY SEWER, 16 IN.	2820.00	LFT
0066	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	37.00	TON
0067	715-08627	PIPE, TYPE 2, CIRCULAR, 4 IN.	103.00	LFT
0068	715-09064	VIDEO INSPECTION FOR PIPE	4589.00	LFT

0069	715-09843	BYPASS PUMPING	1.00	LS
0070	715-92253	SEWER SANITARY LATERAL RECONNECT	50.00	EACH
0071	715-92253	SEWER SANITARY LATERAL RECONNECT	50.00	EACH
0072	720-10114	SANITARY DROP MANHOLE	23.00	EACH
0073	720-12797	CASTING, INLET, ADJUST TO GRADE	3.00	EACH
0074	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00	EACH
0075	720-44015	CASTING, 2, FURNISH AND ADJUST TO GRADE	4.00	EACH
0076	720-44296	INLET, CAP	1.00	EACH
0077	720-45005	INLET, A2	1.00	EACH
0078	720-45265	PIPE CATCH BASIN, 15 IN.	8.00	EACH
0079	720-98174	INLET, B15	18.00	EACH
0080	720-98555	INLET, C15	18.00	EACH
0081	732-11770	AGGREGATE FOR DRAINAGE FILL	49.00	CYS
0082	732-11810	MODULAR BLOCK WALL	1330.00	SFT
0083	732-11811	MODULAR BLOCK WALL ERECTION	1330.00	SFT
0084	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00	EACH
0085	801-06625	DETOUR ROUTE MARKER ASSEMBLY	24.00	EACH
0086	801-06640	CONSTRUCTION SIGN, A	18.00	EACH
0087	801-06645	CONSTRUCTION SIGN, B	19.00	EACH
0088	801-06775	MAINTAINING TRAFFIC	1.00	LS
0089	801-07118	BARRICADE, III-A	50.00	LFT
0090	801-07119	BARRICADE, III-B	338.00	LFT
0091	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	727.00	LFT
0092	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	53.00	EACH
0093	802-09837	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.080 IN. THICKNESS	28.00	SFT
0094	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	196.00	SFT
0095	802-09839	SIGN, DOUBLE-FACED, SHEET, WITH LEGEND, 0.100 IN. THICKNESS	24.00	SFT
0096	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	96.00	SFT
0097	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	30.00	SFT
0098	805-04973	CONDUIT	7000.00	LFT
0099	807-78590	HANDHOLE	61.00	EACH
0100	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	70.00	LFT
0101	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	6266.00	LFT
0102	808-10118	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 24 IN.	40.00	LFT
0103	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	110.00	LFT
0104	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	556.00	LFT

Call: 131

Contract: R -40278-B

Section No.: 1 ADA SIDEWALK RAMP CONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0009	202-02278	CURB, CONCRETE, REMOVE	1068.00 LFT
0010	202-02279	CURB AND GUTTER, REMOVE	49.00 LFT
0011	202-52710	SIDEWALK CONCRETE, REMOVE	953.00 SYS
0012	203-02000	EXCAVATION, COMMON	45.00 CYS
0013	205-06933	TEMPORARY INLET PROTECTION	36.00 EACH
0014	207-09935	SUBGRADE TREATMENT, TYPE IC	828.00 SYS
0015	304-12625	HMA PATCHING FULL DEPTH, TYPE C	257.00 TON
0016	406-05521	ASPHALT FOR TACK COAT	932.00 SYS
0017	604-06070	SIDEWALK, CONCRETE	357.00 SYS
0018	604-08086	CURB RAMP, CONCRETE	509.00 SYS
0019	604-12083	DETECTABLE WARNING SURFACES	94.00 SYS
0020	605-06125	CURB, CONCRETE, MODIFIED	1216.00 LFT
0021	605-06140	CURB AND GUTTER, CONCRETE	49.00 LFT
0022	621-06567	WATER	2.00 KGAL
0023	621-06570	TOPSOIL	45.00 CYS
0024	621-06575	SODDING, NURSERY	387.00 SYS
0025	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	4.00 EACH
0026	720-12797	CASTING, INLET, ADJUST TO GRADE	15.00 EACH
0027	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	8.00 EACH
0028	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	1.00 EACH
0029	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	5227.00 LFT
0030	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00 LS
0031	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	504.00 LFT

0032	801-06640	CONSTRUCTION SIGN, A	226.00	EACH
0033	801-06645	CONSTRUCTION SIGN, B	124.00	EACH
0034	801-06775	MAINTAINING TRAFFIC	1.00	LS
0035	801-07119	BARRICADE, III-B	16.00	LFT
0036	801-11990	TEMPORARY CURB RAMP	49.00	EACH
0037	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	138.00	SYS
0038	802-91122	SIGN GROUND MOUNTED RESET	2.00	EACH
0039	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	12.00	EACH
0040	805-05405	SIGNAL POLE, PEDESTAL, 4 FT	12.00	EACH
0041	805-06595	CONDUIT, PVC, 2 IN.	239.00	LFT
0042	805-11817	PEDESTRIAN PUSH BUTTON, APS	26.00	EACH
0043	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	3327.00	LFT
0044	808-06716	LINE, REMOVE	370.00	LFT
0045	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	500.00	LFT
0046	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	3384.00	LFT

Call: 141

Contract: R -40460-A

Section No.: 1 ROAD RECONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-01845	CONDUIT, REMOVE	60.00 LFT
0012	202-02240	PAVEMENT REMOVAL	274.00 SYS
0013	202-02278	CURB, CONCRETE, REMOVE	1080.00 LFT
0014	202-02637	PIPE ABANDON AND GROUT FILL	34.00 LFT
0015	202-03875	CONCRETE STEPS, REMOVE	11.00 EACH
0016	202-06312	REMOVE	2741.00 SFT
0017	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0018	202-52710	SIDEWALK CONCRETE, REMOVE	302.00 SYS
0019	202-90747	RETAINING WALL, REMOVE	75.00 LFT
0020	202-91385	INLET, REMOVE	5.00 EACH
0021	202-96133	PIPE, REMOVE	479.00 LFT
0022	202-97009	FIRE HYDRANT ASSEMBLY, REMOVE	3.00 EACH
0023	203-02000	EXCAVATION, COMMON	7518.00 CYS
0024	203-02010	EXCAVATION, ROCK	1356.00 CYS
0025	205-12108	STORMWATER MANAGEMENT BUDGET	28135.00 DOL
0026	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0027	205-12618	SWQCP PREPARATION	1.00 LS
0028	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	346.00 CYS
0029	207-08264	SUBGRADE TREATMENT, TYPE II	687.00 SYS
0030	207-08265	SUBGRADE TREATMENT, TYPE IIA	9169.00 SYS
0031	207-12151	SUBGRADE TREATMENT, TYPE IVA	1117.00 SYS

0032	211-02050	B BORROW	6.00	CYS
0033	211-09265	STRUCTURE BACKFILL, TYPE 2	9135.00	CYS
0034	211-09266	STRUCTURE BACKFILL, TYPE 3	159.00	CYS
0035	214-12238	GEOTEXTILE FOR PAVEMENT TYPE 2A	10214.00	SYS
0036	301-12232	COMPACTED AGGREGATE NO. 5	1624.00	CYS
0037	301-12234	COMPACTED AGGREGATE NO. 53	889.00	CYS
0038	302-07455	DENSE GRADED SUBBASE	92.00	CYS
0039	303-01180	COMPACTED AGGREGATE NO. 53	3024.00	TON
0040	303-07449	COMPACTED AGGREGATE NO. 73	37.00	TON
0041	304-07493	WIDENING WITH HMA, TYPE B	8.00	TON
0042	304-12623	HMA PATCHING FULL DEPTH, TYPE B	4.00	TON
0043	306-08034	MILLING, ASPHALT, 1 1/2 IN.	256.00	SYS
0044	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1102.00	TON
0045	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	919.00	TON
0046	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	1105.00	TON
0047	401-10258	JOINT ADHESIVE, SURFACE	10319.00	LFT
0048	401-10259	JOINT ADHESIVE, INTERMEDIATE	10259.00	LFT
0049	401-11785	LIQUID ASPHALT SEALANT	5375.80	LFT
0050	406-05520	ASPHALT FOR TACK COAT	3.50	TON
0051	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0052	601-02241	GUARDRAIL, REMOVE	564.00	LFT
0053	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	521.00	LFT
0054	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	2.00	EACH
0055	603-97461	TEMPORARY FENCE	1530.00	LFT
0056	604-06070	SIDEWALK, CONCRETE	1380.00	SYS
0057	604-07092	BED COURSE MATERIAL	373.00	TON
0058	604-08086	CURB RAMP, CONCRETE	25.00	SYS
0059	604-12083	DETECTABLE WARNING SURFACES	7.00	SYS
0060	604-44251	STEPS, CONCRETE	2.00	CYS
0061	605-06120	CURB, CONCRETE	417.00	LFT
0062	605-52807	CURB AND GUTTER, COMBINED	4008.00	LFT
0063	610-07487	HMA FOR APPROACHES, TYPE B	39.00	TON
0064	610-08446	PCCP FOR APPROACHES, 6 IN.	480.00	SYS
0065	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00	EACH
0066	611-06498	MAILBOX ASSEMBLY, DOUBLE	1.00	EACH
0067	615-06490	RIGHT-OF-WAY MARKER	17.00	EACH
0068	615-06505	MONUMENT, B	1.00	EACH

0069	616-05688	RIPRAP, CLASS 1	87.00	TON
0070	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	116.00	SYS
0071	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0072	621-06559	MULCHED SEEDING R	360.00	SYS
0073	621-06574	SODDING	5742.00	SYS
0074	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. TO 2 IN.	6.00	EACH
0075	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0076	628-12683	FIELD OFFICE, D	24.00	MOS
0077	629-12029	PLANT GROWTH LAYER	6102.00	SYS
0078	702-04325	TEMPORARY SHORING	1.00	LS
0079	702-51005	CONCRETE, A, SUBSTRUCTURE	22.60	CYS
0080	702-51015	CONCRETE, B, FOOTINGS	19.60	CYS
0081	702-90915	CONCRETE, CLASS, A	3.00	CYS
0082	703-06028	REINFORCING BARS	6309.00	LBS
0083	715-02744	GATE VALVE AND VALVE BOX 6 IN.	3.00	EACH
0084	715-05032	PIPE, TYPE 2, CIRCULAR, 15 IN.	255.00	LFT
0085	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	3507.00	LFT
0086	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	16.00	LFT
0087	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	322.00	LFT
0088	715-05153	PIPE, TYPE 2, CIRCULAR, 21 IN.	34.00	LFT
0089	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	71.00	LFT
0090	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	25.00	LFT
0091	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	142.00	LFT
0092	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	1608.00	LFT
0093	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	20.00	LFT
0094	715-05203	PIPE, TYPE 4, CIRCULAR, 4 IN.	130.00	LFT
0095	715-05408	PIPE, SANITARY SEWER, 8 IN.	1476.00	LFT
0096	715-05422	PIPE, SLOTTED DRAIN, 12 IN.	20.00	LFT
0097	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	3.00	TON
0098	715-11879	SEWER, SANITARY LATERAL, CONNECTIONS	565.00	LFT
0099	715-11896	WATER SERVICE CONNECTION	30.00	EACH
0100	715-26777	GRATED BOX END SECTION, I, 2:1 DIAMETER 42 IN.	1.00	EACH
0101	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00	EACH
0102	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0103	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	EACH
0104	715-90853	TAPPING SLEEVE WITH VALVE	30.00	EACH
0105	715-91361	PIPE PVC 6 IN	917.00	LFT

0106	715-94780	WATER MAIN, DUCTILE IRON, 6 IN.	1541.00	LFT
0107	715-95866	GATE VALVE 6 IN.	4.00	EACH
0108	715-98265	WATER MAIN, DUCTILE IRON, 4 IN.	664.00	LFT
0109	718-11685	UNDERDRAIN CLEANOUT PORT	8.00	EACH
0110	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	87.00	SYS
0111	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	2923.00	SYS
0112	718-52610	AGGREGATE FOR UNDERDRAINS	11.00	CYS
0113	720-01915	MANHOLE, E	1.00	EACH
0114	720-01917	CASTING, MODIFIED	2.00	EACH
0115	720-02442	PIPE PLUG EXISTING	7.00	EACH
0116	720-03194	MANHOLE	8.00	EACH
0117	720-03194	MANHOLE	1.00	EACH
0118	720-03194	MANHOLE	1.00	EACH
0119	720-10138	MANHOLE, L7	1.00	EACH
0120	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	5.00	EACH
0121	720-45410	MANHOLE, C4	5.00	EACH
0122	720-94612	MANHOLE, K4	7.00	EACH
0123	720-96999	FIRE HYDRANT ASSEMBLY	3.00	EACH
0124	720-98174	INLET, B15	28.00	EACH
0125	720-98555	INLET, C15	5.00	EACH
0126	720-98625	MANHOLE, C4 DROP	7.00	EACH
0127	720-98869	MANHOLE, L4 MODIFIED	1.00	EACH
0128	732-11770	AGGREGATE FOR DRAINAGE FILL	27.00	CYS
0129	732-11811	MODULAR BLOCK WALL ERECTION	716.00	SFT
0130	732-11812	MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	716.00	SFT
0131	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0132	801-06625	DETOUR ROUTE MARKER ASSEMBLY	27.00	EACH
0133	801-06640	CONSTRUCTION SIGN, A	14.00	EACH
0134	801-06645	CONSTRUCTION SIGN, B	9.00	EACH
0135	801-06775	MAINTAINING TRAFFIC	1.00	LS
0136	801-07118	BARRICADE, III-A	72.00	LFT
0137	801-07119	BARRICADE, III-B	48.00	LFT
0138	801-11990	TEMPORARY CURB RAMP	4.00	EACH
0139	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	89.50	LFT
0140	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	11.30	LFT
0141	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	9.00	EACH
0142	802-07060	SIGN, SHEET, RELOCATE	3.00	EACH

0143	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	47.50	SFT
0144	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	24.80	SFT
0145	807-02426	WIRE, THW, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	455.00	LFT
0146	807-03950	LUMINAIRE ORNAMENTAL	18.00	EACH
0147	807-03951	LIGHT POLE ORNAMENTAL	18.00	EACH
0148	807-04653	LIGHTING FOUNDATION	18.00	EACH
0149	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	455.00	LFT
0150	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1130.00	LFT
0151	807-86805	SERVICE POINT, I	1.00	EACH
0152	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	570.00	LFT
0153	807-86910	CONNECTOR KIT, UNFUSED	18.00	EACH
0154	807-86915	CONNECTOR KIT, FUSED	18.00	EACH
0155	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	51.00	EACH
0156	807-86930	INSULATION LINK, NON-WATERPROOFED	36.00	EACH
0157	807-86950	SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION IDENTIFICATION	18.00	EACH
0158	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2446.00	LFT
0159	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4572.00	LFT
0160	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	24.00	LFT
0161	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	141.00	LFT
0162	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	31.00	EACH

Call: 151

Contract: R -40536-A

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	105-12018	UTILITY PROTECTION	1.00 LS
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-96133	PIPE, REMOVE	162.00 LFT
0014	203-02000	EXCAVATION, COMMON	640.00 CYS
0015	203-02070	BORROW	125.00 CYS
0016	205-11626	PUMP AROUND	3.00 EACH
0017	205-12108	STORMWATER MANAGEMENT BUDGET	8004.00 DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0019	205-12618	SWQCP PREPARATION	1.00 LS
0020	206-51220	EXCAVATION, WET	45.00 CYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	30.00 SYS
0022	207-12498	SUBGRADE TREATMENT, TYPE ID	867.00 SYS
0023	211-09265	STRUCTURE BACKFILL, TYPE 2	136.00 CYS
0024	211-09268	STRUCTURE BACKFILL, TYPE 5	180.00 CYS
0025	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	210.00 SYS
0026	301-12232	COMPACTED AGGREGATE NO. 5	18.00 CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	412.00 TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1112.00 SYS
0029	306-08042	MILLING, SCARIFICATION	1100.00 SYS
0030	306-08043	MILLING, TRANSITION	350.00 SYS
0031	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	273.00 TON

0032	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	228.00	TON
0033	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	279.00	TON
0034	401-10258	JOINT ADHESIVE, SURFACE	2110.00	LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	1500.00	LFT
0036	401-11785	LIQUID ASPHALT SEALANT	1500.00	LFT
0037	406-05520	ASPHALT FOR TACK COAT	7.00	TON
0038	406-05521	ASPHALT FOR TACK COAT	2550.00	SYS
0039	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.00	TON
0040	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	369.00	LFT
0041	601-12287	GUARDRAIL, MGS, LONG SPAN, TYPE 1	2.00	EACH
0042	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0043	616-05688	RIPRAP, CLASS 1	416.00	TON
0044	616-06405	RIPRAP, REVETMENT	31.00	TON
0045	616-06451	RIPRAP, UNIFORM	17.00	TON
0046	616-07266	COIR ROLL	22.00	LFT
0047	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	380.00	SYS
0048	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	108.00	SYS
0049	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0050	621-02770	EROSION CONTROL BLANKET	8000.00	SYS
0051	621-06545	FERTILIZER	0.03	TON
0052	621-06557	SEED MIXTURE, T	300.00	LBS
0053	621-06559	MULCHED SEEDING R	9871.00	SYS
0054	621-06570	TOPSOIL	208.00	CYS
0055	621-06574	SODDING	750.00	SYS
0056	628-09403	FIELD OFFICE, C	8.00	MOS
0057	628-09409	MOBILE INTERNET SERVICE	16.00	MOS
0058	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0059	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0060	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0061	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0062	628-11977	COMPUTER SYSTEM	1.00	EACH
0063	628-12685	TELEPHONE SERVICE, A	16.00	MOS
0064	714-11177	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 8 FT X 4 FT	56.00	LFT
0065	714-12838	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 11 FT X 5 FT	64.00	LFT
0066	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	15.00	LFT
0067	715-05049	PIPE, TYPE 4, CIRCULAR, 8 IN.	20.00	LFT
0068	715-05051	PIPE, TYPE 4, CIRCULAR, 10 IN.	20.00	LFT

0069	715-05052	PIPE, TYPE 4, CIRCULAR, 12 IN.	20.00	LFT
0070	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	6.00	LFT
0071	801-04308	ROAD CLOSURE SIGN ASSEMBLY	14.00	EACH
0072	801-06625	DETOUR ROUTE MARKER ASSEMBLY	57.00	EACH
0073	801-06640	CONSTRUCTION SIGN, A	26.00	EACH
0074	801-06645	CONSTRUCTION SIGN, B	21.00	EACH
0075	801-06775	MAINTAINING TRAFFIC	1.00	LS
0076	801-07118	BARRICADE, III-A	108.00	LFT
0077	801-07119	BARRICADE, III-B	156.00	LFT
0078	802-04893	REFERENCE POST	2.00	EACH
0079	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	21.00	LFT
0080	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	8.00	SFT
0081	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1080.00	LFT
0082	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	140.00	LFT
0083	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	7.00	EACH
0084	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	7.00	EACH

Call: 155

Contract: R -40574-B

Section No.: 1 SMALL STRUCTURE REPLACEMENT

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0014	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0015	203-02000	EXCAVATION, COMMON	938.00	CYS
0016	205-11626	PUMP AROUND	3.00	EACH
0017	205-12108	STORMWATER MANAGEMENT BUDGET	19500.00	DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0019	205-12618	SWQCP PREPARATION	1.00	LS
0020	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	63.00	CYS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	80.00	SYS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	1935.00	SYS
0023	207-12498	SUBGRADE TREATMENT, TYPE ID	103.00	SYS
0024	211-09265	STRUCTURE BACKFILL, TYPE 2	431.00	CYS
0025	211-09268	STRUCTURE BACKFILL, TYPE 5	298.00	CYS
0026	214-12238	GEOTEXTILE FOR PAVEMENT TYPE 2A	787.00	SYS
0027	301-12232	COMPACTED AGGREGATE NO. 5	175.00	CYS
0028	303-01180	COMPACTED AGGREGATE NO. 53	703.00	TON
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	595.00	SYS
0030	306-08043	MILLING, TRANSITION	523.00	SYS
0031	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	100.00	TON

0032	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	152.00	TON
0033	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	85.00	TON
0034	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	216.00	TON
0035	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	620.00	TON
0036	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	212.00	TON
0037	401-10258	JOINT ADHESIVE, SURFACE	2285.00	LFT
0038	401-10259	JOINT ADHESIVE, INTERMEDIATE	1813.00	LFT
0039	401-11785	LIQUID ASPHALT SEALANT	2285.00	LFT
0040	402-10086	HMA FOR TEMPORARY PAVEMENT, TYPE C	117.00	TON
0041	406-05521	ASPHALT FOR TACK COAT	5599.00	SYS
0042	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	3.00	TON
0043	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	1040.00	SFT
0044	601-02241	GUARDRAIL, REMOVE	723.625	LFT
0045	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	296.875	LFT
0046	601-12287	GUARDRAIL, MGS, LONG SPAN, TYPE 1	1.00	EACH
0047	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	3.00	EACH
0048	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	1.00	EACH
0049	601-94689	GUARDRAIL, END TREATMENT, OS	7.00	EACH
0050	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	6.25	LFT
0051	610-07487	HMA FOR APPROACHES, TYPE B	18.00	TON
0052	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0053	615-06490	RIGHT-OF-WAY MARKER	12.00	EACH
0054	615-06505	MONUMENT, B	6.00	EACH
0055	616-06405	RIPRAP, REVETMENT	194.00	TON
0056	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	378.00	SYS
0057	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	584.00	SYS
0058	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0059	621-06559	MULCHED SEEDING R	1526.00	SYS
0060	621-06574	SODDING	907.00	SYS
0061	628-11729	CELLULAR TELEPHONE, TYPE A	3.00	EACH
0062	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0063	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0064	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	42.00	MOS
0065	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0066	628-11977	COMPUTER SYSTEM	3.00	EACH
0067	628-12683	FIELD OFFICE, D	14.00	MOS
0068	628-12685	TELEPHONE SERVICE, A	14.00	MOS

0069	702-04325	TEMPORARY SHORING	1.00	LS
0070	702-51863	FIELD DRILLED HOLE IN CONCRETE	170.00	EACH
0071	703-06028	REINFORCING BARS	5826.00	LBS
0072	703-06029	REINFORCING BARS, EPOXY COATED	3395.00	LBS
0073	704-51002	CONCRETE, C, SUPERSTRUCTURE	41.80	CYS
0074	714-11444	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 13 FT X 7 FT	52.00	LFT
0075	714-12516	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 3 FT X 2 FT	35.00	LFT
0076	714-12545	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 18 FT X 8 FT	47.00	LFT
0077	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	47.00	LFT
0078	719-05440	PIPE, DRAIN. TILE TERMINAL SECTION, 8 IN.	25.00	LFT
0079	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.00	EACH
0080	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00	EACH
0081	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2570.00	LFT
0082	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0083	801-06625	DETOUR ROUTE MARKER ASSEMBLY	69.00	EACH
0084	801-06640	CONSTRUCTION SIGN, A	117.00	EACH
0085	801-06645	CONSTRUCTION SIGN, B	18.00	EACH
0086	801-06710	FLASHING ARROW SIGN	20.00	DAY
0087	801-06775	MAINTAINING TRAFFIC	1.00	LS
0088	801-07118	BARRICADE, III-A	120.00	LFT
0089	801-07119	BARRICADE, III-B	108.00	LFT
0090	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	385.00	LFT
0091	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0092	801-12042	TRUCK MOUNTED ATTENUATOR	20.00	DAY
0093	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0094	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	27.00	LFT
0095	802-91122	SIGN GROUND MOUNTED RESET	3.00	EACH
0096	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	200.00	LFT
0097	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	201.00	LFT
0098	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1999.00	LFT
0099	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	637.00	LFT
0100	808-06716	LINE, REMOVE	860.00	LFT
0101	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	200.00	LFT
0102	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	13.00	EACH
0103	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	13.00	EACH

Call: 161

Contract: R -40603-A

Section No.: 1 INTERSECTION IMPROVEMENT WITH ADDED TURN LANES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-02240	PAVEMENT REMOVAL	62.00 SYS
0012	202-02273	CENTER CURB, CONCRETE, REMOVE	6.00 SYS
0013	202-02278	CURB, CONCRETE, REMOVE	95.00 LFT
0014	202-02279	CURB AND GUTTER, REMOVE	194.00 LFT
0015	202-06542	RELOCATE	1.00 EACH
0016	202-06542	RELOCATE	4.00 EACH
0017	202-06542	RELOCATE	1.00 EACH
0018	202-52710	SIDEWALK CONCRETE, REMOVE	138.00 SYS
0019	202-74035	SIGN, REMOVE	4.00 EACH
0020	202-86946	HANDHOLE, REMOVE	1.00 EACH
0021	202-93995	SIGNAL POLE FOUNDATION, REMOVE	1.00 EACH
0022	203-02000	EXCAVATION, COMMON	345.00 CYS
0023	205-12108	STORMWATER MANAGEMENT BUDGET	5000.00 DOL
0024	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0025	207-08264	SUBGRADE TREATMENT, TYPE II	50.00 SYS
0026	207-09935	SUBGRADE TREATMENT, TYPE IC	519.00 SYS
0027	211-09265	STRUCTURE BACKFILL, TYPE 2	4.00 CYS
0028	211-09266	STRUCTURE BACKFILL, TYPE 3	10.00 CYS
0029	214-11796	GEOGRID, TYPE IB	50.00 SYS
0030	302-07455	DENSE GRADED SUBBASE	9.00 CYS
0031	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	33.00 TON

0032	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	55.00	TON
0033	401-07409	QC/QA-HMA, 4, 64, BASE, 25.0 mm	226.00	TON
0034	401-10258	JOINT ADHESIVE, SURFACE	236.00	LFT
0035	401-10259	JOINT ADHESIVE, INTERMEDIATE	236.00	LFT
0036	401-11785	LIQUID ASPHALT SEALANT	236.00	LFT
0037	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0038	604-06070	SIDEWALK, CONCRETE	164.00	SYS
0039	604-08086	CURB RAMP, CONCRETE	26.00	SYS
0040	604-12083	DETECTABLE WARNING SURFACES	3.00	SYS
0041	605-06140	CURB AND GUTTER, CONCRETE	271.00	LFT
0042	610-09108	PCCP FOR APPROACHES, 9 IN.	50.00	SYS
0043	615-06490	RIGHT-OF-WAY MARKER	6.00	EACH
0044	615-06505	MONUMENT, B	2.00	EACH
0045	621-06575	SODDING, NURSERY	107.00	SYS
0046	628-09403	FIELD OFFICE, C	6.00	MOS
0047	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	138.00	LFT
0048	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	18.00	LFT
0049	720-12797	CASTING, INLET, ADJUST TO GRADE	2.00	EACH
0050	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00	EACH
0051	720-44296	INLET, CAP	1.00	EACH
0052	720-98174	INLET, B15	1.00	EACH
0053	732-11770	AGGREGATE FOR DRAINAGE FILL	21.00	CYS
0054	732-11810	MODULAR BLOCK WALL	542.00	SFT
0055	732-11811	MODULAR BLOCK WALL ERECTION	542.00	SFT
0056	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	3.00	EACH
0057	801-06625	DETOUR ROUTE MARKER ASSEMBLY	18.00	EACH
0058	801-06640	CONSTRUCTION SIGN, A	25.00	EACH
0059	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0060	801-06775	MAINTAINING TRAFFIC	1.00	LS
0061	801-07118	BARRICADE, III-A	48.00	LFT
0062	802-03126	SIGN OVERHEAD RELOCATE	5.00	EACH
0063	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	35.00	LFT
0064	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	17.00	SFT
0065	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0066	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	1.00	EACH
0067	805-01842	HANDHOLE, SIGNAL, TYPE 1	2.00	EACH
0068	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	2.00	EACH

0069	805-08493	RADIO, INTERCONNECTION SYSTEM TESTING	1.00	LS
0070	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	980.00	LFT
0071	805-11817	PEDESTRIAN PUSH BUTTON, APS	4.00	EACH
0072	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	4.00	EACH
0073	805-78415	SPAN, CATENARY, AND TETHER	2.00	EACH
0074	805-78420	DISCONNECT HANGER	2.00	EACH
0075	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	590.00	LFT
0076	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	90.00	LFT
0077	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	670.00	LFT
0078	805-78500	SIGNAL CABLE, CONTROL, COPPER, 11C/14 GAUGE	940.00	LFT
0079	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	2640.00	LFT
0080	805-78785	SIGNAL DETECTOR HOUSING	1.00	EACH
0081	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	270.00	LFT
0082	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	1.00	EACH
0083	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	2.00	EACH
0084	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	104.00	LFT
0085	808-06716	LINE, REMOVE	257.00	LFT
0086	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	49.00	LFT
0087	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	2.00	EACH
0088	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	7.00	EACH
0089	808-10094	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 12 IN.	186.00	LFT
0090	808-12032	GROOVING FOR PAVEMENT MARKINGS	104.00	LFT
0091	808-74815	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 12 IN.	70.00	LFT
0092	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	25.00	LFT
0093	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	1.00	EACH

Call: 165

Contract: R -40736-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0010	202-05545	REGULATED MATERIALS, DISPOSE, TYPE C	50.00 CYS
0011	202-05550	REGULATED MATERIALS, REMOVE, TYPE C	50.00 CYS
0012	202-05555	REGULATED MATERIALS, TRANSPORT, TYPE C	50.00 CYS
0013	203-02000	EXCAVATION, COMMON	2895.00 CYS
0014	205-12108	STORMWATER MANAGEMENT BUDGET	20625.00 DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0016	205-12618	SWQCP PREPARATION	1.00 LS
0017	207-08264	SUBGRADE TREATMENT, TYPE II	1170.00 SYS
0018	207-08266	SUBGRADE TREATMENT, TYPE III	5397.00 SYS
0019	211-02050	B BORROW	1100.00 CYS
0020	214-11796	GEOGRID, TYPE IB	645.00 SYS
0021	301-12234	COMPACTED AGGREGATE NO. 53	455.00 CYS
0022	302-07455	DENSE GRADED SUBBASE	195.00 CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	438.00 TON
0024	502-06457	PCCP, 9 IN.	49.00 SYS
0025	502-06627	PCCP, 6 IN.	164.00 SYS
0026	502-11543	PCCP, 4 IN.	3855.00 SYS
0027	603-91714	FENCE, RAIL WOOD	33.00 LFT
0028	604-01268	HAND RAIL ALUMINUM	22.00 LFT
0029	604-06070	SIDEWALK, CONCRETE	144.00 SYS
0030	604-08086	CURB RAMP, CONCRETE	594.00 SYS
0031	604-12083	DETECTABLE WARNING SURFACES	75.00 SYS

0032	605-06120	CURB, CONCRETE	679.00	LFT
0033	605-06125	CURB, CONCRETE, MODIFIED	555.00	LFT
0034	605-06140	CURB AND GUTTER, CONCRETE	206.00	LFT
0035	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	248.00	LFT
0036	610-08446	PCCP FOR APPROACHES, 6 IN.	525.00	SYS
0037	610-09108	PCCP FOR APPROACHES, 9 IN.	645.00	SYS
0038	618-03812	BENCH	5.00	EACH
0039	618-04181	BICYCLE RACK	3.00	EACH
0040	618-97672	TRASH RECEPTACLE	2.00	EACH
0041	621-06575	SODDING, NURSERY	2136.00	SYS
0042	622-05641	PLANT, DECIDUOUS SHRUB, 36 IN. TO 48 IN.	80.00	EACH
0043	622-05651	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 IN. TO 3.5 IN.	40.00	EACH
0044	622-05653	PLANT, GROUND COVER	2580.00	EACH
0045	628-09403	FIELD OFFICE, C	6.00	MOS
0046	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0047	715-94530	ADJUST WATER VALVE TO GRADE	6.00	EACH
0048	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	6.00	EACH
0049	720-90105	INLET, REPAIR	1.00	EACH
0050	720-90129	MANHOLE, J2	1.00	EACH
0051	720-97008	FIRE HYDRANT ASSEMBLY RELOCATE	2.00	EACH
0052	720-98174	INLET, B15	2.00	EACH
0053	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1550.00	LFT
0054	801-06640	CONSTRUCTION SIGN, A	36.00	EACH
0055	801-06645	CONSTRUCTION SIGN, B	27.00	EACH
0056	801-06710	FLASHING ARROW SIGN	20.00	DAY
0057	801-06735	TUBULAR MARKER, PERMANENT	17.00	EACH
0058	801-06775	MAINTAINING TRAFFIC	1.00	LS
0059	801-07118	BARRICADE, III-A	48.00	LFT
0060	802-04250	SIGN, TRAIL INFORMATION	17.00	EACH
0061	802-07060	SIGN, SHEET, RELOCATE	14.00	EACH
0062	805-01842	HANDHOLE, SIGNAL, TYPE 1	1.00	EACH
0063	805-01843	HANDHOLE, SIGNAL, ADJUST TO GRADE	3.00	EACH
0064	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	4.00	EACH
0065	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	4.00	EACH
0066	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	330.00	LFT
0067	805-11817	PEDESTRIAN PUSH BUTTON, APS	4.00	EACH
0068	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	1190.00	LFT

0069	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	4.00	EACH
0070	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	140.00	LFT
0071	808-06716	LINE, REMOVE	149.00	LFT
0072	808-09968	PAVEMENT MARKING	7217.00	SFT
0073	808-74815	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 12 IN.	1239.00	LFT
0074	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	178.00	LFT

Call: 171

Contract: R -40877-A

Section No.: 1 ASPHALT RESURFACE

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	1303.00	SYS
0013	202-52710	SIDEWALK CONCRETE, REMOVE	37.00	SYS
0014	203-02000	EXCAVATION, COMMON	6274.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	9800.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	207-08264	SUBGRADE TREATMENT, TYPE II	1998.00	SYS
0019	207-12635	SUBGRADE TREATMENT, TYPE IBC	9084.00	SYS
0020	211-09265	STRUCTURE BACKFILL, TYPE 2	1978.00	CYS
0021	211-09265	STRUCTURE BACKFILL, TYPE 2	1186.00	CYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	2443.00	CYS
0023	214-12238	GEOTEXTILE FOR PAVEMENT TYPE 2A	1695.00	SYS
0024	301-12232	COMPACTED AGGREGATE NO. 5	1130.00	CYS
0025	301-12234	COMPACTED AGGREGATE NO. 53	1215.00	CYS
0026	302-06464	SUBBASE FOR PCCP	191.00	CYS
0027	302-07455	DENSE GRADED SUBBASE	270.00	CYS
0028	304-12623	HMA PATCHING FULL DEPTH, TYPE B	47.00	TON
0029	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	499.00	TON
0030	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	831.00	TON
0031	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1329.00	TON

0032	401-10258	JOINT ADHESIVE, SURFACE	2225.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	2225.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	2225.00	LFT
0035	406-05520	ASPHALT FOR TACK COAT	7.00	TON
0036	502-06627	PCCP, 6 IN.	979.00	SYS
0037	603-93373	FENCE, PEDESTRIAN	66.00	LFT
0038	604-06070	SIDEWALK, CONCRETE	1926.00	SYS
0039	604-08086	CURB RAMP, CONCRETE	239.00	SYS
0040	604-12083	DETECTABLE WARNING SURFACES	17.00	SYS
0041	604-44251	STEPS, CONCRETE	2.70	CYS
0042	605-06105	CURB, INTEGRAL CONCRETE, MODIFIED	1531.00	LFT
0043	605-06120	CURB, CONCRETE	159.00	LFT
0044	605-06140	CURB AND GUTTER, CONCRETE	1703.00	LFT
0045	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	2697.00	LFT
0046	610-07487	HMA FOR APPROACHES, TYPE B	38.00	TON
0047	610-08446	PCCP FOR APPROACHES, 6 IN.	1618.00	SYS
0048	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0049	621-06545	FERTILIZER	1.00	TON
0050	621-06554	SEED MIXTURE, U	170.00	LBS
0051	621-06565	MULCHING MATERIAL	2.00	TON
0052	621-06567	WATER	8.00	KGAL
0053	621-06570	TOPSOIL	545.00	CYS
0054	621-06575	SODDING, NURSERY	1977.00	SYS
0055	622-05651	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2.5 IN. TO 3.5 IN.	53.00	EACH
0056	628-09401	FIELD OFFICE, A	20.00	MOS
0057	628-09409	MOBILE INTERNET SERVICE	20.00	MOS
0058	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0059	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0060	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0061	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0062	628-11977	COMPUTER SYSTEM	1.00	EACH
0063	628-12685	TELEPHONE SERVICE, A	20.00	MOS
0064	715-02744	GATE VALVE AND VALVE BOX 6 IN.	2.00	EACH
0065	715-02745	GATE VALVE WITH VALVE BOX 8 IN.	9.00	EACH
0066	715-03718	AIR VACUUM RELEASE VALVE STRUCTURE	1.00	EACH
0067	715-04965	WATER SERVICE LINE	1080.00	LFT
0068	715-04965	WATER SERVICE LINE	180.00	LFT

0069	715-04987	CONNECTION	1.00 EACH
0070	715-04987	CONNECTION	6.00 EACH
0071	715-04987	CONNECTION	3.00 EACH
0072	715-04994	METER	18.00 EACH
0073	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	285.00 LFT
0074	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	6213.00 LFT
0075	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	961.00 LFT
0076	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	16.00 LFT
0077	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	721.00 LFT
0078	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	506.00 LFT
0079	715-05408	PIPE, SANITARY SEWER, 8 IN.	140.00 LFT
0080	715-05409	PIPE, SANITARY SEWER, 10 IN.	628.00 LFT
0081	715-09475	STORMWATER QUALITY STRUCTURE	1.00 EACH
0082	715-11571	WATER MAIN, DUCTILE IRON, 8 IN.	2018.00 LFT
0083	715-11879	SEWER, SANITARY LATERAL, CONNECTIONS	155.00 LFT
0084	715-11896	WATER SERVICE CONNECTION	36.00 EACH
0085	715-12406	VALVE WITH BOX, TAPPING SLEEVE	1.00 EACH
0086	715-91742	WATER METER RELOCATE	18.00 EACH
0087	715-92253	SEWER SANITARY LATERAL RECONNECT	3.00 EACH
0088	715-94780	WATER MAIN, DUCTILE IRON, 6 IN.	70.00 LFT
0089	715-98961	FORCE MAIN	118.00 LFT
0090	715-98961	FORCE MAIN	130.00 LFT
0091	718-04986	CLEANOUT	39.00 EACH
0092	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	3111.00 SYS
0093	718-52610	AGGREGATE FOR UNDERDRAINS	252.00 CYS
0094	720-02367	MANHOLE, J10	5.00 EACH
0095	720-03194	MANHOLE	5.00 EACH
0096	720-03280	MANHOLE, J MODIFIED	4.00 EACH
0097	720-04499	INLET RECONSTRUCT	2.00 EACH
0098	720-45005	INLET, A2	1.00 EACH
0099	720-45045	INLET, J10	10.00 EACH
0100	720-45055	INLET, M10	5.00 EACH
0101	720-45075	INLET, R13	14.00 EACH
0102	720-45410	MANHOLE, C4	1.00 EACH
0103	720-94157	MANHOLE, C	4.00 EACH
0104	720-94208	MANHOLE, C10	1.00 EACH
0105	720-95422	MANHOLE, J4	2.00 EACH

0106	720-96999	FIRE HYDRANT ASSEMBLY	3.00 EACH
0107	732-11770	AGGREGATE FOR DRAINAGE FILL	67.00 CYS
0108	732-11811	MODULAR BLOCK WALL ERECTION	360.00 SFT
0109	732-11812	MODULAR BLOCK WALL WITH GROUND REINFORCEMENT	360.00 SFT
0110	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00 EACH
0111	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	1996.00 LFT
0112	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1913.00 LFT
0113	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	27.00 LFT
0114	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	11.00 LFT
0115	801-06625	DETOUR ROUTE MARKER ASSEMBLY	68.00 EACH
0116	801-06640	CONSTRUCTION SIGN, A	23.00 EACH
0117	801-06645	CONSTRUCTION SIGN, B	2.00 EACH
0118	801-06775	MAINTAINING TRAFFIC	1.00 LS
0119	801-07118	BARRICADE, III-A	96.00 LFT
0120	801-07119	BARRICADE, III-B	144.00 LFT
0121	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	108.00 LFT
0122	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	87.00 SFT
0123	802-91122	SIGN GROUND MOUNTED RESET	4.00 EACH
0124	805-06595	CONDUIT, PVC, 2 IN.	680.00 LFT
0125	807-02191	HANDHOLE, LIGHTING	9.00 EACH
0126	807-03950	LUMINAIRE ORNAMENTAL	11.00 EACH
0127	807-03951	LIGHT POLE ORNAMENTAL	11.00 EACH
0128	807-04653	LIGHTING FOUNDATION	11.00 EACH
0129	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1525.00 LFT
0130	807-86805	SERVICE POINT, I	1.00 EACH
0131	807-86910	CONNECTOR KIT, UNFUSED	11.00 EACH
0132	807-86915	CONNECTOR KIT, FUSED	11.00 EACH
0133	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	12.00 EACH
0134	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	29.00 EACH
0135	807-86930	INSULATION LINK, NON-WATERPROOFED	14.00 EACH
0136	807-86935	INSULATION LINK, WATERPROOFED	48.00 EACH
0137	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	680.00 LFT
0138	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	120.00 LFT
0139	808-12032	GROOVING FOR PAVEMENT MARKINGS	4206.00 LFT
0140	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4206.00 LFT
0141	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	125.00 LFT
0142	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	568.00 LFT

Call: 181

Contract: R -41315-C

Section No.: 1 ROAD RECONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	201-02245	TREE 6 IN., REMOVE	2.00 EACH
0010	201-02250	TREE 10 IN., REMOVE	2.00 EACH
0011	201-02255	TREE 18 IN., REMOVE	3.00 EACH
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-02240	PAVEMENT REMOVAL	41.00 SYS
0014	202-02278	CURB, CONCRETE, REMOVE	794.00 LFT
0015	202-02279	CURB AND GUTTER, REMOVE	9.00 LFT
0016	202-03875	CONCRETE STEPS, REMOVE	2.00 EACH
0017	202-10146	REMOVE	3824.00 SYS
0018	202-52710	SIDEWALK CONCRETE, REMOVE	1793.00 SYS
0019	202-97009	FIRE HYDRANT ASSEMBLY, REMOVE	5.00 EACH
0020	203-02000	EXCAVATION, COMMON	1844.00 CYS
0021	205-12108	STORMWATER MANAGEMENT BUDGET	7040.00 DOL
0022	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0023	205-12618	SWQCP PREPARATION	1.00 LS
0024	207-08264	SUBGRADE TREATMENT, TYPE II	304.00 SYS
0025	207-08266	SUBGRADE TREATMENT, TYPE III	20.00 SYS
0026	207-12635	SUBGRADE TREATMENT, TYPE IBC	6448.00 SYS
0027	211-09264	STRUCTURE BACKFILL, TYPE 1	1040.00 CYS
0028	211-09264	STRUCTURE BACKFILL, TYPE 1	394.00 CYS
0029	214-12236	GEOTEXTILE FOR PAVEMENT, TYPE 1A	5943.00 SYS
0030	301-12234	COMPACTED AGGREGATE NO. 53	35.00 CYS
0031	302-07455	DENSE GRADED SUBBASE	587.00 CYS

0032	303-02125	AGGREGATE, 23	165.00	CYS
0033	502-11564	PCCP, 7 IN.	5943.00	SYS
0034	503-05240	D-1 CONTRACTION JOINT	3128.00	LFT
0035	603-02736	FENCE, WOOD, RESET	620.00	LFT
0036	603-06065	FENCE, CHAIN LINK, RESET	258.00	LFT
0037	603-97461	TEMPORARY FENCE	440.00	LFT
0038	604-03643	BRICK PAVERS	5943.00	SYS
0039	604-06070	SIDEWALK, CONCRETE	1816.00	SYS
0040	604-08086	CURB RAMP, CONCRETE	242.00	SYS
0041	604-12083	DETECTABLE WARNING SURFACES	42.00	SYS
0042	604-44251	STEPS, CONCRETE	1.00	CYS
0043	605-02278	CURB, REMOVE	4408.00	LFT
0044	605-06090	CURB, INTEGRAL CONCRETE	713.00	LFT
0045	605-06105	CURB, INTEGRAL CONCRETE, MODIFIED	3916.00	LFT
0046	605-06140	CURB AND GUTTER, CONCRETE	9.00	LFT
0047	610-08446	PCCP FOR APPROACHES, 6 IN.	270.00	SYS
0048	610-09108	PCCP FOR APPROACHES, 9 IN.	41.00	SYS
0049	621-06567	WATER	8.00	KGAL
0050	621-06574	SODDING	2056.00	SYS
0051	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	16.00	EACH
0052	628-09403	FIELD OFFICE, C	18.00	MOS
0053	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0054	628-11977	COMPUTER SYSTEM	1.00	EACH
0055	702-03607	CORED HOLE IN CONCRETE	1.00	EACH
0056	715-02532	VALVE, WITH BOX, RESTRAINED GATE, DUCTILE IRON, 8 IN.	10.00	EACH
0057	715-02874	CURB STOP AND BOX	9.00	EACH
0058	715-03053	METER PIT	1.00	EACH
0059	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	3693.00	LFT
0060	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1294.00	LFT
0061	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	1090.00	LFT
0062	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	414.00	LFT
0063	715-06651	WATER LINE, 2 IN	110.00	LFT
0064	715-07794	WATER MAIN CONNECTIONS	2.00	EACH
0065	715-07794	WATER MAIN CONNECTIONS	2.00	EACH
0066	715-07794	WATER MAIN CONNECTIONS	1.00	EACH
0067	715-07794	WATER MAIN CONNECTIONS	1.00	EACH
0068	715-07794	WATER MAIN CONNECTIONS	4.00	EACH

0069	715-07794	WATER MAIN CONNECTIONS	1.00 EACH
0070	715-09475	STORMWATER QUALITY STRUCTURE	1.00 EACH
0071	715-11896	WATER SERVICE CONNECTION	3.00 EACH
0072	715-90578	VALVE, WITH BOX, RESTRAINED GATE, DUCTILE IRON, 10 IN.	2.00 EACH
0073	715-90853	TAPPING SLEEVE WITH VALVE	2.00 EACH
0074	715-91739	WATER SERVICE LINE, 0.75 IN.	685.00 LFT
0075	715-92525	WATER MAIN, 10 IN.	145.00 LFT
0076	715-93403	WATER SERVICE CONNECTION, 0.75 IN.	35.00 EACH
0077	715-93913	WATER MAIN, 8 IN.	974.00 LFT
0078	715-96629	WATER SERVICE LINE, 1 IN.	127.00 LFT
0079	716-09129	PIPE INSTALLATION, TRENCHLESS, 8 IN.	1244.00 LFT
0080	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	816.00 SYS
0081	718-52610	AGGREGATE FOR UNDERDRAINS	408.00 CYS
0082	720-12047	UNDERGROUND STORMWATER DETENTION SYSTEM	1.00 LS
0083	720-45410	MANHOLE, C4	10.00 EACH
0084	720-93501	MANHOLE, L4	1.00 EACH
0085	720-94208	MANHOLE, C10	1.00 EACH
0086	720-96999	FIRE HYDRANT ASSEMBLY	6.00 EACH
0087	720-98174	INLET, B15	25.00 EACH
0088	720-98555	INLET, C15	13.00 EACH
0089	801-04308	ROAD CLOSURE SIGN ASSEMBLY	47.00 EACH
0090	801-06625	DETOUR ROUTE MARKER ASSEMBLY	38.00 EACH
0091	801-06640	CONSTRUCTION SIGN, A	20.00 EACH
0092	801-06645	CONSTRUCTION SIGN, B	17.00 EACH
0093	801-06775	MAINTAINING TRAFFIC	1.00 LS
0094	801-07118	BARRICADE, III-A	480.00 LFT
0095	801-07119	BARRICADE, III-B	432.00 LFT
0096	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	126.00 LFT
0097	802-07060	SIGN, SHEET, RELOCATE	18.00 EACH
0098	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	9.00 SFT
0099	807-02191	HANDHOLE, LIGHTING	12.00 EACH
0100	807-02194	SERVICE POINT, II, MODIFIED	1.00 EACH
0101	807-03950	LUMINAIRE ORNAMENTAL	10.00 EACH
0102	807-03951	LIGHT POLE ORNAMENTAL	10.00 EACH
0103	807-04653	LIGHTING FOUNDATION	42.00 EACH
0104	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	723.00 LFT
0105	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	3748.00 LFT

0106	807-12202	LUMINAIRE, LOW LUMEN ROADWAY	42.00 EACH
0107	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE WITH GROUNDING	10.00 EACH
0108	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	2184.00 LFT
0109	807-86910	CONNECTOR KIT, UNFUSED	52.00 EACH
0110	807-86915	CONNECTOR KIT, FUSED	52.00 EACH
0111	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	141.00 EACH
0112	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	12.00 EACH
0113	807-86930	INSULATION LINK, NON-WATERPROOFED	107.00 EACH
0114	807-86935	INSULATION LINK, WATERPROOFED	48.00 EACH
0115	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	751.00 LFT
0116	808-75100	TRANSVERSE MARKING, PAINT, CROSSWALK LINE, WHITE, 6 IN.	112.00 LFT

Call: 185

Contract: R -41322-B

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	20.00	EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	20.00	EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0008	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0009	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0010	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0011	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0012	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0014	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0015	202-02240	PAVEMENT REMOVAL	190.00	SYS
0016	202-02637	PIPE ABANDON AND GROUT FILL	15.00	LFT
0017	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0018	202-96430	FENCE AND POSTS, REMOVE	1.00	LS
0019	203-02000	EXCAVATION, COMMON	4748.00	CYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	13527.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	205-12618	SWQCP PREPARATION	1.00	LS
0023	207-08264	SUBGRADE TREATMENT, TYPE II	478.00	SYS
0024	207-12635	SUBGRADE TREATMENT, TYPE IBC	5968.00	SYS
0025	211-02050	B BORROW	896.00	CYS
0026	211-09265	STRUCTURE BACKFILL, TYPE 2	239.00	CYS
0027	211-09268	STRUCTURE BACKFILL, TYPE 5	3.00	CYS
0028	214-12238	GEOTEXTILE FOR PAVEMENT TYPE 2A	341.00	SYS
0029	301-12234	COMPACTED AGGREGATE NO. 53	1077.00	CYS
0030	302-07455	DENSE GRADED SUBBASE	42.00	CYS
0031	303-01180	COMPACTED AGGREGATE NO. 53	86.00	TON

0032	306-08034	MILLING, ASPHALT, 1 1/2 IN.	351.00	SYS
0033	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	381.00	TON
0034	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	775.00	TON
0035	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	930.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	2644.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	2644.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	2644.00	LFT
0039	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0040	502-11564	PCCP, 7 IN.	555.00	SYS
0041	503-05240	D-1 CONTRACTION JOINT	288.00	LFT
0042	604-06070	SIDEWALK, CONCRETE	375.00	SYS
0043	604-08086	CURB RAMP, CONCRETE	190.00	SYS
0044	604-12083	DETECTABLE WARNING SURFACES	22.00	SYS
0045	605-06140	CURB AND GUTTER, CONCRETE	1228.00	LFT
0046	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	190.00	LFT
0047	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	861.00	LFT
0048	605-06160	CURB AND GUTTER, B, CONCRETE, MODIFIED	283.00	LFT
0049	610-07487	HMA FOR APPROACHES, TYPE B	51.00	TON
0050	610-08446	PCCP FOR APPROACHES, 6 IN.	249.00	SYS
0051	611-06497	MAILBOX ASSEMBLY, SINGLE	5.00	EACH
0052	615-06505	MONUMENT, B	3.00	EACH
0053	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0054	616-06405	RIPRAP, REVETMENT	33.00	TON
0055	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	61.00	SYS
0056	621-06545	FERTILIZER	1.00	TON
0057	621-06567	WATER	5.00	kGAL
0058	621-06575	SODDING, NURSERY	3265.00	SYS
0059	622-07764	IRRIGATION SYSTEM	1.00	LS
0060	628-09401	FIELD OFFICE, A	12.00	MOS
0061	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0062	628-11977	COMPUTER SYSTEM	1.00	EACH
0063	715-02744	GATE VALVE AND VALVE BOX 6 IN.	1.00	EACH
0064	715-03053	METER PIT	1.00	EACH
0065	715-03053	METER PIT	1.00	EACH
0066	715-04964	WATER MAIN	80.00	LFT
0067	715-04964	WATER MAIN	66.00	LFT
0068	715-04965	WATER SERVICE LINE	30.00	LFT

0069	715-04965	WATER SERVICE LINE	55.00	LFT
0070	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	269.00	LFT
0071	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	76.00	LFT
0072	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	57.00	LFT
0073	715-05125	PIPE, TYPE 1, CIRCULAR, 30 IN.	99.00	LFT
0074	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	418.00	LFT
0075	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	94.00	LFT
0076	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	122.00	LFT
0077	715-07794	WATER MAIN CONNECTIONS	1.00	EACH
0078	715-12406	VALVE WITH BOX, TAPPING SLEEVE	3.00	EACH
0079	715-12674	GATE VALVE AND VALVE BOX 12 IN.	7.00	EACH
0080	715-46000	PIPE END SECTION, DIAMETER 12 IN.	5.00	EACH
0081	715-46005	PIPE END SECTION, DIAMETER 15 IN.	6.00	EACH
0082	715-46030	PIPE END SECTION, DIAMETER 30 IN.	2.00	EACH
0083	716-07630	PIPE INSTALLATION, TRENCHLESS, 12 IN.	1125.00	LFT
0084	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	269.00	LFT
0085	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	185.00	SYS
0086	718-52610	AGGREGATE FOR UNDERDRAINS	22.00	CYS
0087	720-96999	FIRE HYDRANT ASSEMBLY	3.00	EACH
0088	720-98174	INLET, B15	2.00	EACH
0089	720-98555	INLET, C15	4.00	EACH
0090	801-03290	CONSTRUCTION SIGN, C	3.00	EACH
0091	801-04308	ROAD CLOSURE SIGN ASSEMBLY	10.00	EACH
0092	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00	EACH
0093	801-06640	CONSTRUCTION SIGN, A	32.00	EACH
0094	801-06645	CONSTRUCTION SIGN, B	3.00	EACH
0095	801-06775	MAINTAINING TRAFFIC	1.00	LS
0096	801-07118	BARRICADE, III-A	96.00	LFT
0097	801-07119	BARRICADE, III-B	120.00	LFT
0098	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH
0099	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	172.00	LFT
0100	802-05705	SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	93.00	LFT
0101	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	122.00	SFT
0102	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	63.00	SFT
0103	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	29.00	SFT
0104	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0105	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1200.00	LFT

0106	805-78930	CONTROLLER CABINET FOUNDATION, M	1.00 EACH
0107	805-90267	CONDUIT, STEEL, GALVANIZED, 3 IN.	450.00 LFT
0108	807-02191	HANDHOLE, LIGHTING	6.00 EACH
0109	807-02394	CONTROLLER, LIGHTING	1.00 EACH
0110	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE WITH GROUNDING	11.00 EACH
0111	807-83492	LIGHT POLE, 30 FT E.M.H., 10 FT MAST ARM, ANCHOR BASE	8.00 EACH
0112	807-84492	LIGHT POLE, 30 FT E.M.H., 10 FT MAST ARM, TRANSFORMER BASE	3.00 EACH
0113	807-86605	LUMINAIRE, ROADWAY, HIGH PRESSURE SODIUM, 150 WATT	11.00 EACH
0114	807-86810	SERVICE POINT, II	1.00 EACH
0115	807-86843	WIRE, NO. 4 COPPER, 1/C	4000.00 LFT
0116	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	192.00 LFT
0117	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1374.00 LFT
0118	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	90.00 LFT
0119	808-11691	LINE, THERMOPLASTIC, DOTTED, WHITE, 12 IN.	120.00 LFT
0120	808-12148	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 36 IN.	156.00 LFT
0121	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	919.00 LFT

Call: 191

Contract: R -41884-C

Section No.: 1 GUARDRAIL ATTENUATORS, NEW OR MODERNIZE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0007	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0008	202-93741	GUARDRAIL, END TREATMENT, REMOVE	147.00 EACH
0009	202-94954	BARRIER WALL, CONCRETE, REMOVE	25.00 LFT
0010	601-02241	GUARDRAIL, REMOVE	6025.00 LFT
0011	601-03467	ALUMINUM TO STEEL SPLICE CONNECTOR, TYPE A S	18.00 EACH
0012	601-06238	IMPACT ATTENUATOR, R1-W1, TL-3	1.00 EACH
0013	601-07009	IMPACT ATTENUATOR, LS-W1, TL-1	2.00 EACH
0014	601-09238	HAND DIG GUARDRAIL POST HOLES	10.00 EACH
0015	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	425.00 LFT
0016	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN. SPACING	150.00 LFT
0017	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	144.00 EACH
0018	601-94689	GUARDRAIL, END TREATMENT, OS	119.00 EACH
0019	601-94690	GUARDRAIL, END TREATMENT, MS	26.00 EACH
0020	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00 EACH
0021	611-06498	MAILBOX ASSEMBLY, DOUBLE	1.00 EACH
0022	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0023	621-06545	FERTILIZER	1.00 TON
0024	621-06553	SEED MIXTURE, R	580.00 LBS
0025	621-06565	MULCHING MATERIAL	6.00 TON
0026	621-06567	WATER	1.00 KGAL
0027	621-06575	SODDING, NURSERY	110.00 SYS
0028	801-06640	CONSTRUCTION SIGN, A	14.00 EACH
0029	801-06775	MAINTAINING TRAFFIC	1.00 LS
0030	801-12042	TRUCK MOUNTED ATTENUATOR	90.00 DAY
0031	802-91122	SIGN GROUND MOUNTED RESET	6.00 EACH

Call: 201

Contract: R -41895-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-02245	TREE 6 IN., REMOVE	2.00 EACH
0012	201-02250	TREE 10 IN., REMOVE	3.00 EACH
0013	201-02260	TREE 30 IN., REMOVE	3.00 EACH
0014	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0015	202-02278	CURB, CONCRETE, REMOVE	2476.00 LFT
0016	202-03875	CONCRETE STEPS, REMOVE	1.00 EACH
0017	202-05545	REGULATED MATERIALS, DISPOSE, TYPE C	38.00 CYS
0018	202-05550	REGULATED MATERIALS, REMOVE, TYPE C	38.00 CYS
0019	202-05555	REGULATED MATERIALS, TRANSPORT, TYPE C	38.00 CYS
0020	202-05571	TESTING FOR WASTES	3.00 EACH
0021	202-52710	SIDEWALK CONCRETE, REMOVE	1730.00 SYS
0022	202-90747	RETAINING WALL, REMOVE	20.00 LFT
0023	202-91385	INLET, REMOVE	6.00 EACH
0024	202-96133	PIPE, REMOVE	125.00 LFT
0025	203-02000	EXCAVATION, COMMON	630.00 CYS
0026	203-02070	BORROW	23.00 CYS
0027	205-12108	STORMWATER MANAGEMENT BUDGET	20291.00 DOL
0028	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0029	205-12618	SWQCP PREPARATION	1.00 LS
0030	207-08264	SUBGRADE TREATMENT, TYPE II	2997.00 SYS
0031	207-08268	SUBGRADE TREATMENT, TYPE IV	1493.00 SYS

0032	207-09895	SUBGRADE TREATMENT, TYPE V	3524.00	SYS
0033	211-09265	STRUCTURE BACKFILL, TYPE 2	786.00	CYS
0034	211-09268	STRUCTURE BACKFILL, TYPE 5	76.00	CYS
0035	214-11796	GEOGRID, TYPE IB	2638.00	SYS
0036	301-12234	COMPACTED AGGREGATE NO. 53	2700.00	CYS
0037	302-07455	DENSE GRADED SUBBASE	334.00	CYS
0038	303-01180	COMPACTED AGGREGATE NO. 53	34.00	TON
0039	304-12623	HMA PATCHING FULL DEPTH, TYPE B	279.00	TON
0040	305-11779	PCC BASE PATCHING, 7 IN.	137.00	SYS
0041	306-08034	MILLING, ASPHALT, 1 1/2 IN.	7630.00	SYS
0042	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	715.00	TON
0043	401-10258	JOINT ADHESIVE, SURFACE	6298.00	LFT
0044	401-10259	JOINT ADHESIVE, INTERMEDIATE	6298.00	LFT
0045	401-11785	LIQUID ASPHALT SEALANT	6298.00	LFT
0046	402-07451	HMA WEDGE AND LEVEL, TYPE B	186.00	TON
0047	406-05520	ASPHALT FOR TACK COAT	6.00	TON
0048	502-11543	PCCP, 4 IN.	2510.00	SYS
0049	604-06070	SIDEWALK, CONCRETE	238.00	SYS
0050	604-08086	CURB RAMP, CONCRETE	319.00	SYS
0051	604-12083	DETECTABLE WARNING SURFACES	52.00	SYS
0052	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	2.00	SYS
0053	605-02493	CURB, ISLAND CONCRETE	11.00	SYS
0054	605-06090	CURB, INTEGRAL CONCRETE	104.00	LFT
0055	605-06120	CURB, CONCRETE	1180.00	LFT
0056	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	2206.00	LFT
0057	607-06175	GUTTER, CONCRETE, A	3.00	LFT
0058	610-07487	HMA FOR APPROACHES, TYPE B	715.00	TON
0059	610-08446	PCCP FOR APPROACHES, 6 IN.	322.00	SYS
0060	610-09108	PCCP FOR APPROACHES, 9 IN.	1668.00	SYS
0061	611-06497	MAILBOX ASSEMBLY, SINGLE	4.00	EACH
0062	615-06527	MONUMENT, SECTION CORNER	1.00	EACH
0063	615-11537	PARKING BARRIER, CONCRETE	8.00	EACH
0064	621-06567	WATER	15.00	KGAL
0065	621-06575	SODDING, NURSERY	3594.00	SYS
0066	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	17.00	EACH
0067	628-09401	FIELD OFFICE, A	26.00	MOS
0068	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH

0069	628-11977	COMPUTER SYSTEM	1.00 EACH
0070	702-90915	CONCRETE, CLASS, A	3.00 CYS
0071	703-06029	REINFORCING BARS, EPOXY COATED	371.00 LBS
0072	706-04683	RAILING	115.00 LFT
0073	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	21.00 LFT
0074	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	15.00 LFT
0075	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1794.00 LFT
0076	715-09064	VIDEO INSPECTION FOR PIPE	1794.00 LFT
0077	715-91361	PIPE PVC 6 IN	50.00 LFT
0078	715-92037	PIPE PVC, 4 IN.	50.00 LFT
0079	720-02442	PIPE PLUG EXISTING	2.00 EACH
0080	720-12797	CASTING, INLET, ADJUST TO GRADE	6.00 EACH
0081	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	7.00 EACH
0082	720-45005	INLET, A2	2.00 EACH
0083	720-45030	INLET, E7	2.00 EACH
0084	720-45045	INLET, J10	7.00 EACH
0085	720-45055	INLET, M10	10.00 EACH
0086	720-45075	INLET, R13	2.00 EACH
0087	720-45145	INLET, J10 MODIFIED	1.00 EACH
0088	720-45410	MANHOLE, C4	1.00 EACH
0089	720-45416	MANHOLE, E4	2.00 EACH
0090	720-90349	MANHOLE, C8	6.00 EACH
0091	720-97317	INLET, F	1.00 EACH
0092	732-11770	AGGREGATE FOR DRAINAGE FILL	21.00 CYS
0093	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	2.00 EACH
0094	801-02595	CONTROLLER RESET TIMING	2.00 EACH
0095	801-03291	CONSTRUCTION SIGN, D	4.00 EACH
0096	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00 EACH
0097	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	1600.00 LFT
0098	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4000.00 LFT
0099	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	1200.00 LFT
0100	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	9.00 EACH
0101	801-06217	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 6 IN.	800.00 LFT
0102	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	200.00 LFT
0103	801-06625	DETOUR ROUTE MARKER ASSEMBLY	44.00 EACH
0104	801-06640	CONSTRUCTION SIGN, A	54.00 EACH
0105	801-06645	CONSTRUCTION SIGN, B	41.00 EACH

0106	801-06775	MAINTAINING TRAFFIC	1.00	LS
0107	801-07118	BARRICADE, III-A	114.00	LFT
0108	801-07119	BARRICADE, III-B	128.00	LFT
0109	801-07612	TEMPORARY PAVEMENT MARKING, 24 IN.	100.00	LFT
0110	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0111	802-04089	SIGN, SHEET, REMOVE	1.00	EACH
0112	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	78.00	LFT
0113	802-07060	SIGN, SHEET, RELOCATE	4.00	EACH
0114	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	69.00	SFT
0115	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	14.00	SFT
0116	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	43.00	SFT
0117	804-11921	DELINEATOR POST FLEXIBLE, TYPE II	3.00	EACH
0118	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0119	805-01842	HANDHOLE, SIGNAL, TYPE 1	4.00	EACH
0120	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	60.00	LFT
0121	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	8.00	EACH
0122	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0123	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	8.00	EACH
0124	805-04782	VIDEO VEHICLE DETECTOR SYSTEM	1.00	EACH
0125	805-05405	SIGNAL POLE, PEDESTAL, 4 FT	8.00	EACH
0126	805-11387	SIGNAL CANTILEVER STRUCTURE, SPREAD FOOTING FOUNDATION, C	3.00	EACH
0127	805-11388	SIGNAL CANTILEVER STRUCTURE, SPREAD FOOTING FOUNDATION, D	1.00	EACH
0128	805-11437	SIGNAL CANTILEVER STRUCTURE, COMBINATION ARM 35 FT	3.00	EACH
0129	805-11439	SIGNAL CANTILEVER STRUCTURE, COMBINATION ARM 45 FT	1.00	EACH
0130	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	1030.00	LFT
0131	805-11817	PEDESTRIAN PUSH BUTTON, APS	8.00	EACH
0132	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	8.00	EACH
0133	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	3.00	EACH
0134	805-78445	SIGNAL SERVICE	1.00	EACH
0135	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	50.00	LFT
0136	805-78480	SIGNAL CABLE, CONTROL, COPPER, 3C/14 GAUGE	1040.00	LFT
0137	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	420.00	LFT
0138	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	850.00	LFT
0139	805-78500	SIGNAL CABLE, CONTROL, COPPER, 11C/14 GAUGE	560.00	LFT
0140	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0141	807-95709	PHOTOCELLS	1.00	EACH
0142	807-95889	WIRE, NO. 10 COPPER, 1/C	2300.00	LFT

0143	808-02977	PAVEMENT MESSAGE MARKING, THERMOPLASTIC, BIKE SYMBOL	2.00	EACH
0144	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	1262.00	LFT
0145	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	1258.00	LFT
0146	808-06716	LINE, REMOVE	3351.00	LFT
0147	808-09450	CROSSWALK, DECORATIVE THERMOPLASTIC	60.00	SFT
0148	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	21.00	LFT
0149	808-11493	LINE, THERMOPLASTIC, DOTTED, YELLOW, 4 IN.	34.00	LFT
0150	808-12316	TRANSVERSE MARKING, PAINT, PARKING LINE, WHITE, 4 IN.	108.00	LFT
0151	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	380.00	LFT
0152	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	6773.00	LFT
0153	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	54.00	LFT
0154	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	289.00	LFT
0155	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	75.00	LFT
0156	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	18.00	EACH
0157	809-05831	REMOTE MONITORING SYSTEM	1.00	EACH

Call: 211

Contract: R -42079-A

Section No.: 1 INTERSECTION IMPROVEMENT, ROUNDABOUT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-02240	PAVEMENT REMOVAL	10368.00 SYS
0013	202-86946	HANDHOLE, REMOVE	5.00 EACH
0014	202-90277	DETECTOR HOUSING, REMOVE	10.00 EACH
0015	202-91385	INLET, REMOVE	1.00 EACH
0016	202-93047	MANHOLE, REMOVE	2.00 EACH
0017	202-93763	LIGHT STANDARD AND FOUNDATION, REMOVE	4.00 EACH
0018	202-93995	SIGNAL POLE FOUNDATION, REMOVE	4.00 EACH
0019	202-95579	SERVICE POINT, REMOVE	1.00 EACH
0020	202-96133	PIPE, REMOVE	382.00 LFT
0021	203-02000	EXCAVATION, COMMON	8185.00 CYS
0022	205-12108	STORMWATER MANAGEMENT BUDGET	25788.00 DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0024	205-12618	SWQCP PREPARATION	1.00 LS
0025	207-08264	SUBGRADE TREATMENT, TYPE II	1293.00 SYS
0026	207-12151	SUBGRADE TREATMENT, TYPE IVA	12546.00 SYS
0027	211-09265	STRUCTURE BACKFILL, TYPE 2	964.00 CYS
0028	214-11796	GEOGRID, TYPE IB	1198.00 SYS
0029	214-12237	GEOTEXTILE FOR PAVEMENT, TYPE 1B	10937.00 SYS
0030	302-07455	DENSE GRADED SUBBASE	293.00 CYS
0031	303-01180	COMPACTED AGGREGATE NO. 53	4086.00 TON

0032	306-08036	MILLING, ASPHALT, 2 IN.	1611.00	SYS
0033	306-08432	MILLING, APPROACH	142.00	SYS
0034	306-11872	MILLING, PROFILE	885.00	SYS
0035	401-07352	QC/QA-HMA, 3, 76, SURFACE, 12.5 mm	1361.00	TON
0036	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1776.00	TON
0037	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	3898.00	TON
0038	401-10258	JOINT ADHESIVE, SURFACE	5988.00	LFT
0039	401-10259	JOINT ADHESIVE, INTERMEDIATE	5388.00	LFT
0040	401-11785	LIQUID ASPHALT SEALANT	5988.00	LFT
0041	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	1753.00	TON
0042	406-05520	ASPHALT FOR TACK COAT	12.00	TON
0043	502-11564	PCCP, 7 IN.	980.00	SYS
0044	503-05240	D-1 CONTRACTION JOINT	315.00	LFT
0045	604-06070	SIDEWALK, CONCRETE	170.00	SYS
0046	604-08086	CURB RAMP, CONCRETE	113.00	SYS
0047	604-12083	DETECTABLE WARNING SURFACES	19.00	SYS
0048	605-06120	CURB, CONCRETE	256.00	LFT
0049	605-06140	CURB AND GUTTER, CONCRETE	1942.00	LFT
0050	605-06160	CURB AND GUTTER, B, CONCRETE, MODIFIED	1317.00	LFT
0051	605-06245	CENTER CURB, B CONCRETE	77.00	SYS
0052	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	14.00	LFT
0053	605-97937	CURB AND GUTTER, ROLL CURB	355.00	LFT
0054	607-06175	GUTTER, CONCRETE, A	16.00	LFT
0055	607-06335	PAVED SIDE DITCH, A	9.00	LFT
0056	610-07487	HMA FOR APPROACHES, TYPE B	75.00	TON
0057	610-08446	PCCP FOR APPROACHES, 6 IN.	95.00	SYS
0058	610-09108	PCCP FOR APPROACHES, 9 IN.	1134.00	SYS
0059	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	3.00	EACH
0060	615-06490	RIGHT-OF-WAY MARKER	10.00	EACH
0061	615-06505	MONUMENT, B	18.00	EACH
0062	615-06510	MONUMENT, C	1.00	EACH
0063	615-06515	MONUMENT, D	20.00	EACH
0064	616-06405	RIPRAP, REVETMENT	26.00	TON
0065	616-11736	DECORATIVE STONE	24.00	TON
0066	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	143.00	SYS
0067	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	59.00	SYS
0068	621-06567	WATER	28.00	KGAL

0069	621-06570	TOPSOIL	771.00	CYS
0070	621-06575	SODDING, NURSERY	6932.00	SYS
0071	621-08538	MULCH	8.00	CYS
0072	622-04990	LANDSCAPE EDGING	419.00	LFT
0073	622-05627	PLANT, CONIFEROUS EVERGREEN, CONE BROAD UPRIGHT, OVER 96 IN.	1.00	EACH
0074	622-05639	PLANT, DECIDUOUS SHRUB, 18 IN. TO 24 IN.	27.00	EACH
0075	622-05640	PLANT, DECIDUOUS SHRUB, 24 IN. TO 36 IN.	22.00	EACH
0076	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	4.00	EACH
0077	622-05654	PLANT, PERENNIAL	320.00	EACH
0078	628-09403	FIELD OFFICE, C	12.00	MOS
0079	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0080	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	2902.00	LFT
0081	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	181.00	LFT
0082	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	969.00	LFT
0083	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	166.00	LFT
0084	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	91.00	LFT
0085	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	575.00	LFT
0086	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	20.00	LFT
0087	715-09064	VIDEO INSPECTION FOR PIPE	1821.00	LFT
0088	715-46010	PIPE END SECTION, DIAMETER 18 IN.	3.00	EACH
0089	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	EACH
0090	718-06529	OUTLET PROTECTOR, 2	3.00	EACH
0091	718-12307	GEOTEXTILE FOR UNDERDRAIN, TYPE 2A	2530.00	SYS
0092	718-52610	AGGREGATE FOR UNDERDRAINS	276.00	CYS
0093	720-03757	MANHOLE, C15	10.00	EACH
0094	720-45030	INLET, E7	2.00	EACH
0095	720-45040	INLET, G7	1.00	EACH
0096	720-45265	PIPE CATCH BASIN, 15 IN.	3.00	EACH
0097	720-98174	INLET, B15	6.00	EACH
0098	720-98555	INLET, C15	6.00	EACH
0099	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0100	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0101	801-03291	CONSTRUCTION SIGN, D	2.00	EACH
0102	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00	EACH
0103	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	13246.00	LFT
0104	801-06625	DETOUR ROUTE MARKER ASSEMBLY	34.00	EACH
0105	801-06640	CONSTRUCTION SIGN, A	22.00	EACH

0106	801-06775	MAINTAINING TRAFFIC	1.00	LS
0107	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00	EACH
0108	801-07118	BARRICADE, III-A	32.00	LFT
0109	801-07119	BARRICADE, III-B	128.00	LFT
0110	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2730.00	LFT
0111	802-04089	SIGN, SHEET, REMOVE	9.00	EACH
0112	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	339.00	LFT
0113	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	80.00	LFT
0114	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	218.00	SFT
0115	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	72.00	SFT
0116	802-91122	SIGN GROUND MOUNTED RESET	5.00	EACH
0117	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00	EACH
0118	805-03968	CONDUIT, PVC, 1 IN. SCHEDULE 80	230.00	LFT
0119	805-90267	CONDUIT, STEEL, GALVANIZED, 3 IN.	195.00	LFT
0120	807-02191	HANDHOLE, LIGHTING	4.00	EACH
0121	807-03950	LUMINAIRE ORNAMENTAL	15.00	EACH
0122	807-03951	LIGHT POLE ORNAMENTAL	15.00	EACH
0123	807-03951	LIGHT POLE ORNAMENTAL	4.00	EACH
0124	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1695.00	LFT
0125	807-11694	ILLUMINATED SIGN	4.00	EACH
0126	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE WITH GROUNDING	4.00	EACH
0127	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE WITH GROUNDING	15.00	EACH
0128	807-86810	SERVICE POINT, II	1.00	EACH
0129	807-95889	WIRE, NO. 10 COPPER, 1/C	1020.00	LFT
0130	808-06716	LINE, REMOVE	853.00	LFT
0131	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	170.00	LFT
0132	808-10032	LINE, MULTI-COMPONENT, DOTTED, WHITE, 8 IN.	104.00	LFT
0133	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	3409.00	LFT
0134	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	1774.00	LFT
0135	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	56.00	LFT
0136	808-10042	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW 12 IN.	152.00	LFT
0137	808-10058	LINE, MULTI-COMPONENT, SOLID, YELLOW, 8 IN.	893.00	LFT
0138	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	29.00	EACH
0139	808-10099	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 24 IN.	187.00	LFT
0140	808-12032	GROOVING FOR PAVEMENT MARKINGS	6696.00	LFT
0141	808-12700	LINE MULTI-COMPONENT DOTTED WHITE 12 IN.	293.00	LFT

Call: 221

Contract: R -42188-A

Section No.: 1 BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	105-11823	CONSTRUCTION ENGINEERING GPS ROVER	1.00	LS
0003	108-09283	CPM SCHEDULE	1.00	LS
0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0005	109-08360	CONTRACT LIENS	1.00	DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0007	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0008	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0009	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0010	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0011	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0012	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0013	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0014	109-12573	SPECIAL MAINTENANCE	40000.00	DOL
0015	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0016	201-01025	SCALPING	33.00	ACRE
0017	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0018	202-02240	PAVEMENT REMOVAL	1618.00	SYS
0019	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00	LS
0020	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0021	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0022	203-02000	EXCAVATION, COMMON	75444.00	CYS
0023	203-02070	BORROW	184788.00	CYS
0024	203-51223	EXCAVATION, WATERWAY	1130.00	CYS
0025	204-02290	SETTLEMENT PLATE	19.00	EACH
0026	204-08415	STAKE, SETTLEMENT	19.00	EACH
0027	205-11626	PUMP AROUND	1.00	EACH
0028	205-12108	STORMWATER MANAGEMENT BUDGET	463163.90	DOL
0029	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0030	205-12618	SWQCP PREPARATION	1.00	LS
0031	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	1357.00	CYS

0032	206-51235	COFFERDAM	1.00	LS
0033	206-93520	TEMPORARY SHEET PILING	3049.00	SFT
0034	207-08264	SUBGRADE TREATMENT, TYPE II	6884.00	SYS
0035	207-09935	SUBGRADE TREATMENT, TYPE IC	3191.00	SYS
0036	207-12498	SUBGRADE TREATMENT, TYPE ID	12379.00	SYS
0037	207-12635	SUBGRADE TREATMENT, TYPE IBC	56312.00	SYS
0038	211-02050	B BORROW	29853.00	CYS
0039	211-06467	AGGREGATE FOR END BENT BACKFILL	136.00	CYS
0040	211-09264	STRUCTURE BACKFILL, TYPE 1	891.00	CYS
0041	211-09265	STRUCTURE BACKFILL, TYPE 2	260.00	CYS
0042	211-09266	STRUCTURE BACKFILL, TYPE 3	9072.00	CYS
0043	211-09268	STRUCTURE BACKFILL, TYPE 5	175.00	CYS
0044	214-11796	GEOGRID, TYPE IB	3600.00	SYS
0045	214-12236	GEOTEXTILE FOR PAVEMENT, TYPE 1A	25.00	SYS
0046	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	3865.00	SYS
0047	217-11917	DRYING SOILS FOR EMBANKMENT	4470.00	TON
0048	301-12231	COMPACTED AGGREGATE NO. 2	92.90	CYS
0049	301-12233	COMPACTED AGGREGATE NO. 8	5875.00	CYS
0050	301-12234	COMPACTED AGGREGATE NO. 53	2561.00	CYS
0051	302-06464	SUBBASE FOR PCCP	665.00	CYS
0052	303-01180	COMPACTED AGGREGATE NO. 53	3851.00	TON
0053	304-07789	WIDENING WITH HMA, TYPE D	7116.00	TON
0054	306-08034	MILLING, ASPHALT, 1 1/2 IN.	4793.00	SYS
0055	306-08039	MILLING, ASPHALT REMOVAL	1131.00	SYS
0056	306-08042	MILLING, SCARIFICATION	1131.00	SYS
0057	306-08159	MILLING, ASPHALT	972.00	SYS
0058	306-08159	MILLING, ASPHALT	2331.00	SYS
0059	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	604.00	TON
0060	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	4349.00	TON
0061	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	601.00	TON
0062	401-07379	QC/QA-HMA, 3, 70, INTERMEDIATE, 12.5 mm	273.00	TON
0063	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	8322.00	TON
0064	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	15988.00	TON
0065	401-10258	JOINT ADHESIVE, SURFACE	38988.00	LFT
0066	401-10259	JOINT ADHESIVE, INTERMEDIATE	38988.00	LFT
0067	401-11785	LIQUID ASPHALT SEALANT	38988.00	LFT
0068	401-12169	INERTIAL PROFILER, HMA	1.00	LS

0069	402-07451	HMA WEDGE AND LEVEL, TYPE B	31.00 TON
0070	402-10084	HMA FOR TEMPORARY PAVEMENT, TYPE B	5895.00 TON
0071	402-10087	HMA FOR TEMPORARY PAVEMENT, TYPE D	293.00 TON
0072	406-05520	ASPHALT FOR TACK COAT	53.00 TON
0073	502-06329	PCCP, 12 IN.	487.00 SYS
0074	502-06627	PCCP, 6 IN.	25.00 SYS
0075	503-03489	RETROFITTED TIE BARS	92.00 EACH
0076	503-05240	D-1 CONTRACTION JOINT	750.00 LFT
0077	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	1124.00 SYS
0078	503-12477	TERMINAL JOINT, TYPE HMA	98.00 LFT
0079	503-12478	TERMINAL JOINT, TYPE PCCP	254.00 LFT
0080	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	253.00 LFT
0081	601-06234	IMPACT ATTENUATOR, R1-W1, TL-2	5.00 EACH
0082	601-06236	IMPACT ATTENUATOR, R1-W2, TL-2	2.00 EACH
0083	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	1763.00 LFT
0084	601-12282	GUARDRAIL, MGS W-BEAM, 3 FT 1.5 IN. SPACING	50.00 LFT
0085	601-12283	GUARDRAIL, MGS W-BEAM, 1 FT 6.75 IN. SPACING	50.00 LFT
0086	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN. SPACING	388.00 LFT
0087	601-12286	GUARDRAIL, MGS W-BEAM, SHOP CURVED, 6 FT 3 IN. SPACING	112.00 LFT
0088	601-12288	GUARDRAIL, MGS, LONG SPAN, TYPE 2	6.00 EACH
0089	601-12291	GUARDRAIL, MGS, TRANSITION WITH CURB	3.00 EACH
0090	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	8.00 EACH
0091	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	4.00 EACH
0092	601-94689	GUARDRAIL, END TREATMENT, OS	3.00 EACH
0093	601-94689	GUARDRAIL, END TREATMENT, OS	3.00 EACH
0094	601-94690	GUARDRAIL, END TREATMENT, MS	2.00 EACH
0095	602-01064	CONCRETE BARRIER	75.00 LFT
0096	602-06729	BARRIER, DELINEATOR	90.00 EACH
0097	605-08636	CURB AND GUTTER, TURNOUT COMBINED	58.00 LFT
0098	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	13631.00 LFT
0099	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	485.00 SYS
0100	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	810.80 SYS
0101	610-07487	HMA FOR APPROACHES, TYPE B	2380.00 TON
0102	611-06497	MAILBOX ASSEMBLY, SINGLE	3.00 EACH
0103	615-06490	RIGHT-OF-WAY MARKER	74.00 EACH
0104	615-06505	MONUMENT, B	66.00 EACH
0105	615-06510	MONUMENT, C	10.00 EACH

0106	615-06527	MONUMENT, SECTION CORNER	2.00 EACH
0107	616-05688	RIPRAP, CLASS 1	50.00 TON
0108	616-06405	RIPRAP, REVETMENT	2366.00 TON
0109	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	2798.00 SYS
0110	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	573.00 SYS
0111	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00 EACH
0112	621-02770	EROSION CONTROL BLANKET	107802.00 SYS
0113	621-06545	FERTILIZER	9.00 TON
0114	621-06553	SEED MIXTURE, R	4727.00 LBS
0115	621-06559	MULCHED SEEDING R	400.00 SYS
0116	621-06565	MULCHING MATERIAL	46.00 TON
0117	621-06567	WATER	35.00 KGAL
0118	621-06574	SODDING	11757.00 SYS
0119	621-12612	SEED MIXTURE, FLOODPLAIN	20.00 LBS
0120	622-52436	SIGN, DO NOT MOW OR SPRAY	5.00 EACH
0121	622-91786	SEEDLING	657.00 EACH
0122	624-92647	HERBICIDE TREATMENT	2.00 ACRE
0123	628-12683	FIELD OFFICE, D	18.00 MOS
0124	701-06011	DYNAMIC PILE LOAD TEST	15.00 EACH
0125	701-08253	PILE, SLEEVES	28.00 EACH
0126	701-09557	TEST PILE, DYNAMIC, PRODUCTION	850.00 LFT
0127	701-09559	TEST PILE, DYNAMIC, RESTRIKE	15.00 EACH
0128	701-09665	PILE, STEEL PIPE, 0.375 IN., 14 IN.	2756.00 LFT
0129	701-09679	CONICAL PILE TIP, 14 IN.	54.00 EACH
0130	701-09683	PILE SHOE, HP 12 X 74	113.00 EACH
0131	701-09739	PILE SHOE, HP 12 X 53	34.00 EACH
0132	701-51195	PILE, STEEL H HP 12 X 53	1395.00 LFT
0133	701-95780	PILE, STEEL H, HP 12 X 74	4163.00 LFT
0134	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	8.00 EACH
0135	702-51005	CONCRETE, A, SUBSTRUCTURE	756.80 CYS
0136	702-51015	CONCRETE, B, FOOTINGS	112.20 CYS
0137	702-51046	CONCRETE, FOUNDATION SEAL	66.00 CYS
0138	702-92857	CONCRETE, C, SUBSTRUCTURE	192.70 CYS
0139	703-01540	THREADED TIE BAR ASSEMBLY	288.00 EACH
0140	703-06028	REINFORCING BARS	110939.00 LBS
0141	703-06029	REINFORCING BARS, EPOXY COATED	636981.00 LBS
0142	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	2379.00 EACH

0143	704-51002	CONCRETE, C, SUPERSTRUCTURE	1252.70	CYS
0144	706-08505	REINFORCED CONCRETE MOMENT SLAB, 18 IN.	573.00	SYS
0145	706-09960	RAILING, CONCRETE FC	66.00	LFT
0146	706-11600	RAILING, CONCRETE FC	65.30	CYS
0147	706-11601	RAILING, CONCRETE FT	71.10	CYS
0148	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	7.00	EACH
0149	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	8.00	EACH
0150	706-94947	RAILING, CONCRETE C, MODIFIED	219.00	CYS
0151	707-05982	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 28 IN. X 12 IN.	3475.00	LFT
0152	707-09634	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 48 IN. X 49 IN.	1266.00	LFT
0153	709-51821	SURFACE SEAL	1.00	LS
0154	709-51821	SURFACE SEAL	1.00	LS
0155	709-51821	SURFACE SEAL	1.00	LS
0156	709-51821	SURFACE SEAL	1.00	LS
0157	709-51821	SURFACE SEAL	1.00	LS
0158	713-04509	TEMPORARY PIPE	1.00	LS
0159	714-11059	STRUCTURE EXTENSION, REINFORCED CONCRETE BOX SECTIONS, 3 FT X 3 FT	80.00	LFT
0160	714-11178	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 8 FT X 5 FT	88.00	LFT
0161	715-01344	PIPE END SECTION, DIAMETER 60 IN.	2.00	EACH
0162	715-02246	PIPE END SECTION, DIAMETER 48 IN.	2.00	EACH
0163	715-04985	VAULT	5.00	EACH
0164	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	219.00	LFT
0165	715-05032	PIPE, TYPE 2, CIRCULAR, 15 IN.	396.00	LFT
0166	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	6679.00	LFT
0167	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	688.00	LFT
0168	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	58.00	LFT
0169	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	26.00	LFT
0170	715-05123	PIPE, TYPE 1, CIRCULAR, 24 IN.	622.00	LFT
0171	715-05128	PIPE, TYPE 1, CIRCULAR, 48 IN.	121.00	LFT
0172	715-05133	PIPE, TYPE 1, CIRCULAR, 60 IN.	80.00	LFT
0173	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	234.00	LFT
0174	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	35.00	LFT
0175	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	173.00	LFT
0176	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	52.00	LFT
0177	715-05175	PIPE, TYPE 3, CIRCULAR, 30 IN.	85.00	LFT
0178	715-46005	PIPE END SECTION, DIAMETER 15 IN.	8.00	EACH
0179	715-46010	PIPE END SECTION, DIAMETER 18 IN.	8.00	EACH

0180	715-46020	PIPE END SECTION, DIAMETER 24 IN.	10.00 EACH
0181	715-46030	PIPE END SECTION, DIAMETER 30 IN.	4.00 EACH
0182	715-46040	PIPE END SECTION, DIAMETER 36 IN.	3.00 EACH
0183	716-07631	PIPE INSTALLATION, TRENCHLESS, 15 IN.	198.00 LFT
0184	716-07632	PIPE INSTALLATION, TRENCHLESS, 18 IN.	851.00 LFT
0185	718-06528	OUTLET PROTECTOR, 1	7.00 EACH
0186	718-06531	OUTLET PROTECTOR, 3	8.00 EACH
0187	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00 LFT
0188	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	3475.00 SYS
0189	718-12308	GEOTEXTILE FOR UNDERDRAIN, TYPE 2B	521.00 SYS
0190	718-52610	AGGREGATE FOR UNDERDRAINS	499.00 CYS
0191	719-05440	PIPE, DRAIN. TILE TERMINAL SECTION, 8 IN.	1000.00 LFT
0192	719-05443	PIPE, DRAIN. TILE TERMINAL SECTION, 12 IN.	1000.00 LFT
0193	719-09392	PIPE, DRAIN, TILE TERMINAL SECTION, 15 IN.	1000.00 LFT
0194	720-45065	INLET, N12	16.00 EACH
0195	720-45066	INLET, N12 MODIFIED	3.00 EACH
0196	720-45410	MANHOLE, C4	2.00 EACH
0197	720-90984	MANHOLE, C2	1.00 EACH
0198	731-93945	FACE PANELS, CONCRETE	18077.00 SFT
0199	731-93946	WALL ERECTION	18077.00 SFT
0200	731-93947	LEVELING PAD, CONCRETE	1050.00 LFT
0201	735-10241	TEMPORARY WIRE FACING	198.00 SFT
0202	735-10242	TEMPORARY WALL ERECTION	198.00 SFT
0203	801-03290	CONSTRUCTION SIGN, C	2.00 EACH
0204	801-04308	ROAD CLOSURE SIGN ASSEMBLY	13.00 EACH
0205	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	93307.00 LFT
0206	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	37093.00 LFT
0207	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	196.00 LFT
0208	801-06625	DETOUR ROUTE MARKER ASSEMBLY	74.00 EACH
0209	801-06640	CONSTRUCTION SIGN, A	57.00 EACH
0210	801-06645	CONSTRUCTION SIGN, B	20.00 EACH
0211	801-06710	FLASHING ARROW SIGN	118.00 DAY
0212	801-06775	MAINTAINING TRAFFIC	1.00 LS
0213	801-07118	BARRICADE, III-A	380.00 LFT
0214	801-07119	BARRICADE, III-B	120.00 LFT
0215	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	5190.00 LFT
0216	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	4170.00 LFT

0217	801-12324	LAW ENFORCEMENT OFFICER	500.00	HRS
0218	802-02475	SIGN, PANEL, RELOCATE	2.00	EACH
0219	802-04893	REFERENCE POST	26.00	EACH
0220	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	503.00	LFT
0221	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	102.00	LFT
0222	802-07057	SIGN, PANEL, WITH LEGEND	2102.00	SFT
0223	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	29.00	EACH
0224	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	139.00	SFT
0225	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	372.00	SFT
0226	802-09861	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE I	1.00	EACH
0227	802-11886	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 48 IN.	1.00	EACH
0228	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	14.00	EACH
0229	802-12223	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, B	24.00	EACH
0230	802-74040	SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	2.00	EACH
0231	802-76055	SIGN POST, A	112.00	LFT
0232	802-76095	STRUCTURAL STEEL, BREAKAWAY	13054.00	LBS
0233	804-06725	DELINEATOR WITH POST, D1	94.00	EACH
0234	805-01842	HANDHOLE, SIGNAL, TYPE 1	24.00	EACH
0235	805-02645	SIGNAL POLE FOUNDATION, 24 IN. X 24 IN. X 36 IN.	2.00	EACH
0236	805-04973	CONDUIT	1040.00	LFT
0237	805-09451	SIGNAL POLE, PEDESTAL, 15 FT	2.00	EACH
0238	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	33839.00	LFT
0239	807-02426	WIRE, THW, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	600.00	LFT
0240	807-04651	WIRE	5137.00	LFT
0241	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	600.00	LFT
0242	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	11550.00	LFT
0243	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	39.00	EACH
0244	807-12557	HIGH MAST TOWER, 105 FT E.M.H.	2.00	EACH
0245	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE WITH GROUNDING	27.00	EACH
0246	807-12792	LIGHTING FOUNDATION, HIGH MAST TOWER, CONCRETE WITH GROUNDING	2.00	EACH
0247	807-85762	LIGHT POLE, 40 FT E.M.H., 15 FT MAST ARM, BREAKAWAY BASE	27.00	EACH
0248	807-86810	SERVICE POINT, II	2.00	EACH
0249	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	3620.00	LFT
0250	807-86910	CONNECTOR KIT, UNFUSED	39.00	EACH
0251	807-86915	CONNECTOR KIT, FUSED	39.00	EACH
0252	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	65.00	EACH
0253	807-86930	INSULATION LINK, NON-WATERPROOFED	84.00	EACH

0254	807-86950	SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION IDENTIFICATION	29.00	EACH
0255	807-86955	CABLE DUCT MARKER	14.00	EACH
0256	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	9959.00	LFT
0257	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	2254.00	LFT
0258	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0259	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	864.00	LFT
0260	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	864.00	LFT
0261	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	684.00	LFT
0262	808-10042	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, YELLOW 12 IN.	298.00	LFT
0263	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	260.00	LFT
0264	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	620.00	LFT
0265	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	678.00	LFT
0266	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN	679.00	LFT
0267	808-12032	GROOVING FOR PAVEMENT MARKINGS	42559.00	LFT
0268	808-12782	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 6 IN.	5246.00	LFT
0269	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	9581.00	LFT
0270	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	1430.00	LFT
0271	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7946.00	LFT
0272	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	7187.00	LFT
0273	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	276.00	LFT
0274	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	1175.00	LFT
0275	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	110.00	LFT
0276	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	4.00	EACH
0277	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	153.00	EACH
0278	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	333.00	LFT
0279	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	1889.00	LFT

Call: 225

Contract: R -42477-C

Section No.: 1 ASPHALT RESURFACE

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	1090.00	SYS
0014	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0015	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0016	202-90277	DETECTOR HOUSING, REMOVE	9.00	EACH
0017	203-02000	EXCAVATION, COMMON	812.00	CYS
0018	203-08607	LINEAR GRADING	1188.00	LFT
0019	203-51223	EXCAVATION, WATERWAY	125.00	CYS
0020	205-12108	STORMWATER MANAGEMENT BUDGET	25700.00	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	205-12618	SWQCP PREPARATION	1.00	LS
0023	207-08264	SUBGRADE TREATMENT, TYPE II	163.00	SYS
0024	207-09935	SUBGRADE TREATMENT, TYPE IC	3872.00	SYS
0025	211-02050	B BORROW	257.00	CYS
0026	211-09264	STRUCTURE BACKFILL, TYPE 1	10.00	CYS
0027	213-09270	FLOWABLE BACKFILL, REMOVABLE	54.00	CYS
0028	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	949.00	SYS
0029	301-12234	COMPACTED AGGREGATE NO. 53	41.00	CYS
0030	302-06464	SUBBASE FOR PCCP	217.00	CYS
0031	302-07455	DENSE GRADED SUBBASE	12.00	CYS

0032	303-01180	COMPACTED AGGREGATE NO. 53	996.00 TON
0033	304-07494	WIDENING WITH HMA, TYPE C	64.00 TON
0034	304-12627	HMA PATCHING FULL DEPTH, TYPE D	530.00 TON
0035	304-12628	HMA PATCHING PARTIAL DEPTH, TYPE D	500.00 TON
0036	306-08034	MILLING, ASPHALT, 1 1/2 IN.	68369.00 SYS
0037	306-08042	MILLING, SCARIFICATION	741.00 SYS
0038	306-08432	MILLING, APPROACH	3738.00 SYS
0039	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1649.00 TON
0040	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	4287.00 TON
0041	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	470.00 TON
0042	401-08364	QC/QA-HMA, 4, 64, BASE, 19.0 mm	734.00 TON
0043	401-08366	QC/QA-HMA, 4, 70, BASE, 19.0 mm	756.00 TON
0044	401-10258	JOINT ADHESIVE, SURFACE	49420.00 LFT
0045	401-10259	JOINT ADHESIVE, INTERMEDIATE	2062.00 LFT
0046	401-11785	LIQUID ASPHALT SEALANT	4460.00 LFT
0047	401-12169	INERTIAL PROFILER, HMA	1.00 LS
0048	401-12483	RAPID PENETRATING EMULSION	44960.00 LFT
0049	406-05520	ASPHALT FOR TACK COAT	28.50 TON
0050	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00 EACH
0051	601-02241	GUARDRAIL, REMOVE	938.00 LFT
0052	601-06238	IMPACT ATTENUATOR, R1-W1, TL-3	2.00 EACH
0053	601-09238	HAND DIG GUARDRAIL POST HOLES	10.00 EACH
0054	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	200.00 LFT
0055	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	1.00 EACH
0056	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	6.00 EACH
0057	601-94689	GUARDRAIL, END TREATMENT, OS	5.00 EACH
0058	602-06729	BARRIER, DELINEATOR	18.00 EACH
0059	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	27076.00 LFT
0060	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	853.00 SYS
0061	610-07487	HMA FOR APPROACHES, TYPE B	349.00 TON
0062	610-08446	PCCP FOR APPROACHES, 6 IN.	67.00 SYS
0063	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	7.00 EACH
0064	615-06505	MONUMENT, B	4.00 EACH
0065	615-06525	CASTING ADJUST TO GRADE, MONUMENT	3.00 EACH
0066	615-06530	BENCH MARK POST	2.00 EACH
0067	616-05688	RIPRAP, CLASS 1	769.00 TON
0068	616-06405	RIPRAP, REVETMENT	671.00 TON

0069	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	2005.00	SYS
0070	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	315.00	SYS
0071	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0072	621-06559	MULCHED SEEDING R	2642.00	SYS
0073	621-06574	SODDING	220.00	SYS
0074	622-05650	PLANT, DECIDUOUS TREE, SINGLE STEM, OVER 2 IN. TO 2.5 IN.	3.00	EACH
0075	628-09403	FIELD OFFICE, C	6.00	MOS
0076	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0077	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0078	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0079	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	12.00	MOS
0080	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0081	628-11977	COMPUTER SYSTEM	1.00	EACH
0082	701-06011	DYNAMIC PILE LOAD TEST	8.00	EACH
0083	701-09557	TEST PILE, DYNAMIC, PRODUCTION	518.00	LFT
0084	701-09559	TEST PILE, DYNAMIC, RESTRIKE	8.00	EACH
0085	701-09663	PILE, STEEL PIPE, 0.312 IN., 14 IN.	3476.00	LFT
0086	701-09675	PILE, STEEL PIPE, EPOXY COATED, 0.312 IN., 14 IN.	360.00	LFT
0087	701-09679	CONICAL PILE TIP, 14 IN.	36.00	EACH
0088	702-04325	TEMPORARY SHORING	1.00	LS
0089	702-04325	TEMPORARY SHORING	1.00	LS
0090	703-06029	REINFORCING BARS, EPOXY COATED	169074.00	LBS
0091	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	1012.00	EACH
0092	704-51002	CONCRETE, C, SUPERSTRUCTURE	628.00	CYS
0093	706-11600	RAILING, CONCRETE FC	34.20	CYS
0094	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00	EACH
0095	709-51821	SURFACE SEAL	1.00	LS
0096	709-51821	SURFACE SEAL	1.00	LS
0097	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	102.00	LFT
0098	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0099	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	11.00	EACH
0100	801-03291	CONSTRUCTION SIGN, D	9.00	EACH
0101	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	50625.00	LFT
0102	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	11276.00	LFT
0103	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	640.00	LFT
0104	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	11.00	EACH
0105	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	243.00	LFT

0106	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	291.00	LFT
0107	801-06640	CONSTRUCTION SIGN, A	109.00	EACH
0108	801-06645	CONSTRUCTION SIGN, B	20.00	EACH
0109	801-06710	FLASHING ARROW SIGN	30.00	DAY
0110	801-06775	MAINTAINING TRAFFIC	1.00	LS
0111	801-07119	BARRICADE, III-B	96.00	LFT
0112	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1644.00	LFT
0113	801-12042	TRUCK MOUNTED ATTENUATOR	30.00	DAY
0114	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0115	801-12324	LAW ENFORCEMENT OFFICER	75.00	HRS
0116	801-12482	DRIVEWAY ASSISTANCE DEVICE	5.00	EACH
0117	801-92448	CONSTRUCTION SIGNS MOBILE	540.00	DAY
0118	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	50.00	LFT
0119	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	3544.00	LFT
0120	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	300.00	LFT
0121	805-78785	SIGNAL DETECTOR HOUSING	9.00	EACH
0122	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1214.00	LFT
0123	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	1730.00	LFT
0124	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	27592.00	LFT
0125	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	311.00	LFT
0126	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2990.00	LFT
0127	808-06716	LINE, REMOVE	1750.00	LFT
0128	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0129	808-12032	GROOVING FOR PAVEMENT MARKINGS	17909.00	LFT
0130	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	2728.00	LFT
0131	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7659.00	LFT
0132	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	243.00	LFT
0133	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	11.00	EACH
0134	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	281.00	EACH
0135	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	281.00	EACH

Call: 231

Contract: R -42478-B

Section No.: 1 AUXILIARY LANE CONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-02240	PAVEMENT REMOVAL	281.00 SYS
0013	202-03000	HOUSES AND BUILDINGS, REMOVE, PARCEL NO.	1.00 LS
0014	202-03729	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	15.00 LFT
0015	202-04890	WELL	1.00 EACH
0016	202-74080	OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	1.00 EACH
0017	202-91840	FENCE, CHAIN LINK, REMOVE	300.00 LFT
0018	202-93741	GUARDRAIL, END TREATMENT, REMOVE	2.00 EACH
0019	202-96022	CONCRETE FOUNDATION, REMOVE	1.00 EACH
0020	203-02000	EXCAVATION, COMMON	4010.00 CYS
0021	205-12108	STORMWATER MANAGEMENT BUDGET	8848.00 DOL
0022	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0023	205-12618	SWQCP PREPARATION	1.00 LS
0024	207-08264	SUBGRADE TREATMENT, TYPE II	1454.00 SYS
0025	207-09935	SUBGRADE TREATMENT, TYPE IC	2316.00 SYS
0026	211-02050	B BORROW	5.00 CYS
0027	211-09265	STRUCTURE BACKFILL, TYPE 2	208.00 CYS
0028	211-09268	STRUCTURE BACKFILL, TYPE 5	5.00 CYS
0029	301-12233	COMPACTED AGGREGATE NO. 8	130.00 CYS
0030	301-12234	COMPACTED AGGREGATE NO. 53	425.00 CYS
0031	302-07455	DENSE GRADED SUBBASE	8.00 CYS

0032	303-01180	COMPACTED AGGREGATE NO. 53	425.00 TON
0033	306-08034	MILLING, ASPHALT, 1 1/2 IN.	7130.00 SYS
0034	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	67.00 TON
0035	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	895.00 TON
0036	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	160.00 TON
0037	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	497.00 TON
0038	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	268.00 TON
0039	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	2221.00 TON
0040	401-10258	JOINT ADHESIVE, SURFACE	7083.00 LFT
0041	401-10259	JOINT ADHESIVE, INTERMEDIATE	4264.00 LFT
0042	401-11785	LIQUID ASPHALT SEALANT	7083.00 LFT
0043	406-05520	ASPHALT FOR TACK COAT	7.00 TON
0044	601-02241	GUARDRAIL, REMOVE	300.00 LFT
0045	604-06070	SIDEWALK, CONCRETE	4.00 SYS
0046	610-07487	HMA FOR APPROACHES, TYPE B	371.00 TON
0047	610-08446	PCCP FOR APPROACHES, 6 IN.	45.00 SYS
0048	611-06497	MAILBOX ASSEMBLY, SINGLE	5.00 EACH
0049	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	1.00 EACH
0050	615-06490	RIGHT-OF-WAY MARKER	23.00 EACH
0051	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1182.00 SYS
0052	621-06567	WATER	16.00 KGAL
0053	621-06570	TOPSOIL	28.00 CYS
0054	621-06574	SODDING	3933.00 SYS
0055	628-09401	FIELD OFFICE, A	10.00 MOS
0056	628-11729	CELLULAR TELEPHONE, TYPE A	1.00 EACH
0057	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0058	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0059	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	6.00 MOS
0060	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0061	628-11977	COMPUTER SYSTEM	1.00 EACH
0062	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	21.00 LFT
0063	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00 EACH
0064	720-97865	MANHOLE, C2 MODIFIED	13.00 EACH
0065	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00 EACH
0066	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	15901.00 LFT
0067	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	1306.00 LFT
0068	801-06640	CONSTRUCTION SIGN, A	24.00 EACH

0069	801-06775	MAINTAINING TRAFFIC	1.00	LS
0070	801-07118	BARRICADE, III-A	276.00	LFT
0071	801-07119	BARRICADE, III-B	60.00	LFT
0072	801-09087	TEMPORARY PAVEMENT MARKING, REMOVABLE, 12 IN.	144.00	LFT
0073	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	91.00	LFT
0074	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	16.00	LFT
0075	802-07060	SIGN, SHEET, RELOCATE	2.00	EACH
0076	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	58.00	SFT
0077	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	5699.00	LFT
0078	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	126.00	LFT
0079	808-06716	LINE, REMOVE	11916.00	LFT
0080	808-12032	GROOVING FOR PAVEMENT MARKINGS	10698.00	LFT
0081	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	94.00	LFT
0082	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4036.00	LFT
0083	808-75260	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 12 IN.	45.00	LFT
0084	808-75290	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 24 IN.	108.00	LFT
0085	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	74.00	LFT
0086	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	6.00	EACH
0087	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	39.00	EACH
0088	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	39.00	EACH
0089	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	516.00	LFT

Call: 241

Contract: R -42491-B

Section No.: 1 CONCRETE PAVEMENT RESTORTATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	10.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	16.00 EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00 DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0010	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0011	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0012	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0014	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0015	202-02240	PAVEMENT REMOVAL	9962.00 SYS
0016	202-62420	BRIDGE RAILING, REMOVE	542.00 LFT
0017	202-91385	INLET, REMOVE	10.00 EACH
0018	202-94954	BARRIER WALL, CONCRETE, REMOVE	4736.00 LFT
0019	202-96133	PIPE, REMOVE	32.00 LFT
0020	203-02000	EXCAVATION, COMMON	2794.00 CYS
0021	205-12108	STORMWATER MANAGEMENT BUDGET	52000.00 DOL
0022	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	1817.00 SYS
0024	207-12151	SUBGRADE TREATMENT, TYPE IVA	18005.00 SYS
0025	211-09267	STRUCTURE BACKFILL, TYPE 4	1.00 CYS
0026	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	8.00 EACH
0027	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	8.00 CYS
0028	301-12233	COMPACTED AGGREGATE NO. 8	90.00 CYS
0029	302-06464	SUBBASE FOR PCCP	5254.00 CYS
0030	402-10087	HMA FOR TEMPORARY PAVEMENT, TYPE D	964.00 TON
0031	501-06266	PROFILOGRAPH PCCP	1.00 LS

0032	502-06332	PCCP, 15 IN.	5090.00	SYS
0033	503-05240	D-1 CONTRACTION JOINT	6632.00	LFT
0034	503-09261	PCCP STITCHING	4570.00	EACH
0035	503-12478	TERMINAL JOINT, TYPE PCCP	672.00	LFT
0036	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	672.00	LFT
0037	503-12668	JOINTED REINFORCED CONCRETE PAVEMENT 15 IN.	2826.00	SYS
0038	506-06333	PCCP PATCHING, FULL DEPTH	10093.00	SYS
0039	507-07480	PROFILING, PCCP	10093.00	SYS
0040	507-07505	RETROFIT LOAD TRANSFER	550.00	EACH
0041	507-08269	CRACKS IN PCCP, FILLED	52300.00	LFT
0042	507-08272	JOINTS IN PCCP, SAW AND SEAL	687554.00	LFT
0043	509-12191	JOINT REPAIR, PARTIAL DEPTH	27694.00	SFT
0044	509-12192	JOINT REPAIR, BOTTOM-HALF	277.00	SFT
0045	601-02241	GUARDRAIL, REMOVE	468.00	LFT
0046	601-06035	GUARDRAIL, RESET	239.00	LFT
0047	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	75.00	LFT
0048	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	6.00	EACH
0049	601-12291	GUARDRAIL, MGS, TRANSITION WITH CURB	6.00	EACH
0050	602-01064	CONCRETE BARRIER	3459.00	LFT
0051	602-01193	CONCRETE BARRIER GLARE SCREEN	1161.00	LFT
0052	602-06729	BARRIER, DELINEATOR	116.00	EACH
0053	602-11938	CONCRETE BARRIER, MODIFIED SECTION	316.20	CYS
0054	605-06095	CURB, INTEGRAL B CONCRETE	644.00	LFT
0055	609-06263	REINFORCED CONCRETE BRIDGE APPROACH, 15 IN.	1817.00	SYS
0056	616-06405	RIPRAP, REVETMENT	48.00	TON
0057	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	90.00	SYS
0058	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0059	621-06560	MULCHED SEEDING U	2853.00	SYS
0060	621-06574	SODDING	61.00	SYS
0061	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0062	628-12683	FIELD OFFICE, D	24.00	MOS
0063	702-51863	FIELD DRILLED HOLE IN CONCRETE	1392.00	EACH
0064	703-06029	REINFORCING BARS, EPOXY COATED	129307.00	LBS
0065	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	415.00	EACH
0066	706-08502	REINFORCED CONCRETE MOMENT SLAB, 15 IN.	324.00	SYS
0067	706-09959	RAILING, CONCRETE FT	8.00	LFT
0068	706-09959	RAILING, CONCRETE FT	494.00	LFT

0069	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	6.00	EACH
0070	709-51821	SURFACE SEAL	1.00	LS
0071	709-51821	SURFACE SEAL	1.00	LS
0072	709-51821	SURFACE SEAL	1.00	LS
0073	709-51821	SURFACE SEAL	1.00	LS
0074	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	644.00	LFT
0075	715-05049	PIPE, TYPE 4, CIRCULAR, 8 IN.	450.00	LFT
0076	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	32.00	LFT
0077	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	72.00	LFT
0078	715-05422	PIPE, SLOTTED DRAIN, 12 IN.	430.00	LFT
0079	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	882.00	SYS
0080	718-52610	AGGREGATE FOR UNDERDRAINS	152.00	CYS
0081	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00	EACH
0082	720-45041	INLET, H5	2.00	EACH
0083	720-45042	INLET, HA5	6.00	EACH
0084	720-96995	CLEAN INLET	4.00	EACH
0085	722-01066	HYDRODEMOLITION	2756.00	SYS
0086	722-12380	BRIDGE DECK OVERLAY, BUDGET	58230.00	DOL
0087	722-12382	TRANSVERSE GROOVING	6155.00	SYS
0088	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	4360.00	SYS
0089	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	257.00	SFT
0090	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1200.00	SFT
0091	727-90308	EPOXY INJECTION, CRACK PREPARATION	638.00	LFT
0092	727-90309	EPOXY INJECTION, EPOXY MATERIAL	75.00	GAL
0093	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0094	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0095	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	22.00	EACH
0096	801-03290	CONSTRUCTION SIGN, C	12.00	EACH
0097	801-04308	ROAD CLOSURE SIGN ASSEMBLY	16.00	EACH
0098	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	975316.00	LFT
0099	801-06204	TEMPORARY PAVEMENT MARKING, 5 IN.	2371.00	LFT
0100	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	172914.00	LFT
0101	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	66646.00	LFT
0102	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	10141.00	LFT
0103	801-06586	TEMPORARY PAVEMENT MARKING, 8 IN.	23928.00	LFT
0104	801-06625	DETOUR ROUTE MARKER ASSEMBLY	153.00	EACH
0105	801-06640	CONSTRUCTION SIGN, A	110.00	EACH

0106	801-06645	CONSTRUCTION SIGN, B	5.00 EACH
0107	801-06649	TEMPORARY RAISED PAVEMENT MARKER, GRADE 1	1107.00 EACH
0108	801-06710	FLASHING ARROW SIGN	215.00 DAY
0109	801-06775	MAINTAINING TRAFFIC	1.00 LS
0110	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	7.00 EACH
0111	801-07118	BARRICADE, III-A	340.00 LFT
0112	801-07119	BARRICADE, III-B	20.00 LFT
0113	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	25070.00 LFT
0114	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	20860.00 LFT
0115	801-08403	TEMPORARY TRAFFIC BARRIER, TYPE 4	9598.00 LFT
0116	801-08507	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 1	290.00 LFT
0117	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	2440.00 LFT
0118	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	22.00 EACH
0119	801-12503	TEMPORARY TRAFFIC BARRIER, RELOCATE	206094.00 LFT
0120	801-12544	AUTOMATED WORK ZONE INFORMATION SYSTEM	3.00 EACH
0121	801-12544	AUTOMATED WORK ZONE INFORMATION SYSTEM	2.00 EACH
0122	801-12652	QUEUE TRUCK	30.00 DAY
0123	801-52817	TEMPORARY Crossover, B	3.00 EACH
0124	801-97643	TEMPORARY BUZZ STRIPS	2016.00 LFT
0125	802-04893	REFERENCE POST	4.00 EACH
0126	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	50.00 LFT
0127	808-06716	LINE, REMOVE	1270396.00 LFT
0128	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0129	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	186836.00 LFT
0130	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	198252.00 LFT
0131	808-10037	LINE, MULTI-COMPONENT, SOLID, WHITE, 8 IN.	50594.00 LFT
0132	808-10043	LINE, MULTI-COMPONENT, SOLID, WHITE, 24 IN.	2950.00 LFT
0133	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	92057.00 LFT
0134	808-11484	LINE, MULTI-COMPONENT, DOTTED, WHITE, 5 IN.	27562.00 LFT
0135	808-12032	GROOVING FOR PAVEMENT MARKINGS	543251.00 LFT
0136	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2986.00 EACH
0137	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2968.00 EACH

Call: 241
Contract: R -42491-B
Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED

Line			Quantity Unit	
Item No	Item Code	Description		
0138	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	4360.00	SYS

Call: 241
Contract: R -42491-B
Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Line			Quantity Unit	
Item No	Item Code	Description		
0139	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	4360.00	SYS

Call: 251

Contract: R -42616-A

Section No.: 1 NEW INTERCHANGE CONSTRUCTION

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	105-11823	CONSTRUCTION ENGINEERING GPS ROVER	1.00	LS
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0010	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0011	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0012	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0013	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0014	113-01614	PARTNERING OVERHEAD	1.00	LS
0015	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0016	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00	LS
0017	202-01000	STRUCTURES AND OBSTRUCTIONS, REMOVE	1.00	LS
0018	202-02273	CENTER CURB, CONCRETE, REMOVE	81.00	SYS
0019	202-02278	CURB, CONCRETE, REMOVE	278.00	LFT
0020	202-02279	CURB AND GUTTER, REMOVE	946.00	LFT
0021	202-06542	RELOCATE	1.00	EACH
0022	202-06542	RELOCATE	1.00	EACH
0023	202-06542	RELOCATE	1.00	EACH
0024	202-07003	REMOVE	1.00	LS
0025	202-52710	SIDEWALK CONCRETE, REMOVE	114.00	SYS
0026	202-91385	INLET, REMOVE	4.00	EACH
0027	202-93047	MANHOLE, REMOVE	6.00	EACH
0028	202-93741	GUARDRAIL, END TREATMENT, REMOVE	2.00	EACH
0029	202-94810	CURB TURNOUT, REMOVE	2.00	EACH
0030	202-96133	PIPE, REMOVE	1745.00	LFT
0031	202-96531	FENCE RIGHT-OF-WAY, REMOVE	3146.00	LFT

0032	202-99187	FENCE, FARM FIELD, REMOVE	65.00	LFT
0033	203-02000	EXCAVATION, COMMON	186155.00	CYS
0034	203-02070	BORROW	10565.00	CYS
0035	205-11626	PUMP AROUND	1.00	EACH
0036	205-12108	STORMWATER MANAGEMENT BUDGET	76090.00	DOL
0037	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0038	205-12618	SWQCP PREPARATION	1.00	LS
0039	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	219.00	CYS
0040	207-08264	SUBGRADE TREATMENT, TYPE II	555.00	SYS
0041	207-08266	SUBGRADE TREATMENT, TYPE III	1305.00	SYS
0042	207-09935	SUBGRADE TREATMENT, TYPE IC	6073.00	SYS
0043	207-12635	SUBGRADE TREATMENT, TYPE IBC	62677.00	SYS
0044	208-02046	GRADING IN GORE AREA	6.00	EACH
0045	211-02050	B BORROW	15538.00	CYS
0046	211-09264	STRUCTURE BACKFILL, TYPE 1	15645.00	CYS
0047	211-09266	STRUCTURE BACKFILL, TYPE 3	21625.00	CYS
0048	214-11796	GEOGRID, TYPE IB	3615.00	SYS
0049	214-12237	GEOTEXTILE FOR PAVEMENT, TYPE 1B	49195.00	SYS
0050	214-12238	GEOTEXTILE FOR PAVEMENT TYPE 2A	42685.00	SYS
0051	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	270.00	SYS
0052	215-12637	CHEMICAL MODIFICATION, SOILS, CEMENT	5850.00	SYS
0053	301-12232	COMPACTED AGGREGATE NO. 5	9710.00	CYS
0054	301-12234	COMPACTED AGGREGATE NO. 53	5747.00	CYS
0055	301-12234	COMPACTED AGGREGATE NO. 53	3205.00	CYS
0056	302-06464	SUBBASE FOR PCCP	68.00	CYS
0057	302-07455	DENSE GRADED SUBBASE	93.00	CYS
0058	303-01180	COMPACTED AGGREGATE NO. 53	1537.00	TON
0059	304-12627	HMA PATCHING FULL DEPTH, TYPE D	917.00	TON
0060	401-06264	PROFILOGRAPH, HMA	1.00	LS
0061	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	3963.00	TON
0062	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	1566.00	TON
0063	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1959.00	TON
0064	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	4933.00	TON
0065	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	4608.00	TON
0066	401-08364	QC/QA-HMA, 4, 64, BASE, 19.0 mm	11349.00	TON
0067	401-10258	JOINT ADHESIVE, SURFACE	31943.00	LFT
0068	401-10259	JOINT ADHESIVE, INTERMEDIATE	31943.00	LFT

0069	401-11785	LIQUID ASPHALT SEALANT	31943.00	LFT
0070	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	8476.00	TON
0071	402-07452	HMA WEDGE AND LEVEL, TYPE C	35.00	TON
0072	402-10086	HMA FOR TEMPORARY PAVEMENT, TYPE C	6130.00	TON
0073	406-05520	ASPHALT FOR TACK COAT	58.00	TON
0074	502-11564	PCCP, 7 IN.	730.00	SYS
0075	503-05240	D-1 CONTRACTION JOINT	1529.00	LFT
0076	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH
0077	601-09149	IMPACT ATTENUATOR, CR1-W1, TL-3	2.00	EACH
0078	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	944.00	LFT
0079	601-12282	GUARDRAIL, MGS W-BEAM, 3 FT 1.5 IN. SPACING	113.00	LFT
0080	601-12284	GUARDRAIL, MGS W-BEAM, DOUBLE FACED 6 FT 3 IN. SPACING	3863.00	LFT
0081	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	4.00	EACH
0082	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0083	602-01064	CONCRETE BARRIER	2470.00	LFT
0084	602-01064	CONCRETE BARRIER	501.00	LFT
0085	602-11938	CONCRETE BARRIER, MODIFIED SECTION	138.00	CYS
0086	604-05528	HMA FOR SIDEWALK	235.00	TON
0087	604-06070	SIDEWALK, CONCRETE	28.00	SYS
0088	604-08086	CURB RAMP, CONCRETE	590.00	SYS
0089	604-12083	DETECTABLE WARNING SURFACES	63.00	SYS
0090	605-06090	CURB, INTEGRAL CONCRETE	738.00	LFT
0091	605-06120	CURB, CONCRETE	1699.00	LFT
0092	605-06125	CURB, CONCRETE, MODIFIED	198.00	LFT
0093	605-06140	CURB AND GUTTER, CONCRETE	4193.00	LFT
0094	605-06145	CURB AND GUTTER, B, CONCRETE	1298.00	LFT
0095	605-06160	CURB AND GUTTER, B, CONCRETE, MODIFIED	8100.00	LFT
0096	605-06255	CENTER CURB, D CONCRETE	147.00	SYS
0097	605-97937	CURB AND GUTTER, ROLL CURB	465.00	LFT
0098	605-97937	CURB AND GUTTER, ROLL CURB	138.00	LFT
0099	606-11064	MILLED PCCP CORRUGATIONS, CONVENTIONAL	1602.00	LFT
0100	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	5432.00	LFT
0101	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	276.00	SYS
0102	610-07487	HMA FOR APPROACHES, TYPE B	515.00	TON
0103	610-07488	HMA FOR APPROACHES, TYPE C	1250.00	TON
0104	610-09108	PCCP FOR APPROACHES, 9 IN.	555.00	SYS
0105	615-06490	RIGHT-OF-WAY MARKER	48.00	EACH

0106	615-06505	MONUMENT, B	27.00	EACH
0107	615-06510	MONUMENT, C	17.00	EACH
0108	615-06515	MONUMENT, D	3.00	EACH
0109	616-06405	RIPRAP, REVETMENT	56.00	TON
0110	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	67.00	SYS
0111	619-04981	CLEAN AND PAINT	1.00	LS
0112	620-01754	SOUND BARRIER PANELS GROUND MOUNTED TYPE	26244.00	SFT
0113	620-01756	SOUND BARRIER ERECTION GROUND MOUNTED TYPE	26244.00	SFT
0114	620-08426	SOUND BARRIER DESIGN AND LAYOUT	1.00	LS
0115	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.00	EACH
0116	621-06545	FERTILIZER	3.00	TON
0117	621-06554	SEED MIXTURE, U	1262.00	LBS
0118	621-06565	MULCHING MATERIAL	14.00	TON
0119	621-06567	WATER	76.00	KGAL
0120	621-06570	TOPSOIL	835.00	CYS
0121	621-06574	SODDING	3569.00	SYS
0122	621-06575	SODDING, NURSERY	11909.00	SYS
0123	628-12684	FIELD OFFICE, E	24.00	MOS
0124	701-06011	DYNAMIC PILE LOAD TEST	3.00	EACH
0125	701-09557	TEST PILE, DYNAMIC, PRODUCTION	265.00	LFT
0126	701-09559	TEST PILE, DYNAMIC, RESTRIKE	3.00	EACH
0127	701-09683	PILE SHOE, HP 12 X 74	62.00	EACH
0128	701-95780	PILE, STEEL H, HP 12 X 74	4269.00	LFT
0129	702-04325	TEMPORARY SHORING	1.00	LS
0130	702-51005	CONCRETE, A, SUBSTRUCTURE	251.60	CYS
0131	702-51015	CONCRETE, B, FOOTINGS	110.40	CYS
0132	702-92857	CONCRETE, C, SUBSTRUCTURE	104.80	CYS
0133	703-06028	REINFORCING BARS	31607.00	LBS
0134	703-06029	REINFORCING BARS, EPOXY COATED	281423.00	LBS
0135	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	40.00	EACH
0136	704-51002	CONCRETE, C, SUPERSTRUCTURE	792.20	CYS
0137	706-09789	REINFORCED CONCRETE MOMENT SLAB, 20 IN.	1816.00	SYS
0138	706-09960	RAILING, CONCRETE FC	2144.00	LFT
0139	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0140	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	1.00	EACH
0141	706-51025	RAILING, CONCRETE C	221.00	LFT
0142	706-94133	RAILING, TUBE, GALVANIZED STEEL	186.00	LFT

0143	707-09865	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 49 IN.	1358.00	LFT
0144	709-51821	SURFACE SEAL	1.00	LS
0145	715-04612	PIPE	2171.00	LFT
0146	715-04985	VAULT	1.00	EACH
0147	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	170.00	LFT
0148	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	19383.00	LFT
0149	715-05049	PIPE, TYPE 4, CIRCULAR, 8 IN.	7140.00	LFT
0150	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	1496.00	LFT
0151	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	2761.00	LFT
0152	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	1557.00	LFT
0153	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	3216.00	LFT
0154	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	492.00	LFT
0155	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	83.00	LFT
0156	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	1177.00	LFT
0157	715-09064	VIDEO INSPECTION FOR PIPE	9456.00	LFT
0158	715-46040	PIPE END SECTION, DIAMETER 36 IN.	2.00	EACH
0159	716-07637	PIPE INSTALLATION, TRENCHLESS, 48 IN.	948.00	LFT
0160	718-06528	OUTLET PROTECTOR, 1	2.00	EACH
0161	718-06531	OUTLET PROTECTOR, 3	8.00	EACH
0162	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3000.00	LFT
0163	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	23768.00	SYS
0164	718-52610	AGGREGATE FOR UNDERDRAINS	2137.00	CYS
0165	720-01092	MANHOLE, J15 MODIFIED	7.00	EACH
0166	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	11.00	EACH
0167	720-45030	INLET, E7	1.00	EACH
0168	720-45042	INLET, HA5	26.00	EACH
0169	720-45075	INLET, R13	1.00	EACH
0170	720-45410	MANHOLE, C4	49.00	EACH
0171	720-45415	MANHOLE, D4	2.00	EACH
0172	720-45605	STRUCTURE, MANHOLE, RECONSTRUCTED	3.00	LFT
0173	720-93501	MANHOLE, L4	2.00	EACH
0174	720-94612	MANHOLE, K4	6.00	EACH
0175	720-95422	MANHOLE, J4	15.00	EACH
0176	720-98174	INLET, B15	2.00	EACH
0177	720-99416	CATCH BASIN, B15	29.00	EACH
0178	720-99417	CATCH BASIN, C15	1.00	EACH
0179	731-93945	FACE PANELS, CONCRETE	36671.00	SFT

0180	731-93946	WALL ERECTION	36671.00	SFT
0181	731-93947	LEVELING PAD, CONCRETE	2462.00	LFT
0182	732-11770	AGGREGATE FOR DRAINAGE FILL	534.00	CYS
0183	735-10241	TEMPORARY WIRE FACING	1834.00	SFT
0184	735-10242	TEMPORARY WALL ERECTION	1834.00	SFT
0185	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	12.00	EACH
0186	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0187	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	60325.00	LFT
0188	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	13.00	EACH
0189	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	75.00	LFT
0190	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	11831.00	LFT
0191	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00	LS
0192	801-06625	DETOUR ROUTE MARKER ASSEMBLY	22.00	EACH
0193	801-06640	CONSTRUCTION SIGN, A	24.00	EACH
0194	801-06645	CONSTRUCTION SIGN, B	15.00	EACH
0195	801-06775	MAINTAINING TRAFFIC	1.00	LS
0196	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	16.00	EACH
0197	801-07118	BARRICADE, III-A	450.00	LFT
0198	801-07119	BARRICADE, III-B	24.00	LFT
0199	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	3780.00	LFT
0200	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	5990.00	LFT
0201	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1350.00	LFT
0202	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0203	801-11990	TEMPORARY CURB RAMP	1.00	EACH
0204	801-12042	TRUCK MOUNTED ATTENUATOR	60.00	DAY
0205	801-12081	PORTABLE SIGNAL	1.00	LS
0206	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0207	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	26.00	SYS
0208	801-52817	TEMPORARY CROSSOVER, B	2.00	EACH
0209	802-04089	SIGN, SHEET, REMOVE	14.00	EACH
0210	802-04893	REFERENCE POST	10.00	EACH
0211	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	722.00	LFT
0212	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	127.00	LFT
0213	802-05703	SIGN POST, SQUARE, TYPE 3, REINFORCED ANCHOR BASE	77.00	LFT
0214	802-07057	SIGN, PANEL, WITH LEGEND	436.00	SFT
0215	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	27.00	EACH
0216	802-07060	SIGN, SHEET, RELOCATE	4.00	EACH

0217	802-09578	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	2.00 EACH
0218	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	173.00 SFT
0219	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	456.00 SFT
0220	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	94.00 SFT
0221	802-11843	RADAR SPEED DISPLAY SIGN ASSEMBLY	4.00 EACH
0222	802-11886	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 48 IN.	2.00 EACH
0223	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	14.00 EACH
0224	802-76095	STRUCTURAL STEEL, BREAKAWAY	1468.00 LBS
0225	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	1.00 EACH
0226	805-02087	TRANSPORTATION OF SALVAGEABLE SIGNAL EQUIPMENT	1.00 LS
0227	805-02728	CONDUIT, PVC, 1 IN.	112.00 LFT
0228	805-04973	CONDUIT	30.00 LFT
0229	805-04973	CONDUIT	2760.00 LFT
0230	805-04973	CONDUIT	350.00 LFT
0231	805-04973	CONDUIT	365.00 LFT
0232	805-04973	CONDUIT	440.00 LFT
0233	805-04973	CONDUIT	105.00 LFT
0234	805-04973	CONDUIT	8120.00 LFT
0235	805-04973	CONDUIT	4000.00 LFT
0236	805-06595	CONDUIT, PVC, 2 IN.	427.00 LFT
0237	805-09845	CONTACT CLOSURE CARD	1.00 EACH
0238	805-09846	RECEIVER PROCESSOR	2.00 EACH
0239	805-10107	WIRELESS MAGNETOMETER DETECTOR	8.00 EACH
0240	805-10108	WIRELESS REPEATER	1.00 EACH
0241	805-11842	CONDUIT, HDPE, 3 IN. SCHEDULE 40	1150.00 LFT
0242	807-02191	HANDHOLE, LIGHTING	9.00 EACH
0243	807-02194	SERVICE POINT, II, MODIFIED	3.00 EACH
0244	807-02426	WIRE, THW, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	1624.00 LFT
0245	807-03950	LUMINAIRE ORNAMENTAL	33.00 EACH
0246	807-03950	LUMINAIRE ORNAMENTAL	24.00 EACH
0247	807-03951	LIGHT POLE ORNAMENTAL	2.00 EACH
0248	807-03951	LIGHT POLE ORNAMENTAL	26.00 EACH
0249	807-03951	LIGHT POLE ORNAMENTAL	5.00 EACH
0250	807-04651	WIRE	35.00 LFT
0251	807-04651	WIRE	35.00 LFT
0252	807-04653	LIGHTING FOUNDATION	33.00 EACH
0253	807-05073	JUNCTION BOX	10.00 EACH

0254	807-05073	JUNCTION BOX	4.00 EACH
0255	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	761.00 LFT
0256	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	6837.00 LFT
0257	807-12206	LUMINAIRE, UNDERPASS	4.00 EACH
0258	807-78590	HANDHOLE	5.00 EACH
0259	807-82054	CIRCUIT INSTALLATION, UNDERPASS, 4 LUMINAIRES	1.00 EACH
0260	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	3034.00 LFT
0261	807-86910	CONNECTOR KIT, UNFUSED	33.00 EACH
0262	807-86915	CONNECTOR KIT, FUSED	33.00 EACH
0263	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	66.00 EACH
0264	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	48.00 EACH
0265	807-86930	INSULATION LINK, NON-WATERPROOFED	66.00 EACH
0266	807-86935	INSULATION LINK, WATERPROOFED	52.00 EACH
0267	807-86950	SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION IDENTIFICATION	37.00 EACH
0268	807-86955	CABLE DUCT MARKER	9.00 EACH
0269	807-86955	CABLE DUCT MARKER	4.00 EACH
0270	807-86955	CABLE DUCT MARKER	7.00 EACH
0271	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	392.00 LFT
0272	808-06701	LINE, THERMOPLASTIC, BROKEN, WHITE, 4 IN.	159.00 LFT
0273	808-06702	LINE, THERMOPLASTIC, BROKEN, WHITE, 5 IN.	3112.00 LFT
0274	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	3111.00 LFT
0275	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	5708.00 LFT
0276	808-06716	LINE, REMOVE	13326.00 LFT
0277	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0278	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	360.00 LFT
0279	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	2.00 EACH
0280	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	117.00 LFT
0281	808-11485	LINE, THERMOPLASTIC, DOTTED, WHITE, 5 IN.	641.00 LFT
0282	808-11698	TRANSVERSE MARKING, THERMOPLASTIC, YIELD LINE, WHITE, 27 IN.	118.00 LFT
0283	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	12318.00 LFT
0284	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	14970.00 LFT
0285	808-75272	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, WHITE, 24 IN.	298.00 LFT
0286	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	103.00 LFT
0287	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	544.00 LFT
0288	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	18.00 EACH
0289	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	151.00 EACH
0290	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	443.00 EACH

0291	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	990.00	LFT
0292	809-04969	SPLICE	152.00	EACH
0293	809-04970	FIBER OPTIC	4.00	EACH
0294	809-04970	FIBER OPTIC	4.00	EACH
0295	809-04982	CABLE	300.00	LFT
0296	809-11707	ITS FIELD SWITCH	2.00	EACH
0297	809-94971	FIBER OPTIC CABLE	350.00	LFT
0298	809-94971	FIBER OPTIC CABLE	8490.00	LFT
0299	809-94971	FIBER OPTIC CABLE	24.00	LFT

Call: 261

Contract: R -43120-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-02273	CENTER CURB, CONCRETE, REMOVE	13.00 SYS
0013	202-74035	SIGN, REMOVE	2.00 EACH
0014	202-91840	FENCE, CHAIN LINK, REMOVE	30.00 LFT
0015	203-02000	EXCAVATION, COMMON	601.00 CYS
0016	203-02070	BORROW	293.00 CYS
0017	205-12108	STORMWATER MANAGEMENT BUDGET	4500.00 DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0019	205-12618	SWQCP PREPARATION	1.00 LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	991.00 SYS
0021	207-08266	SUBGRADE TREATMENT, TYPE III	1383.00 SYS
0022	211-09265	STRUCTURE BACKFILL, TYPE 2	56.00 CYS
0023	214-11796	GEOGRID, TYPE IB	490.00 SYS
0024	302-07455	DENSE GRADED SUBBASE	170.00 CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	516.00 TON
0026	303-07449	COMPACTED AGGREGATE NO. 73	7.00 TON
0027	304-12623	HMA PATCHING FULL DEPTH, TYPE B	115.00 TON
0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	306.00 SYS
0029	402-10084	HMA FOR TEMPORARY PAVEMENT, TYPE B	14.00 TON
0030	603-06045	FENCE, CHAIN LINK, 48 IN.	30.00 LFT
0031	603-97461	TEMPORARY FENCE	550.00 LFT

0032	604-05528	HMA FOR SIDEWALK	170.00	TON
0033	604-06070	SIDEWALK, CONCRETE	2125.00	SYS
0034	604-06070	SIDEWALK, CONCRETE	128.00	SYS
0035	604-08086	CURB RAMP, CONCRETE	109.00	SYS
0036	604-12083	DETECTABLE WARNING SURFACES	30.00	SYS
0037	604-92237	HAND RAIL, STEEL	128.00	LFT
0038	605-06120	CURB, CONCRETE	136.00	LFT
0039	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	354.00	LFT
0040	605-06235	CENTER CURB, D CONCRETE, MODIFIED	5.00	LFT
0041	605-92578	CURB, WALK CONCRETE	198.00	SYS
0042	605-97937	CURB AND GUTTER, ROLL CURB	23.00	LFT
0043	610-07487	HMA FOR APPROACHES, TYPE B	30.00	TON
0044	610-08446	PCCP FOR APPROACHES, 6 IN.	491.00	SYS
0045	610-09108	PCCP FOR APPROACHES, 9 IN.	490.00	SYS
0046	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	7.00	EACH
0047	616-03096	RIVER ROCK	19.00	TON
0048	616-06405	RIPRAP, REVETMENT	13.00	TON
0049	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	13.00	SYS
0050	621-06560	MULCHED SEEDING U	2924.00	SYS
0051	621-06570	TOPSOIL	171.00	CYS
0052	715-04596	WATER SERVICE	5.00	EACH
0053	715-05147	PIPE, TYPE 2, CIRCULAR, 8 IN.	136.00	LFT
0054	715-05148	PIPE, TYPE 2, CIRCULAR, 10 IN.	96.00	LFT
0055	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	5.00	LFT
0056	715-05276	PIPE, TYPE 1, DEFORMED, MIN. AREA 40.9 SFT	10.00	LFT
0057	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00	EACH
0058	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	5.00	EACH
0059	720-12797	CASTING, INLET, ADJUST TO GRADE	5.00	EACH
0060	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	2.00	EACH
0061	720-45270	PIPE CATCH BASIN, 18 IN.	2.00	EACH
0062	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	3.00	EACH
0063	720-97008	FIRE HYDRANT ASSEMBLY RELOCATE	1.00	EACH
0064	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	118.00	LFT
0065	801-06640	CONSTRUCTION SIGN, A	58.00	EACH
0066	801-06645	CONSTRUCTION SIGN, B	22.00	EACH
0067	801-06775	MAINTAINING TRAFFIC	1.00	LS
0068	801-07119	BARRICADE, III-B	112.00	LFT

0069	801-08403	TEMPORARY TRAFFIC BARRIER, TYPE 4	680.00	LFT
0070	801-11990	TEMPORARY CURB RAMP	1.00	EACH
0071	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	24.00	LFT
0072	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	5.00	EACH
0073	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	22.00	SFT
0074	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	176.00	LFT
0075	808-10074	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 8 IN.	435.00	LFT
0076	808-12753	TRANSVERSE MARKING, MULTI-COMPONENT, PARKING LINE, WHITE 4 IN.	190.00	LFT

Call: 271

Contract: R -43212-A

Section No.: 1 DRAINAGE DITCH CORRECTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-91385	INLET, REMOVE	1.00 EACH
0013	202-96133	PIPE, REMOVE	189.00 LFT
0014	203-02000	EXCAVATION, COMMON	5207.00 CYS
0015	205-11626	PUMP AROUND	2.00 EACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	21085.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	205-12618	SWQCP PREPARATION	1.00 LS
0019	207-08266	SUBGRADE TREATMENT, TYPE III	475.00 SYS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	447.00 SYS
0021	211-09265	STRUCTURE BACKFILL, TYPE 2	126.00 CYS
0022	211-09268	STRUCTURE BACKFILL, TYPE 5	118.00 CYS
0023	301-12233	COMPACTED AGGREGATE NO. 8	94.00 CYS
0024	301-12234	COMPACTED AGGREGATE NO. 53	153.00 CYS
0025	302-06464	SUBBASE FOR PCCP	110.00 CYS
0026	304-12625	HMA PATCHING FULL DEPTH, TYPE C	128.00 TON
0027	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1721.00 SYS
0028	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	150.00 TON
0029	401-10258	JOINT ADHESIVE, SURFACE	2241.00 LFT
0030	401-11785	LIQUID ASPHALT SEALANT	2241.00 LFT
0031	402-10086	HMA FOR TEMPORARY PAVEMENT, TYPE C	180.00 TON

0032	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0033	506-06333	PCCP PATCHING, FULL DEPTH	160.00	SYS
0034	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	2241.00	LFT
0035	616-05688	RIPRAP, CLASS 1	175.00	TON
0036	616-06405	RIPRAP, REVETMENT	235.00	TON
0037	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	356.00	SYS
0038	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	731.00	SYS
0039	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	21.00	SYS
0040	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	7.00	EACH
0041	621-06545	FERTILIZER	1.00	TON
0042	621-06554	SEED MIXTURE, U	326.00	LBS
0043	621-06559	MULCHED SEEDING R	5847.00	SYS
0044	621-06565	MULCHING MATERIAL	4.00	TON
0045	621-06574	SODDING	1993.00	SYS
0046	621-12612	SEED MIXTURE, FLOODPLAIN	29.00	LBS
0047	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0048	628-12683	FIELD OFFICE, D	13.00	MOS
0049	702-04325	TEMPORARY SHORING	1.00	LS
0050	702-51005	CONCRETE, A, SUBSTRUCTURE	6.00	CYS
0051	714-12499	STRUCTURE, COATED REINFORCED CONCRETE, BOX SECTIONS, 5 FT X 3 FT	192.00	LFT
0052	715-05019	PIPE, TYPE 1, CIRCULAR, 36 IN.	41.00	LFT
0053	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	83.00	LFT
0054	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	7.00	LFT
0055	715-05173	PIPE, TYPE 3, CIRCULAR, 24 IN.	61.00	LFT
0056	715-05177	PIPE, TYPE 3, CIRCULAR, 36 IN.	49.00	LFT
0057	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	19.00	TON
0058	715-12059	PIPE, TYPE 3, DEFORMED, MIN. AREA 8.8 SFT	29.00	LFT
0059	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0060	715-46020	PIPE END SECTION, DIAMETER 24 IN.	2.00	EACH
0061	715-46040	PIPE END SECTION, DIAMETER 36 IN.	4.00	EACH
0062	716-07631	PIPE INSTALLATION, TRENCHLESS, 15 IN.	76.00	LFT
0063	716-07633	PIPE INSTALLATION, TRENCHLESS, 24 IN.	186.00	LFT
0064	718-06529	OUTLET PROTECTOR, 2	4.00	EACH
0065	720-02442	PIPE PLUG EXISTING	2.00	EACH
0066	720-45065	INLET, N12	1.00	EACH
0067	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0068	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9740.00	LFT

0069	801-06625	DETOUR ROUTE MARKER ASSEMBLY	9.00 EACH
0070	801-06640	CONSTRUCTION SIGN, A	64.00 EACH
0071	801-06645	CONSTRUCTION SIGN, B	18.00 EACH
0072	801-06710	FLASHING ARROW SIGN	105.00 DAY
0073	801-06775	MAINTAINING TRAFFIC	1.00 LS
0074	801-07118	BARRICADE, III-A	72.00 LFT
0075	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1536.00 LFT
0076	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	80.00 LFT
0077	802-91122	SIGN GROUND MOUNTED RESET	1.00 EACH
0078	804-11920	DELINEATOR POST FLEXIBLE, TYPE I	5.00 EACH
0079	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	425.00 LFT
0080	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1215.00 LFT
0081	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1264.00 LFT
0082	808-06716	LINE, REMOVE	2904.00 LFT
0083	808-12032	GROOVING FOR PAVEMENT MARKINGS	2904.00 LFT

Call: 281

Contract: R -43598-A

Section No.: 1 ADDED TRAVEL LANES, CONSTRUCT TURN LANES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	105-09645	CONSTRUCTION ENGINEERING AND INSPECTION UTILITY RELOCATION	1.00	LS
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-02240	PAVEMENT REMOVAL	382.00	SYS
0014	203-02000	EXCAVATION, COMMON	4086.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	10000.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	206-51215	EXCAVATION, X	101.00	CYS
0019	207-08264	SUBGRADE TREATMENT, TYPE II	652.00	SYS
0020	207-09935	SUBGRADE TREATMENT, TYPE IC	6.50	SYS
0021	207-12635	SUBGRADE TREATMENT, TYPE IBC	5132.00	SYS
0022	211-09266	STRUCTURE BACKFILL, TYPE 3	78.60	CYS
0023	214-12238	GEOTEXTILE FOR PAVEMENT TYPE 2A	3002.00	SYS
0024	301-12232	COMPACTED AGGREGATE NO. 5	436.00	CYS
0025	301-12234	COMPACTED AGGREGATE NO. 53	1805.00	CYS
0026	302-07455	DENSE GRADED SUBBASE	18.00	CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	380.00	TON
0028	304-12623	HMA PATCHING FULL DEPTH, TYPE B	2.50	TON
0029	306-11872	MILLING, PROFILE	5108.00	SYS
0030	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	769.00	TON
0031	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	1888.00	TON

0032	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	3890.00	TON
0033	401-10258	JOINT ADHESIVE, SURFACE	6730.00	LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	13460.00	LFT
0035	401-11785	LIQUID ASPHALT SEALANT	6730.00	LFT
0036	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	536.00	TON
0037	406-05520	ASPHALT FOR TACK COAT	7.00	TON
0038	605-06121	CURB, CONCRETE B	217.00	LFT
0039	605-97937	CURB AND GUTTER, ROLL CURB	493.00	LFT
0040	607-06175	GUTTER, CONCRETE, A	462.00	LFT
0041	610-07487	HMA FOR APPROACHES, TYPE B	121.00	TON
0042	610-08446	PCCP FOR APPROACHES, 6 IN.	107.00	SYS
0043	611-06497	MAILBOX ASSEMBLY, SINGLE	9.00	EACH
0044	611-06498	MAILBOX ASSEMBLY, DOUBLE	1.00	EACH
0045	615-06500	MONUMENT, A	6.00	EACH
0046	615-06505	MONUMENT, B	2.00	EACH
0047	615-06510	MONUMENT, C	1.00	EACH
0048	616-05688	RIPRAP, CLASS 1	20.00	TON
0049	616-06405	RIPRAP, REVETMENT	12.00	TON
0050	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	70.50	SYS
0051	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0052	621-02770	EROSION CONTROL BLANKET	330.00	SYS
0053	621-06559	MULCHED SEEDING R	3196.00	SYS
0054	621-06574	SODDING	190.80	SYS
0055	715-02629	SAFETY METAL END SECTION, 6:1, DIAMETER 18 IN.	7.00	EACH
0056	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	2796.00	LFT
0057	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	92.00	LFT
0058	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	202.00	LFT
0059	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	88.00	LFT
0060	715-05171	PIPE, TYPE 3, CIRCULAR, 18 IN.	121.00	LFT
0061	718-06528	OUTLET PROTECTOR, 1	2.00	EACH
0062	718-06531	OUTLET PROTECTOR, 3	5.00	EACH
0063	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	1827.00	SYS
0064	718-52610	AGGREGATE FOR UNDERDRAINS	261.00	CYS
0065	720-12797	CASTING, INLET, ADJUST TO GRADE	2.00	EACH
0066	720-45055	INLET, M10	5.00	EACH
0067	720-45085	INLET, T14	1.00	EACH
0068	720-45615	STRUCTURE, INLET, RECONSTRUCTED	1.00	LFT

0069	720-98555	INLET, C15	2.00 EACH
0070	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00 EACH
0071	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	1.00 EACH
0072	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00 EACH
0073	801-04746	ENERGY ABSORBING TERMINAL, CZ, TL-	2.00 EACH
0074	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	10822.00 LFT
0075	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2676.00 LFT
0076	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	34.00 LFT
0077	801-06625	DETOUR ROUTE MARKER ASSEMBLY	12.00 EACH
0078	801-06640	CONSTRUCTION SIGN, A	15.00 EACH
0079	801-06645	CONSTRUCTION SIGN, B	2.00 EACH
0080	801-06775	MAINTAINING TRAFFIC	1.00 LS
0081	801-07119	BARRICADE, III-B	24.00 LFT
0082	801-08400	TEMPORARY TRAFFIC BARRIER, TYPE 1	1750.00 LFT
0083	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00 EACH
0084	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	95.00 LFT
0085	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	11.00 EACH
0086	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	91.00 SFT
0087	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	15.60 SFT
0088	802-09842	SIGN, SHEET, WITH LEGEND, 0.125 IN.	82.00 SFT
0089	802-91122	SIGN GROUND MOUNTED RESET	1.00 EACH
0090	804-06770	DELINEATOR POST	7.00 EACH
0091	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00 EACH
0092	805-01842	HANDHOLE, SIGNAL, TYPE 1	8.00 EACH
0093	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	1488.00 LFT
0094	805-02445	CONTROLLER AND CABINET, P1	1.00 EACH
0095	805-08244	CELLULAR MODEM KIT	1.00 EACH
0096	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	8.00 EACH
0097	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	2.00 EACH
0098	805-78415	SPAN, CATENARY, AND TETHER	4.00 EACH
0099	805-78420	DISCONNECT HANGER	4.00 EACH
0100	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	37.00 LFT
0101	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	4840.00 LFT
0102	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	244.00 LFT
0103	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	64.00 LFT
0104	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	787.00 LFT
0105	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	3804.00 LFT

0106	805-78785	SIGNAL DETECTOR HOUSING	11.00 EACH
0107	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1580.00 LFT
0108	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00 EACH
0109	805-81032	SIGNAL POLE, STEEL STRAIN, 30 FT	1.00 EACH
0110	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	3.00 EACH
0111	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	4439.00 LFT
0112	808-06716	LINE, REMOVE	9456.00 LFT
0113	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0114	808-11482	LINE, THERMOPLASTIC, DOTTED, WHITE, 4 IN.	277.00 LFT
0115	808-12032	GROOVING FOR PAVEMENT MARKINGS	8105.00 LFT
0116	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2287.00 LFT
0117	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	138.00 LFT
0118	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	102.00 LFT
0119	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	10.00 EACH
0120	808-75994	PRISMATIC REFLECTOR	63.00 EACH
0121	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	35.00 EACH
0122	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	63.00 EACH
0123	808-92027	LINE, THERMOPLASTIC, SOLID, YELLOW, 8 IN.	1102.00 LFT

Call: 291

Contract: R -44036-A

Section No.: 1 INSTITUTION AND PARK ROAD MAINTENANCE

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	207-12151	SUBGRADE TREATMENT, TYPE IVA	294.00	SYS
0010	303-01180	COMPACTED AGGREGATE NO. 53	267.00	TON
0011	304-12623	HMA PATCHING FULL DEPTH, TYPE B	65.00	TON
0012	306-08036	MILLING, ASPHALT, 2 IN.	92.00	SYS
0013	306-08043	MILLING, TRANSITION	356.00	SYS
0014	306-08432	MILLING, APPROACH	330.00	SYS
0015	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	683.00	TON
0016	401-10258	JOINT ADHESIVE, SURFACE	885.00	LFT
0017	401-11785	LIQUID ASPHALT SEALANT	885.00	LFT
0018	402-07451	HMA WEDGE AND LEVEL, TYPE B	203.00	TON
0019	404-11867	SEAL COAT, 3P	3094.00	SYS
0020	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0021	610-07487	HMA FOR APPROACHES, TYPE B	37.00	TON
0022	615-97768	PARKING BARRIER, RESET	10.00	EACH
0023	628-09409	MOBILE INTERNET SERVICE	6.00	MOS
0024	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0025	801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.00	EACH
0026	801-06640	CONSTRUCTION SIGN, A	2.00	EACH
0027	801-06775	MAINTAINING TRAFFIC	1.00	LS
0028	801-07119	BARRICADE, III-B	48.00	LFT

Call: 295

Contract: R -44070-B

Section No.: 1 PAVEMENT PATCHING

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	207-08268	SUBGRADE TREATMENT, TYPE IV	1529.00 SYS
0010	211-09264	STRUCTURE BACKFILL, TYPE 1	18.00 CYS
0011	214-12490	GEOTEXTILE FOR PAVEMENT, TYPE 3A	1216.00 SYS
0012	302-06464	SUBBASE FOR PCCP	383.00 CYS
0013	304-12627	HMA PATCHING FULL DEPTH, TYPE D	455.00 TON
0014	304-12628	HMA PATCHING PARTIAL DEPTH, TYPE D	1806.00 TON
0015	503-03489	RETROFITTED TIE BARS	148.00 EACH
0016	503-05240	D-1 CONTRACTION JOINT	552.00 LFT
0017	506-06333	PCCP PATCHING, FULL DEPTH	1216.00 SYS
0018	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	912.00 LFT
0019	621-06574	SODDING	36.00 SYS
0020	628-09409	MOBILE INTERNET SERVICE	6.00 MOS
0021	628-11729	CELLULAR TELEPHONE, TYPE A	1.00 EACH
0022	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0023	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0024	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	6.00 MOS
0025	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0026	628-11977	COMPUTER SYSTEM	1.00 EACH
0027	628-12683	FIELD OFFICE, D	6.00 MOS
0028	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	912.00 LFT
0029	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	161.00 LFT
0030	718-06529	OUTLET PROTECTOR, 2	9.00 EACH
0031	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	1073.00 LFT

0032	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	855.00	SYS
0033	718-52610	AGGREGATE FOR UNDERDRAINS	99.00	CYS
0034	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	30.00	EACH
0035	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	9044.00	LFT
0036	801-06640	CONSTRUCTION SIGN, A	58.00	EACH
0037	801-06710	FLASHING ARROW SIGN	160.00	DAY
0038	801-06775	MAINTAINING TRAFFIC	1.00	LS
0039	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	3.00	EACH
0040	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1560.00	LFT
0041	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	250.00	LFT
0042	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0043	801-12042	TRUCK MOUNTED ATTENUATOR	160.00	DAY
0044	801-12324	LAW ENFORCEMENT OFFICER	2088.00	HRS
0045	801-12652	QUEUE TRUCK	116.00	DAY
0046	801-12832	TEMPORARY SPEED FEEDBACK ASSEMBLY	2.00	EACH
0047	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0048	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	1223.00	LFT
0049	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	150.00	LFT
0050	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN	303.00	LFT
0051	808-12032	GROOVING FOR PAVEMENT MARKINGS	9046.00	LFT
0052	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	4883.00	LFT
0053	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	1364.00	LFT
0054	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	110.00	EACH
0055	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	110.00	EACH
0056	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	1123.00	LFT

Call: 301

Contract: R -44092-A

Section No.: 1 INSTITUTION AND PARK ROAD MAINTENANCE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	202-02240	PAVEMENT REMOVAL	533.00 SYS
0009	202-91385	INLET, REMOVE	2.00 EACH
0010	203-02000	EXCAVATION, COMMON	6845.00 CYS
0011	207-08264	SUBGRADE TREATMENT, TYPE II	12180.00 SYS
0012	213-09270	FLOWABLE BACKFILL, REMOVABLE	274.00 CYS
0013	303-01180	COMPACTED AGGREGATE NO. 53	7626.00 TON
0014	304-12623	HMA PATCHING FULL DEPTH, TYPE B	23.00 TON
0015	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1139.00 TON
0016	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	2994.00 TON
0017	401-10258	JOINT ADHESIVE, SURFACE	12000.00 LFT
0018	401-11785	LIQUID ASPHALT SEALANT	12000.00 LFT
0019	406-05520	ASPHALT FOR TACK COAT	78.00 TON
0020	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	250.00 LFT
0021	720-04499	INLET RECONSTRUCT	2.00 EACH
0022	720-45075	INLET, R13	2.00 EACH
0023	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	5200.00 LFT

Call: 311

Contract: R -44094-A

Section No.: 1 INSTITUTION AND PARK ROAD MAINTENANCE

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	207-08264	SUBGRADE TREATMENT, TYPE II	1208.00	SYS
0009	303-01180	COMPACTED AGGREGATE NO. 53	340.00	TON
0010	304-12623	HMA PATCHING FULL DEPTH, TYPE B	332.00	TON
0011	306-08033	MILLING, ASPHALT, 1 IN.	30211.00	SYS
0012	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2492.00	TON
0013	401-10258	JOINT ADHESIVE, SURFACE	23504.00	LFT
0014	401-11785	LIQUID ASPHALT SEALANT	23504.00	LFT
0015	406-05520	ASPHALT FOR TACK COAT	63.00	TON
0016	720-04499	INLET RECONSTRUCT	1.00	EACH
0017	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	510.00	LFT
0018	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	16230.00	LFT
0019	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2426.00	LFT
0020	808-75035	LINE, PAINT, SOLID, WHITE, 24 IN.	15.00	LFT

Call: 321

Contract: R -44117-A

Section No.: 1 INSTITUTION AND PARK ROAD MAINTENANCE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-02240	PAVEMENT REMOVAL	91.00 SYS
0012	202-02279	CURB AND GUTTER, REMOVE	94.00 LFT
0013	202-52710	SIDEWALK CONCRETE, REMOVE	86.00 SYS
0014	203-02000	EXCAVATION, COMMON	180.00 CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	42424.00 DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0017	207-08264	SUBGRADE TREATMENT, TYPE II	2930.00 SYS
0018	214-11796	GEOGRID, TYPE IB	262.00 SYS
0019	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	2284.00 SYS
0020	301-12234	COMPACTED AGGREGATE NO. 53	44.00 CYS
0021	302-07455	DENSE GRADED SUBBASE	48.00 CYS
0022	303-01180	COMPACTED AGGREGATE NO. 53	536.00 TON
0023	304-12623	HMA PATCHING FULL DEPTH, TYPE B	656.00 TON
0024	306-08036	MILLING, ASPHALT, 2 IN.	906.00 SYS
0025	306-08042	MILLING, SCARIFICATION	7889.00 SYS
0026	306-08043	MILLING, TRANSITION	731.00 SYS
0027	306-08432	MILLING, APPROACH	516.00 SYS
0028	306-11872	MILLING, PROFILE	5588.00 SYS
0029	307-12253	CORRECTIVE AGGREGATE, FDR	337.00 TON
0030	307-12254	FULL DEPTH RECLAMATION	5588.00 SYS
0031	307-12256	STABILIZING MATERIAL, PORTLAND CEMENT	113.00 TON

0032	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1670.00	TON
0033	401-10258	JOINT ADHESIVE, SURFACE	7470.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	7470.00	LFT
0035	406-05520	ASPHALT FOR TACK COAT	7.00	TON
0036	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.00	TON
0037	604-06070	SIDEWALK, CONCRETE	34.00	SYS
0038	604-08086	CURB RAMP, CONCRETE	52.00	SYS
0039	604-12083	DETECTABLE WARNING SURFACES	9.00	SYS
0040	605-06140	CURB AND GUTTER, CONCRETE	94.00	LFT
0041	610-07487	HMA FOR APPROACHES, TYPE B	207.00	TON
0042	610-08446	PCCP FOR APPROACHES, 6 IN.	284.00	SYS
0043	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0044	621-06560	MULCHED SEEDING U	3972.00	SYS
0045	628-09403	FIELD OFFICE, C	6.00	MOS
0046	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0047	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0048	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0049	628-11781	CELLULAR TELEPHONE SERVICE, 750 MIN.	6.00	MOS
0050	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0051	628-11977	COMPUTER SYSTEM	1.00	EACH
0052	628-12685	TELEPHONE SERVICE, A	6.00	MOS
0053	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	1.00	EACH
0054	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0055	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0056	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0057	801-06775	MAINTAINING TRAFFIC	1.00	LS
0058	801-07118	BARRICADE, III-A	68.00	LFT
0059	801-07119	BARRICADE, III-B	80.00	LFT

Call: 331

Contract: R -44118-A

Section No.: 1 INSTITUTION AND PARK ROAD MAINTENANCE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-02240	PAVEMENT REMOVAL	290.00 SYS
0012	202-02278	CURB, CONCRETE, REMOVE	21.00 LFT
0013	202-52710	SIDEWALK CONCRETE, REMOVE	11.00 SYS
0014	203-02000	EXCAVATION, COMMON	250.00 CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	3359.78 DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0017	207-08264	SUBGRADE TREATMENT, TYPE II	3940.00 SYS
0018	214-11796	GEOGRID, TYPE IB	3940.00 SYS
0019	303-01180	COMPACTED AGGREGATE NO. 53	330.00 TON
0020	304-12623	HMA PATCHING FULL DEPTH, TYPE B	1090.00 TON
0021	304-12624	HMA PATCHING PARTIAL DEPTH, TYPE B	70.00 TON
0022	306-08033	MILLING, ASPHALT, 1 IN.	13300.00 SYS
0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	17000.00 SYS
0024	306-08038	MILLING, ASPHALT, 4 IN.	27.00 SYS
0025	306-08043	MILLING, TRANSITION	1400.00 SYS
0026	306-08432	MILLING, APPROACH	1930.00 SYS
0027	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	2600.00 TON
0028	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	55.00 TON
0029	401-10258	JOINT ADHESIVE, SURFACE	10750.00 LFT
0030	401-11785	LIQUID ASPHALT SEALANT	10750.00 LFT
0031	406-05520	ASPHALT FOR TACK COAT	12.00 TON

0032	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	4.00	TON
0033	604-08086	CURB RAMP, CONCRETE	12.00	SYS
0034	604-12083	DETECTABLE WARNING SURFACES	2.00	SYS
0035	605-06120	CURB, CONCRETE	21.00	LFT
0036	610-07487	HMA FOR APPROACHES, TYPE B	160.00	TON
0037	621-06575	SODDING, NURSERY	5.00	SYS
0038	628-09403	FIELD OFFICE, C	6.00	MOS
0039	720-12797	CASTING, INLET, ADJUST TO GRADE	5.00	EACH
0040	720-45615	STRUCTURE, INLET, RECONSTRUCTED	1.00	LFT
0041	801-06640	CONSTRUCTION SIGN, A	16.00	EACH
0042	801-06775	MAINTAINING TRAFFIC	1.00	LS
0043	802-07058	SIGN, SHEET, ASSEMBLY RELOCATE	2.00	EACH
0044	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1380.00	LFT
0045	808-09314	LINE, PAINT, SOLID, BLUE, 4 IN.	330.00	LFT
0046	808-12316	TRANSVERSE MARKING, PAINT, PARKING LINE, WHITE, 4 IN.	1800.00	LFT
0047	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	58.00	LFT
0048	808-97222	PAVEMENT MESSAGE MARKING, PAINT, ADA ACCESSIBLE SYMBOL	4.00	EACH

Call: 341

Contract: R -44154-A

Section No.: 1 IDIQ, PAVEMENT PATCHING

Line			
Item No	Item Code	Description	Quantity Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0002	109-08360	CONTRACT LIENS	1.00 DOL
0003	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	225000.00 DOL
0009	201-02245	TREE 6 IN., REMOVE	50.00 EACH
0010	201-02250	TREE 10 IN., REMOVE	50.00 EACH
0011	201-02255	TREE 18 IN., REMOVE	25.00 EACH
0012	201-02260	TREE 30 IN., REMOVE	15.00 EACH
0013	201-02265	TREE 48 IN., REMOVE	5.00 EACH
0014	201-02270	TREE 60 IN., REMOVE	2.00 EACH
0015	203-08607	LINEAR GRADING	1000.00 LFT
0016	207-09935	SUBGRADE TREATMENT, TYPE IC	200.00 SYS
0017	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	200.00 SYS
0018	302-06464	SUBBASE FOR PCCP	50.00 CYS
0019	303-01180	COMPACTED AGGREGATE NO. 53	100.00 TON
0020	303-07449	COMPACTED AGGREGATE NO. 73	100.00 TON
0021	304-12625	HMA PATCHING FULL DEPTH, TYPE C	400.00 TON
0022	304-12626	HMA PATCHING PARTIAL, DEPTH TYPE C	200.00 TON
0023	304-12627	HMA PATCHING FULL DEPTH, TYPE D	1000.00 TON
0024	304-12628	HMA PATCHING PARTIAL DEPTH, TYPE D	500.00 TON
0025	306-08036	MILLING, ASPHALT, 2 IN.	4000.00 SYS
0026	401-07347	QC/QA-HMA, 3, 70, SURFACE, 12.5 mm	200.00 TON
0027	401-07353	QC/QA-HMA, 4, 76, SURFACE, 12.5 mm	200.00 TON
0028	401-10258	JOINT ADHESIVE, SURFACE	1500.00 LFT
0029	401-11785	LIQUID ASPHALT SEALANT	1500.00 LFT
0030	406-05520	ASPHALT FOR TACK COAT	5.00 TON
0031	503-03489	RETROFITTED TIE BARS	75.00 EACH

0032	503-05240	D-1 CONTRACTION JOINT	108.00	LFT
0033	506-06333	PCCP PATCHING, FULL DEPTH	200.00	SYS
0034	506-06334	PCCP PATCHING, PARTIAL DEPTH	50.00	SYS
0035	507-07480	PROFILING, PCCP	200.00	SYS
0036	507-08272	JOINTS IN PCCP, SAW AND SEAL	500.00	LFT
0037	509-12191	JOINT REPAIR, PARTIAL DEPTH	300.00	SFT
0038	509-12192	JOINT REPAIR, BOTTOM-HALF	50.00	SFT
0039	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	20.00	EACH
0040	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2500.00	LFT
0041	801-06640	CONSTRUCTION SIGN, A	150.00	EACH
0042	801-06645	CONSTRUCTION SIGN, B	25.00	EACH
0043	801-06710	FLASHING ARROW SIGN	30.00	DAY
0044	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0045	801-12440	MAINTAINING TRAFFIC, IDIQ	225000.00	DOL
0046	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	1000.00	LFT
0047	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	1000.00	LFT
0048	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	5000.00	LFT
0049	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	5000.00	LFT
0050	808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	250.00	LFT
0051	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	15.00	EACH

Call: 351

Contract: R -44187-A

Section No.: 1 IDIQ, PATCH AND REHAB PAVEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0002	109-08360	CONTRACT LIENS	1.00 DOL
0003	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	110-12655	MOBILIZATION AND DEMOBILIZATION, IDIQ	1.00 DOL
0009	201-02245	TREE 6 IN., REMOVE	3.00 EACH
0010	201-02250	TREE 10 IN., REMOVE	3.00 EACH
0011	201-02255	TREE 18 IN., REMOVE	3.00 EACH
0012	201-02260	TREE 30 IN., REMOVE	3.00 EACH
0013	201-02265	TREE 48 IN., REMOVE	3.00 EACH
0014	201-02270	TREE 60 IN., REMOVE	3.00 EACH
0015	202-02240	PAVEMENT REMOVAL	800.00 SYS
0016	202-52710	SIDEWALK CONCRETE, REMOVE	100.00 SYS
0017	202-93615	CONCRETE, REMOVE	100.00 SYS
0018	202-96128	GUTTER, CONCRETE, REMOVE	100.00 LFT
0019	202-96133	PIPE, REMOVE	100.00 LFT
0020	203-02000	EXCAVATION, COMMON	50.00 CYS
0021	207-08264	SUBGRADE TREATMENT, TYPE II	200.00 SYS
0022	207-08268	SUBGRADE TREATMENT, TYPE IV	100.00 SYS
0023	207-09935	SUBGRADE TREATMENT, TYPE IC	200.00 SYS
0024	207-12498	SUBGRADE TREATMENT, TYPE ID	200.00 SYS
0025	213-09270	FLOWABLE BACKFILL, REMOVABLE	50.00 CYS
0026	214-11796	GEOGRID, TYPE IB	200.00 SYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	100.00 TON
0028	303-07449	COMPACTED AGGREGATE NO. 73	100.00 TON
0029	304-12623	HMA PATCHING FULL DEPTH, TYPE B	100.00 TON
0030	304-12624	HMA PATCHING PARTIAL DEPTH, TYPE B	100.00 TON
0031	304-12625	HMA PATCHING FULL DEPTH, TYPE C	400.00 TON

0032	304-12626	HMA PATCHING PARTIAL, DEPTH TYPE C	200.00	TON
0033	304-12627	HMA PATCHING FULL DEPTH, TYPE D	200.00	TON
0034	304-12628	HMA PATCHING PARTIAL DEPTH, TYPE D	200.00	TON
0035	306-08034	MILLING, ASPHALT, 1 1/2 IN.	10000.00	SYS
0036	306-08036	MILLING, ASPHALT, 2 IN.	10000.00	SYS
0037	401-10258	JOINT ADHESIVE, SURFACE	26000.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	26000.00	LFT
0039	402-07451	HMA WEDGE AND LEVEL, TYPE B	200.00	TON
0040	402-07452	HMA WEDGE AND LEVEL, TYPE C	600.00	TON
0041	402-07787	HMA WEDGE AND LEVEL, TYPE D	200.00	TON
0042	406-05520	ASPHALT FOR TACK COAT	4.00	TON
0043	503-03489	RETROFITTED TIE BARS	75.00	EACH
0044	503-05240	D-1 CONTRACTION JOINT	144.00	LFT
0045	506-06333	PCCP PATCHING, FULL DEPTH	700.00	SYS
0046	506-06334	PCCP PATCHING, PARTIAL DEPTH	400.00	SYS
0047	507-08272	JOINTS IN PCCP, SAW AND SEAL	25000.00	LFT
0048	604-06070	SIDEWALK, CONCRETE	1.00	SYS
0049	604-08086	CURB RAMP, CONCRETE	75.00	SYS
0050	605-01870	CURB, CONCRETE A	100.00	LFT
0051	610-09108	PCCP FOR APPROACHES, 9 IN.	50.00	SYS
0052	702-90915	CONCRETE, CLASS, A	10.00	CYS
0053	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	10.00	EACH
0054	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	2500.00	LFT
0055	801-06640	CONSTRUCTION SIGN, A	150.00	EACH
0056	801-06645	CONSTRUCTION SIGN, B	25.00	EACH
0057	801-06710	FLASHING ARROW SIGN	50.00	DAY
0058	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0059	801-12440	MAINTAINING TRAFFIC, IDIQ	1.00	DOL
0060	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	5280.00	LFT
0061	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	5280.00	LFT
0062	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	5280.00	LFT
0063	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	5280.00	LFT
0064	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	100.00	LFT
0065	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	20.00	EACH

Call: 401

Contract: B -39491-A

Section No.: 1 REPLACE SUPERSTRUCTURE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	113-01614	PARTNERING OVERHEAD	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-02240	PAVEMENT REMOVAL	7410.00 SYS
0014	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0015	202-74080	OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	3.00 EACH
0016	202-93741	GUARDRAIL, END TREATMENT, REMOVE	5.00 EACH
0017	203-02000	EXCAVATION, COMMON	5147.00 CYS
0018	203-02588	LAGGING, PRECAST CONCRETE	133.00 SYS
0019	203-08279	EXPANDED POLYSTYRENE FILL	141.00 CYS
0020	204-08396	STANDPIPE PIEZOMETER	18.00 EACH
0021	204-08415	STAKE, SETTLEMENT	9.00 EACH
0022	205-12108	STORMWATER MANAGEMENT BUDGET	22529.00 DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0024	205-12618	SWQCP PREPARATION	1.00 LS
0025	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	1981.00 CYS
0026	207-09935	SUBGRADE TREATMENT, TYPE IC	1218.00 SYS
0027	207-12635	SUBGRADE TREATMENT, TYPE IBC	8779.00 SYS
0028	211-02050	B BORROW	1077.00 CYS
0029	211-06467	AGGREGATE FOR END BENT BACKFILL	82.00 CYS
0030	211-09264	STRUCTURE BACKFILL, TYPE 1	55.00 CYS
0031	214-12238	GEOTEXTILE FOR PAVEMENT TYPE 2A	1354.00 SYS

0032	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	268.00	SYS
0033	301-12232	COMPACTED AGGREGATE NO. 5	226.00	CYS
0034	301-12233	COMPACTED AGGREGATE NO. 8	379.00	CYS
0035	301-12234	COMPACTED AGGREGATE NO. 53	1725.00	CYS
0036	302-06464	SUBBASE FOR PCCP	163.00	CYS
0037	303-01180	COMPACTED AGGREGATE NO. 53	198.00	TON
0038	306-08034	MILLING, ASPHALT, 1 1/2 IN.	796.00	SYS
0039	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	724.00	TON
0040	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	1097.00	TON
0041	401-08364	QC/QA-HMA, 4, 64, BASE, 19.0 mm	3072.00	TON
0042	401-10258	JOINT ADHESIVE, SURFACE	5935.00	LFT
0043	401-10259	JOINT ADHESIVE, INTERMEDIATE	5320.00	LFT
0044	401-11785	LIQUID ASPHALT SEALANT	5935.00	LFT
0045	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	1197.00	TON
0046	402-10087	HMA FOR TEMPORARY PAVEMENT, TYPE D	533.00	TON
0047	503-12477	TERMINAL JOINT, TYPE HMA	84.00	LFT
0048	503-12477	TERMINAL JOINT, TYPE HMA	96.00	LFT
0049	601-02241	GUARDRAIL, REMOVE	831.00	LFT
0050	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	5.00	EACH
0051	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	1103.00	LFT
0052	601-12291	GUARDRAIL, MGS, TRANSITION WITH CURB	8.00	EACH
0053	601-94689	GUARDRAIL, END TREATMENT, OS	5.00	EACH
0054	601-94690	GUARDRAIL, END TREATMENT, MS	2.00	EACH
0055	601-99123	GUARDRAIL, TRANSITION, GP	1.00	EACH
0056	602-06729	BARRIER, DELINEATOR	118.00	EACH
0057	605-06095	CURB, INTEGRAL B CONCRETE	20.00	LFT
0058	605-06121	CURB, CONCRETE B	116.00	LFT
0059	605-06121	CURB, CONCRETE B	136.00	LFT
0060	605-97305	CURB AND GUTTER, TURNOUT COMBINED MODIFIED	8.00	EACH
0061	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	513.00	SYS
0062	615-06505	MONUMENT, B	18.00	EACH
0063	615-06515	MONUMENT, D	2.00	EACH
0064	616-06405	RIPRAP, REVETMENT	294.00	TON
0065	616-09395	GEOMEMBRANE	97.00	SYS
0066	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	452.00	SYS
0067	616-51367	SLOPEWALL, CONCRETE, 4 IN.	957.00	SYS
0068	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH

0069	621-02770	EROSION CONTROL BLANKET	1661.00	SYS
0070	621-04258	SEED MIXTURE	1.00	LBS
0071	621-06554	SEED MIXTURE, U	555.00	LBS
0072	621-06574	SODDING	171.00	SYS
0073	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0074	628-12683	FIELD OFFICE, D	24.00	MOS
0075	701-02936	PILE, STEEL H, HP 14 IN. X 89 IN.	2008.00	LFT
0076	701-06011	DYNAMIC PILE LOAD TEST	17.00	EACH
0077	701-09557	TEST PILE, DYNAMIC, PRODUCTION	2004.00	LFT
0078	701-09559	TEST PILE, DYNAMIC, RESTRIKE	17.00	EACH
0079	701-09684	PILE SHOE, HP 14 X 89	21.00	EACH
0080	701-09826	PILE, STEEL PIPE, 0.5 IN., 14 IN.	28742.00	LFT
0081	701-12836	AUTOMATED PILE DRIVING DATA ACQUISITION DEVICE	2.00	EACH
0082	702-04325	TEMPORARY SHORING	1.00	LS
0083	702-51005	CONCRETE, A, SUBSTRUCTURE	1153.20	CYS
0084	702-51005	CONCRETE, A, SUBSTRUCTURE	72.60	CYS
0085	702-51015	CONCRETE, B, FOOTINGS	342.80	CYS
0086	702-51015	CONCRETE, B, FOOTINGS	435.90	CYS
0087	702-51863	FIELD DRILLED HOLE IN CONCRETE	2673.00	EACH
0088	702-92857	CONCRETE, C, SUBSTRUCTURE	62.70	CYS
0089	703-06028	REINFORCING BARS	342359.00	LBS
0090	703-06029	REINFORCING BARS, EPOXY COATED	1160884.00	LBS
0091	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	96.00	EACH
0092	704-51002	CONCRETE, C, SUPERSTRUCTURE	2925.00	CYS
0093	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	134.00	SYS
0094	706-11601	RAILING, CONCRETE FT	522.30	CYS
0095	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	8.00	EACH
0096	707-09921	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 54 IN. X 49 IN.	4938.00	LFT
0097	709-51821	SURFACE SEAL	1.00	LS
0098	709-51821	SURFACE SEAL	1.00	LS
0099	710-09158	PATCHING CONCRETE STRUCTURES	500.00	SFT
0100	711-51038	STRUCTURAL STEEL	1.00	LS
0101	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	3416.00	LFT
0102	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	247.00	LFT
0103	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	124.00	LFT
0104	715-05407	PIPE, END BENT DRAIN, 6 IN.	144.00	LFT
0105	715-09064	VIDEO INSPECTION FOR PIPE	130.00	LFT

0106	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00 EACH
0107	718-06528	OUTLET PROTECTOR, 1	10.00 EACH
0108	718-06532	VIDEO INSPECTION FOR UNDERDRAINS	3416.00 LFT
0109	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	2342.00 SYS
0110	718-12306	GEOTEXTILE FOR UNDERDRAIN, TYPE 1B	134.00 SYS
0111	718-52610	AGGREGATE FOR UNDERDRAINS	595.00 CYS
0112	720-95310	INLET, P12A MODIFIED	2.00 EACH
0113	724-12772	BRIDGE EXPANSION JOINT, M	46.00 LFT
0114	726-95870	BEARING ASSEMBLY, PTFE	12.00 EACH
0115	734-10240	CUT-WALL, NO.	114.00 SFT
0116	734-10240	CUT-WALL, NO.	25.00 SFT
0117	734-10240	CUT-WALL, NO.	150.00 SFT
0118	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00 EACH
0119	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	35160.00 LFT
0120	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	12.00 LFT
0121	801-06625	DETOUR ROUTE MARKER ASSEMBLY	8.00 EACH
0122	801-06640	CONSTRUCTION SIGN, A	38.00 EACH
0123	801-06645	CONSTRUCTION SIGN, B	4.00 EACH
0124	801-06710	FLASHING ARROW SIGN	270.00 DAY
0125	801-06775	MAINTAINING TRAFFIC	1.00 LS
0126	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	1.00 EACH
0127	801-07119	BARRICADE, III-B	24.00 LFT
0128	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2090.00 LFT
0129	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	130.00 LFT
0130	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00 EACH
0131	802-02475	SIGN, PANEL, RELOCATE	1.00 EACH
0132	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	138.00 LFT
0133	802-07057	SIGN, PANEL, WITH LEGEND	625.00 SFT
0134	802-09577	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE E	2.00 EACH
0135	802-09578	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	1.00 EACH
0136	802-09581	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 36 IN.	3.00 EACH
0137	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	7.00 SFT
0138	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	86.00 SFT
0139	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	4.00 EACH
0140	802-76095	STRUCTURAL STEEL, BREAKAWAY	594.00 LBS
0141	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0142	808-12032	GROOVING FOR PAVEMENT MARKINGS	6000.00 LFT

0143	808-12134	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 4 IN.	27.00	LFT
0144	808-12454	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 8 IN.	400.00	LFT
0145	808-75052	LINE, PREFORMED PLASTIC, SOLID, WHITE, 6 IN.	4376.00	LFT
0146	808-75053	LINE, PREFORMED PLASTIC, SOLID, WHITE, 8 IN.	365.00	LFT
0147	808-75055	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 6 IN.	2222.00	LFT
0148	808-75057	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 6 IN.	4399.00	LFT

Call: 405

Contract: B -39781-C

Section No.: 1 BRIDGE DECK REPLACEMENT

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	105-12018	UTILITY PROTECTION	1.00	LS
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-01261	TESTING FOR ASBESTOS	2.00	EACH
0014	202-02240	PAVEMENT REMOVAL	236.00	SYS
0015	202-02637	PIPE ABANDON AND GROUT FILL	24.00	LFT
0016	202-03729	REGULATED ASBESTOS CONTAINING MATERIALS, REMOVE	80.00	LFT
0017	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0018	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0019	202-93741	GUARDRAIL, END TREATMENT, REMOVE	1.00	EACH
0020	202-96133	PIPE, REMOVE	477.00	LFT
0021	203-02000	EXCAVATION, COMMON	385.00	CYS
0022	205-12108	STORMWATER MANAGEMENT BUDGET	16000.00	DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0024	205-12618	SWQCP PREPARATION	1.00	LS
0025	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	50.00	CYS
0026	206-51235	COFFERDAM	1.00	LS
0027	207-09935	SUBGRADE TREATMENT, TYPE IC	824.00	SYS
0028	211-06467	AGGREGATE FOR END BENT BACKFILL	50.00	CYS
0029	211-09194	B BORROW	32.00	TON
0030	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	266.00	CYS
0031	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	824.00	SYS

0032	301-12234	COMPACTED AGGREGATE NO. 53	244.00	CYS
0033	302-06464	SUBBASE FOR PCCP	64.00	CYS
0034	303-01180	COMPACTED AGGREGATE NO. 53	146.00	TON
0035	306-08043	MILLING, TRANSITION	4175.00	SYS
0036	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	381.00	TON
0037	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	484.00	TON
0038	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	240.00	TON
0039	401-10258	JOINT ADHESIVE, SURFACE	3600.00	LFT
0040	401-10259	JOINT ADHESIVE, INTERMEDIATE	2520.00	LFT
0041	401-11785	LIQUID ASPHALT SEALANT	3600.00	LFT
0042	406-05521	ASPHALT FOR TACK COAT	7951.00	SYS
0043	503-12477	TERMINAL JOINT, TYPE HMA	128.00	LFT
0044	601-02241	GUARDRAIL, REMOVE	1185.00	LFT
0045	601-06035	GUARDRAIL, RESET	1050.00	LFT
0046	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	443.75	LFT
0047	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	7.00	EACH
0048	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	8.00	EACH
0049	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0050	602-06729	BARRIER, DELINEATOR	26.00	EACH
0051	603-97461	TEMPORARY FENCE	700.00	LFT
0052	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	313.60	SYS
0053	616-06405	RIPRAP, REVETMENT	1160.00	TON
0054	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	150.00	SYS
0055	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	1490.00	SYS
0056	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0057	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00	LS
0058	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0059	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0060	619-12506	CLEAN STEEL BRIDGE TOP FLANGES QP-2 BRIDGE NO.	1.00	LS
0061	619-12506	CLEAN STEEL BRIDGE TOP FLANGES QP-2 BRIDGE NO.	1.00	LS
0062	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0063	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00	LS
0064	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0065	621-06559	MULCHED SEEDING R	5000.00	SYS
0066	621-06567	WATER	2.00	KGAL
0067	621-06574	SODDING	44.00	SYS
0068	622-05639	PLANT, DECIDUOUS SHRUB, 18 IN. TO 24 IN.	30.00	EACH

0069	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. TO 2 IN.	66.00 EACH
0070	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00 EACH
0071	628-12683	FIELD OFFICE, D	18.00 MOS
0072	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	16.00 EACH
0073	702-51005	CONCRETE, A, SUBSTRUCTURE	57.40 CYS
0074	702-92857	CONCRETE, C, SUBSTRUCTURE	68.00 CYS
0075	703-06028	REINFORCING BARS	6384.00 LBS
0076	703-06029	REINFORCING BARS, EPOXY COATED	210105.00 LBS
0077	703-08247	EMBEDDED GALVANIC ANODE	200.00 EACH
0078	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	76.00 EACH
0079	704-51002	CONCRETE, C, SUPERSTRUCTURE	518.90 CYS
0080	706-09960	RAILING, CONCRETE FC	956.00 LFT
0081	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00 EACH
0082	709-51821	SURFACE SEAL	1.00 LS
0083	709-51821	SURFACE SEAL	1.00 LS
0084	710-09158	PATCHING CONCRETE STRUCTURES	400.00 SFT
0085	711-51038	STRUCTURAL STEEL	1.00 LS
0086	711-51038	STRUCTURAL STEEL	1.00 LS
0087	711-51864	DRILLED HOLE	84.00 EACH
0088	711-95291	JACKING AND SUPPORTING, STEEL BEAMS	1.00 LS
0089	711-95291	JACKING AND SUPPORTING, STEEL BEAMS	1.00 LS
0090	711-96800	STUD SHEAR CONNECTORS	4424.00 EACH
0091	713-04331	TEMPORARY CAUSEWAY	1.00 LS
0092	713-04331	TEMPORARY CAUSEWAY	1.00 LS
0093	715-02745	GATE VALVE WITH VALVE BOX 8 IN.	12.00 EACH
0094	715-05407	PIPE, END BENT DRAIN, 6 IN.	220.00 LFT
0095	715-07794	WATER MAIN CONNECTIONS	4.00 EACH
0096	715-07794	WATER MAIN CONNECTIONS	4.00 EACH
0097	715-07806	PIPE STEEL CASING	477.00 LFT
0098	715-07806	PIPE STEEL CASING	477.00 LFT
0099	715-08083	CONCRETE ANCHOR, MIN. AREA 58 SFT	16.00 EACH
0100	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	16.00 EACH
0101	715-11571	WATER MAIN, DUCTILE IRON, 8 IN.	717.00 LFT
0102	715-12674	GATE VALVE AND VALVE BOX 12 IN.	4.00 EACH
0103	715-92544	WATER MAIN, DUCTILE IRON, 12 IN.	637.00 LFT
0104	718-12309	GEOTEXTILE FOR UNDERDRAIN, TYPE 3	140.00 SYS
0105	726-92406	BEARING ASSEMBLY ELASTOMERIC	28.00 EACH

0106	801-03290	CONSTRUCTION SIGN, C	8.00 EACH
0107	801-04308	ROAD CLOSURE SIGN ASSEMBLY	14.00 EACH
0108	801-06625	DETOUR ROUTE MARKER ASSEMBLY	47.00 EACH
0109	801-06640	CONSTRUCTION SIGN, A	15.00 EACH
0110	801-06645	CONSTRUCTION SIGN, B	2.00 EACH
0111	801-06775	MAINTAINING TRAFFIC	1.00 LS
0112	801-07118	BARRICADE, III-A	96.00 LFT
0113	801-07119	BARRICADE, III-B	108.00 LFT
0114	802-04089	SIGN, SHEET, REMOVE	1.00 EACH
0115	802-91122	SIGN GROUND MOUNTED RESET	11.00 EACH
0116	803-61430	BRIDGE BRACKET A GALVANIZED	26.00 EACH
0117	803-61430	BRIDGE BRACKET A GALVANIZED	26.00 EACH
0118	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	220.00 LFT
0119	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	3540.00 LFT
0120	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2490.00 LFT
0121	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	28.00 EACH
0122	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	28.00 EACH

Call: 411

Contract: B -39839-A

Section No.: 1 BRIDGE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-02240	PAVEMENT REMOVAL	1590.00 SYS
0012	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0013	203-02000	EXCAVATION, COMMON	4717.00 CYS
0014	203-02070	BORROW	2757.00 CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	24100.00 DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0017	205-12618	SWQCP PREPARATION	1.00 LS
0018	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	194.00 CYS
0019	207-08266	SUBGRADE TREATMENT, TYPE III	1918.00 SYS
0020	211-02050	B BORROW	1245.00 CYS
0021	211-09266	STRUCTURE BACKFILL, TYPE 3	1873.00 CYS
0022	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	190.00 SYS
0023	301-12234	COMPACTED AGGREGATE NO. 53	148.00 CYS
0024	302-06464	SUBBASE FOR PCCP	48.00 CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	43.00 TON
0026	306-08043	MILLING, TRANSITION	280.00 SYS
0027	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	140.00 TON
0028	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	236.00 TON
0029	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	287.00 TON
0030	401-10258	JOINT ADHESIVE, SURFACE	629.00 LFT
0031	401-10259	JOINT ADHESIVE, INTERMEDIATE	529.00 LFT

0032	401-11785	LIQUID ASPHALT SEALANT	1158.00	LFT
0033	406-05521	ASPHALT FOR TACK COAT	3698.00	SYS
0034	601-02241	GUARDRAIL, REMOVE	1438.00	LFT
0035	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	991.00	LFT
0036	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	4.00	EACH
0037	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	4.00	EACH
0038	602-06729	BARRIER, DELINEATOR	6.00	EACH
0039	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	190.00	SYS
0040	615-06490	RIGHT-OF-WAY MARKER	16.00	EACH
0041	615-06505	MONUMENT, B	2.00	EACH
0042	616-06405	RIPRAP, REVETMENT	254.00	TON
0043	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	422.00	SYS
0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0045	621-02770	EROSION CONTROL BLANKET	8611.00	SYS
0046	621-06545	FERTILIZER	1.00	TON
0047	621-06553	SEED MIXTURE, R	362.00	LBS
0048	621-06567	WATER	1.00	KGAL
0049	621-06574	SODDING	59.00	SYS
0050	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0051	628-11977	COMPUTER SYSTEM	2.00	EACH
0052	628-12683	FIELD OFFICE, D	16.00	MOS
0053	701-06011	DYNAMIC PILE LOAD TEST	2.00	EACH
0054	701-09557	TEST PILE, DYNAMIC, PRODUCTION	162.00	LFT
0055	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.00	EACH
0056	701-09683	PILE SHOE, HP 12 X 74	14.00	EACH
0057	701-95780	PILE, STEEL H, HP 12 X 74	852.00	LFT
0058	702-92857	CONCRETE, C, SUBSTRUCTURE	47.40	CYS
0059	703-06029	REINFORCING BARS, EPOXY COATED	51773.00	LBS
0060	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	32.00	EACH
0061	704-51002	CONCRETE, C, SUPERSTRUCTURE	130.40	CYS
0062	706-09960	RAILING, CONCRETE FC	230.00	LFT
0063	706-11455	BRIDGE RAILING PEDESTRIAN FENCE	413.00	LFT
0064	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0065	707-09865	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 49 IN.	540.00	LFT
0066	709-51821	SURFACE SEAL	1.00	LS
0067	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	290.00	LFT
0068	718-12305	GEOTEXTILES FOR UNDERDRAIN, TYPE 1A	226.00	SYS

0069	718-52610	AGGREGATE FOR UNDERDRAINS	23.00	CYS
0070	731-93945	FACE PANELS, CONCRETE	4173.00	SFT
0071	731-93946	WALL ERECTION	4173.00	SFT
0072	731-93947	LEVELING PAD, CONCRETE	270.00	LFT
0073	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0074	801-06625	DETOUR ROUTE MARKER ASSEMBLY	16.00	EACH
0075	801-06640	CONSTRUCTION SIGN, A	10.00	EACH
0076	801-06775	MAINTAINING TRAFFIC	1.00	LS
0077	801-07118	BARRICADE, III-A	48.00	LFT
0078	801-07119	BARRICADE, III-B	48.00	LFT
0079	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1590.00	LFT
0080	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1590.00	LFT

Call: 491

Contract: M -43882-C

Section No.: 1 LIGHTING MAINTENANCE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0005	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	2.00 EACH
0006	802-12223	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, B	2.00 EACH
0007	802-12224	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, C	2.00 EACH
0008	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	1.00 EACH
0009	805-01816	SIGNAL SUPPORT FOUNDATION, 36 IN. X 36 IN. X 96 IN.	1.00 EACH
0010	805-01820	SIGNAL POLE, STEEL STRAIN, INSTALL	1.00 EACH
0011	805-01824	SPAN, CATENARY, AND TETHER, TIGHTEN	1.00 EACH
0012	805-11377	SIGNAL CANTILEVER STRUCTURE, SINGLE ARM 35 FT	1.00 EACH
0013	805-11383	SIGNAL CANTILEVER STRUCTURE, DRILLED SHAFT FOUNDATION, A	1.00 EACH
0014	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	1.00 EACH
0015	805-78230	TRAFFIC SIGNAL HEAD, 5 SECTION, 12 IN.	1.00 EACH
0016	805-78415	SPAN, CATENARY, AND TETHER	1.00 EACH
0017	805-78415	SPAN, CATENARY, AND TETHER	1.00 EACH
0018	805-78420	DISCONNECT HANGER	1.00 EACH
0019	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	50.00 LFT
0020	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	300.00 LFT
0021	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	300.00 LFT
0022	805-86898	CONDUIT, STEEL, GALVANIZED, 0.75 IN.	50.00 LFT
0023	805-91706	ANCHOR BOLT REPAIR	10.00 EACH
0024	805-95518	CONDUIT, FLEXIBLE, 2 IN.	20.00 LFT
0025	805-97042	SIGNAL POLE, WOOD, 5, 35 FT	2.00 EACH
0026	807-01413	POWER DISCONNECT PLUG FOR HIGH MAST TOWER	5.00 EACH
0027	807-01563	HIGH MAST TOWER LOCATING PIN, STAINLESS STEEL	2.00 EACH
0028	807-01564	HIGH MAST TOWER, SMALL GEAR OF CHAIN DRIVE	1.00 EACH
0029	807-01606	HIGH MAST TOWER WINCH DRIVE	2.00 EACH
0030	807-01617	HANDHOLE COVER AND RING	1.00 EACH
0031	807-02191	HANDHOLE, LIGHTING	3.00 EACH

0032	807-04428	CABLE DUCT	750.00	LFT
0033	807-04651	WIRE	15000.00	LFT
0034	807-04988	BOX	2.00	EACH
0035	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	100.00	LFT
0036	807-07703	HIGH MAST TOWER	15.00	EACH
0037	807-08621	LOCATE UNDERGROUND LIGHTING FACILITIES	30.00	EACH
0038	807-11679	LIGHT POLE, 38 FT E.M.H., 15 FT MAST ARM, ANCHOR BASE	1.00	EACH
0039	807-11772	LUMINAIRE, DIAGNOSIS AND REPAIR	750.00	EACH
0040	807-11874	LIGHT POLE, 20 FT E.M.H., 10 FT MAST ARM, BREAKAWAY BASE	1.00	EACH
0041	807-86805	SERVICE POINT, I	2.00	EACH
0042	807-86810	SERVICE POINT, II	2.00	EACH
0043	807-86843	WIRE, NO. 4 COPPER, 1/C	2500.00	LFT
0044	807-86910	CONNECTOR KIT, UNFUSED	50.00	EACH
0045	807-86915	CONNECTOR KIT, FUSED	50.00	EACH
0046	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	160.00	EACH
0047	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	25.00	EACH
0048	807-86930	INSULATION LINK, NON-WATERPROOFED	420.00	EACH
0049	807-86935	INSULATION LINK, WATERPROOFED	30.00	EACH
0050	807-87085	ELECTRICIAN	50.00	HRS
0051	807-87098	CALLOUT REPAIR	25.00	EACH
0052	807-87640	BREAKAWAY COUPLING	5.00	SET
0053	807-91705	CONDUIT POLYETHYLENE REPAIR	20.00	EACH
0054	807-93746	TOWER RING LIFT CABLE, 0.375	50.00	LFT
0055	807-93747	TOWER RING, SUSPENSION CABLE, 0.1875	500.00	LFT
0056	807-94480	LIGHT STANDARD, INSTALL	20.00	EACH
0057	807-95492	SERVICE POINT, II, BREAKER ENCLOSURE	5.00	EACH
0058	807-95513	SERVICE POINT, MAIN BREAKER	2.00	EACH
0059	807-95514	SERVICE POINT, RISER	1.00	EACH
0060	807-95515	SERVICE POINT, WEATHERHEAD	1.00	EACH
0061	807-95516	RELAY SWITCH	5.00	EACH
0062	807-95523	WATERPROOFING OF ELECTRICAL CONNECTOR	30.00	EACH
0063	807-95632	SERVICE POINT, OVERRIDE CIRCUIT	5.00	EACH
0064	807-95705	BREAKAWAY ALUMINUM TRANSFORMER BASE	20.00	EACH
0065	807-95889	WIRE, NO. 10 COPPER, 1/C	3000.00	LFT
0066	807-96069	HIGH MAST TOWER, REPAIR	3.00	EACH
0067	807-96236	LIGHT POLE, HIGH MAST TOWER, POWER CABLE	2.00	EACH
0068	807-96868	LUMINAIRE, INSTALL	75.00	EACH

0069 807-98469 PULL BOX

5.00 EACH

Call: 501

Contract: M -44222-A

Section No.: 1 TREE REMOVAL AND TRIMMING

Line

Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0005	201-02245	TREE 6 IN., REMOVE	25.00	EACH
0006	201-02250	TREE 10 IN., REMOVE	30.00	EACH
0007	201-02255	TREE 18 IN., REMOVE	33.00	EACH
0008	201-02260	TREE 30 IN., REMOVE	25.00	EACH
0009	201-02265	TREE 48 IN., REMOVE	15.00	EACH
0010	201-02270	TREE 60 IN., REMOVE	2.00	EACH
0011	801-06710	FLASHING ARROW SIGN	10.00	DAY
0012	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 601

Contract: T -44221-A

Section No.: 1 ACCESS CONTROL

Line			Quantity Unit	
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0009	203-02000	EXCAVATION, COMMON	285.00	CYS
0010	203-02070	BORROW	164.00	CYS
0011	304-12625	HMA PATCHING FULL DEPTH, TYPE C	379.00	TON
0012	605-06120	CURB, CONCRETE	573.00	LFT
0013	605-06255	CENTER CURB, D CONCRETE	328.00	SYS
0014	621-06570	TOPSOIL	53.00	CYS
0015	621-06575	SODDING, NURSERY	317.00	SYS
0016	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1667.00	LFT
0017	801-06640	CONSTRUCTION SIGN, A	30.00	EACH
0018	801-06775	MAINTAINING TRAFFIC	1.00	LS
0019	801-07118	BARRICADE, III-A	48.00	LFT
0020	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	75.00	LFT
0021	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	768.00	LFT
0022	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	494.00	LFT
0023	805-78785	SIGNAL DETECTOR HOUSING	2.00	EACH
0024	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	192.00	LFT
0025	808-06716	LINE, REMOVE	34.00	LFT
0026	808-12032	GROOVING FOR PAVEMENT MARKINGS	2790.00	LFT
0027	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	736.00	LFT
0028	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	2044.00	LFT
0029	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	68.00	LFT
0030	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	4.00	EACH
0031	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	21.00	EACH

0032	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	10.00	LFT
------	-----------	---	-------	-----