

Schedule of Pay Items Letting Date October 13, 2022 Letting ID 221013

Call: 120

Contract: R -40460-B

Section No.: 1 ROAD RECONSTRUCTION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-01845	CONDUIT, REMOVE	60.00 LFT
0012	202-02240	PAVEMENT REMOVAL	274.00 SYS
0013	202-02278	CURB, CONCRETE, REMOVE	1080.00 LFT
0014	202-02637	PIPE ABANDON AND GROUT FILL	34.00 LFT
0015	202-03875	CONCRETE STEPS, REMOVE	11.00 EACH
0016	202-06312	REMOVE	2741.00 SFT
0017	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0018	202-52710	SIDEWALK CONCRETE, REMOVE	302.00 SYS
0019	202-90747	RETAINING WALL, REMOVE	75.00 LFT
0020	202-91385	INLET, REMOVE	5.00 EACH
0021	202-96133	PIPE, REMOVE	479.00 LFT
0022	202-97009	FIRE HYDRANT ASSEMBLY, REMOVE	3.00 EACH
0023	203-02000	EXCAVATION, COMMON	7518.00 CYS
0024	203-02010	EXCAVATION, ROCK	684.00 CYS
0025	205-12108	STORMWATER MANAGEMENT BUDGET	28135.00 DOL
0026	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0027	205-12618	SWQCP PREPARATION	1.00 LS
0028	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	157.00 CYS
0029	207-08264	SUBGRADE TREATMENT, TYPE II	9856.00 SYS
0030	207-12151	SUBGRADE TREATMENT, TYPE IVA	1117.00 SYS
0031	211-02050	B BORROW	3.00 CYS

0032	211-09265	STRUCTURE BACKFILL, TYPE 2	7124.00	CYS
0033	211-09266	STRUCTURE BACKFILL, TYPE 3	159.00	CYS
0034	214-12238	GEOTEXTILE FOR PAVEMENT TYPE 2A	10214.00	SYS
0035	301-12232	COMPACTED AGGREGATE NO. 5	1624.00	CYS
0036	301-12234	COMPACTED AGGREGATE NO. 53	889.00	CYS
0037	302-07455	DENSE GRADED SUBBASE	92.00	CYS
0038	303-01180	COMPACTED AGGREGATE NO. 53	1580.00	TON
0039	303-07449	COMPACTED AGGREGATE NO. 73	37.00	TON
0040	304-07493	WIDENING WITH HMA, TYPE B	8.00	TON
0041	304-12623	HMA PATCHING FULL DEPTH, TYPE B	4.00	TON
0042	306-08034	MILLING, ASPHALT, 1 1/2 IN.	256.00	SYS
0043	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	570.00	TON
0044	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	919.00	TON
0045	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	1105.00	TON
0046	401-10258	JOINT ADHESIVE, SURFACE	10319.00	LFT
0047	401-10259	JOINT ADHESIVE, INTERMEDIATE	10259.00	LFT
0048	401-11785	LIQUID ASPHALT SEALANT	5376.00	LFT
0049	406-05520	ASPHALT FOR TACK COAT	3.50	TON
0050	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0051	601-02241	GUARDRAIL, REMOVE	564.00	LFT
0052	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	521.00	LFT
0053	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	2.00	EACH
0054	603-97461	TEMPORARY FENCE	1530.00	LFT
0055	604-06070	SIDEWALK, CONCRETE	1380.00	SYS
0056	604-07092	BED COURSE MATERIAL	373.00	TON
0057	604-08086	CURB RAMP, CONCRETE	25.00	SYS
0058	604-12083	DETECTABLE WARNING SURFACES	7.00	SYS
0059	604-44251	STEPS, CONCRETE	2.00	CYS
0060	604-95344	HAND RAIL, PEDESTRIAN	32.50	LFT
0061	605-06120	CURB, CONCRETE	417.00	LFT
0062	605-52807	CURB AND GUTTER, COMBINED	4008.00	LFT
0063	610-07487	HMA FOR APPROACHES, TYPE B	39.00	TON
0064	610-08446	PCCP FOR APPROACHES, 6 IN.	480.00	SYS
0065	611-06497	MAILBOX ASSEMBLY, SINGLE	2.00	EACH
0066	611-06498	MAILBOX ASSEMBLY, DOUBLE	1.00	EACH
0067	615-06490	RIGHT-OF-WAY MARKER	17.00	EACH
0068	615-06505	MONUMENT, B	19.00	EACH

0069	616-05688	RIPRAP, CLASS 1	87.00	TON
0070	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	116.00	SYS
0071	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0072	621-06559	MULCHED SEEDING R	360.00	SYS
0073	621-06574	SODDING	5742.00	SYS
0074	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. TO 2 IN.	6.00	EACH
0075	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0076	628-12683	FIELD OFFICE, D	24.00	MOS
0077	629-12029	PLANT GROWTH LAYER	6102.00	SYS
0078	702-04325	TEMPORARY SHORING	1.00	LS
0079	702-51005	CONCRETE, A, SUBSTRUCTURE	22.60	CYS
0080	702-51015	CONCRETE, B, FOOTINGS	19.60	CYS
0081	702-90915	CONCRETE, CLASS, A	3.00	CYS
0082	703-06028	REINFORCING BARS	6309.00	LBS
0083	715-02744	GATE VALVE AND VALVE BOX 6 IN.	3.00	EACH
0084	715-05032	PIPE, TYPE 2, CIRCULAR, 15 IN.	255.00	LFT
0085	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	3507.00	LFT
0086	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	16.00	LFT
0087	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	322.00	LFT
0088	715-05153	PIPE, TYPE 2, CIRCULAR, 21 IN.	34.00	LFT
0089	715-05154	PIPE, TYPE 2, CIRCULAR, 24 IN.	71.00	LFT
0090	715-05156	PIPE, TYPE 2, CIRCULAR, 30 IN.	25.00	LFT
0091	715-05159	PIPE, TYPE 2, CIRCULAR, 42 IN.	142.00	LFT
0092	715-05161	PIPE, TYPE 2, CIRCULAR, 48 IN.	1608.00	LFT
0093	715-05168	PIPE, TYPE 3, CIRCULAR, 12 IN.	20.00	LFT
0094	715-05203	PIPE, TYPE 4, CIRCULAR, 4 IN.	130.00	LFT
0095	715-05408	PIPE, SANITARY SEWER, 8 IN.	1554.00	LFT
0096	715-05422	PIPE, SLOTTED DRAIN, 12 IN.	20.00	LFT
0097	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	3.00	TON
0098	715-11879	SEWER, SANITARY LATERAL, CONNECTIONS	776.00	LFT
0099	715-11896	WATER SERVICE CONNECTION	30.00	EACH
0100	715-26777	GRATED BOX END SECTION, I, 2:1 DIAMETER 42 IN.	1.00	EACH
0101	715-46000	PIPE END SECTION, DIAMETER 12 IN.	2.00	EACH
0102	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0103	715-46020	PIPE END SECTION, DIAMETER 24 IN.	1.00	EACH
0104	715-90853	TAPPING SLEEVE WITH VALVE	30.00	EACH
0105	715-91361	PIPE PVC 6 IN	917.00	LFT

0106	715-94780	WATER MAIN, DUCTILE IRON, 6 IN.	1541.00	LFT
0107	715-95866	GATE VALVE 6 IN.	4.00	EACH
0108	715-98265	WATER MAIN, DUCTILE IRON, 4 IN.	664.00	LFT
0109	718-04986	CLEANOUT	31.00	EACH
0110	718-11685	UNDERDRAIN CLEANOUT PORT	8.00	EACH
0111	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	87.00	SYS
0112	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	2923.00	SYS
0113	718-52610	AGGREGATE FOR UNDERDRAINS	11.00	CYS
0114	720-01915	MANHOLE, E	1.00	EACH
0115	720-01917	CASTING, MODIFIED	2.00	EACH
0116	720-02442	PIPE PLUG EXISTING	7.00	EACH
0117	720-03194	MANHOLE	8.00	EACH
0118	720-03194	MANHOLE	1.00	EACH
0119	720-03194	MANHOLE	1.00	EACH
0120	720-10138	MANHOLE, L7	1.00	EACH
0121	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	5.00	EACH
0122	720-45410	MANHOLE, C4	5.00	EACH
0123	720-94612	MANHOLE, K4	7.00	EACH
0124	720-96999	FIRE HYDRANT ASSEMBLY	3.00	EACH
0125	720-98174	INLET, B15	28.00	EACH
0126	720-98555	INLET, C15	5.00	EACH
0127	720-98625	MANHOLE, C4 DROP	7.00	EACH
0128	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0129	801-06625	DETOUR ROUTE MARKER ASSEMBLY	29.00	EACH
0130	801-06640	CONSTRUCTION SIGN, A	14.00	EACH
0131	801-06645	CONSTRUCTION SIGN, B	9.00	EACH
0132	801-06775	MAINTAINING TRAFFIC	1.00	LS
0133	801-07118	BARRICADE, III-A	72.00	LFT
0134	801-07119	BARRICADE, III-B	48.00	LFT
0135	801-11990	TEMPORARY CURB RAMP	4.00	EACH
0136	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	89.50	LFT
0137	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	11.30	LFT
0138	802-07059	SIGN, SHEET, AND SUPPORTS, REMOVE	9.00	EACH
0139	802-07060	SIGN, SHEET, RELOCATE	3.00	EACH
0140	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	47.50	SFT
0141	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	24.80	SFT
0142	807-02426	WIRE, THW, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	455.00	LFT

0143	807-03950	LUMINAIRE ORNAMENTAL	18.00 EACH
0144	807-03951	LIGHT POLE ORNAMENTAL	18.00 EACH
0145	807-04653	LIGHTING FOUNDATION	18.00 EACH
0146	807-06592	CONDUIT, STEEL, GALVANIZED, 2 IN.	455.00 LFT
0147	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	1130.00 LFT
0148	807-86805	SERVICE POINT, I	1.00 EACH
0149	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	570.00 LFT
0150	807-86910	CONNECTOR KIT, UNFUSED	18.00 EACH
0151	807-86915	CONNECTOR KIT, FUSED	18.00 EACH
0152	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	51.00 EACH
0153	807-86930	INSULATION LINK, NON-WATERPROOFED	36.00 EACH
0154	807-86950	SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION IDENTIFICATION	18.00 EACH
0155	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2446.00 LFT
0156	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4572.00 LFT
0157	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	24.00 LFT
0158	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	141.00 LFT
0159	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	31.00 EACH

Call: 130

Contract: R -40537-A

Section No.: 1

SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0009	201-02245	TREE 6 IN., REMOVE	2.00	EACH
0010	201-02255	TREE 18 IN., REMOVE	3.00	EACH
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-99187	FENCE, FARM FIELD, REMOVE	151.00	LFT
0013	203-02000	EXCAVATION, COMMON	30.00	CYS
0014	205-11626	PUMP AROUND	2.00	EACH
0015	205-12108	STORMWATER MANAGEMENT BUDGET	2403.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	206-51220	EXCAVATION, WET	20.00	CYS
0019	301-12232	COMPACTED AGGREGATE NO. 5	4.00	CYS
0020	304-12623	HMA PATCHING FULL DEPTH, TYPE B	2.00	TON
0021	601-06035	GUARDRAIL, RESET	70.00	LFT
0022	603-06040	FENCE, FARM FIELD, 47 IN.	151.00	LFT
0023	603-97461	TEMPORARY FENCE	181.00	LFT
0024	616-05689	RIPRAP, CLASS 2	72.00	TON
0025	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	45.00	SYS
0026	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	13.00	SYS
0027	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0028	621-06559	MULCHED SEEDING R	727.00	SYS
0029	621-12612	SEED MIXTURE, FLOODPLAIN	2.00	LBS
0030	622-03672	TREE PROTECTION AND TRIMMING	1.00	LS
0031	702-51005	CONCRETE, A, SUBSTRUCTURE	13.00	CYS

0032	703-06029	REINFORCING BARS, EPOXY COATED	1950.00	LBS
0033	715-01354	CLEAN EXISTING PIPE	42.00	LFT
0034	725-08296	PIPE LINER, CURED-IN-PLACE, 48 IN.	51.00	LFT
0035	725-10245	PERPETUATION, EXISTING PIPE	1.00	EACH
0036	725-11709	PIPE LINER, CURED-IN-PLACE, MIN. AREA 12.5 SFT	42.00	LFT
0037	801-06640	CONSTRUCTION SIGN, A	49.00	EACH
0038	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 140

Contract: R -41414-A

Section No.: 1

SMALL STRUCTURE PIPE LINING

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0010	205-11626	PUMP AROUND	2.00	EACH
	0011	205-12108	STORMWATER MANAGEMENT BUDGET	8417.00	DOL
	0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0013	205-12618	SWQCP PREPARATION	1.00	LS
	0014	601-06035	GUARDRAIL, RESET	100.00	LFT
	0015	616-05689	RIPRAP, CLASS 2	113.00	TON
	0016	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	169.00	SYS
	0017	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
	0018	621-02770	EROSION CONTROL BLANKET	1315.00	SYS
	0019	621-06553	SEED MIXTURE, R	41.00	LBS
	0020	621-06559	MULCHED SEEDING R	494.00	SYS
	0021	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	EACH
	0022	628-12683	FIELD OFFICE, D	8.00	MOS
	0023	725-11922	PIPE LINER, CURED-IN-PLACE, MIN. AREA 38.5 SFT	260.00	LFT
	0024	725-12146	LINER PIPE, THERMOPLASTIC, CIRCULAR, 10.9-12.4 SFT	114.00	LFT
	0025	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
	0026	801-06640	CONSTRUCTION SIGN, A	36.00	EACH
	0027	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
	0028	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 150

Contract: R -41490-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-02271	HEADWALL, REMOVE	2.00 EACH
0014	202-93741	GUARDRAIL, END TREATMENT, REMOVE	4.00 EACH
0015	202-96133	PIPE, REMOVE	6.00 LFT
0016	203-02000	EXCAVATION, COMMON	5.00 CYS
0017	203-02070	BORROW	6.00 CYS
0018	205-12108	STORMWATER MANAGEMENT BUDGET	1000.00 DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	392.00 SYS
0021	213-08068	DRILLED HOLE FOR FLOWABLE BACKFILL	6.00 EACH
0022	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	5.00 CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	932.00 TON
0024	304-12623	HMA PATCHING FULL DEPTH, TYPE B	260.00 TON
0025	304-12624	HMA PATCHING PARTIAL DEPTH, TYPE B	3.00 TON
0026	306-08036	MILLING, ASPHALT, 2 IN.	37629.00 SYS
0027	306-08037	MILLING, ASPHALT, 3 IN.	178.00 SYS
0028	306-08043	MILLING, TRANSITION	1360.00 SYS
0029	306-08432	MILLING, APPROACH	1605.00 SYS
0030	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	3259.00 TON
0031	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	5562.00 TON

0032	401-10258	JOINT ADHESIVE, SURFACE	18329.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	18329.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	18329.00	LFT
0035	401-12169	INERTIAL PROFILER, HMA	1.00	LS
0036	406-05520	ASPHALT FOR TACK COAT	21.00	TON
0037	601-02241	GUARDRAIL, REMOVE	240.00	LFT
0038	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	2.00	EACH
0039	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0040	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	18348.00	LFT
0041	610-07487	HMA FOR APPROACHES, TYPE B	353.00	TON
0042	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0043	621-02770	EROSION CONTROL BLANKET	34.00	SYS
0044	621-06560	MULCHED SEEDING U	34.00	SYS
0045	628-09403	FIELD OFFICE, C	6.00	MOS
0046	720-02442	PIPE PLUG EXISTING	2.00	EACH
0047	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	3445.00	LFT
0048	801-06640	CONSTRUCTION SIGN, A	21.00	EACH
0049	801-06775	MAINTAINING TRAFFIC	1.00	LS
0050	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0051	801-12042	TRUCK MOUNTED ATTENUATOR	14.00	DAY
0052	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0053	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	26596.00	LFT
0054	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	16785.00	LFT
0055	808-12032	GROOVING FOR PAVEMENT MARKINGS	45239.00	LFT
0056	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	1858.00	LFT
0057	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	52.00	LFT
0058	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	40.00	EACH
0059	809-05906	ATR STATION, 2 LANE	1.00	EACH

Call: 160

Contract: R -41507-A

Section No.: 1 PCCP THIN OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
	0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0012	202-93741	GUARDRAIL, END TREATMENT, REMOVE	6.00	EACH
	0013	207-08268	SUBGRADE TREATMENT, TYPE IV	7815.00	SYS
	0014	303-01180	COMPACTED AGGREGATE NO. 53	2638.00	TON
	0015	303-08210	COMPACTED AGGREGATE, NO. 53, TEMPORARY FOR DRIVEWAYS	2643.00	TON
	0016	304-12625	HMA PATCHING FULL DEPTH, TYPE C	2579.00	TON
	0017	306-08033	MILLING, ASPHALT, 1 IN.	171071.00	SYS
	0018	306-08037	MILLING, ASPHALT, 3 IN.	171071.00	SYS
	0019	306-08432	MILLING, APPROACH	10964.00	SYS
	0020	401-06264	PROFILOGRAPH, HMA	1.00	LS
	0021	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	7136.00	TON
	0022	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	15964.00	TON
	0023	401-10258	JOINT ADHESIVE, SURFACE	15976.00	LFT
	0024	401-10259	JOINT ADHESIVE, INTERMEDIATE	15976.00	LFT
	0025	401-11785	LIQUID ASPHALT SEALANT	15976.00	LFT
	0026	406-05520	ASPHALT FOR TACK COAT	22.00	TON
	0027	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	32.00	TON
	0028	501-06266	PROFILOGRAPH PCCP	1.00	LS
	0029	501-06727	CORING, PCCP	1.00	LS
	0030	501-12179	QC/QA-PCC, THIN BONDED OVERLAY, 5 IN.	84569.00	SYS
	0031	501-12183	QC/QA-PCC, ADDITIONAL	681.00	CYS

0032	601-02241	GUARDRAIL, REMOVE	660.00	LFT
0033	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	986.00	LFT
0034	601-94689	GUARDRAIL, END TREATMENT, OS	8.00	EACH
0035	604-06070	SIDEWALK, CONCRETE	424.00	SYS
0036	604-08086	CURB RAMP, CONCRETE	136.00	SYS
0037	604-12083	DETECTABLE WARNING SURFACES	31.00	SYS
0038	605-06120	CURB, CONCRETE	2269.00	LFT
0039	605-06140	CURB AND GUTTER, CONCRETE	46.00	LFT
0040	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	32.00	LFT
0041	606-11064	MILLED PCCP CORRUGATIONS, CONVENTIONAL	31714.00	LFT
0042	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	5792.00	LFT
0043	610-07487	HMA FOR APPROACHES, TYPE B	905.00	TON
0044	615-06520	MONUMENT, RE-ESTABLISH	48.00	EACH
0045	621-06567	WATER	1.00	KGAL
0046	621-06575	SODDING, NURSERY	16.00	SYS
0047	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0048	628-12683	FIELD OFFICE, D	12.00	MOS
0049	720-12797	CASTING, INLET, ADJUST TO GRADE	4.00	EACH
0050	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	3.00	EACH
0051	720-44015	CASTING, 2, FURNISH AND ADJUST TO GRADE	1.00	EACH
0052	720-44045	CASTING, 8, FURNISH AND ADJUST TO GRADE	3.00	EACH
0053	720-44080	CASTING, 15, FURNISH AND ADJUST TO GRADE	1.00	EACH
0054	720-45605	STRUCTURE, MANHOLE, RECONSTRUCTED	3.00	LFT
0055	720-45615	STRUCTURE, INLET, RECONSTRUCTED	2.00	LFT
0056	801-03291	CONSTRUCTION SIGN, D	20.00	EACH
0057	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00	EACH
0058	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	4726.00	LFT
0059	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4671.00	LFT
0060	801-06625	DETOUR ROUTE MARKER ASSEMBLY	29.00	EACH
0061	801-06640	CONSTRUCTION SIGN, A	31.00	EACH
0062	801-06645	CONSTRUCTION SIGN, B	38.00	EACH
0063	801-06775	MAINTAINING TRAFFIC	1.00	LS
0064	801-07118	BARRICADE, III-A	216.00	LFT
0065	801-07119	BARRICADE, III-B	72.00	LFT
0066	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0067	801-11990	TEMPORARY CURB RAMP	2.00	EACH
0068	801-12081	PORTABLE SIGNAL	1.00	LS

0069	801-12482	DRIVEWAY ASSISTANCE DEVICE	20.00	EACH
0070	808-01428	TEMPORARY TRANSVERSE MARKINGS WHITE STOP LINE 24 IN.	96.00	LFT
0071	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0072	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	92219.00	LFT
0073	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	70978.00	LFT
0074	808-10099	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSWALK LINE, WHITE, 24 IN.	37.00	LFT
0075	808-12032	GROOVING FOR PAVEMENT MARKINGS	168017.00	LFT
0076	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	4820.00	LFT
0077	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	937.00	EACH
0078	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	937.00	EACH

Call: 170

Contract: R -41509-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-52710	SIDEWALK CONCRETE, REMOVE	557.00 SYS
0012	202-74035	SIGN, REMOVE	2.00 EACH
0013	202-90277	DETECTOR HOUSING, REMOVE	3.00 EACH
0014	202-91385	INLET, REMOVE	9.00 EACH
0015	202-93996	PEDESTAL BASE, REMOVE	6.00 EACH
0016	205-12108	STORMWATER MANAGEMENT BUDGET	3520.00 DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0018	207-12151	SUBGRADE TREATMENT, TYPE IVA	1043.00 SYS
0019	304-12625	HMA PATCHING FULL DEPTH, TYPE C	574.00 TON
0020	306-08038	MILLING, ASPHALT, 4 IN.	20082.00 SYS
0021	306-08039	MILLING, ASPHALT REMOVAL	7021.00 SYS
0022	306-08041	MILLING, PCCP	7021.00 SYS
0023	306-08043	MILLING, TRANSITION	2085.00 SYS
0024	306-08432	MILLING, APPROACH	2744.00 SYS
0025	401-07334	QC/QA-HMA, 3, 76, SURFACE, 9.5 mm	2409.00 TON
0026	401-07403	QC/QA-HMA, 3, 76, INTERMEDIATE, 19.0 mm	4014.00 TON
0027	401-10258	JOINT ADHESIVE, SURFACE	6544.00 LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	6544.00 LFT
0029	401-11785	LIQUID ASPHALT SEALANT	6544.00 LFT
0030	406-05520	ASPHALT FOR TACK COAT	22.00 TON
0031	604-06070	SIDEWALK, CONCRETE	178.00 SYS

0032	604-08086	CURB RAMP, CONCRETE	406.00	SYS
0033	604-12083	DETECTABLE WARNING SURFACES	73.00	SYS
0034	604-12084	DETECTABLE WARNING SURFACES, RETROFIT	8.00	SYS
0035	605-02278	CURB, REMOVE	1382.00	LFT
0036	605-06125	CURB, CONCRETE, MODIFIED	1382.00	LFT
0037	610-07788	HMA FOR APPROACHES, TYPE D	604.00	TON
0038	615-06505	MONUMENT, B	5.00	EACH
0039	621-06567	WATER	1.00	KGAL
0040	621-06574	SODDING	64.00	SYS
0041	628-09403	FIELD OFFICE, C	12.00	MOS
0042	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0043	720-01917	CASTING, MODIFIED	1.00	EACH
0044	720-12797	CASTING, INLET, ADJUST TO GRADE	1.00	EACH
0045	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	56.00	EACH
0046	720-45010	INLET, A3	5.00	EACH
0047	720-45015	INLET, A8	1.00	EACH
0048	720-45045	INLET, J10	2.00	EACH
0049	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	5.00	EACH
0050	801-04308	ROAD CLOSURE SIGN ASSEMBLY	20.00	EACH
0051	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	19500.00	LFT
0052	801-06640	CONSTRUCTION SIGN, A	24.00	EACH
0053	801-06645	CONSTRUCTION SIGN, B	12.00	EACH
0054	801-06710	FLASHING ARROW SIGN	120.00	DAY
0055	801-06775	MAINTAINING TRAFFIC	1.00	LS
0056	801-07119	BARRICADE, III-B	400.00	LFT
0057	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	34.00	LFT
0058	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	15.00	SFT
0059	802-93675	MARKER, HISTORIC, RESET	12.00	EACH
0060	805-01300	TRAFFIC SIGNAL EQUIPMENT, REMOVE	14.00	EACH
0061	805-02150	PEDESTRIAN SIGNAL HEAD, COUNTDOWN, 18 IN.	28.00	EACH
0062	805-06595	CONDUIT, PVC, 2 IN.	858.00	LFT
0063	805-11817	PEDESTRIAN PUSH BUTTON, APS	28.00	EACH
0064	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	1752.00	LFT
0065	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	2329.00	LFT
0066	805-78785	SIGNAL DETECTOR HOUSING	3.00	EACH
0067	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	496.00	LFT
0068	805-90005	SIGNAL POLE, PEDESTAL, 10 FT	14.00	EACH

0069	805-96309	PEDESTRIAN PUSH BUTTON, RETROFIT	4.00 EACH
0070	808-03439	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 24 IN.	456.00 LFT
0071	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	187.00 LFT
0072	808-06716	LINE, REMOVE	7200.00 LFT
0073	808-09450	CROSSWALK, DECORATIVE THERMOPLASTIC	1007.00 SFT
0074	808-11650	LINE, THERMOPLASTIC, DOTTED, WHITE, 6 IN.	52.00 LFT
0075	808-12032	GROOVING FOR PAVEMENT MARKINGS	4980.00 LFT
0076	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE 4 IN.	1220.00 LFT
0077	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	2169.00 LFT
0078	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	674.00 LFT
0079	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	607.00 LFT
0080	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	1950.00 LFT
0081	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	29.00 EACH
0082	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	9.00 EACH
0083	808-96075	LINE, THERMOPLASTIC, BROKEN, WHITE, 6 IN.	1950.00 LFT

Call: 180

Contract: R -41552-A

Section No.: 1

SMALL STRUCTURE PIPE LINING

Line			Quantity	Unit
Item No	Item Code	Description		
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00	EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0004	109-08360	CONTRACT LIENS	1.00	DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0014	202-91385	INLET, REMOVE	2.00	EACH
0015	202-96133	PIPE, REMOVE	157.00	LFT
0016	202-99187	FENCE, FARM FIELD, REMOVE	335.00	LFT
0017	203-02000	EXCAVATION, COMMON	1369.00	CYS
0018	203-02070	BORROW	680.00	CYS
0019	205-11626	PUMP AROUND	2.00	EACH
0020	205-12108	STORMWATER MANAGEMENT BUDGET	14187.30	DOL
0021	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0022	205-12618	SWQCP PREPARATION	1.00	LS
0023	207-12498	SUBGRADE TREATMENT, TYPE ID	378.00	SYS
0024	211-09265	STRUCTURE BACKFILL, TYPE 2	198.00	CYS
0025	211-09266	STRUCTURE BACKFILL, TYPE 3	65.00	CYS
0026	211-09268	STRUCTURE BACKFILL, TYPE 5	271.00	CYS
0027	301-12233	COMPACTED AGGREGATE NO. 8	78.00	CYS
0028	303-01180	COMPACTED AGGREGATE NO. 53	88.00	TON
0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	168.00	SYS
0030	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	42.00	TON
0031	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	47.00	TON

0032	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	156.00 TON
0033	401-10258	JOINT ADHESIVE, SURFACE	150.00 LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	100.00 LFT
0035	401-11785	LIQUID ASPHALT SEALANT	150.00 LFT
0036	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0037	603-06042	FENCE, FARM FIELD, BARBED WIRE	360.00 LFT
0038	615-06490	RIGHT-OF-WAY MARKER	6.00 EACH
0039	615-06505	MONUMENT, B	2.00 EACH
0040	616-05689	RIPRAP, CLASS 2	748.00 TON
0041	616-06405	RIPRAP, REVETMENT	227.00 TON
0042	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	430.00 SYS
0043	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	1012.00 SYS
0044	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00 EACH
0045	621-06559	MULCHED SEEDING R	3211.00 SYS
0046	621-06574	SODDING	221.00 SYS
0047	628-09403	FIELD OFFICE, C	8.00 MOS
0048	702-51005	CONCRETE, A, SUBSTRUCTURE	18.00 CYS
0049	702-51015	CONCRETE, B, FOOTINGS	35.00 CYS
0050	714-11182	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 10 FT X 5 FT	120.00 LFT
0051	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	106.00 LFT
0052	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	36.00 LFT
0053	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	4.00 LFT
0054	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	212.00 LFT
0055	715-09064	VIDEO INSPECTION FOR PIPE	358.00 LFT
0056	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00 EACH
0057	720-45030	INLET, E7	1.00 EACH
0058	720-45410	MANHOLE, C4	2.00 EACH
0059	720-45515	MANHOLE, D4 MODIFIED	1.00 EACH
0060	725-11986	LINER PIPE, THERMOPLASTIC, CIRCULAR, 76.9-78.6 SFT	175.00 LFT
0061	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00 EACH
0062	801-06625	DETOUR ROUTE MARKER ASSEMBLY	35.00 EACH
0063	801-06640	CONSTRUCTION SIGN, A	35.00 EACH
0064	801-06645	CONSTRUCTION SIGN, B	2.00 EACH
0065	801-06775	MAINTAINING TRAFFIC	1.00 LS
0066	801-07118	BARRICADE, III-A	144.00 LFT
0067	801-07119	BARRICADE, III-B	104.00 LFT
0068	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	40.00 LFT

0069 808-06713 LINE, PAINT, SOLID, WHITE, 4 IN.

300.00 LFT

Call: 190

Contract: R -41896-A

Section No.: 1 BIKE AND PEDESTRIAN FACILITIES

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-02240	PAVEMENT REMOVAL	115.00 SYS
0012	202-02278	CURB, CONCRETE, REMOVE	783.00 LFT
0013	202-02279	CURB AND GUTTER, REMOVE	109.00 LFT
0014	202-04650	PARKING METER	4.00 EACH
0015	202-52710	SIDEWALK CONCRETE, REMOVE	466.00 SYS
0016	202-91385	INLET, REMOVE	3.00 EACH
0017	203-02000	EXCAVATION, COMMON	152.00 CYS
0018	205-12108	STORMWATER MANAGEMENT BUDGET	550.00 DOL
0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	180.00 SYS
0021	211-09266	STRUCTURE BACKFILL, TYPE 3	15.00 CYS
0022	214-12237	GEOTEXTILE FOR PAVEMENT, TYPE 1B	180.00 SYS
0023	301-12233	COMPACTED AGGREGATE NO. 8	5.00 CYS
0024	302-07455	DENSE GRADED SUBBASE	30.00 CYS
0025	303-01180	COMPACTED AGGREGATE NO. 53	107.00 TON
0026	304-12624	HMA PATCHING PARTIAL DEPTH, TYPE B	19.00 TON
0027	305-07464	PCC BASE PATCHING, 9 IN.	229.00 SYS
0028	306-08599	MILLING, ASPHALT, 1/2 IN.	124.00 SYS
0029	401-10258	JOINT ADHESIVE, SURFACE	1033.00 LFT
0030	406-05521	ASPHALT FOR TACK COAT	346.00 SYS
0031	604-06070	SIDEWALK, CONCRETE	245.00 SYS

0032	604-08086	CURB RAMP, CONCRETE	245.00	SYS
0033	604-12083	DETECTABLE WARNING SURFACES	25.00	SYS
0034	605-06120	CURB, CONCRETE	1008.00	LFT
0035	605-06121	CURB, CONCRETE B	40.00	LFT
0036	605-06155	CURB AND GUTTER, CONCRETE, MODIFIED	9.00	LFT
0037	610-07487	HMA FOR APPROACHES, TYPE B	18.00	TON
0038	610-09108	PCCP FOR APPROACHES, 9 IN.	180.00	SYS
0039	621-06570	TOPSOIL	45.00	CYS
0040	621-06575	SODDING, NURSERY	186.00	SYS
0041	621-98038	MULCH HARDWOOD SHREDDED BARK	7.00	CYS
0042	702-90915	CONCRETE, CLASS, A	3.00	CYS
0043	715-05148	PIPE, TYPE 2, CIRCULAR, 10 IN.	10.00	LFT
0044	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	14.00	LFT
0045	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00	EACH
0046	720-04682	INLET	3.00	EACH
0047	720-07309	TRENCH DRAIN	6.00	LFT
0048	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00	EACH
0049	720-45045	INLET, J10	1.00	EACH
0050	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	2.00	EACH
0051	801-06775	MAINTAINING TRAFFIC	1.00	LS
0052	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	96.00	LFT
0053	802-07060	SIGN, SHEET, RELOCATE	17.00	EACH
0054	808-05929	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 8 IN.	43.00	LFT
0055	808-12448	CURB PAINTING	291.00	LFT

Call: 200

Contract: R -42463-D

Section No.: 1 CONCRETE PAVEMENT RESTORATION

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	207-08264	SUBGRADE TREATMENT, TYPE II	1427.20 SYS
0012	214-11796	GEOGRID, TYPE IB	1427.20 SYS
0013	302-06464	SUBBASE FOR PCCP	356.80 CYS
0014	303-01180	COMPACTED AGGREGATE NO. 53	298.00 TON
0015	306-08038	MILLING, ASPHALT, 4 IN.	6850.00 SYS
0016	306-08039	MILLING, ASPHALT REMOVAL	32230.00 SYS
0017	401-07329	QC/QA-HMA, 4, 70, SURFACE, 9.5 mm	3224.00 TON
0018	401-07399	QC/QA-HMA, 4, 70, INTERMEDIATE, 19.0 mm	8740.00 TON
0019	401-10258	JOINT ADHESIVE, SURFACE	12820.00 LFT
0020	401-10259	JOINT ADHESIVE, INTERMEDIATE	12820.00 LFT
0021	401-11785	LIQUID ASPHALT SEALANT	12820.00 LFT
0022	406-05520	ASPHALT FOR TACK COAT	20.00 TON
0023	502-12153	PCCP PRECAST, REMOVABLE	2213.00 SYS
0024	503-03489	RETROFITTED TIE BARS	150.00 EACH
0025	503-05240	D-1 CONTRACTION JOINT	1363.00 LFT
0026	506-06333	PCCP PATCHING, FULL DEPTH	1427.20 SYS
0027	509-12191	JOINT REPAIR, PARTIAL DEPTH	6815.50 SFT
0028	628-11729	CELLULAR TELEPHONE, TYPE A	2.00 EACH
0029	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00 DOL
0030	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00 DOL
0031	628-11781	CELLULAR TELEPHONE SERVICE, 750 MIN.	18.00 MOS

0032	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0033	628-12683	FIELD OFFICE, D	18.00 MOS
0034	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	20.00 EACH
0035	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00 EACH
0036	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	726439.00 LFT
0037	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00 EACH
0038	801-06640	CONSTRUCTION SIGN, A	86.00 EACH
0039	801-06645	CONSTRUCTION SIGN, B	6.00 EACH
0040	801-06710	FLASHING ARROW SIGN	420.00 DAY
0041	801-06775	MAINTAINING TRAFFIC	1.00 LS
0042	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	6.00 EACH
0043	801-07118	BARRICADE, III-A	58.00 LFT
0044	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	19776.00 LFT
0045	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	1344.00 LFT
0046	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	6.00 EACH
0047	801-11845	AUTOMATED WORK ZONE INFORMATION SYSTEM, DETECTORS	1.00 EACH
0048	801-12042	TRUCK MOUNTED ATTENUATOR	300.00 DAY
0049	801-12324	LAW ENFORCEMENT OFFICER	600.00 HRS
0050	801-12421	AUTOMATED WORK ZONE INFORMATION SYSTEM	1.00 LS
0051	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	5600.00 LFT
0052	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	2120.00 LFT
0053	808-06716	LINE, REMOVE	290928.00 LFT
0054	808-09381	RETRO-REFLECTIVITY TESTING	1.00 LS
0055	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	57426.00 LFT
0056	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	57150.00 LFT
0057	808-10047	TRANSVERSE MARKING, MULTI-COMPONENT, CROSSHATCH LINE, WHITE, 12 IN.	117.00 LFT
0058	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	126871.00 LFT
0059	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	30.00 LFT
0060	808-10054	LINE, MULTI-COMPONENT, BROKEN, WHITE, 5 IN.	24236.00 LFT
0061	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	126200.00 LFT
0062	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN	58393.00 LFT
0063	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	11.00 EACH
0064	808-12032	GROOVING FOR PAVEMENT MARKINGS	311464.00 LFT
0065	808-12781	LINE, MULTI-COMPONENT, SOLID, WHITE, 10 IN.	180.00 LFT
0066	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	55.00 EACH
0067	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	55.00 EACH

Call: 210

Contract: R -43068-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0010	202-02278	CURB, CONCRETE, REMOVE	22.00 LFT
0011	202-02279	CURB AND GUTTER, REMOVE	273.00 LFT
0012	202-52710	SIDEWALK CONCRETE, REMOVE	215.00 SYS
0013	202-90277	DETECTOR HOUSING, REMOVE	2.00 EACH
0014	203-02070	BORROW	133.00 CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	1900.00 DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0017	207-08264	SUBGRADE TREATMENT, TYPE II	183.00 SYS
0018	214-11796	GEOGRID, TYPE IB	183.00 SYS
0019	301-12234	COMPACTED AGGREGATE NO. 53	28.00 CYS
0020	303-01180	COMPACTED AGGREGATE NO. 53	25.00 TON
0021	304-12626	HMA PATCHING PARTIAL, DEPTH TYPE C	202.00 TON
0022	306-08034	MILLING, ASPHALT, 1 1/2 IN.	6664.00 SYS
0023	306-08043	MILLING, TRANSITION	1100.00 SYS
0024	306-08432	MILLING, APPROACH	863.00 SYS
0025	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	671.00 TON
0026	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	242.00 TON
0027	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	145.00 TON
0028	401-10258	JOINT ADHESIVE, SURFACE	5178.00 LFT
0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	675.00 LFT
0030	401-11785	LIQUID ASPHALT SEALANT	5178.00 LFT
0031	406-05520	ASPHALT FOR TACK COAT	4.00 TON

0032	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.00	TON
0033	604-03643	BRICK PAVERS	4.00	SYS
0034	604-06070	SIDEWALK, CONCRETE	61.00	SYS
0035	604-08086	CURB RAMP, CONCRETE	143.00	SYS
0036	604-12083	DETECTABLE WARNING SURFACES	26.00	SYS
0037	605-06140	CURB AND GUTTER, CONCRETE	277.00	LFT
0038	610-07487	HMA FOR APPROACHES, TYPE B	162.00	TON
0039	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	1.00	EACH
0040	615-06520	MONUMENT, RE-ESTABLISH	5.00	EACH
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0042	621-04258	SEED MIXTURE	28.00	LBS
0043	621-06567	WATER	2.00	KGAL
0044	621-06570	TOPSOIL	121.00	CYS
0045	621-06575	SODDING, NURSERY	50.00	SYS
0046	628-09403	FIELD OFFICE, C	12.00	MOS
0047	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0048	720-01894	CASTING, FURNISH AND ADJUST TO GRADE	1.00	EACH
0049	720-12797	CASTING, INLET, ADJUST TO GRADE	2.00	EACH
0050	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	3.00	EACH
0051	720-44045	CASTING, 8, FURNISH AND ADJUST TO GRADE	3.00	EACH
0052	720-94840	CASTING, WATER VALVE, ADJUST TO GRADE	6.00	EACH
0053	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0054	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1941.00	LFT
0055	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	236.00	LFT
0056	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	862.00	LFT
0057	801-06640	CONSTRUCTION SIGN, A	43.00	EACH
0058	801-06645	CONSTRUCTION SIGN, B	52.00	EACH
0059	801-06775	MAINTAINING TRAFFIC	1.00	LS
0060	801-07119	BARRICADE, III-B	76.00	LFT
0061	801-11990	TEMPORARY CURB RAMP	12.00	EACH
0062	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	10.00	SYS
0063	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	27.60	LFT
0064	802-07060	SIGN, SHEET, RELOCATE	2.00	EACH
0065	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	1.00	SFT
0066	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0067	805-01843	HANDHOLE, SIGNAL, ADJUST TO GRADE	2.00	EACH
0068	805-09539	LOOP DETECTOR DELAY AMPLIFIER, COUNTING, 2 CHANNEL	1.00	EACH

0069	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	42.00	LFT
0070	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	860.00	LFT
0071	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	120.00	LFT
0072	805-78785	SIGNAL DETECTOR HOUSING	2.00	EACH
0073	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	300.00	LFT
0074	805-96309	PEDESTRIAN PUSH BUTTON, RETROFIT	1.00	EACH
0075	808-06368	TRANSVERSE MARKING, REMOVE	227.00	LFT
0076	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	1269.00	LFT
0077	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	2312.00	LFT
0078	808-12032	GROOVING FOR PAVEMENT MARKINGS	3801.00	LFT
0079	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE 4 IN.	184.00	LFT
0080	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	220.00	LFT
0081	808-75278	TRANSVERSE MARKING, THERMOPLASTIC, CROSSHATCH LINE, YELLOW, 12 IN.	102.00	LFT
0082	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	166.00	LFT
0083	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	882.00	LFT
0084	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	2.00	EACH

Call: 220

Contract: R -43645-C

Section No.: 1 ASPHALT RESURFACE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	10.00	EACH
	0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	20.00	EACH
	0004	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0005	109-08360	CONTRACT LIENS	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0012	202-02240	PAVEMENT REMOVAL	47.00	SYS
	0013	202-97009	FIRE HYDRANT ASSEMBLY, REMOVE	3.00	EACH
	0014	203-02000	EXCAVATION, COMMON	1253.00	CYS
	0015	205-12108	STORMWATER MANAGEMENT BUDGET	13201.00	DOL
	0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0017	205-12618	SWQCP PREPARATION	1.00	LS
	0018	207-08264	SUBGRADE TREATMENT, TYPE II	2042.00	SYS
	0019	207-09935	SUBGRADE TREATMENT, TYPE IC	3521.00	SYS
	0020	211-02050	B BORROW	275.00	CYS
	0021	211-09265	STRUCTURE BACKFILL, TYPE 2	892.00	CYS
	0022	214-11796	GEOGRID, TYPE IB	978.00	SYS
	0023	301-12234	COMPACTED AGGREGATE NO. 53	123.00	CYS
	0024	302-07455	DENSE GRADED SUBBASE	194.00	CYS
	0025	303-01180	COMPACTED AGGREGATE NO. 53	92.00	TON
	0026	304-07493	WIDENING WITH HMA, TYPE B	512.00	TON
	0027	304-12623	HMA PATCHING FULL DEPTH, TYPE B	467.00	TON
	0028	304-12624	HMA PATCHING PARTIAL DEPTH, TYPE B	186.00	TON
	0029	306-08034	MILLING, ASPHALT, 1 1/2 IN.	6508.00	SYS
	0030	306-08036	MILLING, ASPHALT, 2 IN.	2448.00	SYS
	0031	306-08038	MILLING, ASPHALT, 4 IN.	845.00	SYS

0032	306-08432	MILLING, APPROACH	332.00	SYS
0033	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	1073.00	TON
0034	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	1533.00	TON
0035	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	164.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	5933.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	4154.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	5933.00	LFT
0039	406-05520	ASPHALT FOR TACK COAT	6.00	TON
0040	604-06070	SIDEWALK, CONCRETE	1082.00	SYS
0041	604-08086	CURB RAMP, CONCRETE	62.00	SYS
0042	604-12083	DETECTABLE WARNING SURFACES	21.00	SYS
0043	605-06100	CURB, INTEGRAL C CONCRETE	25.00	LFT
0044	605-06140	CURB AND GUTTER, CONCRETE	2261.00	LFT
0045	605-08636	CURB AND GUTTER, TURNOUT COMBINED	8.00	LFT
0046	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	1872.00	LFT
0047	610-07487	HMA FOR APPROACHES, TYPE B	34.00	TON
0048	610-08446	PCCP FOR APPROACHES, 6 IN.	951.00	SYS
0049	610-09108	PCCP FOR APPROACHES, 9 IN.	211.00	SYS
0050	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0051	615-06525	CASTING ADJUST TO GRADE, MONUMENT	1.00	EACH
0052	621-06574	SODDING	2193.00	SYS
0053	628-09403	FIELD OFFICE, C	12.00	MOS
0054	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0055	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0056	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0057	628-11781	CELLULAR TELEPHONE SERVICE, 750 MIN.	12.00	MOS
0058	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0059	628-11977	COMPUTER SYSTEM	1.00	EACH
0060	715-02181	SANITARY SEWER SERVICE ADJUSTMENT	15.00	LFT
0061	715-04596	WATER SERVICE	6.00	EACH
0062	715-04965	WATER SERVICE LINE	325.00	LFT
0063	715-04995	LINE STOP	1.00	EACH
0064	715-04995	LINE STOP	3.00	EACH
0065	715-05024	PIPE, TYPE 2, CIRCULAR, 36 IN.	108.00	LFT
0066	715-05032	PIPE, TYPE 2, CIRCULAR, 15 IN.	10.00	LFT
0067	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	1766.00	LFT
0068	715-06050	CAP	11.00	EACH

0069	715-08048	STORMWATER TREATMENT SYSTEM	1.00 EACH
0070	715-08305	HMA FOR STRUCTURE INSTALLATION, TYPE B	181.00 TON
0071	715-11896	WATER SERVICE CONNECTION	11.00 EACH
0072	715-90853	TAPPING SLEEVE WITH VALVE	5.00 EACH
0073	715-91361	PIPE PVC 6 IN	1100.00 LFT
0074	715-95866	GATE VALVE 6 IN.	7.00 EACH
0075	720-02442	PIPE PLUG EXISTING	2.00 EACH
0076	720-03481	MANHOLE, H4 MODIFIED	1.00 EACH
0077	720-04666	CATCH BASIN	10.00 EACH
0078	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	10.00 EACH
0079	720-45030	INLET, E7	4.00 EACH
0080	720-45035	INLET, F7	3.00 EACH
0081	720-45410	MANHOLE, C4	5.00 EACH
0082	720-90349	MANHOLE, C8	4.00 EACH
0083	720-91973	MANHOLE, H4	3.00 EACH
0084	720-96999	FIRE HYDRANT ASSEMBLY	3.00 EACH
0085	720-98174	INLET, B15	9.00 EACH
0086	720-98555	INLET, C15	15.00 EACH
0087	801-03290	CONSTRUCTION SIGN, C	1.00 EACH
0088	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00 EACH
0089	801-06625	DETOUR ROUTE MARKER ASSEMBLY	36.00 EACH
0090	801-06640	CONSTRUCTION SIGN, A	16.00 EACH
0091	801-06775	MAINTAINING TRAFFIC	1.00 LS
0092	801-07118	BARRICADE, III-A	252.00 LFT
0093	801-07119	BARRICADE, III-B	78.00 LFT
0094	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	237.00 LFT
0095	802-05705	SIGN POST, SQUARE, TYPE 2, UNREINFORCED ANCHOR BASE	26.00 LFT
0096	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	81.00 SFT
0097	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	12.00 SFT
0098	808-12032	GROOVING FOR PAVEMENT MARKINGS	8742.00 LFT
0099	808-12273	TRANSVERSE MARKING, THERMOPLASTIC, PARKING LINE, WHITE 4 IN.	717.00 LFT
0100	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	4550.00 LFT
0101	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	3045.00 LFT
0102	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	73.00 LFT
0103	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	570.00 LFT
0104	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	60.00 EACH
0105	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	577.00 LFT

Call: 230

Contract: R -43664-A

Section No.: 1

SMALL STRUCTURE, NEW

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-02250	TREE 10 IN., REMOVE	2.00	EACH
	0012	201-02255	TREE 18 IN., REMOVE	2.00	EACH
	0013	201-02260	TREE 30 IN., REMOVE	5.00	EACH
	0014	201-02265	TREE 48 IN., REMOVE	1.00	EACH
	0015	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0016	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0017	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0018	203-02000	EXCAVATION, COMMON	3042.00	CYS
	0019	203-02070	BORROW	200.00	CYS
	0020	205-11626	PUMP AROUND	2.00	EACH
	0021	205-12108	STORMWATER MANAGEMENT BUDGET	27500.00	DOL
	0022	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0023	205-12618	SWQCP PREPARATION	1.00	LS
	0024	207-12498	SUBGRADE TREATMENT, TYPE ID	2426.00	SYS
	0025	211-09265	STRUCTURE BACKFILL, TYPE 2	1116.00	CYS
	0026	211-09268	STRUCTURE BACKFILL, TYPE 5	320.00	CYS
	0027	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	1509.00	SYS
	0028	301-12232	COMPACTED AGGREGATE NO. 5	86.00	CYS
	0029	301-12234	COMPACTED AGGREGATE NO. 53	211.00	CYS
	0030	303-01180	COMPACTED AGGREGATE NO. 53	274.00	TON
	0031	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1778.00	SYS

0032	306-08043	MILLING, TRANSITION	1018.00	SYS
0033	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	334.00	TON
0034	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	299.00	TON
0035	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1025.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	2661.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	1661.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	2661.00	LFT
0039	406-05520	ASPHALT FOR TACK COAT	3.00	TON
0040	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	7.00	TON
0041	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0042	601-02241	GUARDRAIL, REMOVE	350.00	LFT
0043	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	324.50	LFT
0044	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	1.00	EACH
0045	601-12293	GUARDRAIL, MGS, STRUCTURE, TOP-MOUNTED POST	6.00	EACH
0046	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0047	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	1200.00	LFT
0048	615-06490	RIGHT-OF-WAY MARKER	10.00	EACH
0049	615-06505	MONUMENT, B	4.00	EACH
0050	616-05688	RIPRAP, CLASS 1	49.00	TON
0051	616-06405	RIPRAP, REVETMENT	838.00	TON
0052	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1439.00	SYS
0053	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0054	621-03909	SEED MIXTURE, NATIVE	21.00	LBS
0055	621-06559	MULCHED SEEDING R	2705.00	SYS
0056	622-05638	PLANT, DECIDUOUS SHRUB, 18 IN. OR UNDER	7.00	EACH
0057	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. TO 2 IN.	14.00	EACH
0058	628-09403	FIELD OFFICE, C	13.00	MOS
0059	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0060	714-11161	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 20 FT X 12 FT	44.00	LFT
0061	714-11749	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 15 FT X 8 FT	158.00	LFT
0062	715-05248	PIPE, TYPE 1, DEFORMED, MIN. AREA 16.6 SFT	200.00	LFT
0063	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0064	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00	EACH
0065	801-06625	DETOUR ROUTE MARKER ASSEMBLY	62.00	EACH
0066	801-06640	CONSTRUCTION SIGN, A	28.00	EACH
0067	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0068	801-06775	MAINTAINING TRAFFIC	1.00	LS

0069	801-07118	BARRICADE, III-A	168.00	LFT
0070	801-07119	BARRICADE, III-B	156.00	LFT
0071	802-91122	SIGN GROUND MOUNTED RESET	6.00	EACH
0072	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1092.00	LFT
0073	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	110.00	LFT
0074	808-10051	TRANSVERSE MARKING, MULTI-COMPONENT, STOP LINE, WHITE, 24 IN.	32.00	LFT
0075	808-12032	GROOVING FOR PAVEMENT MARKINGS	334.00	LFT

Call: 240

Contract: R -43708-A

Section No.: 1 ASPHALT RESURFACE

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	202-02278	CURB, CONCRETE, REMOVE	120.00 LFT
0011	202-07083	REMOVAL	1.00 LS
0012	202-52710	SIDEWALK CONCRETE, REMOVE	123.00 SYS
0013	202-91385	INLET, REMOVE	1.00 EACH
0014	205-12108	STORMWATER MANAGEMENT BUDGET	2000.00 DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0016	207-08268	SUBGRADE TREATMENT, TYPE IV	3356.00 SYS
0017	211-09264	STRUCTURE BACKFILL, TYPE 1	5.00 CYS
0018	304-12623	HMA PATCHING FULL DEPTH, TYPE B	13.00 TON
0019	306-08038	MILLING, ASPHALT, 4 IN.	16404.00 SYS
0020	306-08432	MILLING, APPROACH	422.00 SYS
0021	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	1354.00 TON
0022	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	2256.00 TON
0023	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	2563.00 TON
0024	401-10258	JOINT ADHESIVE, SURFACE	8169.00 LFT
0025	401-10259	JOINT ADHESIVE, INTERMEDIATE	8169.00 LFT
0026	401-11785	LIQUID ASPHALT SEALANT	8169.00 LFT
0027	406-05520	ASPHALT FOR TACK COAT	11.00 TON
0028	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	1.00 TON
0029	604-06070	SIDEWALK, CONCRETE	33.00 SYS
0030	604-08086	CURB RAMP, CONCRETE	110.00 SYS
0031	604-12083	DETECTABLE WARNING SURFACES	25.00 SYS

0032	605-06120	CURB, CONCRETE	147.00	LFT
0033	610-07487	HMA FOR APPROACHES, TYPE B	93.00	TON
0034	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0035	621-06560	MULCHED SEEDING U	75.00	SYS
0036	628-09403	FIELD OFFICE, C	6.00	MOS
0037	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	5.00	LFT
0038	720-12796	CASTING, CATCH BASIN, ADJUST TO GRADE	1.00	EACH
0039	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	9.00	EACH
0040	720-45042	INLET, HA5	1.00	EACH
0041	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0042	801-01504	TEMPORARY PAVEMENT MESSAGE MARKING, LANE INDICATION ARROW	9.00	EACH
0043	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	22196.00	LFT
0044	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	9983.00	LFT
0045	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	11.00	LFT
0046	801-06217	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 6 IN.	330.00	LFT
0047	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	80.00	LFT
0048	801-06640	CONSTRUCTION SIGN, A	31.00	EACH
0049	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0050	801-06710	FLASHING ARROW SIGN	180.00	DAY
0051	801-06775	MAINTAINING TRAFFIC	1.00	LS
0052	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	4.00	EACH
0053	801-07118	BARRICADE, III-A	113.00	LFT
0054	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	5694.00	LFT
0055	801-11990	TEMPORARY CURB RAMP	19.00	EACH
0056	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	48.00	SYS
0057	808-06716	LINE, REMOVE	2735.00	LFT
0058	808-12032	GROOVING FOR PAVEMENT MARKINGS	4922.00	LFT
0059	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	4922.00	LFT
0060	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	84.00	LFT
0061	808-75300	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK LINE, WHITE, 6 IN.	360.00	LFT
0062	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	1.00	EACH

Call: 270

Contract: R -44424-A

Section No.: 1 TREE REMOVAL AND TRIMMING

Line			Quantity	Unit
Item No	Item Code	Description		
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0006	201-01015	CLEARING AND GRUBBING	1.00	LS
0007	201-02245	TREE 6 IN., REMOVE	110.00	EACH
0008	201-02250	TREE 10 IN., REMOVE	65.00	EACH
0009	201-02255	TREE 18 IN., REMOVE	45.00	EACH
0010	201-02260	TREE 30 IN., REMOVE	10.00	EACH
0011	201-02265	TREE 48 IN., REMOVE	2.00	EACH
0012	201-02270	TREE 60 IN., REMOVE	2.00	EACH
0013	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	8.00	EACH
0014	801-06640	CONSTRUCTION SIGN, A	24.00	EACH
0015	801-06710	FLASHING ARROW SIGN	20.00	DAY
0016	801-06775	MAINTAINING TRAFFIC	1.00	LS

Call: 290

Contract: B -39491-B

Section No.: 1

REPLACE SUPERSTRUCTURE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
	0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0012	113-01614	PARTNERING OVERHEAD	1.00	LS
	0013	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0014	202-02240	PAVEMENT REMOVAL	7410.00	SYS
	0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0016	202-74080	OVERHEAD SIGN STRUCTURE, CANTILEVER, REMOVE	3.00	EACH
	0017	202-93741	GUARDRAIL, END TREATMENT, REMOVE	5.00	EACH
	0018	203-02000	EXCAVATION, COMMON	5147.00	CYS
	0019	203-02000	EXCAVATION, COMMON	708.00	CYS
	0020	203-02588	LAGGING, PRECAST CONCRETE	133.00	SYS
	0021	203-08279	EXPANDED POLYSTYRENE FILL	141.00	CYS
	0022	204-08396	STANDPIPE PIEZOMETER	18.00	EACH
	0023	204-08415	STAKE, SETTLEMENT	9.00	EACH
	0024	205-12108	STORMWATER MANAGEMENT BUDGET	22479.00	DOL
	0025	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0026	205-12618	SWQCP PREPARATION	1.00	LS
	0027	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	1981.00	CYS
	0028	207-08264	SUBGRADE TREATMENT, TYPE II	166.00	SYS
	0029	207-09935	SUBGRADE TREATMENT, TYPE IC	1218.00	SYS
	0030	207-12635	SUBGRADE TREATMENT, TYPE IBC	8779.00	SYS
	0031	211-02050	B BORROW	1077.00	CYS

0032	211-06467	AGGREGATE FOR END BENT BACKFILL	82.00	CYS
0033	211-09264	STRUCTURE BACKFILL, TYPE 1	55.00	CYS
0034	214-12238	GEOTEXTILE FOR PAVEMENT TYPE 2A	1354.00	SYS
0035	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	826.00	SYS
0036	301-12232	COMPACTED AGGREGATE NO. 5	226.00	CYS
0037	301-12233	COMPACTED AGGREGATE NO. 8	379.00	CYS
0038	301-12234	COMPACTED AGGREGATE NO. 53	1725.00	CYS
0039	301-12234	COMPACTED AGGREGATE NO. 53	485.00	CYS
0040	302-06464	SUBBASE FOR PCCP	97.00	CYS
0041	302-07455	DENSE GRADED SUBBASE	140.00	CYS
0042	303-01180	COMPACTED AGGREGATE NO. 53	198.00	TON
0043	306-08034	MILLING, ASPHALT, 1 1/2 IN.	796.00	SYS
0044	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	724.00	TON
0045	401-07404	QC/QA-HMA, 4, 76, INTERMEDIATE, 19.0 mm	1097.00	TON
0046	401-08364	QC/QA-HMA, 4, 64, BASE, 19.0 mm	3072.00	TON
0047	401-10258	JOINT ADHESIVE, SURFACE	5935.00	LFT
0048	401-10259	JOINT ADHESIVE, INTERMEDIATE	5320.00	LFT
0049	401-11785	LIQUID ASPHALT SEALANT	5935.00	LFT
0050	401-12137	QC/QA-HMA, 4, 76, INTERMEDIATE, OG, 19.0 mm	1197.00	TON
0051	402-10087	HMA FOR TEMPORARY PAVEMENT, TYPE D	533.00	TON
0052	503-05240	D-1 CONTRACTION JOINT	96.00	LFT
0053	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	139.00	SYS
0054	503-12477	TERMINAL JOINT, TYPE HMA	84.00	LFT
0055	503-12478	TERMINAL JOINT, TYPE PCCP	96.00	LFT
0056	601-02241	GUARDRAIL, REMOVE	831.00	LFT
0057	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	5.00	EACH
0058	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	1103.00	LFT
0059	601-12291	GUARDRAIL, MGS, TRANSITION WITH CURB	8.00	EACH
0060	601-94689	GUARDRAIL, END TREATMENT, OS	5.00	EACH
0061	601-94690	GUARDRAIL, END TREATMENT, MS	2.00	EACH
0062	601-99123	GUARDRAIL, TRANSITION, GP	1.00	EACH
0063	602-06729	BARRIER, DELINEATOR	118.00	EACH
0064	605-06095	CURB, INTEGRAL B CONCRETE	20.00	LFT
0065	605-06121	CURB, CONCRETE B	116.00	LFT
0066	605-06121	CURB, CONCRETE B	136.00	LFT
0067	605-97305	CURB AND GUTTER, TURNOUT COMBINED MODIFIED	8.00	EACH
0068	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	513.00	SYS

0069	610-07487	HMA FOR APPROACHES, TYPE B	39.00 TON
0070	615-06505	MONUMENT, B	18.00 EACH
0071	615-06515	MONUMENT, D	2.00 EACH
0072	616-06405	RIPRAP, REVETMENT	294.00 TON
0073	616-09395	GEOMEMBRANE	97.00 SYS
0074	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	452.00 SYS
0075	616-51367	SLOPEWALL, CONCRETE, 4 IN.	957.00 SYS
0076	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0077	621-02770	EROSION CONTROL BLANKET	1661.00 SYS
0078	621-04258	SEED MIXTURE	1.00 LBS
0079	621-06545	FERTILIZER	2.00 TON
0080	621-06554	SEED MIXTURE, U	555.00 LBS
0081	621-06565	MULCHING MATERIAL	6.00 TON
0082	621-06574	SODDING	171.00 SYS
0083	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0084	628-12683	FIELD OFFICE, D	42.00 MOS
0085	701-02936	PILE, STEEL H, HP 14 IN. X 89 IN.	2008.00 LFT
0086	701-06011	DYNAMIC PILE LOAD TEST	17.00 EACH
0087	701-09557	TEST PILE, DYNAMIC, PRODUCTION	2004.00 LFT
0088	701-09559	TEST PILE, DYNAMIC, RESTRIKE	17.00 EACH
0089	701-09684	PILE SHOE, HP 14 X 89	21.00 EACH
0090	701-09826	PILE, STEEL PIPE, 0.5 IN., 14 IN.	28742.00 LFT
0091	701-12836	AUTOMATED PILE DRIVING DATA ACQUISITION DEVICE	2.00 EACH
0092	702-04325	TEMPORARY SHORING	1.00 LS
0093	702-51005	CONCRETE, A, SUBSTRUCTURE	1153.20 CYS
0094	702-51005	CONCRETE, A, SUBSTRUCTURE	72.60 CYS
0095	702-51015	CONCRETE, B, FOOTINGS	342.80 CYS
0096	702-51015	CONCRETE, B, FOOTINGS	435.90 CYS
0097	702-51863	FIELD DRILLED HOLE IN CONCRETE	2673.00 EACH
0098	702-92857	CONCRETE, C, SUBSTRUCTURE	62.70 CYS
0099	703-06028	REINFORCING BARS	342359.00 LBS
0100	703-06029	REINFORCING BARS, EPOXY COATED	1161020.00 LBS
0101	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	96.00 EACH
0102	704-51002	CONCRETE, C, SUPERSTRUCTURE	2925.00 CYS
0103	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	150.00 SYS
0104	706-11601	RAILING, CONCRETE FT	520.00 CYS
0105	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	4.00 EACH

0106	706-11621	CONCRETE BRIDGE RAILING TRANSITION, TFT	4.00 EACH
0107	707-09921	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 54 IN. X 49 IN.	4938.00 LFT
0108	709-51821	SURFACE SEAL	1.00 LS
0109	709-51821	SURFACE SEAL	1.00 LS
0110	710-09158	PATCHING CONCRETE STRUCTURES	500.00 SFT
0111	711-51038	STRUCTURAL STEEL	1.00 LS
0112	711-51038	STRUCTURAL STEEL	1.00 LS
0113	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	3416.00 LFT
0114	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	247.00 LFT
0115	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	124.00 LFT
0116	715-05407	PIPE, END BENT DRAIN, 6 IN.	144.00 LFT
0117	715-09064	VIDEO INSPECTION FOR PIPE	130.00 LFT
0118	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00 EACH
0119	718-06528	OUTLET PROTECTOR, 1	10.00 EACH
0120	718-06532	VIDEO INSPECTION FOR UNDERDRAIN	3416.00 LFT
0121	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	2342.00 SYS
0122	718-12306	GEOTEXTILE FOR UNDERDRAINS, TYPE 1B	134.00 SYS
0123	718-52610	AGGREGATE FOR UNDERDRAINS	595.00 CYS
0124	720-95310	INLET, P12A MODIFIED	2.00 EACH
0125	722-12732	LONGITUDINAL GROOVING	10018.00 SYS
0126	724-12772	BRIDGE EXPANSION JOINT, M	46.00 LFT
0127	726-95870	BEARING ASSEMBLY, PTFE	12.00 EACH
0128	734-10240	CUT-WALL, NO.	114.00 SFT
0129	734-10240	CUT-WALL, NO.	25.00 SFT
0130	734-10240	CUT-WALL, NO.	150.00 SFT
0131	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	3.00 EACH
0132	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00 EACH
0133	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	35160.00 LFT
0134	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	12.00 LFT
0135	801-06625	DETOUR ROUTE MARKER ASSEMBLY	8.00 EACH
0136	801-06640	CONSTRUCTION SIGN, A	36.00 EACH
0137	801-06645	CONSTRUCTION SIGN, B	1.00 EACH
0138	801-06710	FLASHING ARROW SIGN	270.00 DAY
0139	801-06775	MAINTAINING TRAFFIC	1.00 LS
0140	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	1.00 EACH
0141	801-07119	BARRICADE, III-B	24.00 LFT
0142	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2090.00 LFT

0143	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	130.00	LFT
0144	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0145	802-02475	SIGN, PANEL, RELOCATE	1.00	EACH
0146	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	210.00	LFT
0147	802-07057	SIGN, PANEL, WITH LEGEND	625.00	SFT
0148	802-09577	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE E	2.00	EACH
0149	802-09578	OVERHEAD SIGN STRUCTURE, CANTILEVER, TYPE F	1.00	EACH
0150	802-09581	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 36 IN.	1.00	EACH
0151	802-09581	CANTILEVER SIGN SUPPORT FOUNDATION, DRILLED SHAFT 36 IN.	2.00	EACH
0152	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	7.00	SFT
0153	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	134.00	SFT
0154	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	4.00	EACH
0155	802-76095	STRUCTURAL STEEL, BREAKAWAY	594.00	LBS
0156	808-06716	LINE, REMOVE	1223.00	LFT
0157	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0158	808-12032	GROOVING FOR PAVEMENT MARKINGS	6000.00	LFT
0159	808-12454	LINE, PREFORMED PLASTIC, DOTTED, WHITE, 8 IN.	400.00	LFT
0160	808-75052	LINE, PREFORMED PLASTIC, SOLID, WHITE, 6 IN.	4376.00	LFT
0161	808-75053	LINE, PREFORMED PLASTIC, SOLID, WHITE, 8 IN.	365.00	LFT
0162	808-75055	LINE, PREFORMED PLASTIC, BROKEN, WHITE, 6 IN.	2222.00	LFT
0163	808-75057	LINE, PREFORMED PLASTIC, SOLID, YELLOW, 6 IN.	4399.00	LFT

Call: 300

Contract: B -39836-A

Section No.: 1 BRIDGE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0011	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0012	203-02020	EXCAVATION, UNCLASSIFIED	1991.00	CYS
	0013	205-12108	STORMWATER MANAGEMENT BUDGET	22075.00	DOL
	0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0015	205-12618	SWQCP PREPARATION	1.00	LS
	0016	207-08262	SUBGRADE TREATMENT, TYPE I	2130.00	SYS
	0017	211-02050	B BORROW	981.00	CYS
	0018	211-09265	STRUCTURE BACKFILL, TYPE 2	39.00	CYS
	0019	211-09266	STRUCTURE BACKFILL, TYPE 3	2167.00	CYS
	0020	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	181.00	SYS
	0021	301-12234	COMPACTED AGGREGATE NO. 53	290.00	CYS
	0022	302-06464	SUBBASE FOR PCCP	46.00	CYS
	0023	303-01180	COMPACTED AGGREGATE NO. 53	196.00	TON
	0024	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	145.00	TON
	0025	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	240.00	TON
	0026	401-10258	JOINT ADHESIVE, SURFACE	835.00	LFT
	0027	401-10259	JOINT ADHESIVE, INTERMEDIATE	835.00	LFT
	0028	401-11785	LIQUID ASPHALT SEALANT	835.00	LFT
	0029	406-05521	ASPHALT FOR TACK COAT	1740.00	SYS
	0030	503-05240	D-1 CONTRACTION JOINT	192.00	LFT
	0031	601-02241	GUARDRAIL, REMOVE	200.00	LFT

0032	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	25.00	LFT
0033	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	4.00	EACH
0034	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0035	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	180.00	SYS
0036	615-06505	MONUMENT, B	2.00	EACH
0037	616-06405	RIPRAP, REVETMENT	98.00	TON
0038	616-12251	GEOTEXTILE FOR RIPRAP TYPE 3	85.00	SYS
0039	616-51367	SLOPEWALL, CONCRETE, 4 IN.	12.00	SYS
0040	619-51860	PAINT STEEL BRIDGE, PARTIAL, BRIDGE NO.	1.00	LS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0042	621-06559	MULCHED SEEDING R	2462.00	SYS
0043	621-06570	TOPSOIL	35.00	CYS
0044	621-06574	SODDING	218.00	SYS
0045	628-09403	FIELD OFFICE, C	12.00	MOS
0046	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0047	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00	EACH
0048	701-09770	PILE SHOE, HP 14 X 73	8.00	EACH
0049	701-93575	PILE, STEEL H, HP, 14 X 73	240.00	LFT
0050	702-92857	CONCRETE, C, SUBSTRUCTURE	19.80	CYS
0051	703-06029	REINFORCING BARS, EPOXY COATED	53877.00	LBS
0052	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	32.00	EACH
0053	704-51002	CONCRETE, C, SUPERSTRUCTURE	99.50	CYS
0054	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.00	EACH
0055	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	373.00	SYS
0056	706-11404	RAILING, STEEL PF-1	440.50	LFT
0057	706-11404	RAILING, STEEL PF-1	221.00	LFT
0058	706-11602	RAILING, CONCRETE PF-1	42.60	CYS
0059	709-51821	SURFACE SEAL	1.00	LS
0060	711-51038	STRUCTURAL STEEL	1.00	LS
0061	715-05048	PIPE, TYPE 4, CIRCULAR, 6 IN.	585.00	LFT
0062	715-05053	PIPE, UNDERDRAIN, OUTLET 6 IN.	36.00	LFT
0063	715-05119	PIPE, TYPE 1, CIRCULAR, 15 IN.	36.00	LFT
0064	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	111.00	LFT
0065	715-46005	PIPE END SECTION, DIAMETER 15 IN.	6.00	EACH
0066	718-06531	OUTLET PROTECTOR, 3	3.00	EACH
0067	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	455.00	SYS
0068	718-52610	AGGREGATE FOR UNDERDRAINS	50.00	CYS

0069	731-93945	FACE PANELS, CONCRETE	6754.00	SFT
0070	731-93946	WALL ERECTION	6754.00	SFT
0071	731-93947	LEVELING PAD, CONCRETE	622.00	LFT
0072	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0073	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00	EACH
0074	801-06640	CONSTRUCTION SIGN, A	9.00	EACH
0075	801-06645	CONSTRUCTION SIGN, B	3.00	EACH
0076	801-06775	MAINTAINING TRAFFIC	1.00	LS
0077	801-07118	BARRICADE, III-A	48.00	LFT
0078	801-07119	BARRICADE, III-B	48.00	LFT
0079	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	2000.00	LFT
0080	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	2000.00	LFT

Call: 320

Contract: B -40602-A

Section No.: 1

SMALL STRUCTURE PIPE LINING

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-02245	TREE 6 IN., REMOVE	11.00	EACH
0012	201-02250	TREE 10 IN., REMOVE	9.00	EACH
0013	201-02255	TREE 18 IN., REMOVE	2.00	EACH
0014	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0015	202-02272	PAVED SIDE DITCH, REMOVE	25.00	LFT
0016	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0017	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0018	202-74035	SIGN, REMOVE	9.00	EACH
0019	202-90747	RETAINING WALL, REMOVE	29.00	LFT
0020	202-94747	POST, REMOVE	9.00	EACH
0021	202-96133	PIPE, REMOVE	377.00	LFT
0022	203-02000	EXCAVATION, COMMON	1130.00	CYS
0023	203-02070	BORROW	105.00	CYS
0024	205-11626	PUMP AROUND	8.00	EACH
0025	205-12108	STORMWATER MANAGEMENT BUDGET	29559.00	DOL
0026	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0027	205-12618	SWQCP PREPARATION	1.00	LS
0028	206-51220	EXCAVATION, WET	602.00	CYS
0029	206-51235	COFFERDAM	1.00	LS
0030	207-09935	SUBGRADE TREATMENT, TYPE IC	463.00	SYS
0031	207-12498	SUBGRADE TREATMENT, TYPE ID	2191.00	SYS

0032	211-09264	STRUCTURE BACKFILL, TYPE 1	465.00	CYS
0033	211-09265	STRUCTURE BACKFILL, TYPE 2	1550.00	CYS
0034	211-09268	STRUCTURE BACKFILL, TYPE 5	669.00	CYS
0035	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	1134.00	SYS
0036	301-12232	COMPACTED AGGREGATE NO. 5	131.00	CYS
0037	301-12233	COMPACTED AGGREGATE NO. 8	19.00	CYS
0038	301-12234	COMPACTED AGGREGATE NO. 53	857.00	CYS
0039	303-01180	COMPACTED AGGREGATE NO. 53	257.00	TON
0040	306-08034	MILLING, ASPHALT, 1 1/2 IN.	1528.00	SYS
0041	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	41.00	TON
0042	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	277.00	TON
0043	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	53.00	TON
0044	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	339.00	TON
0045	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	1081.00	TON
0046	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	127.00	TON
0047	401-10258	JOINT ADHESIVE, SURFACE	3203.00	LFT
0048	401-10259	JOINT ADHESIVE, INTERMEDIATE	2477.00	LFT
0049	401-11785	LIQUID ASPHALT SEALANT	3703.00	LFT
0050	406-05520	ASPHALT FOR TACK COAT	15.00	TON
0051	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	5.00	TON
0052	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	2.00	EACH
0053	601-01700	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 1	2.00	EACH
0054	601-01740	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 4	1.00	EACH
0055	601-02241	GUARDRAIL, REMOVE	1220.00	LFT
0056	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	82.00	LFT
0057	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	10.00	EACH
0058	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	10.00	EACH
0059	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0060	605-09131	CURB AND GUTTER, TURNOUT CONCRETE	450.00	LFT
0061	607-06335	PAVED SIDE DITCH, A	25.00	LFT
0062	615-06490	RIGHT-OF-WAY MARKER	42.00	EACH
0063	615-06505	MONUMENT, B	14.00	EACH
0064	616-05688	RIPRAP, CLASS 1	205.00	TON
0065	616-06405	RIPRAP, REVETMENT	479.00	TON
0066	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	688.00	SYS
0067	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	146.00	SYS
0068	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	8.00	EACH

0069	621-02770	EROSION CONTROL BLANKET	109.00	SYS
0070	621-06559	MULCHED SEEDING R	8007.00	SYS
0071	621-06570	TOPSOIL	480.00	CYS
0072	621-12612	SEED MIXTURE, FLOODPLAIN	5.00	LBS
0073	628-09403	FIELD OFFICE, C	10.00	MOS
0074	703-06029	REINFORCING BARS, EPOXY COATED	15618.00	LBS
0075	706-08496	REINFORCED CONCRETE MOMENT SLAB, 12 IN.	338.00	SYS
0076	706-09960	RAILING, CONCRETE FC	186.00	LFT
0077	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	12.00	EACH
0078	709-51821	SURFACE SEAL	1.00	LS
0079	714-11176	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 6 FT X 6 FT	46.00	LFT
0080	715-01354	CLEAN EXISTING PIPE	257.00	LFT
0081	715-05145	PIPE, TYPE 1, CIRCULAR, 96 IN.	174.00	LFT
0082	715-05596	PIPE EXTENSION, CIRCULAR, 18 IN.	21.00	LFT
0083	715-06691	CONCRETE ANCHOR, 96 IN.	2.00	EACH
0084	715-07625	PIPE, TYPE 1, CIRCULAR, 66 IN.	137.00	LFT
0085	715-07626	CONCRETE ANCHOR, 66 IN.	4.00	EACH
0086	723-11203	STRUCTURE REINFORCED CONCRETE THREE-SIDED SECTIONS	43.00	LFT
0087	723-11267	STRUCTURE, REINFORCED CONCRETE, THREE-SIDED SECTIONS, 384 IN.X 96 IN.	47.00	LFT
0088	723-11333	STRUCTURE, REINFORCED CONCRETE, THREE-SIDED SECTIONS, 360 IN. X 126 IN.	43.00	LFT
0089	725-10016	PIPE LINER, CURED-IN-PLACE, MIN. AREA 7.9 SFT	257.00	LFT
0090	725-10245	PERPETUATION, EXISTING PIPE	2.00	EACH
0091	801-04308	ROAD CLOSURE SIGN ASSEMBLY	51.00	EACH
0092	801-06625	DETOUR ROUTE MARKER ASSEMBLY	220.00	EACH
0093	801-06640	CONSTRUCTION SIGN, A	123.00	EACH
0094	801-06775	MAINTAINING TRAFFIC	1.00	LS
0095	801-07118	BARRICADE, III-A	360.00	LFT
0096	801-07119	BARRICADE, III-B	660.00	LFT
0097	802-04314	SIGN	3.00	EACH
0098	802-04893	REFERENCE POST	14.00	EACH
0099	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	347.00	LFT
0100	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	115.00	SFT
0101	802-91122	SIGN GROUND MOUNTED RESET	4.00	EACH
0102	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	10.00	LFT
0103	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	181.00	LFT
0104	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	2237.00	LFT
0105	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	950.00	LFT

0106	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	17.00 EACH
0107	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	17.00 EACH

Call: 330

Contract: B -40993-A

Section No.: 1

BRIDGE DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0012	203-02000	EXCAVATION, COMMON	160.00 CYS
0013	205-11626	PUMP AROUND	1.00 EACH
0014	205-12108	STORMWATER MANAGEMENT BUDGET	15914.00 DOL
0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0016	205-12618	SWQCP PREPARATION	1.00 LS
0017	207-12498	SUBGRADE TREATMENT, TYPE ID	420.00 SYS
0018	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	236.00 SYS
0019	302-06464	SUBBASE FOR PCCP	60.00 CYS
0020	303-01180	COMPACTED AGGREGATE NO. 53	139.00 TON
0021	306-08043	MILLING, TRANSITION	768.00 SYS
0022	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	91.00 TON
0023	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	47.00 TON
0024	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	116.00 TON
0025	401-10258	JOINT ADHESIVE, SURFACE	822.00 LFT
0026	401-10259	JOINT ADHESIVE, INTERMEDIATE	355.00 LFT
0027	401-11785	LIQUID ASPHALT SEALANT	822.00 LFT
0028	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0029	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.00 TON
0030	601-02241	GUARDRAIL, REMOVE	466.00 LFT
0031	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	4.00 EACH

0032	601-94689	GUARDRAIL, END TREATMENT, OS	4.00 EACH
0033	602-06729	BARRIER, DELINEATOR	4.00 EACH
0034	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	236.00 SYS
0035	616-05688	RIPRAP, CLASS 1	533.00 TON
0036	616-06405	RIPRAP, REVETMENT	49.00 TON
0037	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	630.00 SYS
0038	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0039	621-06559	MULCHED SEEDING R	807.00 SYS
0040	621-06567	WATER	1.00 KGAL
0041	621-06574	SODDING	25.00 SYS
0042	628-09403	FIELD OFFICE, C	12.00 MOS
0043	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0044	702-51863	FIELD DRILLED HOLE IN CONCRETE	320.00 EACH
0045	703-06029	REINFORCING BARS, EPOXY COATED	31698.00 LBS
0046	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	128.00 EACH
0047	704-51002	CONCRETE, C, SUPERSTRUCTURE	34.40 CYS
0048	706-11600	RAILING, CONCRETE FC	13.80 CYS
0049	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00 EACH
0050	709-51821	SURFACE SEAL	1.00 LS
0051	710-09158	PATCHING CONCRETE STRUCTURES	10.00 SFT
0052	722-01066	HYDRODEMOLITION	212.00 SYS
0053	722-12380	BRIDGE DECK OVERLAY, BUDGET	6980.00 DOL
0054	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	212.00 SYS
0055	722-12732	LONGITUDINAL GROOVING	492.00 SYS
0056	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	50.00 SFT
0057	722-51874	OVERLAY DAM	62.00 SFT
0058	801-04746	ENERGY ABSORBING TERMINAL, CZ, TL-	2.00 EACH
0059	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1580.00 LFT
0060	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	400.00 LFT
0061	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	44.00 LFT
0062	801-06640	CONSTRUCTION SIGN, A	8.00 EACH
0063	801-06645	CONSTRUCTION SIGN, B	5.00 EACH
0064	801-06775	MAINTAINING TRAFFIC	1.00 LS
0065	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	280.00 LFT
0066	801-12082	FIXED TEMPORARY SIGNAL	1.00 LS
0067	802-04893	REFERENCE POST	1.00 EACH
0068	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	68.00 LFT

0069	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	24.00	SFT
0070	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	90.00	LFT
0071	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	812.00	LFT
0072	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	478.00	LFT

Call: 330

Contract: B -40993-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0073	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	268.00	SYS

Call: 330

Contract: B -40993-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0074	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	268.00	SYS

Call: 340

Contract: B -41177-A

Section No.: 1

BRIDGE REHABILITATION OR REPAIR

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	202-02240	PAVEMENT REMOVAL	110.00 SYS
0010	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0011	203-02000	EXCAVATION, COMMON	15.00 CYS
0012	205-12108	STORMWATER MANAGEMENT BUDGET	4419.00 DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0014	205-12618	SWQCP PREPARATION	1.00 LS
0015	207-09935	SUBGRADE TREATMENT, TYPE IC	120.00 SYS
0016	211-06467	AGGREGATE FOR END BENT BACKFILL	10.00 CYS
0017	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	88.00 SYS
0018	302-06464	SUBBASE FOR PCCP	24.00 CYS
0019	304-12623	HMA PATCHING FULL DEPTH, TYPE B	88.00 TON
0020	503-12477	TERMINAL JOINT, TYPE HMA	48.00 LFT
0021	601-06374	GUARDRAIL, TRANSITION, TGS-1	4.00 EACH
0022	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	110.00 SYS
0023	616-06405	RIPRAP, REVETMENT	172.00 TON
0024	628-09403	FIELD OFFICE, C	9.00 MOS
0025	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0026	702-04325	TEMPORARY SHORING	1.00 LS
0027	702-51863	FIELD DRILLED HOLE IN CONCRETE	60.00 EACH
0028	703-06029	REINFORCING BARS, EPOXY COATED	61608.00 LBS
0029	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	1121.00 EACH
0030	704-51002	CONCRETE, C, SUPERSTRUCTURE	224.00 CYS
0031	706-06344	RAILING, STEEL TS-1	594.00 LFT

0032	710-09158	PATCHING CONCRETE STRUCTURES	70.00	SFT
0033	711-51038	STRUCTURAL STEEL	1.00	LS
0034	718-12305	GEOTEXTILE FOR UNDERDRAINS, TYPE 1A	16.00	SYS
0035	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0036	801-06625	DETOUR ROUTE MARKER ASSEMBLY	39.00	EACH
0037	801-06640	CONSTRUCTION SIGN, A	8.00	EACH
0038	801-06775	MAINTAINING TRAFFIC	1.00	LS
0039	801-07118	BARRICADE, III-A	48.00	LFT
0040	801-07119	BARRICADE, III-B	96.00	LFT
0041	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	878.00	LFT
0042	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	878.00	LFT

Call: 350

Contract: B -41184-A

Section No.: 1

BRIDGE DECK REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0012	203-02000	EXCAVATION, COMMON	404.00	CYS
	0013	205-12108	STORMWATER MANAGEMENT BUDGET	4700.00	DOL
	0014	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0015	205-12618	SWQCP PREPARATION	1.00	LS
	0016	207-08266	SUBGRADE TREATMENT, TYPE III	824.00	SYS
	0017	207-09935	SUBGRADE TREATMENT, TYPE IC	184.00	SYS
	0018	211-06467	AGGREGATE FOR END BENT BACKFILL	38.00	CYS
	0019	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	302.00	SYS
	0020	301-12234	COMPACTED AGGREGATE NO. 53	107.00	CYS
	0021	302-06464	SUBBASE FOR PCCP	46.00	CYS
	0022	303-01180	COMPACTED AGGREGATE NO. 53	102.00	TON
	0023	304-07493	WIDENING WITH HMA, TYPE B	12.00	TON
	0024	306-08043	MILLING, TRANSITION	168.00	SYS
	0025	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	75.00	TON
	0026	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	95.00	TON
	0027	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	115.00	TON
	0028	401-10258	JOINT ADHESIVE, SURFACE	588.00	LFT
	0029	401-10259	JOINT ADHESIVE, INTERMEDIATE	515.00	LFT
	0030	401-11785	LIQUID ASPHALT SEALANT	588.00	LFT
	0031	406-05520	ASPHALT FOR TACK COAT	0.50	TON

0032	503-12477	TERMINAL JOINT, TYPE HMA	63.00	LFT
0033	601-02241	GUARDRAIL, REMOVE	397.50	LFT
0034	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	62.50	LFT
0035	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	25.00	LFT
0036	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	1.00	EACH
0037	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	3.00	EACH
0038	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	1.00	EACH
0039	601-94689	GUARDRAIL, END TREATMENT, OS	3.00	EACH
0040	602-06729	BARRIER, DELINEATOR	16.00	EACH
0041	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	184.00	SYS
0042	615-06490	RIGHT-OF-WAY MARKER	7.00	EACH
0043	615-06530	BENCH MARK POST	1.00	EACH
0044	616-06405	RIPRAP, REVETMENT	112.00	TON
0045	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	211.00	SYS
0046	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0047	621-06559	MULCHED SEEDING R	687.00	SYS
0048	621-06574	SODDING	71.00	SYS
0049	628-09403	FIELD OFFICE, C	6.00	MOS
0050	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0051	702-51863	FIELD DRILLED HOLE IN CONCRETE	48.00	EACH
0052	703-06029	REINFORCING BARS, EPOXY COATED	104658.00	LBS
0053	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	32.00	EACH
0054	704-51002	CONCRETE, C, SUPERSTRUCTURE	251.00	CYS
0055	706-11600	RAILING, CONCRETE FC	48.60	CYS
0056	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0057	707-05984	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 45 IN. X 16 IN.	502.00	LFT
0058	709-51821	SURFACE SEAL	1.00	LS
0059	710-09158	PATCHING CONCRETE STRUCTURES	100.00	SFT
0060	715-05407	PIPE, END BENT DRAIN, 6 IN.	90.00	LFT
0061	722-12732	LONGITUDINAL GROOVING	928.00	SYS
0062	801-04308	ROAD CLOSURE SIGN ASSEMBLY	3.00	EACH
0063	801-06625	DETOUR ROUTE MARKER ASSEMBLY	22.00	EACH
0064	801-06640	CONSTRUCTION SIGN, A	6.00	EACH
0065	801-06775	MAINTAINING TRAFFIC	1.00	LS
0066	801-07118	BARRICADE, III-A	180.00	LFT
0067	801-07119	BARRICADE, III-B	24.00	LFT
0068	802-04089	SIGN, SHEET, REMOVE	7.00	EACH

0069	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	58.00	LFT
0070	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	28.50	SFT
0071	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0072	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	950.00	LFT
0073	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	914.00	LFT
0074	808-06726	TRANSVERSE MARKING, PAINT, STOP LINE, WHITE, 24 IN.	25.00	LFT

Call: 360

Contract: B -41185-A

Section No.: 1 BRIDGE DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-02240	PAVEMENT REMOVAL	750.00 SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0014	203-02000	EXCAVATION, COMMON	448.00 CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	5400.00 DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0017	205-12618	SWQCP PREPARATION	1.00 LS
0018	207-08266	SUBGRADE TREATMENT, TYPE III	1021.00 SYS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	180.00 SYS
0020	211-06467	AGGREGATE FOR END BENT BACKFILL	50.00 CYS
0021	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	226.00 SYS
0022	302-06464	SUBBASE FOR PCCP	194.00 CYS
0023	303-01180	COMPACTED AGGREGATE NO. 53	249.00 TON
0024	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	28.00 TON
0025	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	47.00 TON
0026	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	122.00 TON
0027	406-05521	ASPHALT FOR TACK COAT	1080.00 SYS
0028	502-06327	PCCP, 10 IN.	588.00 SYS
0029	503-05240	D-1 CONTRACTION JOINT	308.00 LFT
0030	503-12478	TERMINAL JOINT, TYPE PCCP	44.00 LFT
0031	601-02241	GUARDRAIL, REMOVE	525.00 LFT

0032	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	287.50	LFT
0033	601-12282	GUARDRAIL, MGS W-BEAM, 3 FT 1.5 IN. SPACING	475.00	LFT
0034	601-12583	GUARDRAIL, MGS, SIDE-MOUNTED POST, DECK	146.00	EACH
0035	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0036	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	180.00	SYS
0037	615-06530	BENCH MARK POST	1.00	EACH
0038	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0039	621-06559	MULCHED SEEDING R	651.00	SYS
0040	628-09403	FIELD OFFICE, C	6.00	MOS
0041	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00	EACH
0042	702-51863	FIELD DRILLED HOLE IN CONCRETE	738.00	EACH
0043	703-06029	REINFORCING BARS, EPOXY COATED	28935.00	LBS
0044	704-51002	CONCRETE, C, SUPERSTRUCTURE	14.80	CYS
0045	704-51006	CONCRETE, C, SUPERSTRUCTURE, MODIFIED	46.30	CYS
0046	709-51821	SURFACE SEAL	1.00	LS
0047	710-09158	PATCHING CONCRETE STRUCTURES	100.00	SFT
0048	715-05407	PIPE, END BENT DRAIN, 6 IN.	100.00	LFT
0049	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	130.00	SYS
0050	722-01066	HYDRODEMOLITION	702.00	SYS
0051	722-12380	BRIDGE DECK OVERLAY, BUDGET	13625.00	DOL
0052	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	702.00	SYS
0053	722-12732	LONGITUDINAL GROOVING	1025.00	SYS
0054	722-51874	OVERLAY DAM	54.00	SFT
0055	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0056	801-06625	DETOUR ROUTE MARKER ASSEMBLY	42.00	EACH
0057	801-06640	CONSTRUCTION SIGN, A	27.00	EACH
0058	801-06775	MAINTAINING TRAFFIC	1.00	LS
0059	801-07118	BARRICADE, III-A	72.00	LFT
0060	801-07119	BARRICADE, III-B	72.00	LFT
0061	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	1048.00	LFT
0062	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	131.00	LFT

Call: 360
Contract: B -41185-A
Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

Line
Item No **Item Code** **Description**
0063 722-51842 BRIDGE DECK OVERLAY, LATEX MODIFIED
Call: 360
Contract: B -41185-A
Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED CONCRETE

Quantity Unit
702.00 SYS

Line
Item No **Item Code** **Description**
0064 722-01061 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Quantity Unit
702.00 SYS

Call: 370

Contract: B -41303-A

Section No.: 1

BRIDGE REHABILITATION OR REPAIR

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0012	205-12108	STORMWATER MANAGEMENT BUDGET	10000.00 DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0014	205-12618	SWQCP PREPARATION	1.00 LS
0015	207-08264	SUBGRADE TREATMENT, TYPE II	45.00 SYS
0016	211-06467	AGGREGATE FOR END BENT BACKFILL	8.00 CYS
0017	214-12237	GEOTEXTILE FOR PAVEMENT, TYPE 1B	45.00 SYS
0018	301-12231	COMPACTED AGGREGATE NO. 2	3.00 CYS
0019	306-08034	MILLING, ASPHALT, 1 1/2 IN.	311.00 SYS
0020	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	30.00 TON
0021	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	7.00 TON
0022	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	15.00 TON
0023	401-10258	JOINT ADHESIVE, SURFACE	200.00 LFT
0024	401-10259	JOINT ADHESIVE, INTERMEDIATE	25.00 LFT
0025	401-11785	LIQUID ASPHALT SEALANT	200.00 LFT
0026	406-05521	ASPHALT FOR TACK COAT	400.00 SYS
0027	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	0.50 TON
0028	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	0.50 TON
0029	601-02241	GUARDRAIL, REMOVE	345.00 LFT
0030	601-06037	GUARDRAIL, END TREATMENT, I	4.00 EACH
0031	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	181.20 LFT

0032	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	4.00 EACH
0033	616-05688	RIPRAP, CLASS 1	146.00 TON
0034	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	217.00 SYS
0035	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0036	621-06559	MULCHED SEEDING R	1111.00 SYS
0037	628-09403	FIELD OFFICE, C	12.00 MOS
0038	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0039	710-02003	REPOINTING MASONRY IN STRUCTURES, MODIFIED	1000.00 SFT
0040	711-51820	TEMPORARY SUPPORT	1.00 LS
0041	712-03820	TIMBER SIDING	4328.00 SFT
0042	712-04272	LUMBER AND TIMBER, UNTREATED	2.00 MFB
0043	712-04686	FIRE PROTECTION	1.00 LS
0044	712-04704	PAINT BRIDGE	1.00 LS
0045	712-05097	METAL PARTS	200.00 LBS
0046	712-05098	TIMBER	21.00 EACH
0047	712-06384	PLANK FLOORS, TWO-PLY	1890.00 SFT
0048	712-11615	ROOF CORRUGATED METAL	3785.00 SFT
0049	712-11616	STONE ABUTMENT REPAIR	1.00 LS
0050	712-94725	STRUCTURAL TIMBER	2487.00 BDFT
0051	715-05407	PIPE, END BENT DRAIN, 6 IN.	20.00 LFT
0052	718-12309	GEOTEXTILE FOR UNDERDRAINS, TYPE 3	13.00 SYS
0053	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00 EACH
0054	801-06640	CONSTRUCTION SIGN, A	4.00 EACH
0055	801-06775	MAINTAINING TRAFFIC	1.00 LS
0056	801-07118	BARRICADE, III-A	48.00 LFT
0057	801-07119	BARRICADE, III-B	48.00 LFT
0058	802-04089	SIGN, SHEET, REMOVE	2.00 EACH
0059	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	10.00 SFT

Call: 380

Contract: B -41384-A

Section No.: 1

BRIDGE REHABILITATION OR REPAIR

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08441	QUALITY ADJUSTMENTS, PCCP	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0011	202-02240	PAVEMENT REMOVAL	317.00	SYS
	0012	202-02273	CENTER CURB, CONCRETE, REMOVE	194.00	SYS
	0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0014	203-02000	EXCAVATION, COMMON	207.00	CYS
	0015	205-12108	STORMWATER MANAGEMENT BUDGET	48471.00	DOL
	0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0017	205-12618	SWQCP PREPARATION	1.00	LS
	0018	206-51235	COFFERDAM	1.00	LS
	0019	207-09935	SUBGRADE TREATMENT, TYPE IC	546.00	SYS
	0020	207-12498	SUBGRADE TREATMENT, TYPE ID	155.00	SYS
	0021	301-12234	COMPACTED AGGREGATE NO. 53	108.00	CYS
	0022	302-07455	DENSE GRADED SUBBASE	48.00	CYS
	0023	303-01180	COMPACTED AGGREGATE NO. 53	58.00	TON
	0024	304-07789	WIDENING WITH HMA, TYPE D	177.00	TON
	0025	402-10087	HMA FOR TEMPORARY PAVEMENT, TYPE D	51.00	TON
	0026	406-05521	ASPHALT FOR TACK COAT	772.00	SYS
	0027	502-06329	PCCP, 12 IN.	86.00	SYS
	0028	503-03489	RETROFITTED TIE BARS	48.00	EACH
	0029	503-12477	TERMINAL JOINT, TYPE HMA	107.00	LFT
	0030	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	214.00	SFT
	0031	601-06035	GUARDRAIL, RESET	350.00	LFT

0032	605-06100	CURB, INTEGRAL C CONCRETE	388.00	LFT
0033	605-06250	CENTER CURB, C CONCRETE	222.00	SYS
0034	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	245.00	SYS
0035	616-05688	RIPRAP, CLASS 1	200.00	TON
0036	616-05689	RIPRAP, CLASS 2	1280.00	TON
0037	616-06405	RIPRAP, REVETMENT	137.00	TON
0038	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1649.00	SYS
0039	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0040	619-95315	CLEAN AND PAINT BEARING ASSEMBLIES, BRIDGE NO.	1.00	LS
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
0042	621-03909	SEED MIXTURE, NATIVE	10.00	LBS
0043	621-06560	MULCHED SEEDING U	1030.00	SYS
0044	621-06565	MULCHING MATERIAL	1.30	TON
0045	621-06567	WATER	1.00	KGAL
0046	621-06570	TOPSOIL	88.00	CYS
0047	621-06575	SODDING, NURSERY	225.00	SYS
0048	621-12612	SEED MIXTURE, FLOODPLAIN	7.00	LBS
0049	622-05640	PLANT, DECIDUOUS SHRUB, 24 IN. TO 36 IN.	20.00	EACH
0050	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. TO 2 IN.	103.00	EACH
0051	622-52436	SIGN, DO NOT MOW OR SPRAY	6.00	EACH
0052	628-09401	FIELD OFFICE, A	12.00	MOS
0053	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0054	702-51863	FIELD DRILLED HOLE IN CONCRETE	1924.00	EACH
0055	703-06029	REINFORCING BARS, EPOXY COATED	20643.00	LBS
0056	703-08247	EMBEDDED GALVANIC ANODE	200.00	EACH
0057	704-51002	CONCRETE, C, SUPERSTRUCTURE	38.40	CYS
0058	709-51821	SURFACE SEAL	1.00	LS
0059	710-09158	PATCHING CONCRETE STRUCTURES	340.00	SFT
0060	711-51878	JACKING AND SUPPORTING, GIRDERS	1.00	LS
0061	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	32.00	EACH
0062	722-01066	HYDRODEMOLITION	4151.00	SYS
0063	722-12380	BRIDGE DECK OVERLAY, BUDGET	105000.00	DOL
0064	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	3865.00	SYS
0065	722-12732	LONGITUDINAL GROOVING	4334.00	SYS
0066	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	1800.00	SFT
0067	722-51874	OVERLAY DAM	332.00	SFT
0068	724-12773	BRIDGE EXPANSION JOINT, PCF	795.00	LFT

0069	727-90308	EPOXY INJECTION, CRACK PREPARATION	160.00	LFT
0070	727-90309	EPOXY INJECTION, EPOXY MATERIAL	16.00	GAL
0071	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0072	801-02595	CONTROLLER RESET TIMING	3.00	EACH
0073	801-03290	CONSTRUCTION SIGN, C	4.00	EACH
0074	801-03291	CONSTRUCTION SIGN, D	6.00	EACH
0075	801-04308	ROAD CLOSURE SIGN ASSEMBLY	1.00	EACH
0076	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	17576.00	LFT
0077	801-06216	TEMPORARY TRANSVERSE PAVEMENT MARKING, 24 IN.	24.00	LFT
0078	801-06539	TEMPORARY TRAFFIC SIGNAL INSTALLATION, MAINTAIN	1.00	LS
0079	801-06625	DETOUR ROUTE MARKER ASSEMBLY	18.00	EACH
0080	801-06640	CONSTRUCTION SIGN, A	21.00	EACH
0081	801-06645	CONSTRUCTION SIGN, B	9.00	EACH
0082	801-06710	FLASHING ARROW SIGN	120.00	DAY
0083	801-06775	MAINTAINING TRAFFIC	1.00	LS
0084	801-06775	MAINTAINING TRAFFIC	1.00	LS
0085	801-07119	BARRICADE, III-B	120.00	LFT
0086	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1115.00	LFT
0087	801-12883	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY CONTINUOUS	2.00	EACH
0088	801-94295	SIGNAL HEAD RELOCATE	12.00	EACH
0089	808-05866	PAVEMENT MESSAGE MARKING, REMOVE	3.00	SYS
0090	808-06716	LINE, REMOVE	1890.00	LFT
0091	808-10031	LINE, MULTI-COMPONENT, BROKEN, WHITE, 4 IN.	657.00	LFT
0092	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2400.00	LFT
0093	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	3000.00	LFT
0094	808-10068	TRANSVERSE MARKING, MULTI-COMPONENT	77.00	LFT
0095	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	3.00	EACH
0096	808-12032	GROOVING FOR PAVEMENT MARKINGS	2974.00	LFT

Call: 380

Contract: B -41384-A

Section No.: 2 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0097	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	4008.00	SYS

Call: 380

Contract: B -41384-A

Section No.: 3 BRIDGE DECK OVERLAY, LATEX, MODIFIED

Line

Item No	Item Code	Description
0098	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED

Quantity Unit

4008.00 SYS

Call: 390

Contract: B -41493-A

Section No.: 1 BRIDGE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	2.00	EACH
	0003	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0004	109-08360	CONTRACT LIENS	1.00	DOL
	0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0012	202-02240	PAVEMENT REMOVAL	174.00	SYS
	0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0014	202-96133	PIPE, REMOVE	53.00	LFT
	0015	203-02000	EXCAVATION, COMMON	390.00	CYS
	0016	203-02070	BORROW	1065.00	CYS
	0017	203-51223	EXCAVATION, WATERWAY	308.00	CYS
	0018	205-11626	PUMP AROUND	1.00	EACH
	0019	205-12108	STORMWATER MANAGEMENT BUDGET	24513.15	DOL
	0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0021	205-12618	SWQCP PREPARATION	1.00	LS
	0022	206-51215	EXCAVATION, X	194.00	CYS
	0023	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	267.00	CYS
	0024	207-09935	SUBGRADE TREATMENT, TYPE IC	595.00	SYS
	0025	211-06467	AGGREGATE FOR END BENT BACKFILL	54.00	CYS
	0026	211-09264	STRUCTURE BACKFILL, TYPE 1	31.00	CYS
	0027	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	169.00	SYS
	0028	301-12232	COMPACTED AGGREGATE NO. 5	23.00	CYS
	0029	301-12234	COMPACTED AGGREGATE NO. 53	23.00	CYS
	0030	302-06464	SUBBASE FOR PCCP	41.00	CYS
	0031	303-01180	COMPACTED AGGREGATE NO. 53	467.00	TON

0032	306-08043	MILLING, TRANSITION	889.00	SYS
0033	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	123.00	TON
0034	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	116.00	TON
0035	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	185.00	TON
0036	401-10258	JOINT ADHESIVE, SURFACE	906.00	LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	428.00	LFT
0038	401-11785	LIQUID ASPHALT SEALANT	906.00	LFT
0039	402-10084	HMA FOR TEMPORARY PAVEMENT, TYPE B	32.00	TON
0040	406-05521	ASPHALT FOR TACK COAT	2054.00	SYS
0041	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.00	TON
0042	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH
0043	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH
0044	601-01626	GUARDRAIL, CONNECTOR SYSTEM, W-BEAM CURVED, 2	1.00	EACH
0045	601-01839	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 6	2.00	EACH
0046	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0047	601-02241	GUARDRAIL, REMOVE	979.00	LFT
0048	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	382.00	LFT
0049	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	3.00	EACH
0050	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	2.00	EACH
0051	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0052	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	69.00	LFT
0053	602-06729	BARRIER, DELINEATOR	14.00	EACH
0054	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	169.00	SYS
0055	615-06490	RIGHT-OF-WAY MARKER	5.00	EACH
0056	615-06505	MONUMENT, B	4.00	EACH
0057	616-05688	RIPRAP, CLASS 1	1625.00	TON
0058	616-06405	RIPRAP, REVETMENT	30.00	TON
0059	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1900.00	SYS
0060	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0061	621-02770	EROSION CONTROL BLANKET	3163.00	SYS
0062	621-06545	FERTILIZER	1.00	TON
0063	621-06553	SEED MIXTURE, R	150.00	LBS
0064	621-06565	MULCHING MATERIAL	2.00	TON
0065	621-06567	WATER	1.00	KGAL
0066	621-06574	SODDING	20.00	SYS
0067	621-09815	ARTICULATED CONCRETE BLOCK	56.00	SYS
0068	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH

0069	628-12683	FIELD OFFICE, D	12.00	MOS
0070	629-12029	PLANT GROWTH LAYER	3511.00	SYS
0071	701-09558	TEST PILE, INDICATOR, PRODUCTION	80.00	LFT
0072	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00	EACH
0073	701-09739	PILE SHOE, HP 12 X 53	14.00	EACH
0074	701-51195	PILE, STEEL H HP 12 X 53	360.00	LFT
0075	702-51005	CONCRETE, A, SUBSTRUCTURE	152.70	CYS
0076	702-51015	CONCRETE, B, FOOTINGS	92.00	CYS
0077	702-92857	CONCRETE, C, SUBSTRUCTURE	62.70	CYS
0078	703-01540	THREADED TIE BAR ASSEMBLY	36.00	EACH
0079	703-06028	REINFORCING BARS	34322.00	LBS
0080	703-06029	REINFORCING BARS, EPOXY COATED	119235.00	LBS
0081	704-51002	CONCRETE, C, SUPERSTRUCTURE	286.10	CYS
0082	706-06351	CONCRETE BRIDGE RAILING TRANSITION, TPF-1	4.00	EACH
0083	706-09962	RAILING, CONCRETE PF-1	378.00	LFT
0084	706-11404	RAILING, STEEL PF-1	395.00	LFT
0085	707-09865	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 49 IN.	798.00	LFT
0086	709-51821	SURFACE SEAL	1.00	LS
0087	715-05121	PIPE, TYPE 1, CIRCULAR, 18 IN.	62.00	LFT
0088	715-05407	PIPE, END BENT DRAIN, 6 IN.	158.00	LFT
0089	715-46010	PIPE END SECTION, DIAMETER 18 IN.	2.00	EACH
0090	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	121.00	SYS
0091	722-12732	LONGITUDINAL GROOVING	983.00	SYS
0092	725-10224	LINER PIPE, THERMOPLASTIC, CIRCULAR, 8.4-8.8 SFT	102.00	LFT
0093	801-04308	ROAD CLOSURE SIGN ASSEMBLY	7.00	EACH
0094	801-06625	DETOUR ROUTE MARKER ASSEMBLY	39.00	EACH
0095	801-06640	CONSTRUCTION SIGN, A	11.00	EACH
0096	801-06775	MAINTAINING TRAFFIC	1.00	LS
0097	801-07118	BARRICADE, III-A	96.00	LFT
0098	801-07119	BARRICADE, III-B	120.00	LFT
0099	802-04893	REFERENCE POST	2.00	EACH
0100	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	9.00	SFT
0101	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	10.00	SFT
0102	802-76055	SIGN POST, A	30.00	LFT
0103	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0104	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	979.00	LFT
0105	808-75035	LINE, PAINT, SOLID, WHITE, 24 IN.	39.00	LFT

0106	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	864.00	LFT
0107	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	11.00	EACH

Call: 400

Contract: B -41502-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	1335.00	SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	203-02000	EXCAVATION, COMMON	300.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	7025.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	206-51235	COFFERDAM	1.00	LS
0019	207-09935	SUBGRADE TREATMENT, TYPE IC	1160.00	SYS
0020	207-12151	SUBGRADE TREATMENT, TYPE IVA	1000.00	SYS
0021	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	1320.00	SYS
0022	302-06464	SUBBASE FOR PCCP	320.00	CYS
0023	304-07493	WIDENING WITH HMA, TYPE B	430.00	TON
0024	306-08043	MILLING, TRANSITION	1490.00	SYS
0025	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	240.00	TON
0026	401-10258	JOINT ADHESIVE, SURFACE	2790.00	LFT
0027	401-10259	JOINT ADHESIVE, INTERMEDIATE	1300.00	LFT
0028	401-11785	LIQUID ASPHALT SEALANT	2790.00	LFT
0029	406-05521	ASPHALT FOR TACK COAT	4160.00	SYS
0030	503-03489	RETROFITTED TIE BARS	96.00	EACH
0031	503-05240	D-1 CONTRACTION JOINT	288.00	LFT

0032	503-12476	JOINTED REINFORCED CONCRETE PAVEMENT 12 IN.	740.00	SYS
0033	503-12478	TERMINAL JOINT, TYPE PCCP	104.00	LFT
0034	503-12479	EXPANSION JOINT WITH LOAD TRANSFER	96.00	LFT
0035	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	100.00	SFT
0036	601-02241	GUARDRAIL, REMOVE	600.00	LFT
0037	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	275.00	LFT
0038	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	4.00	EACH
0039	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0040	602-06729	BARRIER, DELINEATOR	6.00	EACH
0041	606-12399	MILLED HMA CORRUGATIONS, CONVENTIONAL	345.00	LFT
0042	609-06257	REINFORCED CONCRETE BRIDGE APPROACH, 10 IN.	576.00	SYS
0043	616-05689	RIPRAP, CLASS 2	245.00	TON
0044	616-06405	RIPRAP, REVETMENT	182.00	TON
0045	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	394.00	SYS
0046	619-98427	CLEAN DRAINS	6.00	EACH
0047	621-06559	MULCHED SEEDING R	600.00	SYS
0048	621-06567	WATER	1.00	KGAL
0049	621-06574	SODDING	32.00	SYS
0050	621-52448	SIGN, DO NOT SPRAY	14.00	EACH
0051	628-09403	FIELD OFFICE, C	12.00	MOS
0052	702-51863	FIELD DRILLED HOLE IN CONCRETE	344.00	EACH
0053	703-06029	REINFORCING BARS, EPOXY COATED	42530.00	LBS
0054	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	370.00	EACH
0055	704-51002	CONCRETE, C, SUPERSTRUCTURE	10.60	CYS
0056	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0057	706-51020	RAILING, CONCRETE C	14.60	CYS
0058	709-51821	SURFACE SEAL	1.00	LS
0059	709-51821	SURFACE SEAL	1.00	LS
0060	709-51821	SURFACE SEAL	1.00	LS
0061	709-51821	SURFACE SEAL	1.00	LS
0062	710-09158	PATCHING CONCRETE STRUCTURES	420.00	SFT
0063	722-01066	HYDRODEMOLITION	2440.00	SYS
0064	722-12380	BRIDGE DECK OVERLAY, BUDGET	40800.00	DOL
0065	722-12381	BRIDGE DECK OVERLAY, LMC-VE	365.00	SYS
0066	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	230.00	SYS
0067	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	2210.00	SYS
0068	722-12732	LONGITUDINAL GROOVING	3010.00	SYS

0069	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	300.00	SFT
0070	722-51874	OVERLAY DAM	69.00	SFT
0071	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.00	EACH
0072	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0073	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	1688.00	LFT
0074	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	12736.00	LFT
0075	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	4407.00	LFT
0076	801-06625	DETOUR ROUTE MARKER ASSEMBLY	19.00	EACH
0077	801-06640	CONSTRUCTION SIGN, A	84.00	EACH
0078	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0079	801-06710	FLASHING ARROW SIGN	240.00	DAY
0080	801-06775	MAINTAINING TRAFFIC	1.00	LS
0081	801-07118	BARRICADE, III-A	216.00	LFT
0082	801-07119	BARRICADE, III-B	84.00	LFT
0083	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2170.00	LFT
0084	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	5.00	EACH
0085	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0086	801-97643	TEMPORARY BUZZ STRIPS	84.00	LFT
0087	802-04893	REFERENCE POST	4.00	EACH
0088	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	34.00	SFT
0089	802-76055	SIGN POST, A	80.00	LFT
0090	808-10052	PAVEMENT MESSAGE MARKING, MULTI-COMPONENT, ONLY	3.00	EACH
0091	808-10077	PAVEMENT MESSAGE MARKINGS MULTI-COMPONENT LANE INDICATION ARROW	3.00	EACH
0092	808-12032	GROOVING FOR PAVEMENT MARKINGS	6460.00	LFT
0093	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	209.00	LFT
0094	808-75002	LINE, PAINT, BROKEN, WHITE, 6 IN.	450.00	LFT
0095	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	3727.00	LFT
0096	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	2806.00	LFT
0097	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	17.00	EACH
0098	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	17.00	EACH

Call: 400

Contract: B -41502-A

Section No.: 2 BRIDGE DECK OVERLAY LATEX MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0099	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	2645.00	SYS

Call: 400

Contract: B -41502-A

Section No.: 3 BRIDGE DECK OVERLAY SILICA FUME MODIFIED

Line

Item No	Item Code	Description
0100	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Quantity Unit

2645.00 SYS

Call: 410

Contract: B -41516-A

Section No.: 1

BRIDGE REPLACEMENT

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0011	202-02240	PAVEMENT REMOVAL	659.00	SYS
0012	202-02272	PAVED SIDE DITCH, REMOVE	154.00	LFT
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
0014	203-02000	EXCAVATION, COMMON	361.00	CYS
0015	203-51223	EXCAVATION, WATERWAY	865.00	CYS
0016	205-12108	STORMWATER MANAGEMENT BUDGET	18736.60	DOL
0017	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0018	205-12618	SWQCP PREPARATION	1.00	LS
0019	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	91.00	CYS
0020	207-08264	SUBGRADE TREATMENT, TYPE II	68.00	SYS
0021	207-09935	SUBGRADE TREATMENT, TYPE IC	1367.00	SYS
0022	207-12498	SUBGRADE TREATMENT, TYPE ID	69.00	SYS
0023	211-06467	AGGREGATE FOR END BENT BACKFILL	46.00	CYS
0024	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	184.00	SYS
0025	301-12234	COMPACTED AGGREGATE NO. 53	12.00	CYS
0026	302-06464	SUBBASE FOR PCCP	44.00	CYS
0027	303-01180	COMPACTED AGGREGATE NO. 53	232.00	TON
0028	304-07494	WIDENING WITH HMA, TYPE C	196.00	TON
0029	306-11872	MILLING, PROFILE	859.00	SYS
0030	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	144.00	TON
0031	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	120.00	TON

0032	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	389.00 TON
0033	401-10258	JOINT ADHESIVE, SURFACE	1475.00 LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	1295.00 LFT
0035	401-11785	LIQUID ASPHALT SEALANT	1475.00 LFT
0036	406-05521	ASPHALT FOR TACK COAT	4535.00 SYS
0037	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.00 TON
0038	601-02241	GUARDRAIL, REMOVE	433.00 LFT
0039	601-06234	IMPACT ATTENUATOR, R1-W1, TL-2	1.00 EACH
0040	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	112.50 LFT
0041	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	3.00 EACH
0042	601-94689	GUARDRAIL, END TREATMENT, OS	3.00 EACH
0043	602-06729	BARRIER, DELINEATOR	8.00 EACH
0044	607-06335	PAVED SIDE DITCH, A	320.00 LFT
0045	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	182.50 SYS
0046	610-07487	HMA FOR APPROACHES, TYPE B	15.00 TON
0047	611-08232	MAILBOX ASSEMBLY, RESET SINGLE	2.00 EACH
0048	615-06505	MONUMENT, B	2.00 EACH
0049	615-06530	BENCH MARK POST	1.00 EACH
0050	616-06405	RIPRAP, REVETMENT	504.00 TON
0051	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	740.00 SYS
0052	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0053	621-02770	EROSION CONTROL BLANKET	328.00 SYS
0054	621-06559	MULCHED SEEDING R	2024.00 SYS
0055	621-06567	WATER	1.00 KGAL
0056	621-06574	SODDING	82.00 SYS
0057	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0058	628-12683	FIELD OFFICE, D	12.00 MOS
0059	701-09558	TEST PILE, INDICATOR, PRODUCTION	96.00 LFT
0060	701-09560	TEST PILE, INDICATOR, RESTRIKE	2.00 EACH
0061	701-09739	PILE SHOE, HP 12 X 53	14.00 EACH
0062	701-51195	PILE, STEEL H HP 12 X 53	456.00 LFT
0063	702-92857	CONCRETE, C, SUBSTRUCTURE	37.20 CYS
0064	703-06029	REINFORCING BARS, EPOXY COATED	56113.00 LBS
0065	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	38.00 EACH
0066	704-51002	CONCRETE, C, SUPERSTRUCTURE	135.80 CYS
0067	706-09960	RAILING, CONCRETE FC	163.00 LFT
0068	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00 EACH

0069	707-09865	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 49 IN.	324.00	LFT
0070	709-51821	SURFACE SEAL	1.00	LS
0071	715-05407	PIPE, END BENT DRAIN, 6 IN.	100.00	LFT
0072	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	104.00	SYS
0073	722-12732	LONGITUDINAL GROOVING	513.00	SYS
0074	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0075	801-06625	DETOUR ROUTE MARKER ASSEMBLY	31.00	EACH
0076	801-06640	CONSTRUCTION SIGN, A	22.00	EACH
0077	801-06645	CONSTRUCTION SIGN, B	9.00	EACH
0078	801-06775	MAINTAINING TRAFFIC	1.00	LS
0079	801-07118	BARRICADE, III-A	48.00	LFT
0080	801-07119	BARRICADE, III-B	192.00	LFT
0081	802-04893	REFERENCE POST	2.00	EACH
0082	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	1230.00	LFT
0083	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	1230.00	LFT
0084	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	17.00	EACH
0085	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	17.00	EACH

Call: 420

Contract: B -41561-A

Section No.: 1 BRIDGE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0011	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0012	203-02000	EXCAVATION, COMMON	1225.00	CYS
	0013	205-11626	PUMP AROUND	1.00	EACH
	0014	205-12108	STORMWATER MANAGEMENT BUDGET	14000.00	DOL
	0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0016	205-12618	SWQCP PREPARATION	1.00	LS
	0017	206-51235	COFFERDAM	1.00	LS
	0018	207-09935	SUBGRADE TREATMENT, TYPE IC	1087.00	SYS
	0019	211-06467	AGGREGATE FOR END BENT BACKFILL	41.00	CYS
	0020	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	1087.00	SYS
	0021	301-12234	COMPACTED AGGREGATE NO. 53	43.00	CYS
	0022	302-06464	SUBBASE FOR PCCP	56.00	CYS
	0023	303-01180	COMPACTED AGGREGATE NO. 53	320.00	TON
	0024	304-07493	WIDENING WITH HMA, TYPE B	54.00	TON
	0025	306-08043	MILLING, TRANSITION	418.00	SYS
	0026	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	98.00	TON
	0027	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	114.00	TON
	0028	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	276.00	TON
	0029	401-10258	JOINT ADHESIVE, SURFACE	825.00	LFT
	0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	733.00	LFT
	0031	401-11785	LIQUID ASPHALT SEALANT	825.00	LFT

0032	406-05521	ASPHALT FOR TACK COAT	2107.00	SYS
0033	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.00	TON
0034	503-12477	TERMINAL JOINT, TYPE HMA	68.00	LFT
0035	601-02241	GUARDRAIL, REMOVE	235.00	LFT
0036	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	193.75	LFT
0037	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	4.00	EACH
0038	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0039	602-06729	BARRIER, DELINEATOR	8.00	EACH
0040	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	223.00	SYS
0041	615-06490	RIGHT-OF-WAY MARKER	8.00	EACH
0042	615-06505	MONUMENT, B	2.00	EACH
0043	616-05688	RIPRAP, CLASS 1	640.00	TON
0044	616-06405	RIPRAP, REVETMENT	298.00	TON
0045	616-06451	RIPRAP, UNIFORM	160.00	TON
0046	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	1090.00	SYS
0047	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0048	621-02770	EROSION CONTROL BLANKET	3469.00	SYS
0049	621-06545	FERTILIZER	1.00	TON
0050	621-06553	SEED MIXTURE, R	146.00	LBS
0051	621-06574	SODDING	1313.00	SYS
0052	628-09403	FIELD OFFICE, C	8.00	MOS
0053	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0054	701-06011	DYNAMIC PILE LOAD TEST	2.00	EACH
0055	701-09557	TEST PILE, DYNAMIC, PRODUCTION	175.00	LFT
0056	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.00	EACH
0057	701-09683	PILE SHOE, HP 12 X 74	8.00	EACH
0058	701-95780	PILE, STEEL H, HP 12 X 74	465.00	LFT
0059	702-92857	CONCRETE, C, SUBSTRUCTURE	46.00	CYS
0060	703-06029	REINFORCING BARS, EPOXY COATED	59552.00	LBS
0061	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	38.00	EACH
0062	704-51002	CONCRETE, C, SUPERSTRUCTURE	136.00	CYS
0063	706-11600	RAILING, CONCRETE FC	18.00	CYS
0064	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0065	707-09865	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 49 IN.	366.00	LFT
0066	709-51821	SURFACE SEAL	1.00	LS
0067	715-05407	PIPE, END BENT DRAIN, 6 IN.	110.00	LFT
0068	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	110.00	SYS

0069	722-12732	LONGITUDINAL GROOVING	562.00	SYS
0070	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
0071	801-04308	ROAD CLOSURE SIGN ASSEMBLY	6.00	EACH
0072	801-06625	DETOUR ROUTE MARKER ASSEMBLY	38.00	EACH
0073	801-06640	CONSTRUCTION SIGN, A	22.00	EACH
0074	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0075	801-06775	MAINTAINING TRAFFIC	1.00	LS
0076	801-07118	BARRICADE, III-A	48.00	LFT
0077	801-07119	BARRICADE, III-B	96.00	LFT
0078	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	17.00	LFT
0079	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	6.00	SFT
0080	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0081	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	114.00	LFT
0082	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	1150.00	LFT

Call: 430

Contract: B -41567-A

Section No.: 1 BRIDGE DECK OVERLAY

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-02240	PAVEMENT REMOVAL	392.00	SYS
0013	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
0014	202-62420	BRIDGE RAILING, REMOVE	130.00	LFT
0015	203-02000	EXCAVATION, COMMON	85.00	CYS
0016	203-02070	BORROW	105.00	CYS
0017	203-08607	LINEAR GRADING	282.00	LFT
0018	205-11626	PUMP AROUND	1.00	EACH
0019	205-12108	STORMWATER MANAGEMENT BUDGET	9000.00	DOL
0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0021	205-12618	SWQCP PREPARATION	1.00	LS
0022	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	12.00	CYS
0023	206-51235	COFFERDAM	1.00	LS
0024	207-12498	SUBGRADE TREATMENT, TYPE ID	410.00	SYS
0025	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	240.00	SYS
0026	301-12231	COMPACTED AGGREGATE NO. 2	8.00	CYS
0027	302-06464	SUBBASE FOR PCCP	60.00	CYS
0028	303-01180	COMPACTED AGGREGATE NO. 53	54.00	TON
0029	306-08043	MILLING, TRANSITION	966.00	SYS
0030	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	106.00	TON
0031	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	51.00	TON

0032	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	160.00 TON
0033	401-10258	JOINT ADHESIVE, SURFACE	898.00 LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	398.00 LFT
0035	401-11785	LIQUID ASPHALT SEALANT	898.00 LFT
0036	406-05521	ASPHALT FOR TACK COAT	1387.00 SYS
0037	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.00 TON
0038	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00 EACH
0039	601-01701	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 2	1.00 EACH
0040	601-02241	GUARDRAIL, REMOVE	480.00 LFT
0041	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	25.00 LFT
0042	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	3.00 EACH
0043	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	3.00 EACH
0044	601-91147	GUARDRAIL, END TREATMENT, RESET	3.00 EACH
0045	602-06729	BARRIER, DELINEATOR	8.00 EACH
0046	603-06060	FENCE, FARM FIELD, RESET	25.00 LFT
0047	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	240.00 SYS
0048	610-07487	HMA FOR APPROACHES, TYPE B	5.00 TON
0049	615-06505	MONUMENT, B	2.00 EACH
0050	616-06405	RIPRAP, REVETMENT	350.00 TON
0051	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	354.00 SYS
0052	619-11052	CLEAN STEEL BRIDGE, QP-2, BRIDGE NO.	1.00 LS
0053	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00 LS
0054	619-12507	CLEAN AND PAINT STEEL PILING BRIDGE NO.	1.00 LS
0055	619-51859	PAINT STEEL BRIDGE, BRIDGE NO.	1.00 LS
0056	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00 EACH
0057	621-06559	MULCHED SEEDING R	529.00 SYS
0058	621-06574	SODDING	63.00 SYS
0059	628-09403	FIELD OFFICE, C	6.00 MOS
0060	702-51015	CONCRETE, B, FOOTINGS	0.80 CYS
0061	702-51863	FIELD DRILLED HOLE IN CONCRETE	36.00 EACH
0062	703-06029	REINFORCING BARS, EPOXY COATED	31507.00 LBS
0063	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	16.00 EACH
0064	704-51002	CONCRETE, C, SUPERSTRUCTURE	34.70 CYS
0065	706-11600	RAILING, CONCRETE FC	13.40 CYS
0066	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00 EACH
0067	709-51821	SURFACE SEAL	1.00 LS
0068	710-09158	PATCHING CONCRETE STRUCTURES	75.00 SFT

0069	711-51038	STRUCTURAL STEEL	1.00	LS
0070	722-01066	HYDRODEMOLITION	248.00	SYS
0071	722-12380	BRIDGE DECK OVERLAY, BUDGET	4280.00	DOL
0072	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	248.00	SYS
0073	722-12732	LONGITUDINAL GROOVING	540.00	SYS
0074	722-51874	OVERLAY DAM	87.00	SFT
0075	727-90308	EPOXY INJECTION, CRACK PREPARATION	64.00	LFT
0076	727-90309	EPOXY INJECTION, EPOXY MATERIAL	14.00	GAL
0077	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00	LS
0078	801-04308	ROAD CLOSURE SIGN ASSEMBLY	4.00	EACH
0079	801-06625	DETOUR ROUTE MARKER ASSEMBLY	30.00	EACH
0080	801-06640	CONSTRUCTION SIGN, A	30.00	EACH
0081	801-06775	MAINTAINING TRAFFIC	1.00	LS
0082	801-07118	BARRICADE, III-A	96.00	LFT
0083	801-07119	BARRICADE, III-B	120.00	LFT
0084	802-04893	REFERENCE POST	1.00	EACH
0085	802-91122	SIGN GROUND MOUNTED RESET	1.00	EACH
0086	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	96.00	LFT
0087	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	764.00	LFT
0088	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6.00	EACH
0089	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	5.00	EACH

Call: 430

Contract: B -41567-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0090	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	312.00	SYS

Call: 430

Contract: B -41567-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0091	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	312.00	SYS

Call: 440

Contract: B -41589-A

Section No.: 1 BRIDGE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0012	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0014	202-90747	RETAINING WALL, REMOVE	58.00 LFT
0015	202-93741	GUARDRAIL, END TREATMENT, REMOVE	4.00 EACH
0016	202-96133	PIPE, REMOVE	16.00 LFT
0017	202-98488	PIPE END SECTION, REMOVE	1.00 EACH
0018	203-02000	EXCAVATION, COMMON	1838.00 CYS
0019	203-02070	BORROW	305.00 CYS
0020	203-51223	EXCAVATION, WATERWAY	56.00 CYS
0021	205-11626	PUMP AROUND	1.00 EACH
0022	205-12108	STORMWATER MANAGEMENT BUDGET	26912.40 DOL
0023	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0024	205-12618	SWQCP PREPARATION	1.00 LS
0025	206-51220	EXCAVATION, WET	61.00 CYS
0026	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	187.00 CYS
0027	207-08264	SUBGRADE TREATMENT, TYPE II	445.00 SYS
0028	207-12498	SUBGRADE TREATMENT, TYPE ID	2326.00 SYS
0029	211-06467	AGGREGATE FOR END BENT BACKFILL	48.00 CYS
0030	211-09264	STRUCTURE BACKFILL, TYPE 1	5.00 CYS
0031	211-09265	STRUCTURE BACKFILL, TYPE 2	10.00 CYS

0032	211-09268	STRUCTURE BACKFILL, TYPE 5	149.00	CYS
0033	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	1370.00	SYS
0034	301-12232	COMPACTED AGGREGATE NO. 5	26.00	CYS
0035	301-12233	COMPACTED AGGREGATE NO. 8	10.00	CYS
0036	301-12234	COMPACTED AGGREGATE NO. 53	34.00	CYS
0037	302-06464	SUBBASE FOR PCCP	61.00	CYS
0038	303-01180	COMPACTED AGGREGATE NO. 53	204.00	TON
0039	304-07494	WIDENING WITH HMA, TYPE C	405.00	TON
0040	306-08034	MILLING, ASPHALT, 1 1/2 IN.	600.00	SYS
0041	306-08043	MILLING, TRANSITION	1154.00	SYS
0042	306-11872	MILLING, PROFILE	619.00	SYS
0043	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	301.00	TON
0044	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	338.00	TON
0045	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	453.00	TON
0046	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	277.00	TON
0047	401-10258	JOINT ADHESIVE, SURFACE	2652.00	LFT
0048	401-10259	JOINT ADHESIVE, INTERMEDIATE	2652.00	LFT
0049	401-11785	LIQUID ASPHALT SEALANT	2652.00	LFT
0050	406-05521	ASPHALT FOR TACK COAT	8985.00	SYS
0051	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	1.50	TON
0052	601-02241	GUARDRAIL, REMOVE	1156.00	LFT
0053	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	50.00	LFT
0054	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	4.00	EACH
0055	601-94689	GUARDRAIL, END TREATMENT, OS	4.00	EACH
0056	602-06729	BARRIER, DELINEATOR	6.00	EACH
0057	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	238.50	SYS
0058	615-06490	RIGHT-OF-WAY MARKER	6.00	EACH
0059	615-06505	MONUMENT, B	4.00	EACH
0060	615-06530	BENCH MARK POST	1.00	EACH
0061	616-06405	RIPRAP, REVETMENT	600.00	TON
0062	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	783.00	SYS
0063	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	456.00	SYS
0064	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	4.00	EACH
0065	621-02770	EROSION CONTROL BLANKET	553.00	SYS
0066	621-06545	FERTILIZER	1.00	TON
0067	621-06559	MULCHED SEEDING R	1805.00	SYS
0068	621-06567	WATER	6.00	KGAL

0069	621-06574	SODDING	522.00	SYS
0070	621-06575	SODDING, NURSERY	940.00	SYS
0071	621-12612	SEED MIXTURE, FLOODPLAIN	1.00	LBS
0072	628-09403	FIELD OFFICE, C	16.00	MOS
0073	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0074	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0075	628-11732	CELLULAR TELEPHONE, ADDITIONAL MINUTES	1.00	DOL
0076	628-11782	CELLULAR TELEPHONE SERVICE, 1000 MIN.	16.00	MOS
0077	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0078	701-02938	CORED HOLE IN ROCK, 24 IN.	87.00	LFT
0079	701-09558	TEST PILE, INDICATOR, PRODUCTION	61.00	LFT
0080	701-09683	PILE SHOE, HP 12 X 74	12.00	EACH
0081	701-95780	PILE, STEEL H, HP 12 X 74	246.00	LFT
0082	702-04325	TEMPORARY SHORING	1.00	LS
0083	702-92857	CONCRETE, C, SUBSTRUCTURE	48.20	CYS
0084	703-06029	REINFORCING BARS, EPOXY COATED	67058.00	LBS
0085	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	440.00	EACH
0086	704-51002	CONCRETE, C, SUPERSTRUCTURE	154.00	CYS
0087	706-09960	RAILING, CONCRETE FC	163.20	LFT
0088	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0089	707-08158	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 42 IN. X 49 IN.	324.00	LFT
0090	709-51821	SURFACE SEAL	1.00	LS
0091	709-51821	SURFACE SEAL	1.00	LS
0092	714-11957	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 15 FT X 6 FT	68.00	LFT
0093	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	16.00	LFT
0094	715-05407	PIPE, END BENT DRAIN, 6 IN.	120.00	LFT
0095	715-46010	PIPE END SECTION, DIAMETER 18 IN.	1.00	EACH
0096	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	110.00	SYS
0097	720-12798	CASTING, MANHOLE, ADJUST TO GRADE	1.00	EACH
0098	722-12732	LONGITUDINAL GROOVING	590.60	SYS
0099	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.00	EACH
0100	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0101	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	18150.00	LFT
0102	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	48.00	LFT
0103	801-06640	CONSTRUCTION SIGN, A	80.00	EACH
0104	801-06645	CONSTRUCTION SIGN, B	18.00	EACH
0105	801-06775	MAINTAINING TRAFFIC	1.00	LS

0106	801-07118	BARRICADE, III-A	48.00	LFT
0107	801-07119	BARRICADE, III-B	60.00	LFT
0108	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	650.00	LFT
0109	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00	EACH
0110	801-12081	PORTABLE SIGNAL	1.00	LS
0111	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0112	801-97643	TEMPORARY BUZZ STRIPS	1728.00	LFT
0113	802-91122	SIGN GROUND MOUNTED RESET	4.00	EACH
0114	808-06716	LINE, REMOVE	4090.00	LFT
0115	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	1680.00	LFT
0116	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	1680.00	LFT
0117	808-12032	GROOVING FOR PAVEMENT MARKINGS	2828.00	LFT
0118	808-75043	LINE, THERMOPLASTIC, SOLID, WHITE, 6 IN.	2570.00	LFT
0119	808-75247	LINE, THERMOPLASTIC, SOLID, YELLOW, 6 IN.	180.00	LFT
0120	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	21.00	EACH
0121	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	11.00	EACH
0122	808-96078	LINE, THERMOPLASTIC, BROKEN, YELLOW, 6 IN.	209.00	LFT

Call: 460

Contract: B -42245-B

Section No.: 1

SMALL STRUCTURE PIPE LINING

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	3.00 EACH
0003	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0004	109-08360	CONTRACT LIENS	1.00 DOL
0005	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0006	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0007	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0008	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0009	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0010	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0011	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0012	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0014	202-96133	PIPE, REMOVE	66.00 LFT
0015	203-02000	EXCAVATION, COMMON	3290.00 CYS
0016	205-11626	PUMP AROUND	5.00 EACH
0017	205-12108	STORMWATER MANAGEMENT BUDGET	61748.00 DOL
0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0019	205-12618	SWQCP PREPARATION	1.00 LS
0020	206-51220	EXCAVATION, WET	19.50 CYS
0021	206-51225	EXCAVATION, DRY	285.00 CYS
0022	207-09935	SUBGRADE TREATMENT, TYPE IC	1276.00 SYS
0023	207-12498	SUBGRADE TREATMENT, TYPE ID	2498.00 SYS
0024	211-02050	B BORROW	35.00 CYS
0025	211-06467	AGGREGATE FOR END BENT BACKFILL	64.00 CYS
0026	211-09264	STRUCTURE BACKFILL, TYPE 1	176.00 CYS
0027	211-09265	STRUCTURE BACKFILL, TYPE 2	566.00 CYS
0028	211-09268	STRUCTURE BACKFILL, TYPE 5	103.00 CYS
0029	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	7.00 CYS
0030	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	196.00 SYS
0031	301-12232	COMPACTED AGGREGATE NO. 5	2.00 CYS

0032	301-12233	COMPACTED AGGREGATE NO. 8	42.00	CYS
0033	301-12234	COMPACTED AGGREGATE NO. 53	2.00	CYS
0034	302-06464	SUBBASE FOR PCCP	48.00	CYS
0035	303-01180	COMPACTED AGGREGATE NO. 53	872.00	TON
0036	304-07493	WIDENING WITH HMA, TYPE B	96.00	TON
0037	304-07494	WIDENING WITH HMA, TYPE C	379.00	TON
0038	306-08034	MILLING, ASPHALT, 1 1/2 IN.	600.00	SYS
0039	306-08043	MILLING, TRANSITION	2512.00	SYS
0040	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	503.00	TON
0041	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	303.00	TON
0042	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	921.00	TON
0043	401-10258	JOINT ADHESIVE, SURFACE	4884.00	LFT
0044	401-10259	JOINT ADHESIVE, INTERMEDIATE	2850.00	LFT
0045	401-11785	LIQUID ASPHALT SEALANT	4884.00	LFT
0046	406-05520	ASPHALT FOR TACK COAT	4.00	TON
0047	507-08272	JOINTS IN PCCP, SAW AND SEAL	83.00	LFT
0048	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	2.00	EACH
0049	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00	EACH
0050	601-02241	GUARDRAIL, REMOVE	2236.00	LFT
0051	601-05071	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 7	3.00	EACH
0052	601-06035	GUARDRAIL, RESET	25.00	LFT
0053	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	1670.00	LFT
0054	601-12291	GUARDRAIL, MGS, TRANSITION WITH CURB	2.00	EACH
0055	601-94689	GUARDRAIL, END TREATMENT, OS	13.00	EACH
0056	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	138.00	LFT
0057	602-06729	BARRIER, DELINEATOR	6.00	EACH
0058	605-06121	CURB, CONCRETE B	141.00	LFT
0059	605-09137	CURB, TURNOUT	20.00	LFT
0060	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	200.00	SYS
0061	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00	EACH
0062	615-06490	RIGHT-OF-WAY MARKER	46.00	EACH
0063	615-06505	MONUMENT, B	6.00	EACH
0064	616-05688	RIPRAP, CLASS 1	113.00	TON
0065	616-05689	RIPRAP, CLASS 2	141.00	TON
0066	616-06405	RIPRAP, REVETMENT	980.00	TON
0067	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	551.00	SYS
0068	616-12247	GEOTEXTILE FOR RIPRAP TYPE 1B	1105.00	SYS

0069	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	597.00	SYS
0070	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	19.00	SYS
0071	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0072	619-12507	CLEAN AND PAINT STEEL PILING BRIDGE NO.	1.00	LS
0073	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	12.00	EACH
0074	621-02770	EROSION CONTROL BLANKET	420.00	SYS
0075	621-04258	SEED MIXTURE	10.00	LBS
0076	621-06545	FERTILIZER	1.00	TON
0077	621-06559	MULCHED SEEDING R	8949.00	SYS
0078	621-06565	MULCHING MATERIAL	2.00	TON
0079	621-06574	SODDING	98.00	SYS
0080	621-12612	SEED MIXTURE, FLOODPLAIN	13.00	LBS
0081	628-09401	FIELD OFFICE, A	10.00	MOS
0082	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	EACH
0083	701-06011	DYNAMIC PILE LOAD TEST	2.00	EACH
0084	701-09557	TEST PILE, DYNAMIC, PRODUCTION	112.00	LFT
0085	701-09559	TEST PILE, DYNAMIC, RESTRIKE	2.00	EACH
0086	701-09683	PILE SHOE, HP 12 X 74	12.00	EACH
0087	701-09779	PREBORED HOLE, 15 IN.	572.00	LFT
0088	701-95780	PILE, STEEL H, HP 12 X 74	460.00	LFT
0089	702-51005	CONCRETE, A, SUBSTRUCTURE	1.90	CYS
0090	702-92857	CONCRETE, C, SUBSTRUCTURE	29.80	CYS
0091	703-06029	REINFORCING BARS, EPOXY COATED	68860.00	LBS
0092	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	44.00	EACH
0093	704-51002	CONCRETE, C, SUPERSTRUCTURE	151.50	CYS
0094	706-11600	RAILING, CONCRETE FC	19.00	CYS
0095	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0096	707-08158	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 42 IN. X 49 IN.	485.00	LFT
0097	708-51814	WELDED STEEL WIRE REINFORCEMENT	192.00	SFT
0098	709-51821	SURFACE SEAL	1.00	LS
0099	710-09158	PATCHING CONCRETE STRUCTURES	192.00	SFT
0100	711-96800	STUD SHEAR CONNECTORS	64.00	EACH
0101	714-11180	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 8 FT X 7 FT	68.00	LFT
0102	714-11191	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 5 FT X 4 FT	56.00	LFT
0103	714-96273	HEADWALL RECONSTRUCT	1.00	LS
0104	715-01344	PIPE END SECTION, DIAMETER 60 IN.	2.00	EACH
0105	715-01354	CLEAN EXISTING PIPE	66.00	LFT

0106	715-05141	PIPE, TYPE 1, CIRCULAR, 84 IN.	8.00	LFT
0107	715-05145	PIPE, TYPE 1, CIRCULAR, 96 IN.	104.00	LFT
0108	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	135.00	LFT
0109	715-05152	PIPE, TYPE 2, CIRCULAR, 18 IN.	37.00	LFT
0110	715-05169	PIPE, TYPE 3, CIRCULAR, 15 IN.	40.00	LFT
0111	715-05188	PIPE, TYPE 3, CIRCULAR, 60 IN.	41.00	LFT
0112	715-05407	PIPE, END BENT DRAIN, 6 IN.	154.00	LFT
0113	715-46005	PIPE END SECTION, DIAMETER 15 IN.	2.00	EACH
0114	718-12307	GEOTEXTILE FOR UNDERDRAINS, TYPE 2A	196.00	SYS
0115	718-12308	GEOTEXTILE FOR UNDERDRAINS, TYPE 2B	25.00	SYS
0116	720-45275	PIPE CATCH BASIN, 24 IN.	10.00	EACH
0117	722-12732	LONGITUDINAL GROOVING	631.00	SYS
0118	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	498.00	SFT
0119	725-10245	PERPETUATION, EXISTING PIPE	2.00	EACH
0120	725-11289	LINER PIPE, THERMOPLASTIC, CIRCULAR, 23.2 - 23.8 SFT	74.67	LFT
0121	801-04308	ROAD CLOSURE SIGN ASSEMBLY	27.00	EACH
0122	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	992.00	LFT
0123	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4920.00	LFT
0124	801-06625	DETOUR ROUTE MARKER ASSEMBLY	126.00	EACH
0125	801-06640	CONSTRUCTION SIGN, A	53.00	EACH
0126	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0127	801-06710	FLASHING ARROW SIGN	60.00	DAY
0128	801-06775	MAINTAINING TRAFFIC	1.00	LS
0129	801-07118	BARRICADE, III-A	296.00	LFT
0130	801-07119	BARRICADE, III-B	240.00	LFT
0131	802-04893	REFERENCE POST	2.00	EACH
0132	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	54.00	LFT
0133	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	21.00	SFT
0134	804-06740	DELINEATOR WITH POST, D2	2.00	EACH
0135	808-06703	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	2463.00	LFT
0136	808-06716	LINE, REMOVE	1845.00	LFT
0137	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	2740.00	LFT
0138	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	343.00	LFT
0139	808-12032	GROOVING FOR PAVEMENT MARKINGS	5630.00	LFT
0140	808-75240	LINE, THERMOPLASTIC, BROKEN, YELLOW, 4 IN.	309.00	LFT
0141	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	7.00	EACH
0142	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	6.00	EACH

Call: 470

Contract: B -42713-A

Section No.: 1

REPLACE SUPERSTRUCTURE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0011	202-02240	PAVEMENT REMOVAL	388.00	SYS
	0012	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00	LS
	0013	202-93741	GUARDRAIL, END TREATMENT, REMOVE	3.00	EACH
	0014	203-02000	EXCAVATION, COMMON	412.00	CYS
	0015	203-02070	BORROW	170.00	CYS
	0016	205-11626	PUMP AROUND	1.00	EACH
	0017	205-12108	STORMWATER MANAGEMENT BUDGET	7000.00	DOL
	0018	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0019	205-12618	SWQCP PREPARATION	1.00	LS
	0020	206-51220	EXCAVATION, WET	161.00	CYS
	0021	206-51230	EXCAVATION, FOUNDATION, UNCLASSIFIED	57.00	CYS
	0022	207-09935	SUBGRADE TREATMENT, TYPE IC	887.00	SYS
	0023	211-09267	STRUCTURE BACKFILL, TYPE 4	25.00	CYS
	0024	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	399.00	SYS
	0025	302-06464	SUBBASE FOR PCCP	100.00	CYS
	0026	303-01180	COMPACTED AGGREGATE NO. 53	330.00	TON
	0027	304-07494	WIDENING WITH HMA, TYPE C	69.00	TON
	0028	306-08034	MILLING, ASPHALT, 1 1/2 IN.	279.00	SYS
	0029	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	101.00	TON
	0030	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	103.00	TON
	0031	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	245.00	TON

0032	401-10258	JOINT ADHESIVE, SURFACE	775.00	LFT
0033	401-10259	JOINT ADHESIVE, INTERMEDIATE	675.00	LFT
0034	401-11785	LIQUID ASPHALT SEALANT	775.00	LFT
0035	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0036	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH
0037	601-01839	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 6	2.00	EACH
0038	601-02241	GUARDRAIL, REMOVE	665.00	LFT
0039	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	112.50	LFT
0040	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	1.00	EACH
0041	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	3.00	EACH
0042	601-94689	GUARDRAIL, END TREATMENT, OS	1.00	EACH
0043	601-94689	GUARDRAIL, END TREATMENT, OS	2.00	EACH
0044	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	6.25	LFT
0045	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	399.00	SYS
0046	615-06505	MONUMENT, B	2.00	EACH
0047	616-06405	RIPRAP, REVETMENT	312.00	TON
0048	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	358.00	SYS
0049	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
0050	619-12507	CLEAN AND PAINT STEEL PILING BRIDGE NO.	1.00	LS
0051	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0052	621-02770	EROSION CONTROL BLANKET	145.00	SYS
0053	621-06559	MULCHED SEEDING R	145.00	SYS
0054	621-06567	WATER	1.00	KGAL
0055	621-06574	SODDING	76.00	SYS
0056	628-09403	FIELD OFFICE, C	8.00	MOS
0057	702-51005	CONCRETE, A, SUBSTRUCTURE	82.00	CYS
0058	703-06029	REINFORCING BARS, EPOXY COATED	105844.00	LBS
0059	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	46.00	EACH
0060	704-51002	CONCRETE, C, SUPERSTRUCTURE	399.00	CYS
0061	706-11600	RAILING, CONCRETE FC	20.80	CYS
0062	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0063	709-51821	SURFACE SEAL	1.00	LS
0064	801-04308	ROAD CLOSURE SIGN ASSEMBLY	5.00	EACH
0065	801-06625	DETOUR ROUTE MARKER ASSEMBLY	28.00	EACH
0066	801-06640	CONSTRUCTION SIGN, A	18.00	EACH
0067	801-06775	MAINTAINING TRAFFIC	1.00	LS
0068	801-07118	BARRICADE, III-A	48.00	LFT

0069	801-07119	BARRICADE, III-B	36.00	LFT
0070	802-04893	REFERENCE POST	2.00	EACH
0071	802-05701	SIGN POST, SQUARE, TYPE 1, REINFORCED ANCHOR BASE	60.00	LFT
0072	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	12.00	SFT
0073	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	10.00	SFT
0074	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	900.00	LFT
0075	808-12032	GROOVING FOR PAVEMENT MARKINGS	580.50	LFT
0076	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	112.00	LFT
0077	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	12.00	EACH

Call: 480

Contract: B -42718-A

Section No.: 1

BRIDGE THIN DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	506-06334	PCCP PATCHING, PARTIAL DEPTH	42.00 SYS
0009	602-06729	BARRIER, DELINEATOR	26.00 EACH
0010	616-06406	RIPRAP, REVETMENT	7.00 SYS
0011	619-98427	CLEAN DRAINS	10.00 EACH
0012	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0013	628-12683	FIELD OFFICE, D	6.00 MOS
0014	709-12077	FIBER WRAP CONCRETE CASING SYSTEM	140.00 SFT
0015	709-51821	SURFACE SEAL	1.00 LS
0016	709-51821	SURFACE SEAL	1.00 LS
0017	709-51821	SURFACE SEAL	1.00 LS
0018	709-51821	SURFACE SEAL	1.00 LS
0019	710-09158	PATCHING CONCRETE STRUCTURES	46.00 SFT
0020	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	1365.00 SFT
0021	724-12420	BRIDGE JOINT NOSING	326.00 SFT
0022	724-12773	BRIDGE EXPANSION JOINT, PCF	730.00 LFT
0023	738-12855	WARRANTED POLYMER OVERLAY BRIDGE DECK	7579.00 SYS
0024	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	6.00 EACH
0025	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	26448.00 LFT
0026	801-06640	CONSTRUCTION SIGN, A	32.00 EACH
0027	801-06645	CONSTRUCTION SIGN, B	3.00 EACH
0028	801-06710	FLASHING ARROW SIGN	112.00 DAY
0029	801-06775	MAINTAINING TRAFFIC	1.00 LS
0030	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00 EACH
0031	801-12042	TRUCK MOUNTED ATTENUATOR	224.00 DAY

0032	808-06711	LINE, PAINT, BROKEN, WHITE, 4 IN.	1417.00	LFT
0033	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1627.00	LFT
0034	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	5634.00	LFT
0035	808-06716	LINE, REMOVE	6637.00	LFT
0036	808-75994	PRISMATIC REFLECTOR	12.00	EACH

Call: 490

Contract: B -42719-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0011	306-08034	MILLING, ASPHALT, 1 1/2 IN.	971.00	SYS
	0012	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	42.00	TON
	0013	401-07335	QC/QA-HMA, 4, 76, SURFACE, 9.5 mm	38.60	TON
	0014	401-10258	JOINT ADHESIVE, SURFACE	600.00	LFT
	0015	401-11785	LIQUID ASPHALT SEALANT	600.00	LFT
	0016	406-05521	ASPHALT FOR TACK COAT	971.00	SYS
	0017	506-06334	PCCP PATCHING, PARTIAL DEPTH	4.00	SYS
	0018	507-08271	JOINTS IN PCCP, FILLED	158.00	LFT
	0019	507-08272	JOINTS IN PCCP, SAW AND SEAL	178.00	LFT
	0020	628-11976	COMPUTER SYSTEM EQUIPMENT	4.00	EACH
	0021	628-12683	FIELD OFFICE, D	10.00	MOS
	0022	702-51863	FIELD DRILLED HOLE IN CONCRETE	40.00	EACH
	0023	703-06029	REINFORCING BARS, EPOXY COATED	34.00	LBS
	0024	704-51002	CONCRETE, C, SUPERSTRUCTURE	0.20	CYS
	0025	709-51821	SURFACE SEAL	1.00	LS
	0026	709-51821	SURFACE SEAL	1.00	LS
	0027	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	10.00	EACH
	0028	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	561.00	SFT
	0029	738-12855	WARRANTED POLYMER OVERLAY BRIDGE DECK	755.00	SYS
	0030	801-03291	CONSTRUCTION SIGN, D	6.00	EACH
	0031	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	4594.00	LFT

0032	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	22.00	LFT
0033	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0034	801-06640	CONSTRUCTION SIGN, A	38.00	EACH
0035	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
0036	801-06775	MAINTAINING TRAFFIC	1.00	LS
0037	801-07118	BARRICADE, III-A	80.00	LFT
0038	801-12081	PORTABLE SIGNAL	1.00	LS
0039	801-12482	DRIVEWAY ASSISTANCE DEVICE	4.00	EACH
0040	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	330.00	LFT
0041	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1392.00	LFT
0042	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	1484.00	LFT
0043	808-06716	LINE, REMOVE	3960.00	LFT
0044	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	2.00	EACH
0045	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2.00	EACH

Call: 500

Contract: B -42721-A

Section No.: 1

BRIDGE DECK THIN OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0010	203-02070	BORROW	54.00 CYS
0011	205-11626	PUMP AROUND	2.00 EACH
0012	205-12108	STORMWATER MANAGEMENT BUDGET	4000.00 DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0014	205-12618	SWQCP PREPARATION	1.00 LS
0015	211-09268	STRUCTURE BACKFILL, TYPE 5	25.00 CYS
0016	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	56.00 SYS
0017	301-12233	COMPACTED AGGREGATE NO. 8	7.00 CYS
0018	507-08272	JOINTS IN PCCP, SAW AND SEAL	180.00 LFT
0019	603-06060	FENCE, FARM FIELD, RESET	125.00 LFT
0020	616-05689	RIPRAP, CLASS 2	171.00 TON
0021	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	510.00 SYS
0022	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0023	621-02770	EROSION CONTROL BLANKET	3908.00 SYS
0024	621-06553	SEED MIXTURE, R	122.00 LBS
0025	628-09403	FIELD OFFICE, C	7.00 MOS
0026	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00 EACH
0027	709-51821	SURFACE SEAL	1.00 LS
0028	710-09158	PATCHING CONCRETE STRUCTURES	10.00 SFT
0029	714-96273	HEADWALL RECONSTRUCT	1.00 LS
0030	718-06528	OUTLET PROTECTOR, 1	2.00 EACH
0031	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	50.00 SFT

0032	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	43.00	SFT
0033	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	213.00	SFT
0034	724-12773	BRIDGE EXPANSION JOINT, PCF	96.00	LFT
0035	725-11795	LINER PIPE, THERMOPLASTIC, CIRCULAR, 49.2-50.3 SFT	1080.00	LFT
0036	738-12855	WARRANTED POLYMER OVERLAY BRIDGE DECK	1180.00	SYS
0037	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0038	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3595.00	LFT
0039	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	48.00	LFT
0040	801-06640	CONSTRUCTION SIGN, A	33.00	EACH
0041	801-06645	CONSTRUCTION SIGN, B	22.00	EACH
0042	801-06775	MAINTAINING TRAFFIC	1.00	LS
0043	801-07118	BARRICADE, III-A	72.00	LFT
0044	801-12081	PORTABLE SIGNAL	1.00	LS
0045	802-04893	REFERENCE POST	1.00	EACH
0046	808-06716	LINE, REMOVE	2319.00	LFT
0047	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	1206.00	LFT
0048	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	1697.00	LFT

Call: 510

Contract: B -42724-A

Section No.: 1 BRIDGE DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0010	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0011	205-11626	PUMP AROUND	1.00 EACH
0012	205-12108	STORMWATER MANAGEMENT BUDGET	7161.00 DOL
0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0014	205-12618	SWQCP PREPARATION	1.00 LS
0015	306-08034	MILLING, ASPHALT, 1 1/2 IN.	313.00 SYS
0016	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	26.00 TON
0017	401-10258	JOINT ADHESIVE, SURFACE	180.00 LFT
0018	401-11785	LIQUID ASPHALT SEALANT	180.00 LFT
0019	406-05521	ASPHALT FOR TACK COAT	273.00 SYS
0020	507-08272	JOINTS IN PCCP, SAW AND SEAL	204.00 LFT
0021	601-06035	GUARDRAIL, RESET	94.00 LFT
0022	616-05688	RIPRAP, CLASS 1	233.00 TON
0023	616-06405	RIPRAP, REVETMENT	215.00 TON
0024	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	551.00 SYS
0025	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00 EACH
0026	621-06559	MULCHED SEEDING R	823.00 SYS
0027	628-12683	FIELD OFFICE, D	8.00 MOS
0028	709-12077	FIBER WRAP CONCRETE CASING SYSTEM	81.00 SFT
0029	709-51821	SURFACE SEAL	1.00 LS
0030	710-09158	PATCHING CONCRETE STRUCTURES	250.00 SFT
0031	722-01066	HYDRODEMOLITION	637.00 SYS

0032	722-12380	BRIDGE DECK OVERLAY, BUDGET	13237.00	DOL
0033	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	454.00	SYS
0034	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	183.00	SYS
0035	722-12732	LONGITUDINAL GROOVING	637.00	SYS
0036	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	83.00	SFT
0037	722-51874	OVERLAY DAM	82.00	SFT
0038	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	2.00	EACH
0039	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0040	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	3462.00	LFT
0041	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	1469.00	LFT
0042	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0043	801-06640	CONSTRUCTION SIGN, A	12.00	EACH
0044	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
0045	801-06775	MAINTAINING TRAFFIC	1.00	LS
0046	801-07118	BARRICADE, III-A	48.00	LFT
0047	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	665.00	LFT
0048	801-12081	PORTABLE SIGNAL	1.00	LS
0049	801-97643	TEMPORARY BUZZ STRIPS	864.00	LFT
0050	802-04893	REFERENCE POST	1.00	EACH
0051	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	51.00	LFT
0052	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	405.00	LFT
0053	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	3.00	EACH

Call: 510

Contract: B -42724-A

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0054	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	637.00	SYS

Call: 510

Contract: B -42724-A

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Line

Item No	Item Code	Description	Quantity	Unit
0055	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	637.00	SYS

Call: 520

Contract: B -42872-A

Section No.: 1 BRIDGE DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0009	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0010	202-02240	PAVEMENT REMOVAL	270.00 SYS
0011	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0012	203-02000	EXCAVATION, COMMON	465.00 CYS
0013	207-09935	SUBGRADE TREATMENT, TYPE IC	1616.00 SYS
0014	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	1621.00 SYS
0015	301-12234	COMPACTED AGGREGATE NO. 53	132.00 CYS
0016	302-06464	SUBBASE FOR PCCP	68.00 CYS
0017	304-07493	WIDENING WITH HMA, TYPE B	576.00 TON
0018	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	83.00 TON
0019	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	35.00 TON
0020	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	156.00 TON
0021	401-10258	JOINT ADHESIVE, SURFACE	2032.00 LFT
0022	401-10259	JOINT ADHESIVE, INTERMEDIATE	1492.00 LFT
0023	401-11785	LIQUID ASPHALT SEALANT	2032.00 LFT
0024	406-05520	ASPHALT FOR TACK COAT	1.00 TON
0025	503-12477	TERMINAL JOINT, TYPE HMA	76.00 LFT
0026	601-02241	GUARDRAIL, REMOVE	325.00 LFT
0027	601-12282	GUARDRAIL, MGS W-BEAM, 3 FT 1.5 IN. SPACING	12.50 LFT
0028	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	4.00 EACH
0029	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	4.00 EACH
0030	602-06729	BARRIER, DELINEATOR	16.00 EACH
0031	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	270.00 SYS

0032	628-09403	FIELD OFFICE, C	15.00	MOS
0033	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0034	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	2.00	EACH
0035	702-51863	FIELD DRILLED HOLE IN CONCRETE	40.00	EACH
0036	703-06029	REINFORCING BARS, EPOXY COATED	17825.00	LBS
0037	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	122.00	EACH
0038	704-51002	CONCRETE, C, SUPERSTRUCTURE	1.40	CYS
0039	706-09960	RAILING, CONCRETE FC	10.00	LFT
0040	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	4.00	EACH
0041	709-51821	SURFACE SEAL	1.00	LS
0042	710-09158	PATCHING CONCRETE STRUCTURES	50.00	SFT
0043	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	2.00	EACH
0044	722-01066	HYDRODEMOLITION	1041.00	SYS
0045	722-12380	BRIDGE DECK OVERLAY, BUDGET	18608.00	DOL
0046	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	1041.00	SYS
0047	722-12732	LONGITUDINAL GROOVING	1311.00	SYS
0048	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	94.00	SFT
0049	722-51874	OVERLAY DAM	87.00	SFT
0050	801-04746	ENERGY ABSORBING TERMINAL, CZ, TL-	4.00	EACH
0051	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	5656.00	LFT
0052	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0053	801-06640	CONSTRUCTION SIGN, A	27.00	EACH
0054	801-06645	CONSTRUCTION SIGN, B	2.00	EACH
0055	801-06775	MAINTAINING TRAFFIC	1.00	LS
0056	801-07119	BARRICADE, III-B	96.00	LFT
0057	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	1100.00	LFT
0058	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	3.00	EACH
0059	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0060	808-06716	LINE, REMOVE	1574.00	LFT
0061	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	380.00	LFT
0062	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	3548.00	LFT
0063	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	2084.00	LFT
0064	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	15.00	EACH
0065	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	15.00	EACH

Call: 520
Contract: B -42872-A
Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

Line
Item No **Item Code** **Description**
0066 722-51842 BRIDGE DECK OVERLAY, LATEX MODIFIED
Call: 520
Contract: B -42872-A
Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED CONCRETE

Quantity Unit
1041.00 SYS

Line
Item No **Item Code** **Description**
0067 722-01061 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED

Quantity Unit
1041.00 SYS

Call: 530

Contract: B -42921-B

Section No.: 1 BRIDGE DECK OVERLAY

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0012	202-02240	PAVEMENT REMOVAL	340.00	SYS
	0013	203-02000	EXCAVATION, COMMON	85.00	CYS
	0014	205-12108	STORMWATER MANAGEMENT BUDGET	15800.00	DOL
	0015	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0016	205-12618	SWQCP PREPARATION	1.00	LS
	0017	206-51225	EXCAVATION, DRY	10.00	CYS
	0018	206-51235	COFFERDAM	1.00	LS
	0019	207-12498	SUBGRADE TREATMENT, TYPE ID	373.00	SYS
	0020	213-09270	FLOWABLE BACKFILL, REMOVABLE	8.00	CYS
	0021	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	340.00	SYS
	0022	302-06464	SUBBASE FOR PCCP	85.00	CYS
	0023	303-01180	COMPACTED AGGREGATE NO. 53	21.00	TON
	0024	304-07493	WIDENING WITH HMA, TYPE B	125.00	TON
	0025	306-08034	MILLING, ASPHALT, 1 1/2 IN.	264.00	SYS
	0026	306-08043	MILLING, TRANSITION	430.00	SYS
	0027	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	57.00	TON
	0028	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	22.00	TON
	0029	401-10258	JOINT ADHESIVE, SURFACE	829.00	LFT
	0030	401-10259	JOINT ADHESIVE, INTERMEDIATE	559.00	LFT
	0031	401-11785	LIQUID ASPHALT SEALANT	829.00	LFT

0032	406-05521	ASPHALT FOR TACK COAT	1191.00	SYS
0033	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	2.00	TON
0034	506-06333	PCCP PATCHING, FULL DEPTH	6.00	SYS
0035	507-08271	JOINTS IN PCCP, FILLED	92.00	LFT
0036	601-06035	GUARDRAIL, RESET	502.00	LFT
0037	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	90.00	LFT
0038	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	340.00	SYS
0039	616-02281	GROUT FOR RIPRAP	15.00	CYS
0040	616-06405	RIPRAP, REVETMENT	50.00	TON
0041	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0042	621-06559	MULCHED SEEDING R	242.00	SYS
0043	621-06565	MULCHING MATERIAL	1.00	TON
0044	621-06567	WATER	1.00	KGAL
0045	621-12612	SEED MIXTURE, FLOODPLAIN	4.00	LBS
0046	621-52448	SIGN, DO NOT SPRAY	2.00	EACH
0047	628-09403	FIELD OFFICE, C	6.00	MOS
0048	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
0049	702-51863	FIELD DRILLED HOLE IN CONCRETE	44.00	EACH
0050	703-06029	REINFORCING BARS, EPOXY COATED	18664.00	LBS
0051	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	146.00	EACH
0052	709-51821	SURFACE SEAL	1.00	LS
0053	709-51821	SURFACE SEAL	1.00	LS
0054	710-09158	PATCHING CONCRETE STRUCTURES	110.00	SFT
0055	722-01066	HYDRODEMOLITION	932.00	SYS
0056	722-12380	BRIDGE DECK OVERLAY, BUDGET	16300.00	DOL
0057	722-12463	BRIDGE DECK, REMOVE EXISTING CONCRETE OVERLAY	272.00	SYS
0058	722-12464	BRIDGE DECK, REMOVE EXISTING CONCRETE SURFACE	660.00	SYS
0059	722-12732	LONGITUDINAL GROOVING	1272.00	SYS
0060	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	295.00	SFT
0061	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	4.00	EACH
0062	801-06203	TEMPORARY PAVEMENT MARKING, 4 IN.	2730.00	LFT
0063	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1600.00	LFT
0064	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	46.00	LFT
0065	801-06640	CONSTRUCTION SIGN, A	52.00	EACH
0066	801-06645	CONSTRUCTION SIGN, B	11.00	EACH
0067	801-06775	MAINTAINING TRAFFIC	1.00	LS
0068	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	4.00	EACH

0069	801-07118	BARRICADE, III-A	54.00	LFT
0070	801-07119	BARRICADE, III-B	24.00	LFT
0071	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	400.00	LFT
0072	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	440.00	LFT
0073	801-12081	PORTABLE SIGNAL	1.00	LS
0074	801-12082	FIXED TEMPORARY SIGNAL	1.00	LS
0075	802-91122	SIGN GROUND MOUNTED RESET	3.00	EACH
0076	808-06716	LINE, REMOVE	2250.00	LFT
0077	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	1120.00	LFT
0078	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	560.00	LFT
0079	808-12032	GROOVING FOR PAVEMENT MARKINGS	2765.00	LFT
0080	808-12841	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 6 IN.	140.00	LFT
0081	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	1207.00	LFT
0082	808-75047	LINE, PAINT, SOLID, YELLOW, 6 IN.	730.00	LFT
0083	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	5.00	EACH
0084	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	2.00	EACH

Call: 530

Contract: B -42921-B

Section No.: 2 BRIDGE DECK OVERLAY, LATEX MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0085	722-51842	BRIDGE DECK OVERLAY, LATEX MODIFIED	932.00	SYS

Call: 530

Contract: B -42921-B

Section No.: 3 BRIDGE DECK OVERLAY, SILICA FUME MODIFIED CONCRETE

Line

Item No	Item Code	Description	Quantity	Unit
0086	722-01061	BRIDGE DECK OVERLAY, SILICA FUME MODIFIED	932.00	SYS

Call: 540

Contract: B -43023-A

Section No.: 1

SMALL STRUCTURE REPLACEMENT

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
	0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0007	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
	0008	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0009	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0010	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0011	202-02240	PAVEMENT REMOVAL	527.00	SYS
	0012	202-02271	HEADWALL, REMOVE	2.00	EACH
	0013	202-51330	PRESENT STRUCTURE, REMOVE	1.00	LS
	0014	203-02000	EXCAVATION, COMMON	1710.00	CYS
	0015	203-02010	EXCAVATION, ROCK	156.00	CYS
	0016	203-02070	BORROW	3930.00	CYS
	0017	205-11626	PUMP AROUND	1.00	EACH
	0018	205-12108	STORMWATER MANAGEMENT BUDGET	4100.00	DOL
	0019	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0020	205-12618	SWQCP PREPARATION	1.00	LS
	0021	206-93520	TEMPORARY SHEET PILING	1200.00	SFT
	0022	207-09935	SUBGRADE TREATMENT, TYPE IC	1054.00	SYS
	0023	211-02050	B BORROW	565.00	CYS
	0024	211-09265	STRUCTURE BACKFILL, TYPE 2	4759.00	CYS
	0025	301-12232	COMPACTED AGGREGATE NO. 5	78.00	CYS
	0026	301-12233	COMPACTED AGGREGATE NO. 8	78.00	CYS
	0027	301-12234	COMPACTED AGGREGATE NO. 53	78.00	CYS
	0028	303-01180	COMPACTED AGGREGATE NO. 53	110.00	TON
	0029	306-08043	MILLING, TRANSITION	1293.00	SYS
	0030	401-07322	QC/QA-HMA, 3, 64, SURFACE, 9.5 mm	185.00	TON
	0031	401-07392	QC/QA-HMA, 3, 64, INTERMEDIATE, 19.0 mm	133.00	TON

0032	401-07424	QC/QA-HMA, 3, 64, BASE, 19.0 mm	326.00	TON
0033	401-10258	JOINT ADHESIVE, SURFACE	1140.00	LFT
0034	401-10259	JOINT ADHESIVE, INTERMEDIATE	780.00	LFT
0035	401-11785	LIQUID ASPHALT SEALANT	1140.00	LFT
0036	406-05520	ASPHALT FOR TACK COAT	1.00	TON
0037	408-12028	CRACKS IN ASPHALT PAVEMENT, FILL	0.10	TON
0038	601-02241	GUARDRAIL, REMOVE	260.00	LFT
0039	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	260.00	LFT
0040	606-12400	MILLED HMA CORRUGATIONS, SINUSOIDAL	1860.00	LFT
0041	615-06490	RIGHT-OF-WAY MARKER	12.00	EACH
0042	615-06505	MONUMENT, B	2.00	EACH
0043	616-05689	RIPRAP, CLASS 2	278.00	TON
0044	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	339.00	SYS
0045	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	1160.00	SYS
0046	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	1.00	EACH
0047	621-06559	MULCHED SEEDING R	3460.00	SYS
0048	628-09403	FIELD OFFICE, C	12.00	MOS
0049	714-11148	STRUCTURE, REINFORCED CONCRETE, BOX SECTIONS, 19 FT X 11 FT	175.00	LFT
0050	801-04308	ROAD CLOSURE SIGN ASSEMBLY	2.00	EACH
0051	801-06625	DETOUR ROUTE MARKER ASSEMBLY	20.00	EACH
0052	801-06640	CONSTRUCTION SIGN, A	18.00	EACH
0053	801-06775	MAINTAINING TRAFFIC	1.00	LS
0054	801-07118	BARRICADE, III-A	24.00	LFT
0055	801-07119	BARRICADE, III-B	48.00	LFT
0056	808-06712	LINE, PAINT, BROKEN, YELLOW, 4 IN.	155.00	LFT
0057	808-06713	LINE, PAINT, SOLID, WHITE, 4 IN.	1240.00	LFT
0058	808-06714	LINE, PAINT, SOLID, YELLOW, 4 IN.	620.00	LFT

Call: 560

Contract: B -43172-A

Section No.: 1 BRIDGE THIN DECK OVERLAY

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0003	109-08360	CONTRACT LIENS	1.00 DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0008	213-09269	FLOWABLE BACKFILL, NON-REMOVABLE	1.00 CYS
0009	303-01180	COMPACTED AGGREGATE NO. 53	24.00 TON
0010	306-08034	MILLING, ASPHALT, 1 1/2 IN.	27.00 SYS
0011	503-12480	TERMINAL JOINT, RETROFIT POLYMER MODIFIED ASPHALT	182.00 SFT
0012	507-08271	JOINTS IN PCCP, FILLED	103.00 LFT
0013	507-08272	JOINTS IN PCCP, SAW AND SEAL	200.00 LFT
0014	602-06729	BARRIER, DELINEATOR	4.00 EACH
0015	604-05528	HMA FOR SIDEWALK	3.00 TON
0016	628-09403	FIELD OFFICE, C	4.00 MOS
0017	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00 EACH
0018	709-04647	FIBER WRAP CONCRETE CASING SYSTEM	1.00 LS
0019	709-51821	SURFACE SEAL	1.00 LS
0020	709-51821	SURFACE SEAL	1.00 LS
0021	709-51821	SURFACE SEAL	1.00 LS
0022	710-09158	PATCHING CONCRETE STRUCTURES	258.00 SFT
0023	711-97990	TIGHTEN ANCHOR BOLT NUTS	20.00 EACH
0024	722-51401	BRIDGE DECK PATCHING, FULL DEPTH	73.00 SFT
0025	722-51852	BRIDGE DECK PATCHING, PARTIAL DEPTH	313.00 SFT
0026	727-90308	EPOXY INJECTION, CRACK PREPARATION	135.00 LFT
0027	727-90309	EPOXY INJECTION, EPOXY MATERIAL	4.00 GAL
0028	727-93560	EPOXY INJECTION, FURNISHING EQUIPMENT	1.00 LS
0029	738-12855	WARRANTED POLYMER OVERLAY BRIDGE DECK	2429.00 SYS
0030	738-12856	POLYMER OVERLAY, OTHER CONCRETE SURFACE	741.00 SYS
0031	801-04308	ROAD CLOSURE SIGN ASSEMBLY	9.00 EACH

0032	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	1080.00	LFT
0033	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	1200.00	LFT
0034	801-06209	TEMPORARY PAVEMENT MARKING, REMOVABLE, 6 IN.	1745.00	LFT
0035	801-06218	TEMPORARY TRANSVERSE PAVEMENT MARKING, REMOVABLE, 24 IN.	24.00	LFT
0036	801-06625	DETOUR ROUTE MARKER ASSEMBLY	12.00	EACH
0037	801-06640	CONSTRUCTION SIGN, A	55.00	EACH
0038	801-06645	CONSTRUCTION SIGN, B	7.00	EACH
0039	801-06710	FLASHING ARROW SIGN	14.00	DAY
0040	801-06775	MAINTAINING TRAFFIC	1.00	LS
0041	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	4.00	EACH
0042	801-07118	BARRICADE, III-A	119.00	LFT
0043	801-07119	BARRICADE, III-B	60.00	LFT
0044	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	2160.00	LFT
0045	801-12042	TRUCK MOUNTED ATTENUATOR	14.00	DAY
0046	801-12081	PORTABLE SIGNAL	1.00	LS
0047	801-12324	LAW ENFORCEMENT OFFICER	140.00	HRS
0048	801-12641	TEMPORARY ACCESSIBLE PEDESTRIAN PATH	34.00	SYS
0049	801-12862	TEMPORARY PEDESTRIAN CHANNELIZER	363.00	LFT
0050	805-10107	WIRELESS MAGNETOMETER DETECTOR	1.00	EACH
0051	808-10033	LINE, MULTI-COMPONENT, SOLID, WHITE, 4 IN.	729.00	LFT
0052	808-10034	LINE, MULTI-COMPONENT, SOLID, YELLOW, 4 IN.	365.00	LFT
0053	808-10036	LINE, MULTI-COMPONENT, BROKEN, YELLOW, 4 IN.	91.00	LFT
0054	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	303.00	LFT
0055	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN	80.00	LFT
0056	808-12764	LINE, PAINT, BROKEN, YELLOW, 6 IN.	46.00	LFT
0057	808-75007	LINE, PAINT, SOLID, WHITE, 6 IN.	362.00	LFT
0058	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	6.00	EACH

Call: 570

Contract: B -43675-A

Section No.: 1 BRIDGE REPLACEMENT

Line			
Item No	Item Code	Description	Quantity Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00 LS
0002	107-09358	INSPECTION HOLE, DEEPER THAN 3 FT	4.00 EACH
0003	107-09367	INSPECTION HOLE, 3 FT DEEP OR LESS	4.00 EACH
0004	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0005	109-08360	CONTRACT LIENS	1.00 DOL
0006	109-08440	QUALITY ADJUSTMENTS, HMA	1.00 DOL
0007	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0008	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0009	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00 DOL
0010	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00 DOL
0011	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00 DOL
0012	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0013	201-52370	CLEARING RIGHT OF WAY	1.00 LS
0014	202-02240	PAVEMENT REMOVAL	3707.00 SYS
0015	202-51328	PRESENT STRUCTURE, REMOVE PORTIONS	1.00 LS
0016	202-51330	PRESENT STRUCTURE, REMOVE	1.00 LS
0017	203-02000	EXCAVATION, COMMON	862.00 CYS
0018	203-51223	EXCAVATION, WATERWAY	1166.00 CYS
0019	205-12108	STORMWATER MANAGEMENT BUDGET	38000.00 DOL
0020	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00 LS
0021	205-12618	SWQCP PREPARATION	1.00 LS
0022	206-51220	EXCAVATION, WET	521.00 CYS
0023	206-51235	COFFERDAM	1.00 LS
0024	207-08264	SUBGRADE TREATMENT, TYPE II	99.00 SYS
0025	207-09935	SUBGRADE TREATMENT, TYPE IC	5277.00 SYS
0026	211-06467	AGGREGATE FOR END BENT BACKFILL	159.00 CYS
0027	214-12239	GEOTEXTILE FOR PAVEMENT TYPE 2B	6082.00 SYS
0028	302-06464	SUBBASE FOR PCCP	226.00 CYS
0029	303-01180	COMPACTED AGGREGATE NO. 53	872.00 TON
0030	306-08034	MILLING, ASPHALT, 1 1/2 IN.	681.00 SYS
0031	306-08043	MILLING, TRANSITION	344.00 SYS

0032	401-07321	QC/QA-HMA, 2, 64, SURFACE, 9.5 mm	438.00 TON
0033	401-07390	QC/QA-HMA, 2, 64, INTERMEDIATE, 19.0 mm	590.00 TON
0034	401-07407	QC/QA-HMA, 2, 64, BASE, 25.0 mm	881.00 TON
0035	401-07423	QC/QA-HMA, 2, 64, BASE, 19.0 mm	954.00 TON
0036	401-10258	JOINT ADHESIVE, SURFACE	5147.00 LFT
0037	401-10259	JOINT ADHESIVE, INTERMEDIATE	4257.00 LFT
0038	401-12483	RAPID PENETRATING EMULSION	5147.00 LFT
0039	406-05521	ASPHALT FOR TACK COAT	9633.00 SYS
0040	408-07478	CRACKS AND JOINTS IN ASPHALT PAVEMENT, ROUT AND SEAL	2.00 TON
0041	503-12477	TERMINAL JOINT, TYPE HMA	120.00 LFT
0042	601-01846	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 3	1.00 EACH
0043	601-02241	GUARDRAIL, REMOVE	1370.00 LFT
0044	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	275.00 LFT
0045	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	1.00 EACH
0046	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	4.00 EACH
0047	601-94689	GUARDRAIL, END TREATMENT, OS	3.00 EACH
0048	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	6.25 LFT
0049	602-06729	BARRIER, DELINEATOR	22.00 EACH
0050	609-06259	REINFORCED CONCRETE BRIDGE APPROACH, 12 IN.	892.00 SYS
0051	610-07487	HMA FOR APPROACHES, TYPE B	22.00 TON
0052	611-06497	MAILBOX ASSEMBLY, SINGLE	1.00 EACH
0053	615-06490	RIGHT-OF-WAY MARKER	17.00 EACH
0054	615-06505	MONUMENT, B	4.00 EACH
0055	616-05688	RIPRAP, CLASS 1	1444.00 TON
0056	616-06405	RIPRAP, REVETMENT	666.00 TON
0057	616-12248	GEOTEXTILE FOR RIPRAP TYPE 2A	2956.00 SYS
0058	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00 EACH
0059	621-06559	MULCHED SEEDING R	1709.00 SYS
0060	621-06565	MULCHING MATERIAL	1.00 TON
0061	621-06574	SODDING	120.00 SYS
0062	621-12612	SEED MIXTURE, FLOODPLAIN	36.00 LBS
0063	622-05639	PLANT, DECIDUOUS SHRUB, 18 IN. TO 24 IN.	25.00 EACH
0064	622-05649	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. TO 2 IN.	50.00 EACH
0065	622-52436	SIGN, DO NOT MOW OR SPRAY	4.00 EACH
0066	628-09403	FIELD OFFICE, C	12.00 MOS
0067	701-06011	DYNAMIC PILE LOAD TEST	6.00 EACH
0068	701-09557	TEST PILE, DYNAMIC, PRODUCTION	450.00 LFT

0069	701-09559	TEST PILE, DYNAMIC, RESTRIKE	6.00 EACH
0070	701-09679	CONICAL PILE TIP, 14 IN.	68.00 EACH
0071	701-09826	PILE, STEEL PIPE, 0.5 IN., 14 IN.	4130.00 LFT
0072	702-03607	CORED HOLE IN CONCRETE	16.00 EACH
0073	702-04325	TEMPORARY SHORING	1.00 LS
0074	702-12076	GRATES, BASINS, AND FITTINGS, CAST IRON	14.00 EACH
0075	702-51005	CONCRETE, A, SUBSTRUCTURE	196.20 CYS
0076	702-51015	CONCRETE, B, FOOTINGS	180.00 CYS
0077	702-92857	CONCRETE, C, SUBSTRUCTURE	138.90 CYS
0078	703-06028	REINFORCING BARS	30452.00 LBS
0079	703-06029	REINFORCING BARS, EPOXY COATED	283687.00 LBS
0080	703-97936	THREADED TIE BAR ASSEMBLY, EPOXY COATED	628.00 EACH
0081	704-51002	CONCRETE, C, SUPERSTRUCTURE	713.20 CYS
0082	706-11600	RAILING, CONCRETE FC	57.10 CYS
0083	706-11620	CONCRETE BRIDGE RAILING TRANSITION, TFC	8.00 EACH
0084	707-05984	STRUCTURAL MEMBER, CONCRETE, I-BEAM, 45 IN. X 16 IN.	1712.00 LFT
0085	707-09865	STRUCTURAL MEMBER, CONCRETE, BULB-T BEAM, 36 IN. X 49 IN.	652.00 LFT
0086	709-51821	SURFACE SEAL	1.00 LS
0087	709-51821	SURFACE SEAL	1.00 LS
0088	715-05407	PIPE, END BENT DRAIN, 6 IN.	380.00 LFT
0089	715-10238	PIPE, ROADWAY DRAIN CASTING EXTENSION	14.00 EACH
0090	722-12732	LONGITUDINAL GROOVING	2938.60 SYS
0091	801-04308	ROAD CLOSURE SIGN ASSEMBLY	8.00 EACH
0092	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	24983.00 LFT
0093	801-06625	DETOUR ROUTE MARKER ASSEMBLY	37.00 EACH
0094	801-06640	CONSTRUCTION SIGN, A	77.00 EACH
0095	801-06645	CONSTRUCTION SIGN, B	16.00 EACH
0096	801-06710	FLASHING ARROW SIGN	480.00 DAY
0097	801-06775	MAINTAINING TRAFFIC	1.00 LS
0098	801-07023	ENERGY ABSORBING TERMINAL, CZ, TL-2	2.00 EACH
0099	801-07118	BARRICADE, III-A	120.00 LFT
0100	801-07119	BARRICADE, III-B	180.00 LFT
0101	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	560.00 LFT
0102	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	4.00 EACH
0103	801-12042	TRUCK MOUNTED ATTENUATOR	60.00 DAY
0104	801-52817	TEMPORARY CROSSOVER, B	2.00 EACH
0105	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	65.50 LFT

0106	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	12.00	SFT
0107	802-91122	SIGN GROUND MOUNTED RESET	3.00	EACH
0108	808-06716	LINE, REMOVE	3834.00	LFT
0109	808-10049	LINE, MULTI-COMPONENT, SOLID, WHITE, 6 IN.	4490.00	LFT
0110	808-10057	LINE, MULTI-COMPONENT, SOLID, YELLOW, 6 IN.	4310.00	LFT
0111	808-10071	LINE, MULTI-COMPONENT, BROKEN, WHITE, 6 IN	1338.00	LFT
0112	808-12032	GROOVING FOR PAVEMENT MARKINGS	8231.00	LFT
0113	808-75996	SNOWPLOWABLE RAISED PAVEMENT MARKER, REMOVE	44.00	EACH
0114	808-75998	SNOWPLOWABLE RAISED PAVEMENT MARKER	32.00	EACH

Call: 580

Contract: B -43864-A

Section No.: 1

DEBRIS REMOVAL FROM CHANNEL

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0010	201-90788	DEBRIS, REMOVE STRUCTURE NO.	1.00	LS
	0011	203-51223	EXCAVATION, WATERWAY	455.00	CYS
	0012	205-12108	STORMWATER MANAGEMENT BUDGET	11835.00	DOL
	0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0014	205-12618	SWQCP PREPARATION	1.00	LS
	0015	206-51235	COFFERDAM	1.00	LS
	0016	206-51235	COFFERDAM	1.00	LS
	0017	601-06035	GUARDRAIL, RESET	100.00	LFT
	0018	616-05689	RIPRAP, CLASS 2	14.00	TON
	0019	616-06405	RIPRAP, REVETMENT	29.00	TON
	0020	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	36.00	SYS
	0021	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
	0022	621-06559	MULCHED SEEDING R	224.00	SYS
	0023	710-09158	PATCHING CONCRETE STRUCTURES	64.00	SFT
	0024	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	23.00	LFT
	0025	801-06211	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, LANE INDICATION ARROW	3.00	EACH
	0026	801-06212	TEMPORARY PAVEMENT MESSAGE MARKING, REMOVABLE, (ONLY)	3.00	EACH
	0027	801-06469	TEMPORARY PAVEMENT MARKING, REMOVABLE, 8 IN.	675.00	LFT
	0028	801-06640	CONSTRUCTION SIGN, A	61.00	EACH
	0029	801-06645	CONSTRUCTION SIGN, B	4.00	EACH
	0030	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0031	801-07024	ENERGY ABSORBING TERMINAL, CZ, TL-3	1.00	EACH

0032	801-08401	TEMPORARY TRAFFIC BARRIER, TYPE 2	50.00	LFT
0033	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	125.00	LFT
0034	801-12042	TRUCK MOUNTED ATTENUATOR	5.00	DAY
0035	801-12324	LAW ENFORCEMENT OFFICER	16.00	HRS
0036	808-06716	LINE, REMOVE	70.00	LFT
0037	808-12842	LINE, PAINT, DOTTED, WHITE, 6 IN.	20.00	LFT
0038	808-75001	LINE, PAINT, BROKEN, WHITE, 5 IN.	50.00	LFT

Call: 600

Contract: B -44342-A

Section No.: 1 SUBSTRUCTURE REPAIR AND REHABILITATION

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-08463	PROJECT ESTIMATE ADJUSTMENT	1.00	DOL
	0007	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0008	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0009	201-01015	CLEARING AND GRUBBING	1.00	LS
	0010	203-02000	EXCAVATION, COMMON	20.00	CYS
	0011	205-11626	PUMP AROUND	1.00	EACH
	0012	205-12108	STORMWATER MANAGEMENT BUDGET	4315.00	DOL
	0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0014	205-12618	SWQCP PREPARATION	1.00	LS
	0015	601-06035	GUARDRAIL, RESET	63.00	LFT
	0016	616-06405	RIPRAP, REVETMENT	56.00	TON
	0017	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	74.00	SYS
	0018	619-12459	DISPOSAL OF CLEANING WASTE HAZARDOUS BRIDGE NO.	1.00	LS
	0019	619-12507	CLEAN AND PAINT STEEL PILING BRIDGE NO.	1.00	LS
	0020	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
	0021	621-04258	SEED MIXTURE	1.00	LBS
	0022	621-06559	MULCHED SEEDING R	399.00	SYS
	0023	621-12612	SEED MIXTURE, FLOODPLAIN	1.00	LBS
	0024	703-08247	EMBEDDED GALVANIC ANODE	17.00	EACH
	0025	710-09158	PATCHING CONCRETE STRUCTURES	308.00	SFT
	0026	801-03290	CONSTRUCTION SIGN, C	2.00	EACH
	0027	801-04308	ROAD CLOSURE SIGN ASSEMBLY	11.00	EACH
	0028	801-06625	DETOUR ROUTE MARKER ASSEMBLY	91.00	EACH
	0029	801-06640	CONSTRUCTION SIGN, A	21.00	EACH
	0030	801-06645	CONSTRUCTION SIGN, B	6.00	EACH
	0031	801-06775	MAINTAINING TRAFFIC	1.00	LS

0032	801-07118	BARRICADE, III-A
0033	801-07119	BARRICADE, III-B

256.00	LFT
200.00	LFT

Call: 700

Contract: M -44351-A

Section No.: 1 GUARDRAIL, MAINTENANCE OR REPAIR

Line			
Item No	Item Code	Description	Quantity Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0002	109-08360	CONTRACT LIENS	1.00 DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0006	601-01128	GUARDRAIL, TRANSITION, TYPE WGB	1.00 EACH
0007	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	2.00 EACH
0008	601-02103	GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN. SPACING	290.00 LFT
0009	601-02212	GUARDRAIL POST, BRACKET, 8.5 LBS PER FT, GALVANIZED, 1 FT 5 IN.	800.00 EACH
0010	601-03446	CAT TRANSITION CABLE MK CA	1.00 EACH
0011	601-03462	GUARDRAIL, POST STEEL, 8.5 LBS PER LFT, 7 FT 0 IN.	250.00 EACH
0012	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	1.00 EACH
0013	601-03492	GUARDRAIL MISCELLANEOUS MATERIAL AND LABOR FOR REPAIR	1.00 LS
0014	601-03599	GUARDRAIL, THRIE-BEAM, RAIL SECTION, 12 FT 6 IN	6.00 EACH
0015	601-03683	COMBINATION ATTENUATING TERMINAL, REPAIR, LABOR ONLY	2.00 HRS
0016	601-05856	CAT	26.00 EACH
0017	601-05856	CAT	14.00 EACH
0018	601-05856	CAT	1.00 EACH
0019	601-05856	CAT	1.00 EACH
0020	601-05856	CAT	8.00 EACH
0021	601-05856	CAT	10.00 EACH
0022	601-05856	CAT	6.00 EACH
0023	601-05856	CAT	9.00 EACH
0024	601-05856	CAT	1.00 EACH
0025	601-05999	CURVED TERMINAL END	1.00 EACH
0026	601-05999	CURVED TERMINAL END	1.00 EACH
0027	601-05999	CURVED TERMINAL END	1.00 EACH
0028	601-06234	IMPACT ATTENUATOR, R1-W1, TL-2	1.00 EACH
0029	601-06242	IMPACT ATTENUATOR, R2-W1, TL-2	1.00 EACH
0030	601-06246	IMPACT ATTENUATOR, R2-W1, TL-3	1.00 EACH
0031	601-06306	IMPACT ATTENUATOR, RESET, R2-W1, TL-3	1.00 EACH

0032	601-06855	GUARDRAIL, W-BEAM, CABLE TERMINAL ANCHOR	3.00 EACH
0033	601-07607	IMPACT ATTENUATOR	9.00 EACH
0034	601-07607	IMPACT ATTENUATOR	1.00 EACH
0035	601-07607	IMPACT ATTENUATOR	1.00 EACH
0036	601-07607	IMPACT ATTENUATOR	1.00 EACH
0037	601-07607	IMPACT ATTENUATOR	1.00 EACH
0038	601-07607	IMPACT ATTENUATOR	1.00 EACH
0039	601-07607	IMPACT ATTENUATOR	4.00 EACH
0040	601-07607	IMPACT ATTENUATOR	1.00 EACH
0041	601-07607	IMPACT ATTENUATOR	1.00 EACH
0042	601-07607	IMPACT ATTENUATOR	1.00 EACH
0043	601-07607	IMPACT ATTENUATOR	1.00 EACH
0044	601-07607	IMPACT ATTENUATOR	1.00 EACH
0045	601-07607	IMPACT ATTENUATOR	1.00 EACH
0046	601-07607	IMPACT ATTENUATOR	1.00 EACH
0047	601-07607	IMPACT ATTENUATOR	1.00 EACH
0048	601-07607	IMPACT ATTENUATOR	1.00 EACH
0049	601-07607	IMPACT ATTENUATOR	1.00 EACH
0050	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	20.00 EACH
0051	601-52501	GUARDRAIL, POST	1.00 EACH
0052	601-52501	GUARDRAIL, POST	1.00 EACH
0053	601-61340	GUARDRAIL POST, 15.5 LBS PER FT, GALVANIZED, 6 FT 3 IN. LONG	1.00 EACH
0054	601-61350	GUARDRAIL POST BRACKET, 15.5 LBS PER LFT, GALVANIZED, 1 FT 2.25 IN.	1.00 EACH
0055	601-61390	GUARDRAIL, TERMINAL END SECTION, CURVED, SINGLE FACE, GALVANIZED	3.00 EACH
0056	601-62530	GUARDRAIL, PIER CONNECTION, ES	1.00 EACH
0057	601-62540	GUARDRAIL, POST, PLUMB	700.00 EACH
0058	601-91147	GUARDRAIL, END TREATMENT, RESET	1.00 EACH
0059	601-91428	GUARDRAIL, ATTENUATING TERMINAL, NOSE ASSEMBLY, MKN	10.00 EACH
0060	601-91428	GUARDRAIL, ATTENUATING TERMINAL, NOSE ASSEMBLY, MKN	15.00 EACH
0061	601-91502	GUARDRAIL, TERMINAL SECTION, WOOD BREAKAWAY POST	1.00 EACH
0062	601-91504	GUARDRAIL, POST, W1, 10 IN. X 10 IN.	1.00 EACH
0063	601-91505	GUARDRAIL, POST, W2, 8 IN. X 8 IN.	1.00 EACH
0064	601-91542	GUARDRAIL, BLOCKOUT, 6 IN. X 8 IN., B1	1.00 EACH
0065	601-91649	GUARDRAIL, THRIE BEAM TRANSITION SECTION, GALVANIZED	4.00 EACH
0066	601-91653	GUARDRAIL, THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	1.00 EACH
0067	601-94689	GUARDRAIL, END TREATMENT, OS	50.00 EACH
0068	601-94690	GUARDRAIL, END TREATMENT, MS	2.00 EACH

0069	601-95972	GUARDRAIL, POST (CRT), 8 IN X 6 IN TREATED LUMBER, 6 FT 0 IN. LONG	5.00 EACH
0070	601-96591	GUARDRAIL, PANEL, STEEL BEAM	14500.00 LFT
0071	601-97950	GUARDRAIL, POST BRACKET, TREATED TIMBER, 6 IN. X 6 IN.	1.00 EACH
0072	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	1600.00 LFT
0073	601-99108	GUARDRAIL, W-BEAM, DOUBLE FACED, 6 FT 3 IN. SPACING	350.00 LFT
0074	601-99109	GUARDRAIL, W-BEAM, DOUBLE FACED, 3 FT 1.5 IN. SPACING	1.00 LFT
0075	627-11647	CABLE BARRIER SYSTEM, TYPE TL-4, RESET	750.00 LFT
0076	628-09403	FIELD OFFICE, C	18.00 MOS
0077	628-11976	COMPUTER SYSTEM EQUIPMENT	5.00 EACH
0078	801-06775	MAINTAINING TRAFFIC	1.00 LS
0079	801-12042	TRUCK MOUNTED ATTENUATOR	100.00 DAY
0080	801-12324	LAW ENFORCEMENT OFFICER	150.00 HRS

Call: 710

Contract: M -44354-A

Section No.: 1 GUARDRAIL, MAINTENANCE OR REPAIR

Line			
Item No	Item Code	Description	Quantity Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00 DOL
0002	109-08360	CONTRACT LIENS	1.00 DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00 DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00 DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00 LS
0006	601-01128	GUARDRAIL, TRANSITION, TYPE WGB	3.00 EACH
0007	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	3.00 EACH
0008	601-02103	GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN. SPACING	250.00 LFT
0009	601-03444	CAT TRANSITION STEEL POST MK 9	3.00 EACH
0010	601-03445	CAT TRANSITION PANEL MK WC	14.00 EACH
0011	601-03446	CAT TRANSITION CABLE MK CA	4.00 EACH
0012	601-03447	CAT BRACKET MK BK, FOR TRANSITION CABLE, MK CA	40.00 EACH
0013	601-03462	GUARDRAIL, POST STEEL, 8.5 LBS PER LFT, 7 FT 0 IN.	300.00 EACH
0014	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	15.00 EACH
0015	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	6.00 EACH
0016	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	6.00 EACH
0017	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	4.00 EACH
0018	601-03471	CAT UNIT COMPLETE WITHOUT FOUNDATION TUBES OR SOIL PLATES ABOVE GROUND COMPONENTS ONLY	3.00 EACH
0019	601-03492	GUARDRAIL MISCELLANEOUS MATERIAL AND LABOR FOR REPAIR	1.00 LS
0020	601-03599	GUARDRAIL, THRIE-BEAM, RAIL SECTION, 12 FT 6 IN	3.00 EACH
0021	601-03683	COMBINATION ATTENUATING TERMINAL, REPAIR, LABOR ONLY	14.00 HRS
0022	601-05856	CAT	2.00 EACH
0023	601-05856	CAT	4.00 EACH
0024	601-05856	CAT	3.00 EACH
0025	601-05856	CAT	3.00 EACH
0026	601-05856	CAT	6.00 EACH
0027	601-05856	CAT	3.00 EACH
0028	601-05856	CAT	3.00 EACH
0029	601-05856	CAT	4.00 EACH
0030	601-05857	GUARDRAIL, BLOCKOUT, WOOD, 4 IN. X 6 IN.	140.00 EACH
0031	601-06234	IMPACT ATTENUATOR, R1-W1, TL-2	1.00 EACH

0032	601-06242	IMPACT ATTENUATOR, R2-W1, TL-2	1.00 EACH
0033	601-06243	IMPACT ATTENUATOR, R2-W2, TL-2	1.00 EACH
0034	601-06247	IMPACT ATTENUATOR, R2-W2, TL-3	1.00 EACH
0035	601-06273	GUARDRAIL, END TREATMENT, SKT-350	18.00 EACH
0036	601-06273	GUARDRAIL, END TREATMENT, SKT-350	14.00 EACH
0037	601-06273	GUARDRAIL, END TREATMENT, SKT-350	32.00 EACH
0038	601-06273	GUARDRAIL, END TREATMENT, SKT-350	14.00 EACH
0039	601-06273	GUARDRAIL, END TREATMENT, SKT-350	28.00 EACH
0040	601-06306	IMPACT ATTENUATOR, RESET, R2-W1, TL-3	1.00 EACH
0041	601-07607	IMPACT ATTENUATOR	1.00 EACH
0042	601-07607	IMPACT ATTENUATOR	1.00 EACH
0043	601-07607	IMPACT ATTENUATOR	3.00 EACH
0044	601-07607	IMPACT ATTENUATOR	1.00 EACH
0045	601-07607	IMPACT ATTENUATOR	1.00 EACH
0046	601-07607	IMPACT ATTENUATOR	1.00 EACH
0047	601-07607	IMPACT ATTENUATOR	2.00 EACH
0048	601-07607	IMPACT ATTENUATOR	1.00 EACH
0049	601-07607	IMPACT ATTENUATOR	1.00 EACH
0050	601-07607	IMPACT ATTENUATOR	4.00 EACH
0051	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	40.00 EACH
0052	601-61340	GUARDRAIL POST, 15.5 LBS PER FT, GALVANIZED, 6 FT 3 IN. LONG	20.00 EACH
0053	601-61350	GUARDRAIL POST BRACKET, 15.5 LBS PER LFT, GALVANIZED, 1 FT 2.25 IN.	30.00 EACH
0054	601-61390	GUARDRAIL, TERMINAL END SECTION, CURVED, SINGLE FACE, GALVANIZED	2.00 EACH
0055	601-62530	GUARDRAIL, PIER CONNECTION, ES	21.00 EACH
0056	601-62540	GUARDRAIL, POST, PLUMB	935.00 EACH
0057	601-91428	GUARDRAIL, ATTENUATING TERMINAL, NOSE ASSEMBLY, MKN	100.00 EACH
0058	601-91432	GUARDRAIL, ATTENUATING TERMINAL, SIDE PLATE, MKSD	18.00 EACH
0059	601-91504	GUARDRAIL, POST, W1, 10 IN. X 10 IN.	4.00 EACH
0060	601-91505	GUARDRAIL, POST, W2, 8 IN. X 8 IN.	2.00 EACH
0061	601-91542	GUARDRAIL, BLOCKOUT, 6 IN. X 8 IN., B1	68.00 EACH
0062	601-91649	GUARDRAIL, THRIE BEAM TRANSITION SECTION, GALVANIZED	2.00 EACH
0063	601-91653	GUARDRAIL, THRIE BEAM TERMINAL CONNECTOR, GALVANIZED	2.00 EACH
0064	601-93346	GUARDRAIL, CONNECTOR, AS	6.00 EACH
0065	601-94689	GUARDRAIL, END TREATMENT, OS	80.00 EACH
0066	601-94690	GUARDRAIL, END TREATMENT, MS	4.00 EACH
0067	601-95972	GUARDRAIL, POST (CRT), 8 IN X 6 IN TREATED LUMBER, 6 FT 0 IN. LONG	40.00 EACH
0068	601-96591	GUARDRAIL, PANEL, STEEL BEAM	10400.00 LFT

0069	601-97950	GUARDRAIL, POST BRACKET, TREATED TIMBER, 6 IN. X 6 IN.	130.00 EACH
0070	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	1580.00 LFT
0071	601-99123	GUARDRAIL, TRANSITION, GP	2.00 EACH
0072	801-06775	MAINTAINING TRAFFIC	1.00 LS
0073	801-12042	TRUCK MOUNTED ATTENUATOR	30.00 DAY
0074	801-12324	LAW ENFORCEMENT OFFICER	50.00 HRS

Call: 720

Contract: M -44355-A

Section No.: 1 GUARDRAIL, MAINTENANCE OR REPAIR

Line				
Item No	Item Code	Description	Quantity	Unit
0001	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0002	109-08360	CONTRACT LIENS	1.00	DOL
0003	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0004	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0005	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0006	601-01522	GUARDRAIL, TRANSITION, TYPE TGB	1.00	EACH
0007	601-01700	GUARDRAIL, TERMINAL SYSTEM, W-BEAM CURVED, 1	1.00	EACH
0008	601-02103	GUARDRAIL, W-BEAM, SHOP CURVED, 6 FT 3 IN. SPACING	25.00	LFT
0009	601-02212	GUARDRAIL POST, BRACKET, 8.5 LBS PER FT, GALVANIZED, 1 FT 5 IN.	75.00	EACH
0010	601-03460	GUARDRAIL, CHAN 6.7 LBS PER LFT, LABOR ONLY	1.00	LFT
0011	601-03462	GUARDRAIL, POST STEEL, 8.5 LBS PER LFT, 7 FT 0 IN.	100.00	EACH
0012	601-03492	GUARDRAIL MISCELLANEOUS MATERIAL AND LABOR FOR REPAIR	1.00	LS
0013	601-03599	GUARDRAIL, THRIE-BEAM, RAIL SECTION, 12 FT 6 IN	100.00	EACH
0014	601-03683	COMBINATION ATTENUATING TERMINAL, REPAIR, LABOR ONLY	20.00	HRS
0015	601-05856	CAT	1.00	EACH
0016	601-06233	IMPACT ATTENUATOR, ED-W1, TL-3	34.00	EACH
0017	601-06247	IMPACT ATTENUATOR, R2-W2, TL-3	4.00	EACH
0018	601-12289	GUARDRAIL, MGS, HEIGHT TRANSITION	32.00	EACH
0019	601-61340	GUARDRAIL POST, 15.5 LBS PER FT, GALVANIZED, 6 FT 3 IN. LONG	10.00	EACH
0020	601-61350	GUARDRAIL POST BRACKET, 15.5 LBS PER LFT, GALVANIZED, 1 FT 2.25 IN.	10.00	EACH
0021	601-61390	GUARDRAIL, TERMINAL END SECTION, CURVED, SINGLE FACE, GALVANIZED	7.00	EACH
0022	601-62530	GUARDRAIL, PIER CONNECTION, ES	1.00	EACH
0023	601-62540	GUARDRAIL, POST, PLUMB	435.00	EACH
0024	601-91428	GUARDRAIL, ATTENUATING TERMINAL, NOSE ASSEMBLY, MKN	5.00	EACH
0025	601-91432	GUARDRAIL, ATTENUATING TERMINAL, SIDE PLATE, MKSD	9.00	EACH
0026	601-91504	GUARDRAIL, POST, W1, 10 IN. X 10 IN.	2.00	EACH
0027	601-91505	GUARDRAIL, POST, W2, 8 IN. X 8 IN.	1.00	EACH
0028	601-91542	GUARDRAIL, BLOCKOUT, 6 IN. X 8 IN., B1	34.00	EACH
0029	601-91649	GUARDRAIL, THRIE BEAM TRANSITION SECTION, GALVANIZED	1.00	EACH
0030	601-94689	GUARDRAIL, END TREATMENT, OS	30.00	EACH
0031	601-94690	GUARDRAIL, END TREATMENT, MS	5.00	EACH

0032	601-95972	GUARDRAIL, POST (CRT), 8 IN X 6 IN TREATED LUMBER, 6 FT 0 IN. LONG	20.00 EACH
0033	601-96591	GUARDRAIL, PANEL, STEEL BEAM	7500.00 LFT
0034	601-97950	GUARDRAIL, POST BRACKET, TREATED TIMBER, 6 IN. X 6 IN.	65.00 EACH
0035	601-99105	GUARDRAIL, W-BEAM, 6 FT 3 IN. SPACING	580.00 LFT
0036	627-09331	SAFETY TERMINAL TYPE, TL-4	1.00 EACH
0037	627-09910	CABLE LINE POST LESS SOCKET, REPAIR	400.00 EACH
0038	627-09911	TERMINAL POST LESS SOCKET, REPAIR	5.00 EACH
0039	627-09912	CABLE RELEASE POST LESS SOCKET, REPAIR	1.00 EACH
0040	627-09913	CABLE SOCKET WITH CONCRETE, REPAIR	1.00 EACH
0041	627-09915	CABLE SPLICE, REPAIR	80.00 EACH
0042	627-09916	RETENTION CABLE, REPAIR	40.00 EACH
0043	628-09403	FIELD OFFICE, C	12.00 MOS
0044	628-11976	COMPUTER SYSTEM EQUIPMENT	3.00 EACH
0045	801-06775	MAINTAINING TRAFFIC	1.00 LS
0046	801-12042	TRUCK MOUNTED ATTENUATOR	100.00 DAY
0047	801-12324	LAW ENFORCEMENT OFFICER	150.00 HRS

Call: 800

Contract: T -43171-A

Section No.: 1

LIGHTING MAINTENANCE

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0009	202-85996	LIGHT STANDARD AND MAST ARM, REMOVE	11.00	EACH
	0010	202-93763	LIGHT STANDARD AND FOUNDATION, REMOVE	91.00	EACH
	0011	203-02000	EXCAVATION, COMMON	140.00	CYS
	0012	205-12108	STORMWATER MANAGEMENT BUDGET	31000.00	DOL
	0013	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0014	301-12231	COMPACTED AGGREGATE NO. 2	110.00	CYS
	0015	303-01180	COMPACTED AGGREGATE NO. 53	40.00	TON
	0016	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	3.00	EACH
	0017	621-06545	FERTILIZER	1.00	TON
	0018	621-06553	SEED MIXTURE, R	120.00	LBS
	0019	621-06565	MULCHING MATERIAL	1.20	TON
	0020	628-09403	FIELD OFFICE, C	12.00	MOS
	0021	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
	0022	628-11977	COMPUTER SYSTEM	1.00	EACH
	0023	801-06640	CONSTRUCTION SIGN, A	32.00	EACH
	0024	801-06645	CONSTRUCTION SIGN, B	8.00	EACH
	0025	801-06710	FLASHING ARROW SIGN	180.00	DAY
	0026	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0027	801-12042	TRUCK MOUNTED ATTENUATOR	360.00	DAY
	0028	801-12324	LAW ENFORCEMENT OFFICER	300.00	HRS
	0029	805-01844	CONDUIT, STEEL, GALVANIZED, 2 IN.	60.00	LFT
	0030	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	2080.00	LFT
	0031	807-02191	HANDHOLE, LIGHTING	70.00	EACH

0032	807-07580	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, IN TRENCH, 4 1/C	27200.00	LFT
0033	807-12199	LUMINAIRE, HIGH LUMEN ROADWAY	92.00	EACH
0034	807-12398	LIGHT POLE, 40 FT E.M.H., 15 FT MAST ARM, ANCHOR BASE	11.00	EACH
0035	807-12791	LIGHTING FOUNDATION, CONVENTIONAL POLE, CONCRETE WITH GROUNDING	81.00	EACH
0036	807-85762	LIGHT POLE, 40 FT E.M.H., 15 FT MAST ARM, BREAKAWAY BASE	81.00	EACH
0037	807-86889	CABLE, POLE CIRCUIT, THWN, NO. 10 COPPER, STRANDED 1/C	17390.00	LFT
0038	807-86910	CONNECTOR KIT, UNFUSED	92.00	EACH
0039	807-86915	CONNECTOR KIT, FUSED	92.00	EACH
0040	807-86920	MULTIPLE COMPRESSION FITTING, NON-WATERPROOFED	213.00	EACH
0041	807-86925	MULTIPLE COMPRESSION FITTING, WATERPROOFED	80.00	EACH
0042	807-86930	INSULATION LINK, NON-WATERPROOFED	205.00	EACH
0043	807-86935	INSULATION LINK, WATERPROOFED	332.00	EACH
0044	807-86950	SIGN, UNDERPASS, AND ROADWAY LIGHTING LOCATION IDENTIFICATION	92.00	EACH
0045	807-86955	CABLE DUCT MARKER	297.00	EACH
0046	807-97237	WIRE, NO. 4 COPPER, IN PLASTIC DUCT, 4 1/C	5130.00	LFT

Call: 810

Contract: T -43392-A

Section No.: 1 ITS TRAVELER INFORMATION SYSTEMS

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0007	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0008	203-08607	LINEAR GRADING	2169.00	LFT
	0009	601-02241	GUARDRAIL, REMOVE	12.00	LFT
	0010	601-06035	GUARDRAIL, RESET	800.00	LFT
	0011	601-12281	GUARDRAIL MGS W-BEAM, 6 FT 3 IN. SPACING	925.00	LFT
	0012	601-12292	GUARDRAIL, MGS, TRANSITION WITHOUT CURB	1.00	EACH
	0013	601-12294	GUARDRAIL, MGS, W-BEAM, CABLE TERMINAL ANCHOR	6.00	EACH
	0014	601-94689	GUARDRAIL, END TREATMENT, OS	7.00	EACH
	0015	628-09403	FIELD OFFICE, C	12.00	MOS
	0016	628-11976	COMPUTER SYSTEM EQUIPMENT	1.00	EACH
	0017	801-01093	TEMPORARY WORKSITE SPEED LIMIT SIGN ASSEMBLY	22.00	EACH
	0018	801-06640	CONSTRUCTION SIGN, A	132.00	EACH
	0019	801-06645	CONSTRUCTION SIGN, B	132.00	EACH
	0020	801-06710	FLASHING ARROW SIGN	100.00	DAY
	0021	801-06775	MAINTAINING TRAFFIC	1.00	LS
	0022	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	5808.00	LFT
	0023	802-02475	SIGN, PANEL, RELOCATE	3.00	EACH
	0024	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	254.00	LFT
	0025	802-06402	DYNAMIC MESSAGE SIGN	11.00	EACH
	0026	802-07057	SIGN, PANEL, WITH LEGEND	156.00	SFT
	0027	802-07060	SIGN, SHEET, RELOCATE	8.00	EACH
	0028	802-11818	OVERHEAD SIGN STRUCTURE, BUTTERFLY CANTILEVER	11.00	EACH
	0029	802-12222	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, A	4.00	EACH
	0030	802-12223	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, B	2.00	EACH
	0031	802-12224	WIDE FLANGE SIGN POST SUPPORT FOUNDATION, C	2.00	EACH

0032	802-12649	ITS ROADSIDE BALANCED CANTILEVER STRUCTURE FOUNDATION CONCRETE WITH GROUNDING (IN) X (DEPTH)	11.00 EACH
0033	802-74040	SIGN AND SUPPORTS, WIDE FLANGE, REMOVE	3.00 EACH
0034	802-76095	STRUCTURAL STEEL, BREAKAWAY	4352.00 LBS
0035	805-04973	CONDUIT	812.00 LFT
0036	805-04973	CONDUIT	2277.00 LFT
0037	807-02618	WIRE, NO. 2 COPPER, 3 1/C	3022.00 LFT
0038	807-11712	WIRE, NO. 6 COPPER, 1/C	3022.00 LFT
0039	807-12733	HANDHOLE, ATMS	31.00 EACH
0040	809-04652	SERVICE POINT	11.00 EACH
0041	809-04652	SERVICE POINT	5.00 EACH
0042	809-12723	SERVICE POINT, ATMS, CONNECTION ALLOWANCE	12000.00 DOL