

**Schedule of Pay Items Letting Date April 12, 2023 Letting ID 230412**

Call: 891

Contract: T -44332-A

Section No.: 1

NEW SIGNAL INSTALLATION

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0006	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0007	628-11729	CELLULAR TELEPHONE, TYPE A	1.00	EACH
0008	628-11731	CELLULAR TELEPHONE, ADDITIONAL DATA	1.00	DOL
0009	628-12923	CELLULAR TELEPHONE SERVICE, UNLIMITED MIN.	7.00	MOS
0010	801-06640	CONSTRUCTION SIGN, A	9.00	EACH
0011	801-06645	CONSTRUCTION SIGN, B	3.00	EACH
0012	801-06775	MAINTAINING TRAFFIC	1.00	LS
0013	802-04089	SIGN, SHEET, REMOVE	2.00	EACH
0014	802-05704	SIGN POST, SQUARE, TYPE 1, UNREINFORCED ANCHOR BASE	26.00	LFT
0015	802-09838	SIGN, SHEET, WITH LEGEND, 0.080 IN.	32.00	SFT
0016	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	7.00	SFT
0017	805-01815	SIGNAL POLE FOUNDATION, 36 IN. X 144 IN.	4.00	EACH
0018	805-01842	HANDHOLE, SIGNAL, TYPE 1	8.00	EACH
0019	805-02445	CONTROLLER AND CABINET, P1	1.00	EACH
0020	805-08214	CONDUIT, PVC, 2 IN. SCHEDULE 40	897.00	LFT
0021	805-08244	CELLULAR MODEM KIT	1.00	EACH
0022	805-11815	CONDUIT, HDPE, 2 IN. SCHEDULE 80	406.00	LFT
0023	805-78205	TRAFFIC SIGNAL HEAD, 3 SECTION, 12 IN.	6.00	EACH
0024	805-78225	TRAFFIC SIGNAL HEAD, 4 SECTION, 12 IN.	1.00	EACH
0025	805-78415	SPAN, CATENARY, AND TETHER	3.00	EACH
0026	805-78420	DISCONNECT HANGER	3.00	EACH
0027	805-78445	SIGNAL SERVICE	1.00	EACH
0028	805-78467	SIGNAL CABLE, SERVICE, COPPER, 3C/8 GAUGE	163.00	LFT
0029	805-78470	SIGNAL CABLE, ROADWAY LOOP, COPPER, 1C/14 GAUGE	3225.00	LFT
0030	805-78485	SIGNAL CABLE, CONTROL, COPPER, 5C/14 GAUGE	989.00	LFT
0031	805-78490	SIGNAL CABLE, CONTROL, COPPER, 7C/14 GAUGE	60.00	LFT

0032	805-78495	SIGNAL CABLE, CONTROL, COPPER, 9C/14 GAUGE	326.00	LFT
0033	805-78510	SIGNAL CABLE, DETECTOR LEAD-IN, COPPER, 2C/16 GAUGE	2920.00	LFT
0034	805-78785	SIGNAL DETECTOR HOUSING	9.00	EACH
0035	805-78795	SAW CUT FOR ROADWAY LOOP DETECTOR AND SEALANT	1137.00	LFT
0036	805-78925	CONTROLLER CABINET FOUNDATION, P1	1.00	EACH
0037	805-81060	SIGNAL POLE, STEEL STRAIN, 36 FT	4.00	EACH
0038	807-86805	SERVICE POINT, I	1.00	EACH
0039	808-06716	LINE, REMOVE	12.00	LFT
0040	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	79.00	LFT
0041	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	1.00	EACH
0042	808-75325	PAVEMENT MESSAGE MARKING, THERMOPLASTIC ONLY	1.00	EACH