

**Schedule of Pay Items Letting Date May 10, 2023 Letting ID 230510**

Call: 226

Contract: R -41619-B

Section No.: 1 SLIDE CORRECTION

Line	Item No	Item Code	Description	Quantity	Unit
	0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
	0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
	0003	109-08360	CONTRACT LIENS	1.00	DOL
	0004	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
	0005	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
	0006	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
	0007	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
	0008	201-52370	CLEARING RIGHT OF WAY	1.00	LS
	0009	203-02000	EXCAVATION, COMMON	785.00	CYS
	0010	205-11626	PUMP AROUND	1.00	EACH
	0011	205-12108	STORMWATER MANAGEMENT BUDGET	5630.00	DOL
	0012	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
	0013	205-12618	SWQCP PREPARATION	1.00	LS
	0014	206-51235	COFFERDAM	1.00	LS
	0015	615-06490	RIGHT-OF-WAY MARKER	2.00	EACH
	0016	616-05688	RIPRAP, CLASS 1	750.00	TON
	0017	616-12249	GEOTEXTILE FOR RIPRAP TYPE 2B	763.00	SYS
	0018	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
	0019	621-06567	WATER	1.00	KGAL
	0020	621-12612	SEED MIXTURE, FLOODPLAIN	3.00	LBS
	0021	622-05639	PLANT, DECIDUOUS SHRUB, 18 IN. TO 24 IN.	5.00	EACH
	0022	622-05648	PLANT, DECIDUOUS TREE, SINGLE STEM, 1.25 IN. OR UNDER	6.00	EACH
	0023	622-52436	SIGN, DO NOT MOW OR SPRAY	1.00	EACH
	0024	628-09403	FIELD OFFICE, C	12.00	MOS
	0025	731-06223	SOIL NAILED WALL	131.00	SYS
	0026	801-04746	ENERGY ABSORBING TERMINAL, CZ, TL-	2.00	EACH
	0027	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	200.00	LFT
	0028	801-06208	TEMPORARY PAVEMENT MARKING, REMOVABLE, 5 IN.	400.00	LFT
	0029	801-06577	TEMPORARY PAVEMENT MARKING, REMOVABLE, 24 IN.	20.00	LFT
	0030	801-06640	CONSTRUCTION SIGN, A	9.00	EACH
	0031	801-06645	CONSTRUCTION SIGN, B	8.00	EACH

0032	801-06775	MAINTAINING TRAFFIC	1.00	LS
0033	801-08508	TEMPORARY TRAFFIC BARRIER, ANCHORED, TYPE 2	220.00	LFT
0034	801-12081	PORTABLE SIGNAL	1.00	LS
0035	801-97643	TEMPORARY BUZZ STRIPS	720.00	LFT

Call: 624

Contract: T -42602-B

Section No.: 1           AUXILIARY LANES, ACCEL AND DECEL OR TURN LANES

Line				
Item No	Item Code	Description	Quantity	Unit
0001	105-06845	CONSTRUCTION ENGINEERING	1.00	LS
0002	109-08359	LIQUIDATED DAMAGES	1.00	DOL
0003	109-08360	CONTRACT LIENS	1.00	DOL
0004	109-08440	QUALITY ADJUSTMENTS, HMA	1.00	DOL
0005	109-08443	QUALITY ADJUSTMENTS, TEMPORARY TRAFFIC CONTROL DEVICES	1.00	DOL
0006	109-08444	QUALITY ADJUSTMENTS, FAILED MATERIALS	1.00	DOL
0007	109-09377	QUALITY ADJUSTMENTS, PAVEMENT TRAFFIC MARKINGS	1.00	DOL
0008	109-09489	PAYMENT ADJUSTMENT PG ASPHALT BINDER	1.00	DOL
0009	109-11362	QUALITY ADJUSTMENTS, FAILURE TO MAINTAIN TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES	1.00	DOL
0010	110-01001	MOBILIZATION AND DEMOBILIZATION	1.00	LS
0011	201-52370	CLEARING RIGHT OF WAY	1.00	LS
0012	202-91385	INLET, REMOVE	2.00	EACH
0013	203-02000	EXCAVATION, COMMON	1243.00	CYS
0014	203-02070	BORROW	645.00	CYS
0015	205-12108	STORMWATER MANAGEMENT BUDGET	17626.00	DOL
0016	205-12616	STORMWATER MANAGEMENT IMPLEMENTATION	1.00	LS
0017	205-12618	SWQCP PREPARATION	1.00	LS
0018	207-09935	SUBGRADE TREATMENT, TYPE IC	7780.00	SYS
0019	211-09265	STRUCTURE BACKFILL, TYPE 2	336.00	CYS
0020	301-12234	COMPACTED AGGREGATE NO. 53	857.00	CYS
0021	303-01180	COMPACTED AGGREGATE NO. 53	1646.00	TON
0022	304-12625	HMA PATCHING FULL DEPTH, TYPE C	53.00	TON
0023	306-08034	MILLING, ASPHALT, 1 1/2 IN.	4578.00	SYS
0024	401-07328	QC/QA-HMA, 3, 70, SURFACE, 9.5 mm	965.00	TON
0025	401-07398	QC/QA-HMA, 3, 70, INTERMEDIATE, 19.0 mm	1143.00	TON
0026	401-07408	QC/QA-HMA, 3, 64, BASE, 25.0 mm	3657.00	TON
0027	401-10258	JOINT ADHESIVE, SURFACE	22215.00	LFT
0028	401-10259	JOINT ADHESIVE, INTERMEDIATE	22215.00	LFT
0029	401-11785	LIQUID ASPHALT SEALANT	22215.00	LFT
0030	406-05520	ASPHALT FOR TACK COAT	9.00	TON
0031	616-06405	RIPRAP, REVETMENT	5.00	TON

0032	616-12246	GEOTEXTILE FOR RIPRAP TYPE 1A	5.00	SYS
0033	621-01004	MOBILIZATION AND DEMOBILIZATION FOR SEEDING	2.00	EACH
0034	621-06559	MULCHED SEEDING R	11278.00	SYS
0035	628-09409	MOBILE INTERNET SERVICE	18.00	MOS
0036	628-11976	COMPUTER SYSTEM EQUIPMENT	2.00	EACH
0037	628-11977	COMPUTER SYSTEM	1.00	EACH
0038	628-12683	FIELD OFFICE, D	18.00	MOS
0039	715-05149	PIPE, TYPE 2, CIRCULAR, 12 IN.	340.00	LFT
0040	715-05151	PIPE, TYPE 2, CIRCULAR, 15 IN.	163.00	LFT
0041	715-09064	VIDEO INSPECTION FOR PIPE	506.00	LFT
0042	715-46000	PIPE END SECTION, DIAMETER 12 IN.	1.00	EACH
0043	715-46005	PIPE END SECTION, DIAMETER 15 IN.	1.00	EACH
0044	720-01917	CASTING, MODIFIED	6.00	EACH
0045	720-45030	INLET, E7	3.00	EACH
0046	720-45070	INLET, P12A	12.00	EACH
0047	801-06207	TEMPORARY PAVEMENT MARKING, REMOVABLE, 4 IN.	46200.00	LFT
0048	801-06625	DETOUR ROUTE MARKER ASSEMBLY	84.00	EACH
0049	801-06640	CONSTRUCTION SIGN, A	187.00	EACH
0050	801-06645	CONSTRUCTION SIGN, B	53.00	EACH
0051	801-06710	FLASHING ARROW SIGN	390.00	DAY
0052	801-06775	MAINTAINING TRAFFIC	1.00	LS
0053	801-07118	BARRICADE, III-A	3300.00	LFT
0054	801-11642	PORTABLE CHANGEABLE MESSAGE SIGN	2.00	EACH
0055	802-05702	SIGN POST, SQUARE, TYPE 2, REINFORCED ANCHOR BASE	699.00	LFT
0056	802-07060	SIGN, SHEET, RELOCATE	10.00	EACH
0057	802-09840	SIGN, SHEET, WITH LEGEND, 0.100 IN.	364.00	SFT
0058	808-06705	LINE, THERMOPLASTIC, SOLID, WHITE, 8 IN.	7200.00	LFT
0059	808-06706	LINE, THERMOPLASTIC, SOLID, WHITE, 24 IN.	290.00	LFT
0060	808-09381	RETRO-REFLECTIVITY TESTING	1.00	LS
0061	808-12032	GROOVING FOR PAVEMENT MARKINGS	15016.00	LFT
0062	808-75245	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	7515.00	LFT
0063	808-75297	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	11.00	LFT
0064	808-75320	PAVEMENT MESSAGE MARKING, THERMOPLASTIC LANE INDICATION ARROW	26.00	EACH