

DIVISION 800 – TRAFFIC CONTROL DEVICES AND LIGHTING

SECTION 801 – TRAFFIC CONTROLS FOR CONSTRUCTION AND MAINTENANCE OPERATIONS

801.01 Description

This work shall consist of furnishing, placing, and maintaining signs, barricades, temporary pavement markings, and other traffic control devices at construction and maintenance operations in accordance with 105.03.

MATERIALS

10

801.02 Materials

Materials shall be in accordance with the following:

	Automated Flagger Assistance Devices	923.08
	Coarse Aggregate, Class D or Higher, Size No. 73	904.03
	Construction Warning Lights	923.03
	Delineator Posts.....	910.15
	Delineators.....	926.02
	Field Paint.....	909.04
20	Flashing Arrow Sign.....	923.04
	Flexible Delineator Posts.....	926.01
	Pavement Marking Materials.....	921
	Portable Changeable Message Sign.....	923.05
	Steel Posts	910.14
	Temporary Barrier Delineator	926.02(d)
	Temporary Highway Illumination Materials	807
	Temporary Panel Signs.....	919.01
	Temporary Pavement Marking Tape	923.01
	Temporary Raised Pavement Markers.....	923.02
30	Traffic Signal Materials and Equipment.....	922
	Traffic Signs	802
	Tubular Marker.....	923.07
	Wood Sign Posts	911.02(e)
	Worksite Speed Limit Sign Assembly.....	923.06

Non-ground mounted temporary traffic sign backing material and supports shall both be certified to meet NCHRP 350 crash test standards and approved for use by the FHWA. A copy of the FHWA acceptance letter shall be provided to the Engineer upon request. Roll-up materials will not be allowed except as specified in 801.16.

40

The reflective sheeting type used for construction signs, channelizing and delineation devices such as drums, tubular markers, vertical panels, and 42 in. cones, shall be the same for the entire project and shall be in accordance with 919.01(b)1.

The background for all construction signs shall be fluorescent orange reflective sheeting.

Steel sign posts need not be galvanized.

50 Wood posts for temporary panel signs shall be dense southern yellow pine or design calculations shall be provided to the Engineer identifying the type of wood and verifying the location and size of the holes to be drilled through the posts to provide break-away capability.

All temporary traffic control devices which will become the property of the Department shall be a new product at the time of final acceptance.

60 The basis for use for traffic paint; durable pavement marking materials; temporary marking tape Type II; glass beads; barrels; barricades; construction warning lights; steel posts; temporary panel signs; traffic signs, except non-ground mounted signs; tubular markers; and wood sign post used for temporary traffic control will be visual inspection.

The connecting bolt or threaded rod used to connect adjoining sections of temporary barrier wall shall have a tensile strength of 120,000 psi. The spacers used between adjoining sections of temporary barrier wall shall be in accordance with ASTM A36 with a tensile strength of 58,000 psi.

CONSTRUCTION REQUIREMENTS

70 **801.03 General Requirements**

The applicable requirements of the MUTCD shall apply to the installation and materials for traffic control devices subject to the requirements of 107.08 and 107.12. When the plans do not include a maintenance of traffic plan, the Engineer will provide such a plan to the Contractor. The Contractor shall be responsible for the field layout, placement, operation, maintenance, and removal of temporary traffic control devices.

80 A worksite traffic supervisor certified by the American Traffic Safety Service Association, ATSSA, or approved equal certifying organization, shall direct all field layout, placement, operation, inspection, maintenance, and removal of temporary traffic control devices. The certified worksite traffic supervisor, CWTS, shall ensure that all traffic control devices, except temporary concrete barrier, meet acceptable standards as outlined in the plans, specifications, and ATSSA's "Quality Standards for Temporary Traffic Control Devices" prior to installation. The CWTS shall also, prior to installation, ensure that all traffic control devices can be installed in accordance with the plans, specifications, and the MUTCD. All problems shall be reported to the Engineer so a resolution can be worked out prior to installation. The field layout will be reviewed and is subject to approval by the Engineer prior to placement of any temporary traffic control devices. The CWTS shall be present for the initial setup and all phase changes during the life of the project. The CWTS may designate responsible

90 Contractor personnel to perform day to day operation, inspection, and maintenance of the temporary traffic control devices. These responsible personnel shall work under the direction of the CWTS and their names shall be given to the Engineer on the project. A copy of the CWTS's certification shall be provided to the Engineer prior to the start of construction or placement of temporary traffic control devices or if the worksite traffic supervisor changes.

Regulatory control devices shall be erected only as directed.

100 Advisory speeds to be posted will be determined by the Department.

The names and telephone numbers of the superintendent and one other responsible employee shall be furnished. Such employees shall be on call or available at night, on weekends, or during other non-working periods to repair or replace all traffic control devices which may become damaged or inoperative.

110 When traffic lanes are restricted and when specified as a pay item, a patroller shall inspect and maintain traffic control devices. The patroller shall patrol the construction zone and shall immediately correct, maintain, and repair traffic control devices or notify the Contractor designated persons for immediate repair to such traffic control devices. A full time patroller shall be on duty during periods when work is not in progress.

120 Temporary traffic control devices shall be maintained to ensure visibility and to protect the public. All reflective sheeting backgrounds and lights shall be kept clean of foreign matter. The Contractor shall complete and submit a "Traffic Control Device Report" when a temporary traffic control device has been installed, removed, relocated, repaired, or at a minimum of once per week based on field observations. This report is provided in the Proposal for the contract and shall be used to ensure that the traffic control devices are inspected daily. The report shall be completed or reviewed by the CWTS. Each report shall be signed by the person who performed the inspection and shall be initialed by the CWTS that it was reviewed. The Engineer will sign and date the report when received. The Engineer will not be responsible for the report's completeness and accuracy.

130 The location by reference post and the date and time of operation of Temporary Worksite Speed Limit sign assemblies shall be recorded daily on a form provided by the Department. The completed report shall be submitted weekly to the Engineer. The report shall be completed and signed by the CWTS or their designee and shall be reviewed by the CWTS for completeness and accuracy.

Except for construction warning lights and temporary signals, the ATSSA brochure titled "Quality Guidelines for Temporary Traffic Control Devices and Features" will be used as a guide to determine if temporary traffic control devices and markings are Acceptable, Marginal, or Unacceptable. Upon initial setup and phase changes of temporary traffic control devices, all individual devices shall be of the

Acceptable classification. A device not completely covered or removed when the message does not apply or when directed, will be considered unacceptable.

140 A temporary traffic control device will be deemed to be in non-compliance when considered Unacceptable. A type of temporary traffic control device will be deemed to be in non-compliance when 25% or more of the individual devices are considered Marginal. Damages may be assessed in accordance with 105.14 for non-compliance.

Within 10 work days on HMA open to traffic, the edge lines shall be placed and shall be maintained until the next lift of HMA is placed or the permanent lines are placed, as appropriate. On PCCP open to traffic, the edge lines shall be placed, within 10 work days, and shall be maintained until the permanent lines are placed, as appropriate.

150 A quality assurance unit for placed longitudinal temporary pavement markings shall be 500 lft on marked pavement in any combination or pattern, or portion thereof. A quality assurance unit for transverse marking, message, or symbol shall be each.

When longitudinal durable markings are specified, a quality assurance unit for longitudinal temporary markings shall be 5,000 lft for markings that have not been placed.

160 Damages may be assessed in accordance with 105.14 for non-compliance. Damages for temporary pavement markings will not be assessed for patches less than 200 ft in length.

Non-compliance of construction warning lights will be in accordance with 801.14.

All barricades, signs, or flashing arrow signs shall be moved from one location and re-erected at another location as shown on the plans or as directed.

170 Traffic shall be maintained for maintenance activities or for HMA resurface work. The Contractor shall have an extra set of construction signs and an extra flashing arrow sign on the project site so that the taper may be moved forward without suspending the operations and clearing the work area. Additional traffic control devices shall be furnished for situations determined to be more complex, for protection in hazardous areas, and when traffic conditions warrant.

All non-fixed signs shall be removed at the completion of each day's operations. All fixed signs shall remain in place until all temporary pavement markings have been removed. All lanes shall be open to normal traffic during non-daylight hours. If a traffic lane is directed to remain closed during non-daylight hours, traffic shall be maintained on the remaining lanes as shown on the plans.

180 Where two-way traffic is to be maintained on a one-way pavement, and where the existing shoulders on such roadway are earth, aggregate No. 73 shoulders shall be

compacted in accordance with 303.06 as shown on the plans. Compacted aggregate shoulders shall remain in place unless subsequent construction activities on the contract require its removal.

Temporary drainage structures, temporary concrete median barrier units, and other temporary devices required and used for traffic maintenance shall remain the property of the Contractor.

190 **801.04 Construction Signs**

Construction signs shall include the typical sign standards or posts which support the sign, all necessary hardware, and specified construction warning lights.

A route or lane closure notice sign shall consist of a construction sign Type A, in accordance with 801.04(a), which indicates route or lane closure. The sign shall be mounted for a maximum of 14 calendar days and a minimum of seven calendar days before the closure date shown on the sign. The sign shall be removed when the route or lane is closed.

200 Trailers in accordance with 910.14(f) may be used as supports for portable construction signs. The trailer shall be located to hold the sign in a proper position. The position of the tongue shall be so as to cause no hazard to traffic. Wheel chocks other than sandbags shall not be used. The tongue may be pinned to reduce wind-induced rolling if designed to pull up or break from vehicle impact. During non-working hours, trailers with signs that do not apply to existing conditions shall be stored in accordance with 107.08(c).

210 Sign posts and their foundations shall be located and constructed to hold signs in a proper position; to resist swaying, turning, or displacement; and minimize the hazard to motorists. No rigidly fixed sign supports will be allowed in exposed areas where it would be practicable to utilize a breakaway or yielding type design. Signs shall be completely covered or removed when the message does not apply.

If the work on a project, or a portion thereof, is not active, and the roadway is open to unrestricted traffic, construction signs may be removed until work resumes. Removal of such signs shall not relieve the Contractor of responsibilities or liabilities described elsewhere herein.

(a) Type A

220 A Type A sign shall consist of a construction sign as detailed in the MUTCD or on the standard drawings which is 9 sq ft or more in area.

(b) Type B

A Type B sign shall consist of a construction sign as detailed in the MUTCD or on the standard drawings which is less than 9 sq ft in area.

(c) Type C

A Type C sign shall consist of a construction sign which is not detailed in the MUTCD or on the standard drawings and which is 9 sq ft or more but less than 33 sq ft in area.

230

(d) Type D

A Type D sign shall consist of a construction sign which is not detailed in the MUTCD or on the standard drawings and which is less than 9 sq ft.

(e) Temporary Panel Sign

A temporary panel sign shall consist of a sign fabricated and constructed in accordance with 919.01 and which is greater than 33 sq ft. Temporary panel signs shall be mounted on wood posts as shown on the plans or as approved by the Department.

240 External bracing shall not be used.

801.05 Detour Route Marker Assembly

Detour route marker assemblies shall be on a single post for a single route or may be on multiple posts for multiple routes. When two routes are being detoured across a common roadway, each route shall be shown by a separate detour route marker assembly. A detour route marker assembly-multiple route shall be used for three or more routes across a common roadway.

801.06 Road Closure Sign Assembly

250 Road closure sign assemblies shall be used at each road closure location where Type III-A barricades or Type III-B barricades are used. Road closure sign assemblies shall not be used within lane closures where adjacent lanes remain open to traffic, unless otherwise directed. Road closure sign assemblies may be required at other locations as directed.

Permanent road closure sign assemblies shall be left in place after the contract is completed and shall become the property of the Department. They shall be installed just prior to final acceptance of the contract. Supports shall be painted with white field paint for wood.

260

801.07 Barricades

Barricades shall include rails, posts, and all incidentals necessary to complete this part of the work.

High intensity reflective sheeting shall be placed on specified rails of all barricades. The colors for temporary barricades shall be orange and white, and for permanent barricades red and white.

270 All Type III barricades shall be skid mounted within pavement, shoulder, or sidewalk areas, and on ground mounted posts in all other areas. Type III barricades shall be used on all slopes which are 3:1 or flatter for roadway closures.

(a) Type III-A Barricade

Type III-A barricade shall have rails which are reflectorized on one side and shall be used for roadway closures and lane closures where traffic can approach from only one side.

(b) Type III-B Barricade

280 Type III-B barricades shall have rails which are reflectorized on both sides and shall be used for roadway closures and lane closures where traffic can approach the barricade from both sides.

(c) Permanent Type III Barricade

Permanent Type III barricades shall be 10 ft sections and shall be left in place after the contract is completed, and shall become the property of the Department. Permanent Type III barricades shall be installed just prior to final acceptance of the contract. All non-reflectorized wood and non-galvanized steel shall be painted with white field paint. Such barricades shall otherwise be in accordance with 801.07(a).

290 **801.08 Cones and Tubular Markers**

Cones shall be made of a material to withstand impact without damage to striking vehicles. They shall have a substantial base to restrict overturning. Cones and tubular markers shall be as shown on the plans.

Cones shall be used only during temporary activities where portability is advantageous and they remain in place and do not create a hazard to traffic. The use of cones in lieu of drums will be allowed as shown on the plans except cones shall not be used for shift or merge tapers on freeways and 42 in. cones may be used in tangent sections on interstates and freeways only when the use of drums would result in an effective lane width of less than 10 ft.

300

Tubular markers shall be used for separating two-lane two-way traffic on non-freeways as shown on the plans or as directed. Tubular markers may be used to delineate a pavement drop-off on non-freeways when the use of drums would result in an effective lane width of less than 10 ft.

Cones and tubular markers shall be secured in place either by weighting or adhesives. The use of metal bases will not be allowed.

310 **801.09 Drums**

Drums shall be molded orange polyethylene.

The shape of the drum shall appear basically cylindrical to the motorist from any direction in any given application. The top outside diameter shall not exceed the bottom outside diameter. Drums shall be multisided, elliptical or have a flattened side to inhibit rolling.

The top section of the drum shall have at least one construction warning light mounting bracket. The minimum drum height is exclusive of lifting handles or construction warning light mounting brackets.

The drums shall stand on end, be stable against overturning, and shall be internally or externally ballasted to resist wind speeds of up to 50 mph and gusts created by traffic. The weight of the ballast shall be 45 to 55 lb. The top of the drum shall be free from openings. Internally ballasted and externally collar ballasted drums shall not be mixed in each continuous set-up.

Internal ballast shall be sandbags, a molded plastic base filled with sand and closed with a locking cover, or a solid rubber base. The internal ballast shall be placed in the lower 1/4 of the drum. The ballast device shall be self-draining.

The external ballast shall be two rubber tire base collars. The tire base collars shall have a circumferential contact with the road surface. The maximum diameter of the tire base collar shall not exceed 36 in. The height of two tire base collars at the outside edge shall not exceed 5 in. The rubber ballasting collars shall be clean cut, proper in size, black in color, and not curved up at the edges. The interior and exterior circumference of the collar shall not be slit or cut. Drums which are external collar ballasted shall not be used in situations where the width of the collar interferes with proper placement of the drum. The Department's Guidelines for External Ballast will be used for determining acceptability of rubber tire base collars.

Upon impact by a vehicle traveling at a speed of 55 mph, the drum and ballast device shall be of a type that enables the body of the drum to separate from the base, thus allowing vehicles to easily pass over the base.

Construction warning lights shall be used in accordance with 801.14 and as shown on the plans and shall be securely fastened to the mounting brackets. Signs shall not be mounted on drums.

Permanent drums shall be left in place after the contract is complete, and shall become the property of the Department. They shall be installed just prior to final acceptance of the contract.

801.10 Temporary Traffic Barriers

Temporary traffic barrier shall be one of the following four types as shown on the plans.

Type 1

Type 1 temporary traffic barriers shall be used to separate two-way traffic and shall be precast concrete in accordance with applicable requirements of 707 and 602 and as shown on the plans. Type 1 barriers may also be used to separate traffic from the work area. The surfaces of individual precast units shall vary no more than 1/4 in. in 10 ft from the specified cross-section, as measured from a longitudinal straightedge.

The maximum variation in the vertical and horizontal alignment of adjacent units shall be 1/4 in. across the joint, as measured from a 10 ft longitudinal straightedge. Sections that have obvious defects or visual cracks shall not be used. Sections that develop any of these conditions during the contract shall be repaired with concrete or replaced within a reasonable amount of time.

370 Type 1 barrier units precast prior to 2003 shall not be used after January 1, 2012. Units precast after March 1, 2003 shall be clearly marked with the name or trademark of the manufacturer, the year of manufacture, and “INDOT”. The markings shall be indented on an end or on the top of each barrier section. Units precast after January 1, 2007 shall be from the QPL of Certified Precast Concrete Producers.

Type 2

Type 2 barriers may be used to separate traffic from the work **area**. Type 2 temporary traffic barriers shall meet the appropriate test level 2 or 3 MASH or NCHRP 350 crash test standards and shall be approved for use by the FHWA. A copy of the
380 MASH or NCHRP 350 crash test FHWA eligibility letter shall be provided to the Engineer prior to placing the unit. The unit selected shall be appropriate for the location considering the maximum posted speed limit on the project and the allowable area for deflection. The unit shall be installed according to the manufacturer’s recommendations.

If concrete barriers are used as Type 2 barriers, they shall be in accordance with the requirements for Type 1 barriers.

Type 3

390 Type 3 temporary traffic barriers shall be those Type 1 temporary traffic barriers that are to be left in place at the completion of the contract and shall become the property of the Department. They shall be in like-new condition at the completion of the contract. All necessary delineation and required anchor systems shall be left in place.

Type 4

Type 4 temporary traffic barriers shall be those types that are intended to be readily moveable to accommodate the shifting of traffic lanes on a daily basis to better facilitate the changing volumes of traffic during the peak hours of a day. Type 4
400 temporary traffic barriers shall meet the appropriate test level 3 MASH or NCHRP 350 crash test standards and shall be approved for use by the FHWA. A copy of the MASH or NCHRP 350 crash test FHWA eligibility letter shall be provided to the Engineer prior to placing the unit.

(a) Placement

Temporary traffic barriers shall be located as shown on the plans or as directed. Temporary traffic barriers used to close a lane of traffic shall be flared at the rates as shown on the plans for the applicable regulatory speed within the construction zone. If field conditions are such that the required flare rate cannot be utilized, the tapered

410 alignment may be altered, with approval, to a 10:1 flare rate with a 20 ft minimum offset from the edge of the through traffic lane to the approaching end of the flared temporary traffic barrier. If field conditions are such that that the 10:1 flare rate cannot be utilized, the tapered alignment may be further altered, with approval, to a 6:1 flare rate with the 20 ft minimum offset. Flare rates for ends of temporary traffic barriers at locations where a lane of traffic is not being closed to traffic or where the lane has already been closed shall be the same as above, however the minimum offset from the edge of the through traffic lane may be 10 ft. The use of flare rates sharper than those shown on the plans may require additional traffic control devices as directed.

420 Type 2 barriers shall not be intermixed with Type 1 or Type 3 barriers in any run. Type 2 barriers from different manufacturers shall not be intermixed in any run.

(b) Connection

Type 1 and Type 3 barrier sections shall be connected as follows:

1. The adjacent barrier sections shall be placed end to end, with sufficient overlapping of the smooth bar hooks to allow placement of the connecting bolt or threaded rod and the top spacer.
- 430 2. The adjacent barrier sections shall then be moved in opposite directions for a sufficient distance to develop the maximum contact between the smooth bar hooks and the connecting bolt or threaded rod.
3. The bottom spacer and nut shall then be placed as shown on the plans. The nut shall be sufficiently tightened to eliminate all gaps between the adjacent bolt heads, spacers, nuts, and washers which form the connection.

440 Type 1 and Type 3 precast units which have previously been cast meeting earlier Department standards may be used. The Contractor will be allowed to mix Type 1 and Type 3 units in a run as long as the units are in good condition and the connecting devices are compatible. If units meeting earlier Department standards are used, a 1 in. bolt will be allowed to link the units together. The spacer detail shall, however, be in accordance with the current standard. Units cast after March 1, 2003 shall be linked with the 1 1/4 in. bolt.

450 Type 2 temporary traffic barriers shall be connected as recommended by the barrier manufacturer.

(c) Anchorage

Type 1 and Type 3 temporary traffic barriers shall be anchored in accordance with the methods shown on the plans, at the locations described herein. Type 2 barriers shall be anchored as recommended by the barrier manufacturer and at locations described

herein. Temporary concrete traffic barriers shall be anchored when located on or within 60 ft of a bridge, and along tapered alignments. Anchoring at locations in addition to those described herein will be required when directed.

460 Chemical anchor systems with removable bolts, or mechanical anchors may be used to anchor Type 1 barriers to bridge decks, concrete pavement, and concrete shoulders. Mechanical anchors may be ferrous or non-ferrous material. All anchors shall have a shear strength of 10,000 lb and an ultimate pullout strength of 6,500 lb.

Non-ferrous mechanical anchors shall be installed such that the top end of the sleeve is a minimum of 2 1/2 in. below the final finished concrete surface.

Ferrous mechanical anchors shall be completely removed when no longer required. All damage to the pavement shall be repaired as directed.

470

Non-ferrous anchor sleeves and the chemical adhesive component of chemical anchor systems may remain in place when no longer required. The holes remaining in the pavement shall be filled with appropriate material as directed.

(d) Delineation

Type 1 barriers used to separate two-way traffic shall be delineated with top mounted temporary barrier delineators and with side mounted delineators. The top mounted delineators shall be two-sided, shall be yellow, and shall be placed on every other section of barrier wall. The top mounted delineators shall be mounted perpendicular to the direction of traffic flow. The side mounted delineators shall be yellow and shall be mounted in accordance with 602.03(f).

480

Temporary traffic barriers in locations other than separating two-way traffic shall be delineated with either Type C construction warning lights or top mounted temporary barrier delineators and with side mounted barrier delineators. The Type C lights or the top mounted barrier delineators shall be spaced at the number of feet equal to the number of miles per hour in the posted speed limit with a minimum spacing of 20 ft. Bi-directional lenses will be required on the warning lights when the barrier is adjacent to a lane that is carrying alternating one-way traffic. The color of the barrier delineators shall be white when located on the right side of the traffic lane, and yellow when located on the left side of the traffic lane. The color of the barrier delineators shall be white when located adjacent to a lane that is carrying alternating one-way traffic.

490

Where the temporary traffic barrier is located along a tapered alignment and is located behind drums or other reflective delineation devices, the Type C construction warning lights and barrier delineators shall not be used.

(e) End Treatment

500 Where possible, the ends of temporary traffic barriers shall be flared in accordance with 801.10(a). Where conditions do not allow the temporary traffic barrier to be flared

in accordance with 801.10(a), appropriate end treatments shall be incorporated to protect vehicles from the ends of the barriers. The end treatments shall have re-direct capability and shall meet the appropriate test level 2 or 3 NCHRP 350 crash test standards and be approved for use by the FHWA.

(f) Storage

510 No barrier segments shall be stored on the right-of-way unless written permission is given by the Department. Requests for permission to store traffic barrier segments on the right-of-way will not be accepted until after the contract has been awarded.

801.10.1 Construction Zone Energy Absorbing Terminal, CZ

The construction zone energy absorbing terminal, CZ, shall have passed NCHRP 350 level 3 crash test for all Interstate and other construction sites having a construction zone speed limit in excess of 45 mph and level 2 for non-Interstate construction sites having a construction zone speed limit of 45 mph or less. All energy absorbing terminal, CZ, shall have redirect capabilities and shall be approved by the FHWA.

520 A copy of the crash test report confirming the product is NCHRP 350 or MASH compliant for the test level specified, or a copy of the FHWA eligibility letter, shall be furnished to the Engineer prior to the installation of the unit.

The unit's nose cover shall be reflectorized to provide improved visibility.

530 Assembly and installation of the unit shall be supervised or performed at all times by an installer trained and certified by the unit's manufacturer. The size, assembly, and installation shall be in accordance with the manufacturer's recommendations at the locations shown on the plans. When required for bi-directional traffic protection, transition panels and all other necessary hardware shall be included in the installation. A copy of the installer's certificate shall be provided to the Engineer prior to the start of work.

The Contractor shall provide the Department with all necessary manufacturer's installation manuals and working drawings in accordance with 105.02.

540 Sufficient spare parts or complete units shall be stored in a safe, convenient, nearby location. Such standby materials are not shown in the Schedule of Pay Items. The standby materials shall be utilized to repair or replace damaged units in the shortest time possible. Standby materials used in the repair of damaged units shall be replaced within 24 h of their use.

801.11 Temporary Crossovers

Temporary crossovers shall be either Type A or Type B as shown on the plans and shall be constructed in accordance with the applicable sections of 207, 402 or 502. If applicable, a CMDS shall be submitted to the Engineer for approval. Utilization of the Department provided spreadsheet is not required. When required to maintain

median drainage, a 15 in. diameter pipe shall be placed at the centerline of the median under the crossover. If the crossover is to remain in place for future construction, the
550 pipe shall have appropriate grated box ends in accordance with 715.

The pavement structure for the temporary crossover shall be as shown on the plans.

Traffic control devices, including temporary pavement markings, shall be as shown on the plans. Separation of opposing vehicular traffic between two crossovers shall be as shown on the plans.

Refurbishing of a temporary crossover shall consist of the removal of drums or
560 earth cover from an existing temporary crossover. The temporary crossover shall be patched and resurfaced as directed. Excavated soil resulting from the refurbishing operation, if not used as a part of the contract work, shall become the property of the Contractor. Removed drums will remain the property of the Department.

After construction is complete, and prior to the opening of all lanes to traffic, the temporary crossover shall be removed or closed.

Where guardrail is required to be removed for construction or refurbishing of
570 crossovers, such removal and subsequent re-erection shall be done as shown on the plans or as directed.

Acceptance of HMA for temporary crossovers will be in accordance with 402.09.

801.12 Temporary Pavement Marking

Temporary pavement markings shall be new materials placed in accordance with 808.04 and 808.05. However, when temporary markings are to be in place for 10 work days or less the dashed line pattern used on center line and lane lines may be 4 ft line segments on 40 ft centers and gore areas shall be marked by outline only and may be
580 5 in. wide lines. No-passing zones on all undivided two-way roadways shall be identified with signs and centerline markings. Markings shall remain clearly visible during the day and night for a minimum of 200 ft ahead of a vehicle. All temporary markings shall be maintained and replaced until they are no longer applicable.

Where possible, when non-removable temporary markings are used on a final surface, such markings shall be placed at the same location where permanent markings will later be affixed or parallel to and within 12 in. of the permanent marking pattern.

Where temporary pavement markings are to be placed on a pavement which has existing markings, the existing markings which conflict with the temporary markings
590 shall be removed in accordance with 808.10. On asphalt pavement, black temporary tape Type I, may be used to cover conflicting markings. The black temporary tape shall extend at least 1/2 in. beyond the edges of the marking to be covered. Overlapping of temporary tape will not be allowed.

When working under traffic, the temporary pavement markings shall be placed before opening the lane to traffic. This shall include, but not be limited to, the marking patterns of gore areas, outside edge line of deceleration and acceleration lanes, narrow bridge markings, lane reduction transitions, lane lines, centerlines, and transverse markings as appropriate.

600

Temporary pavement markings which are to be in service from December 1 through the following March 31 shall be painted markings. Such markings shall be placed in the standard pavement marking pattern and applied prior to the suspension of the work, or within seven work days after the Contractor is directed to place the markings. Adjustments to these dates to accommodate actual seasonal suspension and continuance of work are subject to approval by the Engineer upon written request.

The prismatic reflectors shall be removed from snowplowable raised pavement markers which conflict with the temporary traffic marking pattern. Snowplowable raised pavement marker castings damaged by the removal of the reflector shall be replaced in accordance with 808.11. New prismatic reflectors shall be mounted on existing castings in accordance with 808.11 when the final traffic pattern is established.

610

Removal of temporary pavement markings shall be in accordance with 808.10.

(a) Temporary Pavement Marking Methods

Pavement markings shall be installed in accordance with 808.07 except that measurement of retro-reflectivity is not required by the Contractor and quality adjustments in accordance with 808.07 will not apply. All other performance measures shall apply.

620

1. Paint

Temporary edge lines shall be painted markings. When traffic is in the final pattern, the temporary edge lines shall be placed at the same location as the permanent markings.

2. Temporary Pavement Marking Tape

Temporary pavement marking tape shall be applied in accordance with the manufacturer's recommendations. Temporary marking tape shall be new Type I or Type II material.

630

All temporary pavement marking tape shall be removed prior to placing the next pavement course, prior to placing an overlay, prior to recycling the pavement, or prior to placing the final pavement markings, except as otherwise described herein.

a. Type I

Type I tape is a removable material. It may be used for longitudinal and transverse markings.

640

Type I tape shall be removed without the use of solvents, grinding, abrasive blasting, or other methods which may damage the pavement. All visible adhesive residue shall be removed without use of solvents or grinding.

b. Type II

Type II tape is a non-removable material. It may be used on PCCP to be removed or on PCCP to be overlaid with an HMA course greater than 165 lb/sq yd. Type II tape placed on HMA pavement shall be removed prior to placing the next pavement course.

650

If it is necessary to remove Type II tape, it shall be removed without the use of solvents. All damage to the pavement shall be repaired.

3. Temporary Raised Pavement Marker

The temporary raised pavement marker shall be grade 1 or grade 2. When used, it shall be a supplement to other temporary pavement markings. The color of the reflector shall be in accordance with the other temporary pavement marking. The color of the shell of the grade 1 marker shall be in accordance with the color of the other temporary pavement marking.

660

Temporary raised pavement markers shall be removed before the next layer of pavement is placed and before the final pavement markings are applied. All damage to the pavement shall be repaired.

4. Temporary Buzz Strips

Temporary buzz strips shall be a set of transverse markings constructed of removable or durable marking material. Durable marking material shall be used in accordance with 808.07(b).

(b) Blank

670

801.13 Temporary Illumination

The temporary highway illumination shall be in accordance with applicable requirements of 807 except as modified herein.

The electric energy necessary to power the luminaires on a continuous basis is the responsibility of the Contractor.

At completion of the contract work, the temporary illumination shall be removed and shall remain the property of the Contractor. After removal of the temporary illumination equipment, all holes and trenches shall be backfilled with B borrow.

680

801.14 Construction Warning Lights

Construction warning lights shall be portable, lens directed, enclosed lights that emit an amber color. All warning lights shall be mounted a minimum of 36 in. above the traveled way to the bottom of the lens, unless otherwise directed. Lights not

working shall be repaired or replaced immediately. For each day that more than 5% of the required warning lights are not operating, a sum equal to \$4.00 per non-working light will be deducted from the monies due the Contractor.

690 **(a) Type A**

Type A lights shall be low intensity flashing warning lights. These lights shall be visible on a clear night from a minimum distance of 3,000 ft when there is no external illumination directly on or in the immediate vicinity of the light. They shall operate from dusk to dawn or when conditions exist which tend to obscure vision. Traffic control devices used for maintaining traffic will not require Type A warning lights during unobscured daylight hours.

(b) Type B

700 Type B lights shall be high intensity, flashing, warning lights. These lights shall be visible on a sunny day from a minimum distance of 1,000 ft when viewed without the sun directly on or behind the light.

(c) Type C

Type C lights shall be steady burning warning lights. These lights shall be visible on a clear night from a minimum distance of 3,000 ft when there is no external illumination directly on or in the immediate vicinity of the light. They shall operate from dusk to dawn or when conditions exist which tend to obscure vision.

(d) Vehicle Warning Lights

710 Vehicle warning lights shall be amber and shall be a strobe light or a flashing, oscillating, or rotating directed beam light. They shall be visible to all approaching traffic for a distance of 1,000 ft.

801.15 Electronic Devices

(a) Flashing Arrow Sign

Where specified, a flashing arrow sign shall be furnished, installed, and maintained. It shall be operated continuously, when necessary, to divert traffic.

720 The flashing arrow sign may be of the solar power assisted type only in stationary operations when the horizontal or vertical curvature in the road is such that motorists do not drive into and out of the beam width of the lighted arrow while within sight of the sign.

(b) Portable Changeable Message Signs, PCMS

This shall consist of furnishing, installing, and maintaining a trailer-mounted, portable sign upon which varying electronically generated messages will be displayed to traffic. The message being relayed to traffic shall be legible and easily understood for a minimum distance of 650 ft.

730

The messages shall be as shown on the plans or as approved or directed by the Engineer. Messages shall be formatted in accordance with the Department's Guidelines for Portable Changeable Message Signs. Only upper case letters shall be used. Each message phase shall be displayed for at least 2 s. Display time for an entire message shall not exceed 8 s.

740 Placement of PCMSs shall be as shown on the plans or as directed by the Engineer. A minimum clearance of 7 ft from pavement to the bottom of the PCMS shall be provided. Units shall be level and PCMSs shall be turned away from traffic, placed in stand-by mode, or left blank until there is a valid message to be displayed. When in use PCMSs shall be turned approximately 3° from perpendicular towards oncoming traffic to minimize glare. A drum shall be placed immediately in front of the PCMS trailer at both corners for delineation.

(c) Temporary Worksite Speed Limit Sign Assembly

750 This shall consist of furnishing and placing portable speed limit signs as shown on the plans or as directed in areas of work activity. When used, the worksite speed limit flashing strobe lights shall be activated when the worksite speed limit is in effect. This shall be only where and while work is actually in progress and workers are present. Each strobe light shall be visible through a range of 120° when viewed facing the sign and shall be visible from a distance of 750 ft.

Wherever a permanent speed limit sign exists within the limits controlled by the worksite speed limit sign assemblies, additional worksite speed limit sign assemblies shall be placed at the permanent signs. The permanent signs shall be covered or removed during continuous worksite speed limit use.

760 A worksite speed limit authorized for intermittent use shall only be activated when workers are present at the site. The intermittent worksite speed limit shall only be used in the area of work. A worksite speed limit authorized for continuous use shall not include the flashing strobe lights or the S4-4 "WHEN FLASHING" plaque.

The worksite speed zone signage shall be placed and maintained by the Contractor. The worksite speed limit will be as shown on the plans or as directed by the Engineer and at least 10 mph below the posted speed limit for the roadway under construction.

770 A worksite reduced speed advance warning sign assembly shall be placed in advance of the first worksite speed limit sign assembly when the reduction in speed limit is greater than 10 mph.

(d) Temporary Traffic Signals

This work shall consist of furnishing, installing, and maintaining temporary traffic signals in accordance with 805 except as modified herein.

Except as shown on the plans, all materials not furnished by the Department shall remain the property of the Contractor after work is completed and the equipment is removed.

780 The traffic signal equipment shall be as specified, but may be either new or used. Used equipment shall be in satisfactory working condition and **will be subject to approval** prior to use.

Two signal heads shall be displayed for each approach. Signal cable may be extended across bridges through conduit which shall be attached to the underside of the coping. Type and spacing of clamps **will be subject to approval** prior to installation.

Conduit shall be steel or plastic. Flexible conduit will be an acceptable alternate for use as ground rod entry, magnetometer, or microloop installations.

790

1. Fixed Temporary Signals

Fixed temporary signals shall be displayed overhead on a span, catenary, and tether utilizing an aircraft cable, unless otherwise directed.

Electric energy necessary to power the fixed temporary signal is the responsibility of the Contractor. Prior to the start of construction, the schedule of activities shall be coordinated with the power company.

800 The Contractor shall obtain permits from local officials, companies, or individuals for the use of poles, right-of-way, or other property incidental to the installation of fixed temporary signals. Although entering into the contract implies permission and authority to install conduit under pavement, sidewalks, and alleys, all damage to underground utilities or interruption of such service shall be the responsibility of the Contractor.

The location, spacing, and timing of fixed temporary signals will be determined by the Engineer.

810 An IMSA certified level II Traffic Signal Construction Technician or a level II Traffic Signal Field Technician shall be available 24 h a day to respond within 2 h for the maintenance of the traffic signal equipment.

The controller shall be traffic actuated solid state digital. For used controllers, the model selected shall be from a manufacturer with a controller on the QPL of Traffic Signal and ITS Devices.

Vehicle detection shall be provided and shall be either inductive loop or wireless unless otherwise noted on the plans.

820

2. Portable Signals

Portable signals shall be selected from the QPL of Portable Traffic Signals. Prior

to the activation, the Contractor shall provide a completed inspection checklist to the Engineer certifying that the portable signal is functioning properly.

The portable signal shall be equipped with remote monitoring. Unless otherwise shown on the plans, Microwave or Doppler vehicle detection as shown on the QPL of Portable Traffic Signals shall be provided. A minimum of three drums shall be placed immediately in front of the portable signal trailer for delineation.

830 A technician certified by the manufacturer shall be available 24 h a day to respond within 2 h for the maintenance of the traffic signal equipment. Copy of the certification shall be provided to the Engineer prior to the placement of the portable signals. Maintenance of the portable signal includes adjustments to the phasing or timing as indicated on the plans or directed by the Engineer. The Contractor shall replace portable signals that cannot be returned to normal operation or that fail two times during the contract.

840 The Contractor shall provide a record of any modifications to the signal timing plan, failures, and all maintenance issues, to the Engineer prior to final acceptance and when otherwise requested. The report shall indicate the date, time, and nature of each event.

(e) Automated Flagger Assistance Devices

An Automated Flagger Assistance Device, AFAD, may be used to control a single lane of approaching traffic on a two-lane highway for flagging operations.

850 Only qualified flaggers who have been trained on the operation of the AFAD shall operate the AFAD. AFAD operators shall provide written proof that they have been trained by the AFAD manufacturer. Two trained flaggers shall be available on-site to provide flagging in case of an AFAD malfunction. The flagger operating the AFAD shall be positioned to have an unobstructed line of sight to approaching traffic and the AFAD. A single flagger may be used to control both approaches to the work site if adequate unobstructed sight distance exists between the AFAD operator and both approaching directions of traffic and both AFADs.

860 The flagger operating the AFAD shall not leave the device unattended at any time while the AFAD is in use. The operating flagger shall be positioned at such point to be in full view of oncoming traffic and the AFAD at all times the AFAD is in use. The flagger operator shall keep a backup handheld remote readily available at all times when the device is being operated.

The AFAD shall be positioned so that the end of the gate arm, if used, shall extend at least to the center of the lane being controlled but shy of the roadway centerline.

A drum shall be placed immediately in front of the AFAD trailer at both corners for delineation.

801.16 Temporary Traffic Control Zone

870 A temporary traffic control zone is a work zone with frequently changing operation, a maximum duration of seven calendar days; mobile operation; or a temporary traffic stoppage.

Daytime lane closures on two-lane two-way roads shall be limited in length to a maximum of 1 mi or the length of a half day's operation, whichever is less, or as shown on an approved alternate traffic control plan.

(a) Temporary Mounted Construction Signs

880 When the vertical mounting height for TTCS is between 12 in. and 18 in. to the bottom of the sign, tripod supports may be used. Temporary mounted construction signs, which are mounted on portable supports such as sign stands and tripods may be used for the construction signs in a temporary traffic control zone. The bottom of a temporary mounted construction sign shall be at least 12 in. above the traveled way. Signs on tripod supports shall be installed so that the angle from vertical does not exceed 30°.

890 Roll-up materials will only be allowed for mobile, short duration, or short-term stationary work which will not exceed one daytime period. Roll-up materials shall be selected from the QPL of Reflective Sheeting. Roll-up sign supports shall be ballasted in accordance with the manufacturer's recommendations.

(b) Maintenance of Traffic for Flagging and Mobile Operations

Signs, flagging, flashing arrow signs, and other required traffic control devices shall be furnished in accordance with the details shown on the plans or as directed. The Engineer reserves the right to stop work at any time to relieve traffic congestion.

900 Flagging operations shall be conducted under the supervision of either the designated CWTS or a flagger certified by ATSSA or approved equal certifying organization. The person supervising the flagging operation shall ensure that the flaggers are trained in proper flagging procedures and that the flagging operation is in accordance with 107.12, the standard drawings, and the applicable sections of the MUTCD.

(c) Traffic Control for Temporary Traffic Stoppage

Traffic shall not be allowed to pass directly beneath personnel or equipment working on an overhead structure. Traffic stoppage during an overhead operation shall not exceed 20 minutes at one time. There shall be enough time between consecutive stoppages to allow traffic to return to normal flow.

910 Three working days prior to commencing work which necessitates temporary stoppage of traffic, written notice shall be given to the Department and the Indiana State Police that highway traffic shall be stopped temporarily at a specific location, time, and date to accomplish specified work. Traffic shall be safely controlled during the stoppage. The following minimum requirements shall be met.

1. On Multi-Lane Divided Highways

Advance warning signs shall be located as specified or as otherwise directed. For each direction of road closure two flaggers shall be located at the site of the work and a minimum of two additional flaggers shall be used to warn approaching traffic.

920

2. On Non-Divided Highways

Advance warning signs shall be located as specified or as otherwise directed. For each direction of road closure, one flagger shall be located at the site of the work and a minimum of one additional flagger shall be used to warn approaching traffic.

801.17 Method of Measurement

930

Construction signs, detour route marker assemblies, detour route marker assemblies-multiple routes, temporary worksite speed limit sign assemblies, road closure sign assemblies, portable changeable message signs, and temporary raised pavement markers will be measured by the number of units installed, maintained, and removed.

Temporary panel signs will be measured by the square foot. Temporary panel sign supports, when required, will be measured by the linear foot, complete and in place.

Type III-A, Type III-B, and permanent Type III barricades will be measured by the linear foot of the width of closure.

940

Temporary traffic barrier will be measured by the linear foot per the type specified. Anchored traffic barrier will be measured by the linear foot, separately from unanchored temporary concrete barrier per the type specified. End treatments, other than construction zone energy absorbing terminals, CZ, used on Type 1, Type 2, or Type 3 temporary traffic barrier will be measured by the linear foot as part of the barrier. All end treatments used on Type 4 temporary traffic barrier will be measured by the linear foot as part of the barrier.

Construction zone energy absorbing terminals, CZ, used on Type 1, or Type 2, or Type 3 temporary traffic barriers will be measured by the number of terminals placed.

950

Temporary crossovers Type A and Type B will be measured per each crossover. The refurbishing of temporary crossovers will be measured per each type of crossover refurbished. HMA mixtures for temporary crossovers will be measured by the ton in accordance with 109.01(b). Initial resurfacing and initial patching of refurbished crossovers will be measured in accordance with 402.19. Temporary drainage pipe for temporary crossovers will be measured by the linear foot. Seeding and sodding placed due to the construction and removal or refurbishing and closing of temporary crossovers, will be measured in accordance with 621.13. Removal and subsequent replacement of permanent pavement markings and snowplowable raised pavement markers for temporary crossovers will be measured in accordance with 808.12.

960 Removal and resetting of guardrail, if required for temporary crossovers, will be measured in accordance with 601.13.

Flashing arrow signs will be measured by the number of calendar days each unit is operated.

Patroller will be measured by the number of calendar days during the phase or phases of traffic control, as shown on the plans or as otherwise directed, that require the patroller's presence. Each portion of a day will be measured as a whole day.

970 Temporary pavement message markings will be measured by the number of each type placed. Longitudinal and transverse temporary pavement markings will be measured by the linear foot of material actually placed. Temporary buzz strips will be measured by the linear foot for each 8 in. strip placed, without regard to the number of passes required to attain the specified height.

Removal, when necessary, of any type of non-removable temporary pavement markings will be measured in accordance with 808.12. Removal of removable temporary pavement markings will not be measured for payment.

980 Where temporary pavement markings are to be placed on a pavement which has existing markings, removal of existing markings which conflict with the temporary markings will be measured in accordance with 808.12. Where conflicting markings are covered with black temporary tape Type I, the black temporary tape will be measured by the linear foot of markings covered.

The removal and replacement of prismatic reflectors on existing snowplowable raised pavement markers will be measured in accordance with 808.12.

990 Compacted aggregate No. 73 used for shoulder material will be measured in accordance with 303.09. Excavation of the existing earth shoulder will not be measured for payment.

Cones and tubular markers will not be measured for payment. Permanent tubular markers will be measured per each.

Temporary illumination, fixed temporary signals, portable signals, and maintaining traffic will not be measured for payment.

801.18 Basis of Payment

1000 The accepted quantities of construction signs, detour route marker assemblies, detour route marker assemblies-multiple routes, temporary worksite speed limit sign assemblies, road closure sign assemblies, permanent road closure sign assemblies and temporary raised pavement markers will be paid for at the contract unit price per each. Payment for temporary worksite speed limit assemblies, and PCMS will be made for the maximum number of such assemblies in place at any one time during the life of

the contract. Type III-A, Type III-B, and permanent Type III barricades will be paid for at the contract unit price per linear foot.

1010 Temporary traffic barrier and anchored temporary traffic barrier will be paid for at the contract unit price per linear foot per the type specified. Payment will be made only once, regardless of the number of times the barrier is moved within each project. Payment will be made for Temporary Traffic Barrier placed in, or relocated to, a separate project.

End treatments, other than construction zone energy absorbing terminal, CZ, used on Type 1, Type 2, or Type 3 will be paid for on a linear basis as part of the barrier. All end treatments used on Type 4 temporary traffic barrier will be paid for on a linear basis as part of the barrier.

1020 Construction zone energy absorbing terminal, CZ, used with Type 1, or Type 2, or Type 3 temporary traffic barriers will be paid for at the contract unit price per each for energy absorbing terminal, CZ, of the test level placed. Each unit will be paid for only once regardless of how many times it is moved within each project. Payment will be made for construction zone energy absorbing terminal, CZ placed in, or relocated to, a separate project. Back-up units will be paid for as energy absorbing terminal, CZ, of the test level placed, if they are placed in service due to non-repairable damage to the units already in service.

1030 The accepted quantities of temporary crossovers will be paid for at the contract unit price per each for the type specified. The accepted quantities of refurbishing existing temporary crossovers will be paid for at the contract unit price per each for the type specified. The accepted quantities of HMA for temporary crossovers will be paid for as HMA for temporary pavement at the contract unit price per ton in accordance with 402.20. Temporary drainage pipe for temporary crossovers will be paid for at the contract unit price per linear foot. Sodding and seeding for temporary crossovers will be paid for in accordance with 621.14. Removal and subsequent replacement of permanent pavement markings and snowplowable raised pavement markers for temporary crossovers will be paid for in accordance with 808.13. Removal and resetting of guardrail, if required for temporary crossovers, will be paid for in accordance with 601.14.

1040 If more than one construction sign is mounted on a common support with the messages facing opposite directions, the largest sign will be paid for at the contract unit price of the sign, and each additional sign will be paid for at half the unit price of the sign if it had been erected independently.

Temporary panel signs will be paid for at the contract unit price per square foot as shown on the plans. Temporary panel sign supports will be paid for at the contract unit price per linear foot, complete and in place.

801.18

1050 **Flashing** arrow signs and patrollers will be paid for at the contract unit price per day per each.

Temporary pavement message markings placed will be paid for at the contract unit price per each, for the message specified. Longitudinal and transverse temporary pavement markings and temporary buzz strips, will be paid for at the contract unit price per linear foot of material, complete in place.

1060 Removal, when necessary, of non-removable temporary pavement lines and message markings will be paid for in accordance with 808.13. The cost of removal of removable temporary pavement markings shall be included in the cost of the pay item for placement of the markings.

Where temporary pavement markings are to be placed on a pavement which has existing markings, removal of the existing markings which conflict with the temporary markings will be paid for in accordance with 808.13. Where conflicting markings are covered with black temporary tape Type I, the specified width of black temporary tape will be paid for at the contract unit price per linear foot of temporary pavement marking, removable.

1070 Permanent tubular markers and permanent drums will be paid for at the contract unit price per each.

Compacted aggregate used for shoulder material will be paid for as compacted aggregate No. 73 in accordance with 303.10.

The removal and replacement of reflectors on existing snowplowable raised pavement markers will be paid for in accordance with 808.13.

1080 Temporary illumination will be paid for at the contract lump sum price.

All temporary traffic control devices which are specified as separate pay items and used for maintenance of traffic will be paid for as set out in the Schedule of Pay Items. The furnishing, placing, moving, removal, and maintenance of all other temporary traffic control devices will be paid for at the contract lump sum price for maintaining traffic.

The accepted fixed temporary and portable signals, complete in place and later removed as specified, will be paid for at the contract lump sum price.

1090 Payment will be made under:

Pay Item **Pay Unit Symbol**

Barricade, _____ LFT
type

	Barricade, III, Permanent	LFT
	Barrier, Direction Indicator	EACH
	Construction Sign, _____ type	EACH
1100	Detour Route Marker Assembly.....	EACH
	Detour Route Marker Assembly, Multiple Routes	EACH
	Drum, Permanent.....	EACH
	Energy Absorbing Terminal, CZ, TL - _____ test level	EACH
	Fixed Temporary Signal.....	LS
	Flashing Arrow Sign.....	DAY
	Maintaining Traffic	LS
	Patroller	DAY
	Portable Changeable Message Sign.....	EACH
1110	Portable Signal	LS
	Road Closure Sign Assembly.....	EACH
	Road Closure Sign Assembly, Permanent.....	EACH
	Temporary Buzz Strips.....	LFT
	Temporary Crossover Drainage Pipe.....	LFT
	Temporary Crossover, _____ type	EACH
	Temporary Crossover, _____, Refurbish..... type	EACH
	Temporary Illumination.....	LS
1120	Temporary Panel Sign Supports	LFT
	Temporary Panel Signs.....	SFT
	Temporary Pavement Marking, _____ in..... width	LFT
	Temporary Pavement Marking, Removable, _____ in..... width	LFT
	Temporary Pavement Message Marking, _____ description	EACH
	Temporary Pavement Message Marking, Removable, _____ description	EACH
1130	Temporary Raised Pavement Marker, _____ grade	EACH
	Temporary Traffic Barrier, _____ type	LFT
	Temporary Traffic Barrier, Anchored, _____ type	LFT
	Temporary Transverse Pavement Marking, _____ in..... width	LFT
1140	Temporary Transverse Pavement Marking, Removable, _____ in..... width	LFT

Temporary Worksite Speed Limit Sign Assembly, [redacted] type EACH
Tubular Marker, Permanent.....	EACH

1150 Each construction sign, barricade, temporary worksite speed limit sign assembly, road closure sign assembly, or flashing arrow sign will be paid for only once regardless of how many times each is moved, replaced, or how many times each is altered to change the sign message within each project. Payment will be made for signs placed in, or relocated to, a separate project. Payment will not be made for signs or barricades used for the convenience of the Contractor.

If a temporary worksite speed limit sign assembly, for intermittent use is not flashing when required beginning 2 h after work begins, or if such assembly is flashing when no work has been taking place for 2 h or longer, \$200.00 will be deducted from payment for such work for each 4 h period or part thereof, beginning after the 2 h grace period.

1160 Temporary mounted construction signs will not be paid for.

Replacement of snowplowable raised pavement marker castings damaged due to removing reflectors will not be paid for.

Electric energy necessary to power luminaires and fixed temporary signals will not be paid for.

The cost of furnishing all materials, erection, maintenance, removal, and necessary incidentals shall be included in the cost of barricades.

1170 The cost of furnishing, installing, maintaining, and subsequent removal of the detour marker, route marker, or street or road name sign, cardinal directional marker, directional arrow marker, posts which support the assembly, and all necessary hardware shall be included in the cost of detour route marker assembly or detour route marker assembly, multiple routes.

1180 The cost of all materials, equipment, labor, and incidentals necessary to install, maintain, repair, and to remove the unit shall be included in the cost of energy absorbing terminal, CZ. The cost of stockpiling standby terminals and terminal materials, whether incorporated into the work or not, shall be included in the cost of energy absorbing terminal, CZ. All units shall remain the property of the Contractor upon completion of the contract.

The cost of the excavation required for placement of compacted aggregate shoulders No. 73 will be included in the pay item maintaining traffic.

If the compacted aggregate No. 73 required for shoulders is removed, the cost of such removal shall be included in the cost of the compacted aggregate.

1190 If the Contractor elects to use more than two simultaneous operations during the installation of snowplowable pavement markers or reflectors, the cost of required traffic protection devices for additional operations shall be included in the cost of maintaining traffic.

The cost of necessary flaggers; automated flagger assistance devices; protection of traffic at structure foundations; and furnishing, erecting, placing, maintaining, relocating, and removing lights, cones, flexible channelizers, tubular markers, drums, delineators, or other devices as directed shall be included in the cost of maintaining traffic.

1200 The cost of furnishing and placing cones or tubular markers in accordance with 801.08 and drums in accordance with 801.09, the watcher in accordance with 107.12, repair or replacement of damaged or inoperative traffic control devices, and traffic maintenance in accordance with 104.04 shall be included in the cost of maintaining traffic.

Additional materials necessary to place the portable changeable message sign in a secure and level manner for site conditions shall be included in the cost of the pay item. All costs to furnish, install, program, activate, deactivate, change messages, move, replace, and maintain the PCMS shall be included in the cost of the pay item.

1210 The cost of IP cellular phone service shall be included in the cost of the pay item.

The cost of the vehicle detection, solar panel, battery cabinet, program timing module, signal heads, wiring, trailer, and all hardware required shall be included in the cost of the portable signal.

The cost of installing, maintaining, and subsequent removal of signs, construction warning lights, assembly supports, and all necessary hardware shall be included in the cost of road closure sign assembly.

1220 The cost of installation, maintenance, and removal or closure of the temporary crossover, including excavation, compaction, subgrade preparation, and reshaping damaged median area shall be included in the cost of temporary crossover.

The cost of removal of earth cover, removal of drums, reshaping damaged median areas, and closure or removal of temporary crossover shall be included in the cost of temporary crossover, refurbish.

The cost of placement, maintenance and replacement of temporary pavement markings shall be included in the cost of the markings.

1230

The cost of cleaning existing pavement and removal of buzz strips shall be included in the cost of buzz strips. Damage to the pavement caused by removal of buzz

strips and temporary pavement markings shall be repaired as directed with no additional payment.

1240 No payment will be made for temporary pavement markings which are in the standard pavement marking pattern, and which are to be in service from December 1 through the following March 31 due to the Contractor’s failure to complete the work as scheduled. However, payment will be made for these markings if the failure to complete the work as scheduled is due to conditions beyond the Contractor’s control.

The cost of furnishing, installing, maintaining, and subsequent removal of temporary raised pavement marker shall be included in the cost of temporary raised pavement marker.

The cost of delineation of temporary traffic barrier shall be included in the cost of temporary traffic barrier.

1250 Damage done to pavement by removal of temporary traffic barriers and anchors shall be repaired with no additional payment.

SECTION 802 – SIGNS

802.01 Description

This work shall consist of furnishing the material for and erecting traffic signs in accordance with 105.03. Signs shall be installed as required unless written approval is obtained from the District Traffic Engineer to make modifications at specific locations.

10 Existing ground mounted signs to be reset shall be removed without damage, stored and re-installed as shown on the plans.

Signs shall be stored in such a manner that they do not come in contact with surface run-off water. Signs shall be stored so that moisture accumulation or heat build-up does not occur.

All signs shall be marked for identification as shown on the plans. The marking shall consist of a Type II sheeting material, with a class I adhesive, shown on the QPL of Reflective Sheeting. It shall be applied to the back of the sign on the lower corner closest to the nearest edge of pavement and shall not be covered by the sign’s supports.

MATERIALS

802.02 Materials

Materials shall be in accordance with the following:

Concrete	702
Fasteners	919.01(d)

	Overhead Sign Structure.....	910.19
	Packaged Patching Products.....	901.08
	Reinforcing Bars.....	910.01
30	Sign Posts.....	910.14
	Traffic Signs.....	919.01

Materials used for temporary construction signs, temporary traffic signs, and temporary panel signs shall meet the requirements herein. The basis for use of the materials will be by visual inspection with no additional testing, evaluation, or documentation.

CONSTRUCTION REQUIREMENTS

40 **802.03 Location of Signs and Sign Structures**

Sign and sign structure locations shall be staked, and the Engineer will either approve the locations or give written notice of necessary changes. The provisions of 109.03 will not apply to posts ordered prior to approval of staked locations.

Two days notice shall be provided for inspection and approval of staked locations.

All signs shall be adjusted to eliminate specular reflection.

50 **802.04 Working Drawings**

Working drawings shall be submitted in accordance with 105.02 for all strain poles and structural frames, except breakaway posts. Roadway cross-sections and bridge dimensions shall be checked, as applicable, in the field prior to preparation of working drawings. If the no-load camber is not shown on the plans, the Contractor shall furnish this information on the working drawings.

60 **802.05 Excavation and Backfill**

The finished pavement or shoulder section shall not be damaged during excavation.

60 The Engineer shall be notified in writing of class X material in accordance with 206.02 encountered within the limits of the traffic sign supports foundation excavation. The Engineer will determine the design for the installation of the foundations. Excavation of class X material shall be in accordance with 206.

The excavation for sign posts shall be made as nearly as possible to neat lines. Sign post encasement shall not be formed except in sandy soil, or as directed.

70 **802.06 Placing Concrete**

70 Placing concrete shall be in accordance with 702, except that foundations incorporated into sections of concrete barrier wall shall receive a finish in accordance with 702.21. Exposed concrete shall have a smooth surface and beveled edges.

Anchor bolt alignment shall be maintained during concrete placement. Temporary positioning plate and associated nuts shall be removed upon completion of the foundation. The threads shall be protected during concrete placement. Any damage to galvanized coating shall be repaired prior to assembly.

Conduit and grounding shall be in accordance with 807.

80 **802.07 Installing Supports**

(a) Posts

Posts shall be vertical after installation. All damaged posts shall be removed and replaced with an acceptable post.

Square sign post foundations shall be reinforced anchor base or unreinforced anchor base as shown on the plans. If sign post Type A or sign post Type B is specified, square sign posts may be used. Splicing of square steel sign posts will not be allowed.

- 90 In locations where class X excavation is encountered if the total length of the anchor bolts cannot be used, they shall be cut off. A steel plate measuring 6 by 6 by 1/2 in. shall be welded to the bottom of the bolts. The plate shall have a hole cut which allows the bolt to pass through it and the plate and bolt shall be completely welded together around the circumference of the bolt on both sides of the plate. No butt welding is allowed. The length of the bolts shall allow the plate to be covered by 3 to 4 in. of concrete at the bottom of the foundation.

- 100 Base plate bolts for panel sign post installations shall be tightened in accordance with 711.65(d). Bolts at the fuse or hinge plate joint shall be tightened in accordance with 711.65(d) or by the direct tension indicator, DTI, method.

(b) Overhead Sign Structures

When erection of the structure has been started, it shall be completed the same day. The structure shall be loaded, to prevent vibration, by attaching signs or lighting supports the same day.

An oxidation inhibitor in accordance with 802.07(b)4 shall be applied to all surfaces that mate with a dissimilar material.

- 110 Fasteners for chord splice connections shall be high strength heavy hex bolts conforming to ASTM F3125, grade A325 with matching lock nuts having steel inserts. Installation shall be in accordance with 711.65. Other bolts and hardware shall conform to the requirements of 910.19.

Fasteners shall be tightened by turn-of-nut tightening, calibrated wrench tightening, or direct tension indicator tightening. The calibrated wrench shall be calibrated by an acceptable tension measuring device such as a Skidmore-Wilhelm.

Anchor bolt hardware tightening shall be by the turn of the nut method and as follows:

1. Anchor bolts shall be clean and not be damaged or out of plumb.
2. The threaded portion of the anchor bolts shall be lubricated within 24 h prior to tightening.
3. The distance from the bottom of the levelling nuts to the top of the foundation shall be less than the diameter of the bolt, unless specified otherwise.
4. The tightening procedure shall be as follows:
 - a. All tightening shall be in the star pattern order as shown on the plans, or in accordance with the FHWA "Guidelines for the Installation, Inspection, Maintenance and Repair of Structural Supports for Highway Signs, Luminaires, and Traffic Signals".
 - b. All leveling nuts shall be brought into contact with the base plate. While holding the levelling nut with a wrench, the top nut shall be brought to a snug tight condition in full contact with the base plate. The levelling nut shall be brought to a snug tight condition. This process shall be repeated for the remaining top and levelling nuts.
 - c. After all top and levelling nuts are made snug tight, the top nuts and base plate shall then be marked, and the nuts further tightened, pretensioned, by a minimum 1/6 turn for bolt diameters that are 1 3/4 in. or greater or a minimum 1/3 turn for bolts less than 1 3/4 in. in diameter.
 - d. For span structures, the top nuts shall be inspected for proper fit no sooner than 10 minutes after the installation of the truss or span on the end bents or columns. Nuts found not to be in a snug tight condition or nuts that have loosened, based on a visual inspection of the relative position marks, shall be tightened by repeating the steps above.

Damage that is detrimental to the structural integrity of the frame or aesthetic appearance shall be repaired.

No field welding will be allowed.

The grounding connection shall be located 12 in. from the bottom of the support and shall be easily accessible from the structure manhole.

Traffic shall be maintained in accordance with 801.16 during installation.

170

1. Trusses

When placed on blocks to produce the required camber, the truss sections shall fit together at the flange connections with a minimum gap of 1/16 in. on any flange assembly. The total of the gaps in any one connection shall not exceed 1/8 in. Gaps shall be shimmed with tapered shims before tightening the flange bolts.

Vertical truss members and vertical diagonals shall be machined to provide a snug tube-to-tube fit to the chord along the entire edge before welding. Horizontal truss members and horizontal diagonals shall be slotted for the dimensions shown on the plans and welded to the gusset plates. They shall be sealed against water penetration.

180

Chord flanges shall be machined from solid rounds. Mating surfaces shall be flat within 1/64 in. Flanges shall be given an additional finish if necessary to ensure contact between plates.

The cap bolts used to attach the top caps of end-support columns shall be located so as to miss the J hook.

The camber shown on the plans is for fabrication only. It shall be measured with the truss fully supported. The allowable camber tolerance is 25% of the specified camber value.

190

All signs and walkway brackets shall be placed as close to the brace points as possible. The Contractor shall verify that the dimensions are suitable for the type of fixture to be supplied.

2. Monotube

The required camber shall be achieved in accordance with the manufacturer's recommendations as detailed on the working drawings.

200

3. Cantilever Arms

Cantilever arms shall fit together at the flange connections between sections with a minimum gap of 1/16 in. on any flange assembly. The total of the gaps in any one connection shall not exceed 1/8 in. Double arm chords are octagonal tubular shape with 0.14 in./ft taper. Quadri-chord arms are circular shape with constant diameter.

4. Bridge Brackets

The location of the sign bracket may be shifted to avoid joints or stiffeners on the bridge. Before placing aluminum in contact with concrete, both the concrete and aluminum surfaces shall be coated with an aluminum-impregnated caulking compound. Where aluminum surfaces are to be placed in contact with steel, the steel

210

surface shall be given one coat of zinc chromate paint and the aluminum surfaces shall be coated with an aluminum-impregnated caulking compound before placement. After the bolts have been tightened, the excess caulking compound shall be removed. All openings around the flanges shall be fully painted and shall be flush with the caulking compound.

802.08 Installing Signs

220 If new signs are to be installed on existing overhead sign structures, the existing mounting hardware, if applicable, may be reused. Bolts, nuts, and washers shall not be reused. Additional new hardware may be required to complete the mounting. All such sign hangers protruding above the new signs shall be cut off flush to the top of the signs. Splicing or overlapping of sign hangers will not be allowed. All unused sign hangers and hardware shall be removed.

230 A minimum of two sign support bracket assemblies will be required for all signs having a width greater than 30 in. Signs 7 ft or less in height shall have sign support bracket assemblies mounted at a maximum spacing of 7 ft. Signs greater than 7 ft in height shall have sign support bracket assemblies mounted at a maximum spacing of 5 ft. Sign overhang beyond the end bracket assembly shall be not more than half the spacing of the bracket assemblies.

(a) Sheet Signs

Sheet signs shall be fastened to the post as shown on the plans. Rivets shall be used to fasten sheet signs mounted to panel or other sheet signs. Steel and plastic washers shall be placed as shown on the plans. Lock-nuts shall be tightened sufficiently so that the sign is held firmly against the post. If the sign sheeting is twisted or damaged, the sign shall be replaced.

240 Lock-nuts for cable span mounted signs shall be tightened so that the sign is held firmly against the cable. There shall be no deformation or twisting of aluminum sheeting, or damage to the reflective sheeting.

(b) Panel Signs

Panel signs shall be mounted as follows:

- 250 1. Up to and including 24 ft of sign width, clips shall be placed on both sides of each post at the top and bottom of the sign. Intermediate clips shall be placed one on each panel on each post and shall alternate left and right on each post.
2. Over 24 ft of sign width, double clips shall be used, one on the right side and one on the left side on each post per panel width, plus the sets necessary to attach the top and bottom of the sign.
3. Lock-nuts shall be torqued two full turns beyond snug fit.

Panels shall be bolted together on 24 in. centers with an allowable gap of no more than 1/16 in. between units. Panels shall be temporarily braced in accordance with the panel manufacturer's recommendations.

260

802.09 Removal, Resetting, or Relocation of Signs or Support Assemblies

Signs to be relocated shall be installed in accordance with the MUTCD and on new posts. Signs to be reset shall be installed in accordance with the MUTCD and on existing posts.

Signs or support assemblies to be removed shall be removed within five work days after the required replacement signs or support assemblies are installed. Concrete foundations shall be removed to a minimum depth of 1 ft below the ground surface. After concrete foundations have been removed, the area shall be backfilled and seeded or sodded in accordance with 621, or treated with a material which matches that in the surrounding area.

270

802.10 Roadway and Bridge Reference Signs

If existing roadway and bridge reference signs interfere with the prosecution of other work, such signs and posts shall be removed, stored, and then reinstalled within 25 ft of their original longitudinal location or as directed.

802.11 Method of Measurement

Sheet signs and panel signs will be measured by the square foot. Sheet signs will be measured as the smallest dimensions of a square or rectangle large enough to make the sign. However, triangular or trapezoidal signs will be measured as the smallest triangle or trapezoid required to make the sign.

280

If the pay unit for sheet signs is shown in the Schedule of Pay Items as each, the number of sheet signs specified, including posts, hardware, and erection, will be measured by the number of units installed.

Sign posts will be measured by the linear foot. Square sign posts will be measured from the top of the post to the termination of the post in the anchor base.

290

Traffic sign support foundations will be measured by the number of units of each type installed. No reduction will be made in a unit if class X material is encountered during foundation excavation.

If class X material is encountered during foundation excavation, the quantity to be measured will be that authorized and removed and in accordance with 206.10.

300

Structural steel, breakaway, will be measured by the pound. Such measurement will include the weight of breakaway sections such as stiffeners, base plates, and fuse plates.

Reference posts, including post, sign, and hardware, will be measured by the number of units installed.

Backfill of traffic sign support foundations will be measured in accordance with 211.09.

310 Overhead sign structures will be measured by the number of units of each type installed.

Overhead sign structures to be removed will be measured by the number of structures removed.

Existing ground mounted signs reset will be measured by the number of signs removed and reinstalled, complete in place.

802.12 Basis of Payment

320 The accepted quantities of sheet signs and panel signs will be paid for at the contract unit price per square foot, of the type and thickness specified, with legend, complete in place.

Sign post will be paid for at the contract unit price per linear foot for the type specified.

Structural steel, breakaway, will be paid for at the contract unit price per pound.

Ground mounted sign support foundations will be paid for at the contract unit price per each type specified.

330 Reference posts will be paid for at the contract unit price per each, complete in place.

Payment for class X material encountered during a foundation excavation will be made in accordance with 206.11.

Payment for backfill of support foundations will be made in accordance with 211.10.

340 The removal of signs, overhead structures, and sign assemblies, will be paid for at the contract unit price per each.

Existing ground mounted signs reset will be paid for at the contract unit price per each.

Payment will be made under:

Pay Item	Pay Unit Symbol
350 Box Truss Sign Structure Foundation, _____ type	EACH

	Cable Span Sign Structure Foundation, _____	EACH
	type	
	Cantilever Sign Support Foundation, _____	EACH
	type	
	Overhead Butterfly Cantilever Sign Structure Foundation, _____	EACH
	type	
	Overhead Sign Structure, _____, Remove	EACH
	type	
360	Overhead Sign Structure, Box Truss, _____	EACH
	type	
	Overhead Sign Structure, Bridge Bracket Assembly.....	EACH
	Overhead Sign Structure, Butterfly Cantilever.....	EACH
	Overhead Sign Structure, Cantilever, _____	EACH
	type	
	Overhead Sign Structure, Monotube	EACH
	Overhead Sign Structure, Tri-Chord, _____	EACH
	type	
	Reference Post.....	EACH
370	Sign and Supports, Wide Flange, Remove	EACH
	Sign Post, _____	LFT
	type	
	Sign Post, Square, _____, Reinforced Anchor Base.....	LFT
	type	
	Sign Post, Square, _____, Unreinforced Anchor Base	LFT
	type	
	Sign, Double Faced, Sheet, With Legend, _____	SFT
	thickness	
	Sign, Ground Mounted, Reset	EACH
380	Sign, Overhead, Remove.....	EACH
	Sign, Panel, Relocate.....	EACH
	Sign, Panel, Remove.....	EACH
	Sign, Panel, With Legend.....	SFT
	Sign, Sheet Assembly, Relocate	EACH
	Sign, Sheet, and Supports, Remove.....	EACH
	Sign, Sheet, Relocate.....	EACH
	Sign, Sheet, Remove.....	EACH
	Sign, Sheet, With Legend.....	EACH
	Sign, Sheet, With Legend, _____	SFT
390	thickness	
	Structural Steel, Breakaway	LBS
	Tri-Chord Sign Structure Foundation, _____	EACH
	type	
	Wide Flange Sign Post Support Foundation, _____	EACH
	type	

The cost of staking sign and sign structure locations, including materials and labor, shall be included in the cost of the pay items in this section.

- 400 The cost of removal of signs, sign assemblies, sign lighting circuitry, supports, concrete foundations, backfill material, sodding, seeding, and necessary incidentals shall be included in the cost of overhead sign structure, remove.

The cost of walkway assembly, where applicable, shall be included in the cost of overhead sign structure.

- 410 The cost of roadway and bridge reference signs and posts to be removed, stored, and reinstalled shall be included in the cost of other pay items, unless otherwise specified. Roadway and bridge reference signs which are damaged by the Contractor shall be replaced with no additional payment.

The cost of the reinforced anchor base or unreinforced anchor base, angle bolts, and rivets shall be included in the cost of sign post, square.

No additional payment will be made if square sign posts are used in lieu of Type A or Type B posts.

- 420 The cost of all hardware to attach the sign to its structural supports, the reflective sheeting on both faces, and all legend shall be included in the cost of double-faced sheet signs.

The cost of all hardware necessary to assemble and attach the sign to its structural supports, all legend, and adjustments necessary to eliminate specular reflection shall be included in the cost of sheet sign or panel sign.

The cost of all necessary hardware including sign hangers, clips, and U bolts required for the mounting of signs to existing or new overhead sign structures shall be included in the cost of the sign.

- 430 The cost of modifying existing hardware to mount a new sign shall be included in the cost of the new sign.

The cost of identification markings for signs shall be included in the cost of the sign.

The cost of existing ground mounted sign removal, existing post removal, and storage shall be included in the cost of sign resetting. Existing signs or posts that are damaged by the Contractor shall be replaced with no additional payment.

- 440 The cost of sign removal, existing post removal, and all mounting hardware necessary to attach the existing sign to new posts, shall be included in the cost of the sign relocation.

The cost of concrete, reinforcement, stub, anchor bolts, conduit, and all necessary hardware shall be included in the cost of the support foundation.

The cost of furnishing and applying aluminum-impregnated caulking compound and zinc chromate paint as required in 802.07, shall be included in the cost of the pay items in this section.

450

The replacement of posts damaged by the Contractor’s activities shall be without additional payment.

The cost of cutting the reinforcing bars and anchor bolts, furnishing the steel plate and welding the plate to the ends of the anchor bolts when class X excavation is encountered shall be included in the cost of the pay items in this section.

The cost of excavation, except for class X material, and necessary incidentals shall be included in the cost of the pay items in this section.

460

SECTION 803 – WELDING ALUMINUM ALLOYS

803.01 Description

This work shall consist of welding aluminum alloys for highway structures. The welding terms used shall be in accordance with definitions included in the AWS Definitions “MD” Welding and Cutting, AWS A3.0. Special conditions shall be fully explained by means of added notes or details.

The aluminum alloys to be welded under these specifications may be any of the following ASTM alloy designations:

10

- (a) wrought non-heat-treatable alloys 3003, 3004, 5052, 5083, 5086, 5456;
- (b) wrought heat-treatable alloys 6061, 6063; or
- (c) cast heat-treatable alloy 356.0.

MATERIALS

20

803.02 Materials

Materials shall be in accordance with the following:

Electrodes	924.01
Filler Material.....	924.01
Shielding Gases	924.01
Welding Rods	924.01

30 Material used for permanent backing shall be at least equivalent in weldability to the base metal being welded.

803.03 Welding Processes

The welding process shall be by the gas metal-arc process or the gas tungsten-arc process. Other processes may be used if prior approval is given.

(a) Preparation of Materials

Joint details shall be in accordance with design requirements and detail drawings. The location of joints shall not be changed without approval.

40 Edge preparation shall be by sawing, machining, clipping, or shearing. Gas tungsten-arc or gas metal-arc cutting may also be used. Cut surfaces shall meet the ANSI surface roughness rating value of 1000. Oxygen cutting shall not be used.

Surfaces and edges to be welded shall be free from fins, tears, and other defects which would adversely affect the quality of the weld. Dirt, grease, forming or machining lubricants, and organic materials shall be removed from the areas to be welded by cleaning with a suitable solvent or by vapor degreasing.

50 The oxide shall be removed from all edges and surfaces to be welded by wire brushing or by other mechanical methods such as rubbing with steel wool or abrasive cloth, scraping, filing, rotary planing, or sanding just prior to welding. If wire brushing is used, the brushes shall be made of stainless steel. Hand or power driven wire brushes which have been used on other materials shall not be used. Where mechanical methods of oxide removal are found to be inadequate, a standard chemical method shall be used. Welding shall be done within 24 h after chemical treatment. When gas tungsten-arc welding with direct current straight-polarity is being used, all edges and surfaces to be welded shall have the oxide removed by a standard chemical method.

60 Welding shall not be done on anodically treated aluminum unless the condition is removed from the joint area to be welded.

(b) Welding Procedure

70 All butt welds requiring 100% penetration, except those produced with the aid of backing, shall have the root of the initial weld chipped or machined out to sound metal before welding is started from the second side. Butt welds made with the use of backing shall have the weld metal fused with the backing. Where accessible, backing for welds that are subject to computed stress or which are exposed to view on the completed structure and which are not otherwise parts of the structure, shall be removed and the joints ground or machined smooth. In tubular members, butt welds subjected to computed stresses shall be made with the aid of permanent backing rings or strips.

The procedure used for production welding of any particular joint shall be the same as used in the procedure qualification for that joint.

All welding operations, either shop or field, shall be protected from air currents or drafts so as to prevent any loss of gas shielding during welding. Adequate gas shielding shall be provided to protect the molten metal during solidification. The work shall be positioned for flat position welding whenever practicable. All weld joints shall be dry at the time of welding.

The size of the electrode, voltage and amperage, welding speed, gas or gas mixture, and gas flow rate shall be suitable for the thickness of the material, design of joint, welding position, and other circumstances attending the work. Gas metal-arc welding shall be done with direct current, reverse polarity. Gas tungsten-arc welding shall be done with alternating current or with direct current, straight polarity.

When the joint to be welded requires specific root penetration, the Contractor shall make a sample joint and a macro etched cross-section of the weld to demonstrate that the joint welding procedure to be used is attaining the required root penetration. The sample joint shall have a length of at least 1 ft and shall be welded with the electrode, polarity, amperage, voltage, speed, gas mixture, and gas flow rate that are proposed to be used in production welding. Evidence on record may be accepted in lieu of the receding test.

Where preheat is needed, the temperature of preheat shall not exceed 350°F for heat-treated alloys and 600°F for non-heat-treated alloys. The temperature shall be measured by temperature indicating crayons or by pyrometric equipment. Heat-treated alloys shall not be held at the maximum preheat temperature or at temperatures near the maximum for more than 30 minutes.

(c) Weld Quality

Welds will not be accepted if they contain cracks in the welds or in the adjacent base metal, copper inclusions, or porosity in excess of that allowed by the AWS D1.2 Structural Welding Code.

Lack of fusion, incomplete penetration, or tungsten or oxide inclusions will be acceptable only if small and well dispersed.

Undercut shall be no more than 0.01 in. deep when its direction is transverse to the primary stress in the part that is undercut. Undercut shall be no more than 1/32 in. deep when its direction is parallel to the primary stress in the part that is undercut. Overlap shall not be allowed. All craters shall be filled to the full cross-section of the welds. Welds having defects greater than the levels of acceptance specified herein shall be considered as rejected unless corrected in accordance with 803.03(e).

(d) Inspection

All welds shall be inspected visually to determine compliance with 803.03(c). In addition, all welds subjected to computed stress shall be inspected by the dye penetrant method except as specified below. For highway sign structures, the dye penetrant method shall be used on butt welds in columns and main chord members; on fillet

welds connecting columns to bases and main chord members, including the associated flanges, gussets, or main load carrying brackets or members; and on fillet welds connecting flanges to the main truss chord members. The dye penetrant tests shall be performed in accordance with ASTM E165, method B. Dye penetrant inspection may be omitted provided that the inspector examines each layer of weld metal with a magnifier of 3X minimum before the next successive layer is deposited.

(e) Corrections

- 130 In lieu of rejection of an entire piece or member containing welding which is unacceptable, the corrective measures listed below may be allowed if approval is obtained prior to making each repair. Defective welds shall be corrected by removing and replacing the entire weld, or as follows:

1. Cracks in Welds or Base Metal

The full extent of cracks shall be determined by dye penetrant method or other positive means. The cracks shall be removed throughout their length and depth, and rewelded.

- 140 **2. Excessive Porosity and Lack of Fusion**
All defective portions shall be removed and rewelded.

3. Copper or Tungsten Inclusions
All defective portions shall be removed and rewelded.

4. Excessive Concavity of Crater, Undercut and Undersize Weld
The weld shall be cleaned and additional weld metal shall be deposited.

- 150 **5. Overlap**
Overlap shall be reduced by removal of the excess weld metal.

The defective areas shall be removed by chipping or machining. Oxygen cutting shall not be used. Before rewelding, the joint shall be inspected to ensure all the defective weld has been removed. If dye penetrant has been used to inspect the weld, all traces of penetrant solutions shall be removed with solvent, water, heat, or other suitable means before rewelding.

803.04 Qualification of Procedures, Welders, and Welding Operators

- 160 Joint welding procedures shall be qualified previously by tests prescribed in the AWS D1.2 Structural Welding Code. Evidence of previous qualification of the joint welding procedures to be employed may be accepted.

All welders and welding operators shall be previously qualified by tests in accordance with the AWS D1.2 Structural Welding Code. Evidence of previous qualification of the welders and welding operators to be employed may be accepted. The same process and type of equipment that is required for execution of the contract work shall be used in qualifying welders and welding operators.

SECTION 804 – DELINEATORS

804.01 Description

This work shall consist of furnishing and erecting delineators in accordance with 105.03 and 107.12. Delineators shall be installed as required unless approval is obtained from the District Traffic Engineer to make modifications.

MATERIALS

10 804.02 Materials

Materials shall be in accordance with the following:

Delineator Posts.....	910.15
Delineators.....	926.02
Flexible Delineator Posts.....	926.01

The types of delineators shall be:

- 20 (a) D1 – single
 (b) D2 – double
 (c) D3 – triple.

Hardware for mounting delineators on posts shall be aluminum alloy in accordance with 919.01(d)2; stainless steel or galvanized steel in accordance with 919.01(d)1; or aluminum pull-through blind rivets. Bolts and lock-nuts or rivets shall be 3/16 in. diameter.

The types of flexible delineator posts shall be:

- 30 (a) Type I - ground mounted
 (b) Type II - surface mounted.

CONSTRUCTION REQUIREMENTS

804.03 Delineator Visibility

Delineator reflector units shall be positioned so as to be visible for a distance of 1,000 ft on tangent sections or at maximum visibility distances on curves. These locations shall be established under normal weather and atmospheric conditions when illuminated by the upper beam of standard automobile headlights.

40

804.04 Posts

Posts shall be installed in accordance with 802.07.

804.05 Flexible Delineator Posts

These posts shall be installed according to the manufacturer's recommendations

and shall be set so that the top is no more than 1/2 in. from any vertical plane through the bottom.

804.06 Method of Measurement

50 Delineators with posts, delineator posts, and flexible delineator posts will be measured by the number of units of the type specified.

804.07 Basis of Payment

The accepted quantities of delineators, delineators with post, delineator post, and flexible delineator post, if set out as a separate pay item, will be paid for at the contract unit price per each for the type specified, complete in place.

Payment will be made under:

60	Pay Item	Pay Unit Symbol
	Delineator Post	EACH
	Delineator Post, Flexible, _____ type	EACH
	Delineator with Post, _____ type	EACH
	Delineator	EACH

70 Where new delineator posts are installed to replace existing delineator posts, the cost of the removal of the existing post shall be included in the cost of the new post.

SECTION 805 – TRAFFIC SIGNALS

805.01 Description

This work shall consist of furnishing miscellaneous materials, not furnished by the Department, and installing traffic signals in accordance with these specifications and in reasonably close conformance with the lines, grades, and locations shown on the plans or as directed.

MATERIALS

10

805.02 Materials

Materials shall be in accordance with the following:

Castings for Handhole	910.05(b)
Coarse Aggregate, Class E or Higher, Size No. 8	904.03
Concrete, Class A, B, or C	702
Loop Detector Sealant	906.02(a)
Reinforced Concrete Pipe.....	907.02
Reinforcing Bars.....	910.01

20 Traffic Signal Materials and Equipment..... 922
 Treated Lumber 911.02

The proposed work shall be examined in order to determine what materials not furnished by the Department are required to complete the contract. The Department will furnish only the materials specified on the Department Furnished Materials special provision. If materials to be furnished by the Contractor are listed, the list is only a guide for estimating purposes. All additional materials required to complete an operating installation as specified shall be furnished.

30 Signal handholes shall be Type I or Type II as shown on the plans.

Pedestrian push buttons shall be the type designated in the contract documents, APS or Non-APS.

Joint sealant material shall be compatible with the roadway materials. If polyethylene duct loop wire is used, only sealant in accordance with 906.02(a)1 shall be used.

40 Timber poles to be furnished shall be in accordance with the current ANSI specifications and dimensions. They shall be of the length and class specified, be fully treated in accordance with 922.10(b), and dry. Minimum circumference at the top and at a point 6 ft from the butt shall be in accordance with ANSI specifications.

Steel strain poles greater than 24 ft in length shall be in accordance with 922.10(a).

The battery cabinet and program timing module for solar powered flashing beacons shall be from the QPL of Traffic Signal and ITS Devices.

CONSTRUCTION REQUIREMENTS

50

805.03 General Requirements

The Contractor shall maintain existing traffic signals in operation until the Engineer determines that the progress of the work necessitates their removal. The new installation shall not interfere with the operation of the existing signal. The work shall proceed in such a manner that the signals are not out of service at any two adjacent intersections at any time. When the operation of an existing traffic signal needs to be interrupted before the new signal is placed in operation, the traffic shall be controlled at all times. The work shall be scheduled so that the interruption is limited to a minimum amount of time and at off peak hours. The new span and catenary installation shall not interfere with the operation of the existing traffic signal. Traffic shall be controlled at all times during the changeover when the existing traffic signal is turned off and the new signal is turned on. This changeover shall take place such that the interruption is limited to a minimum amount of time.

60

When directed, temporary stop signs shall be erected at the intersection. When no work is in progress, the intersection shall have at least two operating signal faces for each approach. When the new installations are completed, all existing signal equipment and materials including timber poles, steel poles, and cast-iron handhole rings and covers which have not been used in the new installation shall be carefully removed. Regardless of the right to materials found on the project, as set out in other sections of these specifications, items designated in the contract documents, and field identified by the Department, as traffic signal equipment to be salvaged by the Department or local unit of government shall be stored at a secure site until such time as it is transported to the designated location, when designated as a pay item, or salvaged by the Department or local unit of government. The Contractor shall verify that the field identification placed by the Department has not been removed by vandalism or natural causes. If the Contractor has reason to believe that field identifications have been removed, the Department shall be contacted. The Contractor shall be responsible for all damage or loss of this equipment and shall repair or replace the damaged or lost equipment as directed. All signal equipment removed and not designated to be salvaged shall become the property of the Contractor and shall be disposed of in accordance with 202.

All existing painted metallic signal equipment to be reused, such as pedestals, bases, controller cabinets, signal weatherheads, pipe arms, shall be cleaned and painted with two coats of highway yellow enamel in accordance with 909.02(c). Existing metallic signal heads to be reused shall be painted with two coats of black or highway yellow enamel as directed by the Engineer and in accordance with 909.02(c). Aluminum poles and signal support structures shall not be painted.

Existing concrete foundations, which have not been used in the new installation, shall be removed to a minimum of 4 in. below the adjacent grade. The openings shall be filled with concrete and the surface finished and broomed, if they are located in sidewalk areas. Otherwise, they shall be filled with acceptable material conforming with the surrounding area.

Existing signal handholes to be removed, shall be filled after removing rings and covers, with B borrow with a minimum of 4 in. of concrete on top to bring it up to grade in a sidewalk area. Surfaces shall be finished and broomed. Otherwise, they shall be filled with acceptable material conforming with the surrounding area.

The signal controller timings will be provided and the Engineer shall be present when the signal intersection is to be placed in operation.

All electrical wiring terminations and splices; controller and cabinet set-up; and testing, review, and turn-on of all operational apparatus at each location shall be done by or in the presence of and under the responsible charge of an employee of the Contractor who holds an IMSA Traffic Signal Construction Technician Level II certification or an IMSA Traffic Signal Field Technician Level II certification. Installation inspections, troubleshooting, maintenance and repair of these systems

shall be accomplished by, or in the presence of and under the responsible charge of, an employee of the Contractor who holds an IMSA Traffic Signal Construction Technician Level II certification. Supervision of non-electrical, traffic signal related construction work and traffic control shall be done by a person holding, at a minimum, an IMSA Work Zone Temporary Traffic Control Technician certification or an equivalent certification approved by the Department.

120 Before starting work, the Contractor shall provide the names of the Level II Traffic Signal Construction Technicians, the Level II Traffic Signal Field Technicians, and Work Zone Temporary Traffic Control Technicians who have been assigned to perform signal related work, and a photocopy of each such person's certification card. If the Level II Traffic Signal Construction, or Field Technicians, or Work Zone Temporary Traffic Control Technicians are dismissed from the work, all signal related work requiring such certified personnel on the project site shall cease until the names and photocopies of certification cards for replacement personnel are provided to the Engineer.

130 Electrical work shall be executed in accordance with the requirements of the National Board of Fire Underwriters, the State Fire Marshal, and the power company which will furnish the electric service. The work shall be in accordance with any local regulations that may apply. The Department will arrange and provide for power service which the power company will bring to the point designated on the plans. Prior to the start of construction, the schedule of activities shall be coordinated with the power company and they shall be contacted again at least 14 days prior to the time the service work is to be completed.

140 The Department will obtain permits from local officials, companies, or individuals for the use of poles, right-of-way, or other property incidental to the installation of traffic signal. Although entering into the contract implies permission and authority to cut into and push under pavement, sidewalks, and alleys, any damage to underground utilities or interruption of such service shall be the responsibility of the Contractor. The Contractor shall be in accordance with local regulations as well as 107.08. Protective devices shall be in accordance with 107.12 and 801.

150 The location of signal heads, controllers, signal poles, signal cantilever structures, detector housing, disconnect hangers, and other installation items will be shown on the plans. However, a change in the location of an item may be ordered during the progress of the work. The work shall be completed as shown on the plans except for those changes specifically authorized in writing.

Flashing beacons shall flash at a rate for each beacon of 50 to 60 times per minute with the illuminated period from 1/2 to 2/3 of the total cycle. Second beacons, if specified, shall flash alternately with the exception of intersection control beacons which shall flash simultaneously.

805.04 Pole Installation

Working drawings for strain poles or cantilever structures shall be provided in

160 accordance with 105.02. Metal poles shall be erected on concrete foundations and shall be reasonably plumb after installation of signal heads. The handhole side of the pole shall be at right angles to the direction of the signal cantilever arm or span, catenary, and tether. Signal cables shall be brought up inside the poles. Any steel pole, signal cantilever arm, or hardware not galvanized shall be painted with structural steel coating system in accordance with 619.09(a). The surface shall be prepared in accordance with 619.08(a) and 619.08(d). Paint shall be applied in accordance with 619. All rust, scale, and dirt shall be cleaned from the metal surface so that paint adheres to the surface.

170 The construction of concrete foundations shall be in accordance with 805.13. Timber poles shall be set a minimum of 7 ft in the ground and raked 12 in.

170 **805.05 Placing Signal Heads**

180 Signal cantilever arm and span mounted signal heads shall have 17.5 ft minimum and 22.5 ft maximum clearance over the roadway unless there are visual obstructions which require lowering the signal head. A signal head over the roadway shall not have a clearance of less than 15 ft. Such signal heads shall be located over the intersection as shown on the plans. Such signal heads shall have a uniform clearance, which will be determined. Signal heads not mounted over a paved roadway, on the top or side of a pole, shall not be less than 10 ft or more than 15 ft above the sidewalk or, if none, above the pavement grade at the center of the roadway. Signal faces shall be directed to the proper approach lane in each direction. Flasher signal faces that supplement signs shall be mounted with the bottom of the housing at not less than 3 ft or more than 13 ft above the edge of pavement. Flasher signal faces that supplement signs shall be directed towards oncoming traffic. Pedestrian signal faces shall be mounted with the bottom of the housing at not less than 7 ft or more than 10 ft above the sidewalk. The pedestrian signal shall be in line with the pedestrian's vision at the appropriate crosswalk being used. Pedestrian push-buttons shall be mounted at a height of 3 1/2 to 4 ft above the sidewalk as shown on the plans. A pedestrian actuated signal sign shall be mounted immediately above the push-button.

190 Signal heads shall be assembled and wired with one conductor, Type THW, stranded wire. Where splices are made, a 2 ft minimum length of cable or wire in excess of that required for a continuous run shall be provided. Splices shall be twisted together and soldered or approved type connectors used. Each splice shall be completely insulated by wrapping with an approved tape and sealed with an approved electrical coating material. Splices shall be made in such manner that the connections are moisture proof. The cables coming out of the signal weatherhead shall be looped to form a drip loop. The drip loop shall be made so that the cables coming out of the weatherhead loop down below the elevation of the weatherhead to prevent water from following the cable into the weatherhead. If used, the splice indicated above shall be located in the top of the coils of cable forming the drip loop.

200 Except for signal heads installed on existing traffic signal cantilever structures, all overhead signal heads shall have backplates, unless otherwise indicated on the plans. Backplates shall not be cut or altered upon installation.

Signal heads shall not be installed until all other work has been completed. If it becomes necessary to mount signal heads for more than 2 h before the lights are to be turned on, the signal heads shall be hooded by placing sacks or similar cover over them so as to conceal them from traffic. Hooded signal heads are not allowed to be in place for more than five days. No signal head shall be left over night with the lights out unless it is hooded. Signal heads shall be securely mounted. The polycarbonate signal face shall be used only when securely supported on both ends of the assembly. In a span cable installation, a tether cable would satisfy this requirement.

210

When installing push buttons with accessible pedestrian signals, APS, features the Contractor shall verify that the audible tone is discernible from the mid-point of the crosswalk.

805.06 Grounding

All signal supports, signal controller supports, and entrance switches shall be grounded in accordance with the applicable requirements of 807.12.

220

805.07 Wire and Cable Installations

All cable runs attached to utility poles shall have code clearance relative to utility cables. They shall be no less than 18 ft above the ground level except over railroad tracks when a minimum of 27 ft clearance shall be maintained. All cable runs shall be installed in continuous lengths without splices between terminals except when necessary at handholes, junction boxes, pole signal bases, and pedestal bases. The type of cable and the number of conductors as well as the gauge shall be as shown on the plans unless otherwise specified.

230

Cable rings shall be used to support the signal cable on the signal span cable. They shall be spaced 12 in. on center. Cable shall be pulled through the conduit to the terminal panel in the controller cabinet. Caution shall be used to prevent damage to the cable when it is being pulled through conduit.

Coded cable conductors shall be used throughout the installation. Cable conductors shall be tagged at all detector housings, handholes, signal pole bases, and controller cabinets. At the ends of each cable, the tag shall be placed between 4 and 8 in. from the end of the wire and on the outer jacket. At all other locations, the tag shall be placed in the middle of the length of cable stored at the location. The tag shall be 1/2 in. wide, thermal printed black on yellow or black on white, polyester or nylon tape with permanent adhesive and shall be water, chemical and scratch resistant. The font shall be arial, size 10px. Tags shall be installed flag style around the cable with the backs of the tag ends placed together. Tags shall identify the cables by their use. The following are the uses which shall be indicated by the tags:

240

1. Power
2. Pedestrian Signal
3. Pedestrian Actuation

250

4. Signal
5. Detection Loop Identification
6. Interconnect.

Signal cables shall be tagged to identify the direction of travel. Detector lead-in cables shall be tagged throughout the installation with the corresponding loop tag information.

260 The tagging material and fastening **will be subject to approval** prior to proceeding with this work. The color coded wires shall be connected properly. The white wire shall be the common or ground. Wire used for all identical indications of any individual phase shall be color coded and, where possible, shall use red wire to connect red lenses, orange wire to connect yellow lenses, and green wire to connect green lenses. Signal heads shall be assembled and wired before being installed. The testing of the loops shall be documented in the Loop Testing Table provided by the State.

805.08 Controller Cabinet, Signal Service, and Detector Housing Installation

270 Three document packets shall be prepared in accordance with 922.02(b) for each cabinet. Each packet shall be labeled with the name of the contract number, the intersection, the commission number of the signal, and the date of installation. One paper packet shall be placed in the cabinet, one paper packet shall be submitted to the Engineer, and one electronic packet shall be submitted to the Asset Manager in the Department's Traffic Management Division within two days after the signal is turned on. Information in the packets shall include all approved changes to the signal installation. All detector loop lead-in tags and detector rack labels shall reflect all approved changes to the signal installation.

280 Additional detector loop amplifier units and detector racks shall be supplied as directed by the Engineer. Additional detector racks shall include all cables or harnesses including, but not limited to a SDLC cable for each added rack, interface panels and a BIU to provide a complete and functional installation. Additional auxiliary BIU panels shall include all cables or harnesses including, but not limited to a SDLC cable for each additional auxiliary BIU panel, terminal strip on BIU panel and BIU to provide a complete and functional installation.

290 For signal cabinets installed by the Contractor, where no detector loop or lead-in work is included in the contract, the Contractor shall perform detector loop tagging, testing, and vehicle simulator testing in accordance with 805.09, only to the extent of documenting the test readings and confirming that all existing detector loops are connected correctly and all detector related equipment in the cabinet is operating correctly.

The controller cabinet shall be mounted securely on a pole, pedestal, or concrete foundation. All cabinets on concrete foundations shall be installed with the anchor bolts inside. Controller cabinets on poles or pedestals shall be mounted at a height of

38 in. \pm 2 in. Pole mounted controller cabinets shall be fastened with two stainless steel bands as shown on the plans. Signal cables and lead-in cable shall be run in conduit from the controller cabinet to the signal support base and to detector housing as indicated on the plans. Galvanized steel elbows shall be used on the detector housing as shown on the plans.

The Contractor shall wire the entrance switch and bring service cable up the riser and out the weatherhead and leave 4 ft of cable outside the weatherhead. The utility company, at their option, may bring the service cables to the load side of the entrance switch. Meter bases, if required, shall be obtained from the power company.

A minimum of 12 in. and a maximum of 18 in. of loop wire duct will be allowed in the detector housing for each loop lead. Concrete used in the installation of detector housings shall be in accordance with 506.04(a), except 506.05 will not apply and calcium chloride shall not be used. A CMDS in accordance with 506.03 shall be submitted, however, utilization of the Department provided spreadsheet is not required. Where a portion of the road is closed or where there is no vehicular traffic, then class A concrete in accordance with 702 may be used. The concrete shall be placed flush with existing surface and shall be covered with a steel plate during the setting time.

805.09 Loop Wire Detector Installation

This work shall consist of placement and testing of loop wire detectors in accordance with the installation details shown on the plans.

(a) Layout

The number, size, arrangement, and locations of loops shall be as shown on the plans except that loop spacing shall be adjusted to avoid PCCP joints. Loops shall be of a regular octagon shape with sides of 2 1/2 ft in length or a circular shape with a diameter of 6 ft. Loops placed longitudinally adjacent in the same lane shall be spaced 15 ft from the center of one loop to the center of the next loop. Loops shall be arranged so that no loop wire will be bent at an angle less than 120°. Regardless of configuration, the loop installation shall match the intention of the loop tagging table.

Prior to installation, loop layout shall be approved in writing by the District Traffic Engineer. The Contractor shall notify the District Traffic Engineer a minimum of two business days prior to the date that loop layout approval is required. All roadway centerlines, edge-lines and stop-bars pertinent to loop layout shall be accurately and clearly identified at the time loop layouts are reviewed for approval. An outline shall be painted where the loops are to be placed. The Contractor shall ensure that the final installed location of each loop matches the intention and functionality of the approved layout for loop spacing, lane width and geometry.

(b) Installation

All loops and lead-in cables shall be tagged according to the plans and 805.07.

The slots shall be saw cut as shown on the plans. A diamond cutting blade shall be used for sawing all loops. All saw-cut loops shall have individual saw cuts to the detector housing. Joints shall be overlapped such that the saw cut at the corner is full depth. Prior to installing roadway loop wire in the roadway saw-cuts, the saw-cuts shall be cleaned in accordance with the manufacturer's requirements for the joint sealant to be used. After proper cleaning, the loop wire shall be installed. All loops shall be wired clockwise as viewed from above. Loops shall be wired with four turns
 350 or as specified then gently tamped with a blunt non-metallic tool. Backer rod 2 to 4 in. in length shall be spaced every 12 in. around the saw-cut above the wire and gently tamped to hold the loop wire snug in the bottom of the saw-cut. Backer rod shall not be continuous around the saw-cut.

After installation of the loop wire, the saw-cut shall be sealed with a joint sealant material. The sealant shall be poured into the saw-cut making a water tight seal. The joint sealant material shall be installed in accordance with the manufacturer's recommendations and 906.02. However, the joint configuration shall not apply. A copy of the sealant manufacturer's written application instructions shall be submitted
 360 to the Engineer prior to any sealant operations. If the Contractor elects to use a sealant complying with 906.02(a)2, the sealant material shall be heated in a kettle or melter constructed as a double boiler with the space between the inner and outer shells filled with oil or other heat-transfer medium. This melter shall have a positive temperature control and a mechanical agitator.

A backer rod shall be used for both cold applied sealants and hot poured sealants. The sealant material shall fill the saw-cut as shown on the plans. All excess joint sealant on the pavement surfaces shall be promptly removed.

370 The black lead-in wire shall be spliced to the loop wire which goes back to the field. Such wire shall be tagged as "Out/Loop (No.)". The white lead-in wire shall be spliced to the loop wire which comes in from the field. Such wire shall be tagged as "In/Loop (No.)".

(c) Splices

For each loop cable and lead-in cable entering a handhole, there shall be 6 ft of cable jacket remaining on each wire after the splice is complete. For each loop cable and lead-in cable entering a detector housing, there shall be 2 ft of cable jacket remaining on each wire after the splice is complete.
 380

For all loop splices, there shall be a maximum of 1/2 in. of non-jacketed wire measured from the end of each cable jacket to the edge of the splice waterproofing material. The splice of the loop wire and lead-in cable shall be soldered and waterproofed at the detector housing or handhole. Waterproofing shall consist of the use of heat shrink tubing which has an internal coating sealant material. The heat shrink tubing shall not be heated by means of a direct flame tool.

(d) Testing and Acceptance

All testing and acceptance procedures performed by the Contractor shall be

390 performed in the presence of the Department personnel assigned by the Engineer. The Contractor shall notify the Engineer a minimum of two business days prior to the date testing is to be performed.

The Contractor shall meter all new loop wire detectors or a new bank of loop wire detectors by means of instruments capable of measuring electrical values for installed loop wires and lead-in cables. The instruments shall measure inductance in microhenries, resistance in ohms, induced AC voltage in volts, and leakage resistance in megohms. All measuring tests shall be performed at the detector housing before the loop wire is spliced to the lead-in cable, and at the cabinet after the loop wire is spliced
400 to the lead-in cable.

1. Electrical Testing

a. Megohm Test Before Splice is Made at Detector Housing for Loop Wire

One of the megohm probes shall be connected to ground and the other probe shall be connected to the “in” or “out” loop wire. The remaining loop wire shall be isolated. The test shall then be performed.

410 b. Megohm Test Before Splice is Made at Detector Housing for Lead-in Cable

The two wires and shield of the lead-in cable at the cabinet shall be isolated and taped. The test shall consist of recording four readings taken at the detector housing or handhole as follows:

- (1) Connect the first megohm probe to ground and the second probe to the shield. Record the reading.
- 420 (2) Connect the first megohm probe to the first lead-in wire and the second probe to the shield. Record the reading.
- (3) Connect the first megohm probe to the second lead-in wire and the second probe to the shield. Record the reading.
- (4) Connect the first megohm probe to the first lead-in wire and the second probe to the second lead-in wire. Record the reading.

430 The lowest of the four readings taken above shall be recorded on the testing document for acceptance.

c. Megohm Test After Splice is Completed at Cabinet

This test shall be performed after the splice at the detector housing is completed. A water solution of one tablespoon of baking soda per pint of water shall be placed in

a metal container. The metal container shall be grounded and the splice shall be fully submerged in the solution for 2 minutes. With the splice submerged, the shield of the lead-in shall be connected to ground at the cabinet. One megohm probe shall then be connected to ground and the other probe connected to one of the lead-in wires and the reading recorded.

2. Delay Amplifier Settings and Vehicle Simulator Test

After all detector loop testing is complete, the detector amplifiers shall be installed and settings adjusted for proper operation at the intersection.

The frequency setting shall be adjusted using the amplifier's display so that adjacent loops in the roadway that are connected to different loop amplifiers have a minimum difference of 5 kHz. This operating frequency setting does not apply to loops that are adjacent to each other in the roadway but are connected to the same loop amplifier.

The sensitivity setting shall be adjusted using the amplifier's display. With an average size front wheel drive vehicle with the front axle centered over the back loop of a series of loops, the sensitivity shall be adjusted in accordance with the manufacturer's recommendations.

The count output shall be enabled for all loops designated as counting loops. The number of loops setting shall be set for loops designated for counting purposes and shall be set to the number of loops connected to that loop amplifier.

This test shall be performed by dragging a test vehicle across the loops using a non-conducting string. The test vehicle shall be fabricated with an 8 ft length of No. 6 bare copper wire formed into a 2 1/2 ft diameter circle. The two ends shall then be electrically spliced.

The test shall be started with all detector amplifiers turned 'Off' except for one approach. All amplifiers for that approach shall be turned 'On' and adjusted to the proper settings. All traffic for the approach being tested shall be stopped and not allowed to cross any loops during the test procedure for that approach. The simulator shall be dragged slowly across each loop system in the same direction as to simulate a vehicle driving through the loop system. As the simulator crosses each loop an IMSA level II certified Signal Technician shall verify that a call is displayed exclusively on the corresponding loop amplifier, controller detector input and controller phases. After completely verifying the loops on the first approach the amplifiers shall be left 'On', and the amplifiers for the next approach to be tested shall be turned 'On' and adjusted to the proper settings. The same procedure shall be followed for each remaining approach.

With large intersections, as the test proceeds, it may become difficult to verify that the calls are going to the correct detector inputs. In this case, traffic control shall be used to stop vehicles before reaching the loops for as many approaches as needed

to accurately complete the testing to the inspector's approval. Testing may be paused between lanes to allow traffic to clear.

3. Acceptance Criteria

The Contractor shall record all test readings, in triplicate, on tabular forms provided by the Department or by copying the one included elsewhere herein. The Contractor shall complete, sign, and date the forms before submitting them to the District Traffic Engineer. The District Traffic Engineer will use these forms for recording the Department's readings on the corresponding space provided.

In order for the loop detector installation to be accepted, the electrical values shall be as follows:

- a. Inductance shall be between 80 and 800 μ H. Inductance shall be determined by means of digital readout meter which drives the field loop system.
- b. Resistance shall be less than or equal to 8 ohms.
- c. Induced AC voltage shall be less than or equal to 3 volt.
- d. Leakage resistance shall be greater than 100 megohms.

Loop wire or lead-in cable failing to meet this requirement shall be replaced at no cost to the Department.

805.10 Other Vehicle Detection Systems

When required, the Contractor shall furnish and install an alternative vehicle detection system from the QPL of Traffic Signal and ITS Devices.

805.11 Steel Conduit

Conduit shall be installed to a depth of no less than 2 ft or more than 5 ft below the finished grade unless otherwise specified or approved. Pockets or traps where moisture might accumulate shall be avoided. Conduit shall be placed under existing pavement by approved jacking or drilling methods. Pavement shall not be disturbed unless otherwise specified. If specified, cuts in pavement areas shall be no greater than 24 in. wide. All cuts in the pavement and sidewalk areas shall be sawed. Sidewalk removal and replacement shall be to the nearest tooled joint. Jacking and drilling pits shall be kept at least 2 ft clear of the edge of any type of pavement or paved shoulder. Excessive use of water that may cause undermining of the pavement shall be avoided. Continuous conduit runs shall not exceed 200 ft in length, unless otherwise shown on the plans.

Expansion fittings as detailed on structure plans shall be installed where conduit crosses an expansion joint in the structure. Where it is deemed inadvisable to install expansion fittings in closely confined areas, the installation of approved flexible tubing

530 may be allowed. Such expansion joints or tubing shall be the same size as the conduit. Any existing underground conduit to be incorporated into a new signal installation shall be cleaned with a mandrel and blown out with compressed air before cable is drawn into pipe. All new conduit runs shall be cleaned and swabbed before cables are installed. All conduit ends shall be capped and shall remain capped until the Contractor is ready to pull cable into the conduit, at which time the caps shall be removed and conduit bushings placed on each end to protect the cable. The inside surface of the conduit shall be kept clean. Conduit to be installed, indicated on the plans for future use of signal cables, shall be left in place with a pull cord on its entire length.

540 Larger size conduit may be used with no additional payment, but when it is used, it shall be for the entire length of the run from outlet to outlet. Conduit runs as shown on the plans are for bidding purposes only and may be changed, with permission, to avoid underground obstructions. A change order may be authorized if the conduit runs can be made on the opposite side of the street to that shown on the plans in order to avoid obstruction and traffic inconvenience or to avoid unnecessary tearing up of existing pavement.

805.12 PVC, HDPE, and Fiberglass Conduit

550 The method of installing PVC, HDPE and rigid fiberglass conduit underground shall be the same as for steel conduit where applicable except trenches for the conduit in areas with class X material as described in 206.02 shall be backfilled with 2 in. of natural sand before the conduit is placed in the trench. Materials excavated may be used for backfill, if approved. If the Engineer deems it necessary, approved B borrow shall be placed over the conduit to a depth of 12 in. and the remainder of the trench shall be filled with excavated material.

560 Schedule 40 or 80 PVC, Schedule 40 HDPE, or rigid fiberglass conduit may be used for conduit placed in trenches with expansion fittings used every 200 ft unless otherwise indicated on the plans. Schedule 80 HDPE, or steel shall be used for conduit that is jacked or bored. Schedule 80 PVC or rigid fiberglass shall be used for conduit on bridges or other structures. A No. 6 AWG copper or No. 14 AWG aluminum ground wire shall be included in all PVC, HDPE, and rigid fiberglass conduit.

805.13 Foundations

570 Foundations for traffic signal structures, cabinets, and pedestals of the type specified shall be constructed, or existing M foundations shall be modified, as shown on the plans or as directed. Pedestal bases shall be plumb and firmly attached to the anchor bolts either by using leveling nuts or shims if top of the foundation is not level. Grouting shall be used when necessary to fill any gap between pedestal base and foundation. Pipe pedestals shall be screwed tightly into the bases and secured with a stainless steel pin. Power and signal cables shall then be pulled from the base into the cabinet. Curing of concrete shall be in accordance with 702.22.

The foundation concrete for traffic signal cantilever structures shall be placed monolithically and shall have no construction joint. Structure bases shall be plumb and

attached to the anchor bolts using leveling nuts. A tooled line or other type of permanent marking shall be provided on the top of the foundation to indicate the direction of the conduits.

580 During excavation of the foundation, all material shall be removed to the full depth as shown on the plans, except if class X material is encountered, the work shall be performed in accordance with 206.02(b).

805.14 Final Clean-Up

When the installation is completed, all disturbed portions of sidewalk, pavement, shoulders, driveways, and sod, shall be cleaned and any excess excavation or other materials shall be disposed. All cutting in the sidewalk and pavement areas shall be done with a saw. Sidewalk removal and replacement shall be to the nearest tool joint. Unless otherwise directed, cuts in pavement areas shall be no greater than 12 in. in width.

590 Within 30 calendar days after completion of the work, as-built drawings shall be submitted in electronic format to the Engineer. The signal as-built drawings shall indicate the as-built location of steel strain poles, signal cantilevers, service points, controller cabinet, loop detectors, conduit runs, and signal handholes.

805.15 Method of Measurement

600 Controller and cabinet; controller cabinet foundation; disconnect hanger; handhole, signal; loop detector delay amplifier; loop detector rack; pedestrian push button; pedestrian signal head; signal cantilever structure, combination arm; signal cantilever structure, drilled shaft foundation type; signal cantilever structure, dual arm; signal cantilever structure, single arm; signal cantilever structure, single arm, combination arm; signal cantilever structure, spread footing foundation type; signal detector housing; signal pole; signal pole foundation; signal service; span catenary and tether; traffic signal head; and traffic signal head, retrofit; will be measured by the number of units installed.

The pay length for a signal cantilever arm or combination arm will be the length shown in the Schedule of Pay Items.

610 Conduit of the type specified will be measured by the linear foot from outside to outside of foundations. All signal cable will be measured by the linear foot.

Saw-cut for roadway loop detector and sealant will be measured by the linear foot for the full depth of slot cut in the pavement as shown on the plans or as directed.

If class X material is encountered during foundation excavation, measurement will be made in accordance with 206.10.

Traffic signal installation, flasher installation, miscellaneous equipment for traffic signals, and final cleanup in accordance with 805.14 will not be measured for payment.

620 Reinforcing bars will not be measured for payment.

Traffic signal equipment removal will be measured per each installation to be removed. Transportation of salvageable signal equipment will not be measured.

805.16 Basis of Payment

Traffic signal installation and flasher installation, all of the type, new or modernized, and the location number specified, will be paid for at a contract lump sum price.

630 If specified as pay items, controller and cabinet; controller cabinet foundation; disconnect hanger; handhole, signal; loop detector delay amplifier; loop detector rack; pedestrian push button; pedestrian signal head; signal cantilever structure, single arm; signal cantilever structure, combination arm; signal cantilever structure, single arm, combination arm; signal cantilever structure, dual arm; signal cantilever structure, drilled shaft foundation type; signal cantilever structure, spread footing foundation type; signal detector housing; signal pole; signal pole foundation; signal service; span catenary and tether; traffic signal head; and traffic signal head, retrofit; will be paid for at the contract unit price per each.

640 Conduit of the type specified will be paid for at the contract unit price per linear foot. The cost of any backfill, ground wire, or expansion fittings shall be included in the cost of conduit.

Saw-cut for roadway loop detector and sealant, and signal cable will be paid for at the contract unit price per linear foot.

650 The removal of existing traffic signal equipment designated to be removed will be paid for at the contract unit price per each for traffic signal equipment, remove for each location removed. When designated as a pay item, the transportation of salvageable signal equipment will be paid for at the contract lump sum price for transportation of salvageable signal equipment.

Class X excavation will be paid for in accordance with 206.11.

Miscellaneous equipment for traffic signals will be paid for at a contract lump sum price.

Payment will be made under:

660	Pay Item	Pay Unit Symbol
	Conduit, _____ type	LFT
	Controller and Cabinet, _____ type	EACH

	Controller Cabinet Foundation, _____	EACH
		type	
	Disconnect Hanger		EACH
670	Flasher Installation, _____,	Location No. _____	LS
		type	
	Handhole, Signal, _____	EACH
		type	
	Loop Detector Delay Amplifier, _____,	_____ Channel.....	EACH
		type no.	
	Loop Detector Rack.....		EACH
	Miscellaneous Equipment for Traffic Signals		LS
	Pedestrian Push Button, _____	EACH
		type	
680	Pedestrian Signal Head, _____,	_____	EACH
		type lens size	
	Saw-Cut for Roadway Loop Detector and Sealant.....		LFT
	Signal Cable, _____, Copper, _____	C/ _____	LFT
		type conductors/size	
	Signal Cantilever Structure, Combination Arm _____	ft	EACH
		length	
	Signal Cantilever Structure, Drilled Shaft Foundation, _____	EACH
		type	
	Signal Cantilever Structure, Dual Arm _____	ft, _____	EACH
690		length length	
	Signal Cantilever Structure, Single Arm _____	ft,	
		length	
	Combination Arm _____	ft.....	EACH
		length	
	Signal Cantilever Structure, Single Arm _____	ft.....	EACH
		length	
	Signal Cantilever Structure, Spread Footing		
	Foundation, _____	EACH
		type	
700	Signal Detector Housing.....		EACH
	Signal Pole Foundation, _____	in. x _____	in. x _____
		in.....	EACH
	Signal Pole, _____,	_____	ft
		type length	EACH
	Signal Service.....		EACH
	Span, Catenary, and Tether		EACH
	Traffic Signal Equipment, Remove		EACH
	Traffic Signal Head, _____	Section, Retrofit	EACH
		no.	
	Traffic Signal Head, _____,	Section, _____
710		no. lens size	EACH
	Traffic Signal Installation, _____,	Location No. _____	LS
		type	

Transportation of Salvageable Signal Equipment LS

The cost of the controller and cabinet, conduit, foundations, vehicle detection, pedestrian signals, signal heads, signal poles, signal service, signal cable and all equipment or materials required to complete the installation shall be included in the cost of traffic signal installation.

720 The cost of the controller and cabinet, conduit, foundations, signal heads, signal poles, signal service, signal cable and all equipment or materials required to complete the installation shall be included in the cost of flasher installation. For a solar powered flasher, the cost of the solar panel, battery cabinet, program timing module, signal heads, wiring, and all hardware required to complete the installation shall be included in the cost of flasher installation.

The cost of the controller assembly, standard loop detector racks, all wiring, hardware, and associated equipment required to operate the intersection shall be included in the cost of controller and cabinet.

730 The cost of concrete, conduits, grounding bushings, ground rod, ground wire, drainage, anchor bolts, and all hardware required to complete the installation shall be included in the cost of controller cabinet foundation.

The cost of all work and hardware required to properly install loop detector delay amplifier, counting or non-counting, as shown on the plans or as directed shall be included in the cost of loop detector delay amplifier.

740 The cost of concrete reinforcing pipe and ring or polymer concrete box, cover and attachment hardware, handhole bottom if required, and aggregate as shown on the plans shall be included in the cost of handhole, signal.

The cost of any supplementary loop detector rack, all wiring, hardware, detector panel, BIU, and associated equipment shall be included in the cost of the loop detector rack.

The cost of the push button, pedestrian actuated signal sign, any accessible pedestrian signal components, and all hardware required to complete the installation shall be included in the cost of pedestrian push button.

750 The cost of signal face hook-up wire, pole plates and arms for side mounts, pipe arms, signal brackets, bulbs, weatherhead, and all additional hardware required to assemble a combination of pedestrian signal indications as shown on the plans shall be included in the cost of pedestrian signal head.

The cost of the slot cut on the pavement, backer rod, loop sealant, and all testing in accordance with 805.09 shall be included in the cost of saw-cut for roadway loop and sealant.

760 The cost of all work and hardware required to properly install overhead or underground signal cable, signal, fiber optic, or interconnect, as shown on the plans or as directed shall be included in the cost of signal cable.

The cost of signal pole section 2 and combination arm, all hardware including the metal skirt base plate, where necessary, to complete the installation as shown on the plans shall be included in the cost of the signal cantilever structure, combination arm.

770 The cost of concrete, reinforcing bars, conduits, ground rod, ground wire, grounding bushings, anchor rods, and all hardware required to complete the installation of the drilled shaft or spread footing foundation for signals shall be included in the cost of signal cantilever structure, drilled shaft or spread footing foundation.

The cost of signal pole and dual arms, all hardware including the metal skirt base plate, where necessary, to complete the installation as shown on the plans shall be included in the cost of the signal cantilever structure, dual arm.

780 The cost of signal pole section 1 and single arm, all hardware including the metal skirt base plate, where necessary, to complete the installation as shown on the plans shall be included in the cost of the signal cantilever structure, single arm.

The cost of signal pole section 1, 2 and single arm, combination arm, all hardware including the metal skirt base plate, where necessary, to complete the installation as shown on the plans shall be included in the cost of the signal cantilever structure, single arm, combination arm, when structure with single arm and combination arm is required in the same contract.

790 The cost of aluminum casting, enclosure concrete, conduit and elbow, and all hardware required to complete the installation shall be included in the cost of signal detector housing.

For a steel signal pole, the cost of the base plate, metal skirt base plate, handhole and cover grounding lug, 2 in. pipe cable entrance, J hook, and top cover as shown on the plans shall be included in the cost of signal pole.

For a timber signal pole, the cost of downguys, anchor rods, downguy guards, and hub-eyes as shown on the plans, and all hardware required to complete the installation shall be included in the cost of signal pole.

800 For a signal pedestal, the cost of the pedestal metal base, pedestal pole, pole cap, and all hardware required to complete the installation shall be included in the cost of signal pole.

The cost of concrete, reinforcing bars, conduits, ground rod, ground wire, grounding bushings, anchor rods, and all hardware required to complete the installation of the signal pole foundation shall be included in the cost of signal pole foundation.

810 The cost of weatherhead, 1 in. conduit riser, entrance switch, 1 to 2 in. conduit reducer, ground rod, ground wire, and all hardware required to complete the installation, including the meter base when required and supplied by the utility company shall be included in the cost of signal service.

The cost of steel pole bands or straight eye bolts, span, catenary, and tether of wire rope cables, cable rings, Type A support cable, wire rope clips, safety cable, thimble, service sleeve, and all hardware required to complete the installation as shown on the plans shall be included in the cost of span, catenary, and tether.

820 The cost of signal face hook-up wire, pole plates and arms for side mounts, mid-mast arm mount, pipe arms, signal brackets, visors, louvers, bulbs, span hanger, backplates, balance adjuster, weatherhead, and all additional hardware required to assemble a combination of signal faces as shown on the plans shall be included in the cost of traffic signal head.

The cost of removing the existing traffic signal head, salvaging the existing LED indicators, replacing the existing signal head with a new housing and backplate, and reinstalling shall be included in the cost of traffic signal head, retrofit.

830 The cost to repair or replace damaged or lost salvageable traffic signal equipment shall be at no additional cost to the Department.

The cost of excavation, backfill, final cleanup in accordance with 805.14, the cost of re-painting existing metallic equipment to be re-used, the preparation and transmittal of as-built drawings and controller assembly document packets, and necessary incidentals shall be included in the cost of the pay items in this section.

SECTION 806 – BLANK

SECTION 807 – HIGHWAY ILLUMINATION

807.01 Description

This work shall consist of installing wire, cable, conduit, lighting standards, luminaires, lamps, and incidental materials in accordance with 105.03.

Lighting installations shall be in accordance with the National Electrical Code and the National Safety Code.

MATERIALS**807.02 Materials**

Materials shall be in accordance with the following:

	Casting for Handholes	922.17(a)
	Coarse Aggregate, Class D or Higher, Size No. 53	904.03
	Concrete, Class A	702
	Conduit	922.19
	Highway Illumination Materials.....	920.01
20	Line Hardware	922.10(e)1
	Paint.....	909
	Reinforced Concrete Pipe.....	907.02
	Reinforcing Bars.....	910.01

Manufacturers' descriptive and technical literature for major items shall be submitted for approval. Where it is normal trade practice to furnish a warranty, a warranty shall be furnished on all major items such as luminaires, lamps, poles, brackets, cable-duct, wire and cable, fuse connectors, and ballasts. The effective date of the warranty shall commence on the date of final acceptance. These items shall bear the seal of approval of the UL.

All flexible conduit shall be galvanized steel, polyvinyl jacketed, and watertight.

Reinforcing bars shall be epoxy coated.

CONSTRUCTION REQUIREMENTS

Existing highway illumination shall be maintained on all projects unless discontinuance of the highway illumination is specifically allowed.

807.03 Working Drawings

Working drawings shall be submitted in accordance with 105.02 for light pole assemblies, luminaires, and external drive assemblies.

Working drawings for each luminaire model submitted shall include the luminaire specifications and data sheets.

For contracts not utilizing the QPL for Luminaires, working drawings for luminaires shall also include the Illumination Engineering Society of North America, IESNA, photometric distribution file if the file number varies from what is shown on the plans. The IESNA photometric distribution file shall be in either Visual, developed by Acuity Brands Lighting, or AGi32 from Lighting Analysis, Inc.

Working drawings for conventional light pole shall show the outside shaft diameter, height, wall thickness, mast arm length and rise, mast arm diameter and

thickness, handhole details, grinding details, materials required, and complete anchor-bolt details including bolt circle-projection and hardware. If a breakaway base is required, its details shall be shown.

- 60 When requested, sufficient design data shall be furnished with the drawings to verify that conventional light pole is in accordance with wind load, deflection, vibration, and breakaway requirements. All of the above shall be based on the light pole details shown on the plans. After approval, the Engineer shall be advised of where changes to the Installation Summary sheets are being made because of existing roadside conditions. Where necessary, additional light pole working drawings shall be submitted for approval.

- 70 If a light pole is designed to support a larger luminaire than that specified, such information shall be shown on the working drawings. A Type C certification in accordance with 916 shall be provided for the breakaway devices certifying that the breakaway devices are in accordance with the breakaway criteria of the AASHTO Standard Specifications for Structural Supports for Highway Signs, Luminaires, and Traffic Signals.

Working drawings for high mast towers shall show the pole height, number of sections, the pole shaft data for each section, luminaire lowering ring assembly, handhole details, materials required, welding details, and complete anchor bolt details including bolt circle-projection and hardware.

- 80 If the high mast is a non-standard design, the following design calculations and data shall be submitted for approval prior to the fabrication of a high-mast pole:
- (a) general dimensions of all component parts,
 - (b) the maximum moments, the section modulus required, and the section modulus furnished at the base of the pole, at all splices, at the connection of the ring, and at least every 20 ft,
 - 90 (c) calculation of stresses in the base plate, connection attachment, and anchor bolts,
 - (d) maximum deflection at the top of the structure under the specified loading,
 - (e) the dimensions and wiring diagrams of the external drive system connection to the pole in accordance with 920.01(b)7.

100 The working drawings shall include the dimensions and wiring diagram of the standard connections of the external drive system.

807.04 Excavation

All excavation for the roadway lighting installation shall be performed in

accordance with the dimensions, elevations, and grades shown on the plans or as directed. If class X material is encountered, foundation excavation shall be completed in accordance with 206.

(a) Trench Excavation

Excavation may be accomplished either manually or with mechanical trenching equipment. The blades of road patrols or graders shall not be used to excavate the
 110 trenches. The depth of trenches shall be a minimum of 2 ft. Walls of trenches for cable-
 duct or conduit shall be essentially vertical. The bottoms of trenches shall be smooth
 and free from aggregate larger than 1/2 in. Bracing, shoring, and sheathing shall be
 provided as necessary. If the excavation, through accident or otherwise, is below the
 required level, the excess excavated area shall be refilled in a satisfactory manner with
 no additional payment. The accumulation of water in excavated areas shall be
 prevented by the use of pumps or other approved means. When rocks or other materials
 which might damage the cable-duct or conduit are encountered, the excavation shall
 be extended to a depth of at least 27 in. and backfilled with a 3 in. compacted layer of
 sand or earth containing no particles that would be retained on a 1/4 in. sieve. No extra
 120 payment will be made for this additional excavation or backfill.

(b) Foundation Excavation

If possible, excavation for concrete foundations shall be accomplished by means
 of drilling with an auger of sufficient size to admit the width of the foundation. Work
 shall be so scheduled that all open excavations are poured with concrete during the
 work day they are dug. No excavations shall remain open over night or over a weekend
 or holiday. Accumulated water shall be removed from the excavation before concrete
 is poured. If class X material is encountered, foundation excavation shall be completed
 in accordance with 206.02(b).
 130

(c) Landscape Replacement

Where roadside shrub plantings interfere with the location of illumination
 installations, the plantings shall be reset at other locations and at such times as directed,
 all in accordance with 622. The cost of this work will not be paid for directly, but shall
 be included in the cost of other pay items.

All slopes for foundation grading shall be sodded. Sod shall be placed in
 accordance with 621.

140 807.05 Backfilling

All suitable materials removed from the excavated areas shall be used in refilling
 cable-duct and conduit trenches. No excavated materials shall be wasted without
 authorization. Materials authorized to be wasted shall be disposed of as approved.
 Backfill for trenches shall be placed in layers not to exceed 6 in., loose measurement.
 The first layer shall be sand or earth containing no particles or lumps that would be
 retained on a 1/4 in. sieve. The second layer shall contain no particles or lumps that
 would be retained on a 1 in. sieve. Subsequent layers shall contain no particles or
 lumps that would be retained on a 3 in. sieve. The second layer and each subsequent

150 layer shall be compacted with pneumatic hand-tampers to prevent any future settlement of the backfilled area. Backfilling of cable-duct and conduit trenches around light pole foundations, handholes, manholes, and other structures shall be in accordance with the applicable provisions of 211. Finish grading of earthwork shall be accomplished in a satisfactory manner.

807.06 Placing Conduit

Conduit shall be placed as shown on the plans and in accordance with applicable provisions of 805.11. Conduit shall be of a size to readily enable the passage of the cable-duct being used.

160 Conduit installed under pavement shall extend a minimum of 2 ft beyond the edge of the paved surface or improved shoulder. The ends of such conduit shall terminate a nominal 2 ft below the ground surface. The ends shall be pitched so as to provide a positive drain to the surrounding soil. The ends shall be protected by threaded cap fittings until the time of installation of cable or cable-duct. Threaded bushing fittings shall be used on all ends before cable installation.

170 Conduits installed in bridge railing concrete sections shall terminate a minimum of 2 ft beyond the end of the bridge railing outside of the paved surface and a minimum of 2 ft under the ground surface. Existing conduit shall be extended as necessary to satisfy these requirements.

Hot dipped galvanized, malleable pipe straps and spacers shall be used to attach conduit to bridge structures. Galvanized steel conduit hangers or pipe clamps will not be allowed. Pipe straps of the proper size shall be installed 4 ft center to center along the conduit. When fastening pipe straps to concrete, a 3/8 in. by 2 1/2 in. galvanized steel lag screw, with an approved sleeve, shall be used; however, other approved expansion anchors may be used. The pipe strap and spacer shall be bolted to the steel beams.

180 Conduit for service supply shall be mounted on a service pole, either company or State owned, near the right-of-way line. For simple supply circuits, one straight, continuous, conduit riser shall be used. The top end shall terminate with a weatherhead device, and the lower end shall terminate at least 2 ft below ground level with a threaded grounding bushing fitting. Unless otherwise directed, the weatherhead shall be 24 ft above the ground. However, the actual elevation of the weatherhead shall meet the requirements of the utility concerned.

807.07 Connections in Base of Light Pole

190 Conductors shall be electrically bonded to each other, as required to satisfy circuit requirements, by means of compression type fittings of the style and type shown on the plans. Inhibitor compound shall be used on each compression connection. Conductor identification shall be maintained by connecting like color connectors.

A multiple conductor compression fitting shall be used to connect supply conductors and an insulating link used to provide an extension as shown on the plans. These fittings shall be covered with snap-on fiber or plastic covers designed to protect them from electrical contact. Taping will not be allowed. The bare extension of the supply conductor from the multiple fitting to the insulation link shall be no longer than necessary to admit the application of the snap-on cover for the multiple fitting.

200

The pole circuits shall be connected by means of easily separated, single conductor connector kits. The connector kit on the “hot” side of the pole circuit shall be fused. The connector kit for the neutral side shall not be fused. Fuses shall be of the “KTK-10” series with a rated capacity three times the operating amperage of the luminaire. If the required capacity is not a standard size, the next larger size fuse shall be used.

The connector kit on the “hot” side of the pole circuit shall have the following features:

210

(a) a line side and load side housing made of plastic or water resisting synthetic rubber suitable for direct burial in the ground or installation in sunlight,

(b) a water seal between the two housings,

(c) each housing permanently marked “Line Side” or “Load Side”,

220

(d) a spring-loaded, 90% minimum conductivity, contact suitable for gripping the “KTK-10” cartridge fuse in each housing. These contacts shall be fully annealed,

(e) an interior arrangement for each housing that will adequately receive and rigidly maintain the fuse contacts,

(f) a terminal on each housing designed for a crimp type connection to the conductor that securely retains the conductor in the proper position,

230

(g) a water seal between the conductor and the housing,

(h) a disconnecting means that shall retain the fuse on the load side when disconnected and keep the conductive parts of the line side inaccessible,

(i) sufficient silicone compound provided and used to lubricate the metal parts and the rubber housings or boots for easy assembly.

240 The neutral side connector kit shall be similar in all respects to that described for
the hot side except that a dummy fuse shall be used for the purpose of completing the
electrical circuit. The bayonet disconnect feature of the connector kits shall be part of
the load side of both the neutral side and the hot side conductors. The line side shall
have a socket to receive the bayonet. These kits shall be installed in the pole circuit
between the luminaire terminals and the compression connection to the underground
distribution circuit as shown on the plans. A separate insulated conductor shall be used
to connect the neutral of the underground distribution circuit and the neutral of the
pole circuit to the ground lug in the pole base from the point at which both neutrals are
connected together by a compression connection. The bayonet disconnect features
from the neutral side and the hot side connector kits as cited above shall be included
250 in the sign structure circuitry when luminaires are installed on the sign structures.
Consecutive roadway luminaires in a circuit shall be alternately connected to opposite
load conductors R or B as specified in the plans to balance the load. Sign luminaires
on individual structures shall be similarly connected.

807.08 Placing Wire and Cable

(a) Underground

260 All underground distribution conductors shall be continuous runs between splice
points. Unless otherwise authorized, splice points shall be inside the bases of light
poles, inside handholes, in service distribution boxes, at point of connection to power
supply in switch boxes, or in junction boxes. All splices shall be made with the proper
connector in accordance with 807.07.

1. Through Cable-duct in Trench

Cable-duct shall be placed either in a trench or plowed into place. Cable-duct shall
be installed without sharp bends or kinks and in straight runs so as to enable
withdrawal of a conductor and the installation of new conductor without additional
excavation or backfill.

270 Plowed cable-duct shall be installed at a minimum depth of 2 ft in a single cavity
gored into the earth by a vibrating plow blade. The equipment used for plowing the
cable-duct shall be designed specifically for that purpose with the power and versatility
to easily and accurately bury the various sizes of cable-duct under all normal soil
conditions. This equipment shall place the cable-duct without twisting, kinking, or
damaging it in any way. Dragging or pulling the cable-duct from the start of the
trenching operation will not be allowed. Where two ducts are to be installed parallel
to each other, the distance between them shall be no less than 12 in. and no more than
24 in.

280 The plastic duct of the cable-duct shall be terminated 4 in. above the top of
foundations or 4 in. inside handholes with sufficient excess conductors as directed. All
terminations of this plastic duct shall be beveled and free from any sharp edges or
burrs. Insulation of the electrical conductor shall not be damaged when cutting the
duct.

2. Through Cable-duct in Conduit

The underground distribution circuit shall be protected by galvanized steel conduit when installed under pavement, in road shoulders, or elsewhere as shown on the plans or as directed.

290

Cable-duct shall be pulled through the entire length of galvanized steel conduit if at all possible. If this is not possible, written authorization shall be obtained to allow the duct to be cut away and the conductors installed in the conduit with a minimum of 2 ft of duct extended into the conduit. Where so authorized, the plastic duct shall be terminated in the proper transition fitting attached to the end of the conduit and each conductor of the cable-duct assembly shall continue undamaged and uninterrupted through the galvanized steel conduit to the other end of the conduit where a transition to the cable-duct shall be used again and the cable-duct shall continue uninterrupted to the next designated splice point. All transitions from galvanized steel conduit to cable-duct shall be accomplished with the proper adapter. This adapter shall provide a durable, watertight transition that has a smooth uniform interior.

300

3. Cable Markers

The location of underground conduits or cable-ducts shall be marked with cable markers. The marker shall be placed at all changes in direction, where the underground distribution circuit is split, and at a maximum of 400 ft intervals on straight runs. Cable markers shall be a slab of concrete 2 ft square by 4 in. thick, with the word "Cable" die impressed into the surface of the marker, a minimum depth of 3/8 in. with letters a minimum of 2 in. high. Arrows showing the direction of the cable shall be die impressed or saw-cut a minimum depth of 3/8 in. into the marker surface.

310

Curing of the concrete shall be in accordance with 702.22. The cable marker shall have a smooth metal trowel finish without scaling.

(b) In Conduit Risers

Cable-duct shall enter the bottom of the conduit riser with a sweeping radius bend and continue up the riser to within 3 in. of the top of the conduit riser. At this point the plastic duct shall be terminated and the conductors shall continue uninterrupted and undamaged into the service cabinet, underpass switchbox, or through the weatherhead with sufficient excess to make the required connections.

320

(c) Through Conduit in Bridge Coping

Where a cable-duct underground distribution circuit is run through conduit installed in bridge coping, the duct shall be cut away and the conductors shall be installed in the conduit with at least 2 ft of duct extended into the conduit. The conductors, through this transition, shall be continuous between authorized splice points. Where more than one light pole is to be installed on the same side of the bridge structure and connected to the same distribution circuit, the cables pulled between these light poles shall be of the same type and size used in the cable-duct underground distribution circuit.

330

(d) Aerial Cable

Aerial cable for overhead distribution circuits shall be supported and terminated as shown on the plans. The aerial cable shall have a sag of no more than 5% of the distance between lighting poles except where slack spans are indicated on the plans. Aerial cables shall have a minimum vertical clearance of 18 ft.

807.09 Lighting Handholes

340 Handholes shall not be placed in areas subject to flowing or ponding water. Handholes shall be installed with the top flush with adjoining surfaces. Precast handholes with integral bottoms will be considered acceptable.

Multiple compression fittings and insulating links installed in handholes shall be taped and waterproofed by application of an approved waterproofing device. The insulation around the area to be waterproofed shall be cleaned before applying the waterproofing device. These waterproofing devices shall be designed for insulating multi-conductor cables with a minimum voltage carrying capacity of 600 volts.

350 Handholes of an alternative material will be allowed as a substitute for a street and alley handhole providing that they meet the requirements of 922.17(b) and can be placed at a location which meets both of the following conditions:

- (a) there is no evidence of vehicles traveling over the area where the handhole is to be located; and
- (b) it is located a minimum of 15 ft from the edge of pavement, unless it is protected by guardrail, non-mountable curb, a structure, or a non-traversable ditch.

360 The handhole shall be backfilled with sand or earth containing no particles that would be retained on a 1/4 in. (6.3 mm) sieve. The backfill shall be placed as shown on the plans. No additional payment will be allowed for this backfill.

807.10 Concrete Foundations For Light Poles

Foundations shall be class A concrete in accordance with 702. Footings may be either round or square in shape as shown on the plans.

370 Anchor bolt circle dimensions shall be furnished and the anchor bolts shall be in accordance with 920.01(a)7. A rigid template shall be used to center the anchor bolts in the foundation. Unless otherwise specified, the template shall be oriented so that the mast arm of the light pole is perpendicular to the center line of the roadway.

Each foundation installation shall have provisions for grounding the light pole in accordance with 807.12. The tops of the concrete foundations shall be constructed level and only shims used to rake the light pole will be allowed. Shims shall not be used with break-away couplings. Each foundation shall have an imprinted arrow or arrows on the top of the foundation to indicate the direction of the cable duct run.

Foundations for high mast towers shall be constructed prior to constructing
380 foundations for conventional roadway lighting.

(a) Cast-in-Place Foundations

If the sidewalls of the excavated areas remain firm and stable, concrete may be poured directly against the dirt below the level of the top 6 in. form. Otherwise, the concrete foundation shall be fully formed by means of a paper preformed liner or other approved means. However, the foundation shall be formed to the proper size for the top 6 in. before concrete is poured. If a paper liner is used, it may be withdrawn as the concrete is placed or it may be left in place permanently. If the liner is left in place, all voids between the excavation walls and the form shall be filled and compacted using
390 coarse aggregate No. 53. If the liner is withdrawn, the top 12 in. of the foundation shall remain formed until the concrete has obtained initial set.

(b) Precast Foundations

Precast foundations shall be complete with reinforcing bars, tie bars, anchor bolts, and entry sleeves located to provide a level mounting for the light pole after installation. The grounding coil, as shown on the plans, may be used for grounding light pole set on precast foundations. Foundation backfill shall consist of coarse aggregate No. 53.

400 **(c) Grading of Foundations**

Foundation projection above the finished grade shall be as shown on the plans. The excavated material may be used for this grading if it is not granular in nature and will readily stabilize and support the growth of sod. If the excavated material is unsuitable, it shall be properly disposed of and approved materials used. The area shall be sodded. Sodding will be in accordance with 621.

807.11 Placing Light Poles

(a) Light Poles Under 45 ft in Height

410 The light pole assembly shall consist of a metal pole, a shoe base, a frangible breakaway base or coupling where shown on the plans, and a metal mast arm for attaching the luminaire. The unit shall be assembled on the ground. Pole circuit wiring shall be installed and the luminaire shall be attached prior to erection. The factory finish of the pole assembly shall be protected from marks, blemishes, scratches, or other damage. Slings and chokers for lifting purposes shall be of nylon or other approved material. Chains, metal rope, or other abrasive materials shall not be used for lifting devices. If damage to the factory finish occurs, repair or replacement shall be as directed.

420 The base plate shall be designed to carry the pole assembly. The plate assembly shall be supported by a transformer base, which shall be in accordance with the breakaway requirements in the AASHTO LRFD Specifications for Structural Supports for Highway Signs, luminaires, and Traffic Signals.

After erection and attachment to the foundation, the pole assembly shall be plumb. The luminaires shall be level in both horizontal areas. Shims shall not be used with breakaway couplings. Shimming will be allowed on other types of installations to rake the pole assembly to obtain the desired attitude of the luminaire where the combined weight of the pole and mast arm requires it and the luminaire saddle will not allow the adjustment. The mast arm shall be perpendicular to the axis of roadway travel unless special orientation is noted on the plans. Unless otherwise specified, the lighting system shall consist of metal pole supports for the luminaires with an underground electrical supply system.

(b) High Mast Towers of 60 ft Height and Over

High mast tower pole sections shall be mechanically fitted in the field using factory supplied hydraulic jack or hoist puller that shall produce a minimum force of 10,000 lb per side. Field assembly procedures and assembly apparatus requirements shall be submitted for approval. Field welds will not be allowed except where shipping limitations prevent permanent factory assembly. Prior approval for field welds is required.

The pole shall be erected on the lower set of the anchor bolt nuts and secured with the top nuts. The adjustments to plumb the pole shall be made prior to the final tightening of the top nuts.

The pole shall be plumbed under no wind conditions before sun-up, after sun-down, or on an overcast day. The deviation from vertical shall not exceed 1/4 in. within any 10 ft of height.

When installing the high mast power cable, one end of the power cable shall be securely connected to the luminaire ring. The other end of the power cable shall be secured to the support and terminated 3 ft below this support with a heavy duty three-wire electrical plug. Adjustments of the three support cable lengths shall be made prior to lowering the ring for the first time. After the support cables have been adjusted and the luminaires installed on the ring, at least one complete cycle operation of the ring shall be conducted on each structure.

As shown on the plans, should the ring provide more luminaire attachment positions than luminaires to be installed, counterweights of the same weight of the luminaire shall be installed on those positions.

807.12 Grounding

Ground wire shall be No. 4 AWG solid bare copper. Ground rods shall be 1/2 in. diameter by 8 ft long copper weld ground electrodes except where larger sizes are specified. The top of the ground rod shall be driven at least 6 in. below grade. Ground rods shall not be installed within the light pole sign structure, or high mast tower foundations.

470 The ground wire shall be connected to the top or side of the ground rod. The ground rod, ground wire connection shall be made by a thermo weld process. The wire and ground rod shall be free of oxidized materials, moisture, and other contaminants prior to inserting the wire and the ground rod into the properly sized mold. The welding material shall sufficiently cover and secure the conductor to the rod. The completed connection shall be non-porous.

As an acceptable substitute to this process, a mechanical ground grid connection of an approved type may be used. Tap type clamps, parallel type clamps, U-bolt flat clamps, and crossover clamps will not be accepted.

480

Luminaire poles shall be grounded by connecting the free end of the ground wire to the grounding lug in the transformer base or pole. The free end of the ground wire shall enter the pole base through the entry sleeve installed in the foundation.

The neutral conductor of the underground distribution circuit shall be connected to the ground lug in the transformer base or pole. This connection shall include a quick-disconnect type connector kit so that in the event of a pole knockdown the connection will readily break without damage to the buried conductor.

490

The breaker boxes for the sign and underpass circuits shall be grounded by connecting the free end of the ground wire to the neutral grounding terminal in the breaker box and connecting this terminal to a grounding lug securely fastened to the metal interior of the breaker box. The conduit terminating in the breaker box and the sign or underpass luminaire housing shall have a good, clean, tight connection and act as a grounding conductor for these luminaires. The neutral conductors of the feed and distribution circuits for underpass and sign illumination shall be connected to the neutral grounding terminal in the switch box or breaker box. The neutral conductor of the distribution circuit for underpass and sign illumination shall be grounded in each luminaire by connecting a jumper from the neutral terminal of the luminaire to a ground lug fastened to the metal housing of the luminaire.

500

Sign structures shall be grounded at one sign column by connecting the free end of the grounding wire at that column to the grounding lug in the column base.

A Type I service for supply of electrical energy shall consist of a conduit riser to a weatherhead. This conduit shall be grounded at the lower end by means of a standard strap grounding connection to the ground wire and ground rod. A Type II service shall consist of a multiple number of conduits from underground to the bottom of the service cabinet and a single conduit to a weatherhead from the top of the service cabinet. All of these conduits shall be connected by a single ground wire from the grounding terminal to a grounding bushing for each conduit within the interior of the service cabinet. In addition a ground wire from the grounding terminal of the service cabinet shall be connected through a conduit to a ground rod.

510

Bridge railing conduits shall be grounded at each end of the bridge railing by

means of a standard grounding strap connected to a ground wire and ground rod. The ends of the conduits terminating in a bridge anchor location shall provide ground continuity by means of a grounding bushing on each conduit end and the connection of the bushing to a ground wire.

520

All equipment used in the highway lighting system shall be grounded. If necessary, additional grounding shall be installed as directed.

807.13 Luminaires

(a) Installation

Luminaire installation shall consist of the physical placing of the luminaire. Each installation shall include the furnishing and placing of the light source as designated. Luminaires shall be compatible with other lighting materials as specified in 920.01.

530

1. Roadway Luminaires

Each luminaire shall be leveled in both directions in the horizontal plane after the light pole has been erected and adjusted. Rotary adjustment of the mast arm and vertical adjustment of roadway luminaires to obtain an installed level position in both directions shall be accomplished by means of the bolted saddle arrangement used to attach the luminaires to the mast arm. For certain light source types such as metal halide lamp socket positions may be shown on the plans by type of Illuminating Engineering Society of North American, IES, and light pattern. The specified lamp socket position or comparable arrangement of LEDs shall be used to obtain the desired light pattern delivery. Proper connections shall be made to provide operation at the voltage being supplied. Replacements needed because of faulty or incorrect voltage connections shall be made with no additional payment. All roadway luminaires provided for an intersection, interchange, or contiguous highway segment shall be the same type, model, and wattage.

540

2. Sign Luminaires

Connections in which plain and galvanized steel are in contact shall be protected such that aluminum surfaces shall receive one coat of zinc chromate primer. Steel surfaces shall be prepared in accordance with 619.08(a), and 619.08(d), and painted with the structural steel paint system in accordance with 619.09(a). All paint shall be allowed to cure before assembly. Conduit fittings, if required, shall be watertight. Required conduit shall be either rigid or flexible as necessary. Conduit shall not be clamped to a sign panel.

550

Sign luminaires shall be mounted on overhead sign structures on two metal channels located at the extremity of the sign walkway support brackets. The distance between lighting unit support channels shall be 7 in. These channels shall be located in such a manner that they readily receive the mounting bolts from the rear of the sign luminaire. The installation of the sign luminaire shall consist of the physical placement of the luminaire on the channels.

560

Sign luminaires shall be connected to a phase conductor and a neutral conductor. The luminaires shall be alternately connected to opposite phase conductors to balance the load. The connections in the base of the sign structure shall be in accordance with 807.06. Conductor splicing shall be in junction boxes, in-ground handholes, inside handholes of sign structures, and circuit breaker enclosures. All sign luminaires provided for an interchange or contiguous highway segment shall be the same model.

3. Underpass Luminaires

570 Underpass luminaires shall be mounted on the vertical side surfaces of bridge bent structures or suspended by means of pendants supported by angle-iron struts or clips fastened to the structural beam members of the bridge. All parts of the pendent pipe assembly shall be hot-dipped galvanized after threads are cut. Silicone caulking compound shall be applied to the threads during assembly of the pendent. Underpass luminaires may require separately mounted ballasts which shall be installed in close proximity to the luminaires.

580 Underpass luminaires shall be connected to a phase conductor and a neutral conductor. The luminaires shall be alternately connected to opposite phase conductors to balance the load. Conductor splicing will only be allowed in junction boxes, in-ground handholes, and circuit breaker enclosures. All underpass luminaires provided for an interchange shall be the same model.

4. High Mast Luminaires

590 The aiming of the luminaires shall be as shown on the plans. During the aiming and adjustment process, the luminaire shall be oriented to conform to its raised position and the ring properly tethered to prevent rotation. The long axis of the luminaire shall be parallel to the aiming direction as shown on the plans. All high mast luminaires provided for an interchange shall be the same model and wattage.

(b) Warranty

600 A non-prorated manufacturer's written warranty, against loss of performance, defects in materials and defects in workmanship, shall be provided to and in favor of the Department. The warranty shall cover a period of 10 years from the date of shipping of the luminaire. The warranty shall cover all components of the luminaire, including but not limited to driver and light source. Loss of performance is defined to include, but is not limited to, the luminaire or any of its components falling out of compliance with the specification in place at the time of installation, which includes but is not limited to the following: there is no light output from 10% or more of the LEDs, the luminaire is operating below the lumen maintenance curve, or the color temperature shifts more than 500K outside of the specified color temperature range. The warranty shall stipulate that repaired or replacement luminaires shall be shipped to the appropriate Department District Office, at no cost to the Department, within 30 days after the manufacturer's receipt of failed luminaires. Replacement luminaires shall be the same model or a model that is equal to, or better, in terms of photometrics, energy consumption, and reliability. Warranty documents shall include the manufacturer's name, address to which failed luminaires are to be shipped for

610 replacement, and the contact person's name, phone number, and email address. Warranty documents shall provide the estimated life cycle of the lamp, LEDs, plasma emitter and power driver. A Type C certification in accordance with 916 shall be provided for the luminaires.

807.14 Sign, Underpass, Roadway, High Mast Lighting Location, and Luminaire Identification

All high mast towers, roadway light poles, underpass lighting installations, and sign lighting installations shall have an identification code number as shown on the plans. In addition, each luminaire at a sign or underpass installation shall be individually identified with a single capital letter.

620 The code number shall be displayed on the light pole, sign structure column, and high mast tower as shown on the plans. The underpass code number shall be displayed near the breaker box at a location as directed.

The code number for the light pole and sign structure column shall be applied to the pole, as specified by the manufacturer, by using individual, pressure sensitive, adhesive backed tags. The code number for the high mast tower shall be applied to an aluminum plate which is mounted with spacers away from the structure as shown on the plans.

630 A luminaire identification sticker shall be provided on each luminaire and on the light pole or tower that supports the luminaire. The sticker shall be titled "LUMINAIRE" and contain the following: light source type, luminaire manufacturer, model, wattage, LED or lamp model, power drive model, surge protection device model, date of shipping, and warranty period. The luminaire identification sticker shall be attached underneath the light pole/tower ID tag, shall face the roadway, and shall have 3/4 in. lettering, and be no greater than 8 in. by 8 in.

807.15 Service Point Power Entry

640 The utility's requirements for service locations shall be coordinated. Unless otherwise specified, a pole shall be furnished for the service point. If the utility requires metering or is specified on the plans of the lighting system, a meter socket shall be obtained from and installed in accordance with the requirements of the utility. Grounding shall be in accordance with 807.12 and shall be a part of the service installation.

Energy shall be provided with 120/240 V service or 240/480 V service with the proper KW capacity on poles located immediately inside the right-of-way at locations designated on the plans. Electrical materials incorporated in the work shall be compatible with the service voltages supplied by the local utility.

650 The service voltages supplied by the local utility shall be checked for compliance with the planned voltages. If a discrepancy exists, it will be resolved as directed before work is started or any electrical equipment is purchased.

(a) Types of Service Points

Service point installations shall be of two types as shown on the plans.

1. Type I Service Point

660 This service point installation shall consist of class 5 timber pole, 2 3/4 in. galvanized steel conduits, weatherhead, photocell, and multiple relay switch. The conduit riser shall be fastened and supported on the pole by means of galvanized hook pipe straps and secured to the pole by means of a galvanized lag screw all of the proper size for the conduit being installed. Cable-duct shall be installed in the conduit riser in accordance with 807.08(c). The conductors shall extend beyond the weatherhead a minimum of 4 ft. The conductors outside of the weatherhead shall be ringed to prevent moisture from entering the conduit enclosure.

2. Type II Service Point

670 This service point installation shall consist of a service cabinet with a single galvanized steel or aluminum conduit riser to the weatherhead. A multiple number of galvanized steel conduits shall extend from the bottom of the service cabinet in accordance with 807.06. Underground cable-duct shall be installed in accordance with 807.08(a). Connections, connectors, and fixtures shall be as shown on the plans.

The service cabinet shall be secured to the pole by means of a galvanized steel channel post or other approved device.

(b) Sign and Underpass Circuits

680 The illumination circuits for sign structures with an overhead power supply shall be protected by circuit breakers mounted on the end support.

Circuits for adjustable end support sign structures, bridge bracket signs, or underpasses shall be protected by circuit breakers mounted on the bridge or sign structure and connected to the underground distribution circuit in a handhole.

Circuits for sign structures with an underground power supply shall be protected by fuse connector kits in the base of the sign support. The fuse connector kits shall include bayonet disconnect features for the “neutral” side and “hot” side.

690 **807.16 Testing of Highway Lighting System**

(a) Testing Lighting Circuitry

All necessary equipment and apparatus properly calibrated for testing the lighting circuits shall be furnished. The supplying utility shall be given advance notice of the test scheduling so their representative may witness the testing procedures if desired. Each main lighting circuit, including its branches, shall be tested for insulation resistance and continuity after it is completely installed but before the pole circuits, underpass circuits, sign circuits, and grounding circuits are connected.

700 The insulation resistance test shall be made with a megohm meter and the resistance to ground shall be no less than 50 megohms in all lighting circuit power cables. The meter shall be set for the voltage rating of the insulation. The continuity test shall be made with an ohmmeter properly scaled for measuring the resistance of the power cables. This test shall verify the following:

1. That each power cable is continuous to its termination points.
2. That the cable coding at junction and termination points is consistent with cable coding at the supply point.
- 710 3. That power cables are not crossed with the neutral or each other.
4. That the main circuit through each of its branches does not have unusual resistance values.

The entire completed installation shall be tested by circuit or by such portions as may be selected and at night if directed. Tests shall demonstrate the following:

- 720 1. That all power, lighting, and control circuits are continuous, free from short circuits, and free from unspecified grounds.
2. That all circuits are properly connected in accordance with applicable wiring diagrams.
3. That all circuits are operable which shall be demonstrated by continuous operation of each lighting circuit for at least 1 h.
- 730 4. That voltage at the ends of each lighting circuit and at inter points is within allowable limits. A maximum of 10% voltage drop will be allowed for each complete circuit.

(b) Testing and Inspecting Luminaires

The lighting system from the service point through the last luminaire shall be subjected to 14 days of normal operation prior to final acceptance. This testing procedure may be conducted separately on each circuit or on the entire system.

740 Normal operation is defined as the luminaires being on during the darkness hours and off during the daylight hours as controlled by the service point photocells and relay switches. Malfunctioning equipment shall be replaced or repaired before final inspection. The pattern of light and correlated color temperature delivered to the pavement by roadway, high mast, and underpass luminaires will be inspected at night. At this inspection, the proper tools, equipment, and personnel shall be available to make all adjustments. These items shall specifically include a bucket truck capable of

reaching all luminaires in the system, safety equipment, and a level to determine the proper luminaire position.

750 Within 30 calendar days after completion of the work, as-built drawings shall be submitted in electronic format to the Engineer. The lighting as-built drawings shall indicate the as-built location of light poles, high mast towers, service points, conduit runs, and lighting handholes.

807.17 Pay Item and Installation Summary Sheets

760 Prior to final inspection, two sets each of installation summary and pay item summary, each marked Final Record, shall be furnished for the light pole as installed. The installation summary shall show the effective mounting height, mast arm length, foundation elevation, pay item, type of base, and catalog number or drawing for each light pole furnished. The pay item summary shall indicate the pay item, quantity, effective mounting height, mast arm length, and type of base for each type of light pole furnished.

807.18 Method of Measurement

770 Luminaire, light pole with mast luminaire arm, high mast tower, identification number, connector kit, multiple compression fitting, insulating link, foundation, handhole, service point, and cable marker will be measured by the number of units installed. Pole circuit conductor and circuit conductor in conduit will be measured by the linear foot. Pole circuit conductor will be measured from the base of the light pole to the terminal block of the luminaire. Pole line extension will be measured in a straight line between each pole.

Conductor in bridge conduit will be measured by the linear foot from end to end of conduit or from the end of conduit to the last bridge light pole foundation entry. An allowance of 5 lft will be made for each foundation entry. An allowance of 2 lft will be made for each junction box.

Removal of existing light structure, which shall include the pole, mast arm, and foundation, will be measured by the number of units removed.

780 Cable-duct and conductor in underground duct or conduit will be measured by the linear foot as follows:

- (a) From the face of the concrete foundation to the center of the handhole or face of the next concrete foundation. An allowance of 5 lft will be made for each entry at foundations. An allowance of 2 lft will be made at handholes for connection purposes.
- (b) From light pole bases or handholes to switch boxes at underpasses. An allowance of 4 lft will be made at the switch box for electrical connections.

790

- (c) From end to end of the conduit when the cable is in conduit under a roadway surface or shoulder. No measurement will be made for cable-duct in conduit where it is part of a service point, sign installation, or underpass lighting system.

807.19 Basis of Payment

800 Luminaire will be paid for at the contract unit price per each for the type specified. Service point will be paid for at the contract unit price per each for the type specified. Light pole will be paid for at the contract unit price per each for the estimated mounting height, length of mast arm, and base type specified. High mast tower will be paid for at the contract unit price for the specified mounting height.

810 Lighting foundation, concrete, with grounding will be paid for at the contract unit price per each for the size specified. If class X material is encountered during lighting foundation excavation, payment will be made for such excavation in accordance with 206. Partial payment for lighting foundation in the amount of 80% will be made if all such work is complete except for finish grading and sodding. The remaining percentage of payment will be made upon completion of the finish grading and sodding.

820 Connector kit will be paid for at the contract unit price per each for fused or unfused, as specified. Multiple compression fitting and insulation link will be paid for at the contract unit price per each for waterproofed or non-waterproofed, as specified. Cable-duct marker, high mast tower winch drive, and handhole, lighting will be paid for at the contract unit price per each. Sign, underpass, and roadway lighting location identification will be paid for at the contract unit price per each. Circuit installation will be paid for at the contract unit price per each for the type, structure number, and number of luminaires specified. Light structure, remove and portable tower lighting drive system will be paid for at the contract unit price per each.

820 Wire will be paid for at the contract unit price per linear foot for the designation, copper gauge, housing, and number of conductors specified. Pole circuit cable, Type THWN, stranded will be paid for at the contract unit price per linear foot for the copper gauge and number of conductors specified. Conduit, steel, galvanized, 2 in. diameter will be paid for at the contract unit price per linear foot.

Payment will be made under:

Pay Item	Pay Unit Symbol
Cable, Pole Circuit, THWN, No. ____ Copper, Stranded, ____/C.....	LFT
Cable-Duct Marker.....	EACH
Circuit Installation, Str. No. __, __ Luminaires..... no.	EACH
Conduit, Steel, Galvanized, 2 in.....	LFT

The cost of the pole; lowering system including winch assembly, power cable, and support cable; concrete pad; luminaire ring; anchor bolts and nuts; lightning rod assembly; grounding system; and all incidental materials necessary to complete the installation shall be included in the cost of high mast tower. The cost of excavation, concrete, sleeves for cable-duct, non-metal pipe, reinforcing bars, backfill, finish grading, and sodding shall be included in the cost of lighting foundation.

890 The cost of wood poles, multiple relay switches, service cabinet, photocells, photocell receptacles, weatherhead, conduit, and other miscellaneous items shall be included in the cost of the service point.

The cost of lamps, LED arrays, plasma emitters, drivers, optical systems, weatherproof housings, surge protection devices, electrical connections, and installation of the luminaire on the pole shall be included in the cost of luminaire.

The cost of snap-on coverings in light pole bases and waterproof coverings in underground handholes shall be included in the cost of multiple compression fitting.

900 The cost of maintaining highway illumination during the life of the contract and the preparation and transmittal of as-built drawings shall be included in the cost of other pay items.

SECTION 808 – PAVEMENT TRAFFIC MARKINGS

808.01 Description

This work shall consist of furnishing and installing, or removing, pavement traffic markings and snowplowable raised pavement markers in accordance with the MUTCD, these specifications and as shown on the plans. Markings shall be installed as required unless written approval is obtained from the District Traffic Engineer to make modifications at specific locations.

10 **MATERIALS**

808.02 Materials

Materials shall be in accordance with the following:

	Beads	921.02(e)
	Cones.....	801.08
	Multi-Component	921.02(c)
	Preformed Plastic	921.02(b)
	Snowplowable Raised Pavement Markers.....	921.02(d)1
20	Thermoplastic	921.02(a)

A Certification, Other, in accordance with 916, shall be provided by the manufacturer that certifies the paint meets all IDEM and EPA regulatory requirements for VOC levels and lead, chromium or other heavy metals.

CONSTRUCTION REQUIREMENTS

808.03 General Requirements

30 Permanent pavement markings shall be placed on the surface course in a standard pavement marking pattern. Center lines shall be placed on two-way two-lane roads, lane lines shall be placed on multi-lane divided roads, and both center lines and lane lines shall be placed on multi-lane undivided roads.

40 The pavement shall be cleaned of all dirt, oil, grease, excess sealing material, excess pavement marking material and all other foreign material prior to applying new pavement traffic markings. New paint pavement markings may be placed over sound existing markings of the same color. New thermoplastic, preformed plastic, or multi-component markings may be applied over sound existing markings of a compatible type if allowed by manufacturer's recommendations, a copy of which shall be supplied to the Engineer prior to placement; otherwise, existing markings shall be removed in accordance with 808.10 prior to placement of the new markings. Removal of pavement marking material shall be in accordance with 808.10. The pavement surface shall be dry prior to applying pavement traffic markings.

50 Control points required as a guide for pavement traffic markings shall be spotted with paint for the full length of the road to be marked. Control points along tangent sections shall be spaced at a maximum interval of 100 ft. Control points along curve sections shall be spaced so as to ensure the accurate location of the pavement traffic markings. The location of control points will be subject to approval prior to the pavement traffic marking application.

808.04 Longitudinal Markings and Milled Corrugations

All longitudinal lines shall be clearly and sharply delineated, straight and true on tangent, and form a smooth curve where required. Lines shall be square at both ends, without mist, drip or spatter.

60 A solid line shall be continuous. A broken line shall consist of 10 ft line segments with 30 ft gaps. A dotted line shall consist of 3 ft line segments with 9 ft gaps unless otherwise indicated on the plans.

All lines shall be gapped at intersections unless otherwise specified or directed.

The actual repainting limits for no-passing zone markings will be determined by the Engineer.

A new broken line placed over an existing broken line shall laterally match the existing broken line, and the new line segments shall not extend longitudinally more

70 than 10% beyond either end of the existing line segments. A new dotted line placed over an existing dotted line shall laterally match the existing dotted line, and the new line segments shall not extend longitudinally more than 6 in. beyond either end of the existing line segments.

(a) Center Lines

Center lines shall be used to separate lanes of traffic moving in opposite directions. All center line markings shall be yellow in color and 6 in. in width on the state highway system, and 4 in. wide on all other roads. They shall be placed such that the edge of the marking, nearest to the geometric centerline of the roadway, shall be offset 3 in. from the geometric centerline on the state highway system and 3 in. on all other roads unless a different offset is approved by the Engineer.

80

The center line of a multi-lane roadway shall be marked with a double solid line. The two lines forming the double solid line shall be spaced 6 in. apart on the state highway system, 6 in. apart on all other roads, and shall be equally offset on opposite sides of the geometric centerline unless a different spacing is approved by the Engineer.

The center line of a two-lane, two-way roadway, where passing is allowed in both directions, shall be marked with a broken line.

90 The center line of a two-lane, two-way roadway, where passing is allowed in one direction only, shall be marked with a double line, consisting of a broken line and a solid line. The broken line and the solid line shall be spaced 6 in. apart on the state highway system, 6 in. apart on all other roads, and shall be equally offset on opposite sides of the geometric centerline unless a different spacing is approved by the Engineer. The solid line shall be offset toward the lane where passing is prohibited. The broken line shall be offset toward the lane where passing is allowed.

100 The center line shall be placed within the milled corrugation when center line rumble stripes are specified. Placement of the center line marking in the milled corrugation does not alter the pavement marking performance requirements of 808.07.

(b) Lane Lines

Lane lines shall be used to separate lanes of traffic moving in the same direction. Normal width lane line markings shall be white in color and shall be 6 in. wide on the state highway system, and 4 in. wide on all other roads. They shall be offset 4 in. to the right of longitudinal pavement joints or divisions between traffic lanes.

110 Wide lane lines for lane drops, route splits, or auxiliary lanes shall be white in color and shall be 10 in. wide on the state highway system, and 8 in. wide on all other roads. White solid lines shall be used to mark lane lines only when specified or directed.

(c) Edge Lines

Edge lines shall be used to outline and separate the edge of pavement from the shoulder. Edge line markings shall be 6 in. in width on the state highway system, and 4 in. wide on all other roads. The edge lines shall be placed such that the edge of the marking nearest the edge of the pavement shall be offset 4 in. from the edge of the pavement except as otherwise directed. Right edge lines shall be marked with a white solid line and left edge lines shall be marked with a yellow solid line.

120

The edge line shall be placed in the milled corrugation when edge line rumble stripes are specified. Placement of the edge line marking in the milled corrugation does not alter the pavement marking performance requirements of 808.07.

(d) Barrier Lines

Barrier lines shall be used as specified or directed. Barrier line markings shall be solid lines of the size and color specified or as directed.

(e) Markings in Retrofitted Corrugations

130

In sections where corrugations are being placed in the existing surface, all existing pavement markings shall be removed in accordance with 808.10 and any existing sealants shall be removed by routing or grinding. Temporary pavement markings placed in accordance with 801.12 shall be offset a sufficient distance from the longitudinal joint so as to not obstruct the installation of the corrugations or the application of the liquid asphalt sealant.

140

The Contractor shall make a record of the existing pavement marking locations so that such markings may be replicated later with the appropriate adjustments for edge line rumble stripes. This record shall show longitudinal and transverse dimensions. The record shall be submitted to, and is subject to approval by the District Traffic Engineer prior to the removal of existing pavement markings. The District Traffic Section shall be notified two weeks prior to applying pavement markings to allow the District Traffic Section time to verify the pavement marking plan.

808.05 Transverse Markings and Pavement Message Markings**(a) Transverse Markings**

150

Transverse marking lines shall be used as specified or directed to delineate channelizing lines, stop lines, crosswalk lines, and parking lines. Parking lines for ADA accessible parking spaces shall be 4 in. wide and blue in color. Unless otherwise specified or directed, all other parking lines shall be 4 in. wide and white in color. All other transverse markings shall consist of all necessary lines, of the width specified or directed and shall be in accordance with the MUTCD.

(b) Pavement Message Markings

Pavement message markings shall be used as specified or directed for railroad crossing approaches, intersection approaches, crosswalk approaches, ADA accessible parking space symbols, and other messages applied to the pavement with pavement

160 marking material. The markings shall consist of all necessary lines, words, and symbols as specified or directed, and shall be in accordance with the MUTCD.

808.06 Curb Markings

Curb markings shall consist of reflectorized paint which shall cover the face and top of the curb.

The existing curb and gutter area shall be cleaned of dirt, dust, oil, grease, moisture, curing compound, and unsound layers of other materials before paint is applied to the curb surface.

170 808.07 Pavement Marking Material Application, Equipment, and Performance Requirements

All double line markings, such as a no passing zone or the center line of an undivided multi-lane roadway, shall be applied in one pass. When a hand-propelled machine is used, the single pass application of double line markings will not be required and control points shall be spaced at a maximum of 10 ft longitudinally.

180 For contracts with completion dates when conditions do not enable application of the specified marking materials, or grooving for durable marking materials, other materials may be substituted with an appropriate unit price adjustment if approved by the Engineer.

Markings shall be installed in accordance with the manufacturer's recommendations, except that the minimum requirements stated herein shall also apply. Products specifically designed for application temperatures below the stated minimums herein are not required but may be used if approved by the Engineer.

190 When directed, the Contractor shall provide the Department with original copies of all necessary current manufacturer's installation manuals prior to beginning installation work, and no installation work shall begin prior to the Department's receipt of these manuals. These manuals shall become the property of the Department.

The markings shall be protected from traffic until dry to eliminate tracking.

The markings shall meet or exceed the following performance criteria:

1. Color. The daytime and nighttime color of the applied markings shall be in accordance with ASTM D6628 when determined in accordance with ASTM E811 and ASTM E1349.
- 200 2. Durability. The pavement markings shall have a minimum resistance to wear of 97% in accordance with ASTM D913.
3. Dry retro-reflectivity. Contracts with 50,000 ft or more of longitudinal paint line or 10,000 ft or more for each type of

longitudinal durable marking line applied shall have retro-reflectivity measured, except black markings and markings placed on seal coat pavements placed in accordance with 404. Longitudinal lines shall meet required minimum initial and retained average retro-reflectivity measurements.

210

All other contracts and markings, except parking lines, shall meet the required longitudinal line minimum measurements and will be measured by the Department at the discretion of the Engineer, except that quality adjustments will not apply. Retained retro-reflectivity is the value at the time of the warranty expiration in accordance with 808.09 and will be measured by the Department at the discretion of the Engineer.

220

4. Wet retro-reflectivity. Contracts with longitudinal durable marking line applied shall meet the required longitudinal line minimum measurements for initial wet retro-reflectivity and will be measured by the Department in accordance with ASTM E2177 at the discretion of the Engineer. The testing period will be not less than 14 days to not more than 30 days after the durable longitudinal lines are applied. The initial wet recovery retro-reflectivity for white markings shall exceed 275 mcd/m²/lx and yellow shall exceed 175 mcd/m²/lx. Sampling zones that do not meet these wet retro-reflectivity levels for white or yellow markings shall be replaced or receive an additional layer of durable marking material and supplemental elements at no additional cost.

230

Retro-reflectivity testing equipment shall be furnished, calibrated, and operated in accordance with ITM 931. The markings shall be tested in a period of not less than 14 days to not more than 30 days after the materials are applied. The retro-reflectivity equipment shall remain the property of the Contractor.

240

The measurement of retro-reflectivity shall be supervised or performed at all times by an operator trained and certified by the unit's manufacturer. A report as described in the ITM and including the specified test results and calculations shall be prepared and provided to the Engineer within three days of each day of testing.

Quality adjustments will be applied to the payment of markings as indicated in the table below. The required minimum initial and retained average retro-reflectivity values for longitudinal line measured in mcd/m²/lx are as follows:

Material Type	White	Yellow	Quality Adjustment*	Retained White	Retained Yellow
Paint	≥ 250	≥ 175	1.00	n/a	n/a
Required Minimum	150 to 249	125 to 174	0.70		
Thermoplastic	≥ 300	≥ 200	1.00	see 808.09	see 808.09
Required Minimum	250 to 299	150 to 199	0.70		
Multi-Component	≥ 300	≥ 200	1.00	see 808.09	see 808.09
Required Minimum	250 to 299	150 to 199	0.70		
Preformed Plastic	≥ 650	≥ 450	1.00	see 808.09	see 808.09
Required Minimum	550 to 649	350 to 449	0.70		
* Quality Adjustments do not apply to the retained retro-reflectivity values.					

(a) Traffic Paint

250

1. Application

Traffic paint shall be applied only when the ambient air and pavement temperature is 40°F or higher and will remain 40°F or higher for 2 h after application.

The markings shall be protected from traffic until dry to eliminate tracking.

The wet film thickness of the traffic paint shall be a minimum of 15 mils. Painted lines and markings shall be immediately reflectorized by applying beads at a uniform minimum rate of 6 lb/gal. of traffic paint. Only standard or modified standard beads shall be used for paint markings.

260

2. Equipment

Traffic paint shall be applied with a spray type machine capable of applying the traffic paint under pressure through a nozzle directly onto the pavement. The truck-mounted machine shall be equipped with the following:

270

- a. air blast device for cleaning the pavement ahead of the application,
- b. guide pointer to keep the machine on an accurate line,
- c. spray guns which can be operated individually or simultaneously,
- d. agitator or recirculation system as appropriate,
- e. control device to maintain uniform flow and application,

- 280 f. capability of heating the material to application temperatures,
- g. automatic device which will provide a line of the required pattern,
- h. automatic bead dispenser which is synchronized with the marking application.

A hand-propelled machine may be used to apply markings. A brush may be used if approved to apply some markings.

290 **3. Performance Requirements**

The color and durability requirements shall be met for a minimum of 90 days after application.

300 Pavement marking segments which are found to have an average retro-reflectivity reading below the minimum required shall be re-stripped with no additional payment. Pavement markings segments which have more than four of 16 individual readings below the minimum required shall be re-stripped with no additional payment. The re-stripping shall begin within 14 calendar days of the completion of the retro-reflectivity measurement. Line segments may be re-stripped with no additional payment. Following each re-stripping, additional retro-reflectivity measurements shall be made with no additional payment. Quality adjustments will be based on the final retro-reflectivity measurements. The alignment of all re-stripped pavement markings shall be placed within ±1/4 in. in width and ±2 in. in length of the original placed markings. Re-stripping will not be allowed more than two times, after which removal and replacement of the markings will be required.

(b) Durable Pavement Marking Material

310 Durable pavement marking material consists of thermoplastic, preformed plastic, or multi-component markings.

Durable pavement marking materials used for center lines, lane lines, or edge lines shall be installed within a groove in the pavement unless otherwise shown on the plans.

Durable pavement marking materials used for barrier lines, pavement message, and transverse markings shall be surface applied unless otherwise indicated on the plans.

1. Grooving for Durable Pavement Markings

320 **a. Application**

The pavement shall be grooved prior to the placement of longitudinal durable pavement markings, excluding bridge decks and approach slabs. The groove or recess shall be installed in a single pass using dry cut equipment that utilizes diamond cutting

blades and that is approved by the pavement marking manufacturer. If there are no markings on the pavement, a guide line shall be placed using paint without glass beads as a template for the grooving operation. The groove shall be at least 1 in. and no more than 2 in. wider than the pavement marking to be placed.

330 The Contractor may leave a gap in the grooving for longitudinal lines that delineate the radii of lane usage transitions, driveways, intersections, or adjacent to curb that does not have a curb offset to the marking of at least 12 in.

The depth of the groove shall be in accordance with the manufacturer's recommendations and shall be at minimum 5 mils greater than the thickness of the marking material including exposed glass beads, up to maximum allowable depth of 150 mils. A continuous groove shall not be allowed for broken or dotted lane lines. The groove may extend up to 3 in. at either end of a lane line. Grooves shall be no closer than 2 in. to the edge of a longitudinal joint.

340 **b. Groove Finish and Cleaning**

The grooved surface shall be cleaned with vacuuming equipment immediately following the grooving operation. The surface shall be clean and dry prior to pavement marking installation. The finished groove surface shall have a fine corduroy-like appearance with a maximum variation in depth of 10 mils.

2. Thermoplastic

a. Application

350 Thermoplastic marking shall be applied in molten form by conventional extrusion, by ribbon type extrusion, or spray when the pavement and ambient air temperatures are 50°F and rising. Heat bonded preformed thermoplastic may be used for transverse or message markings. The average final thickness of the thermoplastic marking shall be no less than 90 mils and no more than 125 mils. Immediately following the application of the thermoplastic markings, retro-reflectorization shall be provided by applying pavement marking beads to the surface of the molten material. A first drop of supplemental elements shall be applied in accordance with the manufacturer's recommendations and a second drop of standard, modified standard, or supplemental beads in accordance with the manufacturer's recommendations. Individual passes of markings shall not overlap or be separated by gaps greater than 1/4 in. longitudinally.

360

b. Equipment

The equipment used for the application of thermoplastic markings shall consist of a kettle for melting the material and an applicator for applying the markings. All of the equipment required for melting and applying the material shall maintain a uniform material temperature within the manufacturer specified limits, without scorching, discoloring or overheating any portion of the material.

A truck-mounted machine shall be equipped with the following: an air blast device for cleaning the pavement ahead of the marking operation; a guide pointer to

370 keep the machine on an accurate line; at least two spray guns which can be operated individually or simultaneously; agitators; a control device to maintain uniform flow and application; an automatic device which will provide a broken line of the required length; and an automatic bead dispenser which is synchronized with the marking application.

A hand-propelled machine may be used to apply markings.

380 The equipment for applying heat bonded preformed plastic shall be in accordance with the manufacturer's recommendations. An open flame shall not come into direct contact with the pavement.

c. Performance Requirements

When the initial average retro-reflectivity measurement is below the required minimum the segment of line shall be removed and replaced with no additional payment. Pavement markings segments which have more than four of 16 individual readings below the minimum required shall be removed and replaced with no additional payment.

3. Preformed Plastic

390

a. Application

The markings shall be applied by technicians certified by the manufacturer. The markings shall be applied when the air temperature is a minimum of 40°F and rising. A primer is required if the ambient air temperature is below 50°F. The pavement surface shall be primed with a binder material in accordance with the manufacturer's recommendations.

b. Performance Requirements

400 When the initial average retro-reflectivity measurement is below the required minimum the segment of line shall be removed and replaced with no additional payment. Pavement markings segments which have more than four of 16 individual readings below the minimum required shall be removed and replaced with no additional payment.

4. Multi-Component

a. Application

410 This material shall be applied only when the pavement and ambient air temperatures are 40°F and rising. The wet film thickness of the marking material shall be a minimum of 25 mils. Immediately following the application of the markings, retro-reflectorization shall be provided by applying pavement marking beads to the surface of the wet marking. A first drop of supplemental elements shall be applied in accordance with the manufacturer's recommendations and a second drop of standard, modified standard, or supplemental beads in accordance with the manufacturer's recommendations.

b. Equipment

The machine used to apply the marking material shall precisely meter each component, and produce and maintain the necessary mixing head temperature within
420 the required tolerances. The machine shall be equipped in accordance with 808.07(a)2.

c. Performance Requirements

Pavement marking segments which are found to have an average retro-reflectivity reading below the required minimum shall be re-stripped with no additional payment. Pavement markings segments which have more than four of 16 individual readings below the minimum required shall be re-stripped with no additional payment. The re-stripping shall begin within 14 calendar days of the completion of the retro-reflectivity measurement. Line segments may be re-stripped with no additional payment. Following
430 each re-stripping, additional retro-reflectivity measurements shall be made with no additional payment.

Quality adjustments will be based on the final retro-reflectivity measurements. The alignment of all re-stripped markings shall be placed within $\pm 1/4$ in. in width and ± 2.0 in. in length of the original placed markings. Re-stripping will not be allowed more than two times, after which removal and replacement of the markings will be required.

808.08 Marking Protection and Maintenance of Traffic

Protection of the traveling public, of the pavement marking crews, and of the pavement markings shall be provided during the marking operation through the use of
440 proper equipment, traffic control devices, safety devices, and proper procedures. Traffic control devices shall be placed in accordance with 107.12. Flaggers shall be provided for traffic control as directed.

(a) Vehicle Signs

Each vehicle in the marking operation shall display the slow moving vehicle emblem when operating at speeds of 25 mph or less. The slow moving emblems shall be removed when the vehicles are operating at speeds greater than 25 mph. The paint crew signs shall be 24 in. high by 96 in. wide, with 12 in. series C black letters on an orange encapsulated lens reflective background. Type A and Type C flashing arrow
450 signs shall be in accordance with 923.04.

(b) Vehicle Warning Lights

All amber flashing warning lights and amber strobe lights mounted on vehicles used in the marking operation shall be in accordance with 801.14(d). All vehicles used in the marking operation shall have a minimum of one flashing amber warning light or amber strobe light which is visible in all directions.

(c) Cones

Cones shall be used to protect marking material which requires more than 60 s
460 drying time. Cones shall remain in place until the marking material is dry or firm enough not to track or deform under traffic. Cones shall be removed as soon as possible

and shall never be left in place overnight. Edge lines shall not require protection with cones.

The maximum spacing of cones shall be as follows:

	40 mph or less	over 40 mph
Broken Lines	every line segment	every fifth line segment
Solid Lines	20 ft to 30 ft	

(d) Front Escort Vehicles

470 A front escort vehicle shall be used if the marking vehicle extends across the center line while operating. This front escort vehicle shall be equipped with a forward facing paint crew sign, a rear facing slow moving vehicle emblem, and a red flag mounted at least 10 ft above the pavement.

(e) Marking Application Vehicles

480 Marking application vehicles such as edgeliner or centerliner trucks shall have a rear facing Type A or Type C flashing arrow sign, an amber flashing warning light mounted near the center of the truck bed, and an amber strobe light mounted on each rear corner of the truck bed. The amber flashing warning light and the amber strobe lights shall be mounted on retractable supports and shall be operated at a height of 12 ft above the pavement unless otherwise directed.

(f) Rear Escort Vehicles

If cones are not required, a rear escort vehicle shall follow a marking application vehicle at a distance of 100 to 500 ft. If an additional rear escort vehicle is required due to drying time or heavy traffic volume, it shall follow the first rear escort vehicle at a maximum distance of 1,000 ft, and may operate in the travel lane or on the paved shoulder.

490 If cones are required, the cone setting truck shall follow the marking application vehicle and shall be followed by a rear escort vehicle. The cone pickup truck shall be followed by another rear escort vehicle.

All rear escort vehicles shall be equipped with a rear facing Type C flashing arrow sign mounted above a rear facing paint crew sign. On two-lane two-way roads, this Type C flashing arrow sign shall be operated with the arrowhead turned off. The supply truck may be used as a rear escort vehicle providing it is empty and is equipped with the required traffic control devices.

808.09 Warranty for Durable Pavement Marking Material

500 Durable pavement marking material shall be warranted against failure resulting from material defects or method of application, or the result of snowplowing and deicing activities. The material shall be warranted to retain its color, adherence to the pavement, and shall be free of other obvious defects or failures. Grooved durable

pavement markings shall also be warranted to retain retroreflectivity as specified below.

All pavement traffic markings which have failed to meet the warranted conditions shall be replaced with no additional payment.

510 For the terms of the warranty a unit shall be defined as a 1,000 ft section of line of specified width in any combination or pattern.

(a) Surface Applied Durable Pavement Marking Warranty

The warranty period for surface applied durable markings shall be 180 days beginning with the substantial completion date for the contract as defined in 101.64, but not prior to November 1 of the calendar year in which the last pavement markings were installed. If more than 3% of a unit or 3% of the total of any one intersection or set of transverse markings fails, the failed portion shall be replaced. All pavement markings required to be replaced under the terms of this warranty shall be replaced
520 within 60 days of the notification of failure.

(b) Grooved Durable Pavement Marking Warranty

The warranty period for durable markings placed in a groove shall be two years beginning with the substantial completion date for the contract as defined in 101.64, but not prior to November 1 of the calendar year in which the last pavement markings were installed. The retained retro-reflectivity, $\text{mcd/m}^2/\text{lx}$, as determined by ITM 931 shall meet or exceed the minimum values at all times during the warranty period as follows:

Material	Year	White	Yellow
Thermoplastic	1	225	150
	2	175	125
Multi-Component	1	225	150
	2	175	125
Preformed Plastic	1	400	300
	2	300	200

530

If more than 5% of a unit or 5% of the total fails, the failed portion shall be replaced. All pavement markings required to be replaced under the terms of this warranty shall be replaced within 60 days of the notification of failure.

808.10 Removal of Pavement Markings

Pavement markings which conflict with revised traffic patterns and may confuse motorists shall be removed immediately before, or immediately following, any change in traffic patterns as directed or approved.

540 Removal of pavement markings shall be to the fullest extent possible without materially damaging the pavement surface. Pavement marking removal methods shall be sandblasting, steel shot blasting, waterblasting, grinding, or other approved

mechanical means. Grooving will not be allowed. Grinding will only be allowed under the following conditions:

- (a) when removing durable pavement markings, or
- (b) when removing non-durable markings where another course of material is to be placed on the existing course.

550

Painting over existing pavement markings to obliterate them will not be allowed.

When a blast method is used to remove pavement markings, the residue, including sand, dust and marking material, shall be vacuumed concurrently with the blasting operation or removed by other approved methods. Accumulation of sand, dust or other residual material, which might interfere with drainage or constitute a traffic hazard, will not be allowed.

560 All damage to the pavement caused by pavement marking removal shall be repaired by approved methods with no additional payment.

808.11 Snowplowable Raised Pavement Markers

Snowplowable raised pavement markers shall be used as supplemental delineation at the locations shown on the plans or as directed.

(a) Surface Preparation

The pavement or bridge deck surface shall be cleaned of dirt, dust, oil, grease, moisture, curing compound, and loose or unsound layers of all materials which would interfere with the proper bonding of the marker to the pavement or bridge deck.

570

(b) Location

Marker locations shall be accurately laid out and **will be subject to approval** prior to the installation operation. Markers shall not be located on surfaces that show visible evidence of cracking, checking, spalling or failure of underlying materials. Markers shall not be located within the intersection of a public road. Any marker location, which falls on any of the restricted areas, shall be moved a longitudinal distance not to exceed 10% of the required marker spacing. If this adjusted location still falls within a restricted area, then that marker location shall be deleted. Marker locations shall be as shown on the plans.

580

(c) Reflector Color

The color combinations of the reflectors shall be as shown on the plans unless otherwise directed. When replacement prismatic reflectors are specified, such reflectors shall not be ordered until the quantity and color combinations have been determined and approved.

(d) Installation

Marker installation shall be in accordance with the manufacturer's

590 recommendations. The pavement surface temperature and the ambient air temperature shall be at least 50°F. The pavement surface shall be dry at the time of marker installation. The installation slot shall be clean and dry before the adhesive is applied. The slot shall be filled with sufficient adhesive to provide a water tight seal between the marker base and the pavement, and to fill all voids between the marker base and the surfaces of the slot. The marker shall be placed in the slot so that the tips of the snowplow deflecting surfaces are below the pavement surface.

If the pavement surface is newly placed HMA, the pavement shall be allowed to cure for two days prior to installing the markers.

600 Installation of markers on new concrete pavement or bridge decks or on newly overlaid bridge decks shall not be done until after the pavement or bridge deck is ready to be opened to traffic as specified elsewhere herein.

The number of slots cut in one day shall not exceed the number of markers which will be installed in that day. No slots shall be left open overnight.

(e) Removal of Markers

610 Markers designated for removal shall be as located on the plans or as otherwise specified or directed. If the pavement surface or bridge deck surface is to be removed, the markers shall be removed prior to any surface removal operation.

The markers shall be removed with a jackhammer or other approved equipment. The area of the pavement or bridge deck disturbed by the marker removal shall not exceed 3 in. in depth or extend more than 3 in. out from any side of the marker base. The marker removal operation shall stop if it is determined that excessive damage is occurring to the pavement, or bridge deck.

620 The resulting holes shall be filled with the appropriate patching material as described herein or as otherwise directed. Concrete pavement which is to be overlaid as part of the contract and HMA pavement shall be patched with HMA intermediate materials. Concrete pavement which is not to be overlaid as part of the contract and concrete bridge decks shall be patched with concrete patching material from the QPL of Rapid Setting Patch Materials. Overlaid bridge decks and bridge decks which are to be overlaid as part of the contract shall be patched with patching material which is compatible with the deck overlay material. All patching material shall be placed in accordance with the appropriate specifications for the patching material.

630 Removed markers shall become the property of the Contractor and removed from the jobsite prior to the completion of the work.

(f) Replacement of Prismatic Reflectors

Reflectors designated for replacement shall be as shown on the plans or as otherwise directed. Prior to placement of the new reflector, the castings shall be cleaned of all remaining butyl pad materials. All loose or foreign material shall be

satisfactorily removed by sandblasting, wire brush, or other approved mechanical means. Removed reflectors shall be disposed of properly off the project site.

808.12 Method of Measurement

640 Broken or dotted lines, placed or removed, will be measured by counting the number of broken or dotted lines placed and multiplying the number of counted lines by the length of the broken or dotted line. Solid lines will be measured as the total distance in linear feet of solid lines placed or removed. The material, type, color, or width of broken, dotted, or solid lines to be removed will not be considered when measuring such lines for payment.

650 Except as otherwise specified, transverse marking lines will be measured as the total distance in linear feet of lines placed or removed. Transverse marking yield lines will be measured transversely including the entire extent of the marking line and gaps. Curb markings will be measured by the linear feet along the front face of the curb. Grooving for pavement markings will be measured as the total distance of grooving for each pavement marking line in linear feet. Pavement message markings will be measured by the total number of each type placed. A railroad crossing pavement message marking shall include the two R's, the X, and the three stop lines per traffic lane. Railroad crossing pavement message markings will be measured by the total number of each marking place. Lane indication arrow pavement message markings will be measured by the number of lane indication arrowheads placed. Removal of pavement message markings will be measured in square yards using areas shown in the following table. The material will not be considered when measuring such markings for pavement.

660

PAVEMENT MESSAGE MARKINGS	
Description	Area
"Ahead"	3.1 SYS
Combo Arrow	3.1 SYS
"Exit"	2.5 SYS
"Left"	2.5 SYS
"Only"	2.5 SYS
Railroad "R"	0.6 SYS
"Right"	3.2 SYS
"RXR"	7.7 SYS
"School"	3.9 SYS
"Stop"	2.6 SYS
Straight Arrow	1.4 SYS
"Turn"	2.6 SYS
Turn Arrow	1.7 SYS
"XING"	2.5 SYS

Snowplowable raised pavement markers will be measured by the number placed or removed. Prismatic reflectors will be measured by the number furnished and

installed. Each two-way prismatic reflector will be measured as one reflector. No measurement will be made of the adhesive or the hole patching material used in the placement or removal of snowplowable raised pavement markers.

808.13 Basis of Payment

670 Lines and transverse markings placed will be paid for at the contract unit price per linear foot for the material, type, color, and width specified. Grooving for pavement markings will be paid for at the contract unit price per linear foot. Curb markings will be paid for at the contract unit price per linear foot for curb painting, of the color specified. Pavement message markings placed will be paid for at the contract unit price per each, for the material and message specified. Lines and transverse markings removed will be paid for at the contract unit price per linear foot. Pavement message markings removed will be paid for at the contract unit price per square yard.

680 Snowplowable raised pavement markers, furnished and installed, or removed will be paid for at the contract unit price per each. Prismatic reflectors will be paid for at the contract unit price per each. Each two-way prismatic reflector will be paid for as one reflector.

Payment for furnishing, calibrating, and operating retro-reflectivity testing equipment will be paid for at the contract price for lump sum. The cost of report preparation shall be included in the cost of retro-reflectivity testing. Adjustments to the contract payment with respect to retro-reflectivity of performance based pavement markings will be included in a quality adjustment in accordance with 109.05.1.

690 The Engineer may waive retro-reflectivity testing due to weather limitations. Retro-reflectivity testing will be waived for markings applied after October 31 and before April 1. If retro-reflectivity testing is waived, no payment will be made for retro-reflectivity testing. If retro-reflectivity testing is not waived by the Engineer due to weather or waived by the seasonal time restriction and retro-reflectivity testing is not performed, no payment will be made for retro-reflectivity testing and payment for the marking items will be made at 70% of the unit price.

Payment will be made under:

700	Pay Item	Pay Unit Symbol
	Curb Painting, _____ color	LFT
	Grooving for Pavement Markings	LFT
	Line, _____, _____, _____, _____ in..... material type color width	LFT
	Line, Remove	LFT
	Pavement Message Marking, _____, _____ material message	EACH
	Pavement Message Marking, Remove	SYS

809.01

710	Prismatic Reflector	EACH
	Retro-Reflectivity Testing	LS
	Snowplowable Raised Pavement Marker	EACH
	Snowplowable Raised Pavement Marker, Remove	EACH
	Transverse Marking, _____, _____, _____, _____ in.....	LFT
	material type color width	
	Transverse Marking, Remove.....	LFT

720 No additional payment will be made for the removal and or replacement of markings that fail to meet the performance or warranty conditions of 808.07 and 808.09.

The cost of removal of existing prismatic reflectors shall be included in the cost of prismatic reflectors.

Beads, binder material for thermoplastic and preformed plastic, adhesive for snowplowable markers, patching material for snowplowable marker removal, guide lines for grooving operations, pavement cleaning and surface preparation, and all necessary incidentals shall be included in the cost of the pay items.

SECTION 809 – ITS CONTROLLER CABINETS AND FOUNDATIONS

809.01 Description

This work shall consist of furnishing and installing ITS cabinets and foundations in accordance with 105.03.

MATERIALS

809.02 Materials

10 Materials shall be in accordance with the following:

ITS Controller Cabinet	925
Padlock	925.04(aa)

Materials for ITS cabinet foundations shall be in accordance with 805.02.

CONSTRUCTION REQUIREMENTS

809.03 General

20 ITS cabinet foundations shall be installed in accordance with 805.13.

A seal of silicone caulking compound shall be placed between each controller cabinet and the concrete foundation after the cabinet placement.

A rubber duct seal shall be used to seal all conduits that enter the bottom of the cabinet.

The input power source to the cabinets shall be 240 volts AC and 60 amps.

- 30 One laminated 11 by 17 in. site drawing shall be included in the data pocket of each cabinet.

809.04 Grounding

All ITS controller cabinets and foundations shall be grounded in accordance with the ITS grounding specification.

809.05 Cabinet Wiring

- 40 Wiring within ITS cabinets shall be neatly arranged and ty-wrapped, or enclosed in expandable braided polyester sleeving. All cabinet wiring harnesses shall be neat, firm, routed, and mechanically supported to minimize crosstalk, electrical interference, and to prevent inadvertent pulling. AC power cables shall be routed and bundled separately from shielded control cables which include, but are not limited to, logic voltage, video cables, and RF cables.

All conductors, except for the equipment-grounding conductors, shall be individually labeled at each termination with a unique identifier. All terminal blocks shall be labeled in accordance with the appropriate standard schematic drawings on the plans.

- 50 Conductors used in cabinet wiring shall terminate with properly sized captive terminals, spade type terminals, or shall be soldered. All crimp-style connectors shall be applied with a proper tool that prevents opening of the handles until the crimp is completed.

No more than three conductors shall be brought to any one terminal. Two flat metal jumpers, straight or U-shaped, may also be placed under a terminal screw. At least two full threads of all terminal screws shall be fully engaged when the screw is tightened. No live parts shall extend beyond the barrier.

- 60 Connectors, or devices plugging into connectors, shall be provided with positive means to prevent any individual circuit from being broken due to vibration, pull on connecting cable, or some similar disruptive force.

809.06 Field Testing

- 70 Cabinets and ITS components shall be field tested in accordance with the field test procedure furnished by the Department and the test results shall be submitted to the ITS Electronics Technician of the Operations Support Division. The Contractor shall record all test readings, in triplicate, on the field test procedure form. The Contractor shall complete, sign, and date the forms before submitting them to the ITS Electronics Technician.

All necessary equipment and personnel shall be provided to ensure the tests are safely conducted. The Electronics Technician shall be present to witness the tests. A cabinet shall pass every test to be accepted. If the cabinet fails, the problem shall be corrected and a new test shall be arranged.

The technician shall be given at least 36 h advance notice of the test.

809.07 Clean-Up

80 When the installation is completed, all disturbed portions of the construction area shall be cleaned and all excess excavation or other materials shall be disposed of in accordance with 104.05 and 203.10. The site shall be restored to its original condition.

809.08 Method of Measurement

ITS controller cabinet foundations will be measured per each installed, complete and in place. ITS controller cabinets will be measured by the number of units installed, complete and in place.

809.09 Basis of Payment

90 ITS controller cabinet foundations will be paid for at the contract price per each. ITS controller cabinets, complete, in place, will be paid for at the contract unit price per each.

Payment will be made under:

Pay Item	Pay Unit Symbol
ITS Controller Cabinet Foundation	EACH
ITS Controller Cabinet	EACH

100

The cost of all cabinet accessories, mounting hardware, anchor bolts, handles, setup and wiring shall be included in the cost of the ITS controller cabinet.

The cost of all grading necessary for installation of the foundations and the final clean-up of the area shall be included in the cost of the ITS controller cabinet foundation.

The cost of padlocks shall be included in the cost of the ITS controller cabinet.