


SIGN NUMBER	SIGN MESSAGE	POST DESIGN		SIGN SIZE	SIGN COLOR		BORDER WIDTH	MARGIN WIDTH	LETTER HEIGHT SERIES-LINE 1	LETTER HEIGHT SERIES-LINE 2	LETTER HEIGHT SERIES-LINE 3	WORD OR LINE ①	PCT. ①	ARROW SIZE		CORNER RADIUS	NUMBER OF POSTS	
		4 x 4 WOOD	STEEL		BACKGROUND	COPY								HEAD	SHAFT		ONE	TWO
XG20-1	"Road Construction Next ___ Miles"	*	B	1500 x 900	Orange	Black	20	15	150 - Series C	150 - Series C						55		X
XG20-2	"End Construction"	*	B	1500 x 600	Orange	Black	15	10	150 - Series C	150 - Series C						35		X
XG20-2a	"End Road Work"	*	B	1200 x 600	Orange	Black	15	10	150 - Series C	150 - Series C						35		X
XG20-4	"Pilot Car Follow Me"	-	-	900 x 450	Orange	Black	15	10	125 - Series C	125 - Series C						35		
XG20-5	(Route number or) " ___ Lane Closed" (date)	*	B	1500 x 900	Orange	Black	20	15	150 - Series C	150 - Series C	150 - Series C					55		X
XG20-5-B	"Worksite" plate	-	-	1200 x 400	Orange	Black	15	10	200 - Series C							35	---	---
XM4-9 (R or L)	"Detour" (above black arrow)	*	A	750 x 600	Orange	Black	15	10	125 - Series D			"Detour"		180 x 200	275 x 90	35		X
XM4-9-B (R or L)	"Detour" (above black arrow)	*	B	1500 x 1200	Orange	Black	30	20	250 - Series D			"Detour"		375 x 405	555 x 180	75		X
XM4-10 (R or L)	"Detour" (inside orange arrow)	*	B	1200 x 450	Black & Orange	Black	---	10	150 - Series D					300 x 340	755 x 200	35		X
XW1-1-A (R or L)	(Turn symbol)	*	A	900 x 900	Orange	Black	20	15						270 x 300	135	55		X
XW1-1-B (R or L)	(Turn symbol)	*	B	1200 x 1200	Orange	Black	30	20						360 x 405	180	75		X
XW1-2-A (R or L)	(Curve symbol)	*	A	900 x 900	Orange	Black	20	15						270 x 300	135	55		X
XW1-2-B (R or L)	(Curve symbol)	*	B	1200 x 1200	Orange	Black	30	20						360 x 405	180	75		X
XW1-3-A (R or L)	(Reverse turn symbol)	*	A	900 x 900	Orange	Black	20	15						270 x 300	135	55		X
XW1-3-B (R or L)	(Reverse turn symbol)	*	B	1200 x 1200	Orange	Black	30	20						360 x 405	180	75		X
XW1-4-A (R or L)	(Reverse curve symbol)	*	A	900 x 900	Orange	Black	20	15						270 x 300	135	55		X
XW1-4-B (R or L)	(Reverse curve symbol)	*	B	1200 x 1200	Orange	Black	30	20						360 x 405	180	75		X
XW1-6	(Single headed arrow)	*	B	1200 x 600	Orange	Black	20	20						335 x 380	655 x 165	35		X
XW1-6-A	(Single headed arrow)	*	B	1500 x 750	Orange	Black	20	15						415 x 465	825 x 200	55		X
XW4-2 (R or L)	(Lane ends merge ___ symbol)	*	A	900 x 900	Orange	Black	20	15	See Traffic Control Standard Sheet 801-TCSN-09							55		X
XW4-2-A (R or L)	(Lane ends merge ___ symbol)	*	B	1200 x 1200	Orange	Black	30	20	See Traffic Control Standard Sheet 801-TCSN-09							35		X
XW6-2a-A	(Divided highway ends symbol)	*	A	900 x 900	Orange	Black	20	15	125 - Series D	125 - Series D	125 - Series D					55		X
XW6-2a-B	(Divided highway ends symbol)	*	B	1200 x 1200	Orange	Black	30	20	175 - Series D	175 - Series D	175 - Series D					75		X
XW6-3-B	(Two way traffic symbol)	*	B	1200 x 1200	Orange	Black	30	20						295 x 350	595 x 150	75		X
XW8-1-A	"Bump"	*	A	900 x 900	Orange	Black	20	15	250 - Series D							55		X
XW8-1-B	"Bump"	*	B	1200 x 1200	Orange	Black	30	20	300 - Series D							75		X
XW8-2-A	"Dip"	*	A	900 x 900	Orange	Black	20	15	250 - Series E							55		X
XW8-2-B	"Dip"	*	B	1200 x 1200	Orange	Black	30	20	300 - Series E							75		X
XW8-3-A	"Pavement Ends"	*	A	900 x 900	Orange	Black	20	15	150 - Series C	150 - Series C						55		X
XW8-4-A	"Soft Shoulder"	*	A	900 x 900	Orange	Black	20	15	150 - Series C	150 - Series C						55		X
XW8-4-B	"Soft Shoulder"	*	B	1200 x 1200	Orange	Black	30	20	200 - Series C	200 - Series C						75		X
XW8-6-A	"Truck Crossing"	*	A	900 x 900	Orange	Black	20	15	150 - Series C	150 - Series C						55		X
XW8-6-B	"Truck Crossing"	*	B	1200 x 1200	Orange	Black	30	20	200 - Series C	200 - Series C						75		X
XW9-1-A (R or L)	" ___ Lane Ends"	*	A	900 x 900	Orange	Black	20	15	150 - Series D	150 - Series D	150 - Series D					55		X
XW9-1-B (R or L)	" ___ Lane Ends"	*	B	1200 x 1200	Orange	Black	30	20	200 - Series D	200 - Series D	200 - Series D					75		X
XW9-2-A (R or L)	"Lane Ends Merge ___ "	*	B	1200 x 1200	Orange	Black	30	20	150 - Series C	200 - Series D	200 - Series D					55		X
XW12-1-C	(Double headed arrow)	*	B	1200 x 1200	Orange	Black	30	20						320 x 380	300 x 135	75		X
XW13-1-A	" ___ MPH" (Advisory speed plate)	*	A	600 x 600	Orange	Black	15	10	250 - Series E	100 - Series E						35	---	---

* Wood post permitted.

GENERAL NOTES

- ① Spacing between letters of this word or line shall be reduced by this percentage as shown in the FHWA document, Standard Highway Sign.
2. See Standard Drawing 801-TCSN-11 for additional general notes.

All Dimensions are in mm unless otherwise specified.

INDIANA DEPARTMENT OF TRANSPORTATION	
SIGN DESIGN DETAILS SCOUR PROTECTION	
SEPTEMBER 2007	
STANDARD DRAWING NO. 801-TCSN-12	
	<i>/s/ Richard L. VanCleave</i> 09/04/07 DESIGN STANDARDS ENGINEER DATE
DESIGN STANDARDS ENGINEER	<i>/s/ Mark A. Miller</i> 09/04/07 CHIEF HIGHWAY ENGINEER DATE