

Worksite Speed Limit
Sign Assembly

## **General Notes:**


- 1. If not trailer mounted, signs and supports shall meet NCHRP 350 crash evaluation criteria.
- 2. Mounting height shall be 7' for interstate applications.
- 3. Advance Warning Sign speed shall match Worksite Sign.
- 4. The Work Site Speed Limit shall be 45 MPH, or 10 MPH below the posted speed limit for the roadway under construction, whichever is less.

## INDIANA DEPARTMENT OF TRANSPORTATION

## WORKSITE SPEED LIMIT SIGN ASSEMBLY

SEPTEMBER 2007

STANDARD DRAWING NO. E 801-TCDV-10



/s/ Richard L. VanCleave
DESIGN STANDARDS ENGINEER

09/04/07 DATE

/s/ Mark A. Miller
CHIEF HIGHWAY ENGINEER

09/04/07 DATE