


GENERAL NOTES:

- ① This sign shall be used on expressways, freeways, and other roadways with design speeds of 50 mph. or more.
2. The minimum vertical and horizontal clearances for construction signs shall be as on Standard Drawing E 801-TCDV-05.
3. The minimum horizontal clearance for construction signs on curbed roadway sections shall be 2'-0" from the face of the curb to the near edge of the sign.
4. The minimum depth for wood or steel posts shall be 4 ft.
5. See Standard Drawing E 801-TCDV-08 for U-Channel Steel Post Splice Detail.
- ⑨ This sign shall be removed, covered, or turned to face away from the roadway during non-working hours.
- ⑩ This sign may be ordered to read "500 FT", "1000 FT", or "1500 FT" in place of the word "Ahead". Such signs may be used in place of, or in conjunction with, the indicated sign.

INDIANA DEPARTMENT OF TRANSPORTATION	
CONSTRUCTION SIGNS GENERAL NOTES SEPTEMBER 2010	
STANDARD DRAWING NO. E 801-TCSN-11	
	<i>/s/ Richard L. VanCleave</i> 09/01/10 <hr/> DESIGN STANDARDS ENGINEER DATE
	<i>/s/ Mark A. Miller</i> 09/01/10 <hr/> CHIEF HIGHWAY ENGINEER DATE
DESIGN STANDARDS ENGINEER	