





## **GENERAL NOTES:**

- 1. Tolerances shown are maximum permissible varations from the dimensions shown on the plans or shop drawings. Tolerances shall not be considered cumulative. Longitudinal tolerances are based on design length. Casting length shall be adjusted to compensate for shrinkage and plastic flow.
- 2. End stirrup bars shall not be more than 2" from the end of the beam.
- 3. Mild reinforcing steel concrete cover tolerance shall be 1/8" to +3/8".
- $\langle 4 \rangle$  Tolerances for reinforcing bars for composite beam.
- Variation of camber shall not be more than 1" on one span nor more than 1/2" between adjacent members to be measured at time of erection.

Permitted camber variation from design camber is as follows:

I-beam or bulb-tee beam:  $\pm 1/8$ " per 10'-0" length with  $\pm 1/2$ " maximum for member length of 80'-0" or less

±1" maximum for member length of greater than 80'-0"

 $\pm 1/8$ " per 10'-0" length with  $\pm 1/2$ " mm maximum Box beam:

- $\langle 6 \rangle$  Tolerance in length of beam shall be checked after the final curing phase and within three days prior to shipping.
- $\langle 7 \rangle$  Horizontal-alignment tolerance shall be checked immediately after removal of forms and strand release, and prior to removal from bed.
- $\langle 8 \rangle$  At concrete bearing area, deviation from plane surface when tested in all directions of the plane surface with a steel straightedge shall not be more than  $\pm 1/16$ ".

## INDIANA DEPARTMENT OF TRANSPORTATION

## **FABRICATION TOLERANCES** GENERAL NOTES SEPTEMBER 2011

STANDARD DRAWING NO. E 707-BPBF-04



/s/Richard L.VanCleave 09/01/11 DESIGN STANDARDS ENGINEER DATE

09/01/11 /s/ Mark A. Miller CHIEF HIGHWAY ENGINEER

DESIGN STANDARDS ENGINEER