

2009 PE/PS Workshop Session 2 part A

Contract Startup Details

Presenter: Roland L. Fegan, Jr., PE

**Area Engineer-Greenfield, INDOT** 

#### **Introduction**

1) General Instructions to Field Employees Section I and II



#### **Preliminary Study of Project**

- 1) Timelines
- **Quantities and Items**
- 3) Designer Calculations
- 4) Maintenance of Traffic and Sign Locations
- 5) Identify Resources
- 6) PIO
- **Schools/Emergency Services/Business Access**



#### **Project Field Investigation**

- 1) Locations
- **Check Site Conditions**
- 3) Constructability
- **Emergency Access**
- 5) Special Conditions
- **Safety Concerns**



#### **Preconstruction Conference**

- 1) Utilities
- 2) EEO
- 3) Area Engineer Check List
- **Shop Drawings**
- 5) Site Manager Setup
- 6) Minutes of Meeting



#### **Preliminary Field Work**

- 1) Early Measuring
- **Cross-Sections**
- 3) Staking of R/W
- 4) Stationing
- 5) Certifications for Testing/Written Tests and Field Verifications



#### **Preliminary Office Work**

- Set up files
- 2) Site Manager
- 3) E-mails and Storage
- 4) Memorandums
- 5) Standard Drawings
- Specification Book and CD's



## 6 phases of a project

1. Enthusiasm



- 1. Enthusiasm
- 2. Disillusionment



- 1. Enthusiasm
- 2. Disillusionment
- 3. Panic



- Enthusiasm
- 2. Disillusionment
- 3. Panic
- 4. Search For the Guilty



- 1. Enthusiasm
- 2. Disillusionment
- 3. Panic
- Search For the Guilty
- 5. Punishment of the Innocent



- Enthusiasm
- 2. Disillusionment
- 3. Panic
- Search for the Guilty
- 5. Punishment of the Innocent
- 6. Praise and Honors for the Non-Participants



#### DARE TO BE GREAT



#### PE/PS Workshop Session#2



**Driving Indiana's Economic Growth** 


- Must meet requirements in 105.17
  - Typically a recurring in Contract Information Book
- Must meet IOSHA requirements
  - Examples
    - Need Ground Plugs on Electrical Outlets
    - Hand rails on stairs



- Initial Duties in SiteManager
  - Enter Milestone Dates
  - Review Key Dates
  - Entering Precon Notes into SM
  - Checking for 730 Approvals
  - Activate Personnel
  - Pre-populate Contract Master List




- Initial Duties in SiteManager
  - Enter Milestone Dates





- Initial Duties in SiteManager
  - Enter Milestone Dates






- Initial Duties in SiteManager
  - Key Dates
    - These are important days to the contract worth recording such as:
      - First Day of Work
      - Authorization to remove Signs
      - Last Day Work
    - Delete Key Dates not applicable
    - Enter Key Date Recipient




- Initial Duties in SiteManager
  - Key Dates






Initial Duties in SiteManager

Key Dates






- Initial Duties in SiteManager
  - Entering Precon Notes into SM





- Initial Duties in SiteManager
  - Entering Precon Notes into SM






- Initial Duties in SiteManager
  - Checking 730 Approvals






- Initial Duties in SiteManager
  - Checking 730 Approvals




- Initial Duties in SiteManager
  - Activate Personnel






- Initial Duties in SiteManager
  - Activate Personnel






- Initial Duties in SiteManager
  - Pre-Populate Contract Master List






- Initial Duties in SiteManager
  - Pre-Populate Contract Master List





- Documents available on Extranet
  - http://netservices.indot.in.gov/





- Documents available on Extranet
  - Contract Information Book
  - Plans
  - Revisions
  - Geotechnical Report
  - Q&A from Bid Process
  - Permits
  - Abestos Report



- Qualified Technician Program
  - Every test run for acceptance must be run by a qualified technician
  - To become qualified
    - Pass written test
    - Perform field proficiency
      - If this is done every 3 years then no more written's
    - IA Side-by-Side Frequency 1 per year
  - Equipment must be calibrated at correct frequency
    - Often overlooked by Consultants



- Frequency Manual
  - Find online at http://www.in.gov/indot/2581.htm
  - These are minimum Test Frequencies
    - Must be met
  - Two Manuals in 2009
    - SiteManager version
    - CRA version



- Contract Sample Checklist
  - SiteManager Reports Page
    - https://sitemanager.in.gov/SMReports/SMLogon.aspx
    - Reports found here:
      - IC642
      - Weekly
      - Item Print outs for Field Office wall by PLN or CLN
      - Item Detail Report
      - Contract Sample Checklist



- Contract Sample Checklist
  - Recreates Frequency Manual per Contract
  - Call District Testing if there is an error
  - Use to track down Estimate Discrepancies



Report Date: 02/22/2009 INDIANA Page 1 of 120

## Department Of Transportation Contract Sample Check List (Sorted by Project and PLN)

| Contract ID<br>IR-29023      |                | Prime Contractor GOHMANN ASPHALT & CONSTRUCTION INC |                                   |                           |              |                      |          |                         |               | Letting Date<br>04/02/2008 |                                    |                                      |
|------------------------------|----------------|---|-----------------------------------|---------------------------|--------------|----------------------|----------|-------------------------|---------------|----------------------------|------------------------------------|--------------------------------------|
|                              |                |   | Item                              |                           |              |                      |          |                         |               | Item Uni                   | t Bid+CO                           | Estimate                             |
| Project                      | PLN            | CLN   | Code                              | Item Description          |              |                      |          |                         |               |                            | Qty                                | Qty                                  |
| 0500436                      | 0019           | 0019  | 211-02050                         | B BORROW                  |              |                      |          |                         |               | CYS                        | 36,000.000                         | 16,933.96000                         |
|                              |                |   |                                   |                           |              |                      |          | Mater                   |               |                            | Bid+CO                             | Estimate                             |
| Material Code<br>904M06940   |                | Material F<br>Structural I                          | ull Name<br>Backfill, 4.75mm (#   | Spec. F<br>(4) 904.01     | Ref Ma<br>TO | iterial U<br>N       | nit      | 1.0                     | actor<br>0000 |                            | Matl Qty<br>36,000.00000           | Matl Qty<br>16,933.96000             |
| Test Method Test Description |                |   | า                                 | Sample Type               | Accpt M      | ethod                | Tota     | al Req'd                | Current       | Req'd                      | Satisfied                          | Frequency                            |
| IT211-v1                     | C.A.F          | P.P.  |                                   | Acceptance<br>Testing     | Approva      | al Numbe             | er 1     |                         | 1             |                            | 1                                  | 9999999                              |
| T255-v1                      | Moist<br>Dryin |   | t of Aggregate By                 | Acceptance<br>Testing     | Test Re      | sults                | 4        | 5                       | 22            |                            | 27                                 | 800                                  |
| T310E-v1                     |                | ity & Moistu<br>SLISH)                              | re by Nuclear Meth                | nod Acceptance<br>Testing | Test Re      | sults                | 4        | 5                       | 22            |                            | 27                                 | 800                                  |
|                              |                |   | Item                              |                           |              |                      |          |                         |               | Item Uni                   | t Bid+CO                           | Estimate                             |
| Project                      | PLN            | CLN   | Code                              | Item Description          |              |                      |          |                         |               |                            | Qty                                | Qty                                  |
| 0500436                      | 0020           | 0020  | 215-07043                         | CHEMICAL MODIF            | FICATION,    | SOILS                |          |                         |               | SYS                        | 60,000.000                         | 12,046.00000                         |
|                              |                |   |                                   |                           |              |                      |          | Mater                   | ial           |                            | Bid+CO                             | Estimate                             |
| Material Code<br>903M00520   |                | Material Full Name<br>Soil, UnClassified            |                                   | Spec. F<br>903            |              | Material Unit<br>TON |          | Conv. Factor<br>0.44444 |               |                            | Matl Qty<br>26,666.40000           | Matl Qty<br>5,353.72424              |
| Test Method Test Description |                |   | Sample Type                       | Accpt M                   | ethod        | Tota                 | al Req'd | Current                 | Req'd         | Satisfied                  | Frequency                          |                                      |
| D6951-v1                     |                |   | enetrometer in<br>nt Applications | Acceptance<br>Testing     | Test Re      | sults                | 2        | 20                      | 4             |                            | 2                                  | 1400                                 |
| Material Co                  |                | Material F<br>Lime By-P                             |                                   | Spec. F<br>913.04         | Ref Ma       | nterial U            | nit      | Mater<br>Conv. F<br>1.0 |               |                            | Bid+CO<br>Matl Qty<br>60,000.00000 | Estimate<br>Matl Qty<br>12,046.00000 |
| Test Method Test Description |                |   | Sample Type                       | Accpt M                   | ethod        | Tota                 | al Req'd | Current                 | Req'd         | Satisfied                  | Frequency                          |                                      |



### SITTE MANAGER

#### MATERIAL RECORD CHEAT SHEET

### 6 Vital Conditions

If your sample does not incorporate these 6 things then it will not count towards your frequency and you will have discrepancies.

- SAMPLE MUST BE MARKED COMPLETE
- 2. SAMPLE TYPE MUST MATCH CHECKLIST
- 3. ACCEPTANCE METHOD MUST MATCH CHECKLIST
- 4. MATERIAL CODE MUST MATCH CHECKLIST
- 5. CONTRACT TAB MUST BE COMPLETED
- 6. Test method must match Checklist



- Failed Material Process
  - Talk to District Testing Engineer
    - Crawfordsville- Kurt Sommer- (765) 361-5625
    - Fort Wayne- Bob Dahman- (260) 969-8238
    - Greenfield- Mike Nelson- (317) 467-3431
    - La Porte- Dave Schelling- (219) 325-7442
    - Seymour- Dave Hamilton- (812) 524-3761
    - Vincennes- Mark Fligor (812) 895-7425



- Failed Material Process
  - District Testing issues Initial Pink Sheet
    - Can be electronic or paper
  - Sent to PE/PS
    - District Construction, Contractor, and Office of Materials Management copied



- Failed Material Process
  - PE/PS responsibilities
    - Need:
      - Failing test
      - Location of material
      - Pay Item
      - Quantity Representited
      - Unit Price
    - Send all this back to DTE



- Failed Material Process
  - DTE Responsibilities
    - DTE can resolve most HMA failures
    - All other failures will be sent to Failed Materials
       Committee for resolution



- Rounding
  - Pay attention to accuracy required by tests
    - Think significant digits
    - For example, Specification 702.05 states yield test must be 100±2%. 102.4% rounds down to 102% and therefore passes.





PE/PS Workshop
Session # 2
Contract Start up Details

Presenter: Dennis A. Kuchler, PE

**State Construction Engineer, Indiana DOT** 

# **Partnering**

#### What is it?

A communication and problem solving tool.

Do you have a pay item?

Item: Partnering Overhead

What causes partnering to work or not work?

Commitment from both sides (Contractor & Public Agency)



## **Public Image is Important**

### Get to know persons effected by your project area:

- 1) Businesses
- 2) Homeowners

### **Contact your District PIO Officer:**

- 1) They need to be involved
- 2) They can get the word out on closures and lane restrictions



## Public Image (Cont.)

#### Be professional at all times.

- 1) Your actions represent the company your working for or are doing work for.
- 2) Control your attitude.
  - A. It is really the only thing you can control.
- 3) Try to keep a neat and organized office.
  - A. First impressions count.



## **CR-2 Form**

#### What is a CR-2?

- 1) A form to rate a contractor's performance
  - a) Prime Contractor
  - b) Sub-Contractor

#### When should it be filled out?

1) See the instructions in your workbook

### Why is it needed?



1) To keep a contractor pre-qualified to do work for INDOT