

BASIS FOR USE
OF RECURRING SPECIAL PROVISIONS
AND RECURRING PLAN DETAILS

CODE Date	Description BASIS FOR USE
100-C-146 R 11-5-99	Payment of Predetermined Minimum Wage (Davis-Bacon) IN970001 ALL PROJECTS IN LAKE, LAPORTE, PORTER, AND ST. JOSEPH COUNTIES EXCEPT BUILDING CONSTRUCTION.
100-C-147 R 11-5-99	Payment of Predetermined Minimum Wage (Davis-Bacon) IN970006 ALL PROJECTS IN COUNTIES OTHER THAN LAKE, LAPORTE, PORTER, AND ST. JOSEPH EXCEPT BUILDING CONSTRUCTION.
100-C-148 A 6-06-97	Payment of Predetermined Minimum Wage (Davis-Bacon) _____ ALL BUILDING CONSTRUCTION - DETERMINED BY CENTRAL OFFICE PERSONNEL
100-C-151 R11-01-99	Federally Funded Contract with DBE AS DETERMINED BY CONTRACTS SECTION
100-C-152 R 1-04-99	Federally Funded Contract without DBE AS DETERMINED BY CONTRACTS SECTION
101-B-042 R 9-1-93	Structure Numbers for Pay Items MORE THAN ONE BRIDGE FILE NUMBER IN CONTRACT, AND LUMP SUM PAY ITEMS SHOWN TO BE REQUIRED FOR EACH SUCH BRIDGE FILE
102-C-082 R 1-04-99	Schedule of Pay Items for Alternate Bids PAY ITEMS IN CONTRACT WHICH REQUIRE ALTERNATE BIDS
102-C-145 R 1-04-99	Toll Road Special Provisions ALL TOLL ROAD CONTRACTS
103-C-036 R 9-22-99	Owners' and Contractors' Protective Liability Insurance Coverage for Operations of the Designated Contractor ALL FEDERAL AID LOCAL PUBLIC AGENCY CONTRACTS
103-C-159 A 9-13-99	Wage Stipulations 100% STATE FUNDED CONTRACTS
104-C-139 A 9-19-95	Geotechnical Evaluation Report GEOTECHNICAL REPORT HAS BEEN DEVELOPED AND APPROVED
104-R-168 R 1-04-99	Schedule of Operations and Traffic Control for Undersealing, Concrete Patching, Placing Underdrains, and Resurfacing PAVEMENT UNDERSEALING, PATCHING, SHOULDER DRAIN PLACEMENT, AND RESURFACING SPECIFIED
105-C-056 R12-09-98	Engineer Application Personal Computer ALL CONTRACTS
105-C-071b R 1-04-99	Fax Machine in Field Office (Advanced Features) AS DETERMINED NECESSARY BY DISTRICT CONSTRUCTION
105-R-305 R 1-04-99	Pipe Structure Pay Items ALL CONTRACTS WITH PIPE STRUCTURE PAY ITEMS

106-C-074 R 1-04-99	Basis for Use of Approved or Prequalified Materials ALL CONTRACTS
106-R-276 R 1-04-99	Protection and Restoration of Established Vegetation ALL BRIDGE, ROAD, AND RESURFACE CONTRACTS
107-B-040 R 1-04-99	Environmental Restrictions AS DETERMINED BY PROJECT DESIGNER
107-C-029 R 7-14-98	Equal Employment Opportunity Trainees AS DETERMINED BY CONTRACT SERVICES
107-C-051 R 1-04-99	U.S.Army Corps of Engineers Permit AS DETERMINED BY PROJECT DESIGNER
107-C-112 R 3-04-99	Traffic Control Changes and On-Call Maintenance of Traffic Control Devices TRAFFIC BEING MAINTAINED ON PRESENT ROADWAY WITH NO WATCHMAN REQUIRED
107-R-042a R 1-04-99	Railroad Information HIGHWAY OVER OR UNDER RAILWAY
107-R-042b R10-08-96	Protection of Railway Interest AS DETERMINED BY UTILITIES SECTION
107-R-169 R 1-04-99	Statements About Existing Conditions of Utilities, Additional Right-of-Way, and Encroachments ALL CONTRACTS
108-C-043 R 1-04-99	Incentive or Disincentive for Opening Project to Traffic Ahead of Schedule AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
108-C-078 R10-25-99	Partnering Overhead AS DETERMINED NECESSARY BY DISTRICT CONSTRUCTION
108-C-089 R 1-04-99	Percentage of Work Required of Prime Contractor AS DETERMINED BY CONTRACT SERVICES PERSONNEL WHO WILL PROCESS CONTRACTS SHORTLY BEFORE LETTING
108-C-090 R 1-04-00	Latest Date to Begin Work DELAYED START OF WORK DESIRED
108-C-091 R 1-04-99	Failure to Complete on Time for Restriction-One Structure LANE RESTRICTIONS ON ONE LANE, PHASE, OR DIRECTION
108-C-092 R 1-04-99	Failure to Complete on Time for Restriction-Two or More Structures LANE RESTRICTIONS ON MORE THAN ONE STRUCTURE, PHASE, OR DIRECTION
108-C-093 R 1-04-99	Failure to Complete on Time for Road Closure AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME FOR CONTRACT WHICH INCLUDES DETOUR

108-C-094 R 1-04-99	Failure to Complete on Time for Intermediate Completion Date AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME FOR CONTRACT IN WHICH A CERTAIN PORTION OF THE WORK IS TO BE COMPLETED BEFORE THE ENTIRE CONTRACT IS
108-C-095 R 1-04-99	Failure to Complete on Time for Calendar Completion Date AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
108-C-096 R 1-04-99	Failure to Complete on Time for Work Days AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
108-C-127 R 1-04-00	Earliest Date To Begin Work AS DETERMINED NECESSARY BY DISTRICT CONSTRUCTION
108-L-001 R 1-04-99	Notice to Proceed With Demolition Work PAY ITEMS: 202-03000 HOUSES AND BUILDINGS PARCEL NO. _____ REMOVE
108-L-012 A 12-1-93	Specialty Pay Items PAY ITEM: 202-01261 TESTING FOR ASBESTOS REMOVAL
108-R-148 R 1-04-99	Construction Equipment in Park Areas PARK CONTRACT
112-C-122 R 1-04-99	State Funded Contract with Davis-Bacon Wage Rates AS DETERMINED BY CONTRACTS SECTION
201-C-052 R 1-04-99	Clearing Right-of-Way PAY ITEMS FOR CLEARING RIGHT-OF-WAY
201-M-030 R 1-04-99	Debris Removal at Bridge Structures DEBRIS REMOVAL MAINTENANCE CONTRACT
201-R-021 R 2-21-90	Burning of Natural Growth Permitted IDEM HAS ISSUED PERMIT TO DEPARTMENT FOR BURNING OF NATURAL GROWTH
201-R-179 R 2-21-90	Air-Curtained Open-Pit Incineration of Natural Growth Required IDEM HAS ISSUED PERMIT TO DEPARTMENT FOR BURNING BY MEANS OF AIR-CURTAINED OPEN-PIT INCINERATOR
202-L-013 1-13-99	Inspection and Testing for Asbestos Material AS DETERMINED BY PRE-ENGINEERING AND ENVIRONMENT
203-B-025 R 1-04-99	Marion County Borrow Pits PROJECT LIMITS IN MARION COUNTY, PAY ITEM: 203-02070
203-R-121 R 1-04-99	Borrow Pit Wetland Enhancement BORROW PIT EXCAVATION EXPECTED TO REACH WATER TABLE
203-R-155 R 1-04-99	Rock Backfill PAY ITEM: 202-92634 ROCK BACKFILL
203-R-260 R 1-04-99	Linear Grading PAY ITEM: 203-90014 OR 203-02080 LINEAR GRADING. EARTH WEDGING AT OUTSIDE EDGE OF SHOULDER OR BEHIND GUARDRAIL, OR MEDIAN EARTH FILLING

203-R-286 R11-08-99	Excess Excavated Materials Disposal Site ALL CONTRACTS EXCEPT MOWING AND HERBICIDE CONTRACTS
203-R-360 A 4-08-98	Embankments Constructed of Coal Combustion By-Products PAY ITEM OF 3800 CUBIC METERS (5000 CYS) OR MORE OF BORROW
204-R-049 R 1-04-99	Piezometers PAY ITEM: 204-02295 PIEZOMETER
206-B-026 R 1-04-99	Steel Sheet Piling at Railroad Grade Separation STEEL SHEET PILING REQUIRED, RAILWAY WITHIN PROJECT LIMITS
206-B-113 R 1-04-99	General Bridge Requirements BRIDGE REPLACEMENT OR NEW BRIDGE CONSTRUCTION
208-R-111 R 1-04-99	Gore Area Treatment PAY ITEM: 203-02046 GRADING OF GORE AREA
211-R-357 R 9-11-98	B Borrow and B Borrow for Structure Backfill PAY ITEMS: B BORROW OR B BORROW FOR STRUCTURE BACKFILL
303-M-002 R 1-04-99	Shoulders Adjacent to Resurface Work RESURFACE CONTRACT WITH UNPAVED SHOULDERS
303-R-248 R 1-31-00	Recycling Existing Concrete Pavement as Compacted Aggregate WHEN DETERMINED NECESSARY BY DISTRICT CONSTRUCTION
304-R-199 R 1-10-00	Subbase for Cement Concrete Pavement PAY ITEM: 304-04403 SUBBASE FOR CEMENT CONCRETE PAVEMENT
305-R-139 R 8-14-97	Partial Depth Joint Patching With HMA Mixtures PAY ITEM: 305-04346 JOINT PATCHING MATERIAL HV
311-R-229 R 2-18-00	Cement Concrete Pavement Cracking and Seating PAY ITEM: CONCRETE PAVEMENT CRACKING AND SEATING
401-R-324 R 8-14-97	Plant Laboratory for Plant Mix Pavements AS DETERMINED BY DISTRICT CONSTRUCTION
402-R-295 R 8-14-97	Micro-Surfacing PAY ITEM OF MICRO-SURFACING
601-R-016 R 5-23-00	Construction Zone Energy Absorbing Terminal PAY ITEM: ENERGY ABSORBING TERMINAL, CZ
601-R-056 R 3-04-99	Reset Impact Attenuator PAY ITEM: IMPACT ATTENUATOR, RESET
601-R-146 R 1-04-99	Removal of Guardrail REMOVED GUARDRAIL TO BECOME PROPERTY OF DEPARTMENT
601-R-183 R 1-04-99	Guardrail End Treatments PAY ITEMS: 601-06037 GUARDRAIL END TREATMENT I, 601-94690 GUARDRAIL END TREATMENT MS, OR 601-94689 GUARDRAIL END TREATMENT OS
601-R-217 R 9-1-95	Guardrail End Treatment Type Breakmaster PAY ITEM: 601-97933 GUARDRAIL END TREATMENT BREAKMASTER

601-R-218 R 9-1-95	Guardrail End Treatment Type ET 2000 PAY ITEM: 601-97932 GUARDRAIL END TREATMENT ET 2000
601-R-237 R 1-04-99	Spare Parts Package for Guardrail End Treatment AS DETERMINED BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
601-R-338 A 4-19-00	Guardrail Blockouts PAY ITEM FOR GUARDRAIL
603-R-109 R 9-1-95	Gate Barricade PAY ITEM: GATE BARRICADE
610-M-008d R 3-1-85	Typical Approach Details DRAWING FOR RESURFACE CONTRACT WHICH INCLUDES DRIVE APPROACHES
611-R-100 R 8-14-97	Median Crossovers MEDIAN CROSSEOVERS REQUIRED AS SHOWN ON PLANS
615-R-020 R 1-04-99	Wood Post Parking Barriers PAY ITEM: PARKING BARRIER WOOD POST
616-R-102 R 9-1-95	Gabion Revet Mattress PAY ITEM: 616-02305 GABIONS
619-B-139 R 6-01-00	Cleaning and Painting Steel Bridges PAY ITEMS FOR CLEANING/PAINTING STEEL BRIDGE
621-R-283 R 1-04-99	Seeding Outside Construction Limits ALL CONTRACTS
622-R-209 A 5-13-91	Wildlife Habitat Species and Spacing PAY ITEM: 621-91786 SEEDLING; SPECIES AND SPACING NOT SHOWN ON PLANS
623-M-025 R 8-24-98	Roadside Mowing MAINTENANCE CONTRACT FOR MOWING
623-M-039 R 10-25-93	Mowing Cycles, Starting Dates, and Failure to Complete Mowing on Time MAINTENANCE CONTRACT FOR MOWING
624-M-024 R 9-27-96	Herbicide Treatment MAINTENANCE CONTRACT FOR HERBICIDE TREATMENT
624-M-040 A 10-14-92	Herbicide Formula and Application Period MAINTENANCE CONTRACT FOR HERBICIDE TREATMENT
625-R-194 R 11-13-98	Gabions PAY ITEM: 616-02305 GABIONS
626-R-165 R 9-1-95	Modified Section Concrete Median Barrier CONCRETE MEDIAN BARRIER REQUIRED OF OTHER THAN STANDARD SHAPE
701-B-068 R 9-01-95	Bitumen Coating for Piles BITUMEN COATED PILES
701-B-078 R 9-01-95	Oversized Predrilled Pile Holes for Integral End Bent Structures PAY ITEM: 701-93633 PILE HOLE PREDRILLED

701-B-101d R11-05-99	Pile Driving and Equipment Data Form PAY ITEMS FOR PILES
701-B-132 R 3-05-99	Pile Driving AS DETERMINED BY THE PROJECT DESIGNER
703-C-138 R 1-04-99	Reinforcing Bars PROJECTS DESIGNED WITH HARD METRIC REINFORCING STEEL
706-B-140d A11-08-99	Bridge Railing Type TS-1 & Guardrail Transition Type TGS-1 PAY ITEM: BRIDGE RAILING TYPE TS-1
707-B-013 R 1-04-99	High Range Water Reducers in Precast Prestressed Concrete Structural Members PAY ITEMS FOR STRUCTURAL MEMBERS CONCRETE
707-B-085 R 9-1-95	Alternate Prestressed Precast Concrete I-Beam to Standard AASHTO Type IV Prestressed Precast Concrete I-Beam ALTERNATE BEAM SECTION PERMITTED IN LOCAL AGENCY PROJECT
709-B-070 R 9-1-93	Tinted Epoxy Penetrating Sealer PAY ITEMS FOR SURFACE SEAL TINTED
709-M-019 R 1-04-99	Surface Seal for Steel Bridge to be Painted PAY ITEMS: CLEAN STEEL BRIDGE, PAINT STEEL BRIDGE
713-B-076 R 1-04-99	Temporary Pipe TEMPORARY PIPE SPECIFIED ON PLANS IN LIEU OF TEMPORARY BRIDGE
714-R-003 R 1-22-97	Bin-Type Retaining Wall PAY ITEMS FOR RETAINING WALL BIN TYPE _____ DESIGN _____
715-R-302 R 7-13-98	Slip Lining of Roadway Culverts With Polyethylene Culvert Pipe Liner PAY ITEM: PIPE, POLYETHYLENE LINER
715-R-341 A 9-04-97	Pipe Material Selection PROJECTS REFERRING TO PIPE BY GROUPS
715-R-342 A 9-04-97	Pipe Backfill Methods METRIC PROJECTS REFERRING TO PIPES BY GROUPS, EXCEPT GROUP K
715-R-361 A 9-01-98	Pipe Material Abbreviations PAY ITEMS FOR PIPE
717-R-152 R 1-04-99	Alternates to Structural Plate Structures PAY ITEMS FOR PIPE STRUCTURAL PLATE
718-R-326 R 1-04-99	Underdrains PAY ITEM FOR GROUP K PIPE
718-R-326a A 5-09-97	Underdrains PAY ITEM FOR UNDERDRAINS
720-M-021 R 9-1-95	Extension of Cast Iron Floor Drains PAY ITEM: DRAIN EXTENSION CAST IRON
720-R-104 R 1-04-99	Capped Inlet PAY ITEM: 720-44296 CAP INLET

720-R-173 R 7-1-95	Proof Load for Castings PAY ITEMS FOR INLETS, CATCH BASINS, OR MANHOLES
720-T-021 R 11-1-92	Drainage Structures TRAFFIC CONTRACT - DRAINAGE STRUCTURES REQUIRED
723-R-282 R 6-05-00	Precast Reinforced Concrete 3-Sided Culvert PAY ITEMS FOR CULVERT PRECAST 3 SIDED
723-R-282f A 6-07-00	Precast Reinforced Concrete 3-Sided Flat-Topped Culvert AS DETERMINED BY THE DESIGNER
724-B-046 R12-08-99	Modular Expansion Joints PAY ITEM: 724-51927 MODULAR EXPANSION JOINT
724-B-086 R 12-1-94	Approved Expansion Joint SS Devices PAY ITEM: 724-51925 EXPANSION JOINT SS
724-B-131 R 1-27-98	Polymer Modified Asphalt Joint System PAY ITEM: 501-02221 EXPANSION JOINT POLYMER MODIFIED ASPHALT
724-B-131d R 7-14-97	Polymer Modified Asphalt Joint System Details ACCOMPANIES 501-R-281
726-B-044 R 1-04-99	Bearing Assemblies PAY ITEM: 707-95870 BEARING ASSEMBLY
727-B-012 R 1-04-99	Concrete Repair by Epoxy Injection PAY ITEMS FOR EPOXY INJECTION EQUIPMENT, CRACK PREPARATION, EPOXY MATERIAL
728-B-039 R 1-04-99	Masonry Coating PAY ITEMS FOR MASONRY COATING; MASONRY COATING SPECIFIED WITHOUT PAYMENT
729-B-009 R 3-28-96	Concrete for Patching Bridge Structures PAY ITEM: CONCRETE, A, PATCHING
731-R-202 R 4-24-00	Mechanically Stabilized Earth Retaining Walls DETAILS FOR PROPRIETARY MECHANICALLY STABILIZED EARTH WALL SYSTEMS INCLUDED IN PLANS
733-B-104 R 6-09-99	Microsilica Concrete Bridge Deck Overlay PAY ITEM: 722-51842 BRIDGE DECK OVERLAY; MICROSILICA ADMIXTURE SPECIFIED
801-C-157 A10-23-98	Certification for Category 1 Temporary Traffic Control Devices PAY ITEM: MAINTENANCE OF TRAFFIC
801-M-006 R 1-04-99	Maintaining Traffic for Maintenance or Resurface Work MAINTENANCE OR RESURFACE CONTRACT, PAY ITEMS FOR MAINTAINING TRAFFIC
801-R-030 R 1-04-99	Temporary U-Turns for Contractor's Vehicles AS DETERMINED NECESSARY BY DEPARTMENT PERSONNEL WHO SET CONTRACT TIME
801-R-253 A 1-14-93	Mobile Construction Signs PAY ITEM: 801-92448 CONSTRUCTION SIGNS, MOBILE

801-T-089 R 7-8-99	Maintaining Existing Traffic Signal Installation PAY ITEM: TEMPORARY TRAFFIC SIGNAL INSTALL AND MAINTAIN
805-T-035 R 1-04-99	Delay Amplifiers CONTRACT WITH TRAFFIC SIGNAL INSTALLATIONS
805-T-036 R 7-01-95	Department Furnished Materials CONTRACT WITH TRAFFIC SIGNAL INSTALLATIONS
805-T-038 R 1-04-99	Preformed Loop Detectors AS DEEMED NECESSARY BY DISTRICT TRAFFIC ENGINEER
805-T-038d A 3-16-93	Loop Tagging System PAY ITEM: 805-01439 MICROLOOP DETECTOR
805-T-039d A 3-16-93	Loop Testing Table PAY ITEM: 805-01439 MICROLOOP DETECTOR
805-T-041 R 7-1-95	Miscellaneous Equipment CONTRACT WITH TRAFFIC SIGNAL INSTALLATIONS
805-T-069 A 2-27-89	Traffic Signalization Locations AT LEAST 2 LOCATIONS TO BE SIGNALIZED
805-T-075 R 1-04-99	Saw Cut Requirement PAY ITEMS FOR LOOP DETECTORS
805-T-076 R 1-04-99	Solid State Controllers PAY ITEMS FOR CONTROLLER SOLID STATE PRE-TIMED
805-T-078 A 8-22-90	Electrical Insulation Sealant CONTRACT WITH TRAFFIC SIGNAL OR LIGHTING INSTALLATIONS
805-T-083 R 1-04-99	Traffic Signal Equipment Salvaged by the Contractor TRAFFIC SIGNAL EQUIPMENT TO BECOME PROPERTY OF CONTRACTOR
805-T-084 R 1-04-99	Traffic Signal Equipment Salvaged by the Department PAY ITEM: 202-96151 TRANSPORTATION OF SALVAGEABLE ITEMS
805-T-085 R 7-01-95	Signal Bulb Replacement, Aerial Inspection, and Loop Replacement TRAFFIC MAINTENANCE CONTRACT FOR SIGNAL BULB REPLACEMENT
805-T-086 R 7-1-95	Traffic Signal Maintenance and Repair TRAFFIC MAINTENANCE CONTRACT FOR NON-BULB SIGNAL MAINTENANCE
805-T-093 A 2-2-93	Detector Card Rack and Detector Modules PAY ITEM: DETECTOR MODULE
805-T-095 R 1-04-99	Signal Controllers PAY ITEMS FOR CONTROLLER AND CABINET
805-T-105 A 7-1-95	Conversion of Metric Standards ENGLISH DESIGNED CONTRACTS; PAY ITEMS FOR TRAFFIC SIGNAL
807-T-087 R 7-1-95	Highway Illumination Maintenance and Repair TRAFFIC MAINTENANCE CONTRACT FOR LIGHTING MAINTENANCE

808-B-114	Repainting No-Passing Zone Pavement Markings
R 1-04-99	BRIDGE CONTRACT; PAY ITEM FOR LINE SOLID YELLOW 4 IN. USED AS NO-PASSING ZONE MARKING
808-M-016	Removal of Snowplowable Markers
R 1-04-99	PAY ITEM: 202-75996 SNOWPLOWABLE RAISED PAVEMENT MARKER REMOVE
808-M-046	Refurbished Snowplowable Raised Pavement Marker Castings
R 1-04-99	PAY ITEM: SNOWPLOWABLE RAISED PAVEMENT MARKER CASTING, INSTALL
808-T-116	Snowplowable Raised Pavement Markers
A 1-03-00	PAY ITEM FOR SNOWPLOWABLE RAISED PAVEMENT MARKERS
913-T-117	Encapsulated Lens High Intensity Reflective Sheeting
A 1-12-00	PAY ITEM FOR SIGN, SHEET