

714-R-578 CONCRETE BOX SCOUR PROTECTION

(Adopted 04-15-10)

The Standard Specifications are revised as follows:

SECTION 714, AFTER LINE 45, INSERT AS FOLLOWS:

*Scour protection shall be installed as shown on the plans.*

*When riprap is specified, geotextile shall first be placed on the in-situ soil in accordance with 616.11. Riprap shall then be placed in accordance with 616.*

SECTION 714, BEGIN LINE 270, DELETE AS FOLLOWS:

Reinforcing bars, plain or epoxy coated, will be paid for in accordance with 703.08. ~~Geotextile or riprap will be paid for in accordance with 616.13.~~ Structure backfill will be paid for in accordance with 211.10. Field drilled holes will be paid for in accordance with 702.28.

SECTION 714, BEGIN LINE 296, INSERT AS FOLLOWS:

The cost of excavation except as provided in 206.11(a), *scour protection*, expansion joint material, perpetuation of existing drains show on the plans, removal of portions of existing structures, cleaning out old channels or structures, approved chemical anchor system, precast reinforced concrete structure joints, and necessary incidentals shall be included in the cost of the pay items in this section.

---