

801-R-030 TEMPORARY U-TURNS FOR CONTRACTOR'S VEHICLES

(Revised 09-01-05)

The Standard Specifications are revised as follows:

SECTION 801, AFTER LINE 327, INSERT AS FOLLOWS:

801.09.1 Temporary U-Turns for Contractor's Vehicles

Construction of temporary U-turns will be permitted in the median at approved locations. The geometrics of such U-turns shall be as shown on the plans. Traffic maintenance devices shall be placed as shown on the plans. The U-turns may be constructed of aggregate of the depth directed in lieu of HMA material. All drainage shall be maintained in the area. When no longer required, such temporary U-turns shall be removed. The median shall then be restored to its original condition.

SECTION 801, AFTER LINE 997, INSERT AS FOLLOWS:

The cost of temporary U-turns for Contractor's vehicles, related traffic signing, and cones shall be included in the cost of other pay items in this section. If an approved permanent crossover is used as a temporary U-turn, the cost of the related traffic signing and cones shall be included in the cost of other pay items in this section.
