

## 808-R-644 REMOVAL OF PAVEMENT MARKERS

(Adopted 06-16-16)

The Standard Specifications are revised as follows:

SECTION 808, BEGIN LINE 544, DELETE AND INSERT AS FOLLOWS:

The resulting holes shall be filled with the appropriate patching material as described herein or as otherwise directed. Concrete pavement which is to be overlaid as part of the contract and HMA pavement shall be patched with HMA intermediate materials. Concrete pavement which is not to be overlaid as part of the contract and concrete bridge decks shall be patched with ~~magnesium-phosphate~~ concrete patching material *from the Department's approved list for Rapid Setting Patch Materials*. Overlaid bridge decks and bridge decks which are to be overlaid as part of the contract shall be patched with patching material which is compatible with the deck overlay material. All patching material shall be placed in accordance with the appropriate specifications for the patching material.

---