

## 303-R-690 AGGREGATE PAVEMENTS AND SHOULDERS

(Adopted 06-20-19)

The Standard Specifications are revised as follows:

SECTION 303, BEGIN LINE 18, DELETE AND INSERT AS FOLLOWS:

**303.03 Preparation of Subgrade**

Subgrade shall be ~~compacted~~ prepared in accordance with 207.04. ~~In areas of 500 ft or less in length, or for temporary runarounds, proofrolling will not be required.~~ Proofrolling will not be required in trench sections *and other areas* where proofrolling equipment cannot be used.

**303.04 Temperature Limitations**

Aggregate shall not be placed when the air temperature is less than 35°F. Aggregate shall not be placed on a frozen subgrade. Frozen aggregate shall not be placed.

**303.05 Spreading**

~~The moisture content of the aggregate shall be between 4% and the optimum moisture content prior to placement when the aggregate is delivered to the project. Unless otherwise directed, water shall not be added to the aggregate on the grade.~~ The aggregate shall be spread in uniform lifts with a spreading and leveling device approved by the Engineer. The spreading and leveling device shall be capable of placing aggregate to the depth, width, and slope specified. The compacted depth of each lift shall be a minimum of 3 in. and a maximum of 6 in., except where utilized as a shoulder. The compacted depth of a lift for a shoulder shall be a minimum of 3 in. and a maximum of 9 in. The aggregate shall be handled and transported to minimize segregation and the loss of moisture. In areas inaccessible to mechanical equipment, approved hand spreading methods may be used.

*The moisture content of the aggregate shall be between 4% and the optimum moisture content when the aggregate is delivered to the project. Water shall not be added to the aggregate on the grade.*

---